



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines


Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>





189

TN
57
M48

THE
COAL AND IRON INDUSTRIES
OF THE
UNITED KINGDOM.



[Illegible text at the top of the page]

[Illegible text in the right margin]



THE
COAL AND IRON INDUSTRIES
OF THE 39606
UNITED KINGDOM.

COMPRISING

A DESCRIPTION OF THE COAL-FIELDS, AND OF THE PRINCIPAL
SEAMS OF COAL, WITH RETURNS OF THEIR PRODUCE AND ITS
DISTRIBUTION, AND ANALYSES OF SPECIAL VARIETIES.

ALSO

AN ACCOUNT OF THE OCCURRENCE OF IRON ORES IN VEINS OR SEAMS;
ANALYSES OF EACH VARIETY; AND A HISTORY OF THE RISE AND
PROGRESS OF PIG IRON MANUFACTURE SINCE THE YEAR 1740,
EXHIBITING THE ECONOMIES INTRODUCED IN THE
BLAST FURNACES FOR ITS PRODUCTION
AND IMPROVEMENT.

BY

RICHARD MEADE,

ASSISTANT KEEPER OF MINING RECORDS.

WITH MAPS OF THE COAL-FIELDS AND IRONSTONE DEPOSITS OF
THE UNITED KINGDOM.



LONDON:

CROSBY LOCKWOOD AND CO.,

7, STATIONERS' HALL COURT, LUDGATE HILL.

1882.

[All rights reserved.]

LONDON

BRADBURY, AGNEW, & CO., PRINTERS, WHITEFRIARS.

PREFACE.

NUMEROUS inquiries made on matters connected with our Iron and Coal Industries led me in the year 1874 to prepare a series of articles on iron for the "Mining Journal." These articles were favourably received, and I was strongly urged from various quarters at home and abroad to publish the information in a more extended form.

It had previously occurred to me that, although much valuable information existed on these subjects, it was too widely diffused to be practically useful.

My aim, therefore, has been to condense all available information, and to introduce into this volume such details relating to our coal, iron and steel industries as were available. These may be briefly enumerated as follows—the coal-fields, their extent and area, the principal coal seams and ironstone measures, the production and distribution of the coal and ironstone; the variations in prices, the population employed under and above ground, and considerations as to the probable duration of the coal deposits.

In carrying this out, the early history of the rise and

progress of pig-iron manufacture has been traced since the year 1740, each iron-making district being separately considered, and the production recorded. The quantities of coal and iron ore used in this important manufacture have been given, and the returns bearing upon economy in the use of coal in the smelting operations of the blast furnace have been carefully collected and stated. Lists of all the works engaged in the manufacture of steel by the Bessemer, Siemens, Siemens-Martins, and Thomas-Gilchrist processes have been included.

I have spared no labour in consulting every authority within reach, and I believe much valuable matter—throwing considerable light upon the manufacture of pig-iron towards the end of the last and beginning of the present century—has been obtained.

Amongst others the annual Reports of H.M. Inspectors of Mines, the Reports of the Royal Coal Commission in 1870, and the select Committee of the House of Commons in 1873, appointed to inquire into the “Cause of the dearness of Coal,” have furnished much information. The consumption of fuel in the manufacture of pig-iron was first ascertained for the latter Committee, and has since then been published regularly in the annual volume of the “Mineral Statistics of the United Kingdom.”

Having referred to the principal sources from which the details have been derived, it remains for me to express my obligations to all who have aided me in my labour. To the officers of the Geological Survey I owe many

obligations, particularly Mr. Frank Rutley, F.G.S., who kindly favoured me with the introductory chapter on "The Mineralogical Character of the principal Iron Ores." To my colleague Mr. James B. Jordan, I am indebted for the map to illustrate the coal and iron districts of the United Kingdom. To the proprietors of the "Mining Journal," who courteously placed at my disposal my early papers published in that journal; and to many gentlemen whose names appear in the text as having rendered valuable assistance, I respectfully tender my sincere thanks.

NOTE.

It may be desirable to state, that throughout the first part of this volume the statistics referring to the "production of coal," have been derived from two sources of information. One of these sources is the series of "MINERAL STATISTICS OF THE UNITED KINGDOM," issued annually from the Mining Record Office; the other the "REPORTS OF H.M. INSPECTORS OF COAL MINES."

In considering the production of the several coal-fields, the "MINERAL STATISTICS" have been used, inasmuch as the series extends over a longer period, and gives annual returns continuously since the year 1854. In computing the probable duration of our coal-fields, the same authority has been taken as a basis of calculation.

With regard to the population employed in our coal-fields, and its relation to the amount of coal raised, and the average produce per man, the "REPORTS OF H.M. INSPECTORS OF MINES," commencing with the year 1864, have been adopted, as relating more especially to these matters.

R. M.

CONTENTS.

PART I.

COAL INDUSTRIES.

CHAPTER I.

DURHAM AND NORTHUMBERLAND COAL-FIELD.

PAGE

Early History of the Coal-field—Extent, Area, and Geological Features of Coal-field—Varieties of Coal and Analyses—Production and Distribution of Coal by Railway and Sea—Prices and Cost of Production—Population employed in Coal Mining—Resources and probable Duration of Coal-field 1

CHAPTER II.

YORKSHIRE COAL-FIELD.

Description of Coal-field—Sheffield, Leeds, and Barnsley, &c., districts—Principal Coal Seams—Analyses of Coals—Barrow Silkstone Colliery near Barnsley—Production of Coal and Distribution by Railway—Price of Coal and cost of Production—Population employed in Coal and Ironstone Mining since 1873—Resources and probable Duration of Coal-field (including Yorkshire, Derbyshire and Nottinghamshire) . . . 32

CHAPTER III.

CUMBERLAND AND WESTMORELAND COAL-FIELDS.

Description of Cumberland Coal-field—Strata and Coal Seams in Whitehaven and Workington Districts—Analysis of Coal—Prices, Production, and Distribution by Railway, Coastwise, and Exported—Population employed in Coal Mining—Resources and Probable Duration of Coal-field—Westmoreland Coal-field—Population Employed and Coal Raised . . . 59

CHAPTER IV.

LANCASHIRE COAL-FIELD.

PAGE

General Description of Coal-field—Principal Coal Seams Wigan and Burnley Districts—Analyses and Production of Coal—Deep Pits at Rosebridge Collieries, Wigan, and Ashton Moss, near Manchester—Pemberton Colliery, General Arrangements—Coal Washing Apparatus—Distribution of Coal—Bridgewater Navigation—Sent Coastwise and Exported—Population employed in Coal Mining—Price of Coal and Cost of Production—Resources of Coal-field, and probable Duration 68

CHAPTER V.

CHESHIRE COAL-FIELD.

Description of Coal-field and Principal Seams—Analyses, Production, and Distribution of Coal—Population Employed in Coal Mining—Resources of Coal-field and probable Duration 92

CHAPTER VI.

DERBYSHIRE COAL-FIELD.

Description of Coal-field and Succession of Strata at Kilburne and Shipley Collieries—Analyses, Production, and Distribution of Coal—Prices of Coal—Population Employed in Coal and Ironstone Mining—(Resources and Duration, included in the Great Coal-field of York, Derby, and Notts). 99

CHAPTER VII.

NOTTINGHAMSHIRE COAL-FIELD.

Description of Coal-field and Section of Strata at Cinderhill Colliery—Analyses, Production, and Distribution of Coal by Railway—Population employed in Coal Mining in Nottinghamshire—(Resources and Duration, included in the Coal-field of York, Derby, and Notts) 111

CHAPTER VIII.

LEICESTERSHIRE COAL-FIELD.

Description of Coal-field—Section in the Moira and Coleorton Districts—Analyses, Production, and Distribution of Coal—Population Employed in Coal Mining—Resources and Probable Duration of Coal-field 118

CHAPTER IX.

PAGE

WARWICKSHIRE COAL-FIELD.

Description of Coal-field and Succession of Strata at Griff Colliery—Production and Distribution of Coal—Cost of Production and Prices—Population employed in Coal Mining—Resources and probable Duration of Coal-field 125

CHAPTER X.

SHROPSHIRE COAL-FIELD.

Description of Coal-field, and Section of Strata at Coalbrookdale—Analyses, Production, and Distribution of Coal—Prices and Cost of Production—Population employed in Coal and Iron Mining—Resources and probable Duration of Coal-field 132

CHAPTER XI.

NORTH STAFFORDSHIRE COAL-FIELD.

Description of Coal-field, its Extent, Area, and Succession of Strata—Coal Seams and Ironstone Measures—Cheadle Coal-field—Analyses, Production, and Distribution of Coal—Quantities Consumed in Ironworks, Potteries, Brick-works, &c.—Price of Coal and Cost of Production—Population Employed in Coal and Ironstone Mining—Resources and probable Duration of Coal-field 140

CHAPTER XII.

SOUTH STAFFORDSHIRE AND WORCESTERSHIRE COAL-FIELD.

Description of Coal-field—South Staffordshire Mines Drainage Association, its Objects—Analyses, Production of Coal-field, and of the Area under the Mines Drainage Act—Yield of Coal Seams per Acre—Distribution of Coal—Prices and Cost of Production—Population employed above and below Ground—Average Output per Man—Resources and probable Duration of Coal-field 153

CHAPTER XIII.

NORTH WALES: ANGLESEA, FLINTSHIRE, AND DENBIGHSHIRE COAL-FIELDS.

Description of the Anglesea, Denbigh, and Flint Coal-fields and Succession of Strata—Analyses, Production and Distribution of Coal—Population employed in Coal Mining—Resources and probable Duration of Coal-fields 172

CHAPTER XIV.

SOUTH WALES: PEMBROKESHIRE, GLAMORGANSHIRE, CAERMARTHENSHIRE, BRECKNOCKSHIRE, AND MONMOUTHSHIRE COAL-FIELD.

| | PAGE |
|---|------|
| Description of Coal-field, including its extension through the Counties of Pembroke, Glamorgan, Caermarthen, Brecon, and Monmouthshire—The Thickness of Strata and Seams of workable Coals—Analyses of the several varieties of Coal, Anthracitic and Bituminous—Coke manufacture at Ebbw Vale—The Coppée Process—The Bességes Process as carried out in France—Production of Coal-field—Parish Returns—Deep Winning at the Harris Navigation Pit—Bute Docks—Distribution of Coal Coastwise to Foreign Countries and by Railway—Prices and Cost of Production—Resources and probable Duration of Coal-field | 188 |

CHAPTER XV.

GLOUCESTERSHIRE COAL-FIELD.

| | |
|---|-----|
| Description of Coal-field—Section of Strata—Area of Woods and Plantations in Forest, and Ancient Rights of Miners—Analyses of Coal—Production and Distribution by Railway and by Ship—Price of Coal—Population employed in Coal and Iron Mining—Resources and probable Duration of Coal-field | 223 |
|---|-----|

CHAPTER XVI.

THE BRISTOL COAL-FIELD IN GLOUCESTERSHIRE AND SOMERSETSHIRE.

| | |
|---|-----|
| General description of the Bristol and Badstock Coal Basin—The Clapton-in-Gordano and Severn Basin, and the Nailsea Basin—Succession of Strata—Analyses, Production, and Distribution of Coal—Prices of Coal—Population employed in Coal Mining—Resources and probable Duration of Coal-field | 235 |
|---|-----|

CHAPTER XVII.

DEVONSHIRE COAL AND LIGNITE DEPOSITS.

| | | |
|---|---|-----|
| <i>Description of Bovey Tracey Coal of Devon—Analyses and Production of</i> | <i>Lignite Deposits—Anthracite of Bideford—Lignite and Anthracite</i> | 249 |
|---|---|-----|

CHAPTER XVIII.

THE COAL-FIELDS OF SCOTLAND.

PAGE

| | |
|--|-----|
| General Description of the Coal-fields—The Carboniferous Series of Scotland—Section of Strata, Order and Occurrence of Coal Seams and Ironstone Measures in different Areas—Varieties of Coal and Analyses—Gas Producing Coals, Cannels, Analyses, and Yield of Gas in Cubic Feet—Production of Coal in the Eastern and Western Districts, and of the several Coal-fields—Distribution Coastwise and to Foreign Countries—Railway Distribution—Prices of Coal and Cost of Production—Population Employed in Coal and Ironstone Mining—Resources and probable Duration of the Coal-fields of Scotland | 254 |
|--|-----|

CHAPTER XIX.

THE COAL-FIELDS OF IRELAND.

| | |
|---|-----|
| Description—Northern (Bituminous) Group—Counties of Leitrim, Tyrone, and Antrim—Analyses of Coal—Southern (Anthracitic) Group, Leinster and Munster—Analyses of Coal—Production of Coal—Population employed in Coal Mining—Resources of Coal-fields | 283 |
|---|-----|

CHAPTER XX.

COAL-FIELDS OF THE UNITED KINGDOM.

| | |
|---|-----|
| General Summary—Areas of Coal-fields—Production of England, Wales, Scotland, and Ireland—Distribution of Coal by Railway—Coal brought into London—Coal sent Coastwise and exported to Foreign Countries—Population employed in Coal Mining—Resources and Probable Duration of Coal-fields | 294 |
|---|-----|

PART II.

IRON INDUSTRIES.

INTRODUCTORY CHAPTER.

| | PAGE |
|--|------|
| THE MINERALOGICAL CHARACTERS OF THE PRINCIPAL IRON ORES. BY FRANK RUTLEY, Esq., F.G.S. | 319 |

CHAPTER I.

DURHAM AND NORTHUMBERLAND IRON INDUSTRIES.

| | |
|---|-----|
| Ironstone of the Coal Measures and Analyses—Iron Ores of the Carboniferous Limestone and Analyses—Production of Iron Ore—Population employed in Iron Mining—Pig Iron Manufacture, early History—Production of Durham and Northumberland—Malleable Iron Works—Coal and Iron Ore used in Pig Iron Manufacture—Quantities of Iron Ore employed and Sources of Supply | 324 |
|---|-----|

CHAPTER II.

YORKSHIRE—(WEST RIDING) IRON INDUSTRIES.

| | |
|--|-----|
| Ironstone of the Coal Measures—Analyses and Production of Ironstone—Pig Iron Manufacture—Early History—Annual Production—Works in Operation—Bessemer Steel Works—Coal and Iron Ore used in the Manufacture of Pig Iron | 347 |
|--|-----|

CHAPTER III.

YORKSHIRE—NORTH RIDING (CLEVELAND DISTRICT) IRON INDUSTRIES.

| | |
|--|-----|
| Geology of—Analyses, Production and average Prices of Ore—Output of the more important Mines—Magnetic Iron Ore of Rosedale—Mines in Cleveland District—Ironstone Mining—Distribution of Ironstone—Population employed in Iron Mining—Barrow's Views on the Mineral Resources of the District—Pig Iron Manufacture—Early History, Production, Distribution and average Prices of Cleveland Pig—Coal and Ironstone used in Manufacture—Malleable Iron and Steel Works—Production and average Prices of Rails, Plates, Bars, and Angles—The Thomas Gilchrist Process of Steel Manufacture | 365 |
|--|-----|

CHAPTER IV.

PAGE

CUMBERLAND IRON INDUSTRIES.

| | |
|---|-----|
| Description of Iron Ore Deposits around Whitehaven—Alston Moor—Eskdale and Millom—Analyses, Production and Distribution of Ore—Population employed in Iron Ore Mining—List of Iron Mines—Pig Iron Manufacture—Charcoal Furnaces, their Early History—Steel Works—Iron Works—Pig Iron made—Coal and Ore used in Manufacture—Works in 1880—Malleable Iron Works and Coal employed | 415 |
|---|-----|

CHAPTER V.

LANCASHIRE IRON INDUSTRIES.

| | |
|---|-----|
| Description of Iron Ore Deposits in Furness—Analyses, Production and Distribution of Ore—Iron Mines in Lancashire—Population employed in Iron Mining—Pig Iron Manufacture—Early History—Barrow and Wigan Coal and Iron Co.'s Works—Production of Pig Iron—List of Iron Works—Malleable Iron and Bessemer Steel Works, and Coal employed—Mersey Steel Works—Coal and Iron Ore used in Pig Iron Manufacture—Sources of Iron Ore | 436 |
|---|-----|

CHAPTER VI.

CHESHIRE IRON INDUSTRIES.

| | |
|---|-----|
| Description of the Engineering and Metallurgical Works of the London and North-Western Railway, Crewe | 460 |
|---|-----|

CHAPTER VII.

DERBYSHIRE IRON INDUSTRIES.

| | |
|--|-----|
| Description of Ironstones of the Coal Measures—Analyses and Production of Ironstone—Pig Iron Manufacture in Derbyshire and Nottinghamshire—Early History of the Industry—Production and Works in Operation—Malleable Iron Works in 1811—Puddling Furnaces and Rolling Mills in recent years and Coal Consumed—Coal and Iron Ore Used in Pig Iron Manufacture—Districts furnishing Iron Ore | 462 |
|--|-----|

CHAPTER VIII.

NOTTINGHAMSHIRE AND WARWICKSHIRE IRON INDUSTRIES.

| | |
|--|-----|
| Ironstone of the Coal Measures—Analyses and Production | 478 |
|--|-----|

CHAPTER IX.

PAGE

SHROPSHIRE IRON INDUSTRIES.

Ironstone of the Coal Measures—Description—Analyses—Production of Ironstone—Yield of Measures and Cost of Working—Pig Iron Manufacture—Early History—Darby's successful Application of Coke in the Blast-Furnace at Coalbrook Dale Works—Production of Pig Iron—Malleable Iron Works—Introduction of Rolling Mills at Coalbrook Dale—Coal consumed in Malleable Iron Works—Coal and Iron Ore used in Pig Iron Manufacture—Districts supplying Iron Ore 480

CHAPTER X.

NORTH STAFFORDSHIRE IRON INDUSTRIES.

Description and Analyses of the Ironstones of the Coal Measures—Churnet Valley Ore and Analysis—Production and Distribution by Canal and Railway—Pig Iron Manufacture—Early History—Apedale and Silverdale Iron Works—Furnaces in Blast and Production of Pig Iron—Malleable Iron Works and Coal used—List of Works in 1880—Coal and Iron Ore used in Pig Iron Manufacture—Districts furnishing Ore . . . 499

CHAPTER XI.

SOUTH STAFFORDSHIRE AND WORCESTERSHIRE
IRON INDUSTRIES.

Description of Ironstone Measures of Coal-field—Analyses and Production of Ironstone—Pig Iron Manufacture—Early History—Sturtevant, Ravenson, and Dudley's Experiments in the Use of Coal previously coked—Production of Pig Iron—Coal and Iron Ore used in Manufacture—Calcination of Ores in Clamps and Kilns—Works in operation in 1880—Malleable Iron Works in 1880, coal used—Prices of Finished Iron . . . 518

CHAPTER XII.

NORTHAMPTONSHIRE IRON INDUSTRIES.

Geology of the Ironstone Deposits of the Northampton Sand—Analyses, Production, and Distribution of Ironstone—Iron Mines in 1880—Pig Iron Manufacture—Early History—Direct Process (Dr. C. W. Siemens' Patent) for making Iron and Steel at Towcester—Iron Works in operation in 1880—Production of Pig Iron—Coal and Ironstone used in Pig Iron Manufacture 538

CHAPTER XIII.

LINCOLNSHIRE IRON INDUSTRIES.

PAGE

| | |
|---|-----|
| Ironstone Deposits—Geology of North Lincolnshire—Scunthorpe, Frodingham—Analyses, Production, and Distribution of Ironstone—Mines in operation in 1880—Pig Iron Manufacture—Production since 1864—Coal and Ore used in Pig Iron Manufacture | 559 |
|---|-----|

CHAPTER XIV.

IRON INDUSTRIES OF NORTH WALES.

| | |
|---|-----|
| Iron Ore Deposits of Denbighshire and Flintshire—Analyses and Production of Iron Ore—Population employed in Iron Mining—Succession of Strata in Denbighshire—Pig Iron Manufacture—Early History—Production—Works in operation in 1880—Malleable Iron Works—Coal and Iron Ore used in Pig Iron Manufacture | 574 |
|---|-----|

CHAPTER XV.

IRON INDUSTRIES OF SOUTH WALES AND MONMOUTHSHIRE.

| | |
|--|-----|
| Ironstones of the Coal Measures—Order of Occurrence—Description and Analyses—Iron Ore Deposits of the Carboniferous Limestone, Whitechurch, Mwyndy, Hendy, and Wenvoe—Production and Analyses—Pig Iron Manufacture—Early History—Monmouthshire, Brecknockshire and Glamorganshire—Account of Cyfarthfa Works—Anthracite Pig Iron—Early History—Production of Pig Iron in Bituminous and Anthracite Coal districts since 1855—Mills and Forges and Bessemer Steel Works and Coal employed—Coal and Iron Ore used in Pig Iron Manufacture in South Wales | 584 |
|--|-----|

CHAPTER XVI.

GLOUCESTERSHIRE IRON INDUSTRIES.

| | |
|---|-----|
| Iron Ore of the Carboniferous Limestone—Description of Deposits—Mines in Operation in 1880—Analyses and Production of Brown Iron Ore—Output of the more important Mines—Distribution of the Forest of Dean Ore—Pig Iron Manufacture—Early History—Production and Yield of Furnaces—Malleable Iron Works, Early History—Quantities of Coal and Iron Ore used in Pig Iron Manufacture | 642 |
|---|-----|

CHAPTER XVII.

SOMERSETSHIRE IRON INDUSTRIES.

PAGE

- Description of the Spathose Iron Ore Deposits of the Brendon and Eisen Hills
 —Early explorations at Gupworthy Mine—Analyses and Production of
 Iron Ore—Pig Iron Manufacture—Mills and Forges 665

CHAPTER XVIII.

WILTSHIRE, DORSETSHIRE, OXFORDSHIRE, BUCKINGHAMSHIRE,
 HAMPSHIRE, AND THE ISLE OF WIGHT
 IRON INDUSTRIES.

- Iron Ore Deposits of the Lower Greensand, Coral Rag, and Marlstone rocks
 of these Counties—Analyses and Production of Ore—Pig Iron Manufac-
 ture in Wiltshire, at Westbury and Seend—Production of Pig Iron in
 Wiltshire (including Gloucestershire and Somersetshire)—Charcoal Pig
 Iron Manufacture in Hampshire—Coal and Iron Ore used in Manufacture 673

CHAPTER XIX.

DEVONSHIRE IRON INDUSTRIES.

- Iron Ore Deposits—Early account of Magnetic Ores wrought at Haytor—
 Deposits at Hennock, Buckfastleigh, North Molton, Smallacombe, Torbay
 (Paint ore) and Exmoor—Analyses, Production and Distribution of Ores 688

CHAPTER XX.

CORNWALL IRON INDUSTRIES.

- Early references to Iron Ore Deposits—Borlase and Pryce—Restormel Iron
 Mine, account of—Analyses of Restormel and other Iron Ores raised in
 Cornwall—The Perran Iron Lode—Production and Distribution of Iron
 Ore—Mines and Localities producing Ore—Distribution of Iron Ore . 702

CHAPTER XXI.

IRON INDUSTRIES OF SCOTLAND.

- Iron Ores of the Coal Measures—Clay Bands and Black Bands—Discovery
 of Black Band Iron Ore by Mushet, in 1801—Analyses and Production
 of Clay and Black Band and other Iron Ores—Population employed in
 Iron Mining—Pig Iron Manufacture—Early History, 1750—Charcoal
 Iron—Carron Works—Smeaton's Blowing Machinery—Account of Devon
 Iron Works, 1782—Hot Blast, invention by Neilson, 1829—Extension of
 Iron Works and their resources—Production of Pig Iron—Works in 1880—
 Distribution and average Prices of Pig Iron—Exports and Home Con-

CONTENTS.

xix

| | PAGE |
|--|------|
| sumption—Malleable Iron Works—Account of Dalziel Steel Works— Production of Malleable Iron and prices—Coal and Iron Ore used in Pig Iron Manufacture—Iron Shipbuilding | 719 |

CHAPTER XXII.

IRON INDUSTRIES OF IRELAND.

| | |
|---|-----|
| Description of the Ironstone Measures of the Northern Coal-fields, Leitrim, Tyrone, Antrim — Analyses and Production — Southern Coal-fields, Leinster, Castlecomer, Kilkenny—Analyses and production—Iron Ore Deposits (Tertiary Age)—County Antrim—Magnetic Ores, county Wick- low—Ores [of county Cavan—Analyses and Production of Ore—List of Iron Mines in 1880, and details of Production—Pig Iron Manufacture— Works at Drumshambo—Account of the Arigna Iron Works—Materials employed in Manufacture—Production of Pig Iron in 1856 | 755 |
|---|-----|

CHAPTER XXIII.

FOREIGN IRON ORES IMPORTED.

| | |
|--|-----|
| General Description of these Ores—Their mode of occurrence—Analyses of Ores—Quantities imported from Spain, Portugal, France, Algeria, Italy, Greece, Norway, Sweden, Russia, and Turkey in Asia—Bauxite and Analyses | 785 |
|--|-----|

CHAPTER XXIV.

FLUXES (LIMESTONES) USED IN PIG IRON MANUFACTURE.

| | |
|--|-----|
| Fluxes (Limestones) used in the reduction of the Ores of Iron in the Blast Furnaces of Great Britain—Description and Analyses of Fluxes used in Durham and Northumberland and the North Riding of Yorkshire— Cumberland—Lancashire—North and South Staffordshire—Northampton- shire—Wiltshire—South Wales and Scotland | 804 |
|--|-----|

CHAPTER XXV.

COAL USED IN PIG IRON MANUFACTURE IN GREAT BRITAIN.

| | |
|---|-----|
| Coal used towards the close of the past century—Mr. W. Jessop's Inquiry— Coal Commission and Mining Record Office Inquiries—Coal used in recent years since 1871—Details of Coal used and Iron made in the years 1872 and 1880—Extent of economy in each year since 1871 | 813 |
|---|-----|

| | |
|--|-----|
| GEOLOGICAL DISTRIBUTION OF BRITISH IRON ORES. By MR. HILARY BAUWMAN, F.G.S. | 821 |
|--|-----|

APPENDICES.



APPENDIX.—No. 1.

| | PAGE |
|--|------|
| IRON ORE PRODUCTION OF THE MINES OF THE UNITED KINGDOM | 825 |
| PURPLE ORE OBTAINED FROM METAL EXTRACTION WORKS. | 827 |



APPENDIX.—No. 2.

| | |
|--|-----|
| FIG IRON MANUFACTURE, VARIOUS RETURNS OF PRODUCTION SINCE THE YEAR 1740 | 829 |
| FIG IRON EXPORTED FROM THE UNITED KINGDOM SINCE THE YEAR 1829 | 839 |



APPENDIX.—No. 3.

| | |
|---|-----|
| MALLEABLE IRON WORKS (MILLS AND FORGES) AND STEEL WORKS —LIST OF WORKS AND PRODUCTION OF BAR IRON IN THE YEAR 1750—AND WORKS IN GREAT BRITAIN SINCE THE YEAR 1861 | 840 |
| BESSEMER STEEL WORKS IN GREAT BRITAIN, AND PRODUCTION OF BESSEMER STEEL SINCE 1871 | 843 |
| SIEMENS' OPEN HEARTH STEEL WORKS IN GREAT BRITAIN, AND PRODUCTION OF OPEN HEARTH STEEL SINCE 1871 | 845 |
| SIEMENS' REGENERATIVE GAS FURNACES FOR MELTING STEEL IN CRUCIBLES, AND PRODUCTION OF STEEL SINCE 1873 | 847 |

APPENDIX.—No. 4.

| | PAGE |
|---|------|
| TIN PLATE MANUFACTURE. PRODUCTION OF TIN, TERNE, AND | |
| BLACK PLATES SINCE THE YEAR 1871 | 849 |
| „ LIST OF WORKS IN GREAT BRITAIN IN THE YEAR 1880 | 851 |
| „ EXPORTS OF TIN PLATES FROM GREAT BRITAIN SINCE THE | |
| YEAR 1873 | 854 |
| „ EXPORTS OF TIN PLATES, AND COUNTRIES TO WHICH | |
| EXPORTED IN EACH YEAR SINCE 1873 | 854 |
| „ EXPORTS AND VALUE FOR THREE YEARS ENDING 1880 | 855 |

:

| | |
|-----------------|-----|
| INDEX | 857 |
|-----------------|-----|





THE
COAL AND IRON INDUSTRIES
OF
THE UNITED KINGDOM.

PART I.
—♦—
COAL INDUSTRIES.



MAP OF IRELAND. Shewing the areas of COAL FIELDS and position of the principal IRON ORE WORKINGS IN 1881.





THE
COAL AND IRON INDUSTRIES
OF
THE UNITED KINGDOM.

PART I.
COAL INDUSTRIES.

CHAPTER I.

THE DURHAM AND NORTHUMBERLAND (OR GREAT NORTHERN)
COAL-FIELD.

Early History of the Coal-field—Extent, Area, and Geological Features of Coal-field—Varieties of Coal and Analyses—Production and Distribution of Coal by Railway and Sea—Prices and Cost of Production—Population employed in Coal Mining—Resources and probable Duration of Coal-field.

Early History of the Great Northern Coal-field.—The early history of this coal-field presents numerous and interesting features, and extends to a remote period; a few of the more general facts may be referred to. As early as the year A.D. 852 there is a record of the Abbey of Peterboro' receiving twelve cart-loads of fossil or pit coal. In 1180 there occurs, in Bishop Pudsey's book (Bishop of Durham), a grant of land to a collier, for providing coals for the cartsmith at Coundon, in the County of Durham; similar grants being made at Bishopwearmouth and Sedgfield in the same county.

Again, in the reign of Henry III., A.D. 1239, a charter was granted to the freemen of Newcastle-upon-Tyne to dig coals in the castle fields, and it appears that it was about this time that coal was first sent to London. About the end of Edward I.'s reign, A.D. 1305, considerable quantities of coal were used by

brewers and smiths; this was followed by numerous complaints being made of the injurious effects of the smoke; the burning of coal was prohibited, and by commission from the King fines levied to prevent it. Nothing appears to have resulted from this prohibition, as coals are stated to have been used a few years later at the King's coronation. In Edward III.'s time a licence was granted to the freemen of Newcastle-upon-Tyne to work coals within the town walls; and about A.D. 1867 coals were also worked in the neighbourhood of Winlaton, near Newcastle-upon-Tyne.

The first government tax was laid upon coals in the year 1879; in 1421 a duty of twopence per chaldron was paid to the Crown "on all coals sold to persons not franchised in the port of Newcastle." This duty having got into arrear, payment was demanded by Queen Elizabeth, and in lieu of arrears a duty of one shilling per chaldron was imposed, which was enforced to the time of Charles II., when it was settled on his natural son the Duke of Richmond. In 1799 the Government of the period purchased the above tax for an annuity of £19,000; this was ultimately repealed in 1831, the tax having been in operation upwards of four centuries in the neighbourhood of the Tyne.

Queen Elizabeth imposed a tax of five shillings per chaldron on coals sent over sea, to which King James I. added three shillings and fourpence per chaldron, and an additional one shilling and eightpence per chaldron on coals exported in foreign ships. After the great fire of London, the Lord Mayor was granted an impost of one shilling per chaldron for rebuilding the City; this was further increased to three shillings per chaldron. In the year 1670 an additional tax of two shillings per chaldron was imposed by Parliament, for the purpose of rebuilding fifty-two parish churches, and in 1677 a further tax of three shillings per chaldron was imposed, partly for rebuilding St. Paul's Cathedral. These duties for rebuilding churches continued during the reign of Queen Anne.

The duties on coal during the eighteenth century varied considerably, being at one time as high as nine shillings and fourpence per chaldron; these duties however have, except the City of London tax on coals of one shilling and one penny per ton, long since been repealed.

The export duty on coals to foreign countries was wholly repealed, by the Act 18 & 14 Vict. c. 95, from 14th August, 1850.

Previous to this period the duties levied on coal, cinders and culm exported from the United Kingdom was three shillings and fourpence per ton in British ships, and six shillings and eightpence per ton in foreign ships, the duties on small coal, &c., being respectively two shillings per ton in British, and four shillings per ton in foreign ships.

The Great Northern, or Durham and Northumberland Coal-field.—This extensive area, comprising an exposed coal-field of 460 square miles and a concealed area of 225 square miles, possesses some of the most important coal-seams wrought in Great Britain. The rivers Blythe, Tyne and Wear naturally give names to the three great divisions of the coal-field. The Blythe coal-field, the Tyne coal-field, and the Wear coal-field are really one, extending from near Warkworth at the mouth of the river Coquet on the north, to near the north bank of the Tees (within 6 miles of Barnard Castle) on the south—a distance of nearly fifty miles in length, by twenty miles in breadth; its greatest diameter being near the centre, along the course of the river Tyne, narrowing in the north after passing the river Blythe. Beyond the exposed and concealed coal-fields above referred to, embracing an area of 685 square miles, there is, extending under the German Ocean, another area of 111 square miles known to be available.

From the Coquet near Warkworth to the river Tyne, the German Ocean limits the coal-field to the east; the Permian rocks then overlie the coal measures, forming an escarpment of magnesian limestone which ranges to the southward. As far south as Hartlepool the sea-cliffs are of magnesian limestone; beyond this is lower land formed of Triassic rocks. The southern boundary of the coal measures will probably be found to occur a little north of Hartlepool, and will from thence range south-westwards to a little north of Bishop Auckland. “The centre of the basin is on a line beneath the North Seaton Colliery and Jarrow. South of the Tyne the axis of the basin passes under the Permian rocks and the magnesian limestone in a line from Jarrow to Monkwearmouth Colliery, which is supposed to be the bottom of the basin. The beds there are nearly flat; they are supposed to rise on all sides.”* The eastern limit of the coal basin will therefore be well out to sea under the German Ocean.

The coal measures of the northern coal-field are about 2,000

* Mr. H. H. Howell. Report of Royal Coal Commission, vol. i., p. 189.

feet in thickness. Those which contain the workable seams probably represent the "Middle Coal Measures" of more southern districts. The "Lower Coal Measures," or Gannister Beds, contain only thin seams; this division cannot be identified in the northern part of the coal-field. It is not certain which part of the series, if any, represents the "Upper Coal Measures." Professor Hull takes the "High Main" as the top of the Middle Coal Measures; this line of division is useful as marking off the more important seams, those lying above the High Main being comparatively unimportant.

The most important seams are the High Main and the Low Main; they are usually separated by about 60 fathoms of strata, in which several other seams occur. As a rough guide and aid to memory it may be useful to note that in Northumberland the following seams, which are some of the most constant in the coal-field, are separated from each other by about 30 fathoms of strata:—

| | |
|-------------------------------------|----------------------|
| Seventy-fathom or Black Close Seam. | Low Main. |
| High Main. | Beaumont, or Harvey. |
| Yard Seam. | Brockwell. |

The following section by Professor Hull, F.R.S., indicates the position, thickness, and order of occurrence of the coal-seams in the Newcastle district.*

COAL SERIES OF NORTHUMBERLAND AND DURHAM.
(NEWCASTLE DISTRICT.)

| | | Ft. | In. |
|---------------|---|----------------|-----|
| UPPER SERIES. | <i>Closing Hill Seam</i> | 1 | 8 |
| | Strata | 450 | 0 |
| | <i>Hebburn Fell Seam</i> | 2 | 8 |
| | Strata | 250 | 0 |
| | <i>Five-quarter Seam</i> | 4 | 0 |
| | Strata | 260 | 0 |
| | <i>Three-quarter (Black Close) Seam</i> | 2 | 0 |
| | Strata | 50 to 180 | 0 |
| | 1. <i>High Main Coal</i> | 6 | 0 |
| | Strata | from 33 to 150 | 0 |

* "Coal Fields of Great Britain," 4th edition, p. 276.

COAL SERIES OF NORTHUMBERLAND AND DURHAM—*continued*.

| | | Ft. | In. |
|-----------------------------------|---|----------------|-----|
| 2. <i>Metal Coal</i> | . | 1 | 6 |
| Strata | . | 33 | 0 |
| 3. <i>Stone Coal</i> | . | 1 | 6 |
| Strata | . | 60 to 100 | 0 |
| 4. <i>Yard Coal</i> (variable) | . | 2 | 10 |
| Strata | . | 60 to 100 | 0 |
| 5. <i>Bensham Coal</i> | . | 2 ft. 5 in. to | 5 0 |
| Strata | . | 78 | 0 |
| 6. <i>Five-quarter Coal</i> | . | 3 | 0 |
| Strata | . | 48 | 0 |
| 7. <i>Low Main or Hutton Coal</i> | . | 6 | 0 |
| Strata | . | 30 to 100 | 0 |
| 8. <i>Crow Coal</i> (inconstant) | . | 2 | 10 |
| Strata | . | 24 | 0 |
| 9. <i>Five-quarter Coal</i> | . | 3 | 8 |
| Strata | . | 30 | 0 |
| 10. <i>Ruler Coal</i> | . | 1 | 10 |
| Strata | . | 96 | 0 |
| 11. <i>Townley or Harvey Coal</i> | . | 3 | 1 |
| Strata | . | 42 | 0 |
| 12. <i>Jetty Coal</i> | . | 2 | 2 |
| Strata | . | 42 | 0 |
| 13. <i>Stone Coal</i> | . | 2 | 5 |
| Strata | . | 18 | 0 |
| 14. <i>Five-quarter Coal</i> | . | 3 | 4 |
| Strata | . | 30 | 0 |
| 15. <i>Three-quarter Coal</i> | . | 2 | 6 |
| Strata | . | 54 | 0 |
| 16. <i>Brockwell Coal</i> | . | 2 | 11 |

The foregoing table applies chiefly to the neighbourhood of Newcastle and the districts to the west of that town. Slight variations and differences of names are met with in other districts, but this sufficiently describes the general succession. It is doubtful if the seams below the Low Main are of much value in the south-east of Northumberland and neighbouring parts of Durham. Boreholes put down to explore them at some collieries of late years have failed to prove the expected seams.

Most of the other important seams can be traced through the greater part of the coal-field, being known by various names in different parts. But on the north of the river Wansbeck there is some difficulty in recognizing the beds. Just north of the river the Low Main has been worked. The "Main Seam" of Ashington and Longhirst Collieries represents the "Grey Seam" (metal and stone coals), of other districts. But the relations of the seams in other collieries are somewhat uncertain.

It has long been the custom in this district to designate many seams by their thickness; thus, the "Yard Coal" is a coal which, where first chiefly worked, averaged a yard in thickness. Other seams are spoken of as so many parts of a yard; thus a "five-quarter seam" is a coal about 3 feet 9 inches thick. The seam most commonly known by this name is that next above the Low Main; but in the table three other seams have the same name.

The Northern coal-field is much intersected by faults, some of very great amount. In the immediate neighbourhood of these the beds often have a high dip, but through the greater part of the coal-field the seams lie at a gentle inclination. Besides the faults, or "slip troubles" of the miners, there are basaltic dykes known as "whin troubles."

In the western and northern parts of Northumberland a large quantity of coal is raised from seams in the carboniferous limestone series. The beds here are on the same geological horizon as the thick limestones of Derbyshire, but on going northwards we find the limestones to be gradually split up by shales and sandstones, until in Durham and Northumberland limestone forms but a small part of the whole.

In Northumberland there are a large number of coal seams worked in these lower beds. In the south of the county the "Little Limestone Coal," or Acomb seam, is the most important; in central Northumberland the Shilbottle seam; in the northern part of the county many seams are worked, the most important collieries being those near Scremerston.

Although as compared with the true coal measures the yield from the limestone district is small, yet taken together it comes to a considerable amount. In 1879 the total yield of the limestone coals in Durham and Northumberland was about 250,000 tons, the total production of the Great Northern coal-field being 29,552,079 tons.

Clay ironstone is not an important product of the Northern coal-field. It is found, however, in some places of sufficient thickness to have been worked. It usually occurs in thin beds in the shale, and contains large numbers of *Anthracosia*; hence it is usually known to the miners as "Mussel-band." The most constant portion of this bed is a little way above the Low Main seam; but occasionally there are shell beds, which sometimes contain ironstone, above other seams.

Clay ironstone in nodules in shale occurs sometimes in the limestone series. The most important horizon for this is below the "Four-fathom Limestone," as worked at Brinkburn and numerous places north of the Tyne; and at a much lower horizon, Ridsdale, Hareshaw, &c.

The coal-field of Northumberland and Durham is naturally divided into districts, which produce the following descriptions of coal: household fire coal, gas coal, manufacturing coal, steam coal, and coking coal.

Household Coal.—The household fire coal of these counties has ever been held in high repute. The celebrated "Wallsend" * was for a long period of years produced from the High Main Coal of the Tyne, the colliery from which it was produced being at Wallsend on the Tyne, and hence the origin of the designation "Wallsend" to distinguish the "Best Household Fire Coal." This coal was also produced at the various collieries of Percy Main, Walker, Heaton, Willington, &c., on the Tyne. It was not that coal of similar, or, indeed, as afterwards turned out, of superior quality, was not produced on the Wear and Tees, but the coal of such quality on the Wear being mixed with and sold with other coals of an inferior quality, no coal of that river, or, indeed, in the whole coal-field, bore such an excellent character, or sold at such high prices as the "Wallsends" of the Tyne. Time, however, arrived when the Hutton coal seam of the Wear (the Low Main of the Tyne district) was sold unmixed with other coal; and being found in the neighbourhood of Rainton, Lambton, and Hetton, of very superior quality, it was brought into the market as a Wallsend coal. The superior Wallsends of the Tyne being worked out, it took their place, and up to

* The name has since been given to several coals, which are not equal to the original.

the present time, has been sold as the best Wallsend coal. This coal is now produced from the Hutton seam of the neighbouring collieries of Stewart, Lambton, Hetton, and Haswell. The only coal for a long period on the Tees, approaching to the quality of the Wallsends of the Wear, was Tees Wallsend, or the Five-quarter and Main coal of the Black Boy Colliery, but more recently, the Five-quarter seam of the Hartlepool district has produced a coal approaching to the Wear Wallsends. Household fire coal of second quality is produced from the collieries of all the other localities.

The household coal of the Great Northern Coal-field has ever had a high reputation in the London market, where it is known as "seaborne coal;" it is largely imported, and commands a high price; it possesses great heating power, is steady and uniform in combustion, leaving but little residue and a small proportion of ash. A few analyses will illustrate the constituents of household coal, that of the Hutton seam being now the best variety in the district.

| Constituents. | Haswell. | Hartley. | Original Hartley. |
|------------------|----------|----------|-------------------|
| Carbon | 83·47 | 84·284 | 81·18 |
| Hydrogen | 6·68 | 5·522 | 5·56 |
| Nitrogen | 1·42 | 2·075 | 0·72 |
| Sulphur | ·06 | 1·181 | 1·44 |
| Oxygen | 8·17 | 6·223 | 8·03 |
| Ash | ·20 | 0·715 | 3·07 |
| | 100·00 | 100·00 | 100·00 |

Gas Coal and Analyses.—The best gas coal in this district is produced from the Hutton seam, which also, as previously stated, produces the best household coal. It is, however, less compact, and liable to disintegration, and as such is not so well adapted for a first-class household coal. Consequently it is of less value for that purpose, but equally valuable as a gas coal. This variety of coal is obtained from the Felling, Pelaw, Pelton, and other collieries, and from some of the lower seams on the Tyne. It is also produced from the same seam on the Wear, and from the Brockwell seam on the Tees. Gas for illuminating purposes was originally introduced by Mr. Murdoch, an assistant of Mr. James Watt, who first lighted his office at Redruth, in Cornwall,

and used gas condensed in cylinders, as a light at night in going to the mines, about the year 1792.

Afterwards, Murdoch having made several improvements in his apparatus, between the years 1798 and 1802,* lighted up with gas the engineering works of Messrs. Boulton and Watt at Soho, near Birmingham, in the last named year. This afforded an opportunity for making a public display of the new system of lighting on the occasion of the Peace rejoicings of that time. About this period Mr. Clegg, a gentleman to whose energy and scientific skill, gas lighting in its earliest stages is much indebted, was working successfully in the same direction. In the year 1810, the Act of Parliament incorporating the London and Westminster Gas Light and Coke Company was passed, and on the 31st December, 1813, Westminster Bridge was lighted with gas. This step was soon followed by the introduction of gas in the place of oil in several of the leading thoroughfares of the metropolis.

Each ton of coal when distilled yields 10,500 cubic feet of gas, and even more. Bands of cannel coal were formerly wrought in Levenson's Colliery, Wallsend; Pelton Main and Washington, and Ramsey's colliery, Newcastle-on-Tyne. The cannel of this last-named pit yielding between 10,000 and 11,000 cubic feet of gas per ton. The bituminous coal of this district is in great request for gas-making. It would be invidious to refer to all those collieries furnishing supplies for this purpose; those selected and of which analyses are given may be regarded as some of the more important, in which the constituents appear as follows:—

| Constituents. | South Pearth. | Bowden Close. | Willington. | Garesfield. |
|------------------|------------------|------------------|-------------|-------------|
| Carbon | 81·41 | 84·92 | 86·81 | 86·9 5·4 |
| Hydrogen | 5·83 | 4·53 | 4·96 | |
| Nitrogen | 2·05 | 0·96 | 1·05 | |
| Sulphur | 0·74 | 0·65 | 0·88 | |
| Oxygen | 7·90 | 6·66 | 5·22 | 5·2 |
| Ash | 2·07 | 2·28 | 1·08 | 2·5 |
| | 100·00 | 100·00 | 100·00 | 100·00 |

These coals yield coke varying from 66·70 to 72·19 per cent.

* An account of which will be found in the Philosophical Transactions for 1808.

Steam Coal and Analyses.—The best coal for steam purposes produced in the Northern coal-field lies to the north of the ninety-fathom dyke, in the Hartley district, and comprises almost all the coal north of that dyke, along the coast from Hartley, and to the crop of the coal in those districts to Warkworth. It is an interesting fact that the same bed of coal, the Hutton seam (or the Low Main of the Tyne), is not only continuous throughout almost the whole extent of the coal-field, but that it also yields the best description of three varieties of coal, suitable for purposes not at all similar to each other, viz., the best household, the best gas, and the best steam coal.

The best coals for these special purposes are obtained from the Low Main seam of the district. Recent workings have shown that the Low Main extends, as a steam coal, under the district in south-east Northumberland which produces good household coal. The annexed analyses of this and other seams of coal, will show generally the prominent constituents of the seams examined.

| Constituents. | Buddles Hartley. | Newcastle Hartley. | Haswell Sunderland. | Seaton Burn. |
|------------------|---------------------|-----------------------|------------------------|-----------------|
| Carbon | 78·69 | 81·81 | 83·71 | 78·65 |
| Hydrogen | 6·00 | 5·50 | 5·30 | 4·65 |
| Oxygen | 10·07 | 2·58 | 2·79 | 13·66 |
| Nitrogen | 2·37 | 1·28 | 1·06 | ... |
| Sulphur | 1·51 | 1·69 | 1·21 | 0·55 |
| Ash | 1·36 | 7·14 | 5·93 | 2·49 |
| | 100·00 | 100·00 | 100·00 | 100·00 |

Coking and Manufacturing Coal.—The best coking coal of the district is obtained from the lower seams of the Tyne and from South Durham. Manufacturing coal, either separate or mixed with a gas coal, is associated with it, and is obtained from the lowest seam of the Auckland district. The best varieties of coke are obtained from the lower coal seams at Marley Hill, Garesfield, Wylam, Townley, &c., on the Tyne, and in Durham from the lower seams at Etherley, Brancepeth, Black Boy, &c.; the seams are said to be equivalent to the Garesfield or Brockwell seams of the Tees, and yield coke of the best quality for locomotive consumption, and for the reduction of the ores of iron in the Cleveland district. This coke is largely exported to remote

districts, its superior quality bearing a high rate for carriage. It is extensively used in the iron-making districts of the north-west coast—Lancashire, and Cumberland; also in Lincolnshire, and other districts even more remote. A second quality of coke is obtained from the Harvey or Beaumont seam, and from the washed small coal of the Hutton seam.

The Great Northern coal-field is essentially a bituminous coal deposit. It does not contain any anthracite, nor, with the exception of a thin bed in a limited locality, does it contain any cannel coal. The specific gravity of this coal varies from 1·2 to 1·5, and the quantity of carbon from 72 to 75 per cent. Further detailed particulars of this coal-field will be found in the pages of the “Coal Fields of Great Britain,” by Professor Hull, F.R.S., and in the “Transactions of the Mining Engineers of Newcastle-upon-Tyne.” The Low Main seam of the Tyne, the equivalent of which is the Hutton seam of the Wear, furnishes the least caking coal of the coal-field, but even the small coal when coked loses all trace of its original form, and leaves the ovens as large masses of coke. The caking coal of the coal-field, though valuable for many purposes, is entirely unfit for use in the raw state in the blast furnaces, in which its fusing property, by impeding the blast, causes the contents of the furnace to hang and slip, and thus to descend at irregular intervals. Against this disadvantage however may be placed the extreme hardness and strength of the coke it produces, which is thereby rendered capable of resisting the crushing effects of a high column of materials existing in the blast furnace. Some interesting experiments made at the Clarence Ironworks showed that a cube of coke two inches on a side, supported a weight of 25 cwt. when cold, and 20 cwt. when hot, before it was crushed.

The process of coking in the ordinary ovens may be thus explained:—When the oven is re-filled with a proper charge, the coal is fired at the surface by the radiated heat from the roof; enough air is admitted to consume the gases given off by the coal, and thus a high temperature is maintained in the roof of the oven. The coal is by this means melted; and those portions of it, which under the influence of a high temperature can of themselves form gaseous compounds, are given off, forming at the moment of their liberation small bubbles or cells; the coke now left is quite safe from waste unless a further supply of air is

allowed to have access to it. At this stage of the process the coke assumes a pentagonal form and columnar structure. When the coke is left exposed to heat for some time after it is formed, it becomes harder, and works better, from being less liable to crush in the furnace, or to decrepitate on exposure to the blast. The best variety of coke obtained from Durham coal yields the annexed results:—

| Constituents. | Durham Coal. | Average Analysis. |
|------------------|--------------|-------------------|
| Carbon | 93·150 | 84·92 |
| Hydrogen | ·721 | 4·53 |
| Nitrogen | 1·276 | ·96 |
| Oxygen | ·905 | 6·66 |
| Sulphur | ... | ·65 |
| Ash | 3·948 | 2·28 |
| Total | 100·000 | 100·00 |

In the Brancepeth district, the Brockwell and Busty seams of coking coal, extensively employed in the blast furnace, show the annexed results on examination:—

| Constituents. | Busty Seam. | | Brockwell Seam. |
|-----------------------|-------------|-------------|-----------------|
| | Upper part. | Lower part. | |
| Carbon | 81·22 | 78·46 | 83·40 |
| Hydrogen | 4·70 | 4·42 | 4·40 |
| Oxygen and Nitrogen . | 9·45 | 8·82 | 7·18 |
| Water | 0·85 | 0·99 | 0·99 |
| Ash | 3·28 | 6·17 | 3·50 |
| Sulphur | 0·81 | 1·83 | 1·00 |
| Total | 100·31 | 100·69 | 100·47 |

The coal of the above seams yields from 60 to 65 per cent. of its weight of coke, and its purity will be understood from the appended analyses of the seams in the following collieries:—

| Collieries. | Carbon. | Ash. | Sulphur. | Water. |
|----------------------|---------|------|----------|--------|
| Hamsteels | 92·53 | 6·36 | ·81 | ·21 |
| Consett | 91·88 | 6·91 | ·84 | ·37 |
| Whitworth | 91·56 | 6·69 | 1·21 | ·54 |
| South Brancepeth . . | 93·41 | 5·30 | ·91 | ·36 |

In the following table appears the ascertained results per cent., of coke from the coal of the collieries named :—

| COLLIERIES. | PER CENT. |
|-----------------------------------|-----------|
| North Percy Hartley | 57·18 |
| Newcastle Hartley | 64·61 |
| Derwentwater Hartley | 54·83 |
| Carr's Cowpen Hartley | 58·59 |
| Gray's West Hartley | 59·02 |
| Davidson's West Hartley | 59·49 |
| Haswell | 62·70 |
| Hedley's Hartley | 72·31 |
| Bowden Olose | 69·69 |
| South Hetton | 72·00 |
| Willington | 72·19 |
| Leverson's Wallsend | 65·10 |
| South Peareth | 72·20 |
| Pelaw Main | 69·70 |
| Pelton Main | 69·80 |
| South Tyne | 63·70 |
| Urpeth | 71·30 |
| Washington | 68·75 |
| Old Etherley | 70·00 |

Taking the average of numerous analytical results of the best varieties of Durham coke, 6 per cent. of ash and about ·60 of sulphur may be considered as the proportion of these constituents. Some general idea will be formed of the ash and sulphur existing in samples of the best coke from the annexed figures :—

| ASH PER CENT. | SULPHUR PER CENT. |
|---------------|-------------------|
| 5·86 | 0·58 |
| 5·79 | 0·68 |
| 7·54 | 0·77 |
| 8·33 | 0·90 |

The first coke made in Durham was obtained from the Six-quarter and Blackwell coal-seams at Garesfield, belonging to the Marquis of Bute and Mr. Blackett. About a quarter of a century since the entire make of coke in all parts of the country was estimated at 2,500,000 tons a year; now, in South Durham alone, the production exceeds 4,000,000 tons. Amongst the largest producers are Messrs. Pease and Partners, the Messrs. Bell Brothers, Messrs. Strakers and Love, Messrs. Bolckow and Vaughan, and the Consett Iron Company; the first-named firm raise from their pits nearly one and a half million tons, and the Messrs. Bell Brothers one million tons

of coal annually, the greater part of which is converted into coke. The best coking coal in Durham will yield about 65 per cent. of coke: some varieties exceed this; and the inferior from 53 to 56 per cent. The local ironworks consume a large tonnage, but a great deal is sent into other iron-making districts, as well as to Sheffield, where the hard-burnt (the costliest in making, being of good size and long in shape) is extensively used in putting round the melting pots in the steel furnace.

The coking coal-field of South Durham lies principally to the west of the North-Eastern Railway going from Bradbury Station to Gateshead—the northern limit—an area of more than 250 square miles. During the past few years efforts have been made to save the gases given off in the ovens, but the success so far has not been equal to what could be desired. At several places, however, the waste heat of the coke ovens has been utilized. To have good coke it is necessary that the gases should have a free outlet, and the ovens kept burning in the ordinary way. To secure this object ovens were erected at the Brownley Colliery, and the results attained have been most favourable. The ovens were built in double rows, back to back, but with larger flues than usual between them. To each stack—about 116 feet in height—were connected about 100 ovens, an equal number on each side, there being four flues and boilers, so arranged that the heat was carried past, when cleaning or repairs were being carried on, the connecting flues being built compact and tight, so that there was great freedom from smoke, owing, no doubt, to the air-tight and perfect character of the flues, the small proportion of air present not cooling the gases to a point below, by which the hydrocarbons escaped imperfectly burnt. This was shown to be the case by admitting the air, when flame was at once seen. By this arrangement no coal whatever was used for the boilers, and the produce of the pits was drawn from a depth of 600 yards, and the water pumped; for which purpose, before the new system was adopted, 600 tons per fortnight were wasted. The amount of heat available for evaporative purposes was found to be very large.

Mr. Steavenson, of Durham, in recently noticing the ovens alluded to, gives the result of 50 of them coking at the rate of 230 tons of coal in 84 hours, which yielded 50 per cent. of coke, composed of 132·7 tons of carbon to 5·3 tons of ash, and found

that the composition and weight of the material lost in coking was:—Carbon, 62·6 tons; Hydrogen, 10·3 tons; Nitrogen, 2·3 tons; Sulphur, 1·4 tons, and Oxygen, 15·3 tons.

At several places the coal is crushed into powder before going into the oven, and this has been found beneficial, producing a larger per-centage of coke with less refuse. In some instances the coal is both crushed and washed, the washing being done in troughs. The total number of ovens in operation in Durham will be close upon 14,000, in which are invested considerably above one million sterling. The time necessary for the burning process varies considerably. An oven charged lightly for 24 hours' carbonisation—charging, burning, and drawing inclusive—will occupy in combustion 18 or 19 hours; if charged for a 48 hours' operation, with a heavier load, combustion will occupy from 30 to 32 hours. But these short hours are for a material for a specific purpose. Coke made for shipment or for smelting, and having regard to appearance and quality, will take from 72 to 96 hours in combustion, and even as much as 120 hours; in the latter time the coke is much harder, more compact and silvery-looking. Some of the Durham coal when crushed yields as much as 60 per cent. of coke, and in the ovens, the coke that was burnt the fewer hours for blast furnace purposes, was inferior to that burnt for a longer period, owing to its not being so easily oxidised into carbonic acid. Excepting the ovens and the general arrangements above referred to at Brownley Colliery, the general type of oven in use in Durham is the old bee-hive pattern. At the Consett Ironworks 150 such are in operation, being 11 feet and 11½ feet in diameter. The annual value of Durham coke exceeds two millions sterling, and it requires about 2,000 drawers to aid the operation.

Production of the Coal-field.—There is much obscurity regarding the early returns of production of this coal-field. As early as the year 1602 the vend of coal from Newcastle amounted to 190,000 tons, increasing to 239,261 tons in the year 1609, of which quantity 214,305 tons were sent coastwise, and 24,956 tons exported to foreign countries. Twenty years later the vend of Newcastle reached 289,922 tons, of which 253,380 tons were shipped coastwise, and 36,542 tons exported.

In subsequent years the figures following will show clearly the vends of the northern ports, the output of the collieries of the

Great Northern coal-field, and the total output of the collieries of Great Britain in each of the same years :— *

| Years. | Vend of Northern Ports. | Production of Great Britain. |
|--------|-------------------------|------------------------------|
| | Tons. | Tons. |
| 1660 | 537,000 | 2,148,000 |
| 1700 | 653,000 | 2,612,000 |
| 1750 | 1,193,457 | 4,773,828 |
| 1770 | 1,551,350 | 6,205,400 |
| 1780 | 1,606,244 | 6,424,976 |

The extension of the canal system between the years 1755 and 1800, led to a great expansion of the coal trade, inasmuch as the means of internal communication in the country afforded increased facilities for distribution, and gave an impetus to the use of coal in the general manufactures of the country. Between the years 1800 and 1827 no less than forty-four canals, or improvements of rivers, were projected. These receiving the sanction of the Legislature, were in due course constructed; eventually the result of this new means of communication was seen in the distribution of the coal to remote parts of the kingdom.

Again, the introduction of gas for illuminating purposes, the application of steam in our manufacturing industries and our mercantile and naval marine, the increased demand for iron due to the development of our railway system, all contributing to increased consumption, led to renewed activity and the increased prosperity, apparent in the returns of later years.

In the year 1816 the production of the Durham and Northumberland coal-field amounted to 4,826,683 tons, the output of the collieries of Great Britain the same year being 15,684,729 tons, leaving 10,808,046 tons as the produce of the other coal-fields of the kingdom. In subsequent years the returns show greatly increased production; details, however, are not readily ascertained. In 1855 more reliable returns appear in the "Mineral Statistics" of the United Kingdom. Previously the most uncertain estimates of the coal raised were prevalent; the quantities of coal carried coastwise and exported were annually published in the returns made by order of the House of Commons, but very little informa-

* "Industrial Resources of the Tyne, Wear, and Tees," read before the British Association at Newcastle in 1863.

tion was to be obtained respecting the inland traffic and distribution of coal, excepting such as was brought into the metropolitan district.

For years the Great Northern coal-field has contributed one-fourth of all the coal raised from the collieries in the United Kingdom. In the year 1879 the 363 collieries in operation produced 29,552,079 tons; the total produce of the 3,877 collieries in the United Kingdom in the same year being 134,008,288 tons.

Returning to the year 1855, when official statistics for the first time appear, the Great Northern coal-field produced 15,431,400 tons, the output of 273 collieries, thus distributed :—

| NUMBER OF COLLIERIES. | |
|---|------------|
| Tyne, Blyth and Coquet | 100 |
| Wear and Seaham | 34 |
| Tees, Hartlepool and Stockton | 64 |
| Landseale Collieries | 75 |
| Total | <u>273</u> |

The principal seams worked in the district may be referred to as the High Main, Five-quarter Main, Low Five-quarter, Brockwell, and Stone-coal seams. Of the coal raised in the year 1855, the following schedule shows its distribution :—

| DISTRIBUTION. | TONS. |
|---|-------------------|
| Sent to London by sea | 3,016,868 |
| Sent to London by rail | 221,689 |
| Sent coastwise to other parts | 2,404,471 |
| Railway sale | 2,924,000 |
| Sent to foreign countries | 3,014,372 |
| Used in iron works | 1,200,000 |
| Colliery consumption | 1,150,000 |
| Local consumption | 1,500,000 |
| Total | <u>15,431,400</u> |

Following the development of this great coal-field, successive years show the returns of production as under, to which is added the produce of the collieries of Great Britain in each of same years :—

| Year. | Northern Coal-field. | Great Britain. |
|-------|----------------------|----------------|
| | Tons. | Tons. |
| 1856 | 15,492,969 | 66,645,450 |
| 1857 | 15,826,525 | 65,394,707 |
| 1858 | 15,853,484 | 65,008,649 |
| 1859 | 16,001,125 | 71,979,765 |
| 1860 | 18,244,708 | 80,042,698 |

The meeting of the British Association in Newcastle-upon-Tyne in 1868 gave rise to some interesting and exhaustive notices of the coal, coke, and mining industries of the North of England, including the varied trades and manufactures of the Tyne, Wear, and Tees. From these reports, prepared by Messrs. Nicholas Wood, John Taylor, John Marley, and J. W. Pease, the produce of the Northumberland and Durham coal-field in the year 1861 amounted to 21,777,570 tons. Writing at this period, now nearly twenty years since, these gentlemen conclude their observations on the duration of the coal-field as follows:—"It has been intimated that it would be very desirable that some observations should be made on the duration of the Northern coal-field. No doubt the quantity of coal yet to work in that coal-field is a subject of national importance, but from the observations already made it will have appeared that such a calculation is attended with more than ordinary difficulty. The coal-field may be said to be that of an oval basin, elongated north and south. On the western side of the basin the outcrops of the seams are pretty well defined, but more than one-half of the basin appears to be covered by the sea." At Monkwearmouth Colliery, near Sunderland, the coal is being wrought under the sea, and at Marsden, South Shields, the Whitburn Coal Company are sinking a pit, under the direction of Mr. Daglish, the eminent mining engineer, to win the coal entirely under the ocean. On examining the section from Radcliffe Colliery, at the northern extremity, the Castle Eden Colliery, near the southern extremity, the beds of coal lie at a very considerable depth below the water level of the sea, and that line of section passes through the deepest explored part of the coal-field. The lowest known point of deepest depression being the Hutton seam of coal (below which there are several workable beds of coal), which is at Monkwearmouth Colliery, 300 fathoms below the level of the sea.

Before passing on to the yield of the coal-field in later years, it will be interesting to see the several heads under which the production of the year 1861, previously referred to, was distributed, amounting to 21,777,570 tons, showing an increase over the output of the year 1860 of 3,582,862 tons, equivalent to nearly 20 per cent. The production of the collieries of Great Britain in the same year being 84,042,698 tons, of which quantity it is said nearly 4,000,000 were wasted on fire heaps.

| DISTRIBUTION. | TONS. |
|--|-------------------|
| House coal | 4,493,450 |
| Gas coal | 1,717,000 |
| Steam coal, small and manufacturing coal | 4,317,120 |
| Distributed by the North Eastern Railway | 2,180,000 |
| Distributed by Carlisle Railway | 120,000 |
| Coke consumed in iron trade | 5,000,000 |
| Alkali and other manufactures | 1,250,000 |
| Colliery and home consumption | 2,200,000 |
| Duff and waste | 500,000 |
| Total | <u>21,777,670</u> |

As previously stated, the total output of the collieries of the Great Northern coal-field yield fully 25 per cent. of the total produce of the United Kingdom, and this proportion continues to be maintained, as appears in the returns of subsequent years, in which the total yield of the United Kingdom appears side by side with the returns of Durham and Northumberland :—

| Year. | Durham and Northumberland. | United Kingdom. |
|-------|-------------------------------|-----------------|
| | Tons. | Tons. |
| 1862 | 19,360,356 | 81,638,338 |
| 1863 | 22,154,146 | 86,292,215 |
| 1864 | 23,284,367 | 92,787,873 |
| 1865 | 25,032,694 | 98,150,587 |
| 1866 | 25,194,550 | 101,630,544 |
| 1867 | 24,867,444 | 104,500,480 |
| 1868 | 24,394,167 | 103,141,157 |
| 1869 | 25,765,430 | 107,427,557 |
| 1870 | 27,613,539 | 110,431,192 |
| 1871 | 29,190,916 | 117,352,028 |
| 1872 | 30,405,000* | 123,497,316 |
| 1873 | 29,640,385 | 127,016,747 |
| 1874 | 30,543,800 | 125,007,916 |
| 1875 | 32,097,323 | 131,867,105 |
| 1876 | 31,991,023 | 133,344,766 |
| 1877 | 31,210,400 | 134,610,763 |
| 1878 | 30,133,884 | 132,607,866 |
| 1879 | 29,552,079 | 134,008,228 |
| 1880† | 34,913,508 | 146,969,409 |

The coal raised in the Durham and Northumberland coal-field

* Including the output of the collieries of the Cumberland coal-field.

† Return H.M. Inspectors of Mines, 1880.

was distributed and used in the following manner in each of the years 1878, 1879 and 1880 :—

| Distribution and Use. | 1878. | 1879. | 1880. |
|---|------------|------------|------------|
| | Tons. | Tons. | Tons. |
| Coal exported | 5,838,529 | 6,702,785 | 7,066,299 |
| *Coke do. | 322,800 | 407,064 | 394,550 |
| Coal sent coastwise | 5,824,578 | 6,266,739 | 6,341,976 |
| *Coke do. | 8,450 | 8,990 | 11,711 |
| Coal by rail for local consumption and land sale | 4,997,264 | 4,847,681 | 5,935,937 |
| Coal for railway use | 576,297 | 552,254 | 610,364 |
| Coal by rail to other districts | 435,810 | 428,544 | 398,257 |
| *Coke by rail for local consumption and land sale | 3,328,956 | 3,282,310 | 4,277,200 |
| Coke by rail south of Al- tofts to Carlisle | 2,073,050 | 2,076,757 | 3,955,100 |
| *Coke for railway use | 12,650 | 13,295 | 10,788 |
| Coal used at iron works, mills and forges, &c. | 2,450,500 | 2,250,000 | 2,770,000† |
| Colliery consumption | 1,515,000 | 1,215,000 | 1,250,000† |
| Local manufactures, domes- tic use, &c. | 2,750,000 | 1,500,660 | 1,891,326† |
| Total | 30,133,884 | 29,552,079 | 34,913,508 |

Distribution of Coal.—All the early accounts bearing on this subject show that for a long period,—extending to a remote date,—coal was distributed through the country by means of pack-horses, mules, and asses; the coals were placed in bags and laid on the backs of these animals, and within the recollection of the present generation vast numbers of these animals were thus employed along roads and in districts impassable to carts. When roads were improved and carts could be used, the usual load for a horse was one ton conveyed ten miles a-day. About the year 1632 wooden railways were introduced and the load increased to two tons in one waggon, or four tons in two waggons on a favourable gradient. In the early period of coal mining, the pits were generally sunk on or near the outcrop of the coal-seam, or in the elevated parts of the districts; at this period two waggons were employed, an extra horse being used in the more hilly parts of the road to drag up the empty waggons. The coals thus transported were

* Equivalent in coal given.

† Estimated quantities.

conveyed from the pits to the river Tyne, from whence they were conveyed in "Keels," or boats carrying twenty chaldrons, to the ships.

About the year 1794 cast-iron rails were introduced and used at the collieries in Durham and Northumberland; these about the year 1815 were succeeded by malleable-iron rails, first in the shape of tram roads and ultimately of round-topped rails. Before the introduction of steam, horses were the motive power employed, the usual load for a horse drawing a waggon on the cast-iron roads being from ten to twelve tons, on a level or slightly inclined road, and the distance traversed daily from twenty to twenty-four miles, the waggons being loaded one-half the distance and empty the other half.

The introduction of locomotive engines on tramroads occurred in the year 1811 on the Wylam Railway, and in the following year Stephenson's improved locomotive on round-topped rails was introduced. At this period the assigned performance of a locomotive was six miles per hour, conveying a load of forty tons; a few years later the performance of a locomotive on the Liverpool Railway was thirty-three tons, conveyed at the rate of five miles per hour, by Messrs. Walker and Rastrick, and by Messrs. Stephenson and Locke, forty-five tons, conveyed at the rate of twelve miles per hour.

The first public railway, the Stockton and Darlington, was opened in the year 1825 for the conveyance of coal, minerals, and passengers; the motive power first employed was horses and subsequently locomotive engines. The first engine which ran on this railway is still to be seen in front of the station at Darlington. Since that period malleable iron rails have been universally used, and in recent years steel has been extensively introduced, and heavier rails have been laid. On the Manchester and Liverpool Railway the weight of the original rails laid was 95 lbs. per yard, forty years later the rails employed were 84 lbs. to the yard.

With the introduction of steam and railways a new era sprung up, giving a marked impetus to the development of the coal, iron, and other industries of the Empire. This is well illustrated by the rapid extension of the mineral traffic in the southern parts of the county of Durham, and by the Stockton and Darlington Railway which, as previously stated, was opened in the year 1825. Twenty years later, in 1845, and the year before the Witton Park

Ironworks were opened, the total quantity of minerals carried, including coal, coke, ironstone, and limestone, amounted to 986,757 tons, increased in the following year to 948,111 tons; five years later, with the opening of the Eston Ironstone Mines in the Cleveland district, of the North Riding of Yorkshire, the mineral traffic increased one hundred-fold, giving an aggregate of: 1,859,207 tons, and in 1856 to 2,952,202 tons, accounted for in the following items, in each of the years named:—

| Distribution. | 1851. | 1856. |
|---|-----------|-----------|
| | Tons. | Tons |
| Coals and coke exported . . . | 441,352 | 219,591 |
| Coals and coke, Landsale, Household and Iron Works. . . | 1,017,644 | 1,557,624 |
| Lime and limestone . . . | 279,607 | 875,199 |
| Ironstone | 120,604 | 299,788 |
| Total | 1,859,207 | 2,952,202 |

The West Hartlepool and Clarence Railways, in like manner showed a rapid development of traffic in coal and coke in each of the years:—

| Years. | | Tons. | Tons. |
|--------|-----------------|---------|-----------|
| 1848 | Land sale . . . | 124,167 | 535,297 |
| | Export . . . | 411,130 | |
| 1858 | Land sale . . . | 434,437 | 1,175,764 |
| | Export . . . | 741,327 | |
| 1862 | Land sale . . . | 591,610 | 1,551,773 |
| | Export . . . | 960,163 | |

Previous to the introduction of railways and canals our knowledge of the detailed distribution of coal and coke is often imperfect. On the whole the following may be regarded as generally reliable, showing the quantities sent coastwise and exported; thus in the year 1602 the total quantity thus distributed did not exceed 190,600 tons; some years later the following details exhibit the extent to which the coal and coke of this coal-field were disposed of:—

| Year. | Coastwise. | Foreign. | Total. |
|-------|------------|----------|---------|
| | Tons. | Tons. | Tons. |
| 1609 | 224,435 | 27,339 | 251,774 |
| 1621 | 301,785 | 43,755 | 345,540 |
| 1630 | 253,380 | 36,542 | 289,922 |

For the next century and more, the details of distribution are somewhat meagre. In the year 1660 the coal and coke distributed amounted to 537,000 tons; forty years later the quantity did not exceed 653,000 tons, receding in 1710 to 650,000 tons. Not again until the year 1750 do returns appear, when 1,193,457 tons were carried coastwise and foreign; in subsequent years accurate data are met with showing the distribution of the fossil fuel of the Great Northern coal-field.

| Year. | Coastwise. | Foreign. | Total. |
|-------|------------|-----------|------------|
| | Tons. | Tons. | Tons. |
| 1791 | 1,814,661 | 264,944 | 2,079,605 |
| 1795 | 2,251,547 | 418,885 | 2,670,432 |
| 1800 | 2,381,986 | 138,089 | 2,520,075 |
| 1805 | 2,426,616 | 147,146 | 2,573,762 |
| 1810 | 2,783,404 | 50,922 | 2,834,326 |
| 1815 | 2,717,509 | 169,174 | 2,876,683 |
| 1820 | 3,246,885 | 158,340 | 3,403,225 |
| 1825 | 3,309,386 | 178,544 | 3,487,930 |
| 1835 | 3,973,659 | 494,485 | 4,468,144 |
| 1840 | 4,517,103 | 1,328,445 | 5,845,548 |
| 1845 | 5,523,178 | 1,784,988 | 7,308,166 |
| 1850 | 6,295,570 | 2,176,115 | 8,471,685 |
| 1855 | 5,410,565 | 2,822,856 | 8,233,421 |
| 1860 | 6,360,051 | 4,000,712 | 10,360,763 |
| 1865 | 6,041,003 | 4,637,759 | 10,678,762 |
| 1870 | 5,414,266 | 6,635,241 | 12,049,607 |
| 1875 | 5,638,074 | 6,519,671 | 12,157,745 |
| 1876 | 5,785,720 | 6,930,305 | 12,716,025 |
| 1877 | 5,890,881 | 6,226,720 | 12,117,601 |
| 1878 | 5,830,501 | 6,071,006 | 11,901,507 |
| 1879 | 6,329,366 | 6,514,012 | 12,843,378 |
| 1880 | 6,349,003 | 7,403,029 | 13,752,032 |

Reference has been already made to the Stockton and Darlington Railway, opened in the year 1825, and to the West Hartlepool and Clarence Railway. These lines, and others, have long since been absorbed into the great system known as the North Eastern Railway, which possessed at the end of 1879 a total length in main line and branches of 1,473 miles.

Since the year 1800, the figures in the above statement show that the movements of coal coastwise and to foreign countries has increased fivefold; in the year 1879 the coal was shipped from the following ports in the quantities given :—*

| Ports of Shipment. | Coastwise. | Exported. | Total. |
|------------------------|------------|-----------|------------|
| | Tons. | Tons. | Tons. |
| Newcastle | 2,650,773 | 3,952,308 | 6,603,081 |
| North Shields | 135,345 | 500,180 | 635,525 |
| South Shields | 239,287 | 361,540 | 600,827 |
| Sunderland | 2,657,505 | 1,098,672 | 3,756,177 |
| Stockton | 1,186 | — | 1,186 |
| Hartlepool | 602,216 | 542,302 | 1,144,518 |
| Middlesborough | 43,054 | 59,010 | 102,064 |
| Totals | 6,329,366 | 6,514,012 | 12,843,378 |

From returns furnished by the North-Eastern Railway the following abstract has been prepared, showing at a glance the magnitude of the traffic, not only in coal and coke, but also of the ironstone carried :—

| Year. | Coal. | Ironstone. |
|-------|------------|------------|
| | Tons. | Tons. |
| 1854 | 2,571,064 | — |
| 1856 | 1,753,045 | 245,998 |
| 1858 | 2,402,011 | 259,617 |
| 1860 | 2,575,303 | 260,388 |
| 1862 | 3,826,590 | 408,979 |
| 1864 | 5,744,501 | 1,700,879 |
| 1866 | 7,350,956 | — |
| 1868 | 7,357,266 | 2,591,711 |
| 1870 | 8,999,784 | 2,816,797 |
| 1871 | 10,089,217 | 4,467,889 |
| 1872 | 10,486,168 | 4,652,052 |
| 1873 | 10,792,280 | 4,928,458 |
| 1874 | 10,689,846 | 4,904,279 |
| 1875 | 11,032,299 | 5,305,113 |
| 1876 | 10,535,438 | 5,426,576 |
| 1877 | 10,439,768 | 5,547,822 |
| 1878 | 9,907,829 | 4,999,448 |
| 1879 | 9,320,511 | 4,190,050 |
| 1880 | 11,661,676 | 5,785,724 |

The coal and coke thus carried by the North Eastern Railway

* Parliamentary Returns, No. 215, Session 2, 1880.

is exclusively the produce of the Durham and Northumberland coal-field. This is distributed for local consumption, land sale, and also employed by the railway company for their own use, in and over the main line and branches, and in those districts traversed by the railway system between Berwick and Kelso in the north, Carlisle and Tebay in the west, and Leeds, Knottingley, Doncaster, and Altofts, in the south.

Other railways contribute in a lesser degree to the distribution of the coal: thus the Great Northern Railway carried the following quantities in each of the years named; side by side are the quantities carried in each of the same years by the Furness Railways of Durham coke, from the Stockton, Darlington, and other districts from the North Eastern Railway;—considerable tonnage being also conveyed by the Midland, and Manchester, Sheffield, and Lincolnshire Railways.

| Year. | Great Northern Railway. | Furness Railway. |
|-------|-------------------------|------------------|
| | Tons. | Tons. |
| 1869 | 509,164 | 330,374 |
| 1870 | 524,695 | 371,559 |
| 1871 | 511,165 | 388,096 |
| 1872 | 409,414 | 426,057 |
| 1873 | 365,143 | 489,305 |
| 1874 | 341,501 | 532,435 |
| 1875 | 404,313 | 474,336 |
| 1876 | 388,089 | 474,653 |
| 1877 | 334,615 | 579,569 |
| 1878 | 289,586 | 551,878 |
| 1879 | 272,896 | 555,180 |
| 1880 | 210,083 | 676,207 |

Prices of Coal and Cost of Production.—In the year 1850 the coal wrought from pits varying in depth from 750 to 1,000 feet cost on an average from 4*s.* 9*d.* to 5*s.* per ton delivered at pit's mouth; the average cost per ton at the several ports of shipment varying according to distance by rail from 5*s.* 3*d.* to 9*s.* 9*d.*, or an average all round of household coals of 7*s.* 3½*d.* per ton; of steam coals, 6*s.* 8*d.* per ton, the highest price being 7*s.* 3*d.*, the lowest 5*s.* 9*d.*; gas coals ranging from 5*s.* 6*d.* to 7*s.* per ton, the average being 6*s.* 1¼*d.* per ton;—the best coking coals varying from 5*s.* 9*d.* to 6*s.* 9*d.* and 7*s.* per ton, or an average through and through of 6*s.* 3¼*d.* per ton; and blacksmith's coal, 6*s.* 1¼*d.* per ton.

In 1860 the coal in the Newcastle district in the Tanfield collieries cost from 3*s.* to 3*s.* 6*d.* per ton at pit's mouth, the charges for conveyance to ports of shipment a distance of 24 miles adding 2*s.* per ton to the cost. The best coals of the Hetton district, greatly screened, all charges of labour, rent, &c., and including railway charges, 1½*d.* per ton per mile, delivered on board ship, costing from 16*s.* to 18*s.* per chaldron of 53 cwts. The average price of the several varieties of Newcastle coal, delivered free on board, in 1860, being: house coals, 9*s.* per ton; steam coals, 8*s.* per ton; and gas, coking, and manufacturing coals, 5*s.* 6*d.* per ton. The fluctuations to which the Newcastle Wallsend coals have been subject since the year 1861, is well shown in the following statement of all sales in the London coal-market in each year, showing the highest, lowest, and average price per ton:—

| Year. | Average. | | Highest. | | Lowest. | |
|-------|-----------|-----------|-----------|-----------|-----------|-----------|
| | <i>s.</i> | <i>d.</i> | <i>s.</i> | <i>d.</i> | <i>s.</i> | <i>d.</i> |
| 1861 | 18 | 4 | 25 | 9 | 16 | 6 |
| 1862 | 15 | 7 | 19 | 0 | 13 | 6 |
| 1863 | 15 | 10 | 18 | 9 | 12 | 9 |
| 1864 | 17 | 10 | 22 | 0 | 14 | 9 |
| 1865 | 18 | 0 | 22 | 9 | 15 | 3 |
| 1866 | 17 | 9 | 20 | 6 | 15 | 3 |
| 1867 | 18 | 3 | 25 | 0 | 16 | 3 |
| 1868 | 15 | 9 | 18 | 3 | 14 | 0 |
| 1869 | 15 | 9 | 21 | 9 | 13 | 3 |
| 1870 | 16 | 3 | 20 | 6 | 13 | 9 |
| 1871 | 17 | 1 | 23 | 0 | 15 | 0 |
| 1872 | 23 | 0 | 29 | 0 | 18 | 0 |
| 1873 | 30 | 9 | 42 | 3 | 26 | 0 |
| 1874 | 23 | 2 | 26 | 6 | 20 | 3 |
| 1875 | 20 | 9 | 22 | 3 | 19 | 3 |
| 1876 | 19 | 6 | 23 | 0 | 15 | 6 |
| 1877 | 17 | 8 | 22 | 9 | 15 | 3 |
| 1878 | 16 | 6 | 21 | 9 | 15 | 0 |
| 1879 | 16 | 6 | 23 | 6 | 13 | 9 |
| 1880 | 14 | 11 | 18 | 5 | 13 | 6 |

The average cost is further increased by the various charges incidental to the conveyance of the coal,—from the ship to the shore, and thence to the cellar of the consumer,—adding between 5*s.* and 6*s.* per ton to the above prices. Bearing on the subject of labour, miners' wages, and arbitration in the Durham coal trade, an able article in the "Colliery Guardian" puts the subject

very clearly. The writer says: "Although the Durham coal trade has not been exempt from strikes, to which the decrease in price is generally attributed, the adjustment of the rate of miners' wages has on the whole been well managed. During the last ten years arbitration has been resorted to from time to time when differences arose as to the remuneration of labour; and with the ability and sound judgment which Mr. David Dale applied to those questions on the side of the employers, and the reason and moderation which Mr. Crawford's salutary counsels generally made to prevail among the miners, one of the most prosperous, as well as one of the most distressing periods in the trade has been tided over without any of those violent dislocations or prolonged interruptions which in former years inflicted serious injuries on all parties, and sometimes threatened to ruin local industry. In Durham the ten years under review comprise the period when this experiment has been put to the severest test, and the history of the fluctuations that have taken place in miners' wages during that period forms one of the most remarkable chapters in the records of the coal-trade,"—and is thus referred to:—

"The first years of course showed an upward movement. When the great rise in prices began in 1872, there was a general consensus of opinion that the rates current in 1871 were fair and reasonable. At all events, whether by accident or by merit, they have formed the basis of nearly all the subsequent movements. Previous to that year prices had shown little or no variation, and the collieries then worked $12\frac{1}{2}$ hours a day; but the Coal Mines Regulation Act that came into operation on January 1, 1873, reduced the hours to eleven. In the beginning of 1872 the prices of coal rose so rapidly that in March the miners obtained an advance of 20 per cent. in wages over the rate current in 1871. Prices still rising, another advance of 18 per cent. was granted in July of the same year; and in February of 1873 a third advance of 15 per cent. took place, so that within twelve months the wages were 58 per cent. more than in 1871. That maximum rate continued for fourteen months, namely, till April, 1874, when a reduction of 10 per cent. took place. The next reduction followed in October of the same year, and it was fixed by arbitration at 9 per cent. Successive reductions of 5, 7, and 6 per cent. respectively were made in April, 1875, February and September,

1876. A sliding scale was then adopted, with the view of regulating wages, according to the certified prices of coal as ascertained at fixed periods. The date of the sliding scale agreement was March, 1877; and it was found that the prices of the previous four months entailed a reduction of $7\frac{1}{2}$ per cent. When the last-named reduction took place, wages were about equal to what they had been in 1870 before the advances began. By the sliding scale agreement the wages now reached the minimum provided for; and as it had been pre-arranged that it should continue binding for two years, the wages continued at that rate, while prices continued to fall. In many cases local arrangements were made between masters and men to work for less wages, rather than cease working altogether; but there was no general reduction during these two years. In the spring of last year, however, steps were taken to effect a general reduction as soon as the sliding scale arrangement expired. After a good deal of negotiation, the masters reduced their first demand of 20 per cent. to 15 per cent., and many of the colliers agreed to this; but others strongly objected, and this led to a general strike throughout the country, lasting from April 14 to May 20—five weeks. The matter was settled by arbitration, which resulted in a reduction of $8\frac{3}{4}$ per cent. The coal owners claimed a further reduction in August last year; and by arbitration they were awarded $1\frac{1}{4}$ per cent., so that wages were thereafter 10 per cent. less than they were in 1871.”

“Another sliding scale has since been adopted, and it differs from the previous one in this respect, that the ratio of variation is fixed, but is interminable. According to the employers’ information the miners were paid 4*s.* 8*d.* a day in 1870 for an average output of 4·67 tons of coal, and 4*s.* 8½*d.* in 1878 for an average output of 4·02 tons, being a decrease of 16 per cent. in the quantity of work done for the same wages.”*

Population Employed in Coal-mines.—The number of persons employed in coal-mining in these two northern counties in the year 1852 was respectively 29,600 men and boys under ground, and 7,900 above ground, giving a total of 37,500 persons. In the year 1854 the number increased to 38,801, of whom 28,265 were employed in Durham, and 10,536 in Northumberland. The

* “Colliery Guardian,” vol. xl. “Ten Years’ Coal Mining,” Northumberland and Durham, pp. 331–2.

total number of persons employed at this period in the collieries of Great Britain being as follows :—

| | No. of Persons. |
|--------------------|-----------------|
| England | 147,070 |
| Wales | 37,314 |
| Scotland | 32,969 |
| Total | <u>217,353</u> |

exclusive of females, who numbered 2,642; of these 38 were employed in Durham, and 8 in Northumberland. According to the Census returns for 1861 the number of male coal miners engaged in this great coal-field and Cumberland was 53,534, increased in the year 1864 to 57,538. The returns in subsequent years give the following as the number of persons employed, with the output of coal, from which is deduced the average output per man in each year :— *

| Year. | Persons Employed. | Total Coal raised. | Average per man. |
|-------|-------------------|--------------------|------------------|
| | Nos. | Tons. | Tons. |
| 1864 | 57,538 | 23,991,544 | 417 |
| 1865 | 58,978 | 24,591,333 | 417 |
| 1866 | 61,367 | 25,693,800 | 418 |
| 1867 | 63,321 | 26,447,500 | 417 |
| 1868 | 69,000 | 26,700,000 | 372 |
| 1869 | 69,800 | 27,296,000 | 391 |
| 1870 | 75,100 | 29,300,000 | 390 |
| 1871 | 79,000 | 30,476,000 | 380 |
| 1872 | 84,300 | 30,405,000 | 360 |

Comparing the results of the year 1864 with those of 1872, when the number of persons engaged was computed by the inspector, each in his own district, we have a falling off, comparing the average output per man, of 57 tons in a period of eight years. When the Coal Mines Regulation Act, 1872, came into operation, the numbers employed were ascertained with more exactness than formerly, and appear in the following table, giving the output of coal and the average per man, showing a steady increase, amounting to 25 tons per man, in a period of six years :—

* According to H.M. Inspectors of Collieries Reports.

| Year. | PERSONS EMPLOYED. | | Total | Coal raised. | Average per Man. |
|-------|-------------------|---------------|---------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 79,358 | 21,184* | 100,542 | 29,742,617 | 296 |
| 1874 | 80,169 | 18,965 | 99,134 | 30,567,244 | 308 |
| 1875 | 81,913 | 20,225 | 102,138 | 32,324,145 | 316 |
| 1876 | 80,587 | 20,508 | 101,095 | 32,254,094 | 319 |
| 1877 | 79,066 | 19,562 | 98,628 | 31,415,225 | 318 |
| 1878 | 74,827 | 17,678 | 92,505 | 30,132,583 | 325 |
| 1879 | 72,138 | 17,471 | 89,609 | 28,788,974 | 321 |
| 1880 | 76,439 | 18,361 | 94,800 | 34,913,508 | 368 |

Taking the year 1879, when the total number of persons employed was 89,609, the reports of Her Majesty's Inspector give the following classification of the ages of those engaged in and about the mines :—

| All Ages. | Under Ground. | Above Ground. | Total. |
|-----------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| From 12 to 13 . | 1,004 | — | 1,004 |
| „ 10 to 13 . | — | 289 | 289 |
| „ 13 to 16 . | 6,495 | 1,783 | 8,278 |
| Above 16 . . | 64,639 | 15,399† | 80,038 |
| Total . | 72,138 | 17,471 | 89,609 |

Resources and Probable Duration of the Durham and Northumberland Coal-field.—Adopting 4,000 feet as the limit of practical depth in coal working, and making due allowance for loss of coal destroyed by faults, barriers, and waste in working, the Commissioners engaged on the Royal Coal Commission (Mr. Thomas E. Forster for the Northumberland coal-field, and Sir George Elliot, Bart., for the Durham coal-field) give the following estimates as to the available coal remaining to be wrought in this Great Northern coal-field.†

GENERAL SUMMARY.

| | |
|--|----------------|
| | Tons. |
| Northumberland Coal Field | 3,148,096,839 |
| Northumberland Mountain Limestone District | 665,180,007 |
| Durham | 6,223,363,390 |
| Total | 10,036,640,236 |

* The total for 1873 includes those persons employed in the Cumberland coal-field.
† Including 8 females above 16 years of age.

‡ Coal Commission Report, vol. i. p. 20—26.

The estimated quantity in the Northumberland division of the coal-field includes the under-sea coal amounting to 403,200,000 tons. This quantity is estimated on the following basis. "It is supposed that from the river Tyne northward to Creswell, a distance of 20 miles, four workable seams of coal will be found, making in the aggregate 14 feet of coal over an area of 40 square miles; taking the extent to be worked seaward at two miles equal to 25,600 acres \times 14 feet thick \times 1,500 tons per foot per acre, and allowing 25 per cent. to be left, the above-named quantity will be available, namely, 403,200,000 tons."

In the Durham division of the coal-field amounting to 6,223,363,390 tons, it is estimated that the total amount of undersea coal available is 2,234,509,005 tons, and in all these estimates the coal seams down to a thickness of 12 inches have been taken into account.

Taking the production of the year 1870 (27,613,539 tons) as a basis of computation, 364 years would bring about the exhaustion of this coal-field. Since the year 1870 the total output of the collieries has greatly increased, amounting in the aggregate to 302,378,849 tons; there would therefore remain in the year 1880 available coal amounting to 9,734,261,387 tons. This quantity at the average production of the ten years ending 1879 (30,237,884 tons) would afford supplies for 322 years to come; while at the rate of production in the year 1880, amounting to 34,913,508 tons, the period would be reduced to 280 years.

CHAPTER II.

THE YORKSHIRE COAL-FIELD.

Description of Coal-field—Sheffield, Leeds, and Barnaley, &c., districts—Principal Coal Seams—Analyses of Coals—Barrow Silkstone Colliery near Barnaley—Production of Coal and Distribution by Railway—Price of Coal and cost of Production—Population employed in Coal and Ironstone Mining since 1873—Resources and probable Duration of Coal-field (including Yorkshire, Derbyshire and Nottinghamshire).

The Yorkshire Coal-field.—This great coal-field occupies a considerable area of the West Riding and southern parts of Yorkshire, and with its extension into the shires of Derby and Nottingham, has a known area of about 800 square miles, its length from north to south being upwards of 66 miles, extending from Bradford and Leeds on the northern boundary, through Sheffield to Derby and Nottingham on the south, its breadth varying from 5 to 20 miles. It is the most continuous of the coal-fields of Great Britain and is almost entirely exposed throughout its area, its eastern margin only being covered by the magnesian limestone or Permian rocks. Sheffield occupies the centre of the coal-field, and in a section of 4,500 feet of coal measures 15 seams of coal occur, each seam having a thickness exceeding two feet, and giving a total thickness of 46 feet of vertical coal, while of the numerous seams less than two feet thick, there exists a vertical section equal to 53 feet of coal. In this Chapter only that part of the coal-field is described which is contained within the county of York.

The rocks of the carboniferous system are usually divided in the centre and north of England into the following groups:—

| | | |
|----------------------------|-------|--|
| <i>Upper Carboniferous</i> | . . . | { Upper coal measures. Middle coal measures. Lower coal measures. Millstone grit. |
| <i>Lower Carboniferous</i> | . . . | { Yoredale rocks. Carboniferous limestone. |

The lowest of these subdivisions, the *Carboniferous limestone*, consists over the greater part of its exposure in Yorkshire, as in

Derbyshire, of very little else but limestone. Partings of clay or shale between the limestone beds occur; their thickness however is inconsiderable when compared with the whole subdivision. The limestones are for the most part thickly bedded, and comparatively free from earthy or sandy admixture. Towards the top of the carboniferous limestone, the limestone beds become thinner and more earthy, and the shale partings grow more numerous, and a passage takes place into the next subdivision, the *Yoredale Rocks*. This group consists largely of dark shale, and beds of limestone and sandstone. These latter are usually thinly bedded, and more or less earthy, frequently passing into calcareous shales.

The Millstone Grit consists of sandstones thick and coarse, the individual beds showing much irregularity, although there are groups of sandstone which maintain considerable persistency over large areas. The coals here found are few in number, for the most part thin and of poor quality, and with one or two exceptions singularly local.

The Lower Coal Measures next occurring contain a few seams of coal of no great thickness and of poor quality, but an improvement upon those seams met with in the Millstone Grit. The sandstones of the lower coal measures, though important rocks, are, as a rule, neither so coarse nor so thick as the massive gritstones of the group below. It is in the lower coal measures that the hard seat-stone, known as "Ganister," occurs most abundantly, although it is not altogether absent from the Millstone grit, and the middle coal measures. "Ganister" is described as a highly silicious rock, which, when ground down and mixed in some cases with powdered fire-brick, or similar materials, forms one of the best fire-resisting materials known. Ganister is found almost exclusively in the lower coal measures, and generally forms the seat of a bed of coal. Professor Green referring to this rock, says, "There is one bed known as the 'Halifax Hard' or Ganister Coal, beneath which Ganister is almost always present; and the seat stone of this seam is not only more constant in its occurrence, but is usually regarded as of better quality than the Ganister of other horizons."

The Middle Coal Measures are alike remarkable for the number and thickness of the coal seams, and the excellent quality of their coals. The sandstones of this division are finely

grained, and not so thick as the sandstones of the two groups below; they are also much less persistent, and can seldom be traced continuously for more than a few miles.

The Upper Coal Measures consist mainly of sandstones and shales of a deep red colour. They also contain thin limestones, and although coal seams are not absent they are neither so numerous nor so valuable as those of the middle coal measures.

With this brief sketch of the Carboniferous rocks, drawn from "The Geology of the Yorkshire Coal-field"* extending from Sheffield in the south, to Leeds in the north, the next point to consider will be the order of occurrence of the principal coal seams in some of the more important localities within the area.

Analyses of Ganisters and Underclays.—These, as the name implies, usually form the seat of a seam of coal, but underclays do occur without any coal seam over them. There is usually, however, if coal be absent, a seam of highly carbonaceous black shale above an underclay. Analyses of these Ganisters and underclays by Mr. J. W. Westmoreland, formerly of the Bowling Iron Works, give the following results:—

SHIPLEY FIRECLAY BENEATH HALIFAX HARD BED.

| | |
|----------------------------|-------|
| Silica | 57·45 |
| Alumina | 35·28 |
| Peroxide of iron | 4·53 |
| Titanic acid | 1·21 |
| Lime | trace |
| Magnesia | 1·00 |
| Potash | ·58 |
| Moisture | ·10 |

GIELDIN'S GANISTER, FROM PLAINTREES ROAD, NEAR
LAISTERDYKE STATION.

| | |
|---|-------|
| Silica | 96·55 |
| Alumina | 1·59 |
| Peroxide of iron with some titanic acid | ·71 |
| Lime | ·18 |
| Magnesia | ·17 |
| Water | ·85 |
| Potash | ·53 |

This Ganister is of very good quality and is used for making "holes" for crucible steel, and forms the seat of the Better Bed Coal.

* By Professor A. H. Green, R. Russell and others. ("Geological Survey Memoir," p. 20.)

Another seat stone, raised at the Bowling Colliery, also the seat of the Better Bed coal, gives on analysis the annexed results:—

| | |
|--|-------|
| Silica | 81.25 |
| Alumina | 8.16 |
| Peroxide of iron with titanic acid | 4.01 |
| Lime | .57 |
| Magnesia | .46 |
| Potash | 1.90 |
| Water | 3.90 |

BETTER BED FIRE-CLAY. BOWLING FIRE-BRICK.

| | |
|----------------------------|-------|
| Silica | 68.12 |
| Alumina | 26.69 |
| Peroxide of iron | 2.00 |
| Titanic acid | .87 |
| Lime | 1.15 |
| Magnesia | .59 |
| Potash | 1.17 |
| Water | .20 |

In the northern part of the Yorkshire coal-field, a comparative section of the lower coal measures discloses the following seams of coal and intervening strata in the neighbourhood of Leeds, in a line from Royds House, by North Moor House, to Heaton Hall, in a section of 570 feet from the Blocking coal to the Better Bed coal.*

| Strata. | Thickness. | | Total Depth. | |
|--------------------------------------|------------|-----|--------------|-----|
| | Ft. | In. | Ft. | In. |
| Blocking Bed Coal | 2 | 0 | | |
| Measures | 117 | 0 | | |
| Upper Lousey Coal | 2 | 6 | 121 | 6 |
| Measures | 67 | 6 | | |
| Lower Lousey Coal | 0 | 10 | 189 | 0 |
| Measures | 10 | 2 | | |
| Sandstone (Oakenshaw Rock) | 120 | 0 | 320 | 0 |
| Measures | 120 | 0 | | |
| Black Bed Coal | 2 | 3 | 442 | 3 |
| Measures | 126 | 0 | | |
| Better Bed Coal | 1 | 6 | 569 | 9 |

The Black Bed coal is soft, friable and dull in appearance; it burns to a red ash, of which it contains about 1.5 per cent. The

* "Geology of Yorkshire," p. 202.

seam furnishes a second-class house-coal, and is largely employed locally as an engine coal. As a soft coal for producing gas it yields from 4,000 to 5,000 cubic feet to the ton, and a large proportion of gas tar.

South of Leeds the Middle Coal measures are illustrated in a section at Emley Moor, between the Blocking coal,* and the Joan coal, of 541 feet; distinguishing the thickness of the seams and the intervening measures, as follows:—†

| Strata. | Thickness. | | Total. | |
|----------------------------------|------------|-----|--------|-----|
| | Ft. | In. | Ft. | In. |
| Measures | | | | |
| Joan Coal | 2 | 0 | | |
| Measures | 64 | 6 | | |
| Flockton Thick Coal | 3 | 6 | 70 | 0 |
| Measures | 15 | 5 | | |
| Emley Rock | 26 | 7 | 112 | 0 |
| Measures | 11 | 0 | | |
| Flockton Thin Coal | 1 | 3 | 124 | 3 |
| Birstal Rock | 83 | 8 | 207 | 11 |
| Coal First Brown Metal | 24 | 7 | 232 | 6 |
| Measures | | | | |
| Old Hards Coal | 2 | 0 | 234 | 6 |
| Measures | 25 | 9 | | |
| Coal Third Brown Metal | 0 | 8 | 260 | 11 |
| Measures | 42 | 5 | 303 | 4 |
| Green Lane Coal | 1 | 2 | 304 | 6 |
| Measures | 71 | 10 | | |
| New Hards Coal | 2 | 3 | 378 | 7 |
| Measures | 47 | 5 | | |
| Three-quarter Coal | 2 | 7 | 423 | 7 |
| Measures | 83 | 6 | 512 | 1 |
| Falhouse Rock | 33 | 9 | | |
| Blocking Coal | 1 | 5 | 541 | 6 |

The Flockton Thick Coal given above as 3 feet 6 inches thick, has a seam of clay 6 inches thick passing through it.

The other important coals occurring before the Warren House seam‡ is reached are the following: the Haigh Moor, Swallow Wood, or Netherton Thin Coal; the Top Haigh Moor Coal, or Netherton Thick Coal, and the Twenty-seven Yards Coal band. These coals are absent in this district but are found at Kippax and elsewhere. The Warren House Coals occurring above, being represented in the Wakefield district by the Barnsley Bed.

* The Blocking coal in the north corresponds in position with the Silkstone in the south, and is the lowest of the Middle Coal-measure coals.

† "Geology of Yorkshire," p. 353.

‡ The equivalent of the Barnsley coal in the south, as regards horizon.

In the southern part of the Yorkshire coal-field the great seam is that of Barnsley. This bed so far exceeds in thickness and value any other of the known seams, with the exception of the Silkstone, that practically these are the only two coals that are wrought, and till they are exhausted no other seams are likely to be touched, except to a small extent for local consumption. The Barnsley bed, according to the authors of the "Yorkshire Coal-Field,"* derives its great value from the fact that a portion of the seam is semi-anthracitic, hard, or "Steam" coal, admirably adapted for use on locomotives, in steam-vessels, and for iron smelting, on account of its high heating power. This portion of the bed is made up of alternating layers of dull and bright coal; the former being probably of a semi-anthracitic and the latter of a more bituminous character. This mixture does away with the difficulty in lighting, which is one of the drawbacks attending the use of pure anthracite, and at the same time allows of a per-centage of carbon high enough to give great heating power. The hard coal, it is observed, occurs in the middle of the seam, the upper and lower portions being soft or bituminous, and extensively used as a house coal.

The annexed section of strata in the Barnsley district gives the respective thickness of the several beds, from the magnesian limestone to the millstone grit:—†

| STRATA. | THICKNESS. |
|--|------------|
| | Ft. In. |
| Magnesian Limestone | 75 0 |
| Lower Permian Sandstone | 54 0 |
| Red Rock of Rotherham | — |
| Strata | 0 to 100 0 |
| Pontefract Rock | 100 0 |
| Strata | 70 0 |
| Ackworth Rock | 54 0 |
| Strata | 510 0 |
| Shafton Coal | 5 0 |
| Strata | 393 0 |
| Muck Coal | 3 10 |
| Strata | 219 0 |
| Woodmoor Coal | 3 0 |
| Strata with Half Yard Coal | 45 0 |
| Winter Coal | 4 0 |
| Strata | — |
| Beamshaw Coal | 3 0 |
| Strata with Kent Coal | 1 0 |
| Mapple Coal (inferior quality) | 4 6 |
| Strata | 216 0 |

* Professor Green, Mr. Russell and others, p. 382.

† The Rev. Wm. Thorpe's "Diagram of Yorkshire Strata."

| STRATA.—continued. | | THICKNESS. | |
|---|-------|------------|-----|
| | | Ft. | In. |
| <i>Barnsley Coal</i> | | 9 | 3 |
| Strata | | 198 | 0 |
| <i>Swallow Wood Coal</i> | | 3 | 0 |
| Strata | | 234 | 0 |
| <i>Joan Coal</i> | | 2 | 0 |
| Strata | | 60 | 0 |
| <i>Flockton Top Coal</i> | | 3 | 3 |
| Strata | | 120 | 0 |
| <i>Parkgate Coal</i> | | 5 | 0 |
| Strata | | 78 | 0 |
| <i>Thorncliffe Thin Coal</i> | | 2 | 6 |
| Strata | | 123 | 0 |
| <i>Four Foot Coal</i> (variable) | | 2 | 6 |
| Strata | | 108 | 0 |
| <i>Silkstone Coal</i> | | 5 | 0 |
| Strata | | 195 | 0 |
| <i>Whin Moor or Low Moor Coal</i> | | 2 | 6 |
| Strata | about | 150 | 0 |
| <i>Flagstone</i> | about | 36 | 0 |
| Strata principally shales | | 495 | 0 |
| <i>Halifax Coal</i> (with <i>Pecten papyraceus</i> in roof and a floor of <i>Ganister</i>) | | 1 | 9 |
| Strata (shales and flags) | | 81 | 0 |
| <i>Halifax Soft Coal</i> | | 1 | 6 |
| Strata | | 150 | 0 |
| <i>Millstone Grit.</i> | | | |

The "Blocking Bed Coal" previously referred to, is the lowest coal seam in the Middle Coal measures: it corresponds in position with the Silkstone Coal and is taken to be its representative. "The 'Silkstone Coal,'" says Professor Green,* "is perhaps the most highly prized of the seams of the Yorkshire Coal-field. Where at its best it is bituminous, very pure, and has the highest reputation as a house coal. Very little of it is offered for sale in the district in which it is raised, the bulk being sent to the London market. The 'Smalls' are washed and converted into coke of excellent quality." A section of the Silkstone seam south of Sheffield and the adjoining part of Derbyshire, at the Renishaw Colliery, by Mr. Appleby, is as follows †:—

| STRATA. | | THICKNESS. | |
|----------------------------|--|------------|--------|
| Roof Coal | | 0 6 | to 0 7 |
| Dirt | | 0 2 | „ 0 5 |
| Hard Steam Coal } Top Coal | | 0 11 | „ 1 1 |
| Bright Gas Coal } | | | |
| Dirt | | 0 0½ | „ 0 4 |
| Bottom Coal | | 1 6 | „ 2 0 |
| Dirt | | 1 3 | „ 1 6 |
| Low Coal | | 1 9 | „ 2 0 |

* "Yorkshire Coal-field," p. 229.

† *Ibid.* p. 229.

Analyses of Yorkshire Coal.—The Barnsley “*Three Yard Seam*,” worked at Hoyland Colliery, described as being “very hard, durable, and excellent for steam purposes,” varies in thickness from 7 feet 6 inches to 8 feet, and is extracted at a depth of 180 yards from surface. The sample examined very much resembled silicified wood in structure, consisting of broad layers of a brownish colour, with alternate bands of a bright jet-like substance. In the use of this coal, it was observed that the best results were obtained when a moderately quick draft was employed.

“*Barnsley Coal*,” raised from Earl Fitzwilliam’s colliery at Elsecar, from a depth of 154 yards, usually has a thickness of 9 feet, and is extensively employed in the various ironworks in the immediate neighbourhood of the mine. It very much resembles the Three Yard seam, but is very much brighter, and contains more iron pyrites.

“*Barnsley Coal, Park Gate Colliery*.”—This colliery is situated near the village of Rawmarsh; the seam varies in thickness from 6 feet 8 inches to 8 feet, but the average is about 7 feet 6 inches, and the coal, like the two former, is largely employed in the locality in the manufacture of iron. The above examples of the Barnsley coal on examination show the annexed constituents* :—

| Constituents. | Barnsley Three-yard. | Elsecar Nine-feet. | Park Gate Seven-feet. |
|--------------------|-------------------------|-----------------------|--------------------------|
| Carbon | 80.05 | 81.93 | 80.07 |
| Hydrogen | 4.93 | 4.85 | 4.92 |
| Nitrogen | 1.24 | 1.27 | 2.15 |
| Sulphur | 1.06 | .91 | 1.11 |
| Oxygen | 8.99 | 8.58 | 9.95 |
| Ash | 3.73 | 2.46 | 1.80 |
| | 100.00 | 100.00 | 100.00 |
| Specific gravity . | 1.317 | 1.296 | 1.311 |
| Coke per cent. . . | 62.50 | 61.60 | 61.70 |

Numerous analyses are available of coals extensively worked in the Barnsley district. The following complete series of six samples of coal showing the gaseous constituents, and chemical composition, are however selected and show the important character of the seams wrought :—

* Reports: Coal suited to the Steam Navy, 1851. Appendix, Third Report, p. 55.

| Constituents. | Wombwell Main. | Darfield Main. | Oaks. | Elsecar. | Masbro' Park. | Edmunds Main. |
|----------------|----------------|----------------|---------|----------|---------------|---------------|
| Carbon . . . | 80.500 | 81.390 | 82.520 | 81.300 | 82.190 | 82.190 |
| Hydrogen . . | 5.500 | 5.500 | 5.025 | 5.190 | 5.173 | 5.080 |
| Oxygen . . . | 6.205 | 7.451 | 6.915 | 8.210 | 8.144 | 8.243 |
| Nitrogen . . . | 1.862 | 1.496 | 2.120 | 1.890 | 1.730 | 1.728 |
| Sulphur . . . | 1.833 | 2.100 | 1.144 | 1.210 | 1.537 | 1.447 |
| Ash | 4.100 | 2.063 | 2.276 | 2.200 | 1.226 | 1.312 |
| | 100.000 | 100.000 | 100.000 | 100.000 | 100.000 | 100.000 |

The specific gravity and yield per cent. of coke of each of the above is as follows :—

| Coals. | Specific gravity. | Coke per cent. |
|---------------------|-------------------|----------------|
| Wombwell Main . . . | 1.266 | 63.130 |
| Darfield Main . . . | 1.270 | 63.188 |
| Oaks | 1.270 | 65.520 |
| Elsecar | 1.290 | 62.000 |
| Masbro' Park . . . | 1.268 | 63.640 |
| Edmunds Main . . . | 1.270 | 63.280 |

The chemical composition of the ash of the same series of coals appears in the annexed statement :—

| Constituents. | Wombwell Main. | Darfield Main. | Oaks. | Elsecar. | Masbro' Park. | Edmunds Main. |
|---------------------|----------------|----------------|--------|----------|---------------|---------------|
| Silica | 18.97 | 21.59 | 31.630 | 37.060 | 33.18 | 32.413 |
| Alumina | 43.04 | 43.86 | 62.340 | 52.390 | 53.63 | 46.900 |
| Oxide of Iron . . . | 16.87 | 20.68 | 1.902 | 3.266 | 3.35 | 7.000 |
| Lime | 4.90 | 1.93 | 0.900 | 2.450 | 1.11 | 5.690 |
| Magnesia | 16.16 | 11.81 | 2.820 | 4.572 | 8.71 | 7.271 |
| Sulphuric Acid . . | 99.94 | 99.87 | 99.592 | 99.738 | 99.93 | 99.274 |

Other important seams met with in the colliery of the Barrow Hematite Company, now in course of development at the Barrow Silkstone Colliery, about four miles from Barnsley, occur in the following descending order, and thickness :—*

| | Ft. | In. |
|------------------------------------|-----|-----|
| <i>Swallow Wood Coal</i> | 3 | 0 |
| <i>Joan Coal</i> | 2 | 0 |
| <i>Parkgate Coal</i> | 4 | 0 |
| <i>Flockton Coal</i> | 2 | 3 |
| <i>Thorncliffe Coal</i> | 4 | 4 |
| <i>Silkstone Coal</i> | 5 | 6 |

* "Mining Journal," Feb. 14, 1880, p. 178.

The last-named seam occurs at a depth of 481 yards from the surface, and 61 yards below the Thorncliffe seam; it is described as a rather tender coal, with about 6 inches of dirt in the middle, and a first-class coal for coking and gas making purposes, whilst the top portion of the Thorncliffe seam, in particular, is well adapted for steam and household purposes, being very hard. The Parkgate seam is said to be inferior to the Silkstone. The chemical compositions of the Silkstone coals are as follows:—

RESULTS TABULATED.

| | |
|--------------------|--------|
| Carbon | 80.46 |
| Hydrogen | 5.08 |
| Nitrogen | 1.67 |
| Oxygen | 6.80 |
| Sulphur | 1.65 |
| Ash | 3.30 |
| Moisture | 1.04 |
| | <hr/> |
| | 100.00 |
| | <hr/> |

These results show that this coal is equal to any found in the district; possessing a high illuminating power and yielding upwards of 11,000 cubic feet of gas per ton, and when coked gives 12 cwt. of coke to the ton of coal, equivalent to 60 per cent. The Silkstone coal raised at the Hoyland Colliery, and examined by Mr. Baynes, the public analyst,* showed the same constituents as the foregoing, while as regards its illuminating power, it was found that taking a number of candles (each burning 120 grains of sperm per hour), required to yield an amount of light equal to a burner consuming 5 cubic feet of gas per hour, corrected to a temperature of 60° Fahr., and a barometrical pressure of 30 inches, the—

| | |
|---|------------------------|
| Average of three experiments was | 17.10 |
| The number of cubic feet of gas yielded by each ton of coal | 11,650 |
| Weight of illuminating matter per ton of coals in pounds of sperm | 683.02 |
| Volatile matter per cent. | 35.52 |
| Coke per cent. | 64.48 |
| Coke yielded by one ton of Coals | 12 cwt. 3 qrs. 16 lbs. |

This coal is also extensively coked, and is in good demand in the steelworks of Sheffield, where it is largely employed.

The coals raised in the Normanton district at Whitwood

* Barnsley.

Colliery,* suited alike for gas manufacture and for general heating purposes, show the following results. The analyses were made by Mr. Wm. Carr, of the Halifax Corporation Gas Works, who describes the samples as of "Silkstone Brights Gas Coals" and "Silkstone Hards." The mineralogical character of the gas coals is thus referred to: "Colour:—bright, black, and shining. Streak:—dull, containing slight deposit of shale. Fracture:—smooth and glossy, containing thin deposit of carbonate of lime. Cross fracture:—irregular, apparently free from iron pyrites; hard, compact, and cohesive. On the fire it intumesces and slightly agglomerates. Colour of ash:—reddish grey." The analyses of the two varieties are as under:—

SILKSTONE BRIGHTS GAS COAL.

| | First. | Second. |
|--------------------------------|------------|------------|
| Volatile matter | 38·54 | 33·34 |
| Fixed combustible matter . . | 58·68 | 62·67 |
| Ash | 2·23 | 3·44 |
| Water (expelled at 212° Fahr.) | 0·55 | 0·55 |
| | 100·00 | 100·00 |
| Specific gravity | 1·268 | 1·268 |
| Weight of a cubic foot . . . | 79·15 lbs. | 79·15 lbs. |

The results arrived at by a practical analysis appear in the annexed details.

RESULTS TABULATED.

| | First. | Second. |
|--|--------------------------|--------------------------|
| Purified gas per ton of coal . . (Bar. 30", ther. 60°) | 10·949 cu. feet | 11·166 cu. feet |
| Illuminating power of gas } standard burner } | 18·22 { sperm candles | 18·23 { sperm candles |
| Value of illuminating matter } per ton of coal in sperm . . } | 684·25 lbs. | 697·90 lbs. |
| Hydro-carbons in gas | 4·25 % | 4·00 % |
| Carbonic oxide | 8·50 % | 9·25 % |
| Carbonic acid | 3·00 % | 2·00 % |
| Sulphuretted hydrogen . . . | 1·75 % | 1·00 % |
| Tar produced per ton of coal . | 200 lbs. | 106·25 lbs. |
| Liquor | 136·25 lbs. | 293·75 lbs. |
| Strength of ammoniacal liquor. | 5° Twaddle | 3° Twaddle |
| Coke produced per ton . . . | 1362·5 lbs. | 1481·25 lbs. |
| Ash in Coke | 3·84 % | 4·24 % |

* Messrs. Hy. Briggs & Co., Limited.

The above results are the mean of four tests in each analysis, and show the coal to be of first class quality for heating purposes.

The "Silkstone Hards Coal" is thus described and reported upon by the same analyst:—*

MINERALOGICAL CHARACTERS.

COLOUR:—Bright, black, and shining.

STREAK:—Irregular, dull black, containing thin deposit of amorphous carbon.

FRACTURE:—Smooth and glossy, containing thin deposit of carbonate of lime.

CROSS FRACTURE:—Irregular and slightly conchoidal, apparently free from iron pyrites and shale—massive, compact, and cohesive. On the fire it splutters slightly, intumesces, and agglomerates.

COLOUR OF ASH:—Light grey.

SPECIFIC GRAVITY:—1·304 (Water=1·000) weight of one cubic foot 81·40 lbs.

CHEMICAL ANALYSIS.

| | |
|--|-----------------|
| Volatile matter | 31·67 per cent. |
| Fixed combustible matter | 65·57 „ |
| Ash | 1·95 „ |
| Water (expelled at 212° Fahr.) | ·81 „ |
| | <hr/> |
| | 100·00 |

PRACTICAL ANALYSIS.

| | |
|---|---------------------|
| Purified gas per ton of coal (Bar. 30", Ther. 60°) . | 10·654 cubic ft. |
| Illuminating power (Standard burner) . | 18·64 sperm candles |
| Value of illuminating matter per ton of coal, in sperm, 680·88 lbs. | |
| Coke produced per ton of Coal (13 cwt. 2 qr.) . | 1·512·5 lbs. |
| Ash in coke | 3·33 per cent. |

The above results are the mean of three tests and shew the coal to be of excellent quality for heating purposes (the per centage of ash being very low, and the quantity of fixed combustible matter very high) and of fair quality for gas purposes.

Production of Coal in the Yorkshire Coal-field.—It appears incidentally from an inquiry made of the quantity of coals conveyed by canals and railways in different parts of the kingdom in 1816, that the quantity carried in and from Yorkshire amounted to 2,563,626 tons; from Derbyshire, 942,218 tons; and from Nottinghamshire, 494,665 tons, or an aggregate of 4,000,509 tons from the coal-field extending through the above-named counties. But little information showing the development of the coal resources of Yorkshire is obtainable until 1854; the shipments, however, from the several ports of Yorkshire, show a great increase, and prove the rapid extension of colliery operations

* Mr. W. Carr, of Halifax.

Thus, between the years 1819 and 1830 the total shipments of coal, from the Yorkshire coal-field, did not exceed 243,812 tons, increased to 1,042,843 tons between 1835 and 1840, and to 2,273,049 tons between 1841 and 1850. In the year 1854 the total output of the West Riding coal-field was 7,260,500 tons; the produce of the respective districts being as under :—

| DISTRICTS. | TONS. |
|------------------------|------------------|
| Leeds | 2,040,000 |
| Bradford | 1,000,000 |
| Wakefield | 700,000 |
| Huddersfield | 300,500 |
| Barnsley | 1,250,000 |
| Halifax | 350,000 |
| Rotherham | 520,000 |
| Sheffield | 650,000 |
| Dewsbury | 450,000 |
| Total | <u>7,260,500</u> |

In subsequent years the number of collieries, and output of coals was as follows :—

| Year. | Number of Collieries. | Coal raised. | Year. | Number of Collieries. | Coal raised. |
|-------|-----------------------|--------------|-------|-----------------------|--------------|
| | | Tons. | | | Tons. |
| 1855 | 333 | 7,747,470 | 1868 | 441 | 9,740,510 |
| 1856 | 399 | 9,083,625 | 1869 | 413 | 10,829,827 |
| 1857 | 374 | 8,875,440 | 1870 | 416 | 10,606,604 |
| 1858 | 383 | 8,302,150 | 1871 | 423 | 12,801,260 |
| 1859 | 383 | 8,247,100 | 1872 | 441 | 14,576,000 |
| 1860 | 387 | 9,284,000 | 1873 | 491 | 15,311,778 |
| 1861 | 397 | 9,374,000 | 1874 | 521 | 14,812,515 |
| 1862 | 418 | 9,255,500 | 1875 | 523 | 15,425,278 |
| 1863 | 415 | 9,402,500 | 1876 | 562 | 15,055,275 |
| 1864 | 420 | 8,809,600 | 1877 | 539 | 15,952,400 |
| 1865 | 434 | 9,355,100 | 1878 | 526 | 15,581,970 |
| 1866 | 447 | 9,714,700 | 1879 | 525 | 16,024,249 |
| 1867 | 454 | 9,843,575 | 1880 | 490 | 17,468,536* |

Previous to the year 1871 the quantities of coal raised in the several districts of Yorkshire were separately ascertained, showing the industrial progress of each district. As these are now no longer published the returns for 1860 and 1870 will serve to show the progress between these two years.

* Report, H. M. Inspector of Mines.

| Districts. | 1860. | | 1870. | |
|------------------------|-------------|--------------|-------------|--------------|
| | Collieries. | Coal raised. | Collieries. | Coal raised. |
| | Nos. | Tons. | Nos. | Tons. |
| Leeds | 81 | 2,459,500 | 96 | 2,414,750 |
| Normanton | 2 | | 5 | 902,450 |
| Bradford | 54 | 1,250,500 | 48 | 670,500 |
| Huddersfield | 51 | 355,000 | 26 | 135,286 |
| Barnsley | 42 | 2,430,000 | 44 | 2,250,750 |
| Halifax | 30 | 375,000 | 29 | 89,750 |
| Wakefield | 36 | 820,000 | 47 | 1,125,700 |
| Rotherham | 20 | 493,000 | 24 | 1,140,000 |
| Sheffield | 29 | 651,000 | 35 | 975,750 |
| Dewsbury | 26 | 450,000 | 31 | 514,877 |
| Penistone | 5 | | 6 | 20,660 |
| Pontefract | 4 | | 6 | 296,440 |
| Bingley | 4 | | 5 | 32,500 |
| Saddleworth and Settle | 3 | | 2 | 14,036 |
| Holmfirth | ... | | 12 | 23,145 |
| Total | 387 | 9,284,000 | 416 | 10,606,604 |

The increase in the production of 1870 as compared with 1860, amounts to 1,822,604 tons, which, divided over the ten years, exhibits an increase of 182,000 tons per annum, a quantity unimportant compared with the returns of recent years. When, however, between the years 1871 and 1872 a great demand for coal arose throughout the country, the coal owners of Yorkshire at once met the industrial requirements by an increased production amounting to 1,774,740 tons over the output of 1871; and again in 1873 an increase of 785,778 tons over the preceding year, the demand being satisfied a falling off appears in 1874, amounting to 499,263 tons, since which year a steady increase is exhibited amounting in 1879 to 1,211,734 tons over the output of 1874, equivalent to an increase of nearly nine per cent. The details of production of the Yorkshire collieries are as follows for the year 1874.

| DISTRICTS. | TONS. |
|------------------------------------|-------------------|
| Barnsley | 3,145,150 |
| Bradford | 695,450 |
| Dewsbury | 455,520 |
| Halifax, Huddersfield, &c. | 186,150 |
| Leeds and Normanton | 4,250,000 |
| Rotherham | 2,525,500 |
| Sheffield and Wakefield | 2,595,520 |
| Smaller districts | 959,225 |
| Total | <u>14,812,515</u> |

Railway Distribution.—The total quantities of coal carried from the Yorkshire coal-field over the Midland Railway system in the year 1854 was 212,009 tons, increased to 363,288 tons in the year 1856. During the next few years the total quantities carried were as under :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1857 | 344,580 | 1863 | 563,665 |
| 1858 | 271,808 | 1864 | 687,124 |
| 1859 | 390,876 | 1865 | 438,444 |
| 1860 | 483,693 | 1866 | 968,600 |
| 1861 | 495,211 | 1867 | 1,028,353 |
| 1862 | 536,318 | 1868 | 1,136,539 |

The great influence exercised by the Midland Railway in the movement and distribution of coal, appears in the gross total carried from all districts, amounting to 2,525,751 tons in the year 1857, increased to 5,822,494 tons in 1868.

Since and during 1869 the quantities carried by this system over their own lines and that passed over to other companies for conveyance will be found in the annexed statement :—

| Year. | MIDLAND RAILWAY. | | Total carried. |
|-------|------------------|------------------------|----------------|
| | Own lines. | Passed to other lines. | |
| | Tons. | Tons. | Tons. |
| 1869 | 1,246,022 | 140,553 | 1,386,575 |
| 1870 | 1,382,808 | 177,693 | 1,560,501 |
| 1871 | 1,503,650 | 177,243 | 1,680,893 |
| 1872 | 1,637,746 | 122,866 | 1,760,602 |
| 1873 | 1,872,312 | 108,611 | 1,980,923 |
| 1874 | 1,497,738 | 102,117 | 1,599,855 |
| 1875 | 1,605,600 | 215,572 | 1,821,172 |
| 1876 | 1,540,432 | 204,409 | 1,744,841 |
| 1877 | 1,732,009 | 217,798 | 1,949,807 |
| 1878 | 2,086,952 | 349,311 | 2,436,263 |
| 1879 | 2,199,892 | 321,328 | 2,521,220 |
| 1880 | 2,408,650 | 298,961 | 2,707,611 |

The North-Eastern Railway carried from Yorkshire collieries for consumption at places on their system, and to Hull and Selby for shipment, the following quantities :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1854 | 338,777 | 1868 | 606,689 |
| 1855 | 278,288 | 1869 | 675,378 |
| 1856 | 287,144 | 1870 | 866,422 |
| 1857 | 357,656 | 1871 | 1,064,407 |
| 1858 | 341,375 | 1872 | 1,134,542 |
| 1859 | 334,835 | 1873 | 1,067,651 |
| 1860 | 412,097 | 1874 | 1,105,021 |
| 1861 | 403,825 | 1875 | 1,231,248 |
| 1862 | 391,097 | 1876 | 1,240,645 |
| 1863 | 361,859 | 1877 | 1,318,887 |
| 1864 | 456,320 | 1878 | 1,344,318 |
| 1865 | 469,080 | 1879 | 1,455,895 |
| 1866 | 527,887 | 1880 | 1,583,942 |
| 1867 | 581,708 | | |

A small proportion of the above coal is derived from Lancashire, but it is not possible to distinguish the quantities, while of the coal thus carried, from 60 to 70 per cent. is used for manufacturing, and household purposes.

The Manchester, Sheffield, and Lincolnshire Railway Company are also great carriers of Yorkshire coal. The extent of the traffic will be understood from the statement below, showing the respective quantities carried from the West Riding and from South Yorkshire, with the total weight since the year 1867 :—

| Year. | West Riding. | South Yorkshire. | Total Weight. |
|-------|--------------|------------------|---------------|
| | Tons. | Tons. | Tons. |
| 1867 | 686,739 | 1,531,142 | 2,217,881 |
| 1868 | 665,890 | 1,498,356 | 2,164,246 |
| 1869 | 752,291 | 1,549,216 | 2,301,057 |
| 1870 | 948,600 | 1,679,443 | 2,628,043 |
| 1871 | 1,069,967 | 2,090,600 | 3,160,567 |
| 1872 | 1,127,956 | 2,441,683 | 3,569,639 |
| 1873 | 1,208,859 | 2,475,088 | 3,683,947 |
| 1874 | 1,233,044 | 2,421,638 | 3,654,682 |
| 1875 | 1,258,498 | 2,788,466 | 4,046,964 |
| 1876 | 1,111,089 | 2,600,070 | 3,711,159 |
| 1877 | 1,047,861 | 3,052,577 | 4,100,438 |
| 1878 | 1,030,464 | 3,067,239 | 4,097,703 |
| 1879 | 1,059,589 | 3,494,690 | 4,554,279 |
| 1880 | 1,104,661 | 3,597,637 | 4,702,298 |

The Great Northern Railway.—The total of coal and coke carried from collieries in Yorkshire in the year 1854 by this

system was 212,327 tons, increased to 474,348 tons in 1855, and 688,743 tons in 1857. Since the year 1860, the quantities carried from the South Yorkshire and West Riding districts are as follows :—

| Year. | South Yorkshire. | West Riding of Yorkshire. | Total carried. |
|-------|------------------|------------------------------|----------------|
| | Tons. | Tons. | Tons. |
| 1860 | 409,623 | 9,893 | 419,516 |
| 1862 | 534,865 | 52,604 | 587,469 |
| 1866 | 497,418 | 412,829 | 910,247 |
| 1867 | 626,219 | 455,888 | 1,082,107 |
| 1868 | 521,739 | 400,783 | 922,522 |
| 1869 | 470,140 | 425,578 | 895,718 |
| 1870 | 551,348 | 443,261 | 994,609 |
| 1871 | 801,504 | 490,571 | 1,292,075 |
| 1872 | 874,620 | 680,068 | 1,554,688 |
| 1873 | 862,139 | 635,097 | 1,497,236 |
| 1874 | 753,162 | 577,048 | 1,330,210 |
| 1875 | 848,551 | 691,145 | 1,539,696 |
| 1876 | 719,183 | 706,556 | 1,425,739 |
| 1877 | 835,883 | 740,073 | 1,575,956 |
| 1878 | 755,808 | 865,570 | 1,621,378 |
| 1879 | 989,554 | 971,236 | 1,960,790 |
| 1880 | 863,575 | 971,074 | 1,834,649 |

The Lancashire and Yorkshire Railway in the year 1869 carried from the Yorkshire coal-field 1,023,261 tons, increased in the year 1880 to 1,751,510 tons; the respective quantities for each of the intervening years :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1866 | 805,429 | 1876 | 1,843,924 |
| 1869 | 1,023,261 | 1877 | 1,750,308 |
| 1872 | 1,359,835 | 1878 | 1,765,380 |
| 1873 | 1,870,452 | 1879 | 1,806,752 |
| 1874 | 1,756,586 | 1880 | 1,751,510 |
| 1875 | 1,851,639 | | |

The London and North Western Railway, in the year 1859, carried 119,985 tons of coal from Yorkshire, and in 1865, 167,780 tons; since 1867 the total quantities carried have been as under, that passed over to other lines for conveyance being distinguished from the quantities conveyed to main line stations :—

| Year. | Conveyed over Main Line. | Passed over to other lines. | Total carried. |
|-------|-----------------------------|--------------------------------|----------------|
| | Tons. | Tons. | Tons. |
| 1867 | 151,270 | 32,104 | 183,374 |
| 1868 | 166,911 | 29,821 | 196,732 |
| 1869 | 175,416 | 57,080 | 232,496 |
| 1870 | 160,848 | 42,357 | 203,205 |
| 1871 | 166,623 | 41,339 | 207,962 |
| 1872 | 219,991 | 5,116 | 225,107 |
| 1873 | 182,211 | 31,861 | 224,072 |
| 1874 | 179,231 | 52,797 | 232,028 |
| 1875 | 217,911 | 60,795 | 278,706 |
| 1876 | 207,543 | 60,096 | 267,639 |
| 1877 | 193,240 | 76,547 | 269,787 |
| 1878 | 173,874 | 76,891 | 250,765 |
| 1879 | 177,355 | 74,100 | 251,455 |
| 1880 | 157,643 | 79,005 | 236,648 |

Coals Shipped Coastwise and Exported to Foreign Countries.—

Previous to the year 1850 there was an export duty on all coal exported in foreign ships; coals to foreign countries and our colonial possessions in British ships being free of duty. In the year 1835 the quantity of coal sent coastwise from the Yorkshire ports of Hull, Goole, and Grimsby was 129,197 tons; that sent to foreign countries being 11,977 tons, or a total movement of 141,174 tons compared with 1,480,465 tons in the year 1880, of which 146,670 tons was shipped coastwise, and 1,333,795 tons to foreign countries. The shipments were as follows in each of the years named:—

| Year. | SHIPMENTS. | | Total. |
|-------|------------|-----------|-----------|
| | Coastwise. | Foreign. | |
| | Tons. | Tons. | Tons. |
| 1835 | 129,197 | 11,977 | 141,174 |
| 1840 | 159,345 | 32,892 | 192,237 |
| 1845 | 195,742 | 49,355 | 245,097 |
| 1850 | 165,889 | 50,862 | 216,751 |
| 1855 | 117,698 | 71,461 | 189,159 |
| 1860 | 133,425 | 249,633 | 382,058 |
| 1865 | 172,726 | 381,070 | 553,796 |
| 1870 | 186,501 | 505,139 | 691,640 |
| 1875 | 194,751 | 945,594 | 1,140,345 |
| 1876 | 172,360 | 1,023,157 | 1,195,517 |
| 1877 | 156,577 | 1,021,551 | 1,178,128 |
| 1878 | 128,100 | 1,046,556 | 1,174,656 |
| 1879 | 169,334 | 972,769 | 1,142,103 |
| 1880 | 146,670 | 1,333,795 | 1,480,465 |

Throughout the foregoing returns showing the distribution of coal, the produce of Yorkshire, a great increase appears, though not in the same proportion as in other coal-fields; the following, showing the respective quantities carried by railway, &c., in each of the years 1870 and 1879, will indicate the increase in the periods referred to:—

| Distribution. By Rail and Sea. | 1879. Quantities. | 1870. Quantities. | Total Increase. |
|---|----------------------|----------------------|--------------------|
| | Tons. | Tons. | Tons. |
| Midland | 2,521,220 | 1,560,501 | 960,719 |
| North-Eastern | 1,455,895 | 866,422 | 589,473 |
| Manchester, Sheffield and Lin- colnshire | 4,554,279 | 2,628,043 | 1,926,236 |
| Great Northern | 1,960,790 | 994,609 | 966,181 |
| London and North Western | 251,455 | 203,205 | 48,250 |
| Lancashire and Yorkshire | 1,806,752 | 1,023,261 | 783,491 |
| Coastwise | 169,234 | 186,501 | |
| Exported | 972,769 | 505,139 | 450,363 |

The aggregate of Yorkshire coal carried by the above-named railways in 1879 was 13,692,894 tons, against 7,967,681 tons in the year 1870, showing an increase in the movement of coal of 5,724,713 tons, equivalent to 70 per cent., and this is exclusive of the increase of coal carried by canals, the early returns of which are not available for comparison with those of recent years.

Price of Coal and Cost of Production.—Twenty years ago, in the Barnsley district, the cost of getting coal varied from 4s. to 5s. per ton. The selling price at the pit's bank varying according to the character of the coal:—"The Barnsley Bed" at this period selling from 4s. 6d. to 7s. per ton; the Barnsley Softs, or House Coals, from 4s. 6d. to 6s.; "Hards," or Steam Coal, from 6s. to 7s.; "the Silkstone Bed" commanding a higher price, from 6s. to 8s. per ton. Ten years previously, in 1851, the average selling price of coals per ton at the pit's mouth in Yorkshire varied from 7s. per ton for ordinary coals to 8s. 4d. for best household coals. In Sheffield the prices ruling at the wharves were as follows per ton:—

| | | |
|--|------------|-----|
| | s. | d. |
| Picked coal for steel making | 10 | 0 |
| House coal | 7s. 6d. to | 8 4 |
| Engine coal. | 5 | 0 |
| Hard coke for steel smelting | 15 | 6 |

an additional charge of from 8d. to 1s. per ton being added for cartage.

In 1870 prices exhibited but little variation compared with 1860. The Barnsley "Hards" were selling for 7s.; House Coal, 6s.; Engine Coal, 4s., and Slack, 1s. 6d. per ton;—the best coals of Bradford, at Bowling, being quoted at 9s. per ton, and Seconds at 7s. 6d. and 5s. In the Leeds district the best coals varied from 8s. to 9s. 6d. per ton; the Seconds, from 5s. to 7s. 6d., and Slack, from 2s. to 2s. 9d. per ton. During the years 1871 to 1878 prices rose, due in a measure to the demand but more especially to the operation of the Coal Mines Regulation Act, which took effect about that time. Since that date, however, prices have fluctuated, and in 1878, 1879, and 1880 the following may be generally regarded as average, highest, and lowest prices of coal and slack at the pit's mouth in the Yorkshire collieries:—

| Year. | Coal and Slack. | Average. | Highest. | Lowest. |
|-------|-------------------|----------|----------|---------|
| | | s. d. | s. d. | s. d. |
| 1878 | Coal (per ton). . | 8 0 | 10 6 | 6 0 |
| | Slack „ . . | 4 0 | 5 4 | 2 6 |
| 1879 | Coal „ . . | 7 9 | 14 0 | 6 0 |
| | Slack „ . . | 4 4 | 5 10 | 2 0 |
| 1880 | Coal „ . . | 8 0 | 11 0 | 6 0 |
| | Slack „ . . | 4 6 | 5 0 | 2 0 |

In respect to wages, it has been generally observed that colliers in Yorkshire have been better paid than in other coal-fields. It is not, however, so easy to give an exact account of the variations in the cost of production, as in Yorkshire payment is usually made by the ton of coal raised, instead of by the day, and as the seams are of varying qualities and thickness the rate varies in different districts and in different seams. It is a fact, however, that the rate rose as quickly and as much in Yorkshire as in any other coal-field during the prosperous years of 1871—78. In the last-named year there were instances in which the colliers were getting exactly 150 per cent. more for their labour than in 1868; but these were extreme cases. In 1871, which is taken generally as a fair basis of comparison, certain collieries paid 3s. 7d. per ton for the labour of raising the coal; that rate rose in 1872 to 5s. 7d., and in 1873 it reached 7s. 1d. The latter extreme rate only lasted a short time. The average maximum

would be more accurately stated at 6*s.* 5*d.*, an increase of over 80 per cent. When wages were at that high pitch, there were undoubted instances in which some of the most industrious and efficient colliers made as much as five pounds per week. In South Yorkshire, about the middle of 1879, the wages of miners averaged 5*s.* 3*d.* a day, or 27*s.* a week for hewers, while in Durham at the same time the average rate was 4*s.* 2*d.* a day.*

Population Employed in Coal and Iron-stone Mining.—The total number of persons of all ages engaged in the Yorkshire coal-field in the year 1854 was 22,194; of these 21,080 were employed in coal mining, and 1,164 in iron-stone mining. The census for 1861 gives the number, including all employed in and about the mines, as 31,938, the quantity of coal raised the same year amounting to 9,374,600 tons, giving an average yield of 293 tons per man. It was not, however, until the year 1873 that the exact number of persons employed was ascertained under the clauses of the "Coal Mines Regulation Act, 1872." It will, however, serve for comparison to note the inspector's returns previous to 1873, which give the aggregate number of persons employed, together with the quantity of coal raised in each year, and the average yield per individual:—

| Year. | Persons employed. | Coal raised. | Average per Man. |
|-------|-------------------|--------------|------------------|
| | Noa. | Tons. | Tons. |
| 1861 | 31,938 | 9,374,600 | 293 |
| 1864 | 34,500 | 9,300,000 | 270 |
| 1865 | 35,000 | 9,300,000 | 266 |
| 1866 | 35,500 | 9,450,000 | 266 |
| 1867 | 37,000 | 9,850,000 | 266 |
| 1868 | 37,000 | 9,705,000 | 262 |
| 1869 | 36,000 | 10,893,000 | 302 |
| 1870 | 36,500 | 11,545,000 | 316 |
| 1871 | 38,600 | 12,801,260 | 331 |
| 1872 | 51,056 | 14,576,000 | 285 |

Comparing the average produce per man in 1872 with 1871, a falling off appears of 46 tons, due to the greater number of persons employed in the year 1872; this is explained by Mr. Frank N. Wardell, the inspector of the district, in his evidence given before the "Select Committee on Coal, 1873," † in

* "Colliery Guardian," 1880, p. 382.

† Report Select Committee on Coal, 1873, p. 32, Question 687.

reply to a question : " But do you know whether this increase has been chiefly or entirely of men working under ground, or of men working above ground ? " " I believe that this return of persons employed which has been given to me this year is a very much more accurate one than has ever been given before, and for this reason, that the return which is now required by this new Act of Parliament embraces every single person, man and boy, employed about the mine, from the face in the pit to the staiths outside ; and I believe there are thousands that I have had returned to me this year who were never returned in any shape or form before."

In the year 1873, for the first time, it was ascertained that the total number of persons employed in the collieries of Yorkshire was 57,523 ; of these 45,828 of all ages were engaged under ground, and 11,695 above ground, their ages being distinguished as follows. In the same year 491 mines were in operation, raising coal, fireclay, and ironstone.

| Ages. | Under Ground. | Above Ground. |
|---------------------|---------------|---------------|
| | Nos. | Nos. |
| From 10 to 12 . . . | 837 | 374 |
| „ 10 to 13 . . . | ... | 10* |
| „ 12 to 13 . . . | 1,846 | ... |
| „ 13 to 16 . . . | 6,807 | 712† |
| Above 16 . . . | 36,338 | 10,599† |
| Total . . . | 45,828 | 11,695 |

The total of minerals wrought in the coal-field in 1873 amounted to 15,695,249 tons, made up of coal, 15,311,778 tons ; fire-clay, 149,180 tons ; and ironstone, 234,341 tons, giving an average of mineral wrought to each person employed of 273 tons. The number of persons employed under ground, and above ground, and of the minerals wrought in each year since 1873, appear in the following table, together with the average yield of mineral per person, amounting in the year 1880 to 295 tons.‡

* Including 8 females.

† Including 15 females.

‡ Reports of H.M. Inspectors of Mines.

PERSONS EMPLOYED AND MINERALS RAISED IN YORKSHIRE SINCE 1873.

| Year. | PERSONS EMPLOYED. | | | MINERALS RAISED. | | | Total Minerals raised. | Average per man. |
|-------|-------------------|---------------|--------|------------------|------------|-------------|------------------------|------------------|
| | Under Ground. | Above Ground. | Total. | Coal. | Fire Clay. | Iron Stone. | | |
| | | | | | | | | |
| Nos. | Nos. | Nos. | Tons. | Tons. | Tons. | Tons. | Tons. | |
| 1873 | 45,828 | 11,695 | 57,523 | 15,311,778 | 149,130 | 234,341 | 15,695,249 | 273 |
| 1874 | 49,683 | 12,816 | 62,499 | 14,827,313 | 187,819 | 212,777 | 15,221,909 | 243 |
| 1875 | 49,006 | 13,184 | 62,190 | 15,855,990 | 183,961 | 236,782 | 16,276,733 | 262 |
| 1876 | 48,367 | 12,650 | 61,017 | 15,129,506 | 183,234 | 240,116 | 15,552,886 | 254 |
| 1877 | 47,808 | 12,786 | 60,594 | 15,805,235 | 188,346 | 249,454 | *16,247,851 | 268 |
| 1878 | 47,985 | 11,792 | 59,777 | 15,582,283 | 174,865 | 226,793 | +15,995,165 | 267 |
| 1879 | 48,327 | 11,760 | 60,087 | 16,241,443 | 155,938 | 199,866 | †16,628,707 | 276 |
| 1880 | 48,654 | 11,820 | 60,474 | 17,468,536 | 178,987 | 180,250 | §17,870,342 | 295 |

* Including 4,816 tons of oil shale.

†

" 31,470

" "

" 11,224

" "

" 42,569

" "

" "

" "

The distribution of labour in Yorkshire shows more than ordinary uniformity throughout the depression of recent years. Since 1878, the average production per man has only once shown any notable variation. This falling off in production occurred in the year 1874, when 4,976 persons were employed in excess of the previous year, the output of coal being 484,465 tons less. The cause is thus explained. In the previous years of scarcity there was a great demand for more labour at the collieries, and it was not till 1874 that that demand was satisfied. It was met however by the influx of all sorts of unskilled labour. Artisans and labourers from other trades were attracted by the high rate of wages offered and flocked to the collieries; but they were necessarily less efficient than a corresponding number of trained hands would have been. Some eighteen months or two years' experience are considered necessary to make an efficient collier, and hence we find that in Yorkshire the anomalous state of the colliery labour that prevailed in 1874 did not continue.

The actual output per man, due to the different positions and thickness of the coal-seams in different collieries show great variations. In some of the best collieries of the district the actual output per man has been as high as 500 tons per annum, in others it has not exceeded 190 tons. In addition to the difference of the character of the coal worked, the number of days which the men worked also affects their actual output. In some districts the collieries have been known to work double the time of others.

During the year 1879 there were 24 new pits being sunk in Yorkshire; most of them being near Leeds and Sheffield, there being only one or two new sinkings near Barnsley.

Of the persons employed in the year 1879 in the Yorkshire coal-field, the following statement will show their respective ages:—

| Ages. | Under ground. | Above ground. |
|---------------------|---------------|---------------|
| | Nos. | Nos. |
| From 10 to 12 . . . | 250 | ... |
| ,, 10 to 13 . . . | ... | 118 |
| ,, 12 to 13 . . . | 769 | ... |
| ,, 13 to 16 . . . | 5,503 | 848 |
| Above 16 . . . | 41,805 | 10,783 |
| Total . . . | 48,327 | 11,760* |

* Including eleven females employed above ground.

Resources and Probable Duration of the Midland Coal-Field.—The coal-fields of South Yorkshire, Derbyshire, and Nottinghamshire comprise a part of the Midland coal-field. The late Mr. J. T. Woodhouse, a member of the Royal Coal Commission, to whom was entrusted this enquiry, has arrived at the following results. The acreage of the coal-field being divided as under :—

| Name of District. | Total Acreage. | Acreage Unwrought. |
|-----------------------------|----------------|--------------------|
| | Acres. | Acres. |
| <i>Outside the Permian</i> | | |
| Midland | 6,039,615 | 5,856,948 |
| Midland deep coal | 265,590 | 265,590 |
| <i>Proved Sub-Permian</i> | | |
| Midland | 1,523,396 | 1,519,517 |
| Midland deep coal | 141,555 | 141,555 |
| Total acreage | 7,970,156 | 7,783,610 |

The quantity of coal estimated as originally existing in the coal-field, all necessary deductions being made for coal which cannot be worked by reason of its being left for boundary pillars, faults, broken ground, waste in working, &c., gave a total of 33,768,362,814 tons, the quantity remaining unwrought, 32,721,198,832 tons, and the net tonnage remaining and available for future supplies, 18,406,799,443 tons.

The details of these quantities apportioned in districts are as under : *—

| Name of District. | TONNAGE. | | |
|-----------------------------|--------------------------|------------------------------|--|
| | Total estimated tonnage. | Tonnage remaining unwrought. | Net tonnage available for consumption. |
| | Tons. | Tons. | Tons. |
| <i>Outside the Permian</i> | | | |
| Midland | 24,714,936,964 | 23,693,839,102 | 13,327,784,524 |
| Midland deep coal | 747,285,800 | 745,285,800 | 420,348,320 |
| <i>Proved Sub-Permian</i> | | | |
| Midland | 7,801,543,230 | 7,777,477,110 | 4,374,830,886 |
| Midland deep coal | 504,596,820 | 504,596,820 | 283,835,713 |
| Total | 33,768,362,814 | 32,721,198,832 | 18,406,799,443 |

* Report Coal Commission, vol. i., p. 31.

It is only necessary to add, that the tonnage estimates are made on the assumption that each cubic foot of coal weighs 80 lbs., which equals within a fraction a yield of 1,536 tons per foot thick per statute acre, and that the depths considered in the estimates of coal yet available for consumption, are 3,000 feet, and in the case of the Midland deep coal, from 3,000 feet to a depth not exceeding 4,500 feet.

Following the consumption of coal during the ten years ending 1879, some interesting results appear regarding the production of the Midland coal-field during the decade; the total output increasing from 17,824,241 tons in the year 1870, to 27,723,861 tons in the year 1879.

That an estimate may be arrived at of the probable exhaustion of the coal area embracing Yorkshire, Derbyshire, and Nottinghamshire, the resources of which are given above, the annexed statement, showing the annual production in each area of the coal-field during the past ten years, will afford the necessary data for the computation :—

| Year. | MIDLAND COAL AREA. | | | |
|-------|--------------------|-------------|------------------|-------------|
| | Yorkshire. | Derbyshire. | Nottinghamshire. | Total. |
| | Tons. | Tons. | Tons. | Tons. |
| 1870 | 10,606,604 | 5,102,265 | 2,115,372 | 17,824,241 |
| 1871 | 12,801,260 | 5,360,000 | 2,469,400 | 20,630,660 |
| 1872 | 14,576,009 | *5,700,000 | *2,650,000 | 22,926,000 |
| 1873 | 15,311,778 | *6,250,000 | *2,800,000 | 24,361,778 |
| 1874 | 14,812,615 | 7,150,570 | 3,127,750 | 25,090,835 |
| 1875 | 15,425,278 | 7,091,325 | 3,250,000 | 25,766,603 |
| 1876 | 15,055,275 | 7,025,350 | 3,415,100 | 25,495,725 |
| 1877 | 15,592,400 | 6,975,550 | 3,895,750 | 26,463,700 |
| 1878 | 15,581,970 | 7,190,000 | 4,107,350 | 26,879,320 |
| 1879 | 16,024,249 | 7,450,370 | 4,249,242 | 27,723,861 |
| Total | 145,787,329 | 65,295,430 | 32,079,964 | 243,162,723 |

Glancing at the total production of this great coal-field in the ten years ending 1879, amounting to 243,162,723 tons, the relative proportion of output appears as follows :—Yorkshire, 60 per cent.; Derbyshire, 27 per cent., and Nottinghamshire, 13 per cent.; while as regards the output in 1879 compared with 1870 an

* Estimated production.

increase appears equivalent to 55 per cent. Notwithstanding the resources of this coal-field it is quite clear they are being rapidly utilized. For example, at the rate of production in 1870 (17,824,241 tons), supplies would be available for 1,033 years. Deducting the production of the past ten years from the original estimate, there yet remain 18,163,636,720 tons for future supplies, to depths exceeding 4,000 feet after making the necessary deductions.

| MIDLAND COAL FIELD. | | TONS. |
|--|--|-----------------------|
| Original quantity available | | 18,406,799,443 |
| Ten years' produce ending 1879 | | 243,162,723 |
| Total available 1880 | | <u>18,163,636,720</u> |

Arguing from these data, and taking the production of 1879 as a basis (27,723,861 tons), the resources would be exhausted in 655 years hence; taking the average of the past ten years, (24,816,272 tons), 747 years would be the limit. The total exhaustion may, however, be expected at a much earlier period, seeing that the production during the past decade has increased to the extent of 55 per cent.

H. M. Inspector's returns for 1880 give the production of this great coal-field as follows :—

| | TONS. |
|---------------------------|-------------------|
| Yorkshire | 17,468,536 |
| Derbyshire | 7,903,834 |
| Nottinghamshire | 4,432,393 |
| Total | <u>29,804,763</u> |

Showing an increase over the previous year of 2,080,902 tons, and giving 609 years hence as the period of the exhaustion of this coal area.

CHAPTER III.

CUMBERLAND AND WESTMORELAND COAL-FIELDS.

Description of Cumberland Coal-field—Strata and Coal Seams in Whitehaven and Workington Districts—Analysis of Coal—Prices, Production, and Distribution by Railway, Coastwise and Exported—Population employed in Coal Mining—Resources and Probable Duration of Coal-field—Westmoreland Coal-field—Population Employed and Coal Raised.

The Cumberland Coal-field.—The total length of this coal-field is twenty miles, and its greatest width, which occurs at Workington, nearly five miles. The coal measures in this area attain a thickness exceeding 2,000 feet, the middle division containing seven and the lower four workable seams of coal, those latter being thin and inferior.

Many of the seams in the middle measures are of considerable thickness and regularity; these seams will be recognised in the accompanying section of strata at Whitehaven.*

| | THICKNESS. |
|-------------------------------------|------------|
| | Feet. |
| Strata | 432 |
| Yard band | 3 |
| Strata | 30 |
| Coal | 2½ |
| Strata (with a coal seam) | 78 |
| Bannock Band | 8 to 9 |
| Strata | 60 |
| Main Band | 6 to 11 |
| Strata | 240 |
| Low Bottom Coal | 4 |

Again, in the Workington district the following seams are met with :—

| | THICKNESS. | | | |
|--------------------------------|------------|------|-----|-----|
| | Ft. | In. | Ft. | In. |
| Fiery Band | | | 2 | 0 |
| Brassy Band | | | 2 | 3 |
| Cannel or Metal Band | 4 | 0 to | 6 | 0 |
| Bannock Band | | | 5 | 6 |
| Lower Main Band | 3 | 0 to | 4 | 0 |
| Main Band | 9 | 0 „ | 10 | 0 |
| Yard Coal | 2 | 0 „ | 3 | 0 |
| Four Foot Coal | | | 4 | 0 |
| Udale Band | 3 | 0 to | 4 | 0 |

The total thickness of workable coal in Cumberland is estimated to amount to 85 feet.

* "Coal Fields of Great Britain," 4th ed., p. 227.

Mining operations are carried out on an extensive scale in the Whitehaven district, where the colliery workings extend from two to three miles under the sea. At Workington also, the coal seams have long been wrought under the sea; and Mr. M. Dunn,* describing the dangers attending these undersea operations from inundation, gives an account of a sad calamity which occurred in this district in July, 1887, when 36 men and boys, and as many horses, together with all the extensive stock under ground, were irrecoverably destroyed from this cause, the waters having filled up the whole of the extensive workings to the level of the sea in a few short hours.

The scene of the accident was the Workington Colliery, where the pits "Lady" and "Isabella" were sunk and the coal worked to the distance of 1,500 yards under the Irish Sea, in a 10 feet seam which was 90 fathoms deep, both pits being situated close upon the sea shore. The workings were driven considerably to the rise, at the rate of one in three, which brought them within 15 fathoms of the bottom of the sea; operations appear to have been carried out in a very unguarded manner, the seams were worked up too far towards the bed of the sea which gave way, flooding the colliery and leading to the disastrous results above noticed.

Analysis of Coal.—In the following appears a chemical analysis and practical assay of an average sample of Cannel coal, from a seam about five inches thick, worked in the Dovenby Colliery, Dearham, Maryport; and made by Dr. William Wallace, Gas examiner for the City of Glasgow.

ANALYSIS.

| | | | | | | |
|--|---|----------------------|-------|---|-------|-------------------|
| Volatile matters | { | Gas, Tar, &c. | 52·65 | } | . . . | 54·47 |
| | | Sulphur | ·86 | | | |
| | | Water, at 212° Fahr. | 1·16 | | | |
| | | Fixed Carbon | 26·25 | | | |
| Coke . . . | { | Sulphur | ·92 | } | . . . | 45·53 |
| | | Ash | 18·36 | | | |
| | | | | | | |
| | | | | | | <u>100·00</u> |
| | | | | | | <u> </u> |
| | | | | | | Cwts. Qrs. Lbs. |
| Coke (dry) per ton of coal 1010 lbs., or | | | | | | 9 0 2 |

ANALYSIS OF THE COKE (DRY).

| | |
|--|-------|
| Carbonaceous or combustible matter | 57·65 |
| Sulphur | 2·02 |
| Ash | 40·33 |
| <u>100·00</u> | |

* "Winning and Working of Coal Mines, 1848," p. 230.

| | |
|--|-------|
| Specific gravity of the coal | 1.271 |
| Weight of a cubic foot in pounds | 79 |

PRACTICAL RESULTS.

| | |
|--|--------------------|
| Gas, per ton of Coal, at 60° Fahr., and 30 inches barometer | 10,765 cubic feet. |
| Illuminating power, in standard sperm candles, by union jet consuming 5 cubic feet per hour at 5 inch pressure | 40.48 candles |
| Value of one cubic foot of gas, in grains of sperm | 971 |
| Equivalent of a ton of coal in pounds of sperm candles | 1493 |
| Durability of one cubic foot of gas, by 5 inch flame | 83 minutes |
| Gravity of the gas, air = 1000 | 660 |

REMARKS.

The gas from this coal is equal in quality to that made from the celebrated Boghead Cannel, and is too rich for illuminating purposes. It is, however, very valuable for mixing with gas made from ordinary soft coal or inferior cannels.

Prices of Coal.—A few general notes will show the average prices of house coal at the pit's mouth in Cumberland. In the year 1851 the average price per ton was 4*s.* 6*d.*, increased in 1856 to 6*s.*, prices gradually decreasing till, in 1859, the quotations for house coal were 5*s.* 8*d.*, in 1864 the average was 6*s.* 10*d.*, and in 1866, 8*s.*, varying in 1868 from 6*s.* to 6*s.* 6*d.* per ton. In 1870 we learn from the Coal Commission report* that the following were the average prices of coals at the collieries named (best coals):—

| COLLIERIES. | <i>s.</i> | <i>d.</i> |
|----------------------------|-----------|-----------|
| Broughton Moor | 8 | 4 |
| Flimby Best Coal | 5 | 9 |
| Frizzington | 7 | 6 |
| Gillhead | 6 | 8 |
| Harrington | 10 | 0 |
| Threapthwaite | 9 | 2 |

The prices of slack varying from 2*s.* 6*d.* to 3*s.* 4*d.* and 5*s.* per ton, according to quality. In the years 1878, 1879 and 1880 the average prices of coal and slack per ton were as follows:—

| Year. | COAL. | | | SLACK. | | |
|-------|----------------------------|------------------------------|----------------------------|----------------------------|----------------------------|----------------------------|
| | Average. | Highest. | Lowest. | Average. | Highest. | Lowest. |
| 1878 | <i>s.</i> <i>d.</i> 8 6 | <i>s.</i> <i>d.</i> 10 10 | <i>s.</i> <i>d.</i> 7 6 | <i>s.</i> <i>d.</i> 3 6 | <i>s.</i> <i>d.</i> 5 0 | <i>s.</i> <i>d.</i> 2 1 |
| 1879 | 8 0 | 10 0 | 6 6 | 4 0 | 5 11 | 3 0 |
| 1880 | 9 0 | +20 0 | 7 6 | 4 3 | 5 1 | 3 6 |

* Vol. iii., "Statistics," Appendix, p. 212.

† Cannel coal.

Production of Coal in Cumberland.—From the report of the Royal Coal Commission many important facts are gleaned bearing on the early history of the coal trade of Cumberland; it is there stated that in the year 1582 the Earl of Lincoln, being Lord High Admiral, caused an account of the ships and mariners of Cumberland to be taken. The vessels amounted to twelve, not one of them being of 80 tons burden; mariners and fishermen, 198.* The insignificant condition of the ports of Cumberland, even so late as the middle of the last century, is shown by the facts that in the year 1752 Maryport consisted of only one farmhouse, and in that year a second house was built.

Coal was first worked at Whitehaven by Sir John Lowther, in the year 1660, and it further appears from Lyson † that steam-engine fuel was used in the year 1787, in which year Whingill and Howgill collieries produced 112,500 tons of coal. But little information is met with giving the output of the Cumberland collieries at an early period; on the other hand the Custom-house returns show the quantities of coal exported from the several ports of Cumberland between the years 1781 and 1792.‡ The great bulk of the coal exported at this period was sent to Ireland, the duty chargeable being 1s. 2d. per ton, while the coal exported to foreign countries was fixed at 5s. per ton.

| Year. | Whitehaven. | Workington, Maryport, and Harrington. |
|-------|-------------|--|
| | Tons. | Tons. |
| 1781 | 119,540 | 118,525 |
| 1782 | 123,393 | 118,164 |
| 1783 | 131,442 | 125,526 |
| 1784 | 128,312 | 136,336 |
| 1785 | 156,279 | 151,738 |
| 1786 | 188,082 | 142,622 |
| 1787 | 109,181 | 164,828 |
| 1788 | 193,633 | 162,228 |
| 1789 | 162,611 | 160,046 |
| 1790 | 144,947 | 152,819 |
| 1791 | 117,401 | 179,645 |
| 1792 | 125,840 | 169,291 |

The average exports of coal from the Whitehaven Collieries about the year 1814 did not exceed 225,000 tons per annum, to

* A General View of the Agriculture of Cumberland.

† Lyson's "Magna Britannia," p. cxxi.

‡ "History and Antiquities of Cumberland," by Wm. Hutchinson. Carlisle. 1794.

which adding the coal of the inland collieries estimated at 15,000 wagon loads of two and-a-half tons each, or 83,750 tons, the total production at this period may be set down at 258,750 tons.

Forty years later it appears that the total output of the Cumberland collieries amounted to 887,000 tons, of which 580,241 tons were shipped from the ports of Cumberland, the prices per ton being quoted at 8s. 5d. shipped and forwarded by rail; and 8s. 4d. for household purposes; the quantity shipped in the previous year amounted to 555,216.

In 1854 and since, the following gives the number of collieries and the annual output of coal :—

| Year. | Number of Collieries. | Coal. | Year. | Number of Collieries. | Coal. |
|-------|-----------------------|-----------|-------|-----------------------|-----------|
| | | Tons. | | | Tons. |
| 1854 | 23 | 887,000 | 1867 | 25 | 1,512,514 |
| 1855 | 23 | 809,546 | 1868 | 27 | 1,378,026 |
| 1856 | 28 | 913,981 | 1869 | 26 | 1,410,808 |
| 1857 | 28 | 942,018 | 1870 | 27 | 1,408,235 |
| 1858 | 28 | 920,137 | 1871 | 27 | 1,423,661 |
| 1859 | 28 | 1,041,890 | 1873 | 37 | 1,747,064 |
| 1860 | 28 | 1,171,052 | 1874 | 34 | 1,102,267 |
| 1861 | 28 | 1,255,644 | 1875 | 36 | 1,226,737 |
| 1862 | 28 | 1,330,287 | 1876 | 37 | 1,399,603 |
| 1863 | 32 | 1,327,368 | 1877 | 35 | 1,515,783 |
| 1864 | 30 | 1,380,795 | 1878 | 31 | 1,392,773 |
| 1865 | 30 | 1,431,047 | 1879 | 33 | 1,459,170 |
| 1866 | 30 | 1,490,481 | 1880 | 27 | 1,680,841 |

Distribution of Coal.—Commencing with the year 1867, and until the year 1871, we have the following statement showing the distribution of the coal produced in Cumberland in each of those years, the coal sent coastwise being chiefly shipped to Irish ports where it is largely employed for household purposes :—

| Year. | Exported. | Coastwise. | Ironworks. | Domestic. |
|-------|-----------|------------|------------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| 1867 | 782,723 | 5,591 | 478,500 | 245,700 |
| 1868 | 10,664 | 675,632 | 459,730 | 250,000 |
| 1869 | 8,964 | 670,584 | 453,150 | 278,110 |
| 1870 | 7,689 | 670,421 | 450,125 | 280,000 |
| 1871 | 3,739 | 599,922 | 525,000 | 295,000 |

A few details will generally indicate the movements of coal ;

for example, the London and North-Western Railway, the Furness Railways, and the Maryport and Carlisle Railway, carried of Cumberland coal the following quantities in each of the years named :—

| Year. | London and North-Western Railway. | Furness Railway. | Maryport and Carlisle. |
|-------|-----------------------------------|------------------|------------------------|
| | Tons. | Tons. | Tons. |
| 1868 | 389,487 | 48,258 | ... |
| 1870 | 345,046 | 43,930 | ... |
| 1871 | 348,668 | 45,614 | ... |
| 1872 | 384,071 | 43,646 | 184,450 |
| 1873 | 348,404 | 50,982 | 282,787 |
| 1874 | 266,866 | 54,787 | 245,671 |
| 1875 | 268,737 | 48,541 | 222,766 |
| 1876 | 318,383 | 51,476 | 291,235 |
| 1877 | 361,276 | 47,303 | 268,978 |
| 1878 | 374,282 | 33,908 | 282,242 |
| 1879 | 354,664 | 54,808 | 305,460 |
| 1880 | 371,755 | 36,965 | 274,602 |

Following the railway distribution since the year 1872 the annexed table shows the quantity shipped from the respective ports of Cumberland, coastwise and to foreign countries, the latter being inconsiderable.

| Year. | COASTWISE. | | | FOREIGN. |
|-------|-------------|-------------|-----------|----------|
| | Workington. | Whitehaven. | Maryport. | Total. |
| | Tons. | Tons. | Tons. | Tons. |
| 1872 | 53,787 | 121,823 | 154,815 | 3,288 |
| 1873 | 35,324 | 89,033 | 240,104 | 490 |
| 1874 | 20,774 | 100,245 | 236,205 | 2,719 |
| 1875 | 28,637 | 128,590 | 234,293 | 2,402 |
| 1876 | 47,038 | 130,290 | 276,784 | 5,516 |
| 1877 | 47,318 | 133,281 | 294,957 | 6,128 |
| 1878 | 56,334 | 129,540 | 282,607 | 6,837 |
| 1879 | 53,718 | 217,245 | 292,526 | 3,500 |
| 1880 | 52,980 | 198,761 | 242,176 | 1,569 |

Since the year 1876, Carlisle (Silloth) has shipped coal coastwise. These quantities added to the above, increase the total shipments coastwise which appear as follows since 1876 :—

| Year. | Carlisle. | Total Shipments. |
|-------|-----------|------------------|
| | Tons. | Tons. |
| 1876 | 45,791 | 499,993 |
| 1877 | 31,994 | 507,550 |
| 1878 | 28,518 | 495,999 |
| 1879 | 21,170 | 584,559 |
| 1880 | 20,088 | 514,035 |

Of the production of Cumberland in the years 1874, 1879, and 1880, the annexed table shows the distribution of coal.

| How Distributed. | 1874. | 1879. | 1880. |
|---|-----------|-----------|------------|
| | Tons. | Tons. | Tons. |
| Coastwise | 357,224 | 584,559 | 514,035 |
| Exported | 2,719 | 3,500 | 3,858 |
| London and North-Western } Railway | 266,866 | 354,664 | 371,755 |
| Maryport and Carlisle Railway | 245,671 | 101,061 | 99,465 |
| Furness Railway | 54,787 | 54,808 | 36,965 |
| Collieries, ironworks, and } local consumption | 175,000 | 365,275 | 654,763* |
| Total | 1,102,267 | 1,463,867 | 1,680,841† |

Population employed in Coal-mining.—The number of persons thus employed in the year 1854 above and below ground in Cumberland was 3,948, of whom 3,579 were engaged in coal mines and 369 in ironstone mines. Previous to the year 1874, the persons employed in coal-mining operations in Cumberland are included in the returns of Durham and Northumberland. Since that date they are separately distinguished and are as follows; side by side appear the coal raised each year, and, for comparison, the quantities raised per man :—

| Year. | Under Ground. | Above Ground. | Total Persons. | Coal Raised. | Average per Man. |
|-------|---------------|---------------|----------------|--------------|------------------|
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 4,251 | 1,427 | 5,678 | 1,036,274 | 183 |
| 1875 | 4,763 | 1,745 | 6,508 | 1,171,341 | 180 |
| 1876 | 4,401 | 1,623 | 6,024 | 1,392,046 | 231 |
| 1877 | 4,381 | 1,440 | 5,821 | 1,447,223 | 248 |
| 1878 | 4,253 | 1,525 | 5,778 | 1,393,514 | 241 |
| 1879 | 4,281 | 1,528 | 5,809 | 1,525,039 | 262 |
| 1880 | 4,407 | 1,537 | 5,944 | 1,680,841 | 283 |

* Estimated quantity.

† According to Returns of H.M. Inspectors, 1880.

The respective ages of those engaged under and above ground in 1879 are thus distinguished :—

CUMBERLAND.

| Male Persons. | Under Ground. | Above Ground. | Total. |
|---------------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| From 12 to 13 . . . | 18 | ... | 18 |
| „ 10 to 13 . . . | ... | 1 | 1 |
| „ 13 to 16 . . . | 292 | 85* | 377 |
| Above 16 . . . | 3,971 | 1,442† | 5,413 |
| Total . . . | 4,281 | 1,528 | 5,809 |

The average tonnage of coal raised per man during the above seven years showing an increase of 100 tons—equal to 55 per cent.

Resources of Cumberland Coal-field and Probable Duration.—

The quantity of coal remaining unworked in the Cumberland coal-field, according to the Report of the Royal Coal Commission, amounts to 405,203,792 tons thus summarised :—‡

THICKNESS OF SEAMS.

YIELD OF COAL ESTIMATED.
Tons.

| | |
|---------------------------------------|------------|
| From 12 in. to 18 in. thick | 8,403,414 |
| „ 18 „ 24 „ | 25,579,019 |
| „ 24 „ 30 „ | 18,105,665 |
| „ 30 „ 36 „ | 52,793,908 |
| „ 36 „ 42 „ | 9,308,974 |
| „ 42 „ 48 „ | 6,770,890 |
| „ 48 „ 54 „ | 21,591,388 |
| „ 54 „ 66 „ | 32,015,571 |
| „ 66 „ 72 „ | 30,786,747 |
| „ 72 „ 84 „ | 43,989,529 |
| „ 84 „ 112 „ | 54,482,687 |

Total tons of coal to be worked from the Cumberland Coal Field as per returns made from the collieries } 303,827,792

Under Sea Coal.—It is estimated that for a distance of eight miles, two workable seams of coal will be found under the sea, making in the aggregate 11 feet of coal over an area of 16 square miles; taking the extent to be worked seaward 2 miles = 10,240 acres × 11 feet, and allowing 40 per cent. to be left = } 101,376,000

Total 405,203,792

* Including 7 females.

† Including 329 females.

‡ Coal Commission Report, vol. I., p. 21.

This quantity, at the rate of production in the year 1870, viz., 1,408,285 tons, would afford supplies for 288 years. During the ten years ending 1879, the output of the collieries of Cumberland amounted to an aggregate of 14,080,029 tons, or an average annual output of 1,408,002 tons; leaving a total of 891,123,499 tons yet available for a period of 277 years. The output of the collieries of Cumberland in 1880 was 1,680,841 tons, showing an increase over the previous year of 155,802 tons, and reducing the period of duration to about 285 years.

Westmoreland Coal-field. Population Employed and Coal Raised.*—The coal produced in Westmoreland is inconsiderable, not exceeding 2,000 or 3,000 tons in any one year. In the year 1854 the total number of persons engaged in coal and iron mining was 109; of these 57 were engaged in coal, and 52 in iron mining. The returns of recent years, as under, show a considerable falling off. The details are as follows:—

| Year. | PERSONS EMPLOYED. | | Total. | Coal raised. | Average per man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under ground. | Above ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 20 | 3 | 23 | 1,972 | 86 |
| 1874 | 12 | 1 | 13 | 1,297 | 99 |
| 1875 | 18 | 1 | 19 | 2,566 | 135 |
| 1876 | 13 | 2 | 15 | 2,020 | 135 |
| 1877 | 13 | 2 | 15 | 2,051 | 136 |
| 1878 | 15 | 2 | 17 | 1,830 | 108 |
| 1879 | 17 | 2 | 19 | 2,026 | 106 |
| 1880 | 13 | 3 | 16 | 1,950 | 122 |

In the years 1877 and 1879 the number engaged in iron-mining was but ten in each year, of whom six were engaged in underground and four in overground operations; the quantities of iron-stone raised amounting to 8,000 tons and 1,454 tons respectively.

The coal raised according to the "Mineral Statistics" in the years 1878 and 1879 is in excess of that of the Inspectors, and is given respectively at 4,540 tons and 4,697 tons.

* Reports of H.M. Inspectors of Mines.

CHAPTER IV.

LANCASHIRE COAL-FIELD.

General Description of Coal-field—Principal Coal Seams Wigan and Burnley Districts—Analyses and Production of Coal—Deep Pits at Rosebridge Collieries, Wigan, and Ashton Moss, near Manchester—Pemberton Colliery, General Arrangements—Coal Washing Apparatus—Distribution of Coal—Bridgewater Navigation—Sent Coastwise and Exported—Population employed in Coal Mining—Price of Coal and Cost of Production—Resources of Coal-field, and probable duration.

The Lancashire Coal-field.—This important coal-bearing tract, most irregular in outline and greatly disturbed by faults, has an estimated area of 217 square miles. The chief centres of activity are Prescott, Saint Helen's, Wigan, Bolton, Bury and Manchester, and the isolated tract of Burnley. The South Lancashire area of the coal-field, extending from Bickerstaffe to Staleybridge, is thirty-two miles in length, its average breadth being about six miles. The number of seams of workable coal, as also the character of the strata in which they occur, vary considerably in different parts of the area; thus in the neighbourhood of Saint Helen's the number of coal seams exceeding two feet are 13, compared with 17 in the Wigan and 18 in the Manchester district; a general thickening out of the coal measures taking place towards the N.N.E., the same coal seams being found further apart at Saint Helen's than at Prescott, and at Wigan than at Saint Helen's.

The coal measures are divided into Upper, Middle and Lower. The Upper form the Manchester coal-field, and include the Ardwick limestone series, containing numerous fish remains overlying the Bradford Four-foot coal. The Middle coal measures, with a section of 3,500 feet, containing all the important seams of coal, from the Worsley Four-foot coal to the Arley mine. The Lower or Ganister series, consisting of flags, shales and thin coals. The seams of the Middle coal measures vary from 3 to 9 feet in thickness, and most of them can be traced over the whole district under different names; for example, the "Little Delf" of Saint

Helen's is the Arley Mine of Wigan, the "Riley Mine" of Bolton, and the "Dogshaw Mine" of Bury. It is the lowest coal bed of the Middle series, and of great economic value.* The following are the more important seams wrought in the Wigan area of the coal-field, with their respective average thickness:—

| | Ft. | In. |
|---|-----|-----|
| Four-foot Coal of Red Bock Bridge | 4 | 0 |
| Ince Yard Coal | 3 | 0 |
| Ince Four-foot Coal | 3 | 7 |
| Ince Seven-foot Coal (with parting) | 7 | 0 |
| Furnace Mine (with parting) | 4 | 7 |
| Pemberton Five-foot Mine | 5 | 2 |
| Pemberton Four-foot Mine | 4 | 6 |
| Wigan Five-foot (inferior) | 4 | 6 |
| Cannel Best Gas Coal from 1 to | 3 | 0 |
| King Coal | 3 | 10 |
| Yard Coal | 3 | 0 |
| Bone Coal | 2 | 3 |
| Smith Coal (Bushy Park) | 3 | 6 |
| Arley Mine | 4 | 0 |

The last-named seam being the next in value to the Cannel.

In the northern and eastern portions of the district and at Upholland, near Wigan, in the lower coal measures, two thin seams of coal are worked, the one known as the "Upper Mountain Mine" in the Oldham district, from 14 to 16 inches thick, and a second, the "Lower Mountain Mine," or "Ganister Coal," varying in thickness from 18 to 30 inches, the two seams separated by intervening strata, amounting to from 60 to 75 yards. The other districts of importance are the coal areas in the neighbourhood of Manchester and the Burnley coal-field; the former lies to the north-east of Manchester, four and a half miles in length, its greatest breadth not exceeding one and a half miles: the latter, small but rich coal basin of Burnley, lying further to the north of the main coal-field. In both these districts important and valuable seams of coal occur. The following gives generally those in the Burnley district, with their average thickness:—

| | Ft. | In. |
|--|-----|-----|
| Doghole Coal. | 6 | 0 |
| Kershaw Coal | 3 | 0 |
| Shell Coal | 2 | 6 |
| Main Coal | 5 | 0 |
| Maiden Coal | 3 | 0 |
| Lower Yard or Five-foot Coal | 5 | 0 |
| Lower Bottom or Four-foot Coal | 3 | 6 |

* Professor Hull's "Coal-fields," 4th ed., p. 200.

| | Ft. | In. |
|--|-----|-----|
| Impure Cannel | 2 | 6 |
| Thin Coal (and Fish Bed) | 2 | 9 |
| Great Mine { Coal, 28 in. } | 4 | 0 |
| { Shale, 12 ,, } | | |
| { Coal, 19 ,, } | | |
| China Bed | 2 | 0 |
| Danchy Bed | 2 | 0 |
| Fulledge Main Coal or Arley Mine | 4 | 0 |

Below the Fulledge Coal, in the lower coal measure, occurs the upper and lower Mountain Mines, the latter, "Ganister Coal," having a thickness of about four feet, the former being about two feet. Bands of ironstone occur in this district, and were formerly worked.

Analyses of Lancashire Coal.—The second Report of Coals suited to the Steam Navy affords very valuable information of the economical value of the Lancashire coal.*

Of the following well-known seams worked in the Wigan district, the annexed particulars are gathered :—

Balcarres Arley Mine.—Described "as a semi-bituminous coal, the vein at a depth of 212 yards from the surface being 5 feet 6 inches thick, and regular. The coal on examination was found to light easily and burn freely, but with the evolution of much smoke during the time of combustion. The amount of ash left was rather considerable, but the quantity of clinker formed was so small that at the expiration of eight hours from the time of lighting the fire the draughtways between the bars remained nearly as clear as before the commencement of the operation. The small quantity of clinker formed was very fusible, and adhered to the bars."

Balcarres Five-foot Mine.—This mine is also situated in the parish of Wigan. The vein is 5 feet 4 inches thick, and has been found to be regular as far as proved. This coal, like the former, was found to light readily, and blows off the steam rapidly, but gives a hard clinker, which adheres so firmly to the bars as to interfere materially with the maintenance of a clear fire. The coal gives off much smoke during combustion, and leaves a considerable amount of reddish ash.

The Balcarres Haigh Yard Mine.—The coal of this seam occurs at a depth of 98 yards from the surface, is 34½ inches in thickness, and very regular, and yields a free burning coal.

* De la Beche and Playfair, 1851.

The coal resembles in appearance the two last coals referred to, and was found during the experiments to burn in a nearly similar way, with the exception of its being consumed rather less rapidly and more steadily than the other specimens. The clinker was found to be small in quantity, but extremely fusible, and by melting on the bars obstructed the draught.

Blackley Hurst Four-foot Vein and Three-foot Vein.—The average thickness of the former is 8 feet 10½ inches, while the latter is usually an inch less than its name implies. The Four-foot Vein is mined at a depth of 60 yards, and the Three-foot Vein at a depth of 140 yards from surface. The coal is described as clean and durable, and has been largely used by the Scotch and Irish steam packets, and it further appears that a mixture of these two veins furnished a supply of fuel to the Halifax and Boston mail steamers for a considerable period. This coal has also been employed for the manufacture of gas, and it was observed during the experiments to be slightly bituminous and rather fragile, yielding much smoke and depositing a considerable amount of soot. Little ash and clinker were, however, left, the latter being of reddish colour and very hard. The following shows the mean composition of average samples of these coals : *—

| Constituents. | BALCARRES COLLIERY. | | | Blackley Hurst Four-foot Mine. |
|--------------------|-----------------------------|--------------------|---------------------|---|
| | Arley, five feet six in. | Five-foot Mine. | Haigh Yard Mine. | |
| Carbon | 83·54 | 74·21 | 82·26 | 82·01 |
| Hydrogen | 5·24 | 5·03 | 5·47 | 5·55 |
| Nitrogen | 0·98 | 0·77 | 1·25 | 1·68 |
| Sulphur | 1·05 | 2·09 | 1·48 | 1·43 |
| Oxygen | 5·87 | 8·69 | 5·64 | 5·28 |
| Ash | 3·32 | 9·21 | 3·90 | 4·05 |
| | 100·00 | 100·00 | 100·00 | 100·00 |
| Specific gravity . | 1·26 | 1·26 | 1·28 | 1·26 |
| Coke per cent. . . | 62·89 | 55·90 | 66·09 | 57·84 |

Other analyses of coal raised in the Wigan district show the

* Second Report, "Coals suited to the Steam Navy," by De la Beche and Playfair, p. 7.

following constituents, the samples examined being from seams in the Ince Hall Collieries, and employed for steam, domestic purposes and gas manufacture. The analysis in the last column is of the Cannel coal worked in the collieries at Walthen House, two miles from Wigan, of Messrs. W. H. Brancker & Co., and extensively used for gas-making, with the exception of small quantities used for household purposes. The principal market for this coal is Liverpool, distant 33 miles from the mine. The results of analyses are thus tabulated:—

| Constituents. | INCE HALL COLLIERIES. | | | Cannel Seam. |
|--------------------|-----------------------|----------------------|----------------------|--------------|
| | Arley Four-foot. | Pemberton Four-foot. | Pemberton Five-foot. | |
| Carbon | 82·61 | 77·01 | 68·72 | 79·23 |
| Hydrogen | 5·86 | 3·93 | 4·76 | 6·08 |
| Nitrogen | 1·76 | 1·40 | 2·20 | 1·18 |
| Sulphur | ·80 | 1·05 | 1·35 | 1·43 |
| Oxygen | 7·44 | 5·52 | 8·63 | 7·24 |
| Ash | 1·53 | 11·09 | 14·34 | 4·84 |
| | 100·00 | 100·00 | 100·00 | 100·00 |
| Specific gravity . | 1·272 | 1·276 | 1·269 | 1·23 |
| Coke per cent. . . | 64·00 | 57·10 | 56·50 | 60·33 |

The coals worked by the Moss Hall Company, whose collieries are situated near Wigan, have also been investigated. The following coals are thus described:—

The Pemberton Four-foot Coal, raised from the Moss Hall Colliery, being obtained from a depth of 208 yards from the surface, the vein exhibiting great regularity, and 4 feet 6 inches thick; the specimen examined being a bright coal, with a cubical fracture, free from iron pyrites, and containing but little shaly matter or mineralized charcoal.

The Pemberton Five-foot Coal is obtained from a colliery situated in the immediate neighbourhood of the preceding, and is described as “hard, burning moderately freely, and very hot.”

The New Main Coal, worked by the same Company at a depth of 110 yards, the vein, which is 4 feet 6 inches thick, being divided in the middle by four inches of metal. The coals from this vein are described as “moderately hard, free burning,

and producing a great heat." This, like the two previous varieties in the experiments made, was found to yield similar results. The annexed shows the mean composition of average samples of the coals referred to:—

| Constituents. | Pemberton Four-foot. | Pemberton Five-foot. | Pemberton New Mine. |
|--------------------|-------------------------|-------------------------|------------------------|
| Carbon . . . | 75.53 | 76.16 | 77.50 |
| Hydrogen . . . | 4.82 | 5.35 | 4.84 |
| Nitrogen . . . | 2.05 | 1.29 | .98 |
| Sulphur . . . | 3.04 | 1.05 | 1.36 |
| Oxygen . . . | 7.98 | 10.13 | 12.16 |
| Ash | 6.58 | 6.02 | 3.16 |
| | 100.00 | 100.00 | 100.00 |
| Specific gravity . | 1.258 | 1.283 | 1.278 |
| Coke per cent. . . | 55.70 | 56.10 | 57.70 |

The coal seams wrought in the Haydock Collieries of Messrs. Richard Evans & Co., situated in the parish of Ashton in Makerfield, near Warrington, and of which analyses are published, exhibit considerable variety, and are thus described:—

The Rushy Park Coals are obtained at a depth of 260 yards from the surface, the seam having a thickness of 4 feet 8 inches. These coals are employed for the generation of steam and other furnace purposes; the specimen examined was bright, with a cubical fracture, and contained rather large quantities of iron pyrites.

The Haydock Little Delf, extracted from the same colliery, at a depth of 320 feet from the surface; the vein is 3 feet 6 inches thick, the coal being chiefly employed for smith's use and coking; this coal closely resembles the foregoing, but is more bituminous, softer, and less bright, contains large quantities of white shale and mineralized charcoal, although but little iron pyrites was observed.

The Haydock Higher Florida Coals, obtained from the colliery of the same name, situated in the same parish as the two preceding mines, is obtained from a vein 4 feet 4 inches thick, at a depth of 250 yards from the surface. The coals are described as "clean, hot and durable," and are largely used by the ocean steamers from the Mersey and at the saltworks in

Cheshire. The coal is very brilliant, and has a cubical fracture, but contains considerable quantities of white shale and iron pyrites, particularly on the planes of cleavage, where a little brown coal and mineralized charcoal are also occasionally met with.

The Florida Main Seam.—These coals are extracted from the same colliery as the foregoing, and are raised from a vein about 10 yards below the higher seam. The roof is composed of fire-clay and shale, and the underlying strata consist of dark shale and grit-stone. The vein is 6 feet in thickness and is tolerably regular.

The composition of average samples of the Haydock seams is as follows:—

| Constituents. | Rushy Park. | Little Delf. | Higher Florida. | Florida Main Seam. |
|----------------------|-------------|--------------|-----------------|--------------------|
| Carbon | 77·65 | 77·91 | 77·33 | 77·49 |
| Hydrogen | 5·53 | 5·16 | 5·56 | 5·50 |
| Nitrogen | ·50 | ·54 | 1·01 | 1·27 |
| Sulphur | 1·73 | ·52 | 1·03 | 0·88 |
| Oxygen | 10·91 | 10·65 | 12·02 | 12·84 |
| Ash | 3·68 | 3·42 | 3·05 | 2·02 |
| | 100·00 | 98·20 | 100·00 | 100·00 |
| Specific gravity . . | 1·323 | 1·257 | 1·218 | 1·267 |
| Coke per cent. . . | 59·40 | 58·10 | 57·10 | 54·40 |

Another analysis of the Rushy Park Coal, described “as slightly caking; lustre of coke, semi-transparent;” showing the following composition:—

RESULTS TABULATED.

| | |
|--------------------|--------------------|
| Carbon | 75·81 |
| Hydrogen | 5·22 |
| Oxygen | 11·14 |
| Nitrogen | 1·93 |
| Sulphur | 0·90 |
| Ash | 5·00 |
| | <hr/> 100·00 <hr/> |

The specific gravity of this sample was 1·279, and the yield of coke per cent. 65·50.

Production of Coal.—The early history of coal-mining in Lancashire and the production of coal is very obscure. It is generally known, however, that towards the close of the past century the coal produced was not considerable, and further, that the construction of the Bridgewater Canal, bringing many of the great centres of industry into communication, greatly contributed to the development of the resources of the coal-field. The above great enterprise was commenced about the year 1759, and was designed and constructed by the celebrated engineer, James Brindley, connecting Worsley with Manchester, and furnishing an important outlet for the coal of that section of the Lancashire coal-fields. The canal was afterwards extended to Liverpool, and in 1762 an Act of Parliament was obtained to extend the canal to the tideway in the river Mersey. The Sankey Brook Canal was formed and opened a few years previously, between 1755 and 1759, connecting the coal-field of Saint Helen's with the river Mersey.

In the year 1854* appeared an interesting paper by Mr. J. Dickinson, H.M. Inspector of Mines, on the Lancashire, Cheshire and North Wales coal-field, in which it is stated regarding Lancashire, that the coal produced in 1852 amounted to 8,255,000 tons, from 384 collieries, the pits being of various depths, up to 520 yards.† Deeper coals were at that time worked by incline planes, from the bottom of shafts, to a depth from surface of 600 yards. The 384 collieries above referred to were worked by 679 pits, the average depth being about 118 yards.

These depths are now greatly exceeded. At Rosebridge Colliery in the Wigan district, coal is being won at a depth of 815 yards from the surface.‡ Recently, at the Ashton Moss Colliery, Auldenshaw, near Manchester, the "Great Mine," a seam of coal 6 feet thick, has been reached at a depth of 895 yards from the surface, or 897 yards including the seam itself. As far back as the year 1874, the Ashton Moss Colliery Company commenced sinking operations, with the view of finding the Four-foot Mine, which was being worked in other parts of the coal-field. At a depth of 450 yards the mine was proved,

* "Memoirs of the Literary and Philosophical Society of Manchester," vol. xii. p. 71.

† Two pits at the Pendleton Colliery (1852).

‡ August, 1880.

and several headings were driven by way of testing the bed, which, however, was found to be not of sufficient thickness to be workable. The proprietors now determined to sink a shaft 250 yards deeper, in all 700 yards. This depth, greater than that of the Astley Deep pit at Dukinfield (686 yards), in the adjoining county of Cheshire, having been reached, and not having overtaken any coal of a workable character, the engineers now directed that borings should be made; the results were encouraging, and orders were given to sink further, and on Saturday, 5th March, 1881, six years after the ground was first broken, the workers reached the "Great Mine" above referred to. This seam is believed to be a continuation, without any intervening fault, of the seams which are at present being worked on the east side of Manchester.

At a depth of 950 yards lies the "Roger Mine," 4 feet thick, and below this are supposed to exist several workable seams of coal, including the Black Mine and the Cannel Mine, both of which are got at Ashton. The coal is a house-fire coal, with coking properties, and is most valuable for position, being so near the large centres of population, available alike for quantity and excellence. The field that can be worked by the Company is about 2,000 acres in extent, from Guide Bridge to Droylsden on one side, and extending from Fairfield to Ashton on the other. A second shaft is now being sunk; being indeed but 200 yards short of the first shaft, and when working operations have fairly begun the mines are calculated to yield from 1,500 to 2,000 tons per day, and plant is being put down with that view. In the sinking operations the miners encountered no less than sixty seams or strata of coal, cannel, or shale, varying from 8 inches to more than 2 feet in thickness, but none until now of a workable character. The temperature, taken at a depth of 860 yards, was 78° Fahr. The "Great Mine," which has just been proved, has been worked from the outcrop to within a distance of 2,000 yards at the Lord's Field Colliery, and about 1,000 yards by the Dukinfield Coal and Cannel Company, "fair rise and dip." The first-named pit pierces the seam vertically at a depth of 130 yards, and the Chapel and Dewsnap Pits of the latter Company strike it at about 250 yards.

In comparison with other pits the Ashton Moss Pit is the deepest in England. The sinkings and borings have penetrated

to a depth of 1,050 yards; the sinkings alone have reached 895 yards, and this will soon be increased to 950 yards. Hitherto the Astley Deep Pit at Dukinfield (686 yards), the Rose Bridge Pit at Wigan, and the Moss Pit, situated in the same locality, extending to a depth of about 820 yards, were regarded as the deepest coal-pits in the kingdom.

Even these great depths are exceeded in the mining districts of continental countries; the deepest perpendicular shaft at present existing is that of Adalbert, at Prizbram, in Bohemia, which has reached the depth of 2,100 metres, or 1,096 yards, though there are others, not quite perpendicular, which are still deeper. The Rock-salt bore-hole, at Spesenberg, near Berlin, was carried down 4,175 feet some few years ago, and a coal-mine at Viviers, Belgium, is now 3,542 feet. Two other shafts in Belgium, at Gilly, are sunk to the depth of 2,847 feet, and from these an exploring shaft was carried 666 feet further, though it was unsuccessful as regards the finding of the expected seam.

The deepest shaft in Prussian mining is the Samson Shaft at the Oberhartz Lead and Silver Works in Hanover, which is 2,437 feet. France has nothing beyond 1,881 feet, at a colliery at Ronchamp. There is only one case on record where a depth exceeding one mile from the earth's surface has been reached; viz., at the Artesian well at Potsdam, Missouri, in the United States of America, where the chisels have been carried down to 5,500 feet, or 1 mile 220 feet.

Resuming with the returns of coal produce in Lancashire, in the following table will be found the number of collieries and output of coal in the North and East or Manchester district; and the Western district (Saint Helen's and Wigan), together with the total number of collieries and produce of coal, from which it will be seen, that since the year 1854 the output of the collieries of Lancashire have increased a hundredfold; and it may be generally observed, that during the year 1880 the coal trade of Lancashire was carried on under very unfavourable circumstances. In the beginning of the year colliery proprietors largely increased their output, due to the revival of trade which set in towards the close of the previous year. These hopes were not realised, and the increased production became a burden on the market. During the last two months of the year, however, a better demand arose for coal; this was met by increased output and better prices.

| Year. | NORTH AND EAST DISTRICT. | | WESTERN DISTRICT. | | TOTAL COAL. | |
|-------|--------------------------|--------------|--------------------|--------------|--------------------|-------------|
| | No. of Collieries. | Coal raised. | No. of Collieries. | Coal raised. | No. of Collieries. | Lancashire. |
| | | Tons. | | Tons. | | Tons. |
| 1854 | ... | ... | ... | ... | 340 | 9,080,500 |
| 1855 | ... | ... | ... | ... | 357 | 8,950,000 |
| 1856 | 248 | ... | 111 | ... | 359 | 8,950,000 |
| 1857 | 247 | ... | 112 | ... | 359 | 8,565,000 |
| 1858 | 273 | ... | 107 | ... | 380 | 8,050,000 |
| 1859 | 272 | 5,750,000 | 109 | 4,900,000 | 381 | 10,650,000 |
| 1860 | 266 | 5,750,000 | 105 | 5,600,000 | 371 | 11,350,000 |
| 1861 | 269 | 5,950,000 | 104 | 6,245,000 | 373 | 12,195,000 |
| 1862 | 272 | 4,975,500 | 107 | 5,622,000 | 379 | 10,597,500 |
| 1863 | 280 | 5,325,500 | 99 | 5,550,000 | 379 | 10,875,500 |
| 1864 | 276 | 5,900,000 | 103 | 5,630,000 | 379 | 11,530,000 |
| 1865 | 249 | 6,312,000 | 93 | 5,650,000 | 342 | 11,962,000 |
| 1866 | 251 | 6,570,000 | 95 | 5,750,500 | 346 | 12,320,500 |
| 1867 | 254 | 6,844,000 | 99 | 5,997,500 | 353 | 12,841,500 |
| 1868 | 293 | 7,053,000 | 93 | 5,747,500 | 386 | 12,800,500 |
| 1869 | 299 | 7,020,000 | 93 | 6,975,500 | 392 | 13,995,500 |
| 1870 | 298 | 7,055,500 | 87 | 6,755,100 | 385 | 13,810,600 |
| 1871 | 287 | 7,576,000 | 89 | 6,275,000 | 376 | 13,851,000 |
| 1872 | 324 | 9,363,236 | 98 | ... | 422 | 16,363,236 |
| 1873 | 325 | 9,500,000 | 160 | 7,500,000 | 485 | 17,000,000 |
| 1874 | 376 | 8,095,570 | 182 | 7,442,950 | 558 | 15,538,520 |
| 1875 | 400 | 8,825,798 | 188 | 8,250,246 | 588 | 17,076,044 |
| 1876 | 385 | 8,265,000 | 174 | 9,125,000 | 559 | 17,390,000 |
| 1877 | 342 | 8,735,055 | 175 | 8,886,476 | 517 | 17,621,531 |
| 1878 | 344 | 8,634,500 | 178 | 9,425,525 | 522 | 18,060,025 |
| 1879 | 362 | 9,020,045 | 179 | 9,591,700 | 541 | 18,612,345 |
| 1880 | 311 | 9,519,858 | 166 | 9,600,436 | 477 | 19,120,294 |

During the years 1879 and 1880, among the many extensive companies raising coal in Lancashire may be mentioned the Wigan Coal and Iron Co., who produce annually from their numerous collieries upwards of one and a half million of tons; the Messrs. Andrew Knowles and Sons, and the Bridgewater Trustees, each raising nearly one million tons.

The yield of Cannel coal is obtainable for a few years only, from 1857 to 1862, and was as follows; these quantities being included in the above totals for each of those years:—

CANNEL COAL PRODUCED IN LANCASHIRE.

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1857 | 300,000 | 1860 | 350,000 |
| 1858 | 275,000 | 1861 | 450,000 |
| 1859 | 295,000 | 1862 | 332,000 |

* Included in the return of North Wales, and estimated at 7,000,000 tons.

Before proceeding further this will be a fitting place to give an account of some of the mechanical arrangements employed in an extensive Lancashire colliery; that of "Pemberton" of Messrs. Blundell, affords an interesting illustration, and was visited in the autumn of 1879 by the members of the Iron and Steel Institute, in whose Journal the following account appears:—

"The Pemberton Colliery has two shafts, sunk to a depth of 624 yards,—a downcast and an upcast. The downcast is 17 feet 4 inches in diameter at the top and 16 feet at the bottom. The shafts were sunk by means of two pairs of horizontal engines, with cylinders 16 inches diameter and 3 feet stroke. Down each side of the shaft run pairs of railway metals, which form guides for the cages. The cages each hold six tubs, are made of steel, and weigh $28\frac{1}{2}$ cwts. The tubs also are made of steel, weigh $3\frac{1}{4}$ cwts., and carry about $7\frac{1}{4}$ cwt. of coal. The ropes are steel, and taper from $1\frac{1}{8}$ inch to $1\frac{1}{4}$ inch, and weigh about 3 tons. The heapsteads are well arranged and substantially built; one of iron, and the other of iron and stone combined. The screening arrangements are well planned. After the round coal has passed the ordinary screen, the remainder falls through an iron hopper into a long tube containing an 18-inch worm or creeper, along which the coal is carried into a well, whence it is mechanically lifted into the apparatus house, and passing through revolving screens, is discharged into waggons, in its various sizes.

"The coal-washing apparatus is of the ordinary kind, the washed coal being converted into coke on the premises. The engine-house is a fine building, containing two pairs of 36-inch cylinder horizontal winding engines, with 6-feet stroke. The winding drums are conical in form, with a maximum diameter of 30 feet 6 inches, and a minimum diameter of 19 feet, arranged for winding from the depth of 624 yards in 22 revolutions. The centre lines of the pulleys are on the flat part of the top of the drums, and consequently there is no chance of the rope slipping, while an additional protection is afforded by the coiling of the rope in a spiral groove. The pulleys are 18 feet in diameter. The boilers are 16 in number, each 28 feet long, and having two flues, each 2 feet 10 inches in diameter. A capstan engine is placed on the ground floor of the engine-house, which can be adapted to either shaft in case of emergency. For this purpose centre pulleys have been fixed in the head-gear.

The colliery is ventilated by a Guibal fan, constructed of steel, and measuring 46 feet in diameter and 15 feet in width. The length of the shaft is 19 feet 3 inches, and its diameter in the centre $16\frac{1}{2}$ inches, and at the pedestal end 12 inches. At the crank end the bearings are 18 inches long, and engines have been specially adapted to work the fan. There are two cylinders 36 inches in diameter, with a stroke of 3 feet 6 inches. One of the cylinders is sufficient to work the fan, but the other can be applied in a few minutes without interfering to any perceptible extent with the ventilation. The shaft is covered at the top with two doors, and the air enters the fan-house by means of a culvert. At the top of the drift, between the fan and the shaft, there is an escape chimney provided with four doors, so that in case of an explosion the blast would pass through these doors, and also through the door in the pit-scaffold, without injuring the fan.

"The fan is calculated to produce 247,000 cubic feet per minute at 53 revolutions and $3\frac{3}{4}$ -inch water-gauge. The fan-engine was constructed by Messrs. Baker and Valiant, of Wigan, and the fan by the Staveley Iron Company. At this colliery has been introduced a new system of working the coal by means of compressed air, invented by Mr. E. Reuss. In this system a circular hole is bored into the face of the coal for the reception of a cast-iron cartridge, which is connected with a powerful hand air-compressor. The cartridges are simply hollow castings, about 14 inches long and 3 inches in diameter, having one end solid and the other tapped to receive the tubing. The cartridge having been inserted in the coal, the air-compressor is started, and when the required pressure has been reached the cartridge bursts with a sharp report, bringing down the coal ready for loading."

Distribution of Coal. — Foremost amongst the railways in the movement of coal, the produce of Lancashire, is the London and North-Western, whose system traverses the coal-field in all directions. In the year 1854 this system carried from Lancashire 1,248,461 tons, increased in 1859 to 1,411,000 tons. Since 1859 the total weight of coal carried, distinguishing that passed on other lines from that carried on the North-Western system, will be seen in the subjoined table, amounting in the last-named year to 7,024,080 tons, of which 5,676,094 tons were conveyed to stations on the London and North-Western Railway, and 1,347,986 tons to stations on the lines of other companies.

| Years. | To Stations on London and North- Western Railway. | To Stations on other Companies' Lines. | Total. |
|--------|---|--|-----------|
| | Tons. | Tons. | Tons. |
| 1859 | ... | ... | 1,411,000 |
| 1862 | ... | ... | 1,641,391 |
| 1863 | ... | ... | 1,796,035 |
| 1864 | ... | ... | 2,557,087 |
| 1865 | ... | ... | 3,440,778 |
| 1866 | ... | ... | 3,321,737 |
| 1868 | 3,375,597 | 366,378 | 3,741,975 |
| 1869 | 3,790,482 | 420,598 | 4,211,080 |
| 1870 | 4,350,534 | 617,251 | 4,967,785 |
| 1871 | 4,612,476 | 824,574 | 5,437,050 |
| 1872 | 5,127,663 | 570,596 | 5,698,258 |
| 1873 | 4,618,324 | 796,739 | 5,415,063 |
| 1874 | 3,862,609 | 1,043,885 | 4,906,494 |
| 1875 | 4,604,432 | 1,230,726 | 5,835,158 |
| 1876 | 4,629,689 | 1,349,685 | 5,979,374 |
| 1877 | 4,812,141 | 1,332,143 | 6,144,284 |
| 1878 | 4,951,485 | 1,263,974 | 6,215,459 |
| 1879 | 5,464,701 | 1,421,252 | 6,885,953 |
| 1880 | 5,676,094 | 1,347,986 | 7,024,080 |

The Lancashire and Yorkshire Railway contributes largely to the movement of Lancashire coal; the quantity in 1869 was 2,261,511 tons, increasing yearly, as shown by the annexed statement:—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1869 | 2,261,511 | 1876 | 3,360,041 |
| 1872 | 2,874,637 | 1877 | 3,556,192 |
| 1873 | 2,781,805 | 1878 | 3,648,663 |
| 1874 | 2,859,742 | 1879 | 3,915,411 |
| 1875 | 3,285,434 | 1880 | 4,120,572 |

The Manchester, Sheffield and Lincolnshire Railway also carries coal from this coal-field, principally to Manchester, Ardwick, Gorton, Guide Bridge, Ashton, and Staleybridge; the quantities received and forwarded are as follows:—

| Year. | Received. | Forwarded. | Year. | Received. | Forwarded. |
|-------|-----------|------------|-------|-----------|------------|
| | Tons. | Tons. | | Tons. | Tons. |
| 1860 | 99,922 | 11,581 | 1865 | 63,152 | 1,285 |
| 1861 | 107,834 | 15,228 | 1866 | 80,428 | 3,594 |
| 1862 | 74,192 | 19,637 | 1867 | 39,870 | 6,938 |
| 1863 | 79,287 | 307 | 1868 | 24,659 | 2,708 |
| 1864 | 63,577 | 571 | 1869 | 18,191 | 1,590 |

The returns of later years appear in a different form and show the quantities carried by the same railway system from Ashton-under-Lyne and Wigan :—

| Year. | Wigan. | Ashton-under-Lyne. | Total. |
|-------|--------|--------------------|--------|
| | Tons. | Tons. | Tons. |
| 1870 | 1,672 | 12,255 | 13,927 |
| 1871 | 2,864 | 9,613 | 12,477 |
| 1872 | 15,357 | 13,783 | 29,140 |
| 1873 | 9,896 | 17,532 | 27,428 |
| 1874 | 10,173 | 12,487 | 22,504 |
| 1875 | 6,346 | 17,857 | 24,203 |
| 1876 | 32,122 | 20,453 | 52,575 |
| 1877 | 23,218 | 38,590 | 61,808 |
| 1878 | 21,262 | 24,667 | 45,929 |
| 1879 | 27,404 | 29,532 | 56,936 |
| 1880 | 23,066 | 32,842 | 55,908 |

Following the distribution of coal by canal in Lancashire, the first return met with of the coal traffic of the Bridgewater Navigation is for the year 1868,* when 501,514 tons were conveyed from the Worsley coal-field; 411,191 tons from the Wigan coal-field, and 5,507 tons from the Saint Helen's district; giving an aggregate carried of 918,212 tons. The importance of the Bridgewater Canals, and the great facilities they afforded at an early period for the conveyance of merchandise and minerals long before the introduction of railways, is thus referred to by a local historian, Aitkin :—"When the Duke of Bridgewater undertook this great design (the construction of the Bridgewater Canal), the price of carriage on the river navigation was 12*s.* the ton from Manchester to Liverpool, while that of land carriage was 40*s.* the ton. The Duke's charge on his canal was limited by Statute to 16*s.*, and together with this vast difference it had all the speed and regularity of land carriage. The articles conveyed by it were likewise much more numerous than those by river navigation. Besides manufactured goods and their raw materials, coals from the Duke's own pits were deposited in yards at various parts of the canal for the supply of Cheshire."†

The only other statement throwing light on the coal traffic

* Coal Commission Report, vol. iii., p. 81.

† Aitkin's "Description of the Country round Manchester," p. 116.

of the Bridgewater Navigation Company is for the years 1878, 1879, and 1880 when the quantities carried were as follows:—

| Districts. | 1878. | 1879. | 1880. |
|---|---------|---------|---------|
| | Tons. | Tons. | Tons. |
| Received from the Wigan District by the Leeds and Liverpool Canal | 313,000 | 260,000 | 315,000 |
| From Worsley and other Collieries | 507,000 | 498,000 | 512,000 |
| Total | 820,000 | 758,000 | 827,000 |

The Leeds and Liverpool Canal also carries large quantities of coal, for shipment in all directions from Lancashire and Yorkshire, amounting in 1878 to 1,150,000 tons, 1,186,000 tons in 1879, and 1,301,105 tons in 1880.

A writer in the *Colliery Guardian*,* referring to the small amount of coal shipments from Lancashire, remarks, “There are few coal-fields whose trade it is more difficult to give an account of than Lancashire. The fact that it is the busiest and most populous county in the United Kingdom no doubt accounts for the fact, that the consumption of coal is almost entirely local. There is no coal-field that exports less coal, nor is this surprising, for in previous years when the production was less than it is now, large quantities had to be imported. Now, however, the local supply has risen to the requirements. As to the chief sources of consumption they are almost too numerous to mention. Some of the largest ironworks in the kingdom are in Lancashire, but those do not rely on Lancashire coal. Hence the supply and demand are not so directly affected by the manufacture of crude iron as might at first sight appear. On the other hand, the textile industries of Lancashire are the largest in the kingdom, but cotton-mills do not consume much coal; and the years of greatest coal production have been those when the mills were least active. The general and domestic consumption, however, must be large:—within the radius of local consumption, nearly equal to that of the London district; and we know that the general and domestic consumption of

* “Ten Years of Coal Mining,” Lancashire. August 20, 1880, p. 291.

London is about nine millions—one-half of the total production of Lancashire. The population of Lancashire, however, is pre-eminently an industrial one, and it is not difficult to understand how her teeming industries can consume as much more coal as the general and domestic consumption. Nearly a million tons are shipped at Liverpool, but compared with other districts having access to the sea, its coal shipments are remarkably small.

The total shipments of coal, coastwise and to foreign countries, from Lancashire, in which the shipments from Cheshire are included, were as follows, in each year given :—

| Year. | Coastwise. | Exported. | Total. |
|-------|------------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| 1842 | 165,428 | 125,357 | 290,785 |
| 1845 | 165,018 | 125,852 | 290,870 |
| 1850 | 279,364 | 264,892 | 544,256 |
| 1860 | 358,654 | 604,168 | 962,822 |
| 1870 | 580,726 | 561,567 | 1,142,293 |
| 1875 | 582,989 | 717,104 | 1,240,093 |
| 1876 | 503,555 | 730,750 | 1,234,305 |
| 1877 | 512,596 | 721,560 | 1,234,156 |
| 1878 | 569,885 | 624,924 | 1,149,809 |
| 1879 | 669,481 | 563,693 | 1,233,174 |
| 1880 | 753,804 | 610,572 | 1,364,376 |

In the year 1879 the details of the coal shipments, coastwise and exported, were as follows, from Lancashire and Cheshire :—

| Ports. | Shipments Coastwise. | Shipments Foreign. | Total Shipments. |
|-----------------|-------------------------|-----------------------|---------------------|
| | Tons. | Tons. | Tons. |
| Chester . . . | 53,455 | 5,855 | 59,310 |
| Liverpool . . . | 459,504 | 549,742 | 1,009,246 |
| Runcorn . . . | 55,165 | 1,190 | 56,355 |
| Preston . . . | 16,348 | ... | 16,348 |
| Fleetwood . . . | 84,721 | 6,030 | 90,751 |
| Barrow . . . | ... | 626 | 626 |
| Lancaster . . . | 288 | 250 | 538 |
| Total . . . | 669,481 | 563,693 | 1,233,174 |

The great bulk of the above coal being despatched from Liverpool, the chief port of shipment, it will be interesting to follow the increase of shipments, coastwise and foreign, from that port. It must be borne in mind, however, that although the

great bulk of the coal is derived from the Lancashire coal-fields, that shipped at Birkenhead, included in the port of Liverpool, is derived from the Cheshire and North Wales coal-fields, while a small quantity is received from Yorkshire. The shipments are as follows from Liverpool:—

| Year. | Coastwise. | Foreign. | Total. |
|-------|------------|----------|-----------|
| | Tons. | Tons. | Tons. |
| 1842 | 56,218 | 117,718 | 173,936 |
| 1845 | 29,289 | 123,456 | 152,745 |
| 1847 | 15,390 | 106,197 | 111,587 |
| 1850 | 117,209 | 260,943 | 378,152 |
| 1852 | 105,932 | 277,645 | 383,577 |
| 1855 | 105,030 | 424,059 | 529,089 |
| 1858 | 166,952 | 474,713 | 641,665 |
| 1860 | 160,238 | 590,128 | 750,366 |
| 1865 | 130,566 | 616,976 | 747,542 |
| 1870 | 141,353 | 531,719 | 673,072 |
| 1871 | 377,209 | 688,085 | 1,065,294 |
| 1872 | 357,940 | 738,489 | 1,096,429 |
| 1873 | 388,520 | 591,368 | 979,888 |
| 1874 | 286,001 | 717,420 | 1,003,421 |
| 1875 | 334,502 | 704,496 | 1,038,998 |
| 1876 | 303,269 | 723,532 | 1,026,801 |
| 1877 | 296,731 | 715,594 | 1,012,325 |
| 1878 | 362,381 | 614,741 | 977,122 |
| 1879 | 459,504 | 549,742 | 1,009,246 |
| 1880 | 487,547 | 568,402 | 1,055,949 |

The total declared value of coal exported in 1880 from Liverpool to foreign countries was £319,313, giving an average value of 11s. 6d. per ton, compared with £608,196, the value of coal sent to foreign countries in 1872, giving an average of 16s. 6d. per ton.

Population Employed in Coal-Mining.—The total number of male persons employed in coal-mining in the year 1854 was 28,834 of all ages. The extensive collieries of Messrs. Andrew Knowles and Sons at this period were producing daily about two thousand four hundred tons of coal. It further appears that in Lancashire, in the same year, an ordinary collier in a Four-foot seam worked about four tons a-day. Each collier having an assistant, called a drawer, who trams the coal to the horse-road or the shaft, this reduces the get per collier to two tons per day, while the holidays usually accorded to underground workmen further reduced the average get per person to the amount above stated. In 1864, for the first time, H.M. Inspectors ascertained

the number of persons employed in and about the coal-mines of Great Britain, and in that year the number in North and East Lancashire, known as the Manchester district, was 23,525, the coal raised amounting to 5,998,875 tons. The Western division of Lancashire, including the Wigan and Saint Helen's districts, being grouped with North Wales, the separate numbers engaged are not distinguished before the year 1873.

The following are the numbers of persons employed in North and East Lancashire and North Wales between the years 1864 and 1872, with the quantities of coal raised in each year and the average produce per man :—

| Year. | Number Employed. | Coal Raised. | Average per Man. |
|-------|------------------|--------------|------------------|
| | | Tons. | Tons. |
| 1864 | 23,525 | 5,998,875 | 255 |
| 1865 | 23,525 | 6,312,000 | 268 |
| 1866 | 25,440 | 6,774,000 | 266 |
| 1867 | 26,820 | 6,844,000 | 255 |
| 1868 | 26,360 | 7,053,000 | 267 |
| 1869 | 26,190 | 7,020,000 | 268 |
| 1870 | 26,200 | 7,030,000 | 268 |
| 1871 | 26,110 | 7,575,800 | 290 |
| 1872 | 28,657 | 9,363,236 | 326 |

In the year 1873 "The Coal Mines Regulation Act" came into operation, and since that date very complete information is found in H.M. Inspectors of Coal Mines' Reports, distinguishing the number engaged underground and above ground and their respective ages. In the annexed table is given the numbers so employed in the North and East Lancashire district, with the output of coals * and average produce per man :—

| Year. | EMPLOYED. | | Total Employed. | Coal Raised. | Average per Man. |
|-------|---------------|---------------|-----------------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 26,429 | 5,453 | 31,882 | 8,063,855 | 253 |
| 1874 | 27,166 | 5,662 | 32,828 | 8,063,974 | 245 |
| 1875 | 27,305 | 5,701 | 33,006 | 8,881,137 | 263 |
| 1876 | 25,048 | 5,334 | 30,382 | 8,264,179 | 272 |
| 1877 | 24,154 | 5,190 | 29,344 | 8,741,387 | 298 |
| 1878 | 24,726 | 5,063 | 29,789 | 8,633,839 | 298 |
| 1879 | 25,495 | 5,262 | 30,757 | 8,993,697 | 292 |
| 1880 | 25,552 | 5,445 | 30,997 | 9,519,858 | 307 |

* H.M. Inspectors of Mines Reports.

The corresponding figures for the Western district, including Wigan and Saint Helen's, being as follows :—

| Year. | EMPLOYED. | | Total Employed. | Coal Raised. | Average per Man. |
|-------|---------------|---------------|-----------------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 22,753 | 6,571 | 29,324 | 7,818,112 | 266 |
| 1874 | 22,709 | 6,813 | 29,522 | 7,446,725 | 252 |
| 1875 | 24,314 | 7,224 | 31,538 | 9,048,914 | 287 |
| 1876 | 23,230 | 6,963 | 30,193 | 9,091,374 | 301 |
| 1877 | 22,812 | 6,734 | 29,546 | 8,952,425 | 303 |
| 1878 | 23,177 | 6,203 | 29,380 | 9,427,572 | 320 |
| 1879 | 23,288 | 6,028 | 29,316 | 9,562,170 | 325 |
| 1880 | 23,314 | 5,932 | 29,246 | 9,600,436 | 328 |

Summarising the two districts, the following shows the total number of persons working underground and above ground in the Lancashire coal-fields, with the coal raised and the average produce per man :—

| Year. | EMPLOYED. | | Total Employed. | Coal Raised. | Average per Man. |
|-------|---------------|---------------|-----------------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 49,182 | 12,024 | 61,206 | 15,881,967 | 260 |
| 1874 | 49,875 | 12,475 | 62,350 | 15,510,699 | 248 |
| 1875 | 51,619 | 12,925 | 64,544 | 17,930,051 | 277 |
| 1876 | 48,278 | 12,297 | 60,575 | 17,455,553 | 288 |
| 1877 | 56,966 | 11,924 | 58,890 | 17,693,812 | 291 |
| 1878 | 47,903 | 11,266 | 59,169 | 18,061,411 | 305 |
| 1879 | 48,783 | 11,290 | 60,073 | 18,555,867 | 309 |
| 1880 | 48,866 | 11,377 | 60,243 | 19,120,294 | 327 |

In 1870 the total coal produced in Lancashire was 13,810,600 tons, and in 1880 the returns show an increase of 5,309,694 tons, giving an increase of nearly 38 per cent. in a period of ten years; indeed, in no other coal-field has the production increased so rapidly. When in 1872 and 1873 the demand for coal became so considerable, many new shafts were sunk and old pits reopened to meet the requirements of the time, and when the temporary pressure was met the number of workings was reduced, prices having fallen, rendering the continuance of operations unproductive. Now, however, it appears that those collieries which continued at work during the years of depression are

producing coal in larger quantities than they did in previous years when prices were better than they at present are.

From the above figures it appears that the individual efficiency of the miner has greatly increased in Lancashire in recent years; the average output per man rising from 260 tons in 1873 to 327 tons in 1880, equivalent to an increase of 25 per cent.

The respective ages of all employed in coal-mining in Lancashire, as previously stated, amounted to 60,073 in the year 1879; the details appear in the annexed table:—

| All Ages. | Males and Females. | NORTH AND EAST. | | WEST. | | Total. |
|---------------|--------------------|-----------------|---------------|---------------|---------------|----------|
| | | Under Ground. | Above Ground. | Under Ground. | Above Ground. | |
| From 10 to 12 | Males | Nos. 191 | Nos. ... | Nos. ... | Nos. ... | Nos. 191 |
| „ 12 to 13 | „ | 485 | ... | 263 | ... | 748 |
| „ 10 to 13 | „ | ... | 118 | ... | 23 | 141 |
| „ 13 to 16 | „ | 2,302 | 291 | 1,817 | 366 | 4,776 |
| „ 13 to 16 | Females | ... | 9 | ... | 120 | 129 |
| Above 16 | Males | 22,517 | 4,616 | 21,208 | 4,269 | 52,610 |
| „ „ | Females | ... | 228 | ... | 1,250 | 1,478 |
| | Total | 25,495 | 5,262 | 23,288 | 6,028 | 60,073 |

Price of Coal and Cost of Production.—About the year 1860 the cost of getting coal on the average was estimated at 4s. 6d. per ton for ordinary coal, and 6s. 6d. for cannel coal, the former selling at bank at 6s. 3d. per ton, although a short time previously it did not exceed 5s. 6d. per ton. For many years prices did not exceed 6s. per ton for manufacturing coal; in 1871 and 1872 however the same variety rose to 20s. and even 25s. per ton, and even at this price manufacturers were greatly inconvenienced, being unable to secure a supply; indeed, it was not uncommon at the period referred to, to use the best house coal instead of ordinary steam coal for manufacturing purposes.

The following table shows generally the prices ruling in the Manchester district, at the pit's mouth, in the year 1870:—*

COLLIERIES.

Altham (coal), 6s.

Bank Hey (coal), 5s. 8d.

Birtle Dean (coal), 7s. 6d.

Brightmet (house coal), 7s. 6d.; (engine coal), 4s. 9d.

* Coal Commission Report, vol. iii., Appendix, p. 213, prices at the pit's mouth.

COLLIERIES.

Broadfield (coal), 5s. 9d., 8s., 12s. 6d.
 Combermere (coal), 4s. 6d.
 Great Lever (best coal), 10s. ; mixed, 8s. ; steam, 5s.
 Lower Moor (best coal), 10s. 6d. ; small, 6s.
 Redsham, 5s. to 8s. 4d.
 Stand Hill (coal), 5s. 3d.
 Wharton, best, 6s. 8d. ; riddled, 5s. 5d. ; burgie, 3s. 9d. ; slack, 2s. 6d.
 Tyldesly, 8s. 9d. summer ; 9s. 7d. winter.

In the Saint Helen's district prices averaged from 4s. 6d. to 5s. 6d. per ton. And in the Wigan district prices varied, best coals from 5s. 9d. to 7s. 6d. per ton ; common from 4s. 8d. to 5s. and slack from 2s. 4d. to 3s. per ton. From the evidence of Mr. Alfred Hewlett, the Managing Director of the Wigan Coal and Iron Company,* in whose collieries some 10,000 persons are employed, producing nearly 2,000,000 tons of coal per annum, some very important facts are gathered. In referring to the condition of the coal trade, he says,—“From 1867 to 1870 the coal trade of the district was in a very depressed state, large stocks were accumulating on the pit banks and on the wharves ; prices were very low. Competition for a market consequently ran high, and the pits were obliged to be put on very short time, in many cases half-time, owing to the absence of demand. An improvement sprung up towards the end of 1870, but still the standard of production of 1867 has not since been reached.” Again, referring to the price realised for coal since 1867, he observes :—“Taking 1867 as the datum, in 1868 the average price of coal was $6\frac{1}{2}$ per cent. less than in 1867 ; in 1869 it was $9\frac{1}{2}$ per cent. less than in 1867 ; in 1870 it was also $9\frac{1}{2}$ per cent. less ; in 1871 it was 8 per cent. less ; in 1872 it was 34 per cent. more than in 1867 ; and for the first quarter of 1873 it was $82\frac{1}{2}$ per cent. higher than in 1867 ; the above represent prices at the pit's mouth.”

About this time (April, 1873), the average earnings of the colliers, working from eight to eight and a half days in the fortnight, were :—in the Cannel Mine, one man earned 13s. 1d. ; another, 10s. 4d. ; another, 11s. 2½d. ; another, 15s. 0½d. ; another, 18s. 4½d. In another seam, at the same time, one man earned 9s. 3d. ; another, 13s. 4½d. ; another, 15s. ; another, 12s. 1d. ; another, 11s. 9d. The general effect of the operation of “The Coal Mines Regulation Act, 1872,” being to increase the cost of

* Select Committee on Coal Report, 1873, pp. 72—74.

production from 1s. 4d. to 1s. 8d. per ton, due to the restrictions as to employment of boys underground, the provision for weighing, and the decrease in the hours of labour.

In the years 1878, 1879, and 1880 the average, with the highest and lowest prices of coal and slack at the pit's mouth, was as under:—

| Year. | COAL. | | | SLACK. | | |
|-------|--------------|---------------|--------------|--------------|--------------|--------------|
| | Average. | Highest. | Lowest. | Average. | Highest. | Lowest. |
| 1878 | s. d. 9 0 | s. d. 13 0 | s. d. 7 0 | s. d. 5 0 | s. d. 6 8 | s. d. 3 0 |
| 1879 | 8 6 | 20* 0 | 6 0 | 4 4 | 5 10 | 2 0 |
| 1880 | 8 9 | 18* 9 | 6 8 | 4 6 | 5 6 | 2 6 |

In December, 1880, the best qualities of Lancashire house-coal were to be bought at from 8s. 6d. to 9s. 6d. per ton; seconds from 6s. 6d. to 7s.; common round coal, 5s. 6d. to 6s. 6d.; burgie, 4s. to 4s. 3d., and good slack, 4s. to 4s. 6d. per ton at the pit's mouth. Now, in March, 1881, best coal is quoted at 10s. to 10s. 6d.; seconds, 8s. to 8s. 6d.; common coal, 6s. 6d. to 7s.; burgie, 5s. to 5s. 10d., and slack, 4s. to 4s. 6d. per ton; these increased prices being due to the recent strike extending through the Lancashire coal-field, involving a complete stoppage of work on the part of, at least, 50,000 men and boys for nearly three weeks, including the colliers and day men employed about the pits. In the Manchester and Bolton districts, from 13,000 to 14,000 men ceased work, during the period of the strike extending over a period of nearly six weeks, and in the West Lancashire district, at one period 36,000 to 37,000 men were out during the period of the dispute, extending to nearly two months.

Resources of Coal-field and Probable Duration.—The total area of the Lancashire coal-field amounts to 5,862,390 statute-foot acres of coal wrought and unwrought, excluding all seams that are not of workable thickness. Of this acreage the portion already wrought amounts to 597,604 statute-foot acres, leaving 5,264,786 statute foot acres for future supplies. From this area, however, necessary deductions are made for faults, supports,

* Cannel Coal.

barriers, &c., leaving unwrought and likely to be clear for working, 3,883,372 statute-foot acres. In computing the available quantity of coal in this acreage (5,436 millions of tons), one-fourteenth has been allowed for unavoidable loss, waste in working, the actual estimated quantity of coal obtained from each foot-acre being taken at 1,400 tons of 2,240 lbs. each.

Taking the production of Lancashire (1870), when the output was 13,810,600 tons, sufficient coal remains from that date for a period of 393 years. The total production during the past ten years amounts to 165,313,301 tons; this, deducted from original estimate, leaves 5,270,686,699 tons; and taking 16,513,330 tons, the average output of the ten years, there would be sufficient to last for 317 years; while at the rate of consumption in 1879, when the production was 18,612,345 tons, the resources of the coal-field would be exhausted in 283 years, and as production will increase, at an earlier period.

From the reports of H.M. Inspectors of Mines for the year 1880, it appears the total production of the Lancashire coal-field exceeded that of any previous year, the output amounting to 19,120,294 tons; at this rate of production the exhaustion of the Lancashire coal deposits would take place about 275 years hence.

CHAPTER V.

CHESHIRE COAL-FIELD.

Description of Coal-field and Principal Seams—Analyses, Production, and Distribution of Coal—Population Employed in Coal Mining—Resources of Coal-field and probable Duration.

The Cheshire Coal-field.—This coal tract lying to the south of the River Mersey has its most northern part situated near Stockport, the central portion lies east of Poynton, and the southern termination of the coal-field is near Macclesfield. The annexed section shows the order of occurrence of the coal series in the neighbourhood of Bredbury, near Stockport, where the following seams have been worked at the Bredbury collieries.*

COAL-SERIES OF BREDBURY, CHESHIRE.

| | Ft. | In. |
|---|-----|-----|
| <i>Black Mine</i> (coal) | 4 | 0 |
| <i>Strata</i> | 24 | 0 |
| <i>Coal</i> | 0 | 10 |
| <i>Strata</i> | 27 | 0 |
| <i>Coal and Dirt</i> | 2 | 0 |
| <i>Strata</i> | 105 | 0 |
| <i>Stone Mine</i> { <i>Coal</i> 1 3 } | 3 | 3 |
| { <i>Stone</i> 1 0 } | | |
| { <i>Coal</i> 1 0 } | | |
| <i>Strata</i> | 45 | 0 |
| <i>Cannel Mine</i> (common coal here) | 1 | 4 |
| <i>Strata</i> | 96 | 0 |
| <i>Peacock or King William Coal</i> | 2 | 6 |
| <i>Strata</i> | 75 | 0 |
| <i>Coal</i> | 0 | 10 |
| <i>Strata</i> | 76 | 0 |
| <i>Coal</i> | 1 | 10 |
| <i>Strata</i> | 45 | 0 |
| <i>Silver Mine</i> (good coal) | 3 | 2 |

Below these occur the following coals not worked at Bredbury :—

| | | |
|---|------------------------|---|
| <i>Water Mine</i> { <i>Coal</i> 3 0 } | 5 | 0 |
| { <i>Shale</i> 1 0 } | | |
| { <i>Coal</i> 1 0 } | | |
| <i>Rosemary Mine</i> | } Thickness uncertain. | |
| <i>Upper Woodley Mine</i> | | |
| <i>Lower Woodley Mine</i> | | |

* "Explanation Horizontal Section of Sheet 65." Geol. Survey of Great Britain.

Professor Hull, referring to this coal-field, says it is bounded along the west by Triassic and Permian rocks, which are brought in along the line of the "Red Rock fault of Cheshire," and that several valuable seams of coal occur, including the "Mill Mine" $4\frac{1}{2}$ feet thick; the "Sheepwash Mine;" the "Great Mine;" the "Silver Mine;" the "New Mine;" and the "Redacre Mine," which represents the Arley or Royley Mine.*

Analysis of Cheshire Coal.—The character of the Cheshire coal will be understood from the results of the annexed analysis showing the composition of coke made from coal raised from the Dukinfield Colliery; the analysis is given by Dr. Percy in his Metallurgy, and was made by Mr. C. Tookey in the laboratory of the Royal School of Mines:—

| | |
|-------------------------------|----------------|
| Carbon | 85.84 |
| Hydrogen | 0.52 |
| Oxygen and Nitrogen | 1.38 |
| Sulphur | 0.86 |
| Ash | 11.40 |
| | <u>100.00†</u> |

Coke, Dr. Percy remarks, "consists essentially of carbon and the fixed inorganic matter of the coal from which it has been derived, but contains, also, hydrogen, nitrogen, and oxygen with sulphur in the state of sulphide of iron. Half the sulphur in the original coal, or thereabouts, is found in the coke made from it; the bisulphide of iron in the coal being converted into proto-sulphide by the burning off of one equivalent of the sulphur, and the production of sulphurous acid."

The Cannel coal, raised by the Dukinfield Coal and Cannel Company from their Dunkirk Colliery, where the seam averages 2 ft. 6 in. in thickness, has been examined by Mr. Robert J. Toothill, analytical chemist of Manchester, with the following results:—

TABULATED.

| | |
|---|-------------------------|
| Yield of gas per ton | 9962 cubic feet. |
| Temperature 60° Fahr. | — |
| Illuminating power | = 25.5 candles. |
| Coke (hot) | 13 cwts. 3 qrs. |
| Coke (slacked) ready for sale | 15 cwts. 3 qrs. 16 lbs. |
| Water | 15 gallons. |
| Specific gravity 4° | at 60° Fahr. |
| Tar | 15 gallons. |
| Specific gravity 28° | at 60° Fahr. |
| Coke | good. |

* "Geology of Stockport, &c." Mem. Geol. Survey, p. 29.

† "Percy's Metallurgy," Fuel, p. 417.

The Cannel nuts raised by the same company yielded per ton 9,700 cubic feet of purified gas, at a temperature of 60 degrs. Fahr. illuminating power = 18·5 candles.

Coke (hot) 13 cwts. 0 qrs. 12 lbs.
 Coke (slacked) ready for sale 16 cwts. 0 qrs. 24 lbs.
 Water, 9 galls. 1 qrt. Specific gravity $5\frac{1}{4}^{\circ}$ at 60° Fahr.
 Tar, 12 galls. 2 qrts. „ „ $26\frac{1}{4}^{\circ}$ at 60° Fahr.

The mine from which the above Dunkirk cannel, and cannel nuts, are obtained is termed the Cannel Mine. Its depth at the above company's Astley Deep Pit from the surface is 786 yards, it being fifty yards below the well-known Black Mine of the district to which the shafts of the company are sunk. It is got at by tunnels from the last-named mine.

Production and Distribution of Coal.—The Cheshire collieries, although yielding a notable quantity of coal, are not accredited with returns of production prior to the year 1854. It is probable that the returns of the Lancashire coal-field at an early period included the Cheshire coal. In the year above-named, 32 collieries in operation gave an output of 786,500 tons of coal, of which quantity the London and North-Western Railway carried 157,505 tons, to the great industrial centres of Manchester, Macclesfield, Stockport, &c. The output of the coal-field and the number of the collieries in recent years are as under :—

| Year. | Number of Collieries. | Coal Raised. | Year. | Number of Collieries. | Coal Raised. |
|-------|-----------------------|--------------|-------|-----------------------|--------------|
| | | Tons. | | | Tons. |
| 1855 | 32 | 755,500 | 1868 | 29* | 937,500 |
| 1856 | 32 | 754,327 | 1869 | 28* | 957,150 |
| 1857 | 31 | 750,500 | 1870 | 29 | 929,150 |
| 1858 | 35 | 695,450 | 1871 | 29 | 975,000 |
| 1859 | 35 | 700,000 | 1872 | 31 | † |
| 1860 | 35 | 750,500 | 1873 | 31 | 1,150,500 |
| 1861 | 39 | 765,570 | 1874 | 36 | 615,105 |
| 1862 | 39 | 787,750 | 1875 | 37 | 658,945 |
| 1863 | 39 | 822,750 | 1876 | 39 | 584,580 |
| 1864 | 38 | 821,700 | 1877 | 36 | 645,500 |
| 1865 | 39 | 850,000 | 1878 | 33 | 616,575 |
| 1866 | 38 | 893,000 | 1879 | 26 | 720,350 |
| 1867 | 39 | 935,000 | 1880 | 30 | 681,000‡ |

* Several small collieries chiefly near Macclesfield ceased to work in those years.

† Included in North Staffordshire. Production not less than 1,000,000 tons.

‡ Report H.M. Inspectors of Mines.

In Cheshire the chief of the great railway lines is the London and North-Western, passing by the south, to Stafford, Crewe and Warrington to the north. From Crewe branches pass to Stockport and Manchester on the east, and to Chester and Birkenhead on the west. At Crewe, it may be mentioned, is situated the great engine factory and steel works of the London and North-Western Railway, which line carried coals from Cheshire as follows in each of the years named:—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1854 | 157,595 | 1864 | 110,891 |
| 1855 | 100,000 | 1865 | 123,588 |
| 1859 | 160,000 | 1866 | 135,092 |
| 1860 | 150,000 | 1868 | 148,236 |

These quantities include coal carried by the company and passed over to other lines, which, in the returns of later years, are separately distinguished as under:—

| Year. | Stations on London and North-Western Line. | Stations on Other Lines. | Total Carried. |
|-------|--|--------------------------|----------------|
| | Tons. | Tons. | Tons. |
| 1869 | 121,202 | 2,964 | 123,896 |
| 1870 | 103,885 | 599 | 104,484 |
| 1871 | 140,452 | 773 | 141,225 |
| 1872 | 132,775 | 239 | 133,014 |
| 1873 | 100,354 | 7,226 | 107,580 |
| 1874 | 117,624 | 1,390 | 119,014 |
| 1875 | 135,304 | 619 | 135,923 |
| 1876 | 147,741 | 685 | 148,426 |
| 1877 | 157,080 | 271 | 157,351 |
| 1878 | 155,062 | 310 | 155,372 |
| 1879 | 168,761 | 338 | 169,099 |
| 1880 | 179,108 | 5,707 | 184,815 |

It is not an easy matter to determine the quantities of coal exported from this coal-field; much of it being shipped from ports on the Mersey, and this is included in the returns of the port of Liverpool. The shipments from the port of Chester to foreign parts show but little variation; but the shipments coastwise show a great diminution, which is explained by the large quantities carried by railway. The movements of coal,

coastwise, and to foreign countries, were as follows in each of the years named :—

| Year. | Coastwise. | Foreign. | Total. |
|-------|------------|----------|---------|
| | Tons. | Tons. | Tons. |
| 1851 | 101,044 | 949 | 101,993 |
| 1854 | 91,469 | 360 | 91,829 |
| 1857 | 73,850 | 107 | 73,957 |
| 1860 | 66,838 | 200 | 58,838 |
| 1863 | 61,866 | 1,431 | 63,297 |
| 1866 | 59,818 | 600 | 60,418 |
| 1869 | 73,813 | 2,797 | 73,610 |
| 1872 | 85,986 | 7,088 | 93,084 |
| 1873 | 109,023 | 10,679 | 119,702 |
| 1874 | 90,049 | 7,959 | 98,008 |
| 1875 | 96,842 | 8,823 | 105,665 |
| 1876 | 67,646 | 6,137 | 73,773 |
| 1877 | 83,512 | 4,822 | 88,334 |
| 1878 | 68,826 | 4,602 | 73,428 |
| 1879 | 53,455 | 5,855 | 64,310 |
| 1880 | 64,349 | 7,679 | 72,028 |

Population employed in Coal-mining in Cheshire.—In the year 1854, the number of persons engaged in coal-mining was 2,618, the coal raised amounting to 786,500 tons. Twenty years later the numbers were 2866, of whom 2,253 were engaged underground, and 613 above ground, the output of coal being 614,956 tons. Since the year 1874 the numbers employed and coal raised have been as under :—*

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 2,253 | 613 | 2,866 | 614,956 | 227 |
| 1875 | 2,059 | 685 | 2,744 | 688,865 | 251 |
| 1876 | 1,939 | 699 | 2,638 | 594,300 | 225 |
| 1877 | 1,814 | 587 | 2,401 | 629,000 | 261 |
| 1878 | 1,875 | 584 | 2,459 | 617,000 | 251 |
| 1879 | 1,835 | 549 | 2,384 | 723,200 | 303 |
| 1880 | 1,961 | 530 | 2,491 | 681,000 | 273 |

A comparison of the average output of each collier between the years 1874 and 1879 exhibits steady working, amounting to an increase of upwards of 30 per cent., the average per man

* Reports of H.M. Inspectors of Mines.

increasing from 227 to 303 tons; a falling off appears in 1880, the average per man not exceeding 273 tons. In the year 1879 the ages of those employed are thus distinguished:—

| All Ages. | Under Ground. | Above Ground. | Total. |
|-------------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| From 12 to 13 . . | 20 | ... | 20 |
| „ 10 to 13 . . | ... | 10 | 10 |
| „ 13 to 16 . . | 141 | 38 | 179 |
| Above 16 | 1,674 | 501 | 2,175 |
| Total | 1,835 | 549 | 2,384 |

Resources of Coal-field and Probable Duration.—The total area of the Cheshire coal-field,* wrought and unwrought, to a depth not exceeding 4,000 feet, amounts to 236,797 statute acres one foot thick. Of this area 232,029 acres occur at a depth not exceeding 3,000 feet; and 4,768 acres at a depth between 3,000 and 4,000 feet.

The portion already wrought of the above 236,797 statute-foot acres in 1870 was 40,000 acres, leaving at that date 196,797 acres for future use. From this area large deductions are made, for faults, supports, barriers, &c., amounting to 54,149 acres, leaving portion unwrought and likely to be clear for working, 142,648 acres of one foot in thickness, equivalent to 200,000,000 tons of coal.

In the above computation the Commissioner allows one-fourteenth for unavoidable loss and waste in working, or 1,400 tons per statute-foot acre.

Considering the production of this coal-field in 1870, amounting to 929,150 tons, supplies are yet available for 215 years from that date. During the ten years ending 1879 the total coal raised amounted to 7,895,705 tons; this deducted, leaves as under:—

| | TONS. |
|--|--------------------|
| Original estimate, 1870 | 200,000,000 |
| Deduct ten years ending 1879 | 7,895,705 |
| Total available | <u>192,104,295</u> |

A reference to the returns of production shows that from 1870 to 1873 the maximum was attained, amounting to 1,150,500 tons.

* Report Royal Coal Commissioners. Mr. Joseph Dickinson, vol. i., p. 18.

Since 1873 a falling off has taken place, the output in 1879 being 720,350 tons. It therefore appears that the output of 1879 would afford supplies for 266 years, while the average output of the ten years, namely, 789,570 tons, would give 243 years, and the output of 1873, the year of greatest production, but 167 years for the exhaustion of the coal to a depth of 4,000 feet.

The returns for the year 1880 exhibit a decrease compared with the previous year, the quantity not exceeding 681,000 tons.

Coal used in Manufacture.—An important industry of Cheshire, namely, salt manufacture, employs considerable quantities of coal, of which it appears 10 cwts. are used in the manufacture of each ton of salt.

CHAPTER VI.

DERBYSHIRE COAL-FIELD.

Description of Coal-field and Succession of Strata at Kilburne and Shipley Collieries—Analyses, Production, and Distribution of Coal—Prices of Coal—Population Employed in Coal and Ironstone Mining—(Resources and Duration included in the Great Coal-field of York, Derby, and Notts).

Derbyshire Coal-field.—This coal-field, with that of Nottinghamshire, includes the southern extension of the Yorkshire coal-field. The succession of strata in Derbyshire is well illustrated by the following section, showing the coal series in descending order from the base of the magnesian limestone. The section is taken across the coal-field, from Wingfield to the escarpment of the magnesian limestone, a distance of nearly seven miles :—*

SUCCESSION OF STRATA.

| | Ft. | In. |
|---|-----|-----|
| Sandstones and shales. | 350 | 0 |
| Coal | 2 | 10 |
| Strata | 107 | 0 |
| Coal | 2 | 1 |
| Strata | 220 | 0 |
| Barnaley Top Hard Coal 5 ft. 10 in. to | 7 | 0 |
| Strata, Brown Rake and Black Rake ironstones | 470 | 0 |
| Soft Coal (generally two seams with partings) | 6 | 0 |
| Strata | 120 | 0 |
| Lower Hard Coal 3 ft. 0 in. to | 4 | 0 |
| Strata | 200 | 0 |
| Furnace Coal 2 ft. 6 in. to | 4 | 0 |
| Strata with nodular ironstone | 140 | 0 |
| Silkstone Clod or Black Shale Coal 5 ft. 0 in. to | 7 | 0 |
| Strata | 385 | 0 |
| Kilburne Coal 4 ft. 0 in. to | 5 | 0 |
| Strata with Honeycrop Ironstone | 200 | 0 |
| Wingfield Flagstones | 350 | 0 |
| Black Shales | 300 | 0 |
| Flagstones and shales | 200 | 0 |
| Coal with a floor of Ganister | 1 | 0 |
| Flagstones and shales | 125 | 0 |
| Ganister Coal (with a floor of Ganister) | 2 | 0 |
| Flagstones and shales | 600 | 0 |
| Millstone grit | | |

* "Geological Survey of England and Wales." Explanation of Horizontal Sections. Sheet 60. 1869.

The total thickness of measures in the above section down to the limestone grit, is 3,808 feet, with about 40 feet of workable coal, the principal seams of which are the "Top Hard" and the "Lower Hard," the "Black Shale" and Kilburne Coal. This last-named coal is the lowest workable seam above the Ganister coal, and the following is the section of the strata above and beneath the coal at Kilburne Colliery:—

SECTION AT KILBURNE COLLIERY.

| | | Ft. | In. |
|--|-------------------------|-----|-----|
| Shales | . | 29 | 7 |
| Coal | . | 2 | 1 |
| Sandstones and shales | . | 65 | 4 |
| Coal | . | 1 | 4 |
| Shales | . | 58 | 0 |
| Coal | . | 1 | 8 |
| Sandstones and shales | . | 95 | 1 |
| Coal and sloom (soft clay) | . | 2 | 6 |
| Sandstones and shales | . | 111 | 7 |
| Kilburne Coal | { Coal . 3 ft. 10 in. } | 5 | 2 |
| | { Sloom . 0 ,, 2 ,, } | | |
| | { Coal . 1 ,, 2 ,, } | | |
| Clunch (soft clay) full of "dogtooth" ironstone. | . | 2 | 7 |
| Ironstone measures | { Ironstone | 0 | 2 |
| | { Dark bind | 2 | 0 |
| | { Ironstone | 0 | 2 |
| | { Dark shaley bind | 1 | 10 |
| | { Ironstone | 0 | 3 |
| | { Shaley bind | 3 | 6 |
| | { Ironstone | 0 | 2 |
| | { Shaley bind | 2 | 2 |
| | { Ironstone | 0 | 3 |
| | { Shaley bind | 2 | 2 |

From the outcrop of the Kilburne coal the dip is north till the centre of Shipley Basin is reached, where the beds are flat, and comprehend all the coal-series from the Top Hard seam inclusive.

The following are the names of the coals at Shipley Colliery:—

| | Ft. | In. |
|---------------------|-----|-----|
| Soft Coal | 1 | 6 |
| and smut | 2 | 10 |
| Soft Coal | 2 | 0 |
| Light-coloured clay | 0 | 6 |
| Soft Coal | 1 | 10 |
| Light-coloured clod | 0 | 4 |
| Soft Coal | 1 | 2 |
| Top Hard Coal | 6 | 2 |
| Old Greaves Coal | 3 | 0 |
| Soft Coal | 1 | 6 |
| " | 0 | 9 |

| | Ft. | In. |
|-----------------------------------|-----|-----|
| <i>Waterloo Coal</i> | 3 | 8 |
| <i>Soft Coal</i> | 1 | 6 |
| " | 2 | 0 |
| " | 1 | 4 |
| <i>Cannel</i> | 2 | 0 |
| <i>Soft Coal</i> | 1 | 4 |
| Coal and shale | 3 | 0 |
| <i>Bright Soft Coal</i> | 4 | 3 |
| Black Clod (Clay) | 4 | 9 |
| <i>Soft Coal</i> | 0 | 9 |
| <i>Bottom Hard Coal</i> | 5 | 6 |

East and north of Shipley Colliery the beds rise and the Top Hard coal crops out.

Analyses of Derbyshire Coal.—Of the various coal seams worked in the Derbyshire area of the Midland coal-field, a few of the more important will show the general character and purposes to which they are suited. The *Top Hard Coal*, for example, worked at Staveley Colliery, four miles N.E. of Chesterfield, is a seam of great regularity in its occurrence, with an average thickness of six feet. The coal is described as a "strong splint which may be exposed for years to atmospheric influence without change or waste," and is extensively used in Derbyshire and Yorkshire in the various stages of iron manufacture. In structure these coals somewhat resemble silicified wood, but seem to have two distinct planes of cleavage at right angles to each other, which give the fragments the form of long four-sided prisms, which, when broken, give rise to splinters of the same shape. The coal is usually found to contain quantities of iron pyrites in the lines of cleavage, and when tried under the boiler, it is found to light easily and burn freely, yielding much smoke, and it was observed that when a fresh charge is thrown on the fire, a crackling is heard occasioned by the decrepitation of the coals.

The "*Loscoe Hard and Soft Coals*" are two seams worked at Loscoe Colliery, situated on the borders of Nottinghamshire, ten miles from Derby, and twelve from Nottingham. The Hard Coal seam is 82 inches in thickness, and is worked at a depth of 180 yards from the surface, whilst the Soft Coal Seam is about 12 inches thick, and is obtained from a depth of 112 yards. These coals differ greatly in their qualities, the "soft" coal being considered a good household and gas coal, whilst the "hard" is chiefly recommended for steam purposes. The Loscoe soft

coal is described as bright, with a splinty fracture containing much shale and iron pyrites; the harder variety is duller in its general appearance, and contains thin layers of very bright coal, together with iron pyrites and white shale.

The "*Langley Hard Coal*." This coal is extracted from the Lower Hard coal seam of Derbyshire and Nottinghamshire; at Heanor in the former county, the seam is three feet in thickness, and is raised at a depth of seventy yards from the surface. This coal finds a ready market in the neighbouring counties of Notts, Lincoln, Leicester, Rutland, and Northampton. The composition of the above-named coals appears in the annexed analyses, to which is added the specific gravity and the yield of coke:—*

| Constituents. | Staveley "Top Hard." | Loscoe Soft Coal. | Langley Hard Coal. |
|--------------------|-------------------------|----------------------|-----------------------|
| Carbon | 79·85 | 77·49 | 77·97 |
| Hydrogen | 4·84 | 4·86 | 5·58 |
| Nitrogen | 1·23 | 1·64 | 0·80 |
| Sulphur | 0·72 | 1·30 | 1·14 |
| Oxygen | 10·96 | 12·41 | 9·86 |
| Ash | 2·40 | 2·30 | 4·65 |
| | 100·00 | 100·00 | 100·00 |
| Specific gravity . | 1·27 | 1·285 | 1·264 |
| Coke per cent. . . | 57·86 | 52·80 | 54·90 |

Dr. Percy † gives the following analyses of Derbyshire coals, the first consisting of the average of a mixture of thirteen different seams worked in the Renishaw Colliery, and the second of coal raised at the Monkwood Colliery also situated near Chesterfield:—

RESULTS TABULATED.

| Constituents. | Renishaw. | Monkwood. |
|-------------------------|-----------|-----------|
| Carbon | 77·12 | 83·18 |
| Hydrogen | 5·05 | 4·76 |
| Oxygen and Nitrogen . . | 8·08 | 6·79 |
| Sulphur | 1·61 | 1·42 |
| Ash | 5·82 | 1·70 |
| Water | 2·32 | 2·15 |
| | 100·00 | 100·00 |

* Appendix, Third Report. Coal Suited to the Steam Navy, pp. 29, 55.

† "Metallurgy," Fuel, p. 32. The Monkwood coal yielding of coke 65·75 per cent.

Production of Coal and Distribution.—Towards the close of the last century, although it was generally known that coal was raised from the many collieries of Derbyshire in considerable quantities, no exact record is met with. It was certainly considerable, besides which a large quantity was conveyed by the Erewash Canal to Leicestershire for consumption in that county. Pilkington,* writing about the year 1789, describes the coal raised in Derbyshire as of two varieties or general divisions, “hard” and “soft.” The soft coal, he adds, “which lies much nearer to the surface, is found in most of those shafts in which the other sort is met with. It is generally shattering and sulphureous. It is much used for burning limestone and the manufacture of iron goods. A large quantity is also converted into coak.” The “hard” coal, which is more useful and valuable, is more varied in its nature and properties.

The earliest return of production met with appears in Farey,† where it is recorded that for the twelve months ending June, 1808, 8,280 boat-loads of coals passed on the Erewash, Cromford, and Nottingham canals, on their way towards the places of consumption; these contained—

| | TONS. |
|----------------------|-------------|
| Hard Coals | 205,006 |
| Soft Coals | 37,289 |
| Cobbles | 27,161 |
| Coke | 24,384 qrs. |

The value of which amounted altogether to £122,838.

Not again until the year 1816 does any reliable data appear showing the quantity of coal raised in Derbyshire, for that year; however, it is gathered from the report of a deputation from the Wear, sent to inquire into the quantities of coals conveyed by railway and canal in different parts of the kingdom, that 355,554 chaldrons were thus distributed, and, assuming these as Newcastle chaldrons of 53 cwt. each, a total appears of 942,000 tons; the total estimated production of the kingdom the same year being set down at 27,020,115 tons. Again, in the year 1854, inquiries over the several districts gave the following as the quantities of coal raised :—‡

* James Pilkington. “View of Derbyshire.” Derby, 1789.

† “View of Derbyshire.” John Farey, 1811, p. 185.

‡ “Mineral Statistics of the United Kingdom.”

| DISTRICTS. | TONS. |
|---------------------------|------------------|
| Chesterfield | 1,098,696 |
| Alfreton | 650,000 |
| Ripley | 145,000 |
| Glossop | 70,000 |
| Ilkeston | 263,000 |
| Burton-on-Trent | 180,000 |
| Total | <u>2,406,696</u> |

Of the collieries in the Erewash Valley district there was sold and conveyed to distant places during the year 1854 :—

| HOW DISTRIBUTED. | TONS. |
|----------------------------------|----------------|
| By canal or water sale | 323,129 |
| By railway sale | <u>599,247</u> |
| Total | <u>922,376</u> |

The London and North-Western Railway carried and distributed 828,505 tons, and large quantities were also carried from the district by the Midland Railway.

In later years the number of collieries and production of coal in Derbyshire were as given in the annexed table :—

| Year. | Number of Collieries. | Coal raised. | Year. | Number of Collieries. | Coal raised. |
|-------|-----------------------|--------------|-------|-----------------------|--------------|
| | | Tons. | | | Tons. |
| 1855 | 171 | 2,256,000 | 1868 | 142 | 4,957,879 |
| 1856 | 176 | 2,298,325 | 1869 | 140 | 5,460,090 |
| 1857 | 171 | 2,612,372 | 1870 | 137 | 5,102,265 |
| 1858 | 161 | *3,960,750 | 1871 | 130 | 5,360,000 |
| 1859 | 153 | *4,250,000 | 1872 | 156 | † |
| 1860 | 153 | *4,940,000 | 1873 | 156 | † |
| 1861 | 158 | *5,116,319 | 1874 | 243 | 7,150,570 |
| 1862 | 155 | 4,534,800 | 1875 | 255 | 7,091,325 |
| 1863 | 155 | 4,550,750 | 1876 | 261 | 7,025,350 |
| 1864 | 154 | 4,470,750 | 1877 | 234 | 6,975,550 |
| 1865 | 154 | 4,595,750 | 1878 | 237 | 7,190,000 |
| 1866 | 150 | 4,750,520 | 1879 | 234 | 7,450,370 |
| 1867 | 150 | 4,550,550 | 1880 | 234 | 7,903,834 |

Examining the above returns of production, it will be seen that in the year 1875 the output had increased threefold compared with the year 1855, since which date the production has been well maintained, exhibiting but little variation; in 1879 a marked increase appears over the previous year, amounting to upwards of 250,000 tons, or nearly 4 per cent.

* Including the produce of Nottinghamshire.

† Included in the returns of Notts, Leicester, and Warwick.

The steady development of the Derbyshire collieries comes out clearly in the returns of distribution. In the year 1855 the Midland Railway carried out of Derbyshire 415,357 tons, which was distributed in Rugby and other places on the London and North-Western Railway. The quantities carried by the Midland Railway and the London and North-Western Railway for 1860 and previous years were as follows :—

| Year. | MIDLAND RAILWAY. | | LONDON AND NORTH-WESTERN. |
|-------|------------------|-----------------|---------------------------|
| | North Derby. | Erewash Valley. | |
| | Tons. | Tons. | Tons. |
| 1856 | 557,825 | 867,288 | ... |
| 1857 | 545,312 | 916,317 | ... |
| 1858 | 595,380 | 972,715 | ... |
| 1859 | ... | 968,026 | 675,000 |
| 1860 | 537,890 | ... | ... |

Before giving the returns of distribution for the past twenty years, it will be desirable to call attention to an early return of the sales of coal by canal from the collieries in the Erewash Valley, dating from the year 1803, when the sales amounted to 254,268 tons, increased to 427,670 tons in the year 1848.* The figures below are from the return referred to :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1803 | 254,268 | 1830 | 253,498 |
| 1806 | 267,204 | 1833 | 316,187 |
| 1809 | 321,056 | 1836 | 377,103 |
| 1812 | 279,280 | 1839 | 377,606 |
| 1815 | 298,482 | 1842 | 410,495 |
| 1818 | 236,372 | 1845 | 334,159 |
| 1821 | 331,840 | 1846 | 385,695 |
| 1824 | 318,624 | 1847 | 475,779 |
| 1827 | 288,678 | 1848 | 427,670 |

From the annual statements of accounts published by the "Association of Coal Owners of the Erewash Valley, Leicestershire, and North and South Derbyshire," very complete returns are obtained, showing the sales of coal by railway and canal. The above-named association was dissolved in 1877 and a new

* For details of each year's sale, see Coal Commission Report, vol. iii., Appendix, p. 16.

one founded.* The returns for a few years will show the condition of the coal industries of Derbyshire under the auspices of the Association; the figures are as follows :—

| Year. | Erewash Valley. | North Derbyshire. | South Derbyshire. |
|-------|-----------------|-------------------|-------------------|
| | Tons. | Tons. | Tons. |
| 1860 | 1,926,167 | 537,890 | ... |
| 1862 | 1,329,766 | 351,208 | ... |
| 1864 | 1,742,543 | 483,132 | ... |
| 1865 | 1,739,979 | 466,448 | ... |
| 1866 | 1,843,397 | 450,515 | ... |
| 1867 | 1,825,798 | 503,137 | 128,381 |
| 1868 | 1,634,624 | 517,384 | 165,210 |
| 1869 | 1,781,964 | 598,086 | 121,392 |
| 1870 | 1,924,718 | 628,153 | 268,477 |
| 1871 | 1,949,428 | 840,291 | 331,790 |
| 1872 | 2,091,377 | 1,041,183 | 374,846 |
| 1873 | 2,046,017 | 1,212,440 | 344,071 |
| 1874 | 2,026,013 | 878,246 | 463,832 |
| 1875 | 1,917,759 | 765,835 | 410,231 |
| 1876 | 1,744,511 | 554,509 | 366,554 |

Beyond these returns, the collieries in Nottinghamshire and Leicestershire, also in the Association, sent away coals in lesser quantities, bringing up the total sales of the Association in each of the same years to the following figures :—

LEICESTERSHIRE AND NORTH DERBYSHIRE ASSOCIATION SALES.

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1857 | 1,837,920 | 1867 | 3,054,303 |
| 1858 | 1,925,584 | 1868 | 2,853,512 |
| 1859 | 2,019,546 | 1869 | 3,282,625 |
| 1860 | 3,115,883 | 1870 | 3,440,374 |
| 1861 | 2,473,732 | 1871 | 3,784,212 |
| 1862 | 2,267,998 | 1872 | 4,227,381 |
| 1863 | 2,492,893 | 1873 | 4,260,704 |
| 1864 | 2,870,148 | 1874 | 3,924,793 |
| 1865 | 2,818,154 | 1875 | 3,482,861 |
| 1866 | 2,952,788 | 1876 | 3,013,925 |

In the above returns it should be remembered that the quantities do not include the local or land sales, nor coals used for iron-making purposes, but only railway and canal sales. The extent of these sales may be gathered from the annexed details for the years given :—

* "The Derbyshire, Leicestershire, and Nottinghamshire Coal Owners Association," from which no returns are published, but issued to members only.

| Districts. | 1860. | 1870. | 1876. |
|--------------------------|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| Erewash Valley | 1,926,167 | 1,924,718 | 1,744,511 |
| Leicestershire | 651,826 | 462,427 | 213,574 |
| North Derbyshire | 537,890 | 628,153 | 554,509 |
| South Derbyshire | ... | 268,477 | 366,554 |
| Nottinghamshire | ... | 156,699 | 134,777 |
| Totals | 3,115,883 | 3,440,374 | 3,013,925 |

Previous to the year 1848, the chief means of distributing the coals of those collieries situated in the Erewash Valley was by the canal bearing the same name; in 1849, however, for the first time, returns are available, showing the quantity carried by railway. These latter show a greatly increased traffic till the year 1875, when a falling off appears, and again in 1876, when the last return was published. The details given below show the sales by railway and canal of the "Associated Collieries of the Erewash Valley District" from 1849 to 1876:—

| Year. | Canal. | Railway. | Total. |
|-------|---------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| 1849 | 386,955 | 43,820 | 430,775 |
| 1851 | 334,922 | 251,079 | 586,001 |
| 1853 | 320,408 | 497,961 | 818,369 |
| 1855 | 223,893 | 753,277 | 977,170 |
| 1857 | 227,704 | 776,948 | 1,004,652 |
| 1859 | 208,905 | 968,026 | 1,176,931 |
| 1861 | 218,421 | 1,282,669 | 1,501,090 |
| 1863 | 223,972 | 1,347,944 | 1,571,916 |
| 1865 | 210,440 | 1,649,542 | 1,859,982 |
| 1867 | 196,579 | 1,749,225 | 1,945,804 |
| 1869 | 192,902 | 1,709,061 | 1,901,963 |
| 1870 | 148,342 | 1,776,114 | 1,924,456 |
| 1871 | 148,926 | 1,800,502 | 1,949,428 |
| 1872 | 146,610 | 1,944,767 | 2,091,377 |
| 1873 | 124,490 | 1,921,527 | 2,046,017 |
| 1874 | 106,163 | 1,919,853 | 2,026,017 |
| 1875 | 105,479 | 1,730,636 | 1,836,115 |
| 1876 | 102,430 | 1,502,378 | 1,604,808 |

The great increase in the movement of coal since the introduction of railways is shown in the above returns. In 1849, the first return of coal carried from the collieries in the Erewash Valley district, gives 43,820 tons, increased to 968,026 tons in 1859, and 1,944,767 tons in 1872, since which a falling off appears. On the other hand the coal sales by canal exhibit a falling off

from 386,955 tons in 1849, to 102,430 tons in 1876, when these returns were discontinued.

The foregoing statements of distribution refer to the produce of those collieries in the districts named; for complete returns of the distribution of coal by railway, the statements annually furnished by the several railway companies, and published in the "Mineral Statistics," afford the desired information. The most important of these returns are those of the Midland Railway, whose system has in a greater degree than any other, contributed to the distribution of the vast deposits of coal of the Midland coal-fields of Yorkshire, Derbyshire, Nottinghamshire, Leicestershire, and Warwickshire.

In the following table is given the distribution of coal, the output of the Derbyshire collieries, by the Midland, London and North-Western, Great Northern, and Manchester, Sheffield, and Lincolnshire Railways, since the year 1855:—

| Year. | Midland Railway. | London and North- Western Railway. | Great Northern Railway. | Manchester, Shef- field and Lincoln- shire Railway. |
|-------|---------------------|---------------------------------------|----------------------------|---|
| | Tons. | Tons. | Tons. | Tons. |
| 1855 | *415,357 | 328,505 | ... | ... |
| 1856 | 1,425,113 | ... | ... | ... |
| 1857 | 1,461,629 | ... | ... | ... |
| 1858 | 1,568,095 | ... | ... | ... |
| 1859 | 1,743,769 | 675,000 | ... | ... |
| 1860 | +2,230,275 | ... | 159,412 | 132,641 |
| 1861 | +2,370,817 | ... | 232,696 | 122,666 |
| 1862 | +2,283,406 | †766,899 | 356,540 | ... |
| 1863 | 2,514,128 | †907,646 | ... | ... |
| 1864 | 3,013,730 | 20,379 | ... | ... |
| 1865 | 2,577,690 | ... | ... | ... |
| 1866 | 3,135,855 | 24,982 | 526,072 | ... |
| 1867 | 3,555,745 | 32,378 | 620,409 | 219,587 |
| 1868 | 2,350,393 | 53,824 | 585,113 | 229,867 |
| 1869 | 3,617,082 | 42,129 | 558,735 | 293,466 |
| 1870 | 4,079,447 | 66,217 | 573,261 | ... |
| 1871 | 4,695,527 | 34,355 | 375,439 | ... |
| 1872 | 4,875,044 | 29,201 | 357,580 | 137,325 |
| 1873 | 5,197,550 | 25,463 | 441,226 | 227,622 |
| 1874 | 5,252,740 | 30,140 | 416,202 | 331,285 |
| 1875 | 5,488,592 | 33,485 | 499,044 | 342,312 |
| 1876 | 5,022,347 | 33,214 | 619,494 | 239,464 |
| 1877 | 5,155,152 | 40,577 | 735,120 | 293,885 |
| 1878 | 5,173,115 | 40,203 | 824,337 | 306,380 |
| 1879 | 5,689,527 | 38,190 | 955,468 | 387,275 |
| 1880 | 5,603,872 | 27,632 | 896,636 | 408,836 |

* Not including collieries in Erewash Valley.

† Including Nottinghamshire collieries.

‡ Midland Coal-field.

Prices of Coal in Derbyshire.—In 1860 the average cost of coal loaded into carts or trucks at the pit's mouth varied from 5s. to 5s. 6d. per ton. The selling price of best coals being about 9s. per ton, and ordinary coals 6s. 6d., cartage in the district increasing the price by about one shilling per ton per mile, while, as regards railway carriage, the cost for long distances, exclusive of waggons, was $\frac{1}{2}$ d. per ton per mile.

Advancing to the year 1870, it appears from the Report of the Coal Commission * that the average prices of coals in the Chesterfield district were as follows :—

| | s. | d. |
|---------------------------------|------------|-----|
| <i>Brimington</i> | 6 | 6 |
| <i>Monkwood</i> | 6s. 0d. to | 9 0 |
| <i>Renishaw</i> | 6 | 8 |
| <i>Woodhouse Hard</i> | 7 | 6 |
| <i>Soft</i> | 7 | 1 |
| <i>Small</i> | 4 | 7 |

And in the Alfreton district :—

| | s. | d. | s. | d. |
|--|----|------|----|----|
| <i>Coates Park, Screened</i> | 5 | 0 to | 5 | 6 |
| <i>Cobbles</i> | 6 | 0,, | 7 | 0 |
| <i>Brights</i> | 8 | 0,, | 8 | 6 |
| <i>Shirland, Round</i> | 5 | 6,, | 8 | 0 |
| <i>Swanwick, average</i> | 5 | 0,, | 12 | 0 |

In recent years the average price per ton at the pit's mouth of coal and slack was as follows :—

| Year. | | Average. | Highest. | Lowest. |
|-------|-------------|--------------|---------------|--------------|
| 1878 | Coal . . . | s. d. 8 4 | s. d. 11 0 | s. d. 6 6 |
| | Slack . . . | 3 6 | 5 3 | 2 6 |
| 1879 | Coal . . . | 7 3 | 10 6 | 6 0 |
| | Slack . . . | 4 3 | 5 9 | 2 0 |
| 1880 | Coal . . . | 7 6 | 10 0 | 6 1 |
| | Slack . . . | 4 4 | 5 0 | 2 4 |

Showing a falling off in the price of coals and an increase in that of slack in 1880 compared with the previous years.

Population employed in Coal and Ironstone Mining.—The total number of male persons employed in coal mining in Derbyshire in 1854 was 5,434, and in ironstone mining 1,428, giving a

* Vol. iii., Appendix, p. 212.

total of 6,862; the total quantity of coal raised in the same year was 2,406,696 tons.

The first return distinguishing the number of persons employed underground and above ground in Derbyshire in coal mines appeared for the year 1878,* when 22,173 persons were engaged underground, and 5,950 above ground, giving an aggregate of 28,123 persons employed, the output of coal amounting to 6,977,587 tons. In the following table the total numbers appear for each year since, with the output of coal and average produce per man :—

| Year. | PERSONS EMPLOYED. | | Total Employed. | Coal raised. | Average per Man. |
|-------|-------------------|---------------|-----------------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 22,173 | 5,950 | 28,123 | 6,977,587 | 249 |
| 1874 | 24,019 | 6,461 | 30,480 | 7,152,944 | 234 |
| 1875 | 23,683 | 6,414 | 30,097 | 7,190,921 | 238 |
| 1876 | 23,078 | 6,508 | 29,586 | 6,959,101 | 242 |
| 1877 | 21,937 | 6,148 | 28,085 | 7,054,091 | 251 |
| 1878 | 21,190 | 5,785 | 26,975 | 7,289,380 | 270 |
| 1879 | 21,713 | 6,146 | 27,859 | 7,561,235 | 271 |
| 1880 | 21,183 | 6,073 | 27,256 | 7,903,834 | 290 |

The average produce per man shows increased efficiency, to the amount of 41 tons in eight years, equal to nearly 16 per cent.

The ages of those employed in the year 1879 above and below ground were as under :—

| Ages. | Under Ground. | Above Ground. |
|-------------------------|---------------|---------------|
| From 10 to 12 | 4 | ... |
| „ 10 to 13 | ... | 35 |
| „ 12 to 13 | 112 | ... |
| „ 13 to 16 | 2,201 | 539 |
| Above 16 | 19,396 | 5,572 |
| Total | 21,713 | 6,146 |

The resources and probable duration of the Derbyshire coal-field are considered in the account of the Yorkshire coal-field.

* See Reports of H.M. Inspectors of Mines.

CHAPTER VII.

NOTTINGHAMSHIRE COAL-FIELD.

Description of Coal-field and Section of Strata at Cinderhill Colliery—Analyses,
Production, and Distribution of Coal by Railway—Population employed in
Coal Mining in Nottinghamshire—(Resources and Duration, included in the
Coal-field of York, Derby, and Notts).

The Nottinghamshire Coal-field.—This coal-field is a continuation of that of Derbyshire and Yorkshire, and Mr. W. T. Aveline, in his "Memoir of the Country around Nottingham," gives the following section, remarking that, "as in other districts, the coal formation is here an accumulation of beds of sandstone, shale-clay, and ironstone, alternating with each other. There are many beds of coal in this field lying at intervals below each other, separated by the sandstones, shales, &c., but it is only a few of these that are thick, or good enough, to be worked to a profit." *

VERTICAL SECTION OF THE NOTTINGHAM AND DERBYSHIRE COAL-FIELD.

The first part (to the Top Hard Coal) from a pit at Cinderhill.

| No. | Description of Strata. | Thickness. | | Depth. | |
|-----|--|------------|-----|--------|-----|
| | | Ft. | In. | Ft. | In. |
| 1 | Limestone (Magnesian) | 5 | 4 | ... | |
| 2 | Light blue and brown stone in beds | 6 | 3 | 11 | 7 |
| 3 | Blue stone | 8 | 5 | 20 | 0 |
| 4 | Dark-pink bind | 3 | 8 | 23 | 8 |
| 5 | Dark-grey stone | 0 | 4 | 24 | 0 |
| 6 | Red stone with pebbles | 1 | 0 | 25 | 0 |
| 7 | Clunch (usually tough clay or shale) | 1 | 9 | 26 | 9 |
| 8 | Bind | 19 | 0 | 45 | 9 |
| 9 | Ironstone | 0 | 3 | 46 | 0 |
| 10 | Soft clunch | 5 | 0 | 51 | 0 |
| 11 | Black shale or bind | 2 | 7 | 53 | 7 |
| 12 | Clunch | 6 | 8 | 60 | 3 |
| 13 | Bind, with bands of ironstone | 40 | 4 | 100 | 7 |
| 14 | Chillery coal | 0 | 7½ | 101 | 2½ |
| 15 | Light and dark clunch | 6 | 0 | 107 | 2½ |
| 16 | Bind | 20 | 9 | 127 | 11½ |
| 17 | Ironstone | 0 | 2½ | 128 | 2 |
| 18 | Bind | 14 | 7 | 142 | 9 |
| 19 | Soft coal | 1 | 1½ | 143 | 10½ |
| 20 | Shale bind and clunch | 20 | 2 | 164 | 0½ |
| 21 | Soft coal | 2 | 4½ | 166 | 5 |
| 22 | Clunch and bind, with bat and shale | 18 | 10 | 185 | 3 |
| 23 | Soft coal | 1 | 0 | 186 | 3 |
| 24 | Clunch and bind | 1 | 0 | 187 | 3 |

* "Memoirs of the Geological Survey," 1861. (Quarter sheet, 71 N.E.)

| No. | Description of Strata. | Thickness. | | Depth. | |
|-----|--|------------|-----|--------|-----|
| | | Ft. | In. | Ft. | In. |
| 25 | Soft coal | 1 | 7½ | 188 | 10½ |
| 26 | Clunch and stone | 9 | 5 | 198 | 3½ |
| 27 | Bind, clunch, stone, and bat, with a little coal and ironstone | 81 | 8½ | 280 | 0 |
| 28 | Coal | 3 | 6½ | 283 | 6½ |
| 29 | Dark clunch, with bat and ironstone | 20 | 8 | 304 | 2½ |
| 30 | Coal | 0 | 7 | 304 | 9½ |
| 31 | Shaly bind | 10 | 1 | 314 | 10½ |
| 32 | Soft coal | 2 | 4 | 317 | 2½ |
| 33 | Shale and bind | 36 | 2 | 353 | 4½ |
| 34 | Soft coal | 3 | 4 | 356 | 8½ |
| 35 | Dark clunch, with impressions | 3 | 11 | 360 | 7½ |
| 36 | Soft coal | 1 | 3 | 361 | 10½ |
| 37 | Clunch and bind | 45 | 3 | 407 | 1½ |
| 38 | Coal | 1 | 5 | 408 | 6½ |
| 39 | Black shale and bind | 29 | 7 | 438 | 1½ |
| 40 | Soft coal | 2 | 5 | 440 | 6½ |
| 41 | Shale clunch, &c. | 68 | 7 | 509 | 1½ |
| 42 | Coal | 3 | 9 | 512 | 10½ |
| 43 | Shale and bind and a few small beds of ironstone | 82 | 3 | 595 | 1½ |
| 44 | Coal (hard) | 2 | 2½ | 597 | 4 |
| 45 | Clunch, bind, and shale | 50 | 0 | 647 | 4 |
| 46 | Main coal | 8 | 2 | 655 | 6 |

Another section in the same district, by Mr. Aveline, gives the following as the depth and thickness of the seams and intervening strata between the "Top Hard" and the "Deep Hard Coal":—

| Description of the Strata. | Thickness. | | Depth below Top Hard. | |
|--|------------|-----|-----------------------|-----|
| | Ft. | In. | Ft. | In. |
| Bind with ironstone | 25 | 2 | ... | ... |
| Coal | 0 | 10 | 424 | 5 |
| Clunch and bind | 11 | 0 | ... | ... |
| Coal | 0 | 10 | 436 | 3 |
| Bat, clunch, and bind | 9 | 9 | ... | ... |
| Coal (probably the Ell coal) | 1 | 0 | 447 | 0 |
| Bind and rock | 54 | 0 | ... | ... |
| The main or deep soft coal | 3 | 0 | 504 | 0 |
| Bat | 1 | 0 | ... | ... |
| Dark clunch and fire-clay | 12 | 6 | ... | ... |
| Bind and rock | 6 | 10 | ... | ... |
| The Deep Hard coal | 3 | 6 | 527 | 10 |

The following section gives the chief coals below the Deep Hard Coal:—

| Description of the Strata. | Thickness. | | Depth below Top Hard. | |
|--|------------|-----|-----------------------|-----|
| | Ft. | In. | Ft. | In. |
| Clunch, bind, &c. | 66 | 0 | ... | |
| Piper coal | 5 | 0 | 71 | 0 |
| Bind, clunch, and other strata | 138 | 0 | ... | |
| Furnace coal | 4 | 0 | 213 | 0 |
| Clunch, bind, &c. | 108 | 0 | ... | |
| Yard coal | 3 | 0 | 324 | 0 |
| Clunch, bind, &c. | 30 | 0 | ... | |
| Black shale coal | 5 | 4 | 359 | 4 |
| Clunch, bind, &c. | 459 | 0 | ... | |
| Kilburne coal | 3 | 6 | 821 | 10 |
| Depth of Kilburne coal below Top Hard coal | ... | | 1,339 | 8 |

It is remarked that of the coals in the above sections, the only beds that are, or have been, worked in this district are the Top Hard, or "Rifler," Waterloo, Main Soft, Lower Hard, and Piper coals; and further, that clunch usually means tough clay or shale; binds, shaley clay often blue, and bat, carbonaceous shale.

Analysis of Coal.—The coal raised in the neighbourhood of Worksop, at the Shireoaks Colliery, examined by Mr. Charles Tookey in Dr. Percy's laboratory, shows the following constituents:—

RESULTS TABULATED.

| | |
|--------------------|--------------------|
| Carbon | 77·40 |
| Hydrogen | 4·96 |
| Oxygen | 7·77 |
| Nitrogen | 1·55 |
| Sulphur | 0·92 |
| Ash | 3·90 |
| Water | 3·50 |
| | <hr/> 100·00 <hr/> |

The ash remaining being described as bulky and slightly pink in colour; the coal, on coking, yielding 63·18 per cent.

Other coals, extensively worked by the Butterley Company, in Notts and Derby, are known as the "Upper Hard Coals" and the "Lower Hard Coals," the former described "as excessively hard and containing much mineralized charcoal in the jointings, with thin strata of bright coal occasionally intervening; the second closely resembles the first, but contains more iron pyrites."* The

* Appendix, Third Report Coal Suited to the Steam Navy, p. 29.

coal, in the first analysis, was obtained from the Portland Colliery of the above-named company, situated at Kirkby, in Ashfield, Notts, at a depth of 180 yards from the surface, the vein, being irregular, varying in thickness from 3 feet 6 inches to 5 feet. The second, the "Lower Hard Coals," examined was obtained from the Langley Colliery of the same company, situated near Heanor, the seam having a thickness of three feet; the following gives the results :—

| Constituents. | Portland Upper Hard. | Langley Lower Hard. |
|-------------------------------|-------------------------|------------------------|
| Carbon | 80·41 | 77·97 |
| Hydrogen | 4·65 | 5·58 |
| Nitrogen | 1·59 | 0·80 |
| Sulphur | 0·86 | 1·14 |
| Oxygen | 11·26 | 9·86 |
| Ash | 1·23 | 4·65 |
| | 100·00 | 100·00 |
| Specific gravity | 1·301 | 1·264 |
| Per centage of Coke | 60·90 | 54·90 |

It is remarked of these coals that they light easily, and when thrown on the fire make a crackling noise. They burn freely, leaving a white-coloured ash, the "Lower Hard" more than the "Upper Hard," and both requiring the frequent use of the rake to prevent the choking of the draught in the furnace. The clinker, though considerable, did not adhere to the fire-bars, and when the stoking or charging the fire took place it was found much smoke was evolved.

Production and Distribution of Coal.—In the year 1816 the quantity of coal carried by inland navigation in Nottinghamshire was 494,665 tons; in Derbyshire, 942,218 tons, and in Yorkshire, 2,563,626 tons, the produce of this great coal-field, extending through the above-named counties. Indeed, these quantities may be regarded as the output of the collieries in operation at the time.

The next return, for the year 1854, gives the output of seventeen collieries in Nottinghamshire as 813,474 tons, the production being doubled since the year 1816. In 1855 the number of collieries increased to 20, and the output fell off to 809,400

tons. Subsequently the number of collieries and production of coal in the Nottinghamshire coal-field has been as under :—

| Year. | No. of Collieries. | Coal Raised. | Year. | No. of Collieries. | Coal Raised. |
|-------|--------------------|--------------|-------|--------------------|--------------|
| | | Tons. | | | Tons. |
| 1816 | ... | 494,665 | 1867 | 24 | 1,575,000 |
| 1854 | 17 | 813,474 | 1868 | 27 | 1,508,439 |
| 1855 | 20 | 809,400 | 1869 | 26 | 1,575,450 |
| 1856 | 24 | * | 1870 | 27 | 2,115,372 |
| 1857 | 23 | * | 1871 | 27 | 2,469,400 |
| 1858 | 23 | * | 1872 | 28 | * |
| 1859 | 23 | * | 1873 | 34 | * |
| 1860 | 21 | * | 1874 | 45 | 3,127,750 |
| 1861 | 22 | * | 1875 | 46 | 3,250,000 |
| 1862 | 21 | 732,666 | 1876 | 48 | 3,415,100 |
| 1863 | 21 | 750,000 | 1877 | 47 | 3,895,750 |
| 1864 | 21 | 796,700 | 1878 | 41 | 4,107,350 |
| 1865 | 21 | 1,095,500 | 1879 | 41 | 4,249,242 |
| 1866 | 25 | 1,600,000 | 1880 | 44 | 4,432,393† |

The development of the Nottinghamshire coal-field is greatly aided by the ample facilities provided by several important systems of railways and canals. The coal-field on the south-west border of the county is traversed by the Midland Railway, which enters the county at the south-west corner running through the Erewash Valley along the border to Codnor, in Derbyshire, and on to Mansfield; a branch coming from Derby runs along the valley of the Trent to Nottingham and from Newark to Lincoln, with branches from Nottingham to Mansfield and Southwell. The impulse given to the coal trade of Nottinghamshire appears in the railway returns. The Midland Railway, in 1863, carried from Nottinghamshire 83,932 tons, and in subsequent years the following quantities, according to returns of "Mineral Statistics :"—

| Year. | Coal Carried. | Year. | Coal Carried. |
|-------|---------------|-------|---------------|
| | Tons. | | Tons. |
| 1864 | 188,753 | 1873 | 967,000 |
| 1866 | 197,873 | 1874 | 1,005,587 |
| 1867 | 180,506 | 1875 | 1,019,793 |
| 1868 | 191,796 | 1876 | 1,222,417 |
| 1869 | 283,548 | 1877 | 1,295,479 |
| 1870 | 471,118 | 1878 | 1,506,936 |
| 1871 | 574,796 | 1879 | 1,625,471 |
| 1872 | 689,407 | 1880 | 1,614,377 |

* Production included in Derbyshire.

† Report H. M. Inspector of Mines.

In the year 1880, and previous years, the following quantities of coal, the produce of the Nottinghamshire collieries, have been used by the Midland Railway Company for locomotive purposes. Side by side is given, for the same years, the total quantities of coal used for similar purposes by the Midland Company throughout their railway system :—

| Year. | Nottingham Coal. | Total Coal Used. |
|-------|------------------|------------------|
| | Tons. | Tons. |
| 1876 | 87,392 | 548,817 |
| 1877 | 126,611 | 612,886 |
| 1878 | 130,457 | 575,117 |
| 1879 | 145,627 | 656,340 |
| 1880 | 94,641 | 707,185 |

The Manchester, Sheffield, and Lincolnshire Railway carried small quantities of coal from Nottinghamshire between the years 1872 and 1878, when the traffic appears to have ceased; the tonnages, though unimportant, were as under, amounting in 1872 to 4,397 tons :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1873 | 4,234 | 1876 | 3,869 |
| 1874 | 4,056 | 1877 | 5,622 |
| 1875 | 3,838 | 1878 | 9,601 |

During the existence of the association known as the “Associated Coal Owners of Derbyshire, Nottinghamshire, and Leicestershire,” information was available showing the respective sales, by railway and canal, of coal, the produce of collieries situated in Nottinghamshire and the adjoining counties. The Association was dissolved in 1877, but up to that date the movement of coal in each year from this coal-field was as under :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1869 | 121,392 | 1873 | 276,645 |
| 1870 | 283,548 | 1874 | 163,765 |
| 1871 | 227,987 | 1875 | 86,315 |
| 1872 | 265,008 | 1876 | 134,777 |

Population Employed in Coal mining in Nottinghamshire.—
The total number of persons of all ages employed in the year 1854

was 8,071; the output of the coal mines amounting to 818,474 tons. In 1873 the numbers were 10,866, of these 7,755 were engaged in underground operations, and 2,611 above ground, the total coal produced in the coal-field amounting to 2,890,929 tons. The numbers employed in subsequent years, and the output of the collieries, and produce per man, appear in the annexed statement :—*

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 7,755 | 2,611 | 10,366 | 2,890,929 | 279 |
| 1874 | 9,099 | 3,129 | 12,228 | 3,125,176 | 255 |
| 1875 | 9,618 | 3,095 | 12,713 | 3,265,368 | 278 |
| 1876 | 10,294 | 3,311 | 13,605 | 3,582,995 | 264 |
| 1877 | 10,182 | 3,210 | 13,392 | 3,877,322 | 289 |
| 1878 | 10,633 | 3,278 | 13,911 | 4,106,392 | 295 |
| 1879 | 10,772 | 3,459 | 14,231 | 4,316,954 | 303 |
| 1880 | 10,357 | 3,235 | 13,592 | 4,432,393 | 326 |

The maximum number of colliers employed in our coal-fields was in the year 1875, when of the 535,845 engaged, 427,017 were underground, and 108,828 above ground; since that date, in most districts, the numbers employed have diminished. In Nottinghamshire, however, the numbers have gone on increasing, and the efficiency of the collier appears in the high average of coal raised by each individual in 1880, compared with 1873 and intervening years.

Of the 14,231 persons employed in coal-mining operations in the year 1879 Her Majesty's inspectors give the following analysis of their respective ages :—

| All Ages. | Under Ground. | Above Ground. | Total. |
|-------------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| From 12 to 13 . . | 58 | ... | 58 |
| „ 10 to 13 . . | ... | 14 | 14 |
| „ 13 to 16 . . | 975 | 225 | 1,200 |
| Above 16 . . | 9,739 | 3,220 | 12,959 |
| Total . | 10,772 | 3,459 | 14,231 |

The resources and probable duration of the Nottinghamshire coal-field are considered in the great coal-field of Yorkshire, Derbyshire, and Nottinghamshire.

* Reports of H.M. Inspectors of Mines.

CHAPTER VIII.

LEICESTERSHIRE COAL-FIELD.

Description of Coal-field—Section in the Moira and Coleorton Districts—Analyses,
Production, and Distribution of Coal—Population Employed in Coal Mining—
Resources and Probable Duration of Coal-field.

The Leicestershire Coal-field, as described by Professor Hull, F.R.S., occupies an irregular-shaped area south of the valley of the Trent, and bounded by strata of New Red Sandstone age, except on the north-eastern side, which is occupied by the ancient shales and porphyries of Charnwood Forest, of Cambrian age. The coal-field he divides into three districts: Moira, occupying the west; Ashby de la Zouch, the centre; and Coleorton, the east, the carboniferous series of the district being thus divided :—

1. *Upper Sandstone.*
2. *Middle Coal Measures.*
3. *Lower Coal Measures.*
4. *Millstone Grit.*
5. *Yoredale Series and Carboniferous Limestone.*

In the Middle Coal Measures are numerous seams of coal, ten of which, exceeding two feet in thickness, are workable, and give an average thickness of from 40 to 45 feet of solid coal. The annexed section shows the order of occurrence of the principal coal seams in the Moira and Coleorton districts :—

| Moira District (West). | | Coleorton District (East). | |
|-------------------------------|---------|-------------------------------|---------|
| | Ft. In. | | Ft. In. |
| Ell Coal | 3 8 | Stour Smut | 4 9 |
| Dicky Gobbler | 3 6 | Swannington | 3 7 |
| Block Coal | 3 6 | Slate Coal | 4 8 |
| Little or Four Feet | 4 6 | Coal | 2 10 |
| Cannel | 3 6 | Coal | 3 7 |
| Main { Over Seam } | 12 0 | Main Coal | 6 0 |
| { Nether Seam } | | Upper Lount | 3 9 |
| Toad | 3 6 | Second Lount | 3 0 |
| Little Woodfield | 2 6 | Middle Lount | 4 6 |
| Woodfield | 5 0 | Nether Lount | 4 6 |
| Stockings | 9 0 | Heath End Coal and | |
| Eureka | 4 6 | Cannel | 10 0 |
| | | Lower Coal Measures | |

The total thickness of measures in the Leicestershire coal-field is at least 2,500 feet, and that part containing the principal coal beds is situated about the centre. Towards the base from 800 to 1,000 feet of unproductive coal measures occur. The main coal of the Moira district is from twelve to fourteen feet thick, that of Coleorton from six to eight feet, and it is observed by Professor Hull that, though the section in the Moira and Coleorton districts cannot be identified, yet it is highly probable, that the productive measures of each, occupy the same general position in the series.

Analyses of Leicestershire Coal—That raised at the Ibstock Colliery, situated about eleven miles from the town of Leicester, whence the coal is sent by canal and railway to various parts of England, is described* as “Mingy or Cleft coal, with a cubical fracture, adapted for house purposes, and more particularly for steamers.” The mine is $128\frac{1}{2}$ yards deep, and the seam $8\frac{1}{2}$ feet thick, and tolerably regular. This coal will not coke, and has been employed by some of the railway companies instead of that fuel. The sample experimented upon was of a full black colour, with a cubical fracture, and contained a considerable amount of pyrites, and but little white shale. On the grate it was found to produce a good clear fire, and with careful stoking gave off but little smoke. The coal behaves precisely like an ordinary splint, and, with a quick draught, leaves a rather large quantity of clinker, which does not, however, attach itself to the bars.

The composition of mean average samples of this coal appears in the annexed analysis, one pound of which was found to evaporate 6·63 lbs. of water at a temperature of 212° Fahr.

RESULTS TABULATED.

| | |
|--------------------|--------|
| Carbon | 74·97 |
| Hydrogen | 4·83 |
| Nitrogen | 0·88 |
| Sulphur | 1·45 |
| Oxygen | 11·88 |
| Ash | 5·99 |
| | <hr/> |
| | 100·00 |

The specific gravity of the coal is 1·291, the per centage

* Third Report, Coals suited to the Steam Navy, pp. 22, 55. By De la Beche and Playfair, 1851.

amount of coke left being 50·80, and the average weight of a cubic foot 47·33 lbs.

The coal raised at the Whitwick Colliery, situated near Coalville, and examined by Dr. Percy, gives the composition per cent. as follows * :—

RESULTS TABULATED.

| | |
|---------------------------------|--------|
| Carbon | 69·00 |
| Hydrogen | 4·35 |
| Oxygen and Nitrogen } | 10·78 |
| Sulphur | 0·78 |
| Ash | 5·42 |
| Water | 9·67 |
| | <hr/> |
| | 100·00 |
| | <hr/> |
| Coke | 58·14 |

It is observed by Dr. Percy that the coke is firm and compact, the flame yellow, slightly smoky, and the colour of the ash pinkish-white.

Production of Coal in Leicestershire.—The output of the coal mines of this coal-field, in 1816, was 176,665 tons, in 1854 the output of eleven collieries in operation was 439,000 tons, increased in later years as under :—

| Year. | Number of Collieries. | Coal Raised. | Year. | Number of Collieries. | Coal Raised. |
|-------|-----------------------|--------------|-------|-----------------------|--------------|
| | | Tons. | | | Tons. |
| 1855 | 11 | 425,000 | 1867 | 11 | 1,150,000 |
| 1856 | 14 | 632,478 | 1868 | 11 | +608,088 |
| 1857 | 14 | 698,750 | 1869 | 10 | 650,700 |
| 1858 | 14 | 750,000 | 1870 | 11 | 599,450 |
| 1859 | 14 | 800,000 | 1871 | 12 | 699,900 |
| 1860 | 14 | 730,000 | 1874 | 24 | 1,100,465 |
| 1861 | 11 | 740,000 | 1875 | 25 | 1,154,619 |
| 1862 | 10 | 696,024 | 1876 | 27 | 1,006,000 |
| 1863 | 10 | 805,750 | 1877 | 27 | 1,149,590 |
| 1864 | 10 | 890,500 | 1878 | 28 | 1,020,500 |
| 1865 | 11 | 965,000 | 1879 | 27 | 1,035,016 |
| 1866 | 11 | 866,560 | 1880 | 27 | 1,063,382 |

Distribution of Coal.—The Midland Railway, in the year

* Percy's "Metallurgy," Fuel, p. 569.

† In previous years the following collieries were included in the Leicestershire return, they are now included in Derbyshire—Bretby Greasley, Granville Stanton, Cadley Hill, and Swadlincote.

1856, carried 487,230 tons of coal, the output of the Leicestershire collieries, and distributed it at various stations over their system; the returns of subsequent years are as follows :—

MIDLAND RAILWAY RETURNS.

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1857 | 520,514 | 1869 | 777,603 |
| 1858 | 634,471 | 1870 | 864,273 |
| 1859 | 648,133 | 1871 | 966,830 |
| 1860 | 717,633 | 1872 | 1,017,201 |
| 1861 | 696,258 | 1873 | 1,162,087 |
| 1862 | 705,275 | 1874 | 1,074,816 |
| 1863 | 766,054 | 1875 | 1,049,664 |
| 1864 | 879,191 | 1876 | 1,106,456 |
| 1865 | 843,928 | 1877 | 869,785 |
| 1866 | 865,240 | 1878 | 987,087 |
| 1867 | 920,476 | 1879 | 954,770 |
| 1868 | 777,603 | 1880 | 1,054,433 |

The quantity of coal carried in 1880 was 1,054,433 tons. Beyond the above tonnages small quantities, not exceeding a few thousand tons of locomotive coal, are carried annually for consumption on the Midland system. The total increase in the movement of Leicestershire coal since 1857 has exceeded 100 per cent., the greatest increase being in the year 1873, since which a diminution is shown. The revival of trade, however, during the past year shows an improvement; the returns being in excess of previous years.

Some interesting particulars are found in the annual reports of the Associated Coal Owners, showing the total sales of coal in Leicestershire by railway and canal; the sales in 1866 amounted to 658,876 tons. As these returns throw considerable light upon the movement of Leicestershire coal, they will be interesting, as indicating the extent of the industry in the years named :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1866 | 658,876 | 1872 | 426,574 |
| 1867 | 596,988 | 1873 | 381,531 |
| 1868 | 536,294 | 1874 | 392,937 |
| 1869 | 559,377 | 1875 | 302,721 |
| 1870 | 462,427 | 1876 | 213,574 |
| 1871 | 434,716 | | |

These quantities, it should be observed, do not include the local or land sales, nor coals used for iron-making purposes, but refer exclusively to railway and canal sales.

The London and North Western Railway are also carriers of coal from Leicestershire; the quantities, however, have never been considerable, and do not increase. For a few years they carried to stations on their own line, and passed over to other lines, the following tonnages :—

| Year. | Conveyed on Main Line. | Passed over to Other Lines. | Total Carried. |
|-------|------------------------|-----------------------------|----------------|
| | Tons. | Tons. | Tons. |
| 1873 | 52,237 | 6,932 | 59,169 |
| 1874 | 33,607 | ... | 33,607 |
| 1875 | 19,009 | ... | 19,009 |
| 1876 | 12,361 | 185 | 12,546 |
| 1877 | 23,302 | 1,587 | 24,889 |
| 1878 | 32,643 | 2,400 | 35,043 |
| 1879 | 43,256 | 3,256 | 46,512 |
| 1880 | 41,700 | 3,138 | 44,838 |

Some coal is also carried by the Great Northern Railway from Leicestershire to stations between London and Hatfield, and Welwyn and Peterboro'. The quantity carried in 1869 was 6,321 tons; in later years as under :—

| Year. | Quantities | Year. | Quantities. |
|-------|------------|-------|-------------|
| | Tons. | | Tons. |
| 1869 | 6,321 | 1875 | 1,254 |
| 1870 | 6,561 | 1876 | 1,104 |
| 1871 | 1,827 | 1877 | 1,045 |
| 1872 | 1,231 | 1878 | 2,308 |
| 1873 | 1,773 | 1879 | 1,566 |
| 1874 | 1,057 | 1880 | 1,829 |

Population Employed in Coal Mining in Leicestershire.

—In the year 1854 there were 1,646 persons thus engaged; in 1873 the number increased to 3,837, of whom 3,038 were under ground, and 799 above ground; the output of coal amounting to 832,504 tons, compared with 439,000 tons in the year 1854. The particulars for the eight years ending 1880 appear in the subjoined table,* with the average production per man in each year :—

* Reports H.M. Inspectors of Mines.

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 3,038 | 799 | 3,837 | 832,504 | 217 |
| 1874 | 3,896 | 982 | 4,878 | 1,101,402 | 225 |
| 1875 | 3,983 | 1,080 | 5,063 | 1,170,460 | 231 |
| 1876 | 3,435 | 1,145 | 4,580 | 893,204 | 195 |
| 1877 | 3,679 | 1,117 | 4,796 | 1,049,594 | 218 |
| 1878 | 3,188 | 1,089 | 4,277 | 1,021,497 | 239 |
| 1879 | 3,493 | 1,076 | 4,569 | 1,103,294 | 241 |
| 1880 | 3,213 | 1,076 | 4,289 | 1,063,382 | 248 |

Of the persons employed in 1879, the following is an analysis of the respective ages of those engaged under and above ground :—

| Ages. | Under Ground. | Above Ground. |
|---------------------|---------------|---------------|
| | Nos. | Nos. |
| From 12 to 13 . . . | 25 | ... |
| „ 10 to 13 . . . | ... | 6 |
| „ 13 to 16 . . . | 290 | 79 |
| Above 16 . . . | 3,178 | 991 |
| Total . . . | 3,493 | 1,076 |

Resources of the Leicestershire Coal-field and probable Duration.—The total available amount of coal in this coal-field, to depths not exceeding 3,000 feet, allowing for necessary deductions, is 836,799,734 tons. From the Report of the Coal Commission, prepared by Mr. J. T. Woodhouse, the Moira and Coleorton districts are estimated to contain the following quantities, making up the total above referred to as available :—

| Name of District. | TONNAGE. | | |
|-----------------------------|--|-----------------------------|--|
| | Total estimated Tonnage in the District. | Tonnage remaining unworked. | Net Tonnage available for consumption. |
| | Tons. | Tons. | Tons. |
| <i>Outside the Permian,</i> | | | |
| Moira . . . | 825,155,925 | 775,652,338 | 436,304,428 |
| Coleorton . . . | 146,418,084 | 108,303,063 | 60,920,465 |
| <i>Proved Sub-Permian,</i> | | | |
| Moira . . . | 35,642,781 | 31,746,710 | 17,857,518 |
| Coleorton . . . | 595,010,079 | 571,941,921 | 321,717,323 |
| Total . . . | 1,602,226,869 | 1,487,644,032 | 836,799,734 |

In the year 1870 the total production of Leicestershire was 599,450 tons, the year of greatest production being 1875, when 1,154,619 tons were produced, since which date a falling off appears in the output, that in 1879 being 1,085,016 tons. Deducting the output of the ten years ending 1879 there remains about 826,799,734 tons, sufficient to afford supplies, at the rate of output in 1879, for 799 years, and, with increased production, for a less period.

The quantity of coal raised in Leicestershire in 1880, according to the returns of H.M. Inspectors of Mines, was 1,068,382 tons, showing a decrease compared with the previous year of nearly 39,000 tons.

CHAPTER IX.

WARWICKSHIRE COAL-FIELD.

Description of Coal-field and Succession of Strata at Griff Colliery—Production and Distribution of Coal—Cost of Production and Prices—Population Employed in Coal Mining—Resources and probable Duration of Coal-field.

The Warwickshire Coal-Field.—This coal-field extends in a direction bearing south-east to north-west in a narrowing band, by Atherstone and Nuneaton, from the hamlet of Wyken in the immediate neighbourhood of Coventry, to the village of Polesworth in the northern part of the county. The length is between 15 and 16 miles, and in the south, near the Hawkesbury railway station and from thence to Baddesley Ensor, it maintains an average width of from one to two miles. At Baddesley Ensor it widens out, exceeding four miles from east to west, and continues about the same width as far north as Shuttington. The following formations enter into the structure of the district :—

Stratified Rocks { *The Lias.*
The Trias or New Red Sandstone.
The Permian Rocks.
The Coal Measures.

Igneous Rocks, Greenstone.

The Coal Measures, the lowest division of the stratified rocks, consist of :—

Sandstones and Shales.
Upper Coal Measures.
Lower Coal Measures.
Millstone Grit.

The sandstones and shales, occupying the top of the coal measures, have a thickness of 50 feet, at the base of which is a thin bed of limestone, ranging in thickness from two to three feet, and known as the "Spinorbis Limestone." The upper division of the coal measures, 1,400 feet in thickness, contains

five workable seams of coal, which occur near the middle of the series. At the northern end of the coal-field these seams are separated by about 120 feet of shales and sandstones, all decreasing in thickness southwards, while the coal seams remain nearly the same. The following shows the order of the coals, and the thickness of strata between each seam, from a section taken at the Griff colliery north of Bedworth : *—

SUCCESSION OF STRATA.

| | Ft. | In. |
|----------------------------------|-----|-----|
| <i>Four-foot Coal</i> | 3 | 0 |
| Intermediate measures | 51 | 0 |
| <i>Two-yard Coal</i> | 6 | 0 |
| <i>Rider Coal</i> | 2 | 0 |
| Parting | 9 | 0 |
| <i>Bare Coal</i> | 4 | 2 |
| Intermediate measures | 72 | 0 |
| <i>Slate Coal</i> | 10 | 0 |
| Intermediate measures | 84 | 0 |
| <i>Seven-foot Coal</i> | 5 | 9 |

These coal seams crop out on the surface to the east side of the coal-field at the north end near Polesworth, and take a direction south to Wykin near Coventry, where they lie concealed by overlying New Red Sandstone, which rests unconformably upon them.

In the southern part of the coal-field, in the neighbourhood of Bedworth and Hawkesbury, the whole of the coals come together, forming one thick seam, with thin partings of fire clay, whereas in the northern part of the coal-field, as previously stated, in the neighbourhood of Tamworth, Polesworth, and Baddesley, the same beds of coal are widely separated, the intermediate strata of sandstones and shales having thickened out.

The Lower Coal Measures attain a thickness of nearly 1,500 feet, and are barren of coal seams. It was in the shales of the lower part of this series at Hartshill Hays, that manganese was formerly wrought, the red colour of the rocks being probably due to the presence of the iron mixed with that mineral disseminated through them. At the base of the coal measures occurs the Millstone Grit, the lowest part of the carboniferous formation, consisting of a hard silicious quartz rock, with thin bands of interstratified shale, the whole exceedingly altered, and traversed along the strike by intrusive lines of Greenstone.

* "Warwickshire Coal-field," by H. H. Howell, F.G.S.

There are a few ironstone measures in this coal-field, worked but to a limited extent and yielding nine cwts. to the square yard; the ironstone giving on analysis upwards of 40 per cent. of metallic iron.

Production and Distribution of Coal. — Several collieries existed in Warwickshire towards the close of the last century, chiefly in the neighbourhood of Bedworth, Griff, Chilvers Coton, Oldbury, and extending in the same line near to Atherstone, Polesworth, and Wilncot, the coal obtained being described as of a sulphurous quality, making hot durable fires and being sold at from three pence to five pence per hundred weight at the pits.*

The production in the year 1816 amounted to 162,962 Newcastle chaldrons, equivalent to 431,849 statute tons.† In 1854 for the first time appeared the number of coal mines in Warwickshire and the output of coal; since that date the particulars are as follows:—

| Year. | Collieries. | Coal Raised. | Year. | Collieries. | Coal Raised. |
|-------|-------------|--------------|-------|-------------|--------------|
| | Nos. | Tons. | | Nos. | Tons. |
| 1854 | 15 | 255,000 | 1868 | 16 | 624,850 |
| 1855 | 17 | 262,000 | 1869 | 16 | 585,630 |
| 1856 | 16 | 335,000 | 1870 | 18 | 647,540 |
| 1857 | 16 | 398,000 | 1871 | 18 | 723,600 |
| 1858 | 17 | 356,500 | 1872 | 19 | 750,000 |
| 1859 | 17 | 355,750 | 1873 | 24 | 780,000 |
| 1860 | 17 | 545,000 | 1874 | 29 | 851,500 |
| 1861 | 16 | 647,000 | 1875 | 31 | 799,750 |
| 1862 | 16 | 678,000 | 1876 | 29 | 884,750 |
| 1863 | 16 | 685,500 | 1877 | 34 | 930,850 |
| 1864 | 16 | 764,000 | 1878 | 32 | 1,025,450 |
| 1865 | 16 | 859,000 | 1879 | 31 | 1,060,016 |
| 1866 | 15 | 775,000 | 1880 | 31 | 1,101,386 |
| 1867 | 15 | 880,850 | | | |

The distribution is mainly effected by railway and canal. The railways form a close network through the county and coal-field, the London and North Western, Great Western, and Midland coming into Birmingham, while the canals, which are numerous, give access to the Trent, the Mersey, the Thames,

* "General View of the Agriculture of the County of Warwick." By Mr. John Wides, 1794.

† Coal Commission Report, vol. iii., pp. 40, 41.

‡ Estimated production. Returns for those years included in Derbyshire, &c.

and the Severn ; indeed the greater part of the county and the coal-field is intersected by canals. The London and North Western between 1854 and 1868 carried the following tonnages of coal from Warwickshire :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1854 | 196,332 | 1864 | 151,535 |
| 1855 | 150,000 | 1865 | 152,881 |
| 1859 | 54,000 | 1866 | 159,010 |
| 1862 | 98,280 | 1867 | 211,144 |
| 1863 | 156,804 | 1868 | 183,346 |

For subsequent years the coal carried by the London and North Western Railway appears in the annexed table, distinguishing that forwarded to stations on their own line, from that passed on to other railway lines :—

| Year. | London and North-Western. | To Stations on other Lines. | Total. |
|-------|---------------------------|-----------------------------|---------|
| | Tons. | Tons. | Tons. |
| 1868 | 159,348 | 23,998 | 183,346 |
| 1869 | 145,849 | 38,037 | 183,886 |
| 1870 | 148,571 | 39,360 | 187,931 |
| 1871 | 173,663 | 38,716 | 212,379 |
| 1872 | 178,889 | 50,126 | 229,015 |
| 1873 | 187,377 | 61,073 | 248,450 |
| 1874 | 128,874 | 85,250 | 214,124 |
| 1875 | 127,702 | 80,542 | 208,244 |
| 1876 | 146,319 | 101,991 | 248,310 |
| 1877 | 145,178 | 103,960 | 249,138 |
| 1878 | 184,275 | 124,245 | 308,520 |
| 1879 | 177,465 | 118,970 | 296,435 |
| 1880 | 171,673 | 134,579 | 306,252 |

The Midland Railway also contributes to the distribution of coal, extending from Derby through Tamworth, and from Leicester to Nuneaton and Whitacre junction, and thence to Birmingham ; other branches bringing it in communication with the London and North Western line. The Midland Railway carried the quantities stated below in each of the following years :—

| Year. | Coal Carried. | Year. | Coal Carried. |
|-------|---------------|-------|---------------|
| | Tons. | | Tons. |
| 1857 | 28,010 | 1869 | 62,903 |
| 1858 | 28,907 | 1870 | 75,863 |
| 1859 | 38,489 | 1871 | 86,826 |
| 1860 | 20,000 | 1872 | 119,122 |
| 1861 | * | 1873 | 158,799 |
| 1862 | * | 1874 | 162,512 |
| 1863 | 79,809 | 1875 | 174,442 |
| 1864 | 85,922 | 1876 | 165,085 |
| 1865 | 86,069 | 1877 | 164,279 |
| 1866 | 74,751 | 1878 | 233,022 |
| 1867 | 60,134 | 1879 | 295,673 |
| 1868 | 60,093 | 1880 | 308,697 |

During the year 1880 the quantity of coal carried by the Midland Railway amounted to 308,697 tons, showing an increase of 13,024 tons, compared with the previous year.

Cost of Production and Prices.—Much of the coal raised in Warwickshire is used for domestic purposes, the small being employed for lime and brick burning. When stacked and exposed to the weather, a considerable amount of small softened coal is found after the removal of the bulk. In 1830, Mr. Thomas Smith gives the average profit per ton on working the best coals as 3*s.* 10*d.* per ton, the average price being 10*s.* 10*d.*; the real average being reduced by the lower price of the small coal to about 9*s.* 3*d.* per ton and the profit to 2*s.* 3*d.* per ton, the cost of getting, work, and royalty in all cases at that period amounting to about 7*s.* per ton.

The entire produce per acre of all the coal seams worked, amounting to 14,521 tons of coals, and 1,086 tons of lumps or cobbles, giving a total of 15,607 tons per acre, the total quantity left in the workings in the form of ribs, being about 1,612 tons per acre. Upon the usual mode of working at this period, each man got per day two tons three cwt. of coal; each ton costing, in loading, drawing out, banking, and loading into waggons, from 1*s.* 3*d.* to 1*s.* 6*d.*, timber, powder, and sundries included.†

In the year 1870‡ the following were the prices at the pit's mouth at the undermentioned collieries in Warwickshire:—

Bedworth, average, 6*s.* 9*d.*

Glascote, best, 10*s.*; slack, 2*s.* 6*d.*

Griff, average, 7*s.* 6*d.*

Peel, best, 6*s.* 8*d.*; slack, 3*s.* 4*d.*

Wyken, best, 6*s.* 2*d.*; slack, 3*s.* 4*d.*

* Not separately distinguished.

† Miner's Guide, 1836, p. 141.

‡ Coal Commission Report, vol. iii., Appendix, p. 212.

Ten years later the average, highest, and lowest prices of coal and slack at the pit's mouth were as follows:—

| Prices. | 1880. | | 1879. | |
|-------------------|--------------|--------------|--------------|--------------|
| | Coal. | Slack. | Coal. | Slack. |
| Average | s. d. 6 6 | s. d. 4 6 | s. d. 7 2 | s. d. 4 0 |
| Highest | 7 5 | 5 6 | 9 0 | 5 6 |
| Lowest | 6 0 | 2 0 | 6 0 | 2 0 |

Population employed in Coal Mining in Warwickshire.—

In 1854 there were 1,646 persons engaged in coal mining, producing 255,000 tons of coal. Twenty-five years later the production of the coal-field was fourfold, exhibiting remarkable progress; the details of the eight years ending 1880 are as follows, with the output of the coal-field and the average produce per man.*

| Year. | PERSONS EMPLOYED. | | Total. | Coal raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 3,578 | 1,070 | 4,648 | 832,387 | 179 |
| 1874 | 3,659 | 1,134 | 4,793 | 852,774 | 178 |
| 1875 | 3,505 | 1,099 | 4,604 | 803,851 | 174 |
| 1876 | 3,453 | 1,124 | 4,577 | 896,246 | 195 |
| 1877 | 2,990 | 1,022 | 4,012 | 922,879 | 230 |
| 1878 | 3,159 | 1,032 | 4,191 | 1,022,915 | 243 |
| 1879 | 3,244 | 1,020 | 4,264 | 1,054,759 | 247 |
| 1880 | 3,207 | 986 | 4,193 | 1,101,386 | 263 |

The steady working of the mines appears in the average output, giving an increase in the eight years of 84 tons, equal to 46 per cent. per man.

The ages of all employed in the year 1879, under and above ground, were as follows:—

| Ages. | Under Ground. | Above Ground. |
|---------------------|---------------|---------------|
| | Nos. | Nos. |
| From 12 to 13 . . . | 17 | ... |
| „ 10 to 13 . . . | ... | 3 |
| „ 13 to 16 . . . | 239 | 76 |
| Above 16 | 2,988 | 941 |
| Total | 3,244 | 1,020 |

* Reports of H.M. Inspectors of Mines.

Resources of the Warwickshire Coal-field and probable Duration.—The total acreage of coal in this coal-field to a depth less than 3,000 feet has been estimated by Mr. J. T. Woodhouse at 163,617 acres, of which 153,909 acres remained unworked in the year 1870. This acreage is thus distributed :—

| Name of District. | Total Acreage. | Acreage Unworked. |
|-----------------------|----------------|-------------------|
| Outside the Permian . | 161,196 | 152,785 |
| Proved Sub-Permian . | 2,421 | 1,124 |
| Total acres . | 163,617 | 153,909 |

Converting the total acreage into tons, at the estimated rate of 1,556 tons per acre per foot thick, there existed originally in this coal-field 995,511,270 tons, the acreage unworked amounting to 815,382,625 tons; and of this quantity there remains—due allowance being made for coals which cannot be worked from various causes—458,652,714 tons. The details of these enumerated quantities are thus given in the Coal Commission Report : *—

| District. | Total estimated Tonnage in Warwickshire. | Tonnage remaining unworked. | Net Tonnage available for consumption. |
|-----------------------|--|-----------------------------|--|
| | Tons. | Tons. | Tons. |
| Outside the Permian . | 880,033,153 | 809,730,113 | 455,473,182 |
| Proved Sub-Permian . | 115,478,117 | 5,652,512 | 3,179,532 |
| Total . | 995,511,270 | 815,382,625 | 458,652,714 |

The total quantity of coal wrought during the ten years ending 1879 amounts to 8,473,456 tons; deducted from the original estimate leaves 450,179,258 tons available for future consumption. This quantity, taking the average of the ten years (847,345 tons), would afford sufficient supplies for 531 years hence, while taking the production of 1879 (1,060,016 tons), the exhaustion of the coal-field would occur in about 425 years. It should be observed that the estimate of coal in Warwickshire includes all workable seams not exceeding a depth of 3,000 feet, and that the output of the coal-field has quadrupled in a quarter of a century, the production of 1880 exceeding that of the previous year by 46,627 tons.

* Vol. i. p. 31.

CHAPTER X.

SHROPSHIRE COAL-FIELDS.

Description of Coal-fields, and Section of Strata at Coalbrookdale—Analyses, Production, and Distribution of Coal—Prices and Cost of Production—Population employed in Coal and Iron Mining—Resources and probable Duration of Coal-field.

The Shropshire Coal-fields.—The coal deposits of Shropshire are not found occurring in one unbroken area, like those of the Great Midland coal-fields of Yorkshire and Derbyshire, but rather in several detached tracts or areas, all referable, geologically, to the same age. Of these the most important is the coal-field of Coalbrookdale; the others are those of Shrewsbury, Oswestry, the Clee Hills, and the Forest of Wyre.

The Coalbrookdale coal-field has an area of twenty-eight square miles, and extends from the Severn, near Broseley and Iron-bridge on the south, having an irregular western boundary at Coalbrookdale, Little Wenlock, and the faults a mile or two to the eastward of Wellington, where it has its greatest width of about four or five miles; it then, becoming gradually narrower, extends to Lilleshall and Church Aston. The greatest thickness of the coal measures in this area exceeds 1,200 feet, in which occur several important seams of coal. Professor Hull gives the following succession of coal seams, and their varying thickness in the Coalbrookdale coal-field.*

| COAL SEAMS. | | THICKNESS. | |
|--------------------------------------|---|------------|---------|
| | | Ft. In. | Ft. In. |
| 1. Chance Pennystone Coal | } Found only at north end of coal-field. | | |
| 2. Fungus Coal | | | |
| 3. Gur Coal | | | |
| 4. Top Coal. | from | 4 0 | to 4 6 |
| 5. Half-yard Coal | | | 1 6 |
| 6. Double Coal | | 5 0 | to 6 0 |
| 7. Yard Coal | | 2 6 | „ 3 0 |
| 8. Big Flint Coal | | 3 0 | „ 4 6 |
| 9. Stinking Coal | | 3 0 | „ 4 0 |
| 10. Clunch Coal | | | 2 0 |
| 11. Two-foot and Best (with parting) | | | 3 4 |
| 12. Randle and Clod Coal | | 4 0 | to 5 0 |
| 13. Little Flint Coal | | 1 6 | „ 2 3 |

* "Coal-fields of Great Britain," 4th edition, p. 143.

The aggregate average thickness of the seams exceeding two feet in this section, is equal to 27 feet of solid coal. It is observable that in passing from the north to the south of the coal-field the thickness of the measures and of the seams of coal diminishes considerably. This appears in the following table, showing the number of seams existing in different parts of the coal-field, and how much they vary in their dimensions in the pits referred to, the united thickness of the mass of coal in any one pit not being dependent upon the number of the seams : *—

| Pits. | Thickness of Coal. | | | No. of Beds of Coal. |
|---------------------|--------------------|-----|-----|----------------------|
| | Yds. | Ft. | In. | |
| Hadley | 15 | 0 | 0 | 16 |
| Sned's Hill | 14 | 2 | 2 | 12 |
| Malinslee | 11 | 0 | 10 | 13 |
| Langley | 11 | 2 | 6 | 11 |
| Dawley | 14 | 0 | 0 | 16 |
| Lightmoor | 13 | 2 | 0 | 17 |
| Madeley | 10 | 2 | 10 | 24 |
| Broseley | 7 | 0 | 9 | 13 |

The Shrewsbury coal-field is of less extent than that of Coalbrookdale, and forms a narrow band from the base of Haughmond Hill, east of Shrewsbury, to the river Severn, near Alberbury, a distance of eighteen miles, its greatest width in any one place not exceeding one mile. In the lower part of the coal measures there are two or three seams of coal worked, but only to a limited extent. The other coal areas of Oswestry and the Forest of Wyre possess some workable seams of coal, but their production is not very considerable. They are thus referred to by a writer in the *Colliery Guardian* † familiar with the district : “ The seam won at Highley is not quite 4 feet thick of good coal ; there is a roof of clod some 2 feet 9 inches thick, and a bat of 9 or 10 inches. At Billingsley this same seam, at a depth of 155 yards, has a thickness of 6 feet 9 inches gross, and they have in addition a ‘ half-yard,’ ‘ four-feet,’ and a ‘ two-feet ’ seam, besides the top or sulphur coal ; they also have seams of fire-clay (one over the Brooch coal) and ironstone, which do not appear at Highley.” Billingsley is situated some two miles to the north-west of the last-mentioned

* Coal Commission Report, Vol. iii., p. 122.

† Vol. xxxviii., Nov. 28, 1879, p. 854.

place, and it appears that the seams of coal between the two places thin out to the east of the coal-field.

Analysis of the Coal. — The following coals, extensively employed in the iron-works of the district, give, upon examination, the annexed results, each 100 parts of coal consisting of—

| Name and Locality. | Volatile Matter. | Carbon. | Ashes. | Specific Gravity. |
|--------------------------------|------------------|---------|--------|-------------------|
| Fungus Coal (Donnington) . | 34·8 | 63·8 | 1·4 | 1·245 |
| Top Coal . . . | 37·1 | 62·1 | 0·8 | 1·267 |
| Flint Coal (Madeley) . . . | 34·6 | 64·9 | 0·5 | 1·269 |
| Sulphur Coal (Ketley) . . . | 41·1 | 56·1 | 2·8 | 1·292 |
| Best Coal (Madeley) . . . | 34·3 | 64·4 | 1·3 | 1·273 |
| Clod Coal . . . | 37·3 | 62·7 | 1·0 | 1·264 |
| Little Flint Coal (Broseley) . | 38·3 | 61·1 | 0·9 | ... |

The Top, Yard, Double, and Big Flint coals, are largely employed for manufacturing purposes; the Clod Coal and Little Flint being most valued for iron smelting, while the "Fungus Coal," chiefly confined to the northern area of the coal-field, is alike useful for all purposes where coal is employed.

Production and Distribution of Coal. — The earliest information appears for the year 1854, when the 48 collieries in the county raised 1,080,000 tons, which were chiefly employed in the iron works and for local consumption. Since 1854, the number of collieries and production of coal are shown in the following table :—

| Year. | Collieries. | Coal. | Year. | Collieries. | Coal. |
|-------|-------------|-----------|-------|-------------|-----------|
| | No. | Tons. | | No. | Tons. |
| 1855 | 56 | 1,105,250 | 1868 | 64 | 1,495,500 |
| 1856 | 55 | 752,100 | 1869 | 59 | 1,392,862 |
| 1857 | 55 | 750,000 | 1870 | 59 | 1,343,300 |
| 1858 | 57 | 749,360 | 1871 | 59 | 1,350,000 |
| 1859 | 59 | 765,750 | 1872 | 60 | * |
| 1860 | 68 | 850,000 | 1873 | 60 | 1,570,000 |
| 1861 | 66 | 829,750 | 1874 | 65 | 1,187,950 |
| 1862 | 65 | 1,029,750 | 1875 | 64 | 1,225,785 |
| 1863 | 66 | 1,150,000 | 1876 | 64 | 1,054,049 |
| 1864 | 66 | 1,150,000 | 1877 | 61 | 927,580 |
| 1865 | 69 | 1,135,000 | 1878 | 63 | 830,575 |
| 1866 | 63 | 1,220,000 | 1879 | 62 | 854,380 |
| 1867 | 62 | 1,558,500 | 1880 | 66 | 905,000 |

* Included in the returns of production for North Staffordshire and Cheshire.

To the distribution of the Shropshire coal, the London and North Western Railway principally contributes: in 1863, the earliest return is met with, when 88,167 tons were carried out of the county, and in 1865 but 75,230 tons; the Great Western Railway, in the same year, carrying 795 tons into South Staffordshire. The quantities carried in later years appear as follows, together with that passed over to other lines by the—

LONDON AND NORTH WESTERN RAILWAY.

| Year. | To Stations on Line. | To other Lines. | Total carried. |
|-------|----------------------|-----------------|----------------|
| | Tons. | Tons. | Tons. |
| 1867 | 45,936 | ... | 45,936 |
| 1868 | 59,186 | ... | 59,186 |
| 1869 | 116,020 | 1,777 | 117,797 |
| 1870 | 113,947 | 3,370 | 117,317 |
| 1871 | 109,519 | 5,077 | 114,596 |
| 1872 | 105,461 | 4,803 | 110,364 |
| 1873 | 100,354 | 7,226 | 107,580 |
| 1874 | 99,532 | 7,559 | 107,091 |
| 1875 | 99,529 | 6,818 | 106,347 |
| 1876 | 88,374 | 3,688 | 92,062 |
| 1877 | 101,552 | 3,090 | 104,642 |
| 1878 | 82,862 | 2,845 | 85,707 |
| 1879 | 65,230 | 3,885 | 69,115 |
| 1880 | 103,502 | 2,831 | 106,333 |

Prices and Cost of Production. — Forty years ago this question was carefully considered, both as regards coal and iron-stone; * the Fungus Coal, the uppermost in the series, yielding 15 cwts. of marketable coal to each cubic yard, of which 10 cwts. were large coal, 2 cwts. lumps, and 3 cwts. slack. At this period the cuttings, or perpendicular channellings, to facilitate the bringing down of the coals, were situated at from four to five yards distance from each other, and to bring down and clear away the usual line of 30 yards in one day cost £2 3s., distributed as follows:—

| | | | |
|----------------------------------|-----------|----------|----------|
| | £ | s. | d. |
| 3 holers at 2s. 9d. per day | 0 | 8 | 3 |
| 3 brushers and cloggers, 3s. 3d. | 0 | 9 | 9 |
| Drawing out | 1 | 5 | 0 |
| Total | £2 | 3 | 0 |

and producing of coals, 17 tons; lumps, 8 tons 8 cwts., and slack, 5 tons 2 cwts., in all a total of 25 tons 10 cwts. The cost

* Thomas Smith's "Miner's Guide," 1836, p. 118.

and production of each seam of coal (per ton) appear in the sub-joined statement :—

| Name of Coal Seams. | Thickness. | COST PER TON. | | |
|---------------------------------------|-------------|---------------|------------|------------|
| | | Coals. | Lumps. | Slack. |
| | Yds. Ft. | s. d. | s. d. | s. d. |
| Fungus Coal | 1 0 | 2 0½ | 1 2 | 1 0 |
| Stone | 1 1 | 1 11 | 1 2 | 1 0 |
| Top | 1 2 | 1 7 | 1 2 | 1 0 |
| Double | 2 0 | 1 9 | 1 2 | 1 0 |
| Yard | 1 0 | 2 0 | 1 2 | 1 0 |
| Flint | 1 2 | 1 10½ | 1 2 | 1 0 |
| Randle and Clod . . . | 2 1 | 1 9 | 1 2 | 1 0 |
| Total | 11 0 | 12 11 | 8 2 | 7 0 |
| Average cost | | 1 10 | 1 2 | 1 0 |
| Dead work | | 2 0 | 2 0 | 2 0 |
| Royalty | | 0 8 | 0 4 | 0 2 |
| Average cost per ton | | 4 6 | 3 6 | 3 2 |

The same authority, considering the yield per acre of the above seams of coal, estimates the produce as follows, to which is added the royalty per ton, and the total royalty per acre :—

| | Produce per Acre. | Royalty. | Amount of Royalty. |
|-----------------|-------------------|----------|--------------------|
| | Tons. | s. d. | £ s. d. |
| Coals | 26,620 | 0 8 | 887 6 8 |
| Lumps | 5,324 | 0 4 | 88 14 8 |
| Slack | 7,986 | 0 2 | 66 11 0 |

Again, the average quantity of coal wrought by each man per day is stated as follows :—

| Coal Seams. | Coals. | Lumps. | Slack. |
|----------------------------------|------------------|------------------|------------------|
| | Tons. Cwts. Qrs. | Tons. Cwts. Qrs. | Tons. Cwts. Qrs. |
| Fungus | 2 16 2 | 0 11 1 | 0 17 0 |
| Stone | 3 4 2 | 0 12 3 | 0 19 1 |
| Top | 5 13 1 | 0 0 0 | 1 8 2 |
| Double | 3 15 2 | 0 15 0 | 1 2 2 |
| Yard | 3 0 0 | 0 12 0 | 0 18 0 |
| Flint | 3 6 2 | 0 13 1 | 1 0 0 |
| Randle and Clod . . . | 5 14 1 | 1 2 3 | 1 14 1 |
| Total per day | 27 10 2 | 4 7 0 | 7 19 2 |
| Average per day | 3 18 2 | 0 12 2 | 1 2 3 |

The aggregate of these totals gives an average of 5 tons 18 cwt. 3 qrs. got by each miner per day of coal from the above-named seams of coal.

Following the prices obtained per ton at the pit's bank in 1868, the annexed shows generally the average: Top Coal, at Old Park Colliery, 10*s.* 4*d.* per ton; Double Coal, 8*s.* 6*d.*; Yard Coal, 8*s.* 6*d.*; Flint, 9*s.* 6*d.* to 10*s.*; New Mine, 6*s.* 6*d.*; Two-foot, 8*s.*, and Little Flint, 10*s.* 4*d.* per ton.

Mr. T. Parton, F.G.S., in his notes on the Shropshire coal-field,* writing in the year 1868, states that at that time the cost of extracting the coal and ironstone varied according to special circumstances, and gives the annexed as the prices delivered on colliery bank as a very close approximation:—

| | from | <i>s.</i> | <i>d.</i> | to | <i>s.</i> | <i>d.</i> |
|----------------------------------|------|-----------|-----------|----|-----------|-----------|
| Top Coal | from | 3 | 0 | to | 4 | 0 |
| Double Coal | „ | 2 | 6 | „ | 3 | 0 |
| Yard Coal | „ | 3 | 6 | „ | 4 | 6 |
| Blue Flatt Ironstone | „ | 7 | 0 | „ | 10 | 0 |
| White Flatt Ironstone | „ | 9 | 0 | „ | 11 | 0 |
| Big Flint Coal | „ | 3 | 0 | „ | 3 | 6 |
| Penny Stone Ironstone | „ | 6 | 0 | „ | 9 | 0 |
| Stinking Coal | „ | 3 | 0 | „ | 4 | 0 |
| Two-foot and Best Coal | „ | 3 | 0 | „ | 4 | 3 |
| Randle Coal | „ | 3 | 0 | „ | 3 | 6 |
| Clod Coal | „ | 3 | 0 | „ | 4 | 0 |
| Little Flint | „ | 4 | 6 | „ | 6 | 0 |

These prices may be regarded as the highest and lowest incurred in getting the coals and ironstones, fluctuating according to the rate of wages.

The average prices of coal and slack during the years 1878 and 1879 exhibit but little variation, and in the last-named year were quoted as follows, to which is added the highest and lowest prices ruling throughout the year:—

| Year. | | Average. | Highest. | Lowest. |
|-------|-----------------|---------------------|---------------------|---------------------|
| | | <i>s.</i> <i>d.</i> | <i>s.</i> <i>d.</i> | <i>s.</i> <i>d.</i> |
| 1879 | Coal | 8 9 | 13 4 | 6 0 |
| | Slack | 3 10 | 5 10 | 2 6 |
| 1880 | Coal | 9 2 | 13 4 | 6 8 |
| | Slack | 4 3 | 6 3 | 2 6 |

Comparing these prices with those ruling in the year 1873,

* Vol. xv. "Colliery Guardian," 1868, p. 223.

known as the year of the "Coal Famine," it appears, in evidence before the Select Committee on Coal,* that in Shropshire, Cheshire, and North Staffordshire, the price of coal per ton in these districts rose from 7*s.* 6*d.* to 20*s.*, while as regards slack, which previous to the year 1872 was sold from 2*s.* 3*d.* to 2*s.* 6*d.* per ton, it rose in this last-named year to 10*s.* 6*d.*; the great demand for coal at this period arising in Shropshire from the iron manufactures, and in Staffordshire from the earthenware industries.

Population employed in Coal and Iron Mining.—The number of male persons employed in coal and iron mining in Shropshire, according to official returns for the year 1854, was 5,722; of these 4,580 persons were engaged in coal mining, and 1,142 in iron mining, the yield of coal the same year being 1,080,000 tons. In later returns the persons employed are included in other districts, but when the Coal Mines Regulation Act, 1872, came into operation, and since, very complete accounts have appeared in the Reports of Her Majesty's Inspectors of Mines, showing the number engaged under ground and above ground, together with the quantities of coal raised. These details appear in the annexed table, to which is added the average tonnage of coal raised per person in each year:—

| Year. | PERSONS EMPLOYED. | | | Coal raised. | Average per Man. | Total Minerals raised.† | Average per Man. |
|-------|-------------------|------------------|--------|--------------------|------------------------|-------------------------------|------------------------|
| | Under Ground. | Above Ground. | Total. | | | | |
| 1873 | ... | ... | ... | Tons. 1,262,490 | Tons. ... | Tons. 1,858,870 | Tons. ... |
| 1874 | 5,635 | 2,487 | 8,122 | 1,188,490 | 146 | 1,623,310 | 200 |
| 1875 | 5,513 | 2,204 | 7,717 | 1,225,180 | 158 | 1,721,720 | 223 |
| 1876 | 4,684 | 1,896 | 6,580 | 1,059,740 | 161 | 1,558,840 | 236 |
| 1877 | 4,191 | 1,583 | 5,774 | 921,700 | 159 | 1,343,370 | 233 |
| 1878 | 3,766 | 1,468 | 5,234 | 827,200 | 158 | 1,195,600 | 213 |
| 1879 | 3,423 | 1,348 | 4,771 | 822,400 | 172 | 995,295 | 208 |
| 1880 | 3,546 | 1,235 | 4,781 | 905,000 | 189 | 1,168,900 | 244 |

The total of persons given as employed in coal mining also includes those engaged in raising fire-clay and ironstone; it is therefore desirable to take the total of minerals raised to follow more clearly the average produce per man, which appears in the last column.

* Mr. Thomas Wynne, H.M. Inspector of Coal Mines. Report, Coal, 1873, p. 42.

† Including coal, fireclay, and ironstone.

Resources and probable Duration of Coal-field.—In the Report of the Royal Coal Commission, the quantity of unworked coal remaining in the Shropshire field is included in the returns of South Staffordshire and East Worcestershire. It has, however, been estimated by reliable authorities that the available coal remaining in Shropshire did not exceed 20,000,000 tons in the year 1870. At the then rate of production, 1,848,800 tons, the exhaustion of the deposits may be expected at no very distant period. Since that date, however, the production has fallen off, being only 822,400 tons in the year 1879, compared with 905,000 tons in 1880, showing an increase of 82,600 tons in the last-named year.

CHAPTER XI.

NORTH STAFFORDSHIRE COAL-FIELD.

Description of Coal-field, its Extent, Area, and Succession of Strata—Coal Seams and Ironstone Measures—Cheadle Coal-field—Analyses, Production, and Distribution of Coal—Quantities Consumed in Ironworks, Potteries, Brick-works, &c.—Price of Coal and Cost of Production—Population Employed in Coal and Ironstone Mining—Resources and probable Duration.

North Staffordshire Coal-field.—This coal-field is remarkable for the number and richness of its beds of coal and ironstone. The coal-field is triangular in form, with its apex at the base of Congleton Edge, and deeply indented along its southern margin by spurs of the Permian formation, which runs far into the heart of the coal measures through the agency of faults. The coal-field has an area of 75 square miles and even more, if the coal lying under the Permian rocks to the south were included. It extends from Handford Lane End and Longton on the south, to Biddulph on the north, again from Oakmoor and Cheddleton on the east to Madeley on the west. Its resources of coal and ironstone greatly exceed that of the South Staffordshire coal-field, though smaller in its area. It has twice the thickness of workable coal, and many of the seams of coal are roofed by measures of rich argillaceous ores of iron.

The coal measures are divided into upper, middle, and lower measures; the upper series of which is barren of profitable coal, while the middle, or pottery coal and ironstone measures, 4,000 feet thick, contain no less than 40 seams of coal, besides numerous bands of ironstone. The lower division includes beds of black shales and flags, with 17 or 18 seams of coal, each having a thickness exceeding two feet. In one area of this coal-field a thickness amounting in the aggregate to 140 feet of coal exists; in another, where 24 seams of coal occur, a total thickness of 109 feet of coal has been ascertained, interstratified with numerous courses of "black band" or carbonaceous iron ore, varying from two to six feet in thickness, and crowded with the characteristic fossil shells "Anthracosia" and "Anthracomya."

The annexed section shows the order of occurrence of the several coal seams and intervening strata, with the respective thicknesses :—

| COAL SEAMS AND INTERVENING STRATA. | THICKNESS. | |
|---------------------------------------|------------|-----|
| | Ft. | In. |
| <i>Peacock Coal</i> | 6 | 6 |
| Strata | 20 | 0 |
| <i>Spencroft Coal</i> | 3 | 9 |
| Strata | 121 | 0 |
| <i>Great Row Coal</i> | 8 | 0 |
| Strata | 71 | 0 |
| <i>Cannel Row Coal</i> | 5 | 0 |
| Strata | 54 | 0 |
| <i>Wood Mine Coal</i> | 2 | 0 |
| Strata | 29 | 0 |
| <i>Deep Mine Coal</i> | 2 | 8 |
| Strata | 361 | 0 |
| <i>Winghay Coal</i> | 4 | 6 |
| Strata | 377 | 0 |
| <i>Ash or Rowhurst Coal</i> | 8 | 0 |
| Strata | 121 | 0 |
| <i>Burnwood Coal</i> | 5 | 0 |
| Strata | 68 | 0 |
| <i>Golden Twist</i> | 3 | 6 |
| Strata | 486 | 0 |
| <i>Mossfield Coal</i> | 4 | 7 |
| Strata | 30 | 0 |
| <i>Coal</i> | 3 | 0 |
| Strata | 270 | 0 |
| <i>Birches Coal</i> | 4 | 6 |
| Strata | 300 | 0 |
| <i>Ten-foot Coal</i> | 6 | 0 |
| Strata | 102 | 0 |
| <i>Bowley Alley Coal</i> | 4 | 6 |
| Strata | 81 | 0 |
| <i>Holly Lane Coal</i> | 5 | 10 |
| Strata | 84 | 0 |
| <i>Sparrow Batts Coal</i> | 4 | 9 |
| Strata | 222 | 0 |
| <i>Flats Coal</i> | 3 | 0 |
| Strata | 108 | 0 |
| <i>Frog's Row Coal</i> | 4 | 6 |
| Strata | 30 | 0 |
| <i>Cockhead Coal</i> | 4 | 6 |
| Strata | 420 | 0 |
| <i>Bulthurst Coal</i> | 4 | 0 |
| Strata | 60 | 0 |
| <i>Winpenny Coal</i> | 3 | 0 |

In the northern part of the coal-field at Rugged Mow Cop, to the south of Congleton, some sixteen coal basins or coal areas, more or less separated, can be distinguished, all geologically of the same age. The resources of this coal-field are considerable, presenting a total thickness of 150 feet of coal, and an available

quantity for future use amounting to 4,826 millions of tons of coal, as ascertained by the Royal Coal Commission, allowing for necessary deductions; while if the whole of the workable seams of coal and ironstone were spread over the area of the coal-field, the solid thickness of coal would be represented by 32 feet, and the ironstone by a thickness of five feet.

The ironstone deposits of this coal-field are no less remarkable than the seams of coal; they are extremely numerous, and exist abundantly in the districts of Longton, Hanley, and Newcastle-under-Lyme. In a section of measures at the Longton Colliery of 250 yards nine distinct seams are worked. At Apedale, three miles north-west of Newcastle-under-Lyme, the principal measures occurring are the "*Black Band*," "*Red Shag*," "*Bassy Mine*," and "*Red Mine*," having a thickness respectively of four, six, seven, and nine feet. The following are the more important measures of ironstone worked, the yield varying according to the thickness and regularity of the seams.*

At Shelton the "*Red Shag*," a black band ironstone, has a thickness, exclusive of shaly partings, of from 15 to 17 inches, lying immediately upon a seam of coal 12 inches thick; this ironstone is extensively exported in a calcined state to the districts of South Staffordshire. This ironstone contains so large a proportion of carbonaceous matter, that no coal is required for its calcination.

The "*Gutter ironstone*," though somewhat poor at Shelton, is said to be the same measure between Chesterton and the mouth of the Harecastle tunnel, where it attains the great thickness of six feet; this stone, when mingled in certain proportions after calcination with hæmatite, is employed as a "puddle ore."

The "*Red Mine*" of Silverdale and Apedale, next in descending order, lies upon a seam of coal two feet thick; the ironstone measure is variable in thickness, the average of which may be taken as 14 inches.

The "*Bassy Mine*," also called "*Red Mine*," is a measure well developed in the eastern part of the coal-field, where it has been extensively wrought. This measure at Shelton has a thickness of 30 inches, and is calcined in large heaps of 2,000 tons, parts of another measure called the "*Cannel Row*" being used in certain proportions to assist in the calcination. At the

* "Iron Ores of Great Britain," Part iv., pp. 272-3.

Lane End Iron Works these "black band" measures, that is the "Red Shag" and "Red Mine," are employed in about equal proportions with argillaceous ironstone, chiefly the "*Pennystone*," with the addition of some hæmatite from the west coast, in the manufacture of pig iron.

The Cannel Mine next occurs ; at Apedale it is described as a black dull compact ironstone, with a fracture slightly conchoidal, and calc spar sparingly exhibited in the faces of the joints. Six beds of these nodules, together 12 inches thick, occur in a section of five feet six inches, and it is reported to yield about 18 cwts. of ironstone to the square yard.

The "*Gabbin ironstone*" measure, occurring some 20 feet below the Spencroft Coal, is a measure from 13 to 16 inches in thickness, interstratified with partings of shale, and bearing a strong resemblance to the measure of the same name in South Staffordshire.

The "*Cannel Row*" and the "*Pennystone*" measures of Shelton are other important seams, the latter consisting of three bands of an aggregate thickness of 20 inches, the lowest band being from 10 to 12 inches in thickness, consisting of a brown stripy coarse-grained stone, with occasional laminæ of black shale, and containing broken fossil remains, and occasional crystalline portions of zinc blende.

The "*Deep Mine*" and "*Chalky Mine*" at Lane End : the former consisting of three bands, and generally regarded as the richest measure of the district, yielding 10 cwts. per square yard ; while the latter, 12 inches in thickness in four bands, yields an average of 12 cwts. of ironstone per square yard. A few other ironstone measures occur in depth, notably the New Mine, Little Mine, and Brownstone, capable of producing from 10 to 12 cwts. to the yard. Fish remains are found in quantity in the associated shales of these measures.

The Cheadle Coal-field.—This coal-field is of comparatively small area, its breadth from east to west being about four miles, while its length from Ipstones to Mobberley has a range of five miles. The coal-field is but slightly productive, being composed of only the lower strata of the formation. Near the town of Cheadle the following seams are worked :—

Two-yard Coal.
Half-yard Coal.
Yard Coal.

Littley Coal.
Four-foot Coal.
Woodhead Coal, 3 ft. thick.

These seams crop out towards the north, west, and east, making a sort of trough, and they ultimately pass below the new red sandstone, between Dilhorne and Mobberley towards the south. To the north of the coal-field rise the high moorlands of the millstone grit; and the strata which immediately overlie this formation are finely opened up by the deep channel of the river Churnet. The coal measures reposing on the millstone grit give a thickness of about 370 yards, in which at intervals occur bands of argillaceous ironstone.

The working of the coal and ironstone in North Staffordshire presents some interesting features, which are thus described. Owing to the high dip of the beds of this coal-field, 14 to 16 inches to the foot, the coal has to be worked by system of pillars 40 feet long by only 10 feet thick, the great inclination not allowing them to be any broader. The mode of working adopted is thus explained. The main level or "horse road" is driven horizontally with the cleat of the coal, together with an "air head" 10 yards off on the upper side, which is thirled into every 20 yards for ventilation. This air head afterwards takes the return air from the workings to the "up take," and no miner is allowed to enter it. At every 160 yards a bord or break dip (so called from a break situated at the top to allow the full car to pull up the empty one) is driven "up bank" at right angles to the main level, the longest being 110 yards. A smaller bord for air is likewise run up beside this and thirled into every ten yards. On reaching the top, two drifts are put out from each break dip at 10 yards apart, and the air "bratticed" up by canvas for 40 yards, when it is thirled. These drifts from either side meet at 80 yards, and, after thirling again, the narrow pillars (of 40 by 10 yards, as before mentioned) are worked away against the cleat, the air being made to pass along the face of the work. As soon as taking away the pillars above is fairly commenced, the next drift is driven, so that the working of the pillar above is always slightly in advance of that immediately below.

The ironstone, occurring in measures of varying thickness, is worked nearer the surface on the west (well seen at New Chapel), where the dip is inconsiderable. Owing to the thin beds, ponies are used entirely, and the mode of getting the stone to the main levels is one of the most primitive to be seen anywhere. A man loads the ore on a wooden sleigh, which he then drags on his

hands and knees, through a small road, made through the Gob by packing up with stones on each side. The ironstone is worked away in a face of 30 yards by "holing" the shale below, and putting the shot in above.

Analyses of the Coal.—The following analyses of coals raised by the Chatterley Iron Company from their Whitfield Colliery, near Tunstall, are given by Mr. Charles Homer, F.G.S., in his paper on the North Staffordshire Coal-field and the ironstone measures contained therein.* The coal seams examined were as follows :—

Little Row Coal.—Worked at a depth of 781 yds., 2 ft. 9 in. to 3 ft. 3 in. thick, a good household coal, sold chiefly in the London market; is of a fine bright appearance and of first-class quality.

Old Whitfield Coal.—Worked at a depth of 801 yds.; the seam is 3 ft. 9 in. thick; is a good blast-furnace, steam, and manufacturing coal, and is also in demand for household purposes.

Bowling Alley Coal.—Worked at a depth of 921 yds.; the seam is from 3 ft. 6 in. thick; is a good manufacturing and household coal, and is also used for ironmaking.

Holly Lane Coal.—Worked at a depth of 947 yds., the seam varying from 3 ft. 6 in. to 4 ft. thick; is one of the best household coals in the district, has a good roof and floor, and is cheaply got.

Hard Mine Coal.—Worked at a depth of 948 yds.; it varies from 3 ft. 6 in. to 4 ft. 6 in. thick, and takes its name from its extreme hardness, and from the analysis it will be seen that it is the best coal in the district for blast-furnace purposes, for which it is solely used, and in great demand. It is also a first-class locomotive coal.

RESULTS TABULATED.

| Constituents. | Little Row. | Old Whitfield. | Bowling Alley. | Holly Lane. | Hard Mine. |
|---------------------------------|-------------|----------------|----------------|-------------|------------|
| Fixed carbon | 61·59 | 61·27 | 63·13 | 61·79 | 63·50 |
| Volatile hydro-carbon | 37·40 | 37·61 | 31·70 | 37·35 | 34·85 |
| Sulphur | 0·20 | 0·12 | 0·62 | 0·06 | 0·00 |
| Ash | 0·81 | 1·00 | 4·55 | 0·80 | 1·65 |
| Total | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 |

Production and Distribution of Coal.—In the year 1856, for the first time, the particulars of the output of the North Staffordshire Collieries are separately distinguished from those of South Staffordshire and Worcestershire; the collieries being grouped in the following districts, numbering 123, and producing an aggregate of 1,295,000 tons :—

* Journal of the Iron and Steel Institute, 1875, p. 340.

| NORTH STAFFORDSHIRE. | | NUMBER OF COLLIERIES. |
|----------------------|---|-----------------------|
| Cheadle | . | 16 |
| Longton | . | 23 |
| Hanley | . | 12 |
| Burslem | . | 18 |
| Tunstall | . | 15 |
| Biddulph | . | 12 |
| Newcastle-under-Lyme | . | 27 |
| Total | | <u>123</u> |

The number of collieries for a few years shows little variation. In the year 1860 the production amounted to 2,376,500 tons, the distribution of which was as follows:—

| DISTRIBUTION. | | TONS. |
|----------------------------------|---|------------------|
| Coal used in iron-works | . | 538,700 |
| „ „ in the potteries | . | 150,000 |
| „ „ „ ordinary local consumption | . | 875,000 |
| Colliery consumption | . | 15,500 |
| Sent out of district | . | 797,300 |
| Total | | <u>2,376,500</u> |

Following the production of coal in North Staffordshire since 1860, the annexed table gives the number of collieries and their output, and side by side the production of South Staffordshire and East Worcestershire in each of the same years:—

| Year. | No. of Collieries. | North Stafford. | South Stafford, and East Worcester. | Total of County. |
|-------|--------------------|-----------------|-------------------------------------|------------------|
| | | Tons. | Tons. | Tons. |
| 1861 | 128 | 2,372,500 | 4,881,250 | 7,253,750 |
| 1862 | 114 | 2,537,250 | 4,985,500 | 7,522,750 |
| 1863 | 114 | 2,698,500 | 5,171,820 | 7,870,320 |
| 1864 | 117 | 3,196,500 | 8,263,351 | 11,459,851 |
| 1865 | 125 | 3,495,750 | 8,705,239 | 12,200,989 |
| 1866 | 107 | 3,734,814 | 8,664,966 | 12,399,780 |
| 1867 | 117 | 3,747,814 | 8,779,509 | 12,527,323 |
| 1868 | 113 | 3,545,830 | 8,748,950 | 12,294,780 |
| 1869 | 112 | 3,724,712 | 8,944,395 | 12,669,107 |
| 1870 | 108 | 3,873,562 | 9,356,500 | 13,230,062 |
| 1871 | 115 | 4,250,000 | 10,031,250 | 14,281,250 |
| 1872 | 121 | * | 10,550,000 | ... |
| 1873 | 123 | 3,892,019 | 9,463,559 | 13,355,578 |
| 1874 | 156 | 4,313,096 | 8,389,343 | 12,702,439 |
| 1875 | 157 | 4,456,213 | 10,251,791 | 14,708,004 |
| 1876 | 152 | 4,077,548 | 10,081,067 | 14,158,615 |
| 1877 | 143 | 4,149,975 | 9,841,191 | 13,991,166 |
| 1878 | 145 | 4,072,416 | 9,130,774 | 13,203,190 |
| 1879 | 144 | 4,025,535 | 9,350,000 | 13,375,535 |
| 1880† | 144 | 4,074,800 | 9,660,000 | 13,734,800 |

* Included in production of Cheshire and Shropshire, giving a total of 6,327,188 tons. Estimated production of North Staffordshire in the year 1872—4,000,000 tons.

† Reports, H.M. Inspectors of Mines, 1880.

The greater part of the coal raised in North Staffordshire is consumed in the numerous industries located in the area; the most important of these are the ironworks, potteries, and brick manufactures; some quantities are sent out of the district by the Trent and Mersey navigation, and the North Staffordshire Railway. In the year 1871 the distribution of coal was as follows:—

| DISTRIBUTION OF COAL. | | TONS. |
|-------------------------------|---|------------------|
| Used in iron works | . | 1,825,000 |
| Potteries and brick works | . | 765,000 |
| Other manufactures | . | 525,951 |
| North Staffordshire Railway | . | 241,841 |
| Trent and Mersey Canal | . | 356,964 |
| Local distribution by railway | . | 505,244 |
| Colliery consumption | . | 30,000 |
| Total | . | <u>4,250,000</u> |

Since 1871 the following statement will give the quantities of coal consumed and distributed as stated:—

DISTRIBUTION BY RAILWAY.

| Year. | NORTH STAFFORDSHIRE. | | TRENT AND MERSEY. | LONDON AND NORTH-WESTERN. |
|-------|----------------------|---------|-------------------|---------------------------|
| | Exported. | Local. | Local. | Exported. |
| | Tons. | Tons. | Tons. | Tons. |
| 1872 | 266,025 | 556,768 | 331,930 | 59,152 |
| 1873 | 472,097 | 476,454 | 297,180 | 83,534 |
| 1874 | 674,924 | 517,336 | 271,016 | 95,070 |
| 1875 | 632,283 | 558,086 | 266,869 | 89,077 |
| 1876 | 739,978 | 632,547 | 215,949 | 73,738 |
| 1877 | 753,141 | 609,879 | 265,267 | 58,645 |
| 1878 | 727,304 | 472,940 | 244,157 | 63,129 |
| 1879 | 891,974 | 473,765 | 250,920 | 73,602 |
| 1880 | 863,704 | 387,791 | 288,321 | 79,595 |

In each of the same years the coal used in the iron works, brick works, and potteries were as follows, to which is added the coal used for domestic and other local consumption:—

| Year. | Iron Works. | Potteries, Brick Works. | Domestic and local use. |
|-------|-------------|-------------------------|-------------------------|
| | Tons. | Tons. | Tons. |
| 1873 | 1,376,000 | 750,000 | 400,000 |
| 1874 | 1,000,000 | 950,000 | 750,000 |
| 1875 | 1,250,000 | 950,000 | 650,000 |
| 1876 | 1,050,000 | 850,000 | 600,000 |
| 1877 | 1,228,429 | 750,000 | 900,000 |
| 1878 | 1,250,000 | 750,000 | 900,000 |
| 1879 | 700,000 | 650,000 | 838,510 |
| 1880 | 780,000* | 670,000* | 863,842* |

* Estimated quantities.

Following the returns of production and the distribution of coal in North Staffordshire, the year 1875 appears as the one of greatest production, when 4,456,213 tons of coal were raised, the distribution of which is thus accounted for; side by side will be found similar details for the years 1879 and 1880:—

| Distribution. | 1875. | 1879. | 1880. |
|---|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| North Staffordshire Railway, } out of District } | 632,283 | 891,974 | 863,704 |
| Local distribution by railway . | 558,086 | 473,765 | 387,791 |
| Local distribution by Trent } and Mersey Canal } | 266,869 | 250,920 | 288,321 |
| London and North-Western } carried } | 89,077 | 73,602 | 77,595 |
| Great Northern carried | 9,898 | 21,168 | 13,547 |
| Used at Iron Works, &c. . . . | 1,250,000 | 700,000 | 780,000 |
| Colliery consumption | 50,000 | 125,596 | 130,000 |
| Potteries, Brick Works, &c. . . | 950,000 | 650,000 | 670,000 |
| Domestic and local consumption | 650,000 | 838,510 | 863,842 |
| Total | 4,456,213 | 4,025,535 | 4,074,800 |

Of the coal raised in 1880 in North Staffordshire, nearly 2,500,000 tons were consumed in the county, the remainder being distributed by railway. Towards the close of 1879 a demand for coal arose in the district: this was met by increased output and better prices, but the demand did not continue beyond March, 1880, when many of the collieries for a time limited their work to three and four days per week.

Prices of Coal and Cost of Production.—The cost of working varies so much in this as in other districts, according to circumstances, that considerable difficulty is met with in arriving at exact information. In the following well-authenticated data appear some general facts bearing on the point.

In the year 1880 the average cost per ton of getting coal and slack at the Apedale Mines was respectively 2*s.* 7*d.* and 1*s.* The royalty gave an average on coals of 1*s.* 0½*d.*, and on slack 4½*d.* The profit on coals amounted to 11½*d.* per ton, and on slack 1½*d.* per ton. Adding to the above the average cost of dead work, 2*s.* 3½*d.* per ton, the average cost per ton of coals in the Apedale Mines amounted to 6*s.* 10*d.*, and of slack 3*s.* 9½*d.* The above prices give the average of seventeen seams of coal in the mines above named.

In the subjoined table appears the thickness of the several

seams, the produce of coal and slack per acre, and the profit per acre.*

| Coal Seams. | Thickness. | | | PRODUCE PER ACRE. | | Profit per Acre. | |
|------------------------|------------|-----|-----|-------------------|--------|------------------|----|
| | | | | Coal. | Slack. | | |
| | Yds. | Ft. | In. | Tons. | Tons. | £ | s. |
| Peacock Coal | 1 | 2 | 0 | 4,840 | 806 | 100 | 16 |
| Spincroft | 1 | 2 | 0 | 4,840 | 806 | 100 | 16 |
| Great Roe | 2 | 0 | 0 | 5,808 | 968 | 169 | 8 |
| Kennel | 2 | 0 | 0 | 5,808 | 968 | 169 | 8 |
| Little Roe | 2 | 1 | 0 | 6,637 | 1,106 | 304 | 3 |
| Rusty Mine | 3 | 0 | 0 | 8,712 | 1,452 | 399 | 6 |
| Chalky Mine | 1 | 0 | 0 | 2,904 | 484 | 24 | 4 |
| Single Four-foot . . . | 1 | 2 | 0 | 4,840 | 806 | 80 | 13 |
| Single Five-foot . . . | 1 | 2 | 0 | 4,840 | 806 | 221 | 0 |
| Ragman | 1 | 0 | 6 | 2,904 | 484 | 105 | 1 |
| One Yard to Seven-foot | 2 | 2 | 6 | 8,228 | 1,371 | 754 | 14 |
| Hams | 1 | 2 | 0 | 4,840 | 806 | 100 | 16 |
| Ten-foot | 3 | 0 | 0 | 8,712 | 1,452 | 980 | 2 |
| Top Two Roe | 0 | 2 | 0 | 1,936 | 322 | ... | |
| Bowling Alley | 1 | 2 | 0 | 4,840 | 806 | ... | |
| Seven-foot Nabbs . . . | 1 | 2 | 6 | 5,280 | 880 | 726 | 0 |
| Eight-foot Nabbs . . . | 1 | 1 | 6 | 4,356 | 726 | 598 | 19 |
| Grey Coal | 3 | 0 | 0 | 8,712 | 1,452 | ... | |

The prices of the above coals and slack delivered into boats or waggons varied, coals from 6*s.* 6*d.* to 12*s.*, and slack from 8*s.* 6*d.* to 5*s.* per ton.

In the year 1860 the cost of getting coal and bringing it to bank varied, according to the depth of seam worked, from 2*s.* 6*d.* to 4*s.* 6*d.* per ton. The selling price at pit's bank being: common coal, 6*s.* 2*d.* per ton; and best household coal, 9*s.* 2*d.* per ton. The prices in the year 1870 show a slight advance, increased in 1873 by the operation of the Coal Mines Regulation Act. During the three years ending 1880 the average prices of coal and slack in North Staffordshire were as follows, to which are added the highest and lowest prices per ton:—

| Prices. | COAL. | | | SLACK. | | |
|-----------------|-----------|-----------|-----------|-----------|-----------|-----------|
| | 1880. | 1879. | 1878. | 1880. | 1879. | 1878. |
| Average price . | s. d. 8 4 | s. d. 7 8 | s. d. 9 3 | s. d. 3 9 | s. d. 3 6 | s. d. 4 6 |
| Highest „ . | 12 6 | 11 8 | 12 6 | 5 6 | 5 0 | 5 0 |
| Lowest „ . | 6 6 | 6 0 | 8 4 | 2 6 | 2 6 | 3 0 |

* Smith's "Miner's Guide," 1836, pp. 108, 105.

Population employed in Coal and Ironstone Mining.—Not until the year 1874 have we precise information on this subject; in previous years the numbers employed were grouped in the inspection district, including North Staffordshire, Cheshire, and Shropshire, which, according to the census of 1861, numbered 16,427 male coal-miners. Later, in the year 1867 and subsequent years until the passing of the Coal Mines Regulation Act, 1872, the number of male persons employed as computed by the inspector of the district was as follows, to which are added the quantity of coal raised, and the average number of tons per man :*—

| Year. | Number of Persons employed. | Tons of Coal raised. | Tons raised per Man. |
|-------|--------------------------------|----------------------|-------------------------|
| | Nos. | Tons. | Tons. |
| 1867 | 21,000 | 6,000,000 | 285 |
| 1868 | 21,000 | 6,000,000 | 285 |
| 1869 | 21,000 | 6,200,000 | 295 |
| 1870 | 21,200 | 6,500,000 | 309 |
| 1871 | 21,000 | 6,500,000 | 307 |
| 1872 | 27,753 | 6,327,188 | 228 |

Mr. Thomas Wynne, H.M. inspector of this district, states, in his evidence before the select committee on coal already referred to, that the number of persons employed in the last-named year was arrived at under entirely different circumstances to those obtained in previous years. He says, "Previous to the year 1872 we had no power to call for returns, and in 1872 we had the power, and we called for them; and the return has been made even up to so close as the men who repair railway waggons, the carpenters and blacksmiths, and the loaders of the boats, and every person employed in and about the colliery,"† above ground and underground.

In the year 1873 and subsequent years those employed above and below ground are separately given, amounting in 1873 to 23,177 under ground and 7,444 above ground, or a total of 30,621 persons, of whom 10,000 were engaged in ironstone mining, producing, according to the returns of H.M. inspectors, 6,257,468 tons of coal, and 3,000,000 tons of ironstone, in the district of North Staffordshire, Cheshire, and Shropshire.

* Select Committee on Coal, 1873, p. 329, North Staffordshire, Shropshire, and Cheshire district.

† Report, Select Committee on Coal, 1873, p. 211.

Since 1874 the details appear separately for North Staffordshire,* and are as follows:—

| Year. | PERSONS EMPLOYED. | | Total employed. | Coal raised. | Raised per Man. |
|-------|-------------------|---------------|-----------------|--------------|-----------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 15,606 | 5,150 | 20,756 | 4,486,483 | 216 |
| 1875 | 14,908 | 4,687 | 19,595 | 4,202,149 | 215 |
| 1876 | 13,958 | 4,603 | 18,561 | 3,905,066 | 210 |
| 1877 | 14,005 | 3,951 | 17,956 | 4,191,320 | 233 |
| 1878 | 13,063 | 3,845 | 16,908 | 4,140,200 | 245 |
| 1879 | 12,660 | 3,346 | 16,006 | 4,017,045 | 251 |
| 1880 | 12,307 | 3,273 | 15,580 | 4,074,800 | 261 |

The ages of the 16,006 persons employed in the year 1879 are thus distinguished by Mr. Thomas Wynne, the inspector of the district:—

| Male persons. | Under Ground. | Above Ground. | Total. |
|---------------------|---------------|---------------|--------|
| Ages. | Nos. | Nos. | Nos. |
| From 12 to 13 . . . | 96 | ... | 96 |
| „ 10 to 13 . . . | ... | 4 | 4 |
| „ 13 to 16 . . . | 946 | 206 | 1,152 |
| Above 16 . . . | 11,618 | 3,136 | 14,754 |
| Total all ages . | 12,660 | 3,346 | 16,006 |

Resources and probable Duration of the Coal-field.—Sir George Elliot, Bart., to whom, as a member of the Royal Commission, was intrusted the investigation into the quantity of coal available in North Staffordshire, reports as follows:†—“The coal-field consists of one large, and several small outlying districts, all of which are separately considered. The chief physical characteristics bearing on the inquiry are, the steep inclination of the seams in some parts; the great thickness of coal (150 feet divided into numerous seams) the anticlinal axis running through the district, and the great fault which throws the strata down about 1,200 feet.”

The principal district has an area of 30,876 acres, and is bounded on the west and south by the new red sandstone and permian rocks, and on the east by the red sandstone and mill-

* Reports, H. M. Inspectors of Mines.

† Report, Coal Commission, vol. i., pp. 26, 27.

stone grit. The area is much disturbed by faults, the dip of the seams varying greatly in different parts. It is further remarked that the above named area of 80,876 acres was arranged in four divisions for purposes of investigation, the aggregate of which appears in the following statement, in which also is given the estimated quantity of coal in each of the outlying districts, available after deducting portions likely to be sacrificed by faults, barriers, and loss in working, at various depths :—

| District. | Surface Area. | Not exceeding 1,500 ft. in Depth. | Between 1,500 ft. and 3,000 ft. in Depth. | Between 3,000 ft. and 6,000 ft. in Depth. | Total at all Depths. |
|----------------|---------------|-----------------------------------|---|---|----------------------|
| | Acres. | Tons. | Tons. | Tons. | Tons. |
| 1, 2, 3, and 4 | 30,876 | 1,325,980,007 | 1,012,361,046 | 564,928,888 | 2,903,269,941 |
| Verges . . | 10,400 | 354,330,240 | 572,824,815 | 791,933,744 | 1,816,289,199 |
| Cheadle . . | 11,616 | 104,524,603 | .. | .. | 104,524,603 |
| Wetley . . | 1,200 | 3,062,400 | .. | .. | 3,062,400 |
| Golditch . . | 90 | 117,450 | .. | .. | 117,450 |
| Total . . | 51,182 | 1,788,014,700 | 1,685,185,861 | 1,356,862,632 | 4,826,273,593 |

In the report of the Commission† the total quantities of coal available at all depths are thus rendered; coal to depths not exceeding 4,000 feet, 3,825,488,105 tons, and below 1,000,785,488 tons, making the aggregate of 4,826,273,593 tons.

Taking the production of the year 1870, as given (3,873,562 tons), since which the production has yearly increased, there remain supplies for the next 1,246 years from that date. Deducting the produce of coal during the ten years ending 1879, amounting to 41,110,364 tons, there remained at that date 4,785,163,229 tons to a depth of 9,000 feet. This quantity, taking the average production of the ten years (4,111,096 tons), it is estimated, will furnish supplies to our numerous industries for a period of 1,164 years compared with 1,246 years from the year 1870. While according to the output in the year 1880, amounting to 4,074,800 tons, ample supplies would be stored for 1,174 years hence.

* This quantity includes 96,210,400 tons of coal in the district of the Verges, at depths between 6,000 and 9,000 feet.

† Report, Coal Commission, vol. i., p. ix.

CHAPTER XII.

SOUTH STAFFORDSHIRE AND WORCESTERSHIRE COAL-FIELD.

Description of Coal-field—The South Staffordshire Mines Drainage Association, its Objects—Analyses, Production of Coal-field, and of the Area under the Mines Drainage Act—Yield of Coal Seams per Acre—Distribution of Coal—Prices and Cost of Production—Population employed above and below Ground—Average Output per Man—Resources and probable Duration of Coal-field.

The South Staffordshire and Worcestershire Coal-field.—This coal-field is one of the most important in central England, and differs from all others in the character of the underlying rock, which is Upper Silurian (Wenlock limestone and shale), the millstone grit, or carboniferous limestone, on which the coal usually rests in other coal-fields, being absent here. In other words, the old land surface, on which the flora of the coal measures grew, was an eroded surface of Upper Silurian rocks.

It has been clearly shown by the late Professor J. B. Jukes, in his "Memoir on the South Staffordshire Coal-field," that, whilst the same accumulations were going on in other parts of England, a broad tract of land, extending over Shropshire, Staffordshire, and Warwickshire, was dry land. Consequently the usually associated condition of other coal-fields is here wanting; both the grits and limestones of the carboniferous series being absent, the well-marked isolated Silurian masses of Dudley, Sedgley, and Walsall, rising from beneath the coal measures, and on which they rest.

The coal-field extends from Rugeley in the north, to the Clent Hills in the south, a distance of twenty miles, embracing the important districts of Cannock Chase, Wolverhampton, Bilston, Dudley, Corngreaves, &c., and has an average width of from seven to eight miles, and is bordered by the Bunter Sandstone and Permian Rock, the former having a thickness of 1,200 feet, the latter exceeding 2,000 feet. The coal measures beneath are divided into upper and middle; the upper division consisting of red and mottled clays, red and grey sandstones, and gravel beds,

and having a total thickness of 800 feet, but barren of coal seams. The middle measures, however, contain a thickness of upwards of 500 feet, in which occur six important seams of coal, interstratified with numerous courses of ironstone. The general thickness of these measures is given as follows by Professor Jukes, the thickness of the seams and strata being the average of many sections in the southern district of the coal-field:—

| UPPER COAL MEASURES. | | Ft. |
|---|--|-----|
| Red and mottled clays, red and gray sandstones and gravel bed | | 800 |
| MIDDLE COAL MEASURES (1300 ft.) | | |
| 1. <i>Brough Coal</i> | | 4 |
| Strata with ironstone | | 130 |
| 2. <i>Thick Coal</i> | | 30 |
| Strata with Gubbin ironstone | | 20 |
| 3. <i>Heathen Coal</i> | | 4 |
| Strata with ironstone | | 109 |
| 4. <i>New Mine Coal</i> | | 8 |
| Strata with ironstone | | 16 |
| 5. <i>Fire-clay Coal</i> | | 7 |
| Strata | | 30 |
| 6. <i>Bottom Coal</i> | | 12 |
| Strata with several courses of ironstone | | 140 |

The above six seams give a total thickness of 65 feet of workable coal, the most important of which is the "Thick Coal," ten yards thick, a source of great wealth to the district of Dudley. This celebrated seam is in the northern part of the coal basin, near Essington and Pelsall, represented by nine distinct seams, divided and separated by 420 feet of sandstone and shales. Each of these seams has its own under-clays, roof, and fossil contents. One interesting feature in this coal-field is the basaltic mass of Rowley Regis, forming a hill two miles in length and 820 feet in height. Professor Jukes* considers that this rock has been poured out in the form of a lava flow during the coal period, for the beds of coal dip under the basalt, and have been followed and found "blackened" or charred, and utterly worthless.†

The flooded condition of the collieries in and around Bilston renders the enormous quantity of 150,000,000 tons of coal unworkable. To provide a remedy, and to make this great mass of coal, and the ironstone measures associated with it, more easily available, the "South Staffordshire Mines Drainage Act, 1873,"

* For detailed information of the "South Staffordshire Coal Field," see "Memoirs of the Geological Survey," by J. Beete Jukes, F.R.S. Second edition, published 1859.

† This coal has of late years been used in several manufactures, also on railways. It is not charred, but converted into a black pulverulent mass.

was passed, the works of which are now in active operation. This flooding or ponding up of water in the mines has been occasioned by a great part of the drainage area having subsided, causing hollows, which, often occurring in the water courses, find their way into the mines below, and become a fruitful source of danger to life and property.

The geological or under-ground configuration of the drainage area may be described as a series of basins, separated by faults, and in each basin the strata incline more or less to the centre of the basin, at which they come at their lowest point. The result is that all mines in any one of these basins are dependent upon each other, and (except so far as surface percolation is concerned) independent of other basins. Consequently the mines on the top edge of a basin are little troubled with water, their water naturally draining into the mines of their less fortunate neighbours lower down.

In carrying the Act into operation, the Commissioners had three important things to consider. First, to subdivide the drainage area into districts, following the natural configuration of the strata, so that each district might consist of a subterranean basin, and, so far as its underground drainage was concerned, be entirely unaffected by, and unable itself to affect, any other district. In the second place, it was necessary to introduce an efficient system of surface drainage to prevent water percolating from surface water-courses and drains into the mines; and thirdly, an efficient system of underground or mine drainage, by removing the water which is actually in the strata itself. The mines in the area are classified under the following heads:—

- (1.) Mines at the top edge of an underground basin ("called mines in the cross"), which are necessarily free from water;
- (2.) Mines obstructed and requiring perpetual pumping;
- (3.) Flooded mines; and
- (4.) Exhausted mines.

The necessary funds for carrying out the Act are provided by two distinct rates—the one called the "General Drainage Rate," applicable for the purposes of surface drainage; the other, the "Mines Drainage Rate," applicable for the purposes of underground drainage.

The engineering works of this comprehensive scheme have

been carried out under the able superintendence of commissioners, assisted by Mr. E. B. Marten, C.E., of Stourbridge; and an instructive model on a large scale of the area of the country included in the Act, constructed by Mr. James B. Jordan, and deposited in the offices of the commissioners at Wolverhampton, illustrates the configuration of the country and the details of the scheme.

Analyses of the Coal.—The Ten Yard, or “Thick Coal,” from the Whyley Colliery, and the “Heathen Coal,” two important seams in the South Staffordshire and Worcestershire coal-field, are thus referred to by Dr. Percy: * “Non-caking coals, rich in oxygen; the Ten Yard or Thick Coal, from the Whyley Colliery, in the vicinity of West Bromwich, this seam consists of ten or more beds, to which special names are applied, viz., ‘Rooves,’ ‘Top Slipper,’ ‘White Coal,’ and ‘Brazils;’ the last-named contains much earthy matter, and is in request for certain reverberatory smelting furnaces in Birmingham.” The powder of each of these coals is brownish-black.

The Heathen Coal, from the Grace Mary Colliery, Rowley Regis.—“This seam is between 5 and 6 feet thick, lies at the depth of a few yards below the Ten Yard Coal, and is overlaid by the Gubbin ironstone. The coal is bright black, non-caking, and yields a buff-coloured ash.”

The composition of these coals appears in the annexed table :—

| Composition exclusive of Water. | TEN YARD OR THICK COAL. | | | | Heathen Coal. |
|---|-------------------------|---------------|---------------|---------------|---------------|
| | Rooves. | Top Slipper. | White Coal. | Brazils. | |
| Carbon | 76·12 | 77·01 | 76·40 | 72·13 | 70·41 |
| Hydrogen | 4·83 | 4·71 | 4·62 | 4·32 | 4·69 |
| Oxygen | 16·72 | 16·72 | 17·43 | 17·11 | 12·47 |
| Sulphur | 1·00 | 0·74 | 0·55 | 0·54 | 0·71 |
| Ash | 2·33 | 1·56 | 1·55 | 6·44 | 2·20 |
| Water | ... | ... | ... | ... | 9·52 |
| Total . | 101·00 | 100·74 | 100·55 | 100·55 | 100·00 |
| Composition exclusive of Sulphur, Ash, and Water. | | | | | |
| Carbon | 78·46 | 78·53 | 77·68 | 77·33 | 80·41 |
| Hydrogen | 4·96 | 4·80 | 4·69 | 4·67 | 5·35 |
| Oxygen and Nitrogen . | 16·58 | 16·67 | 17·63 | 18·00 | 14·24 |
| Total . | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 |

* Percy's “Metallurgy,” Fuel, p. 325.

Other seams, worked at Grace Mary Colliery, Rowley Regis, are thus described : * Sawyer Coal.—“ This coal forms one of the constituent seams of the Ten Yard or Thick Coal ; the sample analysis came from the neighbourhood of an igneous dyke. Coke, slightly coherent, moderately lustrous ; flame, yellow, smoky ; colour of the ash, buff.” Brazils Coal.—“ This also forms part of the Thick Coal, and, like the last sample, came from the neighbourhood of an igneous dyke. Coke, slightly coherent, moderately lustrous. Flame, yellow, smoky. Colour of the ash, buff.” These analyses were made in Dr. Percy’s laboratory, in the Royal School of Mines, by Mr. Charles Law, and give the following results :—

RESULTS TABULATED.

| Constituents. | Sawyer Seam. | Brazils Seam. |
|-------------------------------|--------------|---------------|
| Carbon | 68·40 | 67·34 |
| Hydrogen | 4·43 | 4·62 |
| Oxygen and Nitrogen | 10·28 | 11·68 |
| Sulphur | 1·05 | 0·62 |
| Ash | 8·91 | 8·00 |
| Water | 6·93 | 7·74 |
| | 100·00 | 100·00 |

The composition per cent., exclusive of sulphur, ash, and water, being :—

| Constituents. | Sawyer. | Brazils. |
|-------------------------------|---------|----------|
| Carbon | 82·30 | 80·51 |
| Hydrogen | 5·33 | 5·52 |
| Oxygen and Nitrogen | 12·37 | 13·97 |
| | 100·00 | 100·00 |
| Yield of Coke | 64·00 | 60·70 |

Production of Coal.—It appears, from Plott’s History of Staffordshire, that in the year 1785 there were twelve collieries at work in the coal-field, in the districts of Wednesbury, Dudley, and Sedgley, and twice as many out of work, some of which afforded 2,000 tons yearly, others three, four, or five thousand tons per annum. From which it may be estimated that the production of coal at this period, in these important districts, did not exceed

* Percy’s “Metallurgy,” Fuel, p. 569.

50,000 tons. In the year 1800 a committee was appointed by Parliament to inquire into the inland coal trade. From the evidence bearing on Staffordshire, it is stated by Mr. Alexander Rabey, an iron merchant,* that "the present price of the Staffordshire (coal) at the pit is six shillings per ton, of 21 cwt., and 120 lbs. to the cwt.; inferior coals are sold at three shillings per ton; the small coal for engines are from one shilling to one shilling and sixpence per ton." Mr. Rabey does not give any facts bearing on production or distribution, but he gives the following information, showing the price of coals after the cost of conveyance has been added:—

"I compute the average distance of those collieries (the Dudley collieries), to Brentford, 148 miles; the boatage, $\frac{3}{4}d.$ per ton per mile; 9s. 8d. boy and horse, of back carriage included, would be about $\frac{1}{2}d.$ per ton per mile, is $6\frac{1}{2}d.$ more, in all, about £1 1s. 5d. per ton." A London chaldron of the Newcastle coals will be about twenty-seven cwt.; he adds one-third of the weight and one-third of the price on a London chaldron. Therefore, if Staffordshire coals to Brentford cost £1 8s. 7d. per chaldron, allowing 2s. 11d., they would stand, when imported into London, about 33s. per ton.

Returning to the coal production of Staffordshire, we have it, on the authority of Samuel Salt, for the year 1816, that it amounted to 795,000 tons. The same gentleman, in his "Statistics and Calculations," gives the total output of the collieries of Great Britain for the same year (1816) as 27,020,115 tons.

Since the year 1854, ample information has been published, showing the number of collieries working in the South Staffordshire coal-field, including that portion of the coal-field in the county of Worcester, in the neighbourhood of Dudley. The number of collieries at full work at this period was 500, which had at least 2,000 pits, and of these a large majority produced nearly 100 tons of coal per week. The total production of coal in North and South Staffordshire, at this period was 7,500,000 tons, the quantities carried out of the county being comparatively small, the pig iron industries consuming 3,415,200 tons.

The number of collieries, and the annual output from 1854 to 1863, are as follows:—

* Inland Coal Trade, "Report of the Committee, 1800," Evidence on Staffordshire.

| Year. | Collieries. | Production of Coal. | Year. | Collieries. | Production of Coal. |
|-------|-------------|---------------------|-------|-------------|---------------------|
| | No | Tons. | | No. | Tons. |
| 1854 | 393 | *7,500,000 | 1859 | 422 | 4,450,000 |
| 1855 | 377 | *7,323,000 | 1860 | 441 | 5,271,800 |
| 1856 | 425 | 6,010,500 | 1861 | 452 | 4,881,250 |
| 1857 | 438 | 5,509,625 | 1862 | 457 | 4,985,500 |
| 1858 | 424 | 4,955,780 | 1863 | 465 | 5,171,820 |

Since the year 1864 two sources of information are at hand, giving the output of the collieries in South Staffordshire and Worcestershire; the one from the "Mineral Statistics of the United Kingdom," the other from the "Annual Reports of Her Majesty's Inspectors of Coal Mines." The collieries of this district, it may be observed, are very numerous; many of them, however, are but small workings. It not unfrequently happens that a pit is opened and, a few tons of coal having been obtained, it is closed within a few months. The following table shows the number of collieries in each year, the variation in numbers being due to the cause above referred to, as well as pits being included as collieries, also the respective quantities of coal raised as determined by the Keeper of Mining Records in each year.

| Year. | Collieries. | Mineral Statistics. | Year. | Collieries. | Mineral Statistics. |
|-------|-------------|---------------------|-------|-------------|---------------------|
| | No. | Tons. | | No. | Tons. |
| 1863 | 465 | 5,171,820 | 1872 | 319 | 10,550,000 |
| 1864 | 523 | 8,263,351 | 1873 | 407 | 9,463,559 |
| 1865 | 542 | 8,705,239 | 1874 | 469 | 8,389,343 |
| 1866 | 512 | 8,664,966 | 1875 | 442 | 10,251,791 |
| 1867 | 572 | 8,779,509 | 1876 | 434 | 10,081,067 |
| 1868 | +327 | 8,748,950 | 1877 | 457 | 9,841,191 |
| 1869 | 326 | 8,944,395 | 1878 | 437 | 9,130,774 |
| 1870 | 326 | 9,356,500 | 1879 | 425 | 9,350,000 |
| 1871 | 307 | 10,031,250 | 1880 | 413 | 19,660,000 |

Bearing on the question of production in South Staffordshire, it may be noted that the coal deposits of Cannock Chase are now (June, 1881) in course of rapid development, one company producing on an average 2,000 tons per day, and even more; and should occasion require, the same company is in a position to increase its output to 3,000 tons daily. Recently, at one of the pits of the Cannock and Rugeley Company, 1,051 tons were brought to bank from a depth of 350 yards in a period of eight hours.

The Keeper of Mining Records, referring to the returns for the

* Including the production of North Staffordshire.

† In previous years pits were included as collieries.

‡ Report of H.M. Inspectors of Coal Mines.

year 1864, remarks * : " It will be necessary to make corrections in former years, all the returns being too small. This has arisen from my having taken the 'boat load' as being 20 tons." The best explanation of the difficulty will be given in the following paragraph from a paper read at a conference of mine owners and agents, by Rupert Kettle, Esq., Vice-President of the Dudley and Midland Geological Society :—

" We have in one colliery district three different weights, each called and commonly recognized as a ton. First, the statutable ton, that is, the avoirdupois weight of 2,240 lbs. Next, we have the long hundred, or long weight, as we commonly understand it, that is, 120 lbs. to the hundred-weight instead of 112 lbs., giving 2,400 lbs. to the ton. And then, thirdly, we have the 'boat load' of 24 long hundreds, or 2,880 lbs. to the ton : and, lastly, there is a measure acted upon, I am sorry to say for business purposes, called a 'boat load.' I should very much like some one to tell me any rule by which I can ascertain the exact weight, according to the law standard, of the whole, or any aliquot part of a 'boat load' of coals. I know a boat load is 20 tons, and the furthest to which I can carry the weight is 20 tons 'lease weight,' that is 57,600 lbs. or 25 tons, 13 cwt., 2 qrs., and 16 lbs. weight, and yet I am told that sometimes a 'boat load of coals' will what is called weigh out thirty hundred-weight to the ton."

In considering the production of coal, and the area of this coal-field included under the operation of the " South Staffordshire Mines Drainage Act, 1873," the importance of the work will be understood by the returns of the several districts of coal produced, upon which rates were levied in each year since 1874. It must be remembered, however, that the largest part of the coal obtained annually in South Staffordshire is worked outside the Mine's Drainage area :—

| Districts. | 1874. | 1875. | 1873. | 1879. | 1880. |
|----------------|-----------|-----------|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| Tipton . . . | 1,103,396 | 950,666 | 584,075 | 434,798 | 518,602 |
| Bilston . . . | 640,926 | 568,687 | 242,637 | 175,420 | 204,531 |
| Kingswinford . | 757,937 | 835,561 | 724,530 | 709,315 | 696,658 |
| Old Hill . . . | 782,193 | 884,127 | 699,784 | 684,522 | 828,430 |
| Oldbury . . . | 641,103 | 867,728 | 904,748 | 946,966 | 940,813 |
| Total . | 3,925,555 | 4,106,769 | 3,155,774 | 2,951,021 | 3,189,034 |

* Mineral Statistics, 1864, p. 90.

The yield per acre of the seams of coal is a matter of great importance, varying considerably in this district, more particularly in the "Ten Yard Coal," the thickness of which, exclusive of its partings of clay and shale, averages 8 yards, 2 feet, 3 inches. The following table, by Mr. Thomas Smith, gives practically the average quantities of coals, lumps, and slack obtained from each acre of coal, of the thickness indicated :—*

| Coal Seams. | Thickness. | Coals. | Lumps. | Slack. |
|---|--------------|--------|--------|--------|
| | Yds. Ft. In. | Tons. | Tons. | Tons. |
| Brooch Coal | 1 0 9 | 1,815 | 363 | 1,452 |
| Flying Reed | 1 1 0 | 3,226 | 645 | 968 |
| Thick Coal | 8 2 3 | 10,400 | 1,733 | 3,267 |
| Heathen Coal | 1 0 0 | 2,420 | 484 | 726 |
| New Mine Top and Bot- tom Coal | } 4 2 6 | 11,695 | 2,339 | 3,508 |
| New Mine Bottom Coal. | | | | |
| | 3 2 6 | 9,275 | 1,855 | 2,782 |
| Total thickness . . . | 21 0 0 | | | |
| Total quantities, the Thick Coal being got with ribs and pillars . | } | 38,831 | 7,419 | 12,703 |
| Additional if the Thick Coal be got by long work | | 10,574 | 2,494 | 3,025 |
| Total quantities if got by long work | | 49,405 | 9,913 | 15,728 |

Distribution of Coal.—The London and North Western Railway carried, in the year 1859, out of South Staffordshire, 94,000 tons of coal, the total quantities carried by the same railway system in the year amounting to 2,721,000 tons. In the years 1860 and 1861 the production is thus accounted for :—

| How Distributed. | 1860. | 1861. |
|-------------------------------------|-----------|-----------|
| | Tons. | Tons. |
| Used at Iron Works | 2,975,000 | 2,550,500 |
| Used in Collieries and Lime Works . | 156,800 | 160,750 |
| Local consumption | 650,000 | 650,000 |
| Sent out of district | 490,000 | 1,520,000 |
| Total | 4,271,800 | 4,881,250 |

Ten years later the following details of distribution appear for the years 1870 and 1871 :—

* Thomas Smith's "Miners' Guide, 1836," p. 79.

| How Distributed. | 1870. | 1871. |
|----------------------------------|-----------|------------|
| | Tons. | Tons. |
| Used at Iron Works . . . | 3,185,750 | 3,585,750 |
| Used in other manufactures . . . | 1,350,000 | 1,500,000 |
| Domestic consumption . . . | 1,850,000 | 1,875,500 |
| Colliery „ &c. . . | 1,250,750 | 1,330,000 |
| By Railway and Canal . . . | 1,720,000 | 1,720,000 |
| Total . . . | 9,356,500 | 10,031,250 |

The annexed table shows the quantities of coal used at the ironworks, and sent out of the district by railway:—

| Year. | Iron Works. | London and North Western. | Midland. |
|-------|-------------|---------------------------|----------|
| | Tons. | Tons. | Tons. |
| 1860 | 2,975,000 | 93,000 | 60,104 |
| 1861 | 2,550,500 | ... | 89,048 |
| 1862 | 2,350,500 | 211,210 | 88,248 |
| 1863 | 2,561,320 | 314,695 | 79,809 |
| 1864 | 4,660,945 | 389,174 | 85,922 |
| 1865 | 4,655,940 | 314,121 | ... |
| 1866 | 4,388,375 | 272,892 | 33,376 |
| 1867 | 3,979,379 | 337,417 | 43,263 |
| 1868 | 3,293,450 | 455,967 | 34,667 |
| 1869 | 3,170,500 | 626,308 | 41,189 |
| 1870 | 3,185,750 | 665,720 | 42,305 |
| 1871 | 3,585,750 | 708,597 | 47,660 |
| 1872 | *3,250,000 | 809,622 | 53,842 |

In the last-named year the Great Western Railway carried 494,608 tons out of South Staffordshire, and 408,219 tons from the Ruabon district into the same county. Following the distribution of coal, the annexed statement gives the details for the year 1880 and the three previous years:—

| How Distributed. | 1877. | 1878. | 1879. | 1880. |
|---|-----------|-----------|-----------|------------|
| | Tons. | Tons. | Tons. | Tons. |
| Carried out of County by London and North-Western Railway | 1,138,293 | 1,086,370 | 1,499,337 | 1,511,099 |
| Carried out of County by Midland Railway | 163,903 | 169,392 | 209,561 | 189,247 |
| Carried out of County by the Great Western | 344,702 | 325,364 | 311,178 | 306,141 |
| Carried by Birmingham Canal for Birmingham | 916,288 | 859,122 | 828,942 | 770,245 |
| Carried by Birmingham Canal for Works in Mining Districts | 3,144,460 | 3,030,570 | 2,968,800 | 3,401,613 |
| Carried out of County by ditto Canal | 207,995 | 208,823 | 227,782 | 214,390 |
| Domestic Consumption, in addition to Birmingham | 1,775,550 | 1,801,128 | 1,500,180 | 1,440,266* |
| Colliery Consumption, &c. . . | 1,255,000 | 1,000,000 | 950,110 | 965,000* |
| Used in Manufactures, extra . . | 895,000 | 650,000 | 854,110 | 862,000* |
| Total produce of South Staffordshire and Worcestershire | 9,841,191 | 9,130,774 | 9,350,000 | 9,660,000 |

* Estimated quantities.

Before considering the distribution of coal by canal, it will be desirable to trace generally the distribution by railway since the last returns for the year 1872. It will be useful at the same time to record the quantities of coal brought into South Staffordshire by the Great Western Railway from the Ruabon district :—

| Year. | London and North Western. | Midland. | GREAT WESTERN. | |
|-------|---------------------------|----------|------------------------|--------------|
| | | | Out of South Stafford. | From Ruabon. |
| | Tons. | Tons. | Tons. | Tons. |
| 1873 | 971,525 | 106,484 | 487,635 | 397,069 |
| 1874 | 632,630 | 60,590 | 303,187 | 347,527 |
| 1875 | 1,161,425 | 140,593 | 398,842 | 369,084 |
| 1876 | 1,203,401 | 181,511 | 369,102 | 352,777 |
| 1877 | 1,138,293 | 163,903 | 344,702 | 294,316 |
| 1878 | 1,086,370 | 169,892 | 325,364 | 263,268 |
| 1879 | 1,499,337 | 209,561 | 311,178 | 250,953 |
| 1880 | 1,511,099 | 189,247 | 1,511,099 | 285,850 |

The other items of distribution in each of the same years, attracting attention, are the quantities conveyed by the Birmingham Canal to the various works in the mining districts in South Staffordshire, and for domestic consumption.

| Year. | To Birmingham. | To Mining Districts. | Domestic Consumption. | Collieries Consumption. |
|-------|----------------|----------------------|-----------------------|-------------------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1873 | 812,668 | 3,500,223 | 1,750,000 | 1,300,000 |
| 1874 | 776,881 | 3,114,305 | 1,750,000 | 1,525,000 |
| 1875 | 939,779 | 3,377,355 | 1,675,500 | 1,279,000 |
| 1876 | 936,724 | 3,114,821 | 1,650,000 | 1,250,000 |
| 1877 | 916,288 | 3,144,460 | 1,575,550 | 1,255,000 |
| 1878 | 859,122 | 3,030,570 | 1,801,128 | 1,000,000 |
| 1879 | 828,942 | 2,968,800 | 1,500,180 | 950,110 |
| 1880 | 770,245 | 3,401,613 | 1,440,265 | 965,000 |

The distribution of coal is greatly facilitated in South Staffordshire by the system of water communication traversing the county in all directions; and the Birmingham Canal Navigation, which has direct communication with the adjoining counties of Worcester and Warwick. The annexed table will show the quantities of coal sent by the several canals carrying from South Staffordshire in each of the years named :—

| Year. | Worcester Canal. | Warwick Canal. | Coventry Canal. | Staffordshire and Worcester-shire Canal. | Whittington to Fazeley. |
|-------|------------------|----------------|-----------------|--|-------------------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1866 | 135,585 | 77,205 | 518 | 13,776 | 1,039 |
| 1867 | 148,000 | 94,165 | 2,149 | 19,661 | 3,044 |
| 1868 | 148,186 | 98,248 | 1,778 | 28,317 | 4,772 |
| 1869 | 148,474 | 104,021 | 1,210 | 41,724 | 2,946 |
| 1870 | 140,453 | 103,286 | 773 | 48,502 | 2,812 |
| 1871 | 127,859 | 110,243 | 322 | 52,845 | 2,395 |
| 1872 | 118,779 | 91,374 | 340 | 59,132 | 1,160 |
| 1873 | 118,672 | 90,087 | 452 | 64,650 | 847 |
| 1874 | 102,130 | 67,785 | 405 | 55,951 | 479 |
| 1875 | 117,552 | 25,626 | 213 | 83,660 | 902 |
| 1876 | 116,061 | 9,534 | 405 | 97,555 | 1,972 |
| 1877 | 112,051 | 7,685 | 572 | 85,301 | 2,385 |
| 1878 | 110,176 | 6,834 | 2,373 | 83,755 | 5,689 |
| 1879 | 116,058 | 23,459 | 206 | 83,946 | 4,112 |
| 1880 | 109,909 | 15,269 | 612 | 87,186 | 1,415 |

Supplementing the above quantities with the tonnages of coal sent to Birmingham, and carried for the supply of works in the mining districts, by the Birmingham Canal Navigation, the following totals show the aggregate distribution of coal by canal in each of the years named :—

BIRMINGHAM CANAL NAVIGATION.

| Year. | Coal carried. | Year. | Coal carried. |
|-------|---------------|-------|---------------|
| | Tons. | | Tons. |
| 1866 | 3,601,621 | 1873 | 4,587,600 |
| 1867 | 3,841,062 | 1874 | 4,117,937 |
| 1868 | 3,786,369 | 1875 | 4,545,089 |
| 1869 | 4,302,103 | 1876 | 4,277,054 |
| 1870 | 4,312,582 | 1877 | 4,268,744 |
| 1871 | 4,415,697 | 1878 | 4,098,521 |
| 1872 | 4,495,333 | 1879 | 4,025,525 |

The quantity carried in 1880 amounted to 4,386,248 tons.

Prices of Coal and Cost of Production.—In 1896 Mr. Thos. Smith, in his "Miners' Guide," gives the following quotations per ton of coals of different descriptions delivered into boats or waggons at the pits, the coals quoted being raised at the Deepfield Mine :—

DEEPPFIELD MINE.

| | s. | d. |
|--------------------|----|----|
| Brooch Coal, large | 8 | 0 |
| „ lumps | 5 | 0 |
| „ rakings | 3 | 9 |

DEEPFIELD MINE (continued.)

| | s. | d. |
|--|----|----|
| <i>Brooch Coal</i> , slack | 2 | 6 |
| " " coke, per sack | 1 | 4 |
| <i>Thick Coal</i> , best | 9 | 0 |
| " " second | 8 | 0 |
| " " inferior | 7 | 0 |
| " " furnace coal | 6 | 6 |
| " " lumps | 5 | 0 |
| " " slack, good | 2 | 9 |
| " " small | 2 | 6 |
| <i>New Mine Top and Fire-clay Coals</i> , best | 7 | 0 |
| " " " furnace coal | 6 | 0 |
| " " " lumps | 5 | 0 |
| " " " rakings | 3 | 6 |
| " " " slack, good | 2 | 9 |
| " " " inferior | 2 | 6 |
| <i>New Mine</i> , bottom coal, best | 6 | 0 |
| " " lumps | 4 | 6 |
| " " slack | 2 | 6 |

The above are the actual charges at the time, but the prices of all the varieties of coal vary considerably, according to their quality, which is by no means the same in all parts of the same district or collieries.*

The average cost per ton of getting coals, lumps, and slack from the various coal seams was as follows at the period above referred to :—

| Coal Seam. | Coal. | Lumps. | Slack. |
|--|-------|--------|--------|
| | s. d. | s. d. | s. d. |
| <i>Brooch</i> | 4 3 | 1 2 | 1 0 |
| <i>Flying Reed</i> | 2 6½ | 1 2 | 1 0 |
| <i>Thick Coal</i> | 2 4 | 1 2 | 1 0 |
| <i>Heathen Coal</i> | 2 7 | 1 2 | 1 0 |
| <i>New Mine Top and Fire Clay Coal</i> | 1 10½ | 1 2 | 1 0 |
| <i>New Mine Bottom Coal</i> | 1 10½ | 1 2 | 1 0 |
| Total | 15 5½ | 7 0 | 6 0 |

The average price per ton of these six seams of coal being, coals, 2s. 7d.; lumps, 1s. 2d., and slack, 1s.

When in 1878 a great demand for coal arose, due to the general activity of trade, prices increased considerably, varying from 15s. to 19s. per ton; prices in the previous year ranging from 11s. 3d. to 15s. per ton. Mr. Fisher Smith, in his evidence

* "Miners' Guide," Thomas Smith, p. 84.

before the Select Committee on Coals,* states that upwards of 1,000,000 tons of coal are raised in the year from the collieries belonging to the Earl of Dudley, nearly one-half of which is used in iron manufacture, and in the production of which from 8,000 to 10,000 men are employed. It further appears that hewers' wages in 1873 were 5s. 6d. per day for less hours' work than in the year 1869, when wages varied from 4s. to 4s. 6d. per day. To illustrate this more clearly one pit is taken as a fair average, in which the hewers made in the week 7·3 days, for which they received 29s. 3d. In 1872 they did 7·2 days, earning £1 15s. 7d. per week, and in 1873, in 7·3 days, earning £2 0s. 5d. per week, the above rates being an average of 10 men for each period, some of the highest and some of the lowest. In 1869 they worked 11 hours per day, diminished to 8 hours in 1872 and 1873.

Immediately preceding the passing of the "Coal Mines Regulation Act, 1872," the prices of thick coal, at the respective collieries of the Earl of Dudley, were as follows:—

| | |
|--------------------------|---------------|
| Coal | 13s. per ton. |
| Lumps | 12s. „ |
| Slack (engine) | 6s. „ |

The effect of the Act in the district has been to increase the cost of coal something like 1s. per ton.

The wages of colliers in South Staffordshire have not undergone such great fluctuations during the past ten years as in most other coal-fields. Between 1870 and 1873 they rose from 40 to 45 per cent.; but a good deal of it was in the form of the reduction of the hours of work. In South Staffordshire the hours of labour fell from sixty-six a week in 1871 to forty-eight in 1873, while the wages rose from 5s. a day to 5s. 6d.; that is, the hours of work decreased 29 per cent., and wages increased 10 per cent., making altogether an advance of nearly 40 per cent. In North Staffordshire the hours of labour also fell from 58 to 50 per week, and wages were advanced 30 per cent. Since then the reverse movement has taken place. The wages are now regulated by a sliding scale, according to the selling price of coal.†

The present selling prices of coal per ton of 2,240 lbs., from

* Report, Coal, 1873, p. 91.

† "Ten Years' Coal Mining, Staffordshire," *Colliery Guardian*, vol. xl, 1880, p. 492.

the Earl of Dudley's collieries, are as follows (September, 1881), these prices have been current for upwards of nine months :—

EAST OF DUDLEY (TIPTON DISTRICT).

THICK COAL.

| | INTO BOATS. | |
|---------------------------------|-------------|----|
| | s. | d. |
| Best (Household) | 9 | 0 |
| Furnace | 8 | 0 |
| Forge or Steam | 8 | 0 |
| Engine Slack (Best) | 4 | 0 |
| Fine Slack (Ordinary) | 3 | 6 |

NEW MINE COAL.

| | | |
|------------------------|---|---|
| Large | 9 | 0 |
| Forge | 8 | 6 |
| Engine Slack | 4 | 6 |

HEATHEN COAL.

| | | |
|------------------------|---|---|
| Large | 9 | 0 |
| Forge | 8 | 6 |
| Engine Slack | 4 | 6 |

WEST OF DUDLEY (BRIERLEY HILL DISTRICT).

THICK COAL.

| | | |
|--|----|---|
| 1. Best (Household) | 12 | 0 |
| 2. Furnace | 8 | 6 |
| 3. Steam (For locomotives) | 7 | 0 |
| 4. Screenings (Bright) | 7 | 0 |
| 5. Screenings (Steam) | 6 | 6 |
| 6. Engine Slack (Best Himley Colliery) | 4 | 0 |
| 7. Engine Slack (Ordinary) | 3 | 6 |

In the beginning of February, probably due to the severe weather previously prevailing, the quotations of coal and slack were advanced, making furnace coal, 10s. per ton; forge coal, 8s. 6d., and engine coal and slack, 5s. per ton. These quotations, regulating the basis of the coal trade in Staffordshire, will accordingly lead to an advance of wages of 3d. per day to men working on thick coal, and 1½d. to the men employed in the thin coal seams. No change appears to have been made in the Cannock Chase district, where the Cannock Chase Railway Collieries Company, one of the leading firms, give the following quotations: best deep coal, 10s.; yard coal and best deep cobbles, 9s.; shallows, 8s. 6d.; steam coal, 6s. 6d., and slack, 6s. 6d. and 5s. 6d., according to quality.

Population employed above and below Ground.—In the working of coal and ironstone in Staffordshire, in the year 1854,

there were employed in coal mining 25,681 persons of all ages, and in ironstone mining 2,870 persons; these totals include all employed above and below ground. In the Worcestershire extension of the coal-field 2,188 persons were employed in the same year in coal-mining, and 252 in ironstone mining, giving an aggregate of 27,869 persons in coal mining, and 3,122 persons in ironstone mining. The census of the year 1861 gave 25,235 persons as the number employed in South Staffordshire and Worcestershire; increased in the year 1864 to 26,620 persons, when the production of the coal-field was, according to the returns of Her Majesty's Inspectors of Collieries, 10,206,000 tons of coal, giving an average annual yield per man of 383 tons.

In subsequent years we have the following numbers of persons employed computed by the inspector of the district, to which is added the output of coal, and the average yield per man:—

| Year. | Persons Employed. | Coal Raised. | Average per Man. |
|-------|-------------------|--------------|------------------|
| | No. | Tons. | Tons. |
| 1864 | 26,620 | 10,206,000 | 383 |
| 1865 | 27,000 | 10,201,000 | 380 |
| 1866 | 27,000 | 10,300,000 | 381 |
| 1867 | 27,100 | 10,268,000 | 379 |
| 1868 | 28,000 | 9,900,000 | 350 |
| 1869 | 28,500 | 10,408,000 | 365 |
| 1870 | 29,000 | 10,400,000 | 358 |
| 1871 | 31,000 | 10,500,000 | 338 |
| 1872 | 31,500 | 10,550,000 | 335 |

These returns exhibit a gradual decline between the years 1864 and 1872 in the average output per man of 48 tons, equivalent to a decrease of 12 per cent.

In the year 1873, under the provisions of the Coal Mines Regulation Act, the total number of persons employed in South Staffordshire, in coal and ironstone mining, was 36,829, of whom 27,497 were engaged under ground, and 9,932 above ground. Since that date, the number of persons employed, and the quantity of coal and ironstone raised in South Staffordshire and Worcestershire, has been as follows; * to which is appended the average yield per man in tons:—

* Reports of H.M. Inspectors of Mines.

| Year. | PERSONS EMPLOYED. | | | Coal Raised. | Ironstone. Raised. | Average per Man. |
|-------|-------------------|--------|--------|--------------|-----------------------|---------------------|
| | Under. | Above. | Total. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. | Tons. |
| 1873 | 27,497 | 9,332 | 36,829 | 11,100,000 | 346,644 | 310 |
| 1874 | 27,304 | 9,551 | 36,855 | 8,500,000 | 246,174 | 237 |
| 1875 | 26,457 | 9,211 | 35,668 | 10,300,000 | 384,055 | 299 |
| 1876 | 24,476 | 8,322 | 32,798 | 10,000,000 | 294,482 | 313 |
| 1877 | 21,483 | 7,277 | 28,760 | 9,500,030 | 206,452 | 337 |
| 1878 | 18,681 | 6,422 | 25,103 | 8,976,000 | 191,513 | 365 |
| 1879 | 17,641 | 5,914 | 23,555 | 9,329,197 | 149,204 | 402 |
| 1880 | 17,563 | 5,930 | 23,493 | 9,660,000 | 186,245 | 423 |

In the year 1879, the numbers of persons employed in the South Staffordshire and Worcestershire parts of the coal-field are given separately, and appear as follows :—

| Districts. | Under Ground. | Above Ground. | Total. |
|-----------------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| South Staffordshire . | 15,045 | 5,061 | 20,106 |
| Worcestershire . . | 2,596 | 853 | 3,449 |
| Total . | 17,641 | 5,914 | 23,555 |

Their respective ages being thus distinguished :—

| Male Persons. | Under Ground. | Above Ground. | Total. |
|---------------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| From 12 to 13 . . . | 21 | ... | 21 |
| „ 10 to 13 . . . | ... | 3 | 3 |
| „ 13 to 16 . . . | 1,256 | 368 | 1,624 |
| „ 13 to 16 . . . | ... | 89* | 89 |
| Above 16 . . . | 16,364 | 5,057 | 21,421 |
| „ 16 . . . | ... | 397† | 397 |
| Total . | 17,641 | 5,914 | 23,555 |

In examining the average quantity of coal and ironstone raised per man in South Staffordshire, according to the returns of Her Majesty's Inspectors, a great falling off appears in the year 1874, when it did not exceed 237 tons; the diminished output arose from a "strike," which prevailed for about four months. This, with the depressed condition of the iron trade, on which

* Females, 18 in Staffordshire and 71 in Worcestershire.

† Females, 316 in Staffordshire and 81 in Worcestershire.

the consumption of coal greatly depends, reduced the output from 11,100,000 tons in 1873 to 8,500,000 tons the following year, a decrease of 2,600,000 tons, equal to 23 per cent. Since 1874 the average output has steadily increased, and results in this direction compare favourably with other coal producing districts.

Comparing the results of the past ten years with the average yield per man in the year 1835, we have the following as the actual quantity of coal and ironstone got per man per day in the South Staffordshire coal-field, from the seams named :—*

| Coal Seams. | Coals. | | | Lumps. | | | Slack. | | |
|--|--------|-------|------|--------|-------|------|--------|-------|------|
| | Tons. | Cwts. | Qrs. | Tons. | Cwts. | Qrs. | Tons. | Cwts. | Qrs. |
| Brooch Coal | 1 | 4 | 0 | 0 | 5 | 0 | 1 | 0 | 0 |
| Flying Reed Coal . . . | 2 | 10 | 0 | 0 | 10 | 0 | 0 | 15 | 0 |
| Thick Coal | 5 | 0 | 0 | 1 | 0 | 0 | 1 | 10 | 0 |
| Heathen Coal | 2 | 3 | 0 | 0 | 9 | 0 | 0 | 13 | 0 |
| New Mine Top and Fire Clay Coals | 3 | 9 | 1 | 0 | 10 | 2 | 1 | 0 | 3 |
| New Mine Bottom Coal . | 4 | 10 | 0 | 0 | 18 | 0 | 1 | 7 | 0 |
| | 18 | 16 | 1 | 3 | 12 | 2 | 6 | 5 | 3 |
| Average day's getting . | 3 | 2 | 2 | 0 | 12 | 0 | 1 | 0 | 3 |

giving a total daily production of 4 tons 15 cwts. 1qr. per man. The output of ironstone, according to the same authority, per man per day being as follows, from the ironstone measures named :—*

| IRONSTONE MEASURES. | Tons. | Cwts. | Qrs. |
|--------------------------------------|-------|-------|------|
| Thick Coal or Black Gubbin | 0 | 18 | 3 |
| New Mine " | 0 | 16 | 2 |
| Poor Robin | 0 | 18 | 3 |
| White Stone | 2 | 6 | 0 |
| Balls | 0 | 15 | 0 |
| Gubbin | 0 | 15 | 0 |
| Blue Flats | 2 | 6 | 0 |
| | 8 | 16 | 0 |
| Average day's getting | 1 | 5 | 0 |

Resources of Coal-field and probable Duration.—The result of the Coal Commission Inquiry shows that the aggregate acreage of coal, estimated as remaining unworked in South Staffordshire,

* "Miners' Guide," by Thomas Smith, of Sandy Fields, near Sedgeley, 1836. pp. 82, 83.

East Worcestershire, and Shropshire coal-fields, extend over an area of 136,368 acres, the coal amounting to 2,266,668,310 tons, while 360,548,542 tons are deducted as unavailable through inferior quality, waste in working, or destroyed by faults or other causes, leaving 1,906,119,768 tons available for future use. These estimates do not include any seam less than 12 inches in thickness, nor is any seam known to exist below 500 yards. Assuming 20 millions as the available coal remaining in the Shropshire area, there remained in the year 1870 some 1,886,119,768 tons in the South Staffordshire coal-field, which, at the rate of production (9,356,500 tons) in the year 1870,* would be exhausted in 200 years from that date.

Deducting the coal raised during the ten years ending 1879, amounting to 96,445,475 tons, there remained at the end of 1879 some 1,789,674,293 tons, which, at the average of the past ten years, 9,644,547 tons, would afford supplies for 186 years hence.

The production of this coal-field in the year 1880 shows a slight increase over the average output of the past ten years; the total amounting to 9,660,000 tons, of which 8,231,000 tons was raised in South Staffordshire, and 1,429,000 tons in the Worcestershire extension of the coal-field.

The "ten yard" or thick coal, on either side of Dudley, was estimated by Mr. William Matthews in 1870 to last 40 years from that date, at the then rate of production.

* Mineral Statistics of the United Kingdom.

CHAPTER XIII.

NORTH WALES COAL-FIELDS.

Description of the Anglesea, Denbigh, and Flint Coal-fields and Succession of Strata—Analyses—Production and Distribution of Coal—Population employed in Coal Mining—Resources and probable Duration.

The North Wales Coal Fields.—These are situated in the counties of Anglesea, Denbigh, and Flint. The *Anglesea coal-field** forms a band of country stretching from Hirdrefaig, to Malldreath Bay, a distance of nine miles, its breadth at Malldreath Marsh being a mile and a half. The succession of strata as determined by Professor Ramsay appears in the following section.†

SUCCESSION OF STRATA ANGLESEA COAL-FIELD.

| | Ft. | In. |
|---|-----|-----|
| <i>Permian Rocks.</i> —Red Sandstone, Marl and conglomerate . | 195 | 0 |
| <i>Coal Measures</i> (1309 ft.).—Coal (Glopux) lying in lumps . | 9 | 0 |
| Shale | 51 | 0 |
| Coal | 3 | 0 |
| Shale | 63 | 0 |
| Coal | 4 | 0 |
| Strata | 75 | 0 |
| Coal (irregular) | 2 | 0 |
| Strata | 43 | 0 |
| Coal | 6 | 0 |
| Strata | 90 | 0 |
| Coal (with Cannel roof) | 1 | 8 |
| Strata (about) | 300 | 0 |
| Coal (supposed Berw Uchaf coal, in three beds with partings) | 7 | 6 |
| Strata | 650 | 0 |
| <i>Millstone Grit.</i> —Coal (perhaps in Millstone Grit) 2 ft. 0 in. to | 3 | 0 |
| " " Yellow Sandstone and conglomerate | 200 | 0 |
| <i>Carboniferous Limestone.</i> —Grey and Black Limestone and Sandstone with Productus, Spirifer, Corals, &c. | 450 | 0 |

There are eight seams of coal in this outlying coal-field, from which no coal was raised in the year 1879 or 1880.

The Denbighshire Coal-field is some eighteen miles in length by four in width, commencing three miles south of Oswestry,

* "Coal-fields of Great Britain," pp. 162, 163.

† "Explanation of Section of Geological Survey," sheet 40, and Geological Map, sheet 78.

where the new red sandstone begins to rest directly on the Millstone Grit, and extends northward by Oswestry to Ruabon and Wrexham, to the north of the valley of the Alyn. The seams of coal in the field are not numerous, nine in number. The upper and lower sulphurous seams at the top of the series are not worked. The other seams and strata occur in the following order with the respective thicknesses :—

SUCCESSION OF COAL SEAMS, DENBIGHSHIRE COAL FIELD.

| | Yds. | Ft. | In. |
|---|------------|----------|-----------|
| <i>Top Sulphurous Coal</i> | 0 | 4 | 0 |
| <i>Strata</i> | 70 | 0 | 10 |
| <i>Bottom Sulphurous Coal</i> | 0 | 4 | 6 |
| <i>Strata</i> | 10 | 0 | 7 |
| <i>Smith's Coal</i> | 0 | 2 | 2 |
| <i>Strata</i> | 12 | 1 | 1 |
| <i>Drowsall Coal (good quality)</i> | 0 | 3 | 0 |
| <i>Strata</i> | 9 | 0 | 8 |
| <i>Powell Coal</i> | 0 | 3 | 3 |
| <i>Strata</i> | 9 | 1 | 3 |
| <i>Two-yard Coal</i> | 0 | 6 | 0 |
| <i>Strata</i> | 11 | 0 | 0 |
| <i>Crank Coal</i> | 0 | 2 | 8 |
| <i>Strata with Brassey Ironstone</i> | 10 | 2 | 6 |
| <i>Brassey Coal</i> | 0 | 5 | 0 |
| <i>Strata with Black Band Ironstone 18 in.</i> | 10 | 0 | 11 |
| <i>Main Coal, with a parting of clay 18 in.</i> | 0 | 7 | 6 |
| Total | 156 | 0 | 10 |

Some valuable seams of ironstone occur in this coal-field, the principal being the "Brassey" and "Black Band;" this last measure abounds in fossil remains of fish scales, teeth, and also contains a bivalve shell of the genus *Anthracosia*.

The Flintshire Coal-field extends for a distance of fifteen miles along the western side of the estuary of the Dee to the point of Air, but throughout a considerable part of its range the productive portion is narrow and greatly broken by faults. The coal seams dip beneath the estuary, reappearing through a fault near Parkgate, and underlie the New Red Sandstone of the Cheshire plain. Professor Hull gives the following general section of this coal-field :—

SUCCESSION OF STRATA, FLINTSHIRE COAL FIELD.

| | Ft. | In. |
|---|-----|-----|
| <i>Four-foot Coal (Cannel Coal)</i> | 4 | 0 |
| <i>Strata</i> | 41 | 0 |
| <i>Bind Coal</i> | 2 | 6 |
| <i>Strata with ironstone</i> | 62 | 0 |
| <i>Hollin Coal (in three beds)</i> | 6 | 6 |

| | Ft. | In. |
|---|----------------|-----|
| <i>Cannel</i> | 1 | 6 |
| <i>Strata with ironstone</i> | 29 | 0 |
| <i>Brassey Coal</i> | 3 | 0 |
| <i>Strata</i> | 82 | 0 |
| <i>Main Coal</i> | 7 | 0 |
| <i>Strata</i> | 180 ft. to 300 | 0 |
| <i>Lower Four-foot Coal</i> (in some places <i>Cannel</i>) | 4 | 0 |

The main and Brassey Coal of Flintshire and Denbighshire correspond; the Hollin of the first is the Two Yard of the second, while the "Bind" and the "Powell" seams are identified, so also with the intermediate measures of ironstone of Flintshire; they also correspond with Denbighshire. These coal-fields were probably at one time continuous, though they are now divided by the Millstone Grit, and severed by the Great Bala fault, one of the most extensive in Great Britain, traceable from the sea on the coast at Merionethshire through Bala lake into Cheshire, and with a displacement of from 10,000 to 12,000 feet. The total area of the Flintshire coal-field is 85 square miles with an estimated thickness of 85 feet of coal.

The coal and shales of these coal-fields are of considerable importance as gas and oil producers, as well as being adapted to household purposes. Those employed for gas-making (cannel) in Flintshire constitute a large portion of the Hollin Coal, and of the Lower four-foot coal of Leeswood near Mold. This latter seam is reported to yield a larger percentage of gas than the far-famed Wigan cannel, but the rich gas-producing area is limited to a comparatively small district, and is being rapidly exhausted.

Analyses of the North Wales Coal.—The bituminous coals of Denbighshire, examined by Mr. Lewis Thompson, show the following constituents; the coals reported upon being seams worked in the Ruabon district, known as the following:—

| Constituents. | RUABON COALS. | | | |
|-----------------------------------|---------------|------------|------------|------------|
| | Top Yard. | Main Seam. | Yard Seam. | Nant Seam. |
| Volatile matter | 37·50 | 41·50 | 34·00 | 37·90 |
| Coke | 62·50 | 58·50 | 66·00 | 62·10 |
| Ash | 2·50 | 1·00 | 1·40 | 1·40 |
| Sulphur in coal | 1·40 | 0·85 | 1·10 | 1·10 |
| " in coke | 0·80 | 0·45 | 0·60 | 0·70 |
| " in volatile matter | 0·60 | 0·40 | 0·50 | 0·40 |
| Ash in coke (per cent.) | 4·00 | 1·70 | 2·10 | 2·20 |
| Specific gravity | 1·269 | 1·284 | 1·271 | 1·269 |

The Ruabon Main Coal in the above series yielding by far the greatest proportion of volatile matter is thus described: "Coal black and laminated; fracture irregular, inclining to cubical; cross-fracture, foliated and splinty, with numerous layers of charcoal and other indications of iron pyrites; streak, dull black. On the fire swells, and fuses together; ash, pale yellow."

The "Main Coal" and the "Two Yard Coal" worked by the Brymbo Company, Wrexham, employed as furnace and steam coal afford the following results on examination:—

RESULTS TABULATED.

| Constituents. | Brymbo Main Coal. | Brymbo Two-yard. |
|--------------------|----------------------|---------------------|
| Carbon | 77·87 | 78·13 |
| Hydrogen | 5·09 | 5·53 |
| Nitrogen | 0·57 | 0·54 |
| Sulphur | 2·73 | 1·88 |
| Oxygen | 9·52 | 8·02 |
| Ash | 4·22 | 5·90 |
| | 100·00 | 100·00 |

The yield of coke from these coals is equivalent respectively to 55·40 and 56·20 per cent., the specific gravity being 1·301 and 1·288.

Other analyses made in Dr. Percy's laboratory in the Royal School of Mines by Mr. W. L. Ward, give the following results. The coal examined was obtained from the "Main Seam" and the "Crank Seam," Wrexham, Denbighshire.

RESULTS TABULATED.

| Constituents. | Main Coal. | Crank Coal. |
|-------------------------------|------------|-------------|
| Carbon | 78·44 | 81·29 |
| Hydrogen | 5·27 | 4·23 |
| Oxygen and Nitrogen | 8·30 | 6·77 |
| Sulphur | 0·99 | 0·91 |
| Ash | 2·15 | 2·50 |
| Water | 4·85 | 4·10 |
| | 100·00 | 99·80 |

The Main Coal yields when coked 61·88 per cent., the coke being somewhat lustrous and coherent, the colour of the ash light red. The Crank Coal, it should be observed, is a non-caking

coal; colour of the ash light red. This coal is largely composed of the fibrous charcoal-like stuff, commonly called "mother of coal."

The coal of several seams raised at the Ffrwd Collieries of Messrs. Sparrow and Poole situated near Wrexham in Denbighshire, gave the following results on examination by Mr. Edward Riley. The annexed refers to the five feet coal, the best furnace coal of the district. The whole of the sample was intimately pulverised. It contained moisture 4·32 per cent. The coal dried at 212° Fahr., giving the following:—

RESULTS TABULATED.

| | |
|-------------------------|-------|
| Coke, per cent. | 67·28 |
| Sulphur | ·94 |
| Ash | 4·27 |

The ash consisting of silica 49 per cent, iron peroxide, and alumina, 3·06 per cent., with lime and traces of magnesia 72 per cent.; a second analysis of the same coal giving 66·59 per cent. of coke, and 4·43 per cent. of ash.

The Powell coal examined consisted of three samples, each of which was pulverized separately, and an intimate mixture made of equal weights of the powder. The mixture gave moisture 3·48 per cent. The coal dried at 212° Fahr., giving the following:—

RESULTS TABULATED.

| | |
|-------------------------|-------|
| Coke, per cent. | 66·61 |
| Sulphur | 4·15 |
| Ash | 6·61 |

The ash consisted of silica 1·14 per cent., oxide of iron and alumina 5·28 per cent., and an appreciable amount of phosphoric acid and lime, amounting to 0·19 per cent. A second sample of the same coal prepared under similar conditions gave of coke 67·18 per cent. and 6·50 per cent. of ash. This coal appears to be extensively used for lime-burning, brick-making, &c.; it is a caking coal and makes a good coke, it has been tried in the blast furnace, but it was found after some days' trial it would only make white iron.

Samples of the Top, Bind, and Bottom seams examined under similar conditions as the preceding seams, the samples being pulverized, and equal weights of each intimately mixed, gave of moisture 3·38 per cent., and dried at a temperature of 212° Fahr. the annexed results were obtained of two varieties:—

RESULTS TABULATED.

| Constituents. | First. | Second. |
|------------------------|--------|---------|
| Coke per cent. | 67·91 | 67·01 |
| Sulphur | 1·15 | ... |
| Ash | 2·25 | 2·48 |

The ash in the first analysis consisted of 0·68 per cent. of silica, oxide of iron and alumina 1·28 per cent., and 0·56 per cent. of lime with a little magnesia.

The second example examined is a furnace coal of second quality, containing but a small proportion of sulphur; so far as experience goes it does not appear to be a strong coal, crushing to some extent in the blast furnace, while as a coking coal it gives very good results.

Another seam of coal in the Wrexham district, examined also by Mr. Riley, name not stated, gave the annexed results. The coal contained moisture 4·79 per cent., giving when dried at 212° Fahr. :—

RESULTS TABULATED.

| | |
|-------------------------|-------|
| Coke, per cent. | 66·31 |
| Sulphur | 0·96 |
| Ash | 1·48 |

The ash consisting of silica 0·45 per cent., oxide of iron and alumina 0·63 per cent., and 0·40 per cent. of lime, with a little magnesia. It is remarked of this coal that the ash is white in colour; the coal appears to make a hard coke, well adapted for use in the blast furnace, the percentage of sulphur being inconsiderable.

In this seam, and in others in the district, there are occasionally found thin veins or balls of iron pyrites; these when carefully removed not only increase the value of the coal, but render it available for use in the blast furnace.

The Flintshire Coals, described as free burning, strong, not binding, and leaving a white ash, the principal markets for which are Liverpool, Chester, Holyhead, the Isle of Man, and the local metallurgical establishments, give the following composition:—Those examined, the “Ewloe” and the “Bagillt Main Coal,” are thus referred to. The Ewloe coal is a “splinty coal of a brown black colour, containing large quantities of mineralised charcoal and iron pyrites, although less white shale was observed than usually occurs in coals of this part of the principality.” The

Ewloe coal is worked in the parish of Hawarden. The thickness of the seam varies from 8 to 10 feet, and occurs at a depth of 160 yards from the surface. The "Bagillt Main Seam" is a vein 5 feet thick, worked at a depth of 100 yards from the surface; the colliery is situated in the parish of Holywell, bordering on the River Dee, from which river it is distant about one mile. As steam coals they are found to light easily, burn freely, and blow off much steam. These coals evolve much smoke and soot, and a considerable amount of ash and cinder; the amount of clinker left, however, is small. The mean composition of average samples of these coals is as follows:—*

RESULTS TABULATED.

| Constituents. | Ewloe Coal. | Bagillt Main. |
|---------------------------------|-------------|---------------|
| Carbon | 80·97 | 88·48 |
| Hydrogen | 4·96 | 5·62 |
| Nitrogen | 1·10 | 2·02 |
| Sulphur | 1·40 | 1·36 |
| Oxygen | 8·20 | 0·86 |
| Ash | 3·37 | 1·62 |
| | 100·00 | 199·96 |
| Specific gravity | 1·275 | 1·269 |
| Coke per cent. | 54·50 | 55·80 |
| Weight of a cubic foot | 54·51 lbs. | 49·63 lbs. |
| Space occupied by a ton | 44·44ft. | 45·16 ft. |

Cannel coal is not widely diffused in our coal-fields, the most noted localities being Wigan in Lancashire, the most important in Great Britain; and Leeswood (south of Mold), Flintshire; Gilmerton, near Edinburgh; Muirkirk, in Lanarkshire, and a few other localities in Ayrshire and Fifeshire. The character of cannel coal is very variable; where it occurs in its most perfect form, as at Leeswood Green, near Mold, Flintshire, the roof of the seam is usually of a rich oleaginous shale, from 4 to 10 inches through. Next below comes what is termed the smooth cannel, which is about 27 inches thick. This mineral is described as possessing a flat conchoidal fracture, and in addition to its more important commercial properties might, if required, be converted into jet-like ornaments. The smooth cannel passes insensibly down, trending into what is known and highly prized as "curly cannel," which may be said

* "Coals Suited to the Steam Navy," 3rd Report, pp. 16, 31, and 55.

to average 18 inches in thickness. The cannel seat or floor is a highly bituminous shale, occasionally passing into an impure coal, and associated with a black band ironstone. The aspect of the curly cannel is quite unique; it is lustrous, compact, and imperfectly conchoidal, with numerous flat circular disc-like appearances.

In a report on the Leeswood cannel, made by Dr. Andrew Fife, to ascertain its value as a gas-producing mineral, and also as a coke-giving coal, the annexed table noting the results of his examination exhibits the character, in comparison with other well-known cannels:—

| | Leeswood smooth Cannel. | Leeswood curly Cannel. | Wigan Cannel. | Leesmahago Cannel. | Torbane or Boghead Coal. |
|---|-------------------------------|------------------------------|------------------|-----------------------|--------------------------------|
| Cubic feet of gas per ton | 9,972 | 14,280 | 12,100 | 10,176 | 15,482 |
| Durability of gas per foot: min. | 58.05 | 82.30 | 48.35 | 70.00 | 84.40 |
| Illuminating power per foot, candles | 8.2 | 1.09 | 5.00 | 8.70 | 10.30 |
| Grains of sperm per foot | 0.981 | 1.308 | 0.36 | 1.044 | 1.242 |
| Value of coals in lbs. of sperm | 1401.7 | 2668.3 | 617.00 | 1517.0 | 2736.0 |
| Comparative value of the coals | 5.610 | 5.025 | ... | 1.16 | 2.86 |

Production of Coal.—From Pennant, in his “Tour in Wales,” * written in the year 1810, we have the following account of the Mostyn collieries in Flintshire:—“The collieries of Mostyn and Bychton have been worked for a very considerable time, and in the last century (the eighteenth) supplied Dublin and the eastern side of Ireland with coals. They were discovered in the township of Mostyn as early as the time of Edward I., as appears by an “Extent” of that place, in the 28rd year of his reign. They are at present in a low state, partly from the rise of the works at Whitehaven, but more from the loss of channel of the Dee, which in the beginning of this century flowed so close to our shore, that ships of 200 tons lay under this parish with their cables twisted round the trees. At present vessels of 60 or 70 tons cannot approach nearer than two miles, the Dee now flowing under the opposite shore. Still, we load a few vessels for Ireland, and some for North Wales. Much is also consumed by the neighbouring smelting-houses and the inland parts of Denbighshire.

* Thos. Pennant's “Tour in Wales,” Vol. i., p. 23, 1810.

The improvement of land by lime has of late occasioned a great consumption of coal by the farmers, and by the persons who burn it for sale."

From the agricultural survey of North Wales, published in 1794,* it appears that there was but one colliery in Anglesea producing ten tons per day, or about 3,000 tons a year, and sold at 16s. per ton at the pit's mouth. The metallurgical works of the Pary's Mountain and Sulphur Company, now known as the Mona Smelting Works, appear to have been the only manufacture then carried on in the district. Until the year 1854 there does not exist any information showing the production of the coal-fields of North Wales, the output of the collieries being included with those of other coal-fields. In that year, however, 1,148,000 tons were raised from the 60 collieries then in operation in Denbighshire, Flintshire, and Anglesea, and in the following year 1,125,000 tons, the yield of 65 collieries.

In subsequent years the production of the respective coal-fields in North Wales are separately distinguished, the quantities being as follows, with the total number of collieries in the three coal-fields:—†

| Year. | Number of Collieries. | Denbighshire. | Flintshire. | Anglesea. |
|-------|-----------------------|---------------|-------------|-----------|
| | Nos. | Tons. | Tons. | Tons. |
| 1856 | 81 | 527,000 | 519,500 | † |
| 1857 | 84 | 527,000 | 519,500 | † |
| 1858 | 81 | 525,000 | 497,000 | † |
| 1859 | 81 | 1,039,500 | 587,500 | 35,000 |
| 1860 | 84 | 1,139,500 | 590,500 | 20,500 |
| 1861 | 78 | 1,250,000 | 600,500 | 19,750 |
| 1862 | 77 | 1,016,000 | 625,500 | 18,500 |
| 1863 | 81 | 1,078,500 | 631,500 | 18,000 |
| 1864 | 81 | 1,381,560 | 590,500 | 15,000 |
| 1865 | 84 | 1,395,000 | 575,000 | 12,500 |
| 1866 | 80 | 1,500,000 | 570,000 | 12,000 |
| 1867 | 75 | 1,475,250 | 885,500 | 10,500 |
| 1868 | 66 | 1,520,000 | 857,500 | 7,500 |
| 1869 | 65 | 1,427,701 | 725,288 | 2,191 |
| 1874 | 122 | 1,435,950 | 985,000 | 3,850 |
| 1875 | 124 | 1,379,560 | 955,500 | 2,248 |
| 1876 | 128 | 1,355,500 | 850,000 | 1,750 |
| 1877 | 112 | 1,622,500 | 855,750 | 1,330 |
| 1878 | 107 | 1,513,900 | 707,785 | 672 |
| 1879 | 105 | 1,498,985 | 720,697 | ... |
| 1880 | 76 | 1,650,406 | 778,909 | ... |

* The Rev. Walter Davies, M.A., 1794.

† Mineral Statistics.

‡ Included in Flintshire.

Summarising the above returns of the coal produce of North Wales, the following shows the number of collieries in each county, as also the total output :—

| Year. | NUMBER OF COLLIERIES. | | | Total of North Wales. |
|-------|-----------------------|-------------|-----------|--------------------------|
| | Denbigh- shire. | Flintshire. | Anglesea. | |
| | Nos. | Nos. | Nos. | Tons. |
| 1854 | 25 | 30 | 5 | 1,143,000 |
| 1855 | 29 | 31 | 5 | 1,125,000 |
| 1856 | 34 | 42 | 5 | 1,046,500 |
| 1857 | 39 | 40 | 5 | 1,046,500 |
| 1858 | 39 | 37 | 5 | 1,022,500 |
| 1859 | 38 | 38 | 5 | 1,662,000 |
| 1860 | 39 | 40 | 5 | 1,750,500 |
| 1861 | 35 | 38 | 5 | 1,870,250 |
| 1862 | 31 | 41 | 5 | 1,660,000 |
| 1863 | 35 | 41 | 5 | 1,728,000 |
| 1864 | 35 | 41 | 5 | 1,987,060 |
| 1865 | 36 | 43 | 5 | 1,983,000 |
| 1866 | 35 | 40 | 5 | 2,082,000 |
| 1867 | 34 | 37 | 4 | 2,371,250 |
| 1868 | 29 | 34 | 3 | 2,385,000 |
| 1869 | 31 | 32 | 2 | 2,155,180 |
| 1870 | 23 | 28 | 2 | 2,329,030 |
| 1871 | 24 | 32 | 2 | 2,500,000 |
| 1872 | 38 | 34 | 2 | * |
| 1873 | 50 | 62 | 3 | 2,450,000 |
| 1874 | 59 | 60 | 3 | 2,425,300 |
| 1875 | 61 | 60 | 3 | 2,337,308 |
| 1876 | 61 | 64 | 3 | 2,207,250 |
| 1877 | 59 | 51 | 2 | 2,479,580 |
| 1878 | 54 | 51 | 2 | 2,222,357 |
| 1879 | 53 | 52 | ... | 2,219,682 |
| 1880 | 38 | 38 | ... | 2,429,315† |

Cannel coal appears to have been discovered in Flintshire about the year 1862, at Leeswood, when 28,816 tons were raised. This quantity was increased to 120,000 tons in the year 1864, when the following collieries were raising cannel coal :—Leeswood Green, Leeswood Hill, Coed Talon, Coppa and Nerquis, all situated near Mold, and at Wern near Bagillt. The production of cannel in 1865 amounted to 150,000 tons in Flint-

* Included in West Lancashire, but estimated at 2,600,000 tons.

† Report H.M. Inspectors of Mines, 1880.

shire. The production of the seams yielding cannel the same year in the collieries of the United Kingdom was as follows :—

| | TONS. |
|--------------------|------------------|
| England | 946,175 |
| Wales | 150,000 |
| Scotland | 322,000 |
| Total | <u>1,418,175</u> |

The yield of cannel coal not being separately distinguished from that of bituminous coal and anthracite since the above-named year, the following details of the quantity raised in England in 1865 will generally indicate those coal-fields from which the cannel coal was then obtained :—

| COUNTIES. | TONS. |
|---------------------------------------|----------------|
| South Staffordshire | 10,000 |
| Nottinghamshire | 46,950 |
| Derbyshire | 42,225 |
| Yorkshire | 185,000 |
| Lancashire | 630,000 |
| Cheshire | 12,000 |
| Total production in England | <u>946,175</u> |

Of the total cannel coal raised in the year 1865, it was estimated that 250,000 tons were submitted to distillation for coal-oil, leaving 1,168,175 tons available for gas manufacture and other purposes.

Distribution of Coal.—The coal of North Wales has long enjoyed a high reputation for various commercial purposes, and is extensively employed as a steam coal, for gas manufacture and coking, and some varieties for the blast-furnace and foundry. As a house coal some seams of the Ruabon district, in Denbighshire, are especially suitable, and these coals are in good demand in the midland counties and the metropolis. The early returns bearing on the distribution of coal from North Wales are not important; those returns, however, of recent years, show in a marked manner the increasing demand. The following table giving the quantities carried out of the district by the London and North-Western and Great Western Railways, will show the extent of the distribution since 1863 :—

| Year. | London and North-Western Railway. | Great Western Railway. |
|-------|--------------------------------------|---------------------------|
| | Tons. | Tons. |
| 1863 | 196,957 | ... |
| 1864 | 216,043 | ... |
| 1865 | 305,000 | 625,291 |
| 1866 | 310,863 | 600,000 |
| 1867 | 372,755 | 627,355 |
| 1868 | 381,668 | 703,379 |
| 1869 | 321,367 | 611,524 |
| 1870 | 376,512 | 646,810 |
| 1871 | 391,516 | 839,090 |
| 1872 | 408,667 | 967,855 |
| 1873 | 481,284 | 950,746 |
| 1874 | 464,808 | 864,162 |
| 1875 | 424,118 | 802,763 |
| 1876 | 368,554 | 1,055,775 |
| 1877 | 373,464 | 1,183,205 |
| 1878 | 328,325 | 988,675 |
| 1879 | 316,200 | 952,154 |
| 1880 | 304,509 | 960,934 |

While the above figures exhibit the increased distribution of the North Wales coal since the year 1863, the London and North-Western Railway, it appears, carried over its extensive system from the several coal-fields which it traverses in the same year, 3,756,111 tons, increased to 8,299,491 tons in the year 1873, and 11,100,891 tons in the year 1880. The Great Western Railway in the same manner carried a total of 982,104 tons in the year 1857, increased to 6,412,798 tons in the year 1877, and 6,909,968 tons in the year 1880.

Population employed in Coal Mining in North Wales. ANGLESEA.—The number employed in the year 1854 in coal mining was 51 persons of all ages. Not again until 1874 do any returns appear; in that year, however, and until 1878, the numbers employed under and above ground are as follows :—

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 32 | 20 | 52 | 3,746 | 72 |
| 1875 | 15 | 7 | 22 | 2,248 | 102 |
| 1876 | 12 | 7 | 19 | 1,820 | 96 |
| 1877 | 10 | 7 | 17 | 1,320 | 77 |
| 1878 | 7 | 6 | 13 | 672 | 51 |

DENBIGHSHIRE.—The number engaged in coal mining in the year 1854 was 3,017, and in iron mining three persons. The quantity of coal raised being included in the production of North Wales, which in that year amounted to 1,143,000 tons, the total number of persons engaged in its output being 4,623, of whom 1,555 were in Flintshire, and 51 in Anglesea. Since the year 1874 the figures are as under :—*

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 6,488 | 1,628 | 8,116 | 1,431,959 | 176 |
| 1875 | 6,419 | 1,683 | 8,102 | 1,381,380 | 171 |
| 1876 | 5,947 | 1,497 | 7,444 | 1,560,388 | 210 |
| 1877 | 5,228 | 1,444 | 6,672 | 1,618,077 | 243 |
| 1878 | 5,025 | 1,232 | 6,257 | 1,514,829 | 242 |
| 1879 | 5,377 | 1,278 | 6,655 | 1,499,857 | 225 |
| 1880 | 5,689 | 1,270 | 6,959 | 1,650,406 | 237 |

In the year 1879 the ages of those employed above and below ground are thus distinguished :—

| All Ages. | Under Ground. | Above Ground. | Total. |
|-----------------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| Between 12 and 13 . . | 33 | ... | 33 |
| „ 13 and 16 . . | 398 | 98† | 496 |
| „ 16 and 18 . . | ... | 7‡ | 7 |
| Above 18 | 4,946 | 1,173§ | 6,119 |
| Total | 5,377 | 1,278 | 6,655 |

FLINTSHIRE.—The total number of persons of all ages engaged in coal mining in Flintshire in the year 1854 was 1,555. Occasional returns are met with in later years, but none sufficiently complete for comparison. In 1874,|| and since the necessary data are available, and appear in the annexed table, showing the numbers employed, the quantities of coal raised, and the average produce per man :—

* Reports of H.M. Inspectors of Mines.

† Including 11 females. ‡ Including 4 females. § Including 61 females.

|| Report H.M. Inspector of Coal Mines, Mr. Henry Hall.

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 4,567 | 1,401 | 5,968 | 993,332 | 166 |
| 1875 | 4,266 | 1,208 | 5,474 | 965,490 | 176 |
| 1876 | 3,472 | 1,046 | 4,518 | 855,257 | 189 |
| 1877 | 3,078 | 1,029 | 4,107 | 854,923 | 208 |
| 1878 | 2,608 | 766 | 3,374 | 708,724 | 210 |
| 1879 | 2,733 | 754 | 3,487 | 721,697 | 207 |
| 1880 | 2,633 | 616 | 3,249 | 778,909 | 240 |

In the year 1879 the respective ages of those employed are classified as follows :—*

| All Ages. | Under Ground. | Above Ground. | Total. |
|-----------------------|---------------|---------------|--------|
| | Nos. | Nos. | Nos. |
| From 13 to 16 | 108 | 86 | 194 |
| Above 16 | 2,625 | 663 | 3,293 |
| Total | 2,733 | 754 | 3,487 |

Summarising the number of persons employed in the coal-fields of Anglesea, Denbighshire, and Flintshire, for the seven years ending 1880, the annexed table shows the aggregate employed in North Wales, with the total output of coal, which is supplemented by the average output of coal per man for the whole district :—*

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. North Wales. | Average per Man. |
|-------|-------------------|---------------|--------|------------------------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 11,087 | 3,049 | 14,136 | 2,429,037 | 172 |
| 1875 | 10,700 | 2,898 | 13,598 | 2,349,118 | 172 |
| 1876 | 9,431 | 2,550 | 11,981 | 2,417,965 | 202 |
| 1877 | 8,316 | 2,480 | 10,796 | 2,474,320 | 229 |
| 1878 | 7,640 | 2,004 | 9,644 | 2,224,225 | 230 |
| 1879 | 8,110 | 2,032 | 10,142 | 2,221,554 | 220 |
| 1880 | 8,322 | 1,886 | 10,208 | 2,429,315 | 238 |

Mr. H. Hall, in 1879, gives the average quantity of coal raised per man in North Wales as 220 tons, and in West Lancashire also, in his inspection district, 326 tons. This apparent deficiency

* Reports H.M. Inspector of Coal Mines, Mr. Henry Hall, West Lancashire and North Wales.

in individual efficiency, Mr. Hall remarks, appears from year to year, and it is difficult to fix the cause. "The 'output' at many of the North Wales collieries is very small, and machinery for hauling is not so general as in other districts, thus entailing more manual labour, and the demand for the class of coal produced is not such as to keep the collieries constantly at work; nor is the atmosphere of many of the mines such as is likely to encourage energetic labour."

Resources of the North Wales Coal-fields.—The total number of statute foot acres of coal wrought and unwrought in the North Wales coal-fields as enumerated by Mr. Joseph Dickinson, in the "Coal Commission Report,"* amounts to 2,585,315 acres, and of this area 364,210 acres have already been wrought at the date of the Report (1870).

The acreage of the respective coal-fields, the depths of coal from surface, the total originally existing, and those portions wrought, appear in the annexed statement:—

| North Wales Coal-fields. | DEPTHS FROM THE SURFACE. | | | Portion already Wrought. |
|--------------------------|---------------------------|-------------------------------|------------------------------|--------------------------|
| | Not exceeding 3,000 feet. | Between 3,000 and 4,000 feet. | Total Wrought and Unwrought. | |
| | Acres. | Acres. | Acres. | Acres. |
| Anglesea . . . | 7,513 | ... | 7,513 | 1,959 |
| Denbighshire . . | 915,882 | 299,080 | 1,214,962 | 80,000 |
| Flintshire† . . . | 1,362,840 | ... | 1,362,840 | 282,251 |
| Total acres . . | 2,286,235 | 299,080 | 2,585,315 | 364,210 |

Of the acreage of coal yet remaining in the above coal-fields, considerable reductions for faults, supports, barriers, &c., are made, leaving the portion unwrought, likely to be clear for working, 1,435,788 statute foot acres. This acreage is apportioned as under:—

| North Wales Coal-fields. | Acreage remaining unwrought. | Acreage unwrought deducted for faults, barriers, &c. | Acreage unwrought likely to be clear for Working. |
|--------------------------|------------------------------|--|---|
| | Acres. | Acres. | Acres. |
| Anglesea . . . | 5,554 | 1,586 | 3,968 |
| Denbighshire . . . | 1,134,962 | 215,622 | 919,340 |
| Flintshire . . . | 1,080,589 | 568,109 | 512,480 |
| Total . . . | 2,221,105 | 785,317 | 1,435,788 |

* Vol. i., p. 18. † Including Neston in Cheshire and the Estuary of the Dee.

In the computation of the acreage remaining unwrought, and likely to be clear for working, an allowance of one-fourteenth has been made for unavoidable loss and waste in working, and 1,400 tons have been taken as the average yield of each foot acre. This estimate gives to each of the North Wales coal-fields the available quantities as follows, in statute tons of 2,240 lbs.:—

| North Wales Coal-fields. | Tons of Coal remaining unwrought in each Coal-field. |
|--------------------------|---|
| Anglesea | Tons. 5,000,000 |
| Denbighshire | 1,287,000,000 |
| Flintshire | 718,000,000 |
| Total | 2,010,000,000 |

With the production of 1870,* amounting to 2,329,030 tons, and the above quantities, supplies would be available for 863 years. Deducting the production of North Wales for the ten years ending 1879, amounting to 23,770,507 tons, there remains 1,986,229,493 tons. This at the average of the ten years (2,377,050 tons), would afford supplies for 839 years; while, if the year of greatest production be taken (1872), when 2,600,000 tons were the output, the exhaustion of these coal-fields at that rate would occur 764 years hence.

* Mineral Statistics of the United Kingdom.

CHAPTER XIV.

SOUTH WALES COAL-FIELD.

Description of Coal-field, including its extension through the Counties of Pembroke, Glamorgan, Caermarthen, Breckon, and Monmouthshire—The Thickness of Strata and Seams of workable Coals—Analyses of the several varieties of Coal, Anthracitic and Bituminous—Coke manufacture at Ebbw Vale—The Coppée Process—The Bességes Process as carried out in France—Production of Coal-field—Parish Returns—Deep Winning at the Harris Navigation Pit—Bute Docks—Distribution of Coal Coastwise to Foreign Countries and by Railway—Prices and Cost of Production—Resources and probable Duration of Coal-field.

The South Wales Coal-field.—Excepting the coal basin of the Clyde in Scotland this is the largest coal-field in Great Britain, having a total area of 1,000 square miles, and a vertical section of strata associated with the coal measures of between 11,000 and 12,000 feet. The coal-field occupies a large area of the county of Glamorgan, and its extension appears in the neighbouring counties of Monmouth, Brecon, Caermarthen, and Pembroke, distributed as follows:—

| COUNTIES. | SQUARE MILES. |
|----------------------------|---------------|
| Monmouthshire | 104 |
| Glamorganshire | 518 |
| Brecknockshire | 74 |
| Caermarthenshire | 228 |
| Pembrokeshire | 76 |
| Total | <u>1000</u> |

Risca, Pontypool, and Blaenavon mark the eastern limit of the coal-field in Monmouthshire, from Pontypool to Saint Bride's Bay in Pembrokeshire, the western limit of the coal-field; its greatest length is about 89 miles; its greatest breadth in Glamorganshire being about 21 miles. From Abersychan, in Monmouthshire, to the Glyncoerrwg Fault in Glamorgan, the length is 24 miles and the average width 18 miles. From the Glyncoerrwg Fault going west to Neath, a distance of 9 miles, the average width is 20 miles. At Aberafon, 5 miles due south of Neath, a portion of the coal-field runs beneath Swansea Bay for a distance of 9 miles, and with an average breadth of

2½ miles, appearing again at Oystermouth. From the latter place to Kidwelly, a distance of 14 miles, it has an average breadth of 14 miles; a considerable portion of this part of the coal-field, however (9 miles long by 5 miles broad), lies beneath the estuary of the Burry and Llwchwr rivers. At Kidwelly the whole coal-field is lost beneath the waters of Caermarthen Bay, reappearing at Amroth, in Pembrokeshire; the portion beneath the sea being 15 miles in length, with an average width of 6 miles. From Amroth the coal-field runs uninterruptedly to Saint Bride's Bay, a distance of 20 miles, with an average breadth of only 5 miles. North of Walton, West Pembrokeshire, at the westernmost extremity of the field, the coal-measures take a sudden bend to the north for a distance of 5½ miles, with an average width of 1½ miles. This latter portion, however, is not taken into consideration in estimating the length of the coal-field. The average width west of the Glyncoirwg Fault is 9½ miles. From the exhaustive paper of Thomas Foster Brown, Esq., F.G.S., former President of the South Wales Institute of Engineers, on the South Wales coal-field, the foregoing facts are gathered, as also are the following general references to the geological succession of rocks in the area of the coal-field.

The Coal Measures repose principally on the millstone grit; westward, however, of Swansea Bay the millstone grit disappears, and the Lower coal-measures repose upon the Mountain limestone, and still further west the coal-measures lie immediately upon the Lower Silurian rocks. The millstone grit is of the usual lithological character of these beds; it contains few fossils. At its base occurs a stratum of conglomerate about 20 feet in thickness, its maximum thickness, where fully developed, being 220 feet. This formation is often confounded with the Farewell rock of the district, which is a true marine stratum lying above the millstone grit and in the true coal-measures.

The Mountain Limestone, immediately underlying the millstone grit and resting upon the Old Red Sandstone, is generally seen to dip, where it is exposed, conformably with the coal-measures. On the north of the coal-field the limestone ridge reaches a considerable altitude, in some places being more than 1,200 feet above the sea, while on the south crop the usual height is from 400 to 500 feet. The limestone is divisible into two horizons; first, upper beds, consisting of alternating dark shales, with bands of limestones passing downwards into massive beds

of the latter, the aggregate thickness being about from 700 to 1,000 feet.

The Old Red Sandstone, Upper Devonian, occupies a large proportion of the district under consideration. It consists of conglomerates, red and brown sandstones, marls, and calcareous constones, from 8,000 to 10,000 feet in thickness. On the north of the field these beds form the highest ground in South Wales, rising to the height of 2,910 feet above the level of the sea.

Silurian.—This formation consists of the Upper Silurian rocks (Ludlow and Wenlock series) in the east, and Middle Silurian (Llandovery rocks), and Lower Silurian (Llandeilo flags) in the west. Their thickness probably averages between 600 and 700 feet. They form tolerably high ground on the east of the coal-field, between Pontypool and Usk in Monmouthshire. South of Llandegfydd in the same shire, they are lost beneath the Old Red Sandstone, cropping up again around Llanfrechfa, three miles north of Newport, and again at Malpas, Penrhas, Llanhennock and Christchurch, all within a few miles from Newport. On the west, after striking beneath the beds of the Old Red Sandstone for some distance, they re-appear on the surface near Saint Mellon's; from whence they run uninterruptedly to Pen-y-lan and Rumney, near Cardiff. In the west of the coal-field the Lower Silurian beds occupy a great portion of the counties of Caermarthen and Pembroke, by far the larger part of which is occupied by the Llandeilo flags, while the upper Llandovery rocks only occur on the southern border, between Langwm, Pembrokeshire, and Saint Bride's Bay.

The Coal Measure Series.—According to Mr. Vivian's Coal Commission Report in the South Wales' coal-field, the whole series of strata, from the uppermost Pellengare beds down to the millstone grit, is from 10,000 to 12,000 feet in thickness, containing about 80 seams of coal, of which 25 are from 2 feet upwards, with an aggregate thickness of 84 feet of workable coal. In the eastern part of the coal-field in Monmouthshire, according to Mr. Clarke of Dowlais, Coal Commission Report, the coal-measure series has a thickness of 11,650 feet, consisting of "Shales, with ironstones; sandstones, including the Gower series, and coal-beds of which there are about 25 more than 2 feet thick." The coal-measures are thus divided:—

Upper Pellengare Series, more than 3,400 feet.

Pennant Grit Series (Swansea), 3,246 feet.

Lower Coal Measures, 450 to 850 feet.

The upper series are thus divided: the first, consisting of shales and sandstones, down to the Mynyddysllwyn coal; the second strata, with 26 coal-seams, down to the Hughes Vein, 9 of the seams being over 2 feet thick; the Pennant Grit series, consisting of hard and thick bedded sandstones, &c., with 15 coal-seams, 5 of which are over 2 feet thick; the Lower coal-measures, consisting principally of shales, rich in ironstone and coal-seams, of which there are 34 in all, 8 of which exceed 2 feet in thickness.

The character of the coals of this great coal-field vary considerably in their chemical composition, as will be shown. The seams occupying the north-east side of the basin are chiefly coking or partly bituminous, those to the north-west are anthracitic. Again, on the south side of the basin, the seams are bituminous or gaseous, while the seams in the centre of the coal-field are known as semi-bituminous or steam coals. In the Aberdare area, in Glamorganshire, the seams are of that kind known as free burning and smokeless, hence their great importance for steam purposes, especially the Aberdare "Four Feet" steam coal, which is now nearly exhausted.

Analyses of the Coal.—Household, general manufacturing, and colliery coals are raised in the eastern part of the coal-field from the Upper and Lower Pennant Grit series. In the neighbourhood of Maesteg the lower coal-measures appear at a comparatively shallow depth, also at Carnarvon to the west; further to the west the same conditions appear, also to the northern, southern, and western edges of the basin, while in the inner area of the coal-field the Upper Pennant series is developed.

From the Merthyr, Taff Vale, and Rhondda Valleys the steam coal is principally obtained from the seams in the Lower coal-measures; on the northern outcrop, from Hirwain to Blaenavon, the coal raised is principally employed in the manufacture of iron at the several works in the limits above named.

The western limits of the coal-field alone produce anthracite. "As a mineral, anthracite occurs massive and amorphous; has a subconchoidal fracture, less or more of a metallic lustre, of a greyish-black or iron colour; streak unaltered, conducts electricity perfectly, and burns with a very weak or no flame." *

* Dr. Page's "Economic Geology."

The following analyses exhibit generally the chemical constituents of some of the principal anthracite coals of South Wales :—

| Districts. | Carbon. | Volatile Matter. | Ashes. |
|-------------------|---------|------------------|--------|
| Neath Abbey . . . | 91·08 | 5·01 | 4·00 |
| Swansea | 89·00 | 7·50 | 3·50 |
| Ystalyfera . . . | 92·46 | 6·04 | 1·50 |
| Cwm Neath . . . | 93·12 | 5·22 | 1·50 |

This variety of coal is also largely employed in the hop-drying and malt manufactures, while the small is much in request for the burning of lime. The annexed analysis exhibits the ordinary composition of the "Brass Vein" of the Cwmllynfell Colliery in Glamorganshire, also yielding anthracite. The seam is 4 feet thick, and takes its name from a vein of pyrites which runs through it; the coal in its immediate vicinity is considered by the colliers to be brighter, harder, and purer than any other portion of the seam. The analyses, side by side, is of anthracite from the Bonville Court Colliery, in Pembrokeshire, and Gwendraeth, in Caermarthenshire :—

| Constituents. | Brass Vein. | Bonville Court. | Gwendraeth. |
|--------------------|-------------|-----------------|-------------|
| Carbon | 91·44 | 94·18 | 92·17 |
| Hydrogen | 3·46 | 2·99 | 3·10 |
| Nitrogen | ·21 | ·76 | 1·08 |
| Sulphur | ·79 | ·59 | ·34 |
| Oxygen | 2·58 | ·50 | 2·22 |
| Ash | 1·52 | ·98 | 1·09 |
| | 100·00 | 100·00 | 100·00 |

The respective yield of coke being 92 and 93 per cent.

The coal-seams, as developed in the Western district of the coal-field in Pembrokeshire, are exclusively of the anthracitic variety. The same may be said generally of the north crop of the coal-field east of Caermarthen, while the south crop yields coal of a bituminous character, the centre of the basin yielding a free burning coal.

Beyond the above the annexed analyses gives the constituents of the following well-known seams of anthracite in South Wales :—

| Constituents. | CAERMARTHEN. | | PEMBROKE. | |
|--------------------|--------------|-----------|--------------|-----------|
| | Pontycaets. | Big Vein. | Timber Vein. | Watneys.* |
| Carbon | 91·16 | 88·7 | 93·0 | 92·17 |
| Oxygen | 2·74 | 7·4 | 1·67 | 2·22 |
| Nitrogen | ·91 | | ·54 | 1·08 |
| Hydrogen | 3·11 | | 3·08 | 3·10 |
| Sulphur | ·86 | ·5 | ·68 | ·34 |
| Ash | 1·12 | 3·4 | 1·03 | 1·09 |
| | 99·90 | 100·0 | 100·00 | 100·00 |

The valuable qualities of anthracite as a fuel have been long known and appreciated. Dr. Frankland who, in 1850, made careful analyses of the coal obtained in the neighbourhood of Saunders-foot; † recognises four special points connected with anthracite which especially recommend it as a steam coal. These are:—"the high evaporative power; the very small quantity of sulphur which it contains, and its entire freedom from iron pyrites (metallic cinder); the small amount of ash and clinker; and its requiring no stoking, and the entire absence of smoke during its combustion; these qualities, it may be further observed, are such important considerations, that although there are several bituminous coals which have, according to the Admiralty experiments, nearly the same evaporative power when well stoked, yet, in practice, would be found very greatly inferior because it is impossible to get the stoker to take the requisite trouble. This coal, however, places the manufacturer independent as it were of his stokers, who even by the most careless firing could scarcely perceptibly reduce its evaporative power."

The constant increase of evaporative power, with the increase of draught, as exhibited in the following experiments, indicates that a still higher result would be obtained with a stronger draught such as an ordinary steam shaft commands; but this is by no means the case with bituminous coals, which frequently give much better results with a slow than with a quick draught.

The following gives a comparative summary of the chief characteristics fitting coal for the mercantile marine. The first in the list is an anthracite coal, those following are some of

* Analysis, by Dr. Lyon Playfair.

† Report, printed by R. Mason, Tenby, 1850.

the most important varieties in the kingdom, and are intended for comparison :—

| Name of Coal. | Pounds of Water evaporated by one pound of Coal. | Cubic feet occupied by one ton. | Cohesive Power of Coal (per centage of large coal). | Pounds of Clinkers per ton of Coal. |
|------------------------|--|---------------------------------|---|-------------------------------------|
| Bonville's | 9·39 | 41·29 | 77·0 | 7·2 |
| Pentrefelin | 7·40 | 33·85 | 52·7 | 23·0 |
| Dalkeith | 7·10 | 44·98 | 85·7 | 62·2 |
| Wallsend, Elgin . . . | 8·67 | 41·02 | 64·0 | 14·6 |
| Neath Abbey | 9·65 | 37·77 | 50·0 | 19·2 |
| Newcastle, Hartley . . | 8·65 | 44·35 | 78·5 | 17·0 |
| Original Hartley . . . | 6·98 | 45·62 | 80·0 | 10·1 |
| Haswell's Wallsend . . | 7·85 | 45·25 | 79·5 | 9·8 |
| Cowpen Hartley . . . | 7·02 | 46·76 | 74·0 | 3·7 |
| Pontypool | 8·04 | 40·216 | 57·5 | 20·9 |

In addition to these advantages are the economic weight (space occupied by one ton), and great cohesive power possessed, which renders it a very valuable fuel for sea-going vessels, whilst its composition and general freedom from iron pyrites furnish a fair guarantee of its being little liable to spontaneous combustion.

Comparing the anthracite with other coals examined and reported upon in the Admiralty investigation, the annexed table of the constituents of the coals previously referred to, shows, in a remarkable manner, the purity of the anthracite :—

| Name of Coal. | Carbon. | Hydrogen. | Nitrogen. | Sulphur. | Ash. |
|--------------------------|---------|-----------|-----------|----------|-------|
| Bonville's Coal . . . | 94·16 | 2·99 | ·50 | ·59 | ·90 |
| Pentrefelin | 85·52 | 3·72 | trace | ·12 | 6·00 |
| Pontypool | 80·70 | 5·66 | 1·35 | 2·39 | 5·52 |
| Dalkeith (Jewel Seam) . | 74·55 | 5·14 | ·10 | ·33 | 4·37 |
| Wallsend Elgin | 76·09 | 5·22 | 1·41 | 1·53 | 10·70 |
| Neath Abbey | 89·04 | 5·05 | 1·07 | 1·60 | 3·55 |
| Newcastle Hartley . . . | 81·82 | 5·50 | 1·28 | 1·69 | 7·15 |
| Original Hartley | 81·18 | 5·56 | ·72 | 1·44 | 3·08 |
| Haswell Steam Wallsend | 83·76 | 5·31 | 1·06 | 1·21 | 5·94 |
| Cowpen Hartley | 82·20 | 5·10 | 1·69 | ·71 | 2·33 |

In the first report by De la Beche and Playfair on the coals suited to the steam navy * it has been shown that the true practical value of coals for steam purposes depends upon a combination of qualities which could only be elicited by carefully and properly

* See "Memoirs of the Geological Survey," vol. ii., part 2, p. 558.

continued experiments. These qualities, so far as regards steam ships of war, are referred to as follows:—

1. The fuel should burn so that steam may be raised in a short period, if this be desired; in other words, it should be able to produce a quick action.
2. It should possess high evaporative power, that is, be capable of converting much water into steam with a small consumption of coal.
3. It should not be bituminous, lest so much smoke be generated as to betray the position of ships of war when it is desirable that this should be concealed.
4. It should possess considerable cohesion of its particles, so that it may not be broken into too small fragments by the constant attrition which it may experience in the vessel.
5. It should combine a considerable density, with such mechanical structure that it may easily be stowed away in small space; a condition, which in coals of equal evaporative values, often involves a difference of more than 20 per cent.
6. It should be free from any considerable quantity of sulphur and should not progressively decay, both of which circumstances render it liable to spontaneous combustion.

Bituminous coals exhibit several varieties adapted to special purposes, known commercially as steam coal, furnace coal, household coal, gas coal, and coking coal. Those suited for raising steam are usually hard, burn open, and give a white heat; for the smelting of the ores of iron those free from sulphur and other impurities are selected. A good household coal is that which burns with a cheerful flame and leaves comparatively little ash. Gas coals are those which yield a large amount of dry, incondensable gas, and coking coal, such as yield a hard, dense, crystallized coke, capable of resisting the blast in the furnace.

The annexed are analyses of some of the principal coals wrought in the eastern part of the coal-field in Monmouthshire, from the Abercarne, Cwm Tybery, and Risca collieries, situated near Newport, and the Cwm Ffrwd colliery near Pontypool. These coals are in good demand for steam, furnace, and domestic purposes:—

MONMOUTHSHIRE COALS.

| Constituents. | Charcoal Vein. | Rock Vein. | Black Vein. | $\frac{1}{2}$ Rock Vein. | New Black Vein. |
|--------------------|----------------|------------|-------------|--------------------------|-----------------|
| Carbon | 81.26 | 82.25 | 81.78 | 75.15 | 83.68 |
| Hydrogen | 6.31 | 5.84 | 4.73 | 4.93 | 5.21 |
| Nitrogen | .77 | 1.11 | 1.11 | 1.07 | |
| Sulphur | 1.86 | 1.22 | 6.69 | 2.85 | 8.87 |
| Oxygen | 9.76 | 3.58 | | 5.04 | |
| Ash | 2.04 | 6.00 | 6.80 | 10.96 | 2.24 |
| | 102.00 | 100.00 | 100.00 | 100.00 | 100.00 |

Other analyses of the Black Vein steam coal, raised at Celynear Colliery, near Merthyr, and of Merthyr steam coal, show the following results :—

| Constituents. | Black Vein. | MERTHYR. | |
|--------------------|-------------|----------|------------------|
| | | Coal. | Coked and Dried. |
| Carbon | 85.98 | 90.00 | Coke. 87.92 |
| Hydrogen | 4.70 | 4.37 | 4.37 |
| Sulphur | .59 | 0.90 | 0.90 |
| Nitrogen | .90 | 0.51 | 0.51 |
| Oxygen | 5.53 | 3.14 | 4.88 |
| Ash | 2.30 | 1.08 | 1.08 |
| | 100.00 | 100.00 | 99.66 |

The Black Vein coal examined by Mr. Thomas Crowder, F.C.S., of Bristol, is described as igniting readily and giving an intense heat, with a bright flame, and making a clean fire; it is small, without washing, yielding a coke of very good quality. The practical heating power of the coal is excellent; one pound of the coal will convert nearly 14 lbs. of boiling water into steam. The analysis of the Merthyr coal and coke was made by Mr. William A. Miller.

The yield of coke from the above and other seams of the district being :—

| | PER CENT. |
|-----------------------------------|-----------|
| Charcoal Vein | 68.40 |
| Rock Vein | 68.80 |
| Black Vein | 71.80 |
| Three-quarter Rock Vein | 62.50 |
| New Black Vein | 68.00 |
| Bedwas | 71.70 |
| Elle Vein | 70.00 |
| Nantygroes | 65.60 |
| New Rock Vein | 70.00 |

Of the Caermarthenshire coals a few examples will indicate generally the composition of the seams named, the coals raised from these seams being employed extensively for steam, furnace, and domestic purposes :—

CAERMARTHENSHIRE COAL.

| Constituents. | Pump Quart Seam. | Fiery Vein. | Fiery Vein. | Llangennech. |
|------------------|------------------|-------------|-------------|--------------|
| Carbon | 92·17 | 87·87 | 88·66 | 85·46 |
| Hydrogen | 3·10 | 3·93 | 4·63 | 4·20 |
| Nitrogen | 1·08 | 2·02 | 1·43 | 1·07 |
| Sulphur | ·34 | ·83 | ·33 | ·29 |
| Oxygen | 2·22 | 7·04 | 1·03 | 2·44 |
| Ash | 1·09 | | 3·92 | 6·54 |
| | 100·00 | 101·69 | 100·00 | 100·00 |

These and other coals of the district yield coke in the following proportion :—

| | |
|-----------------------------|-----------------|
| Fiery Vein | 79·80 per cent. |
| Llangennech | 83·69 „ |
| Bynea, Fiery Vein | 88·10 „ |

Of the bituminous coal of South Wales the Mynyddysllwyn Seam, in the Newport district, in Monmouthshire, has obtained the greatest celebrity. This seam may now be said to be all but exhausted. Of the free burning or steam coal, in the Glamorganshire area, the seam worked by the Messrs. Cory, Yeo and Company, known as the Graig Merthyr, or “Six Feet Vein,” or “Graigola Vein” is the chief, it is worked extensively, and in the coal markets far and wide enjoys a deservedly high reputation, being generally regarded as the best steam coal of the district. The seam is identified with the Cwmclydach Colliery, and locally known as the “Graigola Seam,” and is identical with the Six Feet Seam on the north crop of the coal basin. The composition of this and other veins in Glamorganshire appears as follows :—

| Constituents. | Six-feet Seam. | Nine-feet Seam. | Nixon's Merthyr. | Birchgrove Graigola. | Thomas' Merthyr. |
|------------------|----------------|-----------------|------------------|----------------------|------------------|
| Carbon | 88·28 | 86·18 | 90·27 | 84·25 | 90·12 |
| Hydrogen | 4·24 | 4·31 | 4·12 | 4·15 | 4·33 |
| Nitrogen | 1·66 | 1·09 | ·63 | ·73 | 1·00 |
| Sulphur | ·91 | ·87 | 1·20 | ·86 | ·85 |
| Oxygen | 1·65 | 2·21 | 2·53 | 5·58 | 2·02 |
| Ash | 3·26 | 5·34 | 1·25 | 4·43 | 1·68 |
| | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 |

The specific gravity and yield of coke of the foregoing and other varieties of coal of this district are shown in the annexed table:—

| Coal Seams. | Specific Gravity. | Yield of Coke. |
|-------------------------------|-------------------|----------------|
| Six-foot Seam | 1·31 | 85·83 |
| Nine-foot Seam | 1·33 | 86·54 |
| Nixon's Merthyr | 1·31 | 79·11 |
| Birchgrove Graigola | 1·36 | 85·10 |
| Thomas's Merthyr | 1·30 | 86·53 |
| Powell's Duffryn | 1·326 | 84·30 |
| Aberaman Merthyr | 1·305 | 85·00 |
| North Duffryn | 1·35 | 82·25 |
| Gadly's Nine-feet | 1·33 | 86·54 |
| Gadly's Four-feet | 1·32 | 82·23 |
| Cwmbach Four-feet | 1·31 | 85·83 |
| Cwmbach Six-feet | 1·31 | 85·83 |

In reference to the economy of coal in working it may be interesting to refer generally to the point. Writers of experience say that in the Gwendraeth Valley coals "break out" four-fifths large, the remainder small, while the bituminous coal of the neighbourhood of Swansea does not cut out more than one-fourth large, and some not even this. The free burning coal found in the centre of the coal-field from Tyr Cenol, Morriston, and Swansea Valley on the east, through Coalbrook Colliery to Llanelly on the west, is of this character.

In South Wales, as in Durham, coke manufacture is carried out on an extensive scale. In the Durham district the ovens generally employed are of the type known as the "bee-hive," already described, but some modified forms are now being introduced. In South Wales the form of oven is almost rectangular, their construction giving the following average dimensions:—Width at the front, 6 feet, and at back, 5 feet; length of oven, 14 feet, and the height, inside to crown of arch, 5 feet. These ovens are generally built back to back, with chimney between them, and several have side and bottom flues.

This form of oven is charged sometimes at the door and sometimes at the top. The usual charge is $4\frac{1}{4}$ tons for the first three days in the week, and for the remaining four days, 5 tons. For the coking of the smaller charge 72 hours are generally allowed, and 96 hours for the larger charge. The charge, which consolidates upon a wrought-iron bar laid along the length, and another transversely to it at the back of the oven, is drawn by means of

a windlass. The cooling of the coke is sometimes done in the oven and sometimes after the coke is drawn. At some works the small coal is washed before being coked, and the result is a denser and more valuable description of coke.

With respect to the ordinary "Bee-hive ovens," experience has shown that the coke burnt in them for fewer hours was inferior for smelting purposes to that burnt for a longer period, owing to its not being so easily oxidised; the more intense combustion of the purer carbon and its greater density fitting it more thoroughly for its work. The usual time occupied in burning is from 72 to 96 hours.

By the Belgium process of Coppée the coke is made in about 24 hours; this system is in operation at the works of the Ebbw Vale Company, where they were erected in the year 1874. The Coppée ovens are usually constructed in batches of 30 each, and were designed for coking only finely divided coal, such as is produced by crushing coal in a disintegrator. The chief advantages claimed by the system are rapidity of coking, largely increased yield (which is considered to be the most important advantage), and better coke. The chief characteristics of the "Coppée oven" are,—a small width and an arrangement of channels especially suited for poor coals; a combustion of gas by a double admission of air, which entirely suppresses the smoke; the combination of all the hot gases in a large conduit beneath the ovens and their utilization for heating boilers; and galleries for cooling and preserving the brickwork.* The mode of working at Ebbw Vale is thus described. The small coal is first washed to free it from intermixed shale, and then crushed in a Carr's disintegrator. It is next lifted by suitable machinery into a large cast-iron bin (capable of holding about 200 tons of crushed coal,) the bottom of which is sufficiently high above the tops of the ovens to allow the trams to run under it. When filled, the trams are pushed by hand along to the top of the oven for which the charge is intended; the previous charge not having yet been withdrawn. The front and back doors of the oven are now opened and the mass of coke, 30 feet long, 8 feet high, and 16 inches thick, is pushed out of the oven. This is effected by a ram, the face of which presses against the coke. This face

* For details of the Coppée Oven, see Dr. Percy's "Metallurgy," Fuel, p. 545.

is a little smaller than the cross-sectional area of the oven, and is fixed to the end of an iron girder, somewhat longer than the oven, and having a rack on its upper surface worked by a pinion. The whole is set upon an iron frame, together with a small engine and boiler, and the frame is mounted on wheels, rails being laid down in front of the ovens from end to end of the batch. The machine can be brought opposite each oven in turn. The ram having pushed the coke out of the oven is then drawn back as quickly as possible and the lower doors are closed. The oven is then immediately charged through three openings in the top by drawing out the slides in the bottom of the trams, and the coal is levelled by two men by means of rakes, which are introduced through the upper doors at each end of the oven and reach to its centre. The upper doors are then closed, and together with the lower doors, carefully luted to prevent access of air to the coal; carbonization immediately commences owing to the heat of the oven and to the circulation of the heated products from the adjacent ovens through the contiguous flues.

The process of emptying and refilling the oven as above described need not occupy more than eight minutes. The coke is quenched immediately after leaving the oven; to facilitate this operation the mass of coke which is pushed out of the oven is divided vertically and longitudinally into two equal parts by means of a drag. This separation is easily effected, since carbonization takes place from the two sides towards the centre, whereby a vertical plane, similar to a plane of cleavage, is formed through the centre of the mass of coke.* The ovens are numbered consecutively; the odd numbers are emptied and recharged in the morning and the even numbers in the afternoon, six days a week. Six charges are thus coked in each oven per week, each charge yielding about two tons of coke. The steam required for the coal-washing machine and for the disintegrator is generated by the waste heat of the ovens. An examination of the coke prepared by the Coppée system gives as much as 6 per cent. of water, a point of considerable importance in estimating the yield, which on a large scale, with coal containing 20 per cent. of shale, gives 62·5 per cent. of coke. It is remarked, that although the

* An explanation of this curious result is given in Dr. Percy's "Metallurgy," Fuel, in the remarks upon experiments on the formation of coke in the Appolt oven, p. 451.

coke made in the Coppée's ovens is doubtless sufficiently firm to withstand the weight of the overlying mass in the blast furnace, yet the large quantity of water contained in it, unless it be quenched with more than ordinary care, is a serious drawback to its use in such furnaces.

Mr. Emerson Bainbridge, who has gone very fully into the respective merits of the "Beehive" and "Coppée" systems of coke manufacture, has prepared the following summary of the chief points of comparison, which exhibit some interesting features :—*

| | Beehive. | Coppée. |
|---------------------------------------|-----------------|--------------|
| First cost per 2 tons of coke per day | £119 7s. | £100 |
| Time of burning | 48 to 120 hours | 24 hours |
| Area per ton of coke daily | 1,218 sq. ft. | 234 sq. ft. |
| Per cent. of yield | 45 per cent. | 59 per cent. |
| Outside cooling surface per 2 tons | 1,002 sq. ft. | 175 sq. ft. |
| Time in emptying and refilling | 60 minutes | 8 minutes |
| Units of heat in waste gases per oven | 966,710 | 1,401,584 |
| Labour charge per ton | 1s. 3d. | 11d. |

The coke manufactured in the ordinary way in South Wales, although exceedingly hard and dense, does not appear to have attained all the economical results possible; experience has shown that the carbonization of the coal is not complete, the long, deep fissures in the coke thus manufactured exhibiting, on examination, a considerable amount of dark carbonaceous matter not carbonized.

A new system of manufacture recently introduced by the Ynysawdre Coal Company, at their works near Bridgend in Glamorganshire, which promises very satisfactory results, is thus described :—The coal is, in the first instance, reduced to a state of powder, being crushed by suitable apparatus; it is then subjected to a careful washing by which the sulphur is removed. It is now dried, and subsequently in this state charged in the oven and treated in the ordinary way. The increased value of coke made in this manner is considerable. Towards the close of the year 1879 when coke in South Wales averaged about 7s. 6d. per ton at the place of production, coke of the quality above referred to commanded an increased price of 8s. per ton, or 10s. 6d. per ton, compared with the price of coke made in the

* "Ure's Dictionary of Arts, Manufactures, and Mines," vol. iv., p. 262.

ordinary way. Since the date referred to the demand for coke has greatly increased, and prices have also risen.

The waste of valuable products in the manufacture of coke has received considerable attention. Dr. Angus Smith, in his report for the years 1877 and 1878 as inspector under "The Alkali Act," calls attention to some important facts:—In the combustion of every ton of coal made into coke 20 lbs. of ammonia are given off and allowed to go to waste. The products of distillation of coal are daily becoming more valuable, and the amount of ammonia and tar destroyed in manufacturing coke is very great, equal to 36,000 tons of the first from 15,000,000 tons of coal, used in the year 1876, for iron only. Or 139,764 tons of sulphate of ammonia, which is sometimes worth £20 per ton, or £2,795,280, a sum which is certainly enormous. In addition to this, the tar allowed to go to waste in the same way, amounts to half that sum, which swells the annual loss to the enormous sum of more than three and a half millions sterling. The loss does not stop here; for as Dr. A. Smith proceeds to show, ammonia being a valuable fertilizing substance, it follows that if the amount wasted, as above noted, were saved and properly applied the yield would be much increased.

Dr. Angus Smith * gives in his last report an interesting and detailed account of the manufacture of coke at Bességes, in France, where coke-burning is practised on a very extensive scale, and the gases evolved in the process utilized, showing that the saving of these valuable elements is practicable. He further adds that "if it were found convenient to adopt for this country the *Bességes* method of making coke, the makers of it would obtain a gross income from the sulphate of ammonia and tar of £1,680,000; taking the amount of coal made into coke to be equal to fifteen million tons per annum and taking the *Bességes* calculation of expense. This is about 2s. 4d. per ton for every ton of coal, with the tar, which is nearly the half, or £875,000."

In an agricultural point of view the advantages to be secured are of vast importance, as shown by Dr. A. Smith, who conclusively shows that if the amount of the valuable products wasted were properly applied, it would yield an increase of crops equal

* Fourteenth and Fifteenth Annual Reports of the Inspector. Alkali Acts. Manufacture of Coke, p. 48. Translated from the French by F. Tourget.

to eight million pounds sterling at least. Beyond this the valuable and beautiful products from tar have a great effect on many of the arts.

In Bességes the gas is used for heating the coal; if this gas were saved for burning, a little more coal would be required, but gas may be sold at a much higher price than coal. If, then, the Bességes method were connected with gas-making we should have an enormous amount of saving, besides the amount of gain, and I scarcely dare to venture further in the calculations, but it is certain that some millions more must be added to the already large sum.

Production of the Coal-field.—The data existing on this subject before the present century is scanty and incomplete, the only reliable statistics met with being a return showing the quantity of coal brought into the port of London from the South Wales coal-field in each of the years between 1745 and 1765,* of which the annexed statement is a summary :—

| Year. | Quantity. | Year. | Quantity. |
|-------|-----------|-------|-----------|
| | Tons. | | Tons. |
| 1745 | 1,857 | 1756 | 3,726 |
| 1746 | 1,636 | 1757 | 4,310 |
| 1747 | 2,655 | 1758 | 2,289 |
| 1748 | 1,935 | 1759 | 1,950 |
| 1749 | 2,859 | 1760 | 3,422 |
| 1750 | 2,596 | 1761 | 2,774 |
| 1751 | 2,467 | 1762 | 2,865 |
| 1753 | 2,973 | 1763 | 4,400 |
| 1754 | 3,862 | 1764 | 3,373 |
| 1755 | 2,827 | 1765 | 4,003 |

The principal ports of shipment in South Wales at this period were Milford, Tenby, Haverfordwest and Caermarthen, from whence the great bulk was shipped; while from Swansea, Neath and Llanelly, during the whole period, the shipments did not exceed in the aggregate 1,300 tons.

Although much information exists showing the distribution of coal sent coast-wise and exported half a century since, yet returns of production are wanting. Not until the year 1854, when the "Mineral Statistics," including the yield of our coal-fields and make of pig-iron was published, does any reliable information appear. In the volume referred to, the output of the collieries of

* Coal Commission Report, vol. iii., Statistics, p. 22.

the South Wales Coal-field is given as 8,500,000 tons, of which quantity 1,000,000 tons was anthracite and 7,500,000 bituminous and free-burning coal. From 1855 till the year 1859 the returns of production were as follows, distinguishing the anthracite from the bituminous coal, and to this is appended the number of collieries in the South Wales Coal-field in each of those years, including the output of the Monmouthshire collieries, which in later years are separately given :—

| Year. | Collieries. | Anthracite. | Bituminium. | Total, South Wales. |
|-------|-------------|-------------|-------------|---------------------|
| | Nos. | Tons. | Tons. | Tons. |
| 1855 | 245 | 997,500 | 7,552,770 | 8,550,270 |
| 1856 | 304 | 964,500 | 7,954,600 | 8,919,100 |
| 1857 | 325 | 960,500 | 6,171,804 | 7,132,304 |
| 1858 | 352 | 737,590 | 6,757,699 | 7,495,289 |
| 1859 | 388 | 800,000 | 8,800,350 | 9,600,350 |

The total production of coal in the United Kingdom in the year 1855 was 64,453,079 tons, increased in the year 1859 to 71,979,765 tons, showing an increase in five years of 7,526,686 tons.

Later returns distinguish the output of the collieries in Monmouthshire from those situated in the rest of the coal-field, and throw considerable light on the coal resources of the district. Thus, in the following years, the production increased as under : *—

| Divisions of Coal-field. | 1860. | 1861. | 1862. |
|------------------------------------|------------|-----------|------------|
| | Tons. | Tons. | Tons. |
| Monmouthshire . . . | 3,800,750 | 4,650,000 | 3,750,000 |
| Glamorganshire, Eastern Edge . . . | 200,000 | 325,000 | |
| Glamorganshire— | | | |
| Aberdare District . . | 1,754,813 | 1,790,771 | 2,214,455 |
| Merthyr District . . | 850,000 | 925,000 | 975,000 |
| South Crop, &c. . . | 1,800,000 | 1,875,000 | 2,100,000 |
| Pembrokeshire . . . | 1,850,000 | 2,100,000 | 1,250,000 |
| Cardiganshire . . . | | | |
| Total . . . | 10,255,563 | 9,665,771 | 10,289,455 |

Following the course of production, there appears some interesting detailed statements for the next three years of the output in the following districts, in which the quantities raised

* Coal Commission Report, vol. iii., p. 132.

in Monmouthshire are separately given. Thus, in the year 1863, Monmouthshire contributed 4,075,000 tons, the rest of the South Wales Coal-field, 6,917,081 tons; of which latter quantity the annexed statement gives the quantities, the first four items being the respective returns of parishes in Glamorganshire:—

| DISTRICTS. | TONS. |
|--|------------|
| Merthyr (Parish) | 812,778 |
| Gelligaer „ | 639,055 |
| Aberdare „ | 2,148,980 |
| Llanwonno „ | 293,288 |
| Rhondda Valley | 328,000 |
| Lower end of Taff Vale and Llantwit Vardre | 141,000 |
| South Outcrop to Neath | 655,000 |
| Neath and Vale of Neath | 305,000 |
| Swansea and Swansea Valley | 517,000 |
| Glyncorrwg | 36,000 |
| Pembrokeshire and Caermarthenshire | 1,041,000 |
| | <hr/> |
| | 6,917,081 |
| Monmouthshire | 4,075,000 |
| | <hr/> |
| Total of South Wales Coal-field | 10,992,081 |

Passing to subsequent years, the annexed summary displays the number of collieries and the output of coal:—

| Year. | SOUTH WALES. | | MONMOUTHSHIRE. | | Total. |
|-------|--------------|------------|----------------|-----------|------------|
| | Collieries. | Coal. | Collieries. | Coal. | |
| | Nos. | Tons. | Nos. | Tons. | Tons. |
| 1864 | 316 | 6,948,000 | 102 | 4,028,500 | 10,976,500 |
| 1865 | 322 | 8,531,336 | 104 | 4,125,000 | 12,656,336 |
| 1866 | 332 | 9,376,443 | 100 | 4,445,000 | 13,821,443 |
| 1867 | 329 | 9,092,300 | 92 | 4,659,500 | 13,751,800 |
| 1868 | 298 | 8,959,500 | 92 | 4,250,500 | 13,219,000 |
| 1869 | 315 | 9,179,650 | 73 | 4,275,150 | 13,454,800 |
| 1870 | 328 | 9,299,770 | 75 | 4,364,342 | 13,664,112 |
| 1871 | 299 | 9,120,000 | 74 | 4,915,525 | 14,035,525 |
| 1872 | 284 | 10,131,000 | 85 | ... | ... |
| 1873 | 423 | 9,841,523 | 118† | 4,500,000 | 14,341,523 |
| 1874 | 371 | 10,184,885 | 119† | 5,038,820 | 15,223,705 |
| 1875 | 415 | 10,632,597 | 91 | 3,525,975 | 14,158,572 |
| 1876 | 400 | 11,973,336 | 134† | 4,499,985 | 16,473,321 |
| 1877 | 325 | 12,634,335 | 116 | 4,350,785 | 16,885,120 |
| 1878 | 329 | 12,926,225 | 131 | 4,490,290 | 17,416,515 |
| 1879 | 325 | 13,126,397 | 129 | 4,640,340 | 17,766,737 |
| 1880† | 370 | 16,126,031 | 166 | 5,039,549 | 21,165,580 |

* Including the output of those collieries in Brecknockshire and on the edge of Glamorganshire.

† Included in another district.

‡ Reports H. M. Inspectors of Mines, 1880.

This will be a fitting place to note the development of the South Wales Coal-field, as shown in the parish returns, compiled annually by the parochial authorities for purposes of assessment, in Glamorganshire. These returns form but a part of the coal raised, but the steady increase appearing year after year is a good index to the output of the collieries. Formerly returns were published by five parishes, but the annexed schedule shows the annual yield in the parishes named (in tons of 2,520 lbs. each) :—

| Year. | Aberdare. | Gelligaer. | Llanwanno. | Ystradfydwg. |
|-------|-----------|------------|------------|--------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1844 | 176,953 | ... | 11,830 | ... |
| 1847 | 269,116 | ... | 44,500 | ... |
| 1850 | 477,208 | ... | 42,880 | ... |
| 1855 | 1,203,847 | ... | 99,873 | ... |
| 1860 | 1,754,813 | 716,156 | 110,220 | ... |
| 1862 | 2,214,455 | 591,468 | 289,820 | ... |
| 1864 | 2,048,472 | 764,521 | ... | 428,489 |
| 1866 | 2,185,571 | 866,895 | 395,091 | 649,828 |
| 1868 | 2,053,509 | 807,424 | 361,921 | 981,787 |
| 1870 | 2,070,920 | 909,911 | 415,536 | 1,332,059 |
| 1871 | 1,836,954 | 962,946 | 346,825 | 1,325,037 |
| 1872 | 2,013,718 | 1,067,959 | 395,594 | 1,555,853 |
| 1873 | 2,054,879 | 1,078,347 | 425,731 | 1,940,566 |
| 1874 | 1,963,141 | 1,227,477 | 436,081 | 1,947,936 |
| 1875 | 1,612,428 | 916,695 | 336,463 | 1,951,606 |
| 1876 | 1,832,981 | 1,333,819 | 436,177 | 2,370,359 |
| 1877 | 1,645,906 | 1,284,489 | 533,425 | 2,492,867 |
| 1878 | 1,653,157 | 1,234,653 | 790,645 | 2,922,234 |
| 1879 | 1,682,033 | 1,268,429 | 969,551 | 3,019,568 |
| 1880 | 1,832,002 | 1,388,620 | 1,231,573 | 3,547,239 |

Regarding the great depths from which coal is now won in South Wales, some interesting particulars on the subject of deep winning, in connection with the Harris Navigation pits, situated near Quaker's Yard, Glamorganshire, the deepest in the district, have recently appeared, by Messrs. Thomas Forster Brown and George Frederick Adams, MM. Inst. C.E., who are professionally connected with the operations.*

"The depth of the lowest seam at present sunk to was 760 yards; the pits were each 17 feet in diameter inside the walling. In addition to the depth, a special feature was the thickness of hard and heavily-watered rock penetrated. Guide ropes, upon

* Paper read at the Institute of Civil Engineers on the 18th of January, 1881.

the Galloway principle, were used in sinking, and the value of this system was shown in the saving of over two minutes in steadying the bowk at the bottom of the pit at depths of 475 and 530 yards, the total time occupied in clearance at the latter depth being three minutes twenty-six seconds. The method of dealing with the various feeders of water during sinking was described: one of the pits was drained by a hole bored by the diamond machine, which was put down, at a depth of 175 yards from the surface, for a farther depth of 860 feet. Where the strata were conformable, and cut up by faults which intersected all the measures, considerable objection existed to metal tubbing, even for comparatively shallow depths; for the water could rarely be prevented from forcing its way through fissures into the underlying strata. Moreover, provision had to be made for the probable working of the Brithdir seam, a very watery measure, lying at a depth of 250 yards. On account of these and other circumstances, it was ultimately decided to provide for the permanent pumping of all the feeders, and a powerful 100 inch Cornish pumping engine was erected. The parallel motion for the main pump rods was obtained by a gudgeon, attached to the top rods carrying two slide blocks, which worked in cast-iron guides 13 feet long and 27 inches wide. This gudgeon was attached to the beam by two hammered iron radius-rods, 43 feet long, 10 inches wide, and tapering from 3 inches thick at the top and bottom to $1\frac{1}{2}$ inch at the middle. The space between the rods was filled with pitch pine 12 inches thick at the top and bottom and 18 inches wide in the middle. Five lifts, three of which were 26 inches in diameter, and the others 22 inches and $21\frac{1}{2}$ inches, were worked by the Cornish engine. The total feeders amounted to 440 gallons, of which 298 were pumped from a depth of 467 yards. The rods were double, of pitch pine, 16 inches square. To economise space in the pit, the lifts were fixed in one perpendicular line; to effect this the rods directly above the plunger and the rods below were connected by side-rods and distance pieces; the horizontal connecting pipe of the H-piece being cast semi-circular to allow the rods to pass down in a straight line. The total weight of rods, &c., amounted to $181\frac{1}{2}$ tons, that of the water being 133 tons; 35 tons of the difference were counterbalanced by a balance beam in the pit, leaving $13\frac{1}{2}$ tons to overcome friction.

“A large diamond boring machine was used for a portion of the

sinking. The apparatus weighed 10 tons, and consisted of four beams, or transoms, fixed to a centre piece; on the transoms were placed the drills—ten in number—which could be moved to any part of, or inclined to any angle parallel with, the face of the transoms, and each drill could be started or stopped singly. In making the first trials, thirty to forty short holes, at varying angles, and from 3 feet to 5 feet in depth, were bored, the operation requiring twelve to fourteen hours. Nearly one-half of this time was occupied in jacking the machine for the various positions required to bore the sumping holes, bench holes to sump, and finally the cropping holes. Long holes from 15 feet to 30 feet in depth were subsequently tried, and blasted in sections; but having to be bored vertically, so as not to pass out of the line of the shaft, they had not always the most effectual lifting power. Better progress was made with single drills, but the cost of diamonds became too great for the frequent holes and changes, and the contracting company completed their contract by means of a percussive drill, designed by Colonel Beaumont. 'Ingersoll' drills were afterwards used; these had a diameter of $3\frac{1}{4}$ inches, and a stroke of $4\frac{1}{2}$ inches, and gave excellent results; the only difficulty experienced being in the wear and tear of the tappets, which, when they broke, generally caused damage in the cylinder.

"In hard and wet rock dynamite was found to be a much more effective explosive than gunpowder, requiring about half the number of holes, and saving tamping. In shale, without water, powder was more effective, dynamite being more rapid in its action. In sinking through three yards of dry Pennant rock, the cost of powder and dynamite was, respectively, £12 1s. 3d. and £10 1s. 8d.

"Under the circumstances which attended this sinking in hard and wet rocks, 3 yards were considered good progress by hand, and $4\frac{1}{2}$ yards by machine per week; but the authors were of opinion that this rate ought to be improved upon with further experience; they had also arrived at the conclusion that the cost of sinking by machine was less than by hand labour. The average rate of sinking, including walling, but exclusive of stoppages, was 3·77 yards per week, there being nearly an equal per centage of hard rock and shale: the actual sinking occupied about one-half the total time, and walling 12 per cent. The south pit, which was the deeper of the two, was commenced in February,

1878, and finished in February, 1879. The average cost per yard of sinking in shale by hand and without pumps, near the bottom of the shaft, was £11 19s. 6·8d.; with pumps, £13 2s. 8·9d.; in hard Pennant rock by hand without pumps it was £40 8s. 5·4d.; with pumps, £44 13s. 2·9d. In Pennant rock with pumps and three drills the cost was £34 8s. The cost of the 18-inch walling without pumps, including the proportion of iron curbs, came to £11 7s. 10d. per yard in depth, or £1 8s. 10d. per cubic yard; with pumps, to £1 7s. 5d. per cubic yard. These averages included all labour, stores, coal, &c."

Messrs. Brown and Adams, in referring to the question of ventilation, allude to a furnace as being probably the most effective means at great depths; but leaving this question for future consideration, they had meantime erected a Schiele Fan fourteen feet three inches in diameter, and capable of producing a current of about 250,000 cubic feet per minute. This had been done after a series of experiments in various districts. They further urge objections to the positive type ventilators, viz., that in the event of obstructions occurring in the air ways, undue pressure might be applied to separation doors, air crossings, &c.; besides which, they caused a vibratory motion, were costly to erect, and the working parts were in some cases liable to get out of repair. Of the closed fans, which it was stated gave slightly better results than open fans, the Guibal and Schiele were the best.

The winding engine in course of construction is designed to raise 2,000 tons of coal in 10 hours of constant drawing; the weight, exclusive of the rope, being $10\frac{1}{2}$ tons, and the velocity of the ascending cage 40 to 45 feet per second. The scroll drum, with a smaller diameter of 18 feet, rising by fourteen coils to 32 feet, was considered the best method of counterbalancing the rope. The cylinders were 4 feet 6 inches in diameter, with 7 feet stroke; they were inverted and placed on cast-iron supports, the drum being fixed below on masonry pillars. The valves were double beat; and for the steam valves Barclay's simple trip expansion gear was used. The rope was a parallel flat rope of the best selected steel, and consisted of 114 No. 11 gauge wires. The calculated breaking strain was 104 tons, and the factor of safety was nine.

The pit frame is described as constructed entirely of wrought-iron; arrangements being also introduced for loading and un-

loading a single decked cage by gravitation of tubs. The empty trams were hoisted about six feet, and made to run down an inclined way to the cage, being stopped and relieved by a system of catches, the cage being so arranged that on landing on the steps the bottom was inclined. In the above deep winning, at the Harris Navigation Pits, the deepest in the district, the shaft pillar is described as having an area of 400 yards square.

Distribution of Coal.—In the eastern part of the South Wales coal-field Newport and Cardiff are the ports of shipment. Newport is situated on the river Usk, and this part of the coal-field is traversed and Newport is connected with the Great Western, Eastern Valleys, Western Valleys, and Newport and Brecon Railways, affording ample facilities for the distribution of coal. The dock accommodation is considerable; the docks have an area of nearly twelve acres, and were opened in the year 1858. More recently increased facilities for commerce have been secured by the opening of the Alexandra Dock, with an area of twenty-eight acres, having ample hydraulic machinery for the shipping of coal. In addition to these docks Newport is most favourably situated, possessing an extensive water frontage on the river Usk, by means of which an extensive trade is carried on.

Cardiff is situated on the river Taff, and is connected with all parts of the kingdom by the Great Western, Taff Vale, and Rhymney Railways. The port has the advantage of a magnificent roadstead and extensive docks constructed by the trustees of the Marquis of Bute. Until these docks were constructed the only outlet for the minerals of this district, of which Merthyr is the capital, was the Glamorganshire Canal, the access to which was very imperfect and the dimensions wholly inadequate for the rapidly increasing trade of this great coal and iron district. It is interesting to trace the early incidents connected with the Bute Docks. They may be briefly stated as follows:—"The Marquis of Bute was the owner of a large tract of land that intervened between the town and the sea, called 'Cardiff Moors,' and conceived the idea of converting it into a harbour on a scale commensurate with the prospective wants of the neighbourhood. In the year 1830 he obtained an Act for constructing a new port, the 'Bute Ship Canal,' and steadily proceeded amidst many difficulties to carry out the design at his individual cost." The work, which was considered a wild speculation, commenced in 1834 with the con-

struction of a feeder from the river Taff. The first stone of the docks was laid in March, 1837, and the docks opened in October, 1839. A few years previously the high character of the coal-seams in the Aberdare and Merthyr districts attracted attention from their valuable qualities as a steam coal, and a great impetus was given to their development by the opening of the West Bute Dock in 1839, and the East Bute Dock in 1859. It may be briefly stated that the West Bute Dock contains a water area of 18 acres; the East Bute Dock an area of 42 acres, with a basin area of 3 acres. Beyond this the Port of Cardiff possesses greatly increased accommodation in late years by the addition of the Penarth Dock and Tidal Harbour, the former having a dock area of 18 acres and a basin of 3 acres, while the latter has a total length of 13,200 feet. This great area has been further supplemented by the New Bute Basin, with an area of 12 acres, with machinery capable of shipping 4,480 tons of coal per day; and the Glamorganshire Canal Dock, with a length of upwards of 5,000 feet, for discharging and loading small vessels, and beyond which increased accommodation has recently been added by the addition of a new dock on the east side of the existing East Dock, with a water area of 55 acres.

Previous to the opening of the Taff Vale Railway in the year 1840, coal was conveyed down the Glamorganshire Canal already referred to, which has a length of 25 miles, with a rise of 611 feet. This great undertaking commenced in the year 1791, and was completed and opened in the year 1794 to Cardiff. The only information showing the extent of mineral traffic on this canal is found in Mr. Jellinger Symons' "Industrial Capacities of South Wales,"* from which it appears that in the year 1846 the coal carried amounted to 287,271 tons, and in each of the years between 1846 and 1852 to the following quantities:—

| Year. | Coal Carried. | Year. | Coal Carried. |
|-------|---------------|-------|---------------|
| | Tons. | | Tons. |
| 1847 | 262,077 | 1850 | 268,361 |
| 1848 | 281,967 | 1851 | 294,537 |
| 1849 | 245,785 | 1852 | 301,829 |

The other principal ports of shipment in South Wales for the export of coal are those of Swansea, Llanelly, and Milford. The

* Published by R. Mason, Tenby, 1855, p. 22.

growth of the port of Swansea has been very rapid ; it has been remarked that of all the ports in the Bristol Channel, "there are none more favourably situated than Swansea ; for it is an important fact, that Swansea Harbour is accessible to any stranger that may arrive in the bay when blowing too strong for pilots to get off." The stone piers enclosing the outer harbour were erected under an Act passed in the year 1791, and stretch some 600 yards on the east, and 300 yards on the west side.

The following are some of the particulars of the dock accommodation :—The North Docks were commenced in the year 1849 and completed in the year 1861, and possess an area of lock and half-tide basin of $18\frac{1}{2}$ acres. The South Docks were completed in 1859, the area of the entrance basin being 3 acres, and the dock area 13 acres. Ample provision is here made for shipping coal, large iron boxes, with false bottoms, being employed, each containing $2\frac{1}{2}$ tons, and four of which are conveyed upon a truck each journey ; beyond these ordinary tipping-waggons are used.

Llanelly is situated some 10 miles to the west of Swansea, and both ports are the seats of some of the most extensive and important metallurgical works in the kingdom ; more especially for the smelting of copper ore, the manufacture of tin-plate, and the reduction of the ores of iron, &c. The port has good docks, is situated on the estuary of the Burry and Llwchwr rivers on the east of Caermarthen Bay, and is connected with the Llanelly and the Great Western Railways. The principal coal shipped at Llanelly is anthracite ; which variety of coal is also shipped at Burry Port and Kidwelly, smaller ports to the west of Llanelly.

Milford was formerly a great outlet of the coal of Pembroke-shire ; the trade has of late years moved eastward, but is still of considerable importance. The ports of Milford and Pembroke, situated at the mouth of the Dancleddaw river, which here flows into an inlet of the Atlantic, constituting one of the finest harbours in the world, and giving rise to an important naval arsenal. It is here that the South Wales section of the Great Western Railway terminates, the port having extensive commercial relations with the south of Ireland.

With the foregoing brief reference to the more important ports contributing to the distribution, coastwise and to foreign countries, of coal the produce of South Wales, the following statistics will show the growth of the coal-trade. The earliest

accessible returns are for Swansea, where the shipments coastwise, to foreign countries and Ireland, were as follows in each of the years :—

| Year. | Coastwise. | Exported. | Total. |
|-------|------------|-----------|---------|
| | Tons. | Tons. | Tons. |
| 1816 | 159,181 | 29,974 | 189,155 |
| 1817 | 167,251 | 57,784 | 225,035 |
| 1818 | 190,022 | 34,321 | 224,343 |

The Cardiff and Newport shipments in each of the same years of coal, the produce of the South Wales coal-field, were as follows :—

| Year. | Coastwise. | Exported. | Total. |
|-------|------------|-----------|---------|
| | Tons. | Tons. | Tons. |
| 1816 | 177,044 | 75,199 | 252,243 |
| 1817 | 207,753 | 90,090 | 297,843 |
| 1818 | 218,800 | 95,414 | 314,214 |

In subsequent years the returns of each port are separately distinguished.

The Llanelly and Pembroke shipments in each of the same years stood thus :—

| Year. | LLANELLY. | | Total. | PEMBROKE. | | Total. |
|-------|------------|-----------|--------|------------|-----------|--------|
| | Coastwise. | Exported. | | Coastwise. | Exported. | |
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1816 | 29,418 | 15,480 | 44,898 | 27,532 | 271 | 27,803 |
| 1817 | 38,512 | 26,527 | 65,039 | 21,956 | 3,333 | 25,289 |
| 1818 | 34,570 | 18,427 | 52,997 | 28,970 | 3,462 | 32,432 |

The total shipments from Milford during the same years amounted to but 1,895 tons.

Summarising the above returns, the total quantities of coal and anthracite sent coastwise and exported in each of the above years appear thus, and afford reliable data for comparison :—

| Year. | Coastwise. | Exported. | Total. |
|-------|------------|-----------|---------|
| | Tons. | Tons. | Tons. |
| 1816 | 393,175 | 120,924 | 514,119 |
| 1817 | 435,472 | 177,734 | 613,206 |
| 1818 | 472,362 | 151,624 | 623,986 |

From these totals, compared with the total exports previous to the year 1800, when Swansea was the chief port of export, may be gathered some interesting facts bearing on the growth of the coal industries of South Wales. It only remains to add that, during the same years, from 1780 to 1799, the total exports from Cardiff, Llanelly, and Pembroke did not exceed 8,700 tons :— *

| Year. | Swansea. | Year. | Swansea. |
|-------|----------|-------|----------|
| | Tons. | | Tons. |
| 1780 | 64,502 | 1790 | 157,588 |
| 1781 | 53,772 | 1791 | 154,943 |
| 1782 | 71,597 | 1792 | 179,595 |
| 1783 | 70,725 | 1793 | 218,060 |
| 1784 | 102,391 | 1794 | 169,999 |
| 1785 | 88,624 | 1795 | 182,746 |
| 1786 | 90,645 | 1796 | 181,213 |
| 1787 | 98,111 | 1797 | 202,023 |
| 1788 | 101,412 | 1798 | 211,172 |
| 1789 | 113,509 | 1799 | 244,976 |

In the above quantities are included the coal sent coastwise, which formed the great bulk, the quantities at this period sent to foreign countries not exceeding from 30,000 to 40,000 tons per annum; while in the three years above referred to, the coal sent coastwise, and shipped to Ireland and foreign countries, amounted to :—

| Year. | Coastwise. | Ireland and Foreign Countries. | Total. |
|-------|------------|--------------------------------|-----------|
| | Tons. | Tons. | Tons. |
| 1816 | 4,145,909 | 824,536 | 4,970,445 |
| 1817 | 4,067,722 | 873,806 | 4,941,528 |
| 1818 | 4,253,007 | 821,329 | 5,074,336 |

Ten years later it is stated on the authority of the author of "Fossil Fuel," that upwards of 64,000 tons of "Stone coal or Culm," were exported from Swansea; while in 1829 Swansea, Newport and Neath, shipped 550,000 tons of coal, and Cardiff 60,000 tons; these quantities presumably included that sent coastwise. For a few years about this period the details bearing on the distribution of coal raised in the South Wales coal-field are somewhat uncertain; in the year 1830 and in subsequent years, returns made by the Commissioners of H.M.

* Coal Commission Report, vol. iii., Appendix, p. 6.

Customs to Parliament, afford all the necessary information bearing on the distribution of our coal, whether to our Colonies, foreign countries, or that sent coastwise to other ports in the United Kingdom, and in late years the coals shipped to Ireland. From the returns above referred to the following details appear for the years named :—

COAL, CINDERS, AND CULM EXPORTED FROM THE UNITED KINGDOM.

| Ports. | 1830. | 1831. | 1832. | 1833. |
|----------------|--------|--------|--------|--------|
| | Tons. | Tons. | Tons. | Tons. |
| Cardiff . . . | 711 | 726 | 1,052 | 1,521 |
| Newport . . . | 1,930 | 4,698 | 5,244 | 2,609 |
| Llanelly . . . | 3,855 | 5,817 | 4,740 | 7,109 |
| Swansea . . . | 6,403 | 7,013 | 8,198 | 13,501 |
| Milford . . . | 10 | ... | 214 | ... |
| Total . . | 12,909 | 18,254 | 19,448 | 24,740 |

In each of the same years the total quantities exported stood as follows, together with the amount of duties received thereon. The duties in the year 1830 varying from 1s. per ton to British possessions and 5s. 9d. per ton in British ships to foreign countries, while in other ships it amounted to 10s. In the year 1835 all duties on coal to British possessions were remitted. The remaining duties, a few years later, were reduced, and finally abolished in the year 1850, since which year all coals have been exported free of duty :—

| Year. | Quantities Exported. | Amount of Duty Received. |
|-------|----------------------|--------------------------|
| | Tons. | £ s. d. |
| 1830 | 504,419 | 63,889 17 6 |
| 1831 | 510,831 | 55,237 5 10 |
| 1832 | 588,446 | 56,706 2 10 |
| 1833 | 634,448 | 65,008 8 6 |
| 1834 | 615,255 | ... |
| 1835 | 736,060 | ... |

From this time forward ample details from Parliamentary and other returns are accessible, showing the distribution of coal, from which the following figures are gathered. In the annexed table appears the quantities of coal, culm, and cinders sent coastwise and exported from the ports of South Wales, including Monmouthshire, in each of the years named since 1834 :—

| Year. | Coastwise. | Exported. | Total. |
|-------|------------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| 1834 | 1,026,838 | 30,404 | 1,572,242 |
| 1836 | 1,066,261 | 46,110 | 1,112,371 |
| 1838 | 1,227,083 | 65,902 | 1,292,985 |
| 1840 | 1,374,419 | 63,867 | 1,438,286 |
| 1842 | 1,453,154 | 109,819 | 1,562,973 |
| 1845 | 1,656,963 | 236,061 | 1,893,024 |
| 1848 | 1,663,937 | 300,189 | 1,964,126 |
| 1851 | 1,573,773 | 453,125 | 2,126,898 |
| 1854 | 1,786,878 | 772,481 | 2,559,359 |
| 1857 | 2,004,225 | 1,418,026 | 3,422,251 |
| 1860 | 2,238,875 | 1,719,560 | 3,958,436 |
| 1863 | 2,231,071 | 2,272,540 | 4,503,611 |
| 1866 | 2,432,654 | 2,971,920 | 5,404,574 |
| 1869 | 2,511,080 | 3,226,790 | 5,737,870 |
| 1872 | 2,555,805 | 3,592,767 | 6,148,573 |
| 1873 | 2,492,404 | 3,348,147 | 5,540,551 |
| 1874 | 2,270,512 | 3,992,316 | 6,262,818 |
| 1875 | 2,182,535 | 3,696,724 | 5,879,259 |
| 1876 | 2,390,402 | 5,092,392 | 7,482,792 |
| 1877 | 2,376,466 | 5,283,417 | 7,659,883 |
| 1878 | 2,415,667 | 5,798,565 | 8,214,232 |
| 1879 | 2,538,179 | 6,291,337 | 8,809,516 |
| 1880 | 2,492,204 | 6,893,839 | 9,386,043 |

The great development of the coal industries of the South Wales coal-field is well shown in the above table, more especially when comparing the returns of the year 1850 (when the export duty on coal was repealed,) with those of the year 1860. The coal sent coastwise, although showing a considerable increase, bears no proportion to the yearly increasing quantities exported. In the annexed statement for the years 1860, 1879, and 1880 appear the respective shipping ports and quantities of coal sent coastwise and exported to foreign countries in each of those years from the ports named:—

| Ports. | 1860. | | 1879. | | 1880. | |
|------------------|------------|-----------|------------|-----------|------------|-----------|
| | Coastwise. | Exported. | Coastwise. | Exported. | Coastwise. | Exported. |
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| Cardiff . . | 782,002 | 1,133,086 | 827,458 | 4,427,602 | 864,899 | 4,991,317 |
| Newport . . | 629,206 | 187,591 | 983,725 | 935,556 | 868,963 | 1,015,550 |
| Swansea . . | 227,675 | 295,102 | 251,992 | 775,301 | 248,853 | 688,604 |
| Neath . . | 185,310 | 13,740 | .. | .. | .. | .. |
| Llanelly . . | 284,170 | 89,996 | 116,389 | 69,740 | 120,383 | 75,874 |
| Milford . . | 51,351 | 45 | 27,153 | .. | 25,168 | .. |
| Briton Ferry . . | .. | .. | 185,287 | 53,406 | 191,573 | 94,070 |
| Port Talbot . . | 61,965 | .. | 79,434 | 21,272 | 80,922 | 16,798 |
| Porth Cawl . . | 17,196 | .. | 66,741 | 8,460 | 91,443 | 11,626 |
| Total . . | 2,238,875 | 1,719,560 | 2,538,179 | 6,291,337 | 2,492,204 | 6,893,839 |

Railway Distribution.—The Taff Vale and Great Western Railways and their many branches contribute mainly to the distribution of the great bulk of coal to the ports of shipment and to remote parts of the kingdom, other lines of railways contributing in a lesser degree. The Taff Vale main line, extending from Merthyr Tydvil to Cardiff, was opened in October, 1840, and completed in April of the following year; originally it had but a single line of rails, which were far from sufficient for the traffic, and soon double rails were laid down. The detailed returns of mineral traffic published annually, leave nothing to be desired as regards the statistics of coal conveyed over the main line and branches, which had increased enormously during the forty years the railway has been in existence, and may be gathered from the annexed figures taken from the Company's return of coal and coke carried by all trains in each of the years given :—

| Year. | Tons. | Year. | Tons. |
|-------|-----------|-------|-----------|
| 1841 | 41,669 | 1871 | 3,593,932 |
| 1844 | 187,740 | 1872 | 4,213,506 |
| 1847 | 360,324 | 1873 | 4,527,641 |
| 1850 | 594,222 | 1874 | 4,352,778 |
| 1853 | 874,362 | 1875 | 3,776,813 |
| 1856 | 1,394,394 | 1876 | 4,879,180 |
| 1859 | 1,759,422 | 1877 | 5,170,953 |
| 1862 | 2,540,657 | 1878 | 5,613,639 |
| 1865 | 2,855,198 | 1879 | 5,849,184 |
| 1868 | 3,540,324 | 1880 | 6,894,403 |

Of the aggregate quantities, the following table, prepared from the railway return previously referred to, shows the quantities carried in each of the years to the places named :—

| Distribution. | 1847. | 1865. | 1878. | 1879. | 1880. |
|------------------------------------|---------|-----------|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| Cardiff and Penarth Junction | 336,769 | 2,501,689 | 4,761,254 | 5,064,111 | 5,955,457 |
| Sold retail | 23,555 | 212,075 | 327,506 | 294,556 | 356,691 |
| Quaker's Yard Junction | .. | 102,611 | 90,664 | 121,405 | 135,419 |
| Mountain Ash Junction | .. | 37,024 | 17,903 | 10,160 | 4,006 |
| Conveyed over by other Railways | ... | 1,799 | 413,781 | 352,329 | 345,757 |
| Brecon and Merthyr Junction | .. | .. | 254 | 5,916 | 97,010 |
| Walnut Tree Bridge Junction | .. | .. | 2,277 | 707 | 63 |
| Total | 360,324 | 2,855,198 | 5,613,639 | 5,849,184 | 6,894,403 |

The Great Western Railway passes through the entire length

of the coal-field, and like the Taff Vale exercises a great influence in the distribution of the coal. The Great Western carrying it inland, not only to remote parts of the kingdom but also to the Metropolis. An early return for the year 1857, when the traffic originated, gives the quantity carried from South Wales as 120,080 tons; in 1865 the Midland Railway conveyed 1,988 tons from the coal-field, advancing to the year 1866, when the railway returns assume a definite form, the distribution is traced with much clearness, the quantities in each year appearing as follows :—

| Year. | Great Western. | Midland. | Monmouthshire and Canal. | Vale of Neath. | London and North-Western. |
|-------|----------------|----------|-----------------------------|----------------|------------------------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1865 | 1,345,512 | ... | 1,315,783 | 700,592 | 37,670 |
| 1867 | 2,238,342 | 1,637 | 1,579,410 | 911,600 | ... |
| 1868 | 2,553,487 | 573 | 1,389,660 | 1,046,432 | 47,648 |
| 1869 | 2,800,790 | 390 | 1,528,354 | 1,106,064 | 71,415 |
| 1870 | 2,850,412 | 4,730 | 1,676,486 | * | 70,321 |
| 1872 | 3,067,685 | 27,351 | 1,759,356 | * | 107,520 |
| 1874 | 3,427,576 | 191,027 | 2,120,700 | * | 439,493 |
| 1876 | 4,445,775 | 570,120 | * | * | 750,524 |
| 1878 | 4,422,464 | 591,333 | * | * | 758,790 |
| 1879 | 4,763,429 | 639,553 | * | * | 827,831 |
| 1880 | 5,384,411† | 707,458 | * | * | 903,335 |

It is only necessary to add that details of the distribution of the above quantities will be found in the "Mineral Statistics of the United Kingdom" and vol. iii. of the "Coal Commission Report, 1871."

Prices of Coal and Cost of Production.—An inquiry instituted about the year 1860 shows that at that period the cost of cutting coals and filling into trams varies, according to the district, from 10*d.* to 2*s.* 6*d.* per ton. These extreme variations are due to the thickness of the seam and to its quality top and bottom. The cost at bank, including royalties and all expenses, but not interest on capital expended, being about 5*s.* 6*d.* per ton. At this period, 1860, the selling price of coal at pit's bank, subject to variation, being, on the average, as follows :—

* Included in the Great Western return.

† Beyond this quantity in the year 1880 the Great Western Railway carried 2,696,610 tons of coal from Monmouthshire.

| SOUTH WALES. | | s. | d. |
|--|--|----|----|
| Large coal | | 6 | 6 |
| Brunsh coal (i.e., coal cut and sold thorough and thorough as it is in the seam) | | 5 | 6 |
| Clean small coal | | 4 | 6 |

These rates also apply to Monmouthshire.

Railway charges, according to old Acts of Parliament, were as follows about the year 1860 :—

| | s. | d. | |
|---|----|----|-------------------|
| For tonnage (i.e., the use of the road) | 0 | 1 | per ton per mile. |
| For locomotive power | 0 | 0½ | „ „ |

These rates have been considerably reduced in recent years. The average distance of the South Wales collieries from the ports of shipment may be taken at about 18 miles, and the cost of shipping at port, per ton, 6*d.* In the year 1860 the cost of Welsh coal, at port, will have been about :—

| | s. | d. | |
|---------------------------------|----|----|----------|
| Getting coal | 5 | 6 | per ton. |
| Conveyance to ports and waggons | 1 | 10 | „ |
| Shipping | 0 | 6 | „ |
| Total | 7 | 10 | „ |

During the next ten years, till 1870, the wages of coal-miners were but moderate; in the following year, 1871, a period of prosperity set in, when the iron-workers sought an increase of wages, this was succeeded by the coal-miners seeking corresponding advantages. On the average, at this period, the collier worked four days per week, receiving 40*s.* per week, or 10*s.* per day. Between 1872—74 the great strike occurred in South Wales, when it may be remembered about 60,000 out of 65,000 hands engaged in the collieries and ironworks of the district struck work from the 1st December, 1872, to the middle of February, 1873, causing the stoppage of 118 collieries.

The loss of production in the interval referred to has been estimated at 1,170,000 tons of coal; the total cost of the strike to the masters and men at about £2,000,000; the loss of wages alone amounting to about £800,000.

Towards the close of the year 1873 the tide of prosperity turned, prices fell and wages decreased, till in 1877 colliers' wages in South Wales did not exceed from 4*s.* to 4*s.* 6*d.* per day for ordinary pitmen, and 5*s.* to 5*s.* 3*d.* for hewers, since

which date wages have continued to decrease. The disastrous strike of 1877 at Saundersfoot, in Pembrokeshire, is another example of loss to industry. Here a cessation of labour continued for seven months, the colliers eventually resuming labour on the former terms.

The average price of coal prevailing in the year 1878 was 8*s.* per ton; the highest price, 10*s.* per ton, and the lowest, 6*s.* 6*d.* per ton. While in 1879 the average price did not exceed 7*s.* 3*d.* per ton; the highest price, 11*s.* per ton, and the lowest, 6*s.* per ton, compared with 7*s.* 6*d.*, 18*s.*, and 6*s.* in the year 1880.

Population employed in Coal and Iron-mining in the South Wales Coal-field.—The number of male persons employed in coal-mining operations in South Wales in the year 1854 was 82,478; the number in ironstone-mining, 10,272, thus apportioned to the respective counties of South Wales in which the mineral basin occurs :—

| Counties. | Coal Mining. | Iron Mining. |
|------------------------|--------------|--------------|
| | No. | No. |
| Glamorganshire . . . | 15,295 | 5,079 |
| Monmouthshire . . . | 11,367 | 3,404 |
| Caermarthenshire . . . | 3,344 | 19 |
| Brecknockshire . . . | 1,541 | 1,767 |
| Pembrokeshire . . . | 926 | 3 |
| Total . . . | 32,473 | 10,272 |

The total number of females employed in coal-mining in South Wales in the same year was 1,059, of whom 395 were employed in the Monmouthshire area of the coal-field.

Referring to the annual reports of H.M. Inspectors of Mines for the year 1878, the total number of persons employed in the South Wales coal-field, exclusive of that part of the coal-field in Monmouthshire, was, in coal-mining, 45,474, of whom 36,316 were employed underground, and 9,158 over ground. The number in ironstone mines being 1,090, of whom 805 were under and 285 above ground.

In subsequent years since 1874, the numbers employed in the South Wales coal-field in coal and ironstone-mining have been as follows, distinguishing those engaged under and above ground and the quantity of coal and ironstone raised, according to the reports of H.M. Inspectors, to which is added, for comparison, the average quantity raised per man in each year :—

| Year. | PERSONS EMPLOYED. | | | Coal Raised. | Ironstone Raised. | Total Coal and Ironstone. | Average per man. |
|-------|-------------------|---------------|--------|--------------|-------------------|---------------------------|------------------|
| | Above Ground. | Under Ground. | Total. | | | | |
| | | | | Tons. | Tons. | Tons. | Tons. |
| 1874 | 13,865 | 59,463 | 73,328 | 16,432,060 | 363,131 | 16,785,191 | 229 |
| 1875 | 11,893 | 60,750 | 72,643 | 14,173,143 | 398,533 | 14,571,676 | 200 |
| 1876 | 10,836 | 56,647 | 67,483 | 16,972,284 | 223,386 | 17,195,670 | 255 |
| 1877 | 10,180 | 55,126 | 65,306 | 16,921,214 | 214,429 | 17,135,643 | 262 |
| 1878 | 9,590 | 54,146 | 63,736 | 17,517,118 | 196,331 | 17,713,449 | 278 |
| 1879 | 10,187 | 56,308 | 66,495 | 17,819,043 | 143,525 | 17,962,268 | 270 |
| 1880 | 10,920 | 58,238 | 69,158 | 21,165,580 | 148,101 | 21,318,981 | 308 |

The population employed above and below ground in the South Wales coal-field was as follows in the year 1879, distinguishing the number of persons in each county :—

| County. | Under Ground. | Above Ground. | Total. |
|----------------------|---------------|---------------|----------|
| | Persons. | Persons. | Persons. |
| Brecknockshire . . | 438 | 65 | 503 |
| Glamorganshire . . | 39,843 | 7,238 | 47,081 |
| Caermarthenshire . . | 1,964 | 542 | 2,506 |
| Pembrokeshire . . | 424 | 182 | 606 |
| Monmouthshire . . | 13,639 | 2,160 | 15,799 |
| Total . . . | 56,308 | 10,187* | 66,495 |

Resources and Probable Duration of the South Wales Coal-field.—From the Report of the Royal Coal Commission the total quantity of coal ascertained by Messrs. H. Hussey-Vivian and George T. Clarke as remaining in this great coal-field was 36,566,195,917 tons; of this quantity the amount existing to depths not exceeding 4,000 feet is given as 32,456,208,918 tons, that existing at depths exceeding 4,000 feet amounting to 4,109,987,004 tons. An analysis of the Report of the Royal Coal Commission distinguishes the net quantity of coal remaining unwrought in the several divisions of the coal-field as follows :—

SOUTH WALES MINERAL BASIN.†

| | |
|--|-----------------------|
| | TONS. |
| Pembrokeshire | 215,693,910 |
| Eastern division of coal field to the Glyncorrwg Fault on the west | 12,963,230,517 |
| Division of coal-field westward of the Glyncorrwg Fault | 23,387,269,490 |
| Total quantity of unworked coal in coal-field | <u>36,566,195,917</u> |

* Of this number 990 were females, of whom 558 were above 16 years and 432 under that age.

† Coal Commission Report, vol. i., pp. 7, 8, and 15.

At the rate of production in the year 1870, namely, 13,664,112 tons, this coal-field would furnish supplies for 2,676 years. Since the year 1870 the output of the collieries has largely increased, amounting in the year 1879 to 17,819,043 tons, and in 1880 to 21,165,580 tons, apportioned as follows:—

| COUNTY. | COAL RAISED. Tons. |
|----------------------------|-----------------------|
| Brecknockshire | 100,616 |
| Glamorganshire | 15,320,096 |
| Caermarthenshire | 625,933 |
| Pembrokeshire | 79,386 |
| Monmouthshire | 5,039,549 |
| Total | <u>21,165,580</u> |

The output of 1880 exceeding that of 1879 by 3,346,537 tons, equivalent to upwards of 18 per cent.

The total production in the ten years ending 1879 was 154,162,130 tons; this quantity, deducted from the original estimate, would leave 36,412,033,787 tons available for future use, which at the average consumption of the past ten years (15,416,213 tons,) would yield supplies for 2,362 years; and at the rate of production in 1880 the exhaustion of the South Wales coal-field would take place 1,720 years hence.

CHAPTER XV.

GLOUCESTERSHIRE COAL-FIELD.

Description of Coal-field—Section of Strata—Area of Woods and Plantations in Forest, and Ancient Rights of Miners—Analyses of Coal—Production and Distribution by Railway and by Ship—Price of Coal—Population employed in Coal and Iron Mining—Resources and probable Duration of Coal-field.

Gloucestershire Coal-field.—*Forest of Dean.*—The coal-field bearing this name occupies a superficial area of 84 square miles; it is distant some 14 miles from the city of Gloucester, and lies between the rivers Severn and Wye. In form and outline this basin is more perfect than any other coal-field in Great Britain. The coal measures, in their greatest section, are no less than 2,765 feet, and the uniform dip of the strata, from the margin of the coal-field towards the centre, is so regular in its occurrence that each division of its strata is well known. In this section occur 15 seams of coal, varying in thickness. Of these seams, exceeding 2 feet thick and upwards, there are eight, giving an aggregate thickness of solid coal of 24 feet. Professor E. Hull, F.R.S., in his “Coal Fields of Great Britain,” gives the following section, showing the succession of the coal seams:—

| | Ft. | In. |
|---|-----|-----|
| Sandstone and shales, with thin coals | 830 | 0 |
| 1. Cow Delf | 0 | 8 |
| Strata | 91 | 10 |
| 2. Dog Delf | 1 | 2 |
| Strata | 46 | 9 |
| 3. Smith Coal | 2 | 6 |
| Strata | 34 | 6 |
| 4. Little Delf | 1 | 8 |
| Strata | 48 | 8 |
| 5. Park End High Delf | 3 | 7 |
| Strata | 56 | 0 |
| 6. Starkey Delf, with parting | 2 | 0 |
| Strata | 50 | 0 |
| 7. Rocky Delf | 1 | 9 |
| Strata | 77 | 6 |

| | Ft. | In. |
|--|-----|-----|
| 8. Upper Churchway Delf, with partings | 1 | 11 |
| Strata | 34 | 0 |
| 9. Lower Churchway Delf | 1 | 6 |
| Strata | 150 | 0 |
| 10. Braizley Delf | 1 | 9 |
| Strata | 430 | 0 |
| 11. Nag's Head or Yorkley Delf | 2 | 9 |
| Strata | 153 | 0 |
| 12. Whittington Delf | 2 | 6 |
| Strata | 137 | 0 |
| 13. Coleford High Delf 2 ft. to | 5 | 0 |
| Strata | 124 | 0 |
| 14. Upper Trenchard Delf | 2 | 0 |
| Strata | 72 | 0 |
| 15. Lower Trenchard or Bottom Coal | 1 | 4 |

The thick series of sandstones occurring between the Churchway and Coleford High Delf coal seams yields an excellent building stone, and have given rise to numerous quarries; and Professor Smyth is of opinion that these sandstones appear to be the equivalent of the Pennant of the Bristol coal-field.

The coal measures are surrounded by belts of millstone grit and carboniferous or mountain limestone, upon which they rest, and the carboniferous limestone, in turn, reposes upon a bed of Old Red Sandstone. Sir Henry de la Beche gives the following details in the "Memoirs of the Geological Survey,"* showing the thickness of the several divisions of the strata of this coal-field:—

| | Feet. |
|--|-------|
| Coal measures, with fifteen coal seams | 2765 |
| Millstone grit | 455 |
| Carboniferous limestone | 480 |
| Lower limestone shale | 165 |
| Old Red Sandstone | 8000 |

Of the 24,000 acres comprising the area of the Forest of Dean, it appears 18,500 acres belong to the Crown, subject to certain rights of the free miners; between 600 and 700 acres belong to the Crown, free from all rights of common, the remaining 4,800 acres being the property of private individuals; the existing woods and plantations in the Forest extend over between 14,000 and 15,000 acres, consisting almost entirely of oak, of ages varying from 2 to 70 years; the greater portion, however, are from 50 to 60 years old, and in general are in a thriving condition. From the report of the Select Committee of the House of Commons, dated July, 1874, are gathered many interesting facts: it is there

* Vol. i., p. 203.

stated that the surface of the Forest occupied by the mines is estimated at 1,000 acres, within which is included spoil banks, quarries, railways, tramways, and other works, while the present income to the Crown from coal mines varies from £11,000 to £12,000 per annum, and from iron mines from £4,000 to £5,000 per annum.

Special privileges are inherited by the male population, that is to say, every male person born and abiding in the hundred of Saint Briavels, of the age of 21 years, who has worked for a year and a day in a coal or an iron mine within the hundred, is entitled to be registered as a free miner. These registered free miners, according to the returns published in the year 1888, numbered 1,200; they are not now so numerous as then, their numbers in the year 1874 probably not exceeding 700 or 800. The privilege possessed by these free miners consists in their being entitled to the exclusive rights of having grants from the Crown of what are called "gales," which confer licenses to work in mines. These "gales" number about 260, in which coal and iron occur, and of this number not less than 55 were in operation in the year 1879 and 63 in the year 1880.

Other deposits of coal occur in the Gloucestershire portion of the Bristol coal-field. A considerable section of the Bristol coal-field belongs to Somersetshire; these will be considered in a succeeding chapter, referring to the East Somerset and Bristol coal-fields.

Analyses of the Forest of Dean Coal.—A reference to the distribution of coal, the produce of the Forest of Dean, for the years 1867, 1868, and 1870, will sufficiently show the extent to which it is employed in the industries of the district and the surrounding neighbourhood. It is extensively used in the ironworks of the Forest, being previously converted into coke. It is also in great demand for household consumption; its hardness, large size, and good burning qualities, rendering it especially suitable for this purpose.

In the Admiralty investigation on the coals suited to the Steam Navy, the coal raised at the Park End Colliery, from the "Park End High Delf," or Lowry Vein, is thus referred to and described. "The vein is generally regular, and about 3 feet thick, and is worked long work, as in the thin veins of the Staffordshire coal-field. The overlying and subjacent strata are of the usual

kind of shale. The dip varies from 6 inches to 2 feet in the yard, or from one in six to two in three." The coal is described to be of a "free burning character, of great strength and durability." The distance from the shipping port of Lydney is 5 miles. The current price in summer is 10s. per ton; in winter, 11s., free on board, and the principal markets are in Ireland, Cornwall, Cheltenham, and the manufacturing districts of Gloucestershire and Bridgewater. The coal examined had a very hard and compact structure, with a clean and bright fracture, and contained iron pyrites in very large quantities in every joint, even when broken down into the smallest sized pieces. It was remarked during the examination that the coal kindled easily, but that it made a very dirty, smoky fire, which, at the ordinary working draught, caused immense volumes of dense smoke to appear at the chimney top. When the draught was increased, the fire became clearer, but then the rush of smoke swept the loose soot from the flues and chimney, and carried it out in large flakes from the chimney top. If the draught was lessened, the fire would hardly burn, and, on opening the doors, the whole place was instantly filled with the loose ashes, and smoke forced out from the fire. The cinders, ashes, and clinker, were of a light weight, and clean; the clinker contained much scoria, some of it quite vitrified. The Park End seam, above referred to, has the annexed composition:—

RESULTS TABULATED.

| | |
|--------------------|---------------|
| Carbon | 73·52 |
| Hydrogen | 5·69 |
| Nitrogen | 2·04 |
| Sulphur | 2·27 |
| Oxygen | 6·48 |
| Ash | 10·00 |
| Total | <u>100·00</u> |

The specific gravity of the coal is 1·288; its yield of coke, 57·8 per cent.; the mean weight of a cubic foot, 54·44 lbs., and the economic weight or space occupied by one ton, 41·14 cubic feet.

The Coleford High Delf and Trenchard seams, extensively worked in the Forest, and favourably regarded as serviceable coals, much in request for domestic purposes, the small being used for raising steam, are thus referred to. The Coleford High Delf, worked on the north-western side of Dean Forest, in the

neighbourhood of Symond Yat, on the River Wye, where the seam is 5 feet thick, is thus constituted. Some portions of the seam in the High Meadow district occasionally yield a peculiar character of coal, known locally as "black coal," containing, by analysis, 87 per cent. of carbon. The Trenchard Coal, of which the analysis appears side by side, has a thickness, in the neighbourhood of Lydney, of 4 feet :—

RESULTS TABULATED.

| Constituents. | Colford High Delf. | Trenchard. |
|--------------------|--------------------|------------|
| Carbon | 78·810 | 80·709 |
| Hydrogen | 5·303 | 5·425 |
| Oxygen | 9·055 | 7·060 |
| Nitrogen | 1·750 | 0·735 |
| Sulphur | 2·062 | 1·271 |
| Ash | 3·020 | 4·800 |
| Total | 100·000 | 100·000 |

Production of Coal.—The earliest information on this subject takes us back to the year 1788, when, of the 131 collieries then existing in the Forest, 90 were in operation, producing 1,816 tons of coal per week, equivalent to an annual production of 94,432 tons. The first railway constructed in the Forest of Dean, and made available for the conveyance of mineral traffic, was about the year 1809, from Newnham to Churchway, a distance of seven and a half miles. A careful search of numerous documents and treatises referring to the Forest of Dean since the year 1788, has not been fruitful of results until the year 1854, when it appears 60 collieries were in active operation, producing 420,866 tons of coal. In subsequent years, as in 1854, the returns of production of coal in the Forest of Dean were included in the total produce of the coal-fields of Gloucestershire, Somersetshire, and the Anthracite and Lignite deposits of Bideford and Bovey Tracey in Devonshire.

The following figures indicate the production of the above-named deposits, as published for the year 1854 :—

| COAL FIELDS. | TONS. |
|---|------------------|
| Gloucestershire, "Forest of Dean" | 420,866 |
| Somersetshire, "Bristol Coal Field" | 1,050,000 |
| Devonshire, Bovey Tracey Lignite | 15,000 |
| „ Bideford Anthracite | 6,500 |
| Total | <u>1,492,366</u> |

In the year, 1855, and until 1867, the returns include the output of the collieries of Gloucestershire, Somersetshire, and Devonshire, and appear as follows :—

| Year. | NUMBER OF COLLIERIES. | | | Production of Coal. |
|-------|-----------------------|----------------|-------------|---------------------|
| | Gloucestershire. | Somersetshire. | Devonshire. | |
| 1855 | 55 | 31 | 2 | Tons. 1,430,620 |
| 1856 | 56 | 29 | 2 | 1,530,000 |
| 1857 | 62 | 35 | 2 | 1,225,000 |
| 1858 | 59 | 35 | 2 | 1,125,250 |
| 1859 | 60 | 35 | 2 | 1,250,000 |
| 1860 | 63 | 37 | 2 | * |
| 1861 | 71 | 40 | 2 | * |
| 1862 | 76 | 42 | 2 | 1,750,000 |
| 1863 | 78 | 41 | 2 | 1,950,000 |
| 1864 | 94 | 37 | 2 | 1,950,000 |
| 1865 | 97 | 37 | 1 | 1,875,000 |
| 1866 | 79 | 35 | ... | 1,850,700 |
| 1867 | 76 | 34 | ... | 1,975,000 |

About this period the production of the collieries in Dean Forest is separated, and is shown in the annexed table, with the number of collieries working in each year. The totals in the last column include the production of Somersetshire in each of the years from 1867 to 1873 :—

| Year. | FOREST OF DEAN. | | Total of Gloucestershire. |
|-------|-----------------------|------------------|---------------------------|
| | Number of Collieries. | Coal Produced. | |
| 1867 | 54 | Tons. 847,667 | Tons. 1,975,000 |
| 1868 | 54 | 848,128 | 1,969,000 |
| 1869 | 50 | 852,125 | 1,979,000 |
| 1870 | 44 | 907,183 | 1,955,950 |
| 1871 | 54 | 837,893 | 2,086,475 |
| 1872 | 59 | 730,409 | * |
| 1873 | 76 | 790,374 | 1,858,740 |
| 1874 | 71 | 666,697 | 1,147,272 |
| 1875 | 69 | 702,080 | 1,273,080 |
| 1876 | 69 | 668,009 | 1,257,547 |
| 1877 | 64 | 638,319 | 1,194,726 |
| 1878 | 60 | 655,903 | 1,147,605 |
| 1879 | 55 | 779,428 | 1,250,718 |
| 1880 | 63 | 759,853 | 1,195,930† |

Since the year 1873, the production of Gloucestershire is dis-

* Included in the Monmouthshire return.

† Return H.M. Inspectors of Mines.

tinguished, and includes the output of the Forest mines; the difference between the two columns in later years will be coal raised in that part of the county belonging to the Bristol district.

For the years 1867 and 1868 the coal raised from the Forest mines is shown in the following statement :—

| Workings. | 1867. | 1868. |
|---|---------|---------|
| | Tons. | Tons. |
| Galee's return of quantities worked exclusive of colliery consumption and workmen's allowance | 777,677 | 778,828 |
| Consumed by engines | 40,000 | 40,000 |
| Consumed by workmen | 30,000 | 30,000 |
| Total raisings | 847,677 | 848,128 |

The following are the quantities of coal raised in the several collieries in the Forest of Dean in the year 1880, amounting to 759,853 tons :—

| COLLIERIES. | TONS. | COLLIERIES. | TONS. |
|--------------------------------|---------|---------------------------|---------|
| Arles Level | 2,011 | Brought forward | 288,746 |
| Bailey Hill | 5,232 | Nagahead | 22,089 |
| Bilson | 4,482 | Old Fire Engine | 14 |
| Britannia | 33,060 | Patches | 632 |
| Bridewell | 58 | Parkend | 8,093 |
| Brooming Hold | 1,007 | Prosper | 34 |
| Chapel Quarry | 1,120 | Princes Royal | 2,665 |
| Coalway Hill | 120 | Parkhill | 2,565 |
| Coal Pit Hill | 362 | Pluckpeny | 179 |
| Cross Knaves | 769 | Resolution | 83,059 |
| Crump Meadow | 75,173 | Royal Forester | 56,976 |
| Dark Hill | 4,206 | Rose in Hand | 60,961 |
| Deans Meend | 3 | Regulator No. 4 | 665 |
| Farmer's Folly | 7,924 | Richard Winter | 14,065 |
| Foxes Bridge | 126,978 | Smith's Delight | 2,345 |
| Gentlemen Colliers | 3,937 | Society | 763 |
| Hopewell Engine | 4,331 | Speedwell | 1,894 |
| Haywood | 2,344 | Soundwell | 41,555 |
| Hillers Land | 80 | Saint Vincent | 1,643 |
| Hawkin | 35 | Success | 6,670 |
| Invention | 313 | Speculation | 18,694 |
| Knockley Sump | 684 | Small Profit | 24,173 |
| Lightmoor | 60 | Tormentor | 1,416 |
| Little Brookhollands | 1,562 | Trafalgar | 88,794 |
| Lonk Level | 618 | Uncertainty | 595 |
| Little Britain | 297 | Unity | 6,331 |
| Lydbrook D. Level | 5 | Vallet's Level | 779 |
| Morses Level | 139 | Wallsend | 8,847 |
| New Fancy | 8,382 | Whirrley | 654 |
| New Found Out | 2,285 | Worrall Hill | 13,739 |
| New Road Level | 1,154 | Wiemell | 50 |
| Old Croft Level | 15 | Well Level | 68 |
| Carried forward | 288,746 | Total | 759,853 |

Distribution of Coal.—The principal shipping ports are those of Gloucester and Bristol, from which considerable quantities of coal are sent coastwise and to foreign countries. Previous to the year 1831 an export duty was levied on all coals sent out of the United Kingdom, but in that year the duties levied on coals sent to our British possessions were repealed, and it was not till the year 1850 that the duties levied on coals sent to foreign countries were wholly repealed.

The respective shipments from Bristol and Gloucester were as follows in each of the years given since 1819 :—

| Year. | Bristol. | Gloucester. | Total. |
|-------|----------|-------------|--------|
| | Tons. | Tons. | Tons. |
| 1819 | 3,711 | 3,485 | 7,196 |
| 1821 | 2,543 | 15,615 | 18,158 |
| 1823 | 4,427 | 22,799 | 27,226 |
| 1825 | 4,986 | 14,077 | 19,063 |
| 1827 | 6,658 | 18,591 | 25,249 |
| 1829 | 6,517 | ... | 6,517 |
| 1830 | 6,517 | 98 | 6,615 |

As already stated, the duty on coal sent to our colonial possessions was repealed in the year 1831. In the two previous years the duties varied from 8*d.* to 1*s.* per ton. At the same period, the duty levied on coals sent to foreign countries was 3*s.* 4*d.* per ton, when conveyed in British ships, and 6*s.* 8*d.* in ships of other countries. While as regards cinders, small coal, and culm, the respective duties were 2*s.* per ton in British ships, and 4*s.* per ton in those of other countries.

The total amount of duties received in the year 1830, on 504,419 tons, was £63,889 17*s.* 6*d.*, and in the year 1832, on 588,446 tons, £56,706 2*s.* 10*d.* During the few years prior to the total abolition of all duties on coal exported, the quantities and duties received were as under :—

| Year. | Quantities. | Duty. |
|-------|-------------|------------|
| | Tons. | £ s. d. |
| 1847 | 2,483,161 | 4,195 12 5 |
| 1848 | 2,785,300 | 4,393 2 10 |
| 1849 | 2,826,039 | 3,233 13 2 |
| 1850 | 3,351,880 | 1,045 15 1 |

In each of the above-named years, the shipments from Bristol

and Gloucester were as follows; the amount of duty does not appear, the sum, however, will have been inconsiderable :—

| Year. | Bristol. | Gloucester. | Total. |
|-------|----------|-------------|---------|
| | Tons. | Tons. | Tons. |
| 1847 | 10,968 | 112,202 | 123,170 |
| 1848 | 11,959 | 119,993 | 131,952 |
| 1849 | 15,479 | 89,272 | 104,751 |
| 1850 | 13,547 | 85,707 | 99,254 |

In subsequent years the total exports of coal are shown in the following table, the great bulk being sent coastwise to other ports in the United Kingdom :—

| Year. | Bristol. | Gloucester. | Total. |
|-------|----------|-------------|---------|
| | Tons. | Tons. | Tons. |
| 1852 | 11,050 | 89,229 | 100,279 |
| 1854 | 13,425 | 79,023 | 92,448 |
| 1856 | 11,662 | 97,288 | 108,950 |
| 1858 | 12,084 | 138,438 | 150,522 |
| 1860 | 10,897 | 163,982 | 174,879 |
| 1862 | 5,791 | 168,698 | 174,489 |
| 1864 | 11,196 | 172,104 | 183,300 |
| 1866 | 10,944 | 175,647 | 186,591 |
| 1868 | 13,228 | 171,859 | 185,087 |
| 1870 | 11,854 | 200,209 | 212,063 |
| 1872 | 12,437 | 345,876 | 358,313 |
| 1874 | 7,353 | 205,438 | 212,791 |
| 1876 | 8,959 | 172,053 | 181,012 |
| 1877 | 7,146 | 167,495 | 174,641 |
| 1878 | 10,121 | 202,785 | 212,906 |
| 1879 | 12,110 | 254,862 | 266,972 |
| 1880 | 10,731 | 218,496 | 229,227 |

From the above table it will be seen that the greatest exports from Bristol and Gloucester took place in the year 1872, when 358,313 tons were shipped; of this quantity 344,450 tons were shipped coastwise from Gloucester, and 1,426 tons exported to foreign countries, the shipments from Bristol amounting to 12,295 tons. Since 1872 a decline of shipments is shown from the above-named ports, the total in 1880 being but 229,227 tons.

Some interesting details of the distribution of the Dean Forest coal appear for the years 1867, 1868, and 1870, in which the quantities carried out of the district are separately distinguished from that used locally, and in the ironworks of the district. The returns for these years are as follows :—

| How Distributed. | 1870. | 1868. | 1867. |
|---|---------|---------|---------|
| | Tons. | Tons. | Tons. |
| By G. W. Railway from Lydney | 16,728 | 7,617 | 7,760 |
| From Bullo Pill Railway . . | 284,819 | 306,000 | 300,000 |
| By water from Lydney . . . | 171,919 | 168,404 | 166,992 |
| By water from Bullo Pill . . | 96,307 | 61,220 | 59,380 |
| Land sales in the Forest and surrounding districts . . . | 82,000 | 80,000 | 82,000 |
| Consumed by engines and workmen | 70,000 | 70,000 | 70,000 |
| Consumed at iron, tin, and wire works in the Forest . } | 185,410 | 154,887 | 161,545 |
| Totals | 907,183 | 848,128 | 847,667 |

The earliest return of coal carried by the Midland Railway from Gloucestershire is for the year 1856, showing that 182,085 tons, compared with 230,745 tons in the year 1866, and 226,643 tons in the year 1867, were carried. The following shows the coal carried from collieries in Gloucestershire since the year 1858 :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1858 | 174,840 | 1871 | 234,420 |
| 1860 | 227,265 | 1872 | 232,875 |
| 1862 | 223,606 | 1873 | 293,069 |
| 1863 | 233,174 | 1874 | 225,013 |
| 1865 | 246,625 | 1875 | 243,753 |
| 1866 | 230,745 | 1876 | 227,740 |
| 1867 | 226,643 | 1877 | 200,253 |
| 1868 | 210,138 | 1878 | 192,007 |
| 1869 | 215,718 | 1879 | 188,542 |
| 1870 | 219,010 | 1880 | 223,098 |

The quantity carried in the year 1880 was 223,098 tons, the total quantities of coal carried by the Midland Railway system the same year, from all districts, giving an aggregate total of 12,388,910 tons.

The Gloucester and Berkley Canal Company are also carriers of coal from the Forest of Dean Collieries. In the year 1873 the total amounted to 1,612 tons, increased to 4,933 tons in 1874, and in the years 1877 and 1880, from Dean Forest and South Wales respectively, 31,262 tons and 14,591 tons.

Price of Coal.—We learn from the “Survey of Gloucestershire,” written by Mr. Rudge, that, in the beginning of the

present century, house coal from Dean Forest pits was sold at 7*s.* per ton, and smiths' coal for 5*s.* per ton; much of the coal consumed in the city of Gloucester and the neighbourhood, at that time, being principally supplied from Shropshire and Staffordshire. In the year 1870 prices of coal were as follows:—

COLLIERIES, FOREST OF DEAN.

Hopewell, Coleford, 5*s.* 6*d.* and 6*s.*
 Miles Level, Coleford, 3*s.* 6*d.* to 8*s.*
 Nelson, Coleford, 5*s.* 6*d.*, 7*s.* and 8*s.*
 Pillowell, Lydney, 8*s.* 6*d.*
 Royal Forrester, Coleford, 6*s.* and 7*s.*

The above were the average prices per ton at the pit's mouth.

Here, as in other districts, prices have fluctuated since the year 1870. The average prices ruling in 1879 were about 9*s.* 9*d.* per ton for coal (best household), and for slack, 4*s.* 9*d.*, the highest price of coal being 14*s.*, and the lowest 6*s.* 6*d.* per ton; the slack ranging from 3*s.* 6*d.* to 5*s.* per ton. The average price at the pit's mouth in 1880 was about 10*s.*, and slack 4*s.* 6*d.* per ton.

Population Employed.—In the year 1854 the number of persons employed in coal and iron mining, in the Forest of Dean, was 2,218; of these 2,007 were coal, and 211 ironstone miners. Twenty years later the total persons employed amounted to 5,050, of whom 3,962 were engaged under ground, and 1,088 above ground. Since that date Her Majesty's Inspectors of Mines give the numbers engaged as follows, to which is added the produce of coal and the individual output per man:—

| Year. | Under Ground. | Above Ground. | Total. | Coal Raised. | Average per Man. |
|-------|---------------|---------------|--------|--------------|------------------|
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 3,962 | 1,088 | 5,050 | 671,232 | 133 |
| 1875 | 3,803 | 891 | 4,694 | 702,053 | 149 |
| 1876 | 3,573 | 861 | 4,433 | 619,805 | 139 |
| 1877 | 3,468 | 680 | 4,148 | 627,401 | 151 |
| 1878 | 3,291 | 694 | 3,985 | 657,275 | 165 |
| 1879 | 3,677 | 614 | 4,291 | 788,501 | 180 |
| 1880 | 3,207 | 623 | 3,830 | 720,123 | 188 |

These figures refer exclusively to the Forest of Dean coal-field; the population employed in the Bristol district, also in Gloucestershire, will be included in the Somersetshire coal-field.

Of the population employed in 1879 there were 3,305 working under ground above the age of 16, and of those above ground, 581 were above the same age, the remainder being under ; while a total absence of female labour appears throughout the Forest of Dean, as well as the Bristol district.

Resources of Coal-field and probable Duration.—The total area of the Forest of Dean coal-field, as recorded by the Royal Coal Commission,* amounts to 302,671 statute acres, one foot thick. Of this area, the portion already wrought amounts to 37,787 statute foot acres, the portion unwrought, deducted for faults, barriers, supports, &c., amounting to 75,681 statute acres, of the same thickness, leaving unwrought, and likely to be clear for working, 189,203 statute foot acres. In this computation, after making due allowance for unavoidable loss and waste in working, each statute acre is estimated to yield 1,400 tons, giving a total quantity of coal yet available (1870) of 265,000,000 tons.

Taking the production of the year 1870, as recorded in the "Mineral Statistics," 907,188 tons, the coal remaining would last for 292 years. Since 1870, however, a diminished production appears, that of 1880 giving but 759,853 tons. The total yield during the past ten years is 7,376,295 tons, giving an average annual output, from the Forest of Dean collieries, of 737,629 tons. Making the necessary deduction, and taking this average, there yet remains available 257,623,705 tons ; sufficient to last for a period of about 349 years.

* "Coal Commission Report," vol. i., p. 18, Mr. Joseph Dickinson, H.M. Inspector of Mines.

CHAPTER XVI.

THE BRISTOL COAL-FIELD IN GLOUCESTERSHIRE AND SOMERSETSHIRE.

General description of the Bristol and Radstock Coal Basin—The Clapton-in-Gordano and Severn Basin, and the Nailsea Basin—Succession of Strata—Analyses, Production, and Distribution of Coal—Prices of Coal—Population employed in Coal Mining—Resources and probable Duration of Coal-field.

The Somersetshire and Bristol Coal-field.—Few coal-fields possess more interesting features. The following section gives the succession of rocks and their average thickness:—

| | | THICKNESS. Feet. |
|-----------------------------|-----------------------------------|---------------------|
| <i>Trias</i> | Rhoetic beds | 50 |
| | New Red Marl | 300 |
| | Dolomitic Conglomerate | 25 |
| <i>Carboniferous system</i> | Coal measures | 5,000 |
| | Millstone grit | 800 |
| | Carboniferous limestone | 3,000 |
| | Lower limestone shales | 500 |
| <i>Old Red Sandstone</i> | Old Red Sandstone | 4,000 |

The dolomitic conglomerate reposing on the coal measures, and so called from its peculiar character, contains hematite iron ore deposits; the variable thickness however of this, the lower division of the trias, rarely exceeding from 25 to 30 feet in this area, has rendered mining operations somewhat uncertain, and hence the deposits have been developed but to a limited extent. The coal measures of this district consist generally of a series of shales and sandstones, with seams of coal and occasional measures of ironstones, and may be taken in their average depth as having a thickness of not less than 5,000 feet. These measures are divided into an upper and lower series, between which interposes an arenaceous rock, averaging in thickness about 2,000 feet, and known as the "Pennant Grit," consisting of thick beds of sandstone, varying in colour from grey to dark red. These beds frequently alternate with thin shales, and occasionally a seam of coal interposes.

The upper and lower coal measures series contain productive seams of coal, while some measures of ironstone are met with in the lower series. The Pennant Grit, however, is the principal division of the coal measures in which ores of iron are met with, and in the neighbourhood of Bristol these ores have been wrought in several localities.

In the millstone grit, at the base of the coal measures, beds or courses of iron ore are occasionally met with; the millstone grit, it may be stated, is familiarly known as the "Farewell Rock," from the fact that when reached there is no longer any probability of meeting any coal in depth. The millstone grit in Somersetshire and Gloucestershire has a varying thickness. In the Mendip Hills it does not exceed 500 feet in thickness, while in the Bristol area it may be taken as varying from 800 to 1,000 feet. It is composed of beds of sandstone, grit, hard and close grained, thin beds of sandy shale, with occasional seams of coal and beds of conglomerate containing quartz pebbles.

The carboniferous or mountain limestone upon which the millstone grit reposes, is also a repository of the ores of iron in this area: it is made up of numerous beds of grey and blue limestone, interstratified here and there with chert in bands and strings. These beds are traversed by joints, veins and faults, in which are found the deposits of ore in irregular veins, pockets, and fissures. The true carboniferous limestone in this area has an average thickness of 3,000 feet and rests upon the lower limestone shales, the lowest member of the carboniferous system, having an average thickness of not less than 500 feet, and forming as it were a passage between the old red sandstone and the carboniferous limestone: it consists of shales and limestones, occasionally sandy and micaceous, varying in colour from blue to grey, and brown, while in the uppermost part are beds of tough bluish limestone.

Three coal basins in isolated tracts occur in the area of the Somerset and Bristol coal-field, namely, that of Bristol and Radstock; of Clapton-in-Gordano; and Nailsea.

The Bristol and Radstock Coal Basin.—The extreme length of this coal-field from its northern apex at Cromhall to the flanks of the Mendips is about twenty-five miles; at Frampton Cotterell it has an average width of four and-a-half miles, from Stapleton to Mangotsfield about five miles, and a line drawn from Bristol

eastward to Naishcombe Hill about six miles. In the above area the coal-field may be conveniently divided into two sections, or into a northern and southern basin, separated by the Kingswood anticlinal, which forms a natural division. Mr. McMurtrie remarks that the whole of the northern part of the coal-field commencing at Kingswood has been raised to a higher elevation than the Somersetshire end of the basin, and it has thus been more exposed to those powerful denuding forces which have swept over the district. In the northern basin the upper coal measures yield but four workable seams of coal. At Coal Pit Heath the succession of beds is illustrated by the following section :—

FROG LANE PIT, COAL PIT HEATH.

(From the Report of the Royal Coal Commission.)

| | Ft. | In. |
|------------------------------------|-----|-----|
| Coal measures | 455 | 2 |
| Rag Coal | 0 | 10 |
| Coal measures | 16 | 0 |
| Top or Hard Coal | 2 | 0 |
| Coal measures | 71 | 6 |
| Stinking Seam | 0 | 6 |
| Coal measures | 10 | 0 |
| Holybush Seam | 2 | 0 |
| Coal measures | 68 | 0 |
| High Seam (in two bands) | 4 | 0 |

In the southern or Radstock basin the following section shows the succession of strata in the district at the Paulton Engine Pit:—

PAULTON ENGINE PIT.

(From the Report of the Royal Coal Commission.)

| | Ft. | In. |
|-----------------------------|-----|-----|
| Coal measures | 348 | 0 |
| Great Seam | 2 | 0 |
| Coal measures | 34 | 0 |
| Upper Little Seam | 1 | 6 |
| Coal measures | 82 | 6 |
| Middle Seam | 1 | 1 |
| Coal measures | 82 | 11 |
| Slyving Seam | 1 | 10 |
| Coal measures | 32 | 2 |
| Under Little Seam | ... | |
| Coal measures | ... | |
| Bull Seam | 0 | 9 |

The Clapton-in-Gordano, and Severn Basin.—This coal tract, the exposed portion of which lies between Clevedon and Port-

bury, has in recent years been the subject of much interest occasioned by the discovery of coal measures in the bed of the Severn, east of Almondbury.* The following is the account of a boring made near to Clapton Farm:†—

| | Ft. | In. |
|--------------------------------------|-----|-----|
| Soil and New Red Sandstone | 10 | 0 |
| Dolomitic conglomerate | 11 | 0 |
| Pennant Grit | 114 | 0 |
| Bed of marl with water | 1 | 0 |
| Pennant Grit | 20 | 0 |
| Clay | 5 | 2 |
| Coal | 0 | 10 |
| Shales | 60 | 0 |
| Pennant Grit | 220 | 0 |
| Shales | 5 | 0 |
| Pennant Grit | 63 | 0 |
| Total | 510 | 0 |

Coal also appears to have been found, one seam four feet thick, in the railway cutting at Almondbury, and at Cattybrook, burning freely with a white ash; these seams lying almost vertically appear to have been worked during the past century, from the fact that old tokens (1756) of the Birmingham Mining Company have been found there.

Nailsea Basin.—The upper coal measures are absent in this basin; at Nailsea the Pennant Grit occupies all the central part of the valley about Nailsea church and village, and is seen to pass westwards. Its maximum thickness at Nailsea appears to be about 150 yards, and it contains a good seam of workable coal known as "Grace's Seam," three feet thick, which has been extensively wrought from several shafts in the neighbourhood of Nailsea church.‡ In the upper series of coal measures there are 16 seams of coal, in the Pennant series from two to three, and in the lower series 26 seams in the central area, decreasing to seven in the northern area.

THE RADSTOCK GROUP contains eight seams, varying from 10 inches to two feet four inches, and even more in thickness, giving from 70 to 100 feet thickness of coal. The group in the Farringdon series has eight seams, varying from 1 foot to 3 feet

* "Royal Coal Commission Report," vol. i., p. 57.

† "Coal-fields of Gloucestershire and Somersetshire," p. 55.

‡ "Coal-fields of Gloucestershire and Somersetshire," p. 66.

10 inches in thickness. Again, at Coal Pit Heath, and Parkfield in Gloucestershire, there are six seams, varying in thickness from 18 inches to 2 feet 10 inches.

THE NETTLEBRIDGE DISTRICT contains four seams of coal in the Pennant Grit which have been occasionally worked; the coal wrought from these seams is mostly small, and the hardness of the rock and the presence of water renders the working of these thin seams unprofitable. The lower coal measures contain the most valuable and the greatest number of coal seams, which are also those most extensively worked. In the Nettlebridge Valley this series comprises about 25 seams, varying in thickness from 15 inches to 6 feet. At Bitton Bristol and Kingswood there are about 29 seams, varying in thickness from 1 foot to 6 feet.*

Coal has been wrought, though not in considerable quantities, for three or four centuries, in the Nettlebridge Valley, and probably in the neighbourhood of the Bristol coal-field. In the working of the coal seams, the "long wall" system is that usually adopted, and Mr. W. W. Smyth observes, "that the mode of working adopted in the district, coupled with certain local advantages, has rendered it possible to work coal seams of little more than one foot thick."† At the Writhlington collieries a seam is worked which often does not exceed 8 to 10 inches in thickness. This would not be worked if it were continuously of such small size, but its ordinary thickness is 14 inches in the neighbourhood of Radstock.

Underground water appears rarely to interfere with the working of coal in this coal-field; in reference to this point Professor Prestwich observes that "the faults as usual assist in impeding the circulation of underground water. But probably this is owing to the great extent of secondary rocks covering and protecting the outcropping edges of the coal measures from rain and surface waters."‡ In some districts, however, as at Kingswood, the water accumulated in the old workings is a source of great danger to modern collieries, so much so, that the fear of tapping them has retarded to some extent mining operations.

* "East Somerset and Bristol Coal-field," pp. 32, 33.

† "Coal and Coal Mining," 1867, p. 64.

‡ "Coal Commission Report," vol. i. p. 41.

Analyses of the Coal.—A few examples of the constituents of the coals raised in the Bristol coal-field will show generally their commercial value. The coals from the Radstock seams are usually considered as the best for household purposes; they burn briskly, make a clear fire, and as they give out a great heat are valuable as a cooking coal, and leave but a small quantity of ash. The Hard Vein or Top Coal, the uppermost seam of the workable coal, having a rock roof of considerable thickness above, the seam largely composed of stems of calamites, &c., in the body of the coal, causing some difficulty in working it free from shales and impurities. Another seam, lower in the series, is the "Holybush," a coal tolerably hard and suitable for gas manufacture. Analyses of these seams give the annexed results:—

| Constituents. | Hard Seam. | Holybush Seam. |
|--------------------------|------------|----------------|
| Ash | 4·27 | 5·93 |
| Fixed Carbon | 63·55 | 59·10 |
| Volatile matter | } 32·18 | 34·97 |
| Water | | |
| | 100·00 | 100·00 |
| Specific gravity | 1·28 | 1·28 |
| Sulphur | 1·625 | 1·64 |

One pound of coal of the Hard Seam will convert 18·80 lbs. of water into steam at the temperature of 212° Fahr. The evaporative power of the Holybush Seam being 14·40 lbs. of water converted into steam under the same conditions.

The "Great Vein" of the Kingswood series, and indeed of the Bristol coal-field, is greatly valued as a steam coal, and is extensively used in the Bristol district as a house coal; the seam averages from 4 ft. 6 in. to 5 ft. in thickness, is easily wrought, though requiring much timbering to keep the roads secure and the workings safe; and it is said to be very free from dirt. Other good workable seams, the "Two-foot," or "Little Toad Vein," and the "Lower Fire Coals," may be referred to; this last seam is made up of five coals with shaly partings, the latter collectively 2 ft. thick, leaving 8 ft. of coal. The top of this seam is sound, and the ironstone measures in the roof render it

a valuable seam. The above-named coals show the annexed results on analyses :—*

| Constituents. | Great Vein. | Little Toad Vein. | Lower Five Coals. |
|--------------------------|-------------|-------------------|-------------------|
| Ash | 5·84 | 9·59 | 7·64 |
| Fixed Carbon | 70·84 | 69·80 | 68·10 |
| Water | 1·50 | 1·43 | ... |
| Volatile matter | 21·82 | 19·18 | 24·26 |
| | 100·00 | 100·00 | 100·00 |
| Sulphur | 1·16 | 1·80 | 1·85 |
| Specific gravity | ... | ... | 1·34 |

Production and Distribution of Coal.—In the beginning of the present century there were 24 collieries in Somersetshire, with a total of 29 pits from which coal was drawn; they were distributed as follows in districts :—

| Districts. | Collieries. | Pits. |
|----------------------|-------------|-------|
| Nettlebridge | 7 | 8 |
| Paulton | 10 | 14 |
| Radstock | 7 | 7 |
| Total | 24 | 29 |

At the time referred to (1800) careful inquiries assume that 20 tons of coal were daily drawn from each pit, giving an annual production of 185,540 tons; since, however, many of the collieries would lie idle in summer, and all of them working leisurely, it is estimated that not more than 140,000 tons were raised. The general character of the coals raised will appear from the following remarks by Professor Prestwich :†—"The quality of the coals of the Somersetshire and Gloucestershire coal-field is not such as to compete for household purposes with the Newcastle coals in other markets, owing to their leaving an ash in burning. Many of the seams are otherwise of a good and useful description, whilst others are extremely well adapted for steam and locomotive purposes, for gas making, and some are especially

* "The Bristol Coal-field," a paper read before the British Association, at Bristol, 1875.

† "Coal Commission Report," vol. i., p. 39.

valuable as smiths' coal and for iron smelting. With the exception of their use for the latter purpose, which even now leads them to be sent to Reading and as far as Birmingham, they are not likely, for the present at all events, to be much sought after for a distant supply."

The seams in the upper coal measures at Radstock and Farington furnish good household coals, those in and around Bristol are chiefly used for gas manufacture. The lower coal measures in Gloucestershire furnish some good household coals, particularly the Kingswood "Great Seam;" they also yield smiths', coking, and steam coals. In the Nettlebridge valley the seams generally afford good smiths' or coking coal.

In the year 1864 Messrs. Greenwell and McMurtrie gave the following as the number of collieries and pits in the Radstock district; they were:—

| Districts. | Collieries. | Pits. |
|----------------------|-------------|-------|
| Nettlebridge | 4 | 4 |
| Radstock | 10 | 13 |
| Paulton | 12 | 12 |
| Total | 26 | 29 |

The estimated daily output in the same year being—Nettlebridge, 290 tons; Paulton, 650 tons; and Radstock, 1,160 tons, giving a daily total yield of 2,100 tons. Making due allowance for inactivity during the summer months, the annual production of coal did not exceed 600,000 tons. In the year 1867 the output of these collieries amounted to 413,678 tons; the details are thus given:—

| Districts. | Coal. | Slack. | Total. |
|----------------------|---------|--------|---------|
| | Tons. | Tons. | Tons. |
| Nettlebridge | 10,919 | 8,081 | 19,000 |
| Radstock | 219,502 | 38,940 | 258,442 |
| Paulton | 110,846 | 25,390 | 136,236 |
| Total | 341,267 | 72,411 | 413,678 |

In order to arrive at the total returns of coal raised in Somersetshire it is necessary to add an additional return of six collieries

in the Radstock district, not included in the above, also coal allowance to workmen, and engine coal. The output of the Radstock collieries would therefore stand as follows for the year 1867:— *

| | TONS. |
|---------------------------------|----------------|
| Returns received | 413,678 |
| Radstock (additional) | 115,000 |
| Workmen's coal | 7,000 |
| Engine coal | 10,000 |
| Total | <u>545,678</u> |

For a few years the collieries in the Radstock and Nailsea districts are separately distinguished, producing coals in the following quantities:—

| Year. | Radstock. | Nailsea. |
|-------|-----------|----------|
| | Tons. | Tons. |
| 1863 | ... | 22,295 |
| 1864 | 600,000 | 33,234 |
| 1867 | 545,678 | 23,224 |
| 1868 | 586,000 | 20,000 |
| 1869 | 539,000 | ... |

The production of the Nailsea collieries in 1868 was distributed as follows:— †

DISTRIBUTION AND USES.

| | TONS. |
|---------------------------------------|---------------|
| The glass works consumed | 15,500 |
| Sales in the country around | 3,000 |
| Engine coals and pit fires | 1,250 |
| Colliers' allowance | 250 |
| Total | <u>20,000</u> |

Since the year 1870 the output of the collieries in the Somerset coal-field, together with the produce of collieries in the Bristol district, are available, and are given in the following quantities, with the total number of collieries in both divisions of the coal-field; the production of Somersetshire, in 1880, amounting to 757,802 tons, and the Bristol Coal-field 475,807 tons, giving a total of 1,233,609 tons, compared with 1,048,567 tons in the year 1870:—

* "Coal Commission Report," vol. iii., p. 127.

† Ibid., 126.

| Year. | SOMERSETSHIRE. | | BRISTOL. | | TOTAL. | |
|-------|----------------|---------|-------------|---------|-------------|------------|
| | Collieries. | Coal. | Collieries. | Coal. | Collieries. | Coal. |
| | Nos. | Tons. | Nos. | Tons. | Nos. | Tons. |
| 1870 | 34 | 525,000 | 18 | 523,567 | 52 | 1,048,567 |
| 1871 | 35 | 673,878 | 18 | 573,704 | 53 | 1,247,582 |
| 1872 | 33 | * | 15 | * | 48 | 1,280,000† |
| 1873 | 34 | * | 16 | * | 50 | 1,068,366 |
| 1874 | 38 | 609,684 | 18 | 480,275 | 56 | 1,089,959 |
| 1875 | 40 | 654,878 | 20 | 571,000 | 60 | 1,225,878 |
| 1876 | 45 | 650,415 | 21 | 589,538 | 66 | 1,239,953 |
| 1877 | 41 | 666,500 | 20 | 556,407 | 61 | 1,222,907 |
| 1878 | 39 | 693,000 | 21 | 539,121 | 60 | 1,232,121 |
| 1879 | 39 | 767,930 | 22 | 471,290 | 61 | 1,239,220 |
| 1880 | 39 | 757,802 | 22 | 475,807 | 61 | 1,233,609 |

The returns for the year 1880 giving an increase of 185,042 tons beyond those of 1870, and showing that while the Somerset area of the coal-field has increased its production to the extent of 232,802 tons in the period, the collieries of the Bristol district have fallen off to the extent of 47,760 tons. The distribution of the Somersetshire coal-field is mainly effected by the Great Western Railway, which system carried from the Radstock district coals in the following quantities since 1866:—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1865 | 211,936 | 1873 | 237,372 |
| 1866 | 211,948 | 1874 | 204,890 |
| 1867 | 222,948 | 1875 | 199,456 |
| 1868 | 254,134 | 1876 | 183,691 |
| 1869 | 271,326 | 1877 | 195,492 |
| 1870 | 294,310 | 1878 | 202,031 |
| 1871 | 306,732 | 1879 | 203,988 |
| 1872 | 261,657 | 1880 | 258,482 |

The great bulk of the above quantities were carried over the main line of the Great Western Railway, quantities not exceeding one-tenth of the above being passed over the stations beyond their system. The Westbury Iron Company in Wiltshire, it may be observed, derive their supplies of coal for their blast furnaces from their own collieries in the Nettlebridge Valley.

Prices of Coal at the Pit's mouth.—During the years 1868 and 1869, the best varieties of house coal obtained from the Easton and Whitehall Collieries in the Bristol district, varied at

* Production included in South Wales district.

† Production estimated.

the pit's mouth from 10*s.* to 13*s.* per ton; and coal suitable for steam purposes from 5*s.* to 6*s.* per ton, the cost of cartage to Bristol being 2*s.* and to Clifton 3*s.* per ton.

The coal of the Ashton Vale and Bedminster Collieries in the Paulton district were quoted at the same period: Bedminster screened, 10*s.* 6*d.*; picked lumps, 13*s.*; Ashton Vale slack, 5*s.* per ton. In the Radstock district in 1870 the best varieties of coal were quoted as follows:—Bull Hall coal, 11*s.* 8*d.* to 14*s.* 2*d.*; slack, 4*s.* 9*d.* to 5*s.* 6*d.*; Coal Pit Heath, from 7*s.* to 10*s.*, and slack, 4*s.* per ton; while in the Paulton and Bedminster Collieries coals varied from 8*s.* to 11*s.*, and slack from 3*s.* to 7*s.* per ton.

In the year 1880 in the Bristol district the average prices of best house coals at the pit's mouth was 9*s.* 9*d.*, and in Somersetshire generally about 10*s.*, the highest price obtained for coals being 14*s.*, and the lowest 6*s.* 10*d.* per ton; slack varied from 2*s.* 4*d.* to 5*s.*, the average being 4*s.* per ton.

Population employed in Coal Mining.—In the year 1854 the number of persons of all ages engaged in coal mining was 5,180, and in iron mining 68. There is no information available in subsequent years showing the numbers of persons employed until the year 1873, arising from the fact, that in intervening years the numbers thus engaged were included in other districts. In 1873 and since ample information is available, giving the number of persons employed underground and above ground, distinguishing the Somersetshire from the Bristol area of the coal-field.* The numbers engaged in Somersetshire were as follows, with the quantity of coal raised, to which is added the average produce per person in each year:—

SOMERSETSHIRE AREA OF THE COAL-FIELD.

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 3,707 | 967 | 4,674 | 609,039 | 130 |
| 1875 | 3,674 | 916 | 4,590 | 640,508 | 139 |
| 1876 | 3,631 | 891 | 4,522 | 650,714 | 144 |
| 1877 | 3,347 | 783 | 4,130 | 670,256 | 164 |
| 1878 | 3,348 | 844 | 4,192 | 692,942 | 163 |
| 1879 | 3,464 | 786 | 4,250 | 742,060 | 174 |
| 1880 | 3,508 | 757 | 4,265 | 757,802 | 178 |

* H.M. Inspectors of Mines' Reports, 1874 to 1880.

The efficiency of the mines in this division of the coal-field shows favourably in 1880 compared with 1874, to the extent of 48 tons per man, equivalent to an increase of 83 per cent.

In the Bristol division of the coal-field the numbers of persons employed were as under, with the coal produced, and the average yield per man :—

BRISTOL AREA OF THE COAL-FIELD.

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 2,713 | 600 | 3,313 | 497,042 | 150 |
| 1875 | 2,782 | 675 | 3,457 | 571,050 | 165 |
| 1876 | 2,518 | 607 | 3,125 | 541,853 | 173 |
| 1877 | 2,516 | 618 | 3,134 | 518,995 | 166 |
| 1878 | 2,305 | 590 | 2,895 | 482,129 | 166 |
| 1879 | 2,362 | 606 | 2,968 | 501,559 | 169 |
| 1880 | 2,382 | 578 | 2,960 | 475,807 | 160 |

In that part of the Bristol coal-field in Somersetshire a steady increase per man appears in 1880 compared with 1874. However, to arrive at average results for the whole coal-field, it is necessary that both districts should be summarised; the result is as follows :—

SOMERSET AND BRISTOL COAL-FIELD.

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1874 | 6,420 | 1,567 | 7,987 | 1,206,081 | 151 |
| 1875 | 6,456 | 1,591 | 8,047 | 1,211,558 | 150 |
| 1876 | 6,149 | 1,498 | 7,647 | 1,192,567 | 156 |
| 1877 | 5,863 | 1,401 | 7,264 | 1,189,251 | 163 |
| 1878 | 5,653 | 1,434 | 7,087 | 1,175,071 | 163 |
| 1879 | 5,826 | 1,392 | 7,218 | 1,243,619 | 172 |
| 1880 | 5,890 | 1,335 | 7,225 | 1,233,609 | 171 |

Resources and probable Duration of the Coal-field.—This coal-field has an area of 238 square miles, 14 of which are exposed, including that part in Gloucestershire. The coal-field is remarkable from the circumstance of so large a portion of it

being covered by the New Red Sandstone, Lias, and Oolites, under which it is worked to a considerable extent. Its area may be divided into three portions.*

EXTENT OF THE SOMERSETSHIRE AND BRISTOL COAL-FIELD.

| | AREA IN ACRES. |
|--|----------------|
| Portion of exposed coal measures | 30,580 |
| Portion of coal measures covered by and worked under the newer formations | 24,111 |
| Portion of coal measures covered by the newer formations and not yet worked | 98,089 |
| Total extent of the Coal Measures | <u>152,780</u> |

The coal already wrought is estimated to cover an area of 24,111 acres, each acre being estimated to yield 1,500 tons of one foot thick, an allowance of from one-tenth to one-third being made for waste in working, faults, &c. The quantity of coal already wrought amounts to 114,024,685 tons, obtained as follows:—

| COAL MEASURES. | TONS. |
|---------------------------------|--------------------|
| From the Upper Series | 49,698,786 |
| „ Pennant Grit | 1,245,025 |
| „ Lower Series | 58,080,874 |
| „ sundry small pits | 5,000,000 |
| | <u>114,024,685</u> |

All this coal, except 27,000 tons, has been wrought at a depth not exceeding 1,500 feet, the 27,000 tons being wrought at a depth of from 1,500 feet to 1,940 feet.

The total coal remaining unwrought and available for use to a depth of 9,000 feet is estimated to amount to 6,944,810,982 tons, from which a deduction of one-fifth is made for possible over estimates on the coals of the lower series (amounting to 4,200,000,000), equal to 840,000,000 tons, leaving the total of workable coal remaining unwrought as above stated 6,944,810,982 tons. Or, taking the total at all depths down to 4,000 feet, there yet remains available for future supplies 4,218,970,762 tons. The distribution of the coal is as follows to the depth of 9,000 feet:—

* “Coal Commission Report,” vol. i., p. 36.

| | TONS. |
|--|----------------------|
| 1. Not exceeding 1,500 ft. | 1,718,791,280 |
| 2. Between 1,500 ft. and 3,000 ft. | 1,519,997,981 |
| 3. „ 3,000 ft. and 6,000 ft. | 2,227,531,577 |
| 4. „ 6,000 and 9,000 ft. | 637,990,144 |
| Total to 9,000 ft. | <u>6,104,310,982</u> |
| Total to 4,000 ft. | <u>4,218,970,762</u> |

Professor Prestwich observes with regard to the duration of the coal-field: The present quantity of coal wrought in this coal-field has been calculated to vary from 750,000 tons (1859) to 1,000,000 tons, at which latter Mr. Cossham estimated it in 1868. Adopting the latter estimate, the quantity of coal remaining unwrought, at this rate of consumption, is sufficient, supposing the whole quantity to be available, for 6,104 years, or supposing a limit in depth, the duration of the supplies from the respective zones would be as under:—

| | YEARS. |
|---|--------------|
| 1. Not exceeding 1,500 ft. sufficient for | 1,719 |
| 2. Between 1,500 and 2,000 ft. sufficient for | 1,520 |
| 3. „ 3,000 and 6,000 ft. „ | 2,227 |
| 4. „ 6,000 and 9,000 ft. „ | 638 |
| | <u>6,104</u> |

Or the total to the depth of 4,000 feet may be estimated as equal to a supply for 4,219 years.*

Taking the production of Somersetshire as recorded in the “Mineral Statistics, 1870,” amounting to 1,048,567 tons, and dealing with the above available quantities, sufficient supplies would be ensured by the store of coal to the depth of 9,000 feet for 5,821 years, and to the depth of 4,000 feet for 4,024 years.

Again, deducting the production of the past ten years (amounting to 11,894,553 tons), from the original quantities unwrought, there remained at the end of 1879 to the depth of 9,000 feet 6,092,416,429 tons, and to the depth of 4,000 feet 4,207,076,209 tons, which at the average production of the ten years (1,189,455 tons) would afford supplies at the former depth for 5,122 years, and the latter 3,527 years.

* “Coal Commission Report,” vol. i., pp. 50, 51.

CHAPTER XVII.

DEVONSHIRE COAL AND LIGNITE DEPOSITS.

Description of Bovey Tracey Coal or Lignite Deposits—Anthracite of Bideford—Analyses and Production of Lignite and Anthracite.

Devonshire. Bovey Coal, or Bovey Tracey Lignite.—This deposit is found near the town or village of Bovey Tracey, on the left bank of the river Bovey, and about two miles and a half above the point at which it falls into the river Teign, being about eleven miles distant from each of the towns Exeter, Torquay, and Totnes.

The deposit is described by Mr. Pengelly, F.G.S.,* as stretching away in a south-easterly direction, having a length of six miles from a point about a mile west of Bovey to another nearly as far east as Newton; its greatest breadth, from Chudleigh Bridge on the north-east, to Blackpool on the south-west, being about four miles. It forms a lake-like expansion of the valleys of the Teign and Bovey rivers, especially the latter, whose course it may be said to follow in the higher part, where it is most fully developed; whilst the Teign constitutes its axis below the junction of the two streams. Its upper or north-western portion immediately adjacent to the village, is known as "Bovey Heathfield," and extends over an area of about 700 acres.

Shafts and other excavations have shown that this basin consists of an accumulation of coarse gravel (mixed with sand and clay) of variable thickness, unconformably covering distinct strata of lignite, clay, and sand, which are familiar to geologists as the "Bovey deposit," whilst the lignite is equally well known as "Bovey Coal." This deposit not only occupies the plain which has been described, but is continued in a narrow southerly direction from Newton, to near Kingskerswill, about three and a half

* "Memoirs on the Lignites and Clays of Bovey Tracey." Transactions of the Royal Society, part 2, 1862.

miles from Torbay; and where it crosses the estuary of the Teign it is distant about four miles from the coast.

The most important of the excavations is that known as the "Coal Pit," which is situated on the Heathfield, somewhat less than a mile south of the village, and about the same distance from the western margin of the deposit. It is open to the day, and is in form a rude parallelogram, having its longest side about 960 feet, whilst the shortest measures 340 feet, its greatest depth at the western end being about 100 feet. Subterranean excavations have been carried on very extensively in various directions by means of tunnels opening out of the pit at its bottom.

Attention was first directed to this deposit in the year 1760, when the Rev. Jeremiah Milles communicated his views to the Royal Society in a letter addressed to the Earl of Macclesfield,* although it appears that the lignite was discovered about the year 1745, and probably at an earlier period. Dr. Maton, about the year 1796, in his "Observations on the Western Counties of England," gives some particulars respecting the Bovey deposits, apparently from actual observations. The pits at this time were of considerable depth, 80 feet, and the lignite was worked to supply fuel for a pottery close by. About the year 1812, another pottery was established near Bovey Tracey, called Folley Pottery, from the coal-pits, the lignite being locally known as Folley Coal. In 1853 the pottery kilns were fired with lignite; later, in 1869, it was not employed in the earthenware kilns, the small quantity then used being in the brick-works of the neighbourhood, where it is also used in small quantities in the cottages, but the disagreeable smell which it gives out in burning renders it objectionable.

Some years since a company engaged in working iron ore at Ilington proposed to use this Bovey lignite for smelting the ore; two blast furnaces were commenced, but ere they were completed the company was dissolved, and the experiment for using this lignite for iron smelting was never tried.

Analysis of the Bovey Tracey Lignite.—The Bovey coal, examined by Fred. Vaux, Esq., in his paper "On the Ultimate Analysis of some Varieties of Coal," † is thus described:—Be-

* "Philosophical Transactions," li., part 2, p. 534, &c.

† "Journal of the Chemical Society of London," vol. i., p. 318 (1849).

comes quite rotten after immersion in water; that it does not soil the fingers; that the coke has a semi-metallic lustre, does not smell, cakes but slightly, and does not take the form of the crucible; that it is easily converted into a bulky red ash, interspersed with filaments; that before the blowpipe it is partially, but with difficulty, fusible into a black clinker; and that its composition is shown in the annexed table, giving the relative proportions in 100 parts of Bovey lignite, exclusive of water.

RESULTS TABULATED.

| | |
|--------------------|--------|
| Carbon | 66·314 |
| Hydrogen | 5·627 |
| Oxygen | 22·861 |
| Nitrogen | 0·565 |
| Sulphur | 2·364 |
| Ash | 2·269 |
| Water | 34·660 |
| Coke | 30·799 |

Free from Water and Ash.

| | |
|--------------------|---------|
| Carbon | 67·8535 |
| Hydrogen | 5·7576 |
| Oxygen | 23·3920 |
| Nitrogen | 0·5781 |
| Sulphur | 2·4188 |

Copper and lead, it is stated, were detected in the ash.

Another sample of the Bovey lignite called "Board Coal," from a bed about four feet thick in the "Board Coal Seam," is thus described in Dr. Percy's "Metallurgy."* The analysis was made by Mr. William Ratcliffe, and was communicated by the late Mr. Ebenezer Rogers, of Abercarne, near Newport, Monmouthshire:—"It abounds in the remains of dicotyledonous plants, and is woody in structure. It is said to yield a bright, hard, porous coke. The hygroscopic water was estimated by the loss in weight by drying at 100° C., and the specimen analysed had been previously dried at that temperature. It is stated that there are also twenty seams of what is locally termed "rough coal," with which a large proportion of clay is intimately mixed; a specimen of this variety yielded after air-drying at 37° C., 52·37 per cent. of coke, containing 29·98 of ash, which contained 0·532 per cent. of phosphoric acid, and of which 65·48 per cent.

* "Fuel," 1875, pp. 312, 313.

was insoluble in hydrochloric acid, and consisted chiefly of silica."

The results appear in the annexed analysis, the composition per cent. being exclusive of water, which gave 2·21 per cent., the yield of coke amounting to 51·50 per cent.

RESULTS TABULATED.

| | |
|--------------------|--------|
| Carbon | 66·76 |
| Hydrogen | 5·59 |
| Oxygen | 22·81 |
| Sulphur | 2·09 |
| Ash | 2·75 |
| | <hr/> |
| | 100·00 |

The composition per cent., exclusive of ash and water, being carbon, 70·15; hydrogen, 5·88; oxygen and nitrogen, 23·97 per cent.

Production of Lignite.—The quantity raised at the Brown Coal Mine in the year 1854 amounted to 15,000 tons; in subsequent years the output has been as follows :—

| YEAR. | TONS. |
|----------------|-------|
| 1856 | 5,600 |
| 1857 | 3,850 |
| 1867 | 1,368 |
| 1868 | 1,383 |

The above are the only returns obtainable. Since the last-named year some quantities have been raised from time to time, but being included in other districts the exact quantities are not known.

Bideford Anthracite.—Another description of coal which has been worked in Devonshire is the variety known as culm or anthracite of Bideford. These beds of anthracite stretch across the country, from Barnstaple Bay by Bideford and Alverdiscot towards Chittlehampton, and there are evidences that these culm deposits were worked on the line of the out-crop at a remote period. Many old workings have from time to time been discovered, some of the pits having been carried to depths of from eight to ten fathoms. The beds of culm are very variable in thickness, the middle or great anthracite bed upon which all the chief workings have been carried is described as varying from

6 inches to 14 feet in thickness, the average being about 7 feet. According to Lysons, the beds in the vicinity of Eastacot were extensively worked in the middle of the last century. A pit here was re-opened about the year 1790, and abandoned in the following year on account of the water, when the pit reached a depth of 25 fathoms, the quantity of anthracite raised being about 900 bushels per week.

Sir Henry de la Beche,* writing in 1838, says, culm or anthracite beds are now at work about a mile on the east of Bideford. Mr. John Rundle, M.P., who is interested in them, states that about twelve or eighteen months previously, they drove a little under the adit, and in a short time obtained from 600 to 700 tons of anthracite. It appears that these mines were partially opened about 1825 for 200 fathoms in length, above an adit 15 fathoms deep. The eastern mine in full work employed three men and five boys, and produced about 700 bushels or 58 tons of anthracite per week. From the western mine about 1,500 tons were raised in the year. The quantities raised of late, as far as returns are available, are inconsiderable, and are as under :—

| YEAR. | TONS. |
|----------------|-------|
| 1854 | 6,500 |
| 1856 | 5,036 |
| 1857 | 4,173 |

Some quantities, it is said, were raised in the year 1877 and since; they were, however, small, and do not appear to have been recorded.

This fuel was at one time extensively used at Greenacliff in Barnstaple to burn with the limestones brought there from South Wales. A variety of the anthracite, probably formed from decomposed portions of it, has long been raised near Bideford and employed as a pigment. Lysons † says it was used in Plymouth in 1822, and at a later period it was sent to Chatham for the same purpose. The quantity (paint-clay) raised in the year 1880 amounted to 200 tons.

* "Geological Report on Cornwall, Devon, and West Somerset," 1839, p. 514.

† "Magna Britannia," Devonshire, p. ccxcii.

CHAPTER XVIII.

THE COAL-FIELDS OF SCOTLAND.

General Description of the Coal-fields—The Carboniferous Series of Scotland—Section of Strata, Order and Occurrence of Coal Seams and Ironstone Measures in different Areas—Varieties of Coal and Analyses—Gas Producing Coals, Cannels, Analyses, and Yield of Gas in Cubic Feet—Production of Coal in the Eastern and Western Districts, and of the several Coal-fields—Distribution Coastwise and to Foreign Countries—Railway Distribution—Prices of Coal and Cost of Production—Population Employed in Coal and Ironstone Mining—Resources and probable Duration of the Scotch Coal-fields.

Coal-fields of Scotland.—The carboniferous rocks of Scotland cross the country in a direction from south-west to north-east, stretching from sea to sea, from the Firth of Clyde on the east to the Firth of Forth on the west, and occupying the great synclinal hollow or trough along the valley, and parallel to the mountain chains of the Grampians and Lammermuirs, or between the slopes of the Grampians and the north flanks of the southern uplands. This great hollow, or depression, is filled with a coal-field nearly 100 miles in length, extending from Saint Andrew's, near Greenock, to the eastern coast, and from Dalkeith, near Edinburgh, to Ayr on the western coast, an average breadth of 25 miles. The area thus described is not all productive of coal; in it occur several distinct coal-fields, or basins, divisible into six, viz., the coal-fields of the Clyde basin, the Mid Lothian, Edinburgh and Haddington coal-field, the East Lothian coal-field, the Fifeshire, Clackmannan, Ayrshire, and Lesmahago coal-fields.

The greatest part of the workable coal seams of the Scottish area is included in the carboniferous limestone group; for the English lower carboniferous rocks undergo a gradual physical change in their extension, from south to north, or from the Midland Counties into Northumberland and South Berwickshire, and coal seams occur and are worked in them near the base, associated with thick beds of shale, the calcareous beds having greatly diminished. Below the equivalents of our carboniferous limestone are a series of white and grey sandstones, shales,

cement stones, and thin coal seams. These equal the English lower limestone shales, and are termed "calciferous sandstones," which sometimes attain a thickness of 4,000 feet.

The carboniferous series of Scotland, divisible into four groups, are thus classified by Professor A. Geikie, F.R.S., in the third edition of Juke's "Manual of Geology:"—

| DIVISIONS. | | ENGLISH EQUIVALENTS. |
|---------------------------------------|--|--|
| 4. Coal measures | { Red sandstones (Hamilton) white and grey sand- stones, shales, fire-clays, coal seams, and ironstone. | Middle and Lower coal measures. |
| 3. Millstone grit | { Moorstone rock, or Roslin sandstone and conglom- erate. | Millstone grit and Yoredale series. |
| 2. Carboniferous limestone series. | { Sandstones, sometimes coarse shales, coals, black- band, and clay-band iron- stones, oil shales, and fossiliferous limestones. | Carboniferous or mountain lime- stone. |
| 1. Calciferous sandstone series. | { White and grey sandstone shales, cement stones, cyprid limestones and occasional coal seams. | Lower limestone shale. |

The aggregate thickness of the carboniferous series of the centre of Scotland gives a section of from 8,000 feet to 9,000 feet, the greater part of which is regarded as of marine origin.

The lowest series, the calciferous sandstones, may be described as being composed of a lower group of red sandstones and another group, the characteristic feature of which is the presence of bituminous shale. Next in order of occurrence ascending appears the carboniferous limestone series, divisible into three well-marked groups. First, an upper group, consisting chiefly of sandstone, &c., and with some three or more seams of limestone; the second, a middle group of sandstones and argillaceous shales, with numerous seams of coal and ironstone, but no limestone; and the third, a lower series or group of strata, with seams of coal and ironstone and a variable number of limestones.

The lower group is very variable as regards the number and quality of its coal, ironstone, and limestone seams, and the absolute thickness in which these occur. In some districts, as in Ayrshire, one or two limestones occur in a thickness of eight or ten fathoms of strata, and not unfrequently no coal or ironstone

seams of commercial value. In other localities, as at Carluke, and along the southern borders of the Lanarkshire coal-field, no fewer than eleven limestones occur in a thickness of 35 fathoms of strata, while at the same time occur a number of excellent bands of argillaceous ironstone. The middle group of the limestone series is characterised by the presence of numerous coal and ironstone seams, and by the total absence of limestones. One or two seams of black-band ironstone appear in this horizon, and about midway, between the top and bottom of the series, occurs the celebrated Lesmahago gas-producing coal, yielding 13,500 cubic feet of gas, of a high illuminating power, from one ton of coal. The upper limestone group, of the carboniferous series, as exhibited in Lanarkshire, has a great sameness of character in all the localities where it occurs. Usually it contains three limestones, and here and there one or two lenticular and inconstant seams of the same mineral, of variable qualities and thickness. Mr. James Geikie, in his interesting papers on the "Coal and Ironstone-bearing Strata of Scotland," from which many of the foregoing facts are drawn, considers that the numerous coal seams point to the frequent occurrence of a land surface, and the gas coals and ironstones to the former existence of numerous wide lakes and lagoons.

It is not uncommon to find lines and ribs of gas coal associated with seams of splint, and even with seams of common coals. Gas coals are not unfrequently found to pass into common coals, or into black shales, and sometimes into black band ironstone, and thus the same mineral seam may be alternately a common splint or gas coal, an oil shale or a black-band ironstone, according as the physical condition varied at the time of its formation. The millstone grit, reposing on the carboniferous limestone series above referred to, occasionally yields clay ironstone of good quality, the Curdly seam being the best known, and is an ironstone of variable thickness and purity, occurring in nodular masses. The coal measures at the top of the series, reposing on the millstone grit, consist of two groups, the upper consisting of a series of red sandstones, with intervening sandy marl and impure fire clays, resting unconformably upon the coal-bearing strata, and in the deeper parts of the Lanarkshire coal-field attaining a thickness of upwards of 700 feet. The lower or coal-bearing group, rich in coal, containing 18 workable seams; it

also contains several important seams of black-band and clay-band ironstones, which have been extensively wrought, and some nearly exhausted. The black-bands vary considerably, and do not often exceed 18 inches in thickness. In one locality, however, the Crofthead slaty-band is said to have reached the thickness of six or seven feet.

In the Western coal-fields of Scotland seven principal black-band measures are known, occurring in the following order :—

| | THICKNESS. | |
|---|------------|-----|
| | Ft. | In. |
| Palace Craig, <i>black-band</i> | 1 | 2 |
| Airdrie, <i>black-band</i> | 1 | 4 |
| Bellside, <i>black-band</i> | 0 | 6 |
| Kiltongue, <i>black-band</i> | 0 | 8 |
| Calderbank or Kennelburn, <i>black-band</i> | 0 | 6 |
| Upper slaty, <i>black-band</i> | 1 | 3 |
| Lower slaty, <i>black-band</i> | 0 | 8 |

The above thicknesses are, however, subject to considerable variation, and the same seam is rarely continuous over any large area. Thus, at Airdrie, it occurs in workable quantities over an area not exceeding ten square miles, but its equivalent, in the form of a thin seam of coal, extends over an area of between 50 and 60 square miles. In Linlithgowshire the equivalent of the black-band ironstone is found in the celebrated Boghead cannel coal, or as it is also known by the name of the Torbane Hill mineral, which some years ago gave rise to much litigation.

The foregoing brief sketch of the carboniferous series of Scotland shows generally the geological features bearing on the occurrence of the coal seams and ironstone measures; some of the more important of the latter, as they occur in the Western coal-fields, being noted above. The next subject to follow will be the several coal-fields of Scotland.

Clyde Basin Coal-field.—This important coal-field, the largest in Great Britain, is traversed throughout its entire length by the Clyde, and includes the greatest part of the Shires of Renfrew, Dumbarton, Stirling, and nearly the whole of Lanark. The coal-bearing series are 4,000 feet thick, divided into upper, middle, and lower, and respectively 840 feet, 960 feet, and 2,200 feet thick, the base of the whole being the calciferous sandstone. The upper and lower series are the chief repositories of the coal seams. The upper series has ten seams of coal exceeding two feet in thickness, and three valuable bands of ironstone. The

lower series contain three courses of ironstone, and several valuable beds of coal, west of Glasgow. The black-band ironstones occasionally pass into coal seams, the carbonaceous matter gradually replacing the argillaceous carbonate of iron.

The following section, communicated to the Philosophical Society of Glasgow by Mr. William Moore, shows the order of occurrence of the coal and ironstone series in that part of the coal-field lying in the valley of the Clyde:—

COAL AND IRONSTONE SERIES.

| DEPTH IN FATHOMS. | | | THICKNESS. | |
|----------------------|--|-----------|------------|-----|
| | | | Ft. | In. |
| 42. | Palace Craig <i>Ironstone</i> (impure) | | 0 | 0 |
| 48. | Upper Coal (good) | 3 ft. to | 4 | 6 |
| 63. | Ell Coal (good) | 4 ft. to | 8 | 0 |
| 67. | Pyotahaw Coal (splint) average | | 4 | 0 |
| 68. | Main Coal (good soft quality) | 3½ ft. to | 5 | 0 |
| 76. | Humph Coal | | 1 | 8 |
| 81. | Splint Coal (for iron smelting) | | 3 | 0 |
| 84. | Sour Milk Coal (variable) | | 3 | 0 |
| 103. | Mushet <i>Black-band Ironstone</i> | | 1 | 4 |
| 106. | Soft-band <i>Ironstone</i> | | 1 | 8 |
| 120. | Curly-band <i>Ironstone</i> | | 0 | 5 |
| 127. | Virtue Well Coal | | 2 | 6 |
| 132. | Bellside <i>Ironstone</i> | | 0 | 7 |
| 134. | Calderbrae <i>Ironstone</i> | | 0 | 8 |
| 136. | Kiltongue Coal (variable) | | 5 | 0 |
| 148. | Drumgray or Coxrod Coal | | 2 | 0 |
| 203. | Slaty <i>Black-band Ironstone</i> | | 4 | 6 |
| 208. | Boghead Gas Coal (1 to 20 in.) | | 0 | 10 |
| 447. | Possil <i>Ironstone</i> | | 1 | 0 |
| 467. | Lesmahago Gas Coal | | 1 | 0 |
| 502. | Govan Band <i>Ironstone</i> | | 1 | 0 |

Analyses of the Coal.—The brown Cannel coal known as the Torbane Hill Mineral, and previously referred to, occurs in the upper coal measures, immediately above the millstone, grit, having a thickness varying from 16 inches to 2 feet, in contact with shale and clay ironstone, and resting on a bed of underclay, after the manner of ordinary coal. The principal localities in which it occurs is at Torbane, Inchcross, Boghead, Cappers, and Bathvale near Bathgate. It is the most valuable mineral known for making gas and paraffin oil. Dr. Andrew Fyfe, who examined and determined its composition, obtained from a single ton 14,880 cubic feet of gas, of an illuminating power equal to 7·72 spermaceti candles, besides 700 lbs. weight of coke; it also yields, on distillation, 125 gallons of paraffin oil per ton. A

striking characteristic of this Cannel is its indestructibility under atmospheric exposure, which does not depreciate its value in its gas-giving powers. Out of Scotland the only other localities in which Cannel coal is worked is at Leeswood (south of Mold), in Flintshire; Wigan, in Lancashire; and at Newcastle. The following table shows the results of Dr. Fyfe's examination of the Torbane Hill Mineral in comparison with other well-known Cannel coals. In Scotland the term "Parrot Coal" is applied to Cannel coal, from the loud crackling noise with which it flies to pieces, when placed upon the fire:—

| | LEESWOOD. | | Lancashire Wigan Cannel. | Torbane or Boghead Cannel. |
|---|-------------------|------------------|--------------------------------|----------------------------------|
| | Smooth Cannel. | Curly Cannel. | | |
| Cubic feet of gas per ton | 9·972 | 14·280 | 12·100 | 14·880 |
| Durability of gas per foot | 55·05 | 82·30 | 48·35 | 84·400 |
| Illuminating power per foot, candles | 8·2 | 1·09 | 5·00 | 10·300 |
| Grains of sperm per foot | 0·981 | 1·308 | 0·36 | 1·242 |
| Value of coals in pounds of sperm | 1401·7 | 2668·3 | 617·00 | 2736·000 |
| Comparative value of the coals | 5·610 | 5·025 | ... | 2·86 |

Other analyses of coal, made by Mr. Lewis Thompson, exhibit the following constituents; of these the Lesmahago Cannel is thus described: "massive, dull black; principal fracture, slaty conchoidal; cross fracture, conchoidal and angular; streak, black and somewhat shining: thrown on the fire, decrepitates slightly; does not split or fuse; colour of ash, white, with nitrate of cobalt, dirty blue; specific gravity, 1·220":—

| Constituents. | Lesmahago. | Boghead. | Capeldrea. | Lochgelly. |
|----------------------------|------------|----------|------------|------------|
| Volatile matter . . . | 49·60 | 68·40 | 54·50 | 33·60 |
| Coke | 50·40 | 31·60 | 45·50 | 66·50 |
| Ash | 9·10 | 22·80 | 10·50 | 13·10 |
| Sulphur in coal . . . | 2·23 | 0·53 | 0·65 | 0·75 |
| Sulphur in coke . . . | 1·14 | 0·08 | 0·20 | 0·25 |
| Sulphur in volatile matter | 1·09 | 0·45 | 0·45 | 0·50 |
| Ash in coke per cent. . | 18·05 | 70·25 | 23·07 | 29·70 |

The average yield of gas in cubic feet per ton of the above coals appears as follows: Lesmahago, 18,500; Capeldrea, 14,000;

and Lochgelly, 9,500. The above results were obtained after three distinct experiments were made upon each variety of Cannel operated upon. Another variety of Cannel, the Pirnie, at Methill, gives on analysis the following results:—

RESULTS.

| | |
|-----------------------------------|-------------------|
| Specific gravity | 1.126 |
| Gas, per ton | 13.500 cubic feet |
| Illuminating power | 28 candles |
| Coke and ash | 36.00 per cent. |
| Hydrocarbons | 20.00 " |
| Sulphuretted hydrogen | .50 " |
| Carbonic acid | 4.75 " |
| Carbonic oxide | 7.75 " |
| Volatile matter in coal | 65.00 " |
| Specific gravity of gas | .700 |

In the annexed statement appears the respective yield per ton in cubic feet of Cannel coals, extensively used in the manufacture of gas in Great Britain:—

| Cannels. | Counties. | Cubic Feet per Ton. |
|---|----------------------|---------------------|
| Boghead or Torbane } Mineral } | Linlithgow | 14,880 |
| Lesmahago | Lanark | 13,500 |
| Methill Pirnie | Fife | 13,500 |
| Overtown | Lanark | 13,000 |
| Wemyss | Fife | 14,300 |
| Arniston | Midlothian | 12,600 |
| Ramsay | " | 10,300 |
| Kirkness | Kinross | 12,800 |
| Capeldrea | Fife | 14,000 |
| Skatrig | Lanark | 10,400 |
| Lochgelly | Fife | 9,500 |
| Rigside | Lanark | 10,400 |
| Rochsoles | " | 11,900 |
| Leeswood (smooth) | Flint | 9,972 |
| " (curly) | " | 14,280 |
| Wigan | Lancashire | 12,100 |
| Ince Hall | " | 11,673 |
| Pelton | Durham | 11,500 |
| Levenson | " | 11,600 |
| Washington | " | 10,500 |

The quantity of coal used in Scotland in gas manufacture, as determined by the Royal Coal Commission in the year 1867, amounted to 263,261 tons, and in the year 1868 to 299,919 tons.

The celebrated Lesmahago gas coal, yielding 13,500 cubic feet

of gas, of a high illuminating power, exhibits the following constituents on analysis by T. H. Read, Esq. :—

| RESULTS TABULATED. | |
|-----------------------------|---------------|
| Carbon | 36·70 |
| Volatile material | 56·23 |
| Sulphur | ·55 |
| Ash | 4·30 |
| Water | 3·15 |
| Total | <u>100·93</u> |

The coals used in iron smelting and manufacturing purposes in Scotland, are numerous and various. In iron smelting, the Splint coal is generally employed in the furnace without previous coking, and from the following selected analyses it will be seen that these coals do not vary to any considerable extent in composition. The Splint coal is a variety of bituminous (Cannel) coal, with a slaty structure; its constituents appear in the annexed analyses :—

| Constituents. | 1. | 2. | 3. | 4. |
|-----------------------------|--------|--------|--------|--------|
| Carbon in coke | 52·83 | 54·25 | 52·04 | 53·77 |
| Volatile products | 35·57 | 32·95 | 39·14 | 31·07 |
| Sulphur | ·36 | ·20 | ·11 | ·34 |
| Ash | 2·38 | 3·25 | 1·07 | 4·27 |
| Water | 8·86 | 9·35 | 7·6 | 10·55 |
| Total | 100·00 | 100·00 | 100·00 | 100·00 |
| Coke per cent. | 55·35 | 57·58 | 54·05 | 58·45 |
| Specific gravity | 1·31 | 1·293 | 1·255 | 1·240 |

Coal for domestic purposes is extensively furnished by the following coal seams: the Ell, Main, Pyotshaw, Virtue Well, Kiltongue, and Drumgray. The last-named give the constituents following, on analyses :—

| RESULTS TABULATED. | |
|-------------------------------|--------------|
| Carbon | 55·8 |
| Hydrogen and Oxygen | 5·4 |
| Sulphur | 2·0 |
| Nitrogen | 34·0 |
| Ash | 2·8 |
| | <u>100·0</u> |

The coals of the above-named seams are also employed for steam purposes. As it might be interesting to view the quantity of coal in the light of the power it is capable of giving out, Mr. Ralph Moore, H.M. Inspector of Mines, illustrates the point. He states that a steam engine of average quality consumed ten pounds of coal per horse-power per hour, or it consumed 100 lbs. every day of ten hours while it did the work of a horse. A ton of coal would supply a horse's power for 24 days, and the quantity of coal raised in Great Britain, say 125,000,000 tons, would supply the power of 10,000,000 horses, or five times as many men. The coal annually exported, say 15,000,000 tons, would supply the power of 6,000,000 men. Taking the consumption of coal at 12 tons for the power of five men, and the coals at 10s. per ton, the power of five men could be obtained for £6 per year, or a man's power could be obtained for 25s. per year, 6d. per week, or 1d. per day, and thus the coal raised in the United Kingdom would be equal to an army of 50,000,000 of men, giving out their work at one penny per day.*

The Mid-Lothian, Haddington, and Edinburgh Coal-field.—This triple coal-field on the south-western side of the Firth of Forth, the waters of which separate it from the Fifeshire coal-field, possesses much interest geographically and physically, and with the Fifeshire area are the most interesting of the Scotch coal-fields. This triple coal-field, described by Professor Hull as a double trough, the deeper of which lies in Edinburghshire on the west, and the shallower on the east in Haddingtonshire, has nearly 50 seams of coal of varying thickness, giving in the aggregate 122 feet of solid coal. Celebrated amongst other coals here occur the 8-feet "Great Seam," and the "North Greens," 1,500 feet below the "Great Seam," yielding the well-known Parrot coal, having a thickness of 3 feet, and greatly esteemed as a coal for the manufacture of gas. Both the above-named seams occur in the carboniferous limestone, which has, in a section of 1,600 feet, 17 workable seams of coal; the coal measures proper, reposing on the millstone grit, having a thickness of 1,220 feet, in which are found 11 seams of coal. This coal-field has an area of 64 square miles, and the following section, taken from the centre of the coal-field near Dalkeith, shows the various coal-seams and their order of occurrence.

* Lecture by Mr. Moore. See Report, "Mining Journal," 4th March, 1876, p. 259.

COAL SEAMS OF MID LOTHIAN.

| | Ft. | In. |
|----------------------------------|-----|-----|
| Sandstone and shale | 346 | 0 |
| Clay Knowes Coal | 3 | 6 |
| Splint Coal | 3 | 10 |
| Beefie Coal | 3 | 6 |
| Jewell Coal | 4 | 0 |
| Coal | 2 | 8 |
| Cowpit's Little Splint | 2 | 2 |
| Cowpit's Five-foot | 5 | 6 |
| Glass Coal | 2 | 0 |
| Burr's Coal | 4 | 0 |
| Cowpit's Three-foot | 3 | 0 |
| Cowpit's Six-foot | 4 | 6 |
| Millstone Grit | 340 | 0 |

In this same area the carboniferous limestone series has a thickness of 1,590 feet, in which appear numerous seams of coal upwards of 2 feet thick, and in the same section are recognised nine seams of ironstone, of 2 inches thick and upwards:—*

CARBONIFEROUS LIMESTONE COAL SEAMS.

| | Ft. | In. |
|-----------------------------------|-----|-----|
| Cowden Deception Coal | 2 | 2 |
| „ Cryne | 2 | 6 |
| „ Mavis | 2 | 8 |
| „ Great Seam | 8 | 0 |
| „ Diamond | 2 | 7 |
| „ Lilla Willie | 5 | 1 |
| „ Blackbird Seam | 3 | 11 |
| „ Coronation | 3 | 10 |
| „ Hard Splint | 3 | 3 |
| „ Smithy Coal | 2 | 9 |
| „ Bryant's Splint | 5 | 8 |
| „ Aleck's Coal | 2 | 7 |
| „ Coal | 2 | 6 |
| „ Little Splint | 2 | 1 |
| Cowden Coal | 2 | 1 |
| „ Parrot Seam | 3 | 0 |
| „ Chalkieside Lime Coal | 3 | 0 |

The Jewell seam, in the Mid Lothian section (Edinburghshire), 4 feet in thickness, and the Coronation seam, in the carboniferous limestone series, 3 feet 10 inches in thickness, both seams worked at Dalkeith, have been examined and reported upon in the “Third Report of Coals Suited to the Steam Navy,” it being observed, during the experiments on these coals, “that they lighted easily, and burned freely, without the production of much smoke. They also required little stoking, and left but an inconsiderable quantity of incombustible matter.”

* “Coal Fields of Great Britain,” 4th edition, p. 305.

RESULTS TABULATED.*

| Constituents. | DALKEITH. | |
|--|------------------|--------------|
| | Coronation Seam. | Jewell Seam. |
| Carbon | 76·94 | 74·55 |
| Hydrogen | 5·20 | 5·14 |
| Nitrogen | trace | 0·10 |
| Sulphur | 0·38 | 0·33 |
| Oxygen | 14·37 | 15·51 |
| Ash | 3·11 | 4·37 |
| Total | 100·00 | 100·00 |
| Yield of coke | 53·5 | 49·8 |
| Specific gravity | 1·316 | 1·277 |
| Weight of cubic foot of coal | 55·16 lbs. | 49·8 lbs. |
| Space occupied by one ton | 43·36 c. f. | 44·98 c. f. |

The East Lothian Coal-field (Haddingtonshire), with an area of 30 square miles, possesses ten seams of coal of varying thickness. The strata in which they occur is carboniferous limestone, which completely encircles the coal-field on the east and south-east. The coal and ironstone of this area are regarded as the equivalents of the edge-coals of Mid Lothian. The following is a section of the coal series of East Lothian :—†

COAL SERIES OF EAST LOTHIAN.

| | Ft. | In. |
|---|-----|-----|
| Coal "Great Seam" | 7 | 0 |
| Strata | 50 | 0 |
| Splint Coal | 4 | 0 |
| Strata from 7 ft. to | 18 | 0 |
| Parrot Coal | 1 | 8 |
| Strata from 7 ft. to | 34 | 0 |
| Three-foot Coal | 2 | 6 |
| Strata | 9 | 0 |
| Four-foot Coal from 3 ft. 8 in. to | 4 | 11 |
| Strata | 118 | 0 |
| Five-foot Coal | 4 | 0 |
| Strata with Black Band Ironstone about | 130 | 0 |
| Panwood Coal | 1 | 6 |
| Strata | 72 | 0 |
| Splint and Rough Coals (16 ft. apart) | 4 | 0 |
| Strata | 100 | 0 |
| Haughliel Coals (sometimes "Parrot Coal") 16 in. to | 1 | 6 |
| Strata | 35 | 0 |

* The above series repose on the Lower Limestone group, con-

* Report on Coal suited to the Steam Navy, p. 9.

† "Geology of the East Lothian Coal Field," by Messrs. Howell, Geikie, and Young, 1866, p. 57.

sisting of three principal beds of limestone. These limestones form a broad zone, encircling the coal-field on the east and south-east; and underneath occur the calciferous sandstones, rich in its fauna and flora.

Fifeshire Coal-field.—Situated on the north side of the Firth of Forth, for nearly a distance of 30 miles, but with a varying width, possesses some important seams of coal, and some anthracite, valuable for household purposes, gas manufacture, iron smelting, and steam purposes. In this coal-field occur 29 coal seams, having an aggregate thickness of 120 feet. Nearly the whole of the seams enter the sea between Kirkaldy and East Wemyss, and many of these are of high quality for the purposes above enumerated.

The following analyses exhibit generally the constituents of the coals examined and extensively raised in the Fifeshire coal-field. The first analysis refers to the "Fordell Splint Coal," from the colliery of the same name. The seam varies from 4 to 4½ feet in thickness, and is raised from the "Splint seam," at a depth of from 50 to 80 fathoms from the surface. This coal is described as hard, bituminous, and lively in burning, and when broken divides into rhombic fragments; spots of pyrites sometimes occur, but not in any considerable quantity. The second analysis, the "Elgin Wallsend," raised in the Balmule Colliery, a steam coal, resembles much in appearance the Fordell Splint, is described as a caking splint coal of cubical texture, burning freely with a strong flame. The third is an analysis of "Splint Coal," raised at the Wellwood Colliery, and used for raising steam and iron smelting:—*

| Constituents. | FIFESHIRE COALS. | | |
|------------------------|-------------------------|----------------------------|--------------------------|
| | Fordell Splint Coal. | Balmule Elgin Wallsend. | Wellwood Splint Coal. |
| Carbon | 79·58 | 76·09 | 81·36 |
| Hydrogen | 5·50 | 5·22 | 6·28 |
| Nitrogen | 1·13 | 1·41 | 1·53 |
| Sulphur | 1·46 | 1·53 | 1·57 |
| Oxygen | 8·33 | 5·05 | 6·37 |
| Ash | 4·00 | 10·70 | 2·89 |
| Total | 100·00 | 100·00 | 100·00 |
| Yield of coke | 52·03 | 58·45 | 59·15 |
| Specific gravity . . . | 1·25 | 1·20 | 1·27 |

* Report on Coal suited to the Steam Navy, p. 9.

Clackmannanshire Coal-field.—This coal-field extends along the northern and eastern banks of the river Forth, and is in three divisions, separated by formidable faults. The southern portion is much exhausted; the middle area has long been, and still is, extensively worked, and the northern field is comparatively entire north of the river Devon. The following is a section of the coals, in descending order, at Old Sauchie :—*

| | Ft. | In. |
|---------------------------|-----|-----|
| Coal | 2 | 6 |
| Three-foot Coal | 3 | 0 |
| Upper Five-foot | 5 | 0 |
| Four-foot Coal | 4 | 0 |
| Nine-foot Coal | 9 | 0 |
| McNish Coal | 2 | 9 |
| Mosie Coal | 2 | 0 |
| Lower Five-foot | 5 | 0 |
| Splint Coal | 2 | 9 |
| Coalsnaughton | 4 | 6 |
| Total | 40 | 6 |

Ayrshire Coal-field.—This productive area is separated from the Clyde basin by the Dunlop Hills and rocks of trap of Devonian age. Much, however, of the minerals have been destroyed through the agency of intrusive, igneous masses and dykes of dolerite and basalt, which also interferes to a great extent with the prosecution of successful mining operations. The Girvan Valley, an important district, has an elongated coal-field about four miles long and half a mile broad, the greatest depth being probably 150 fathoms, embracing six seams of coal, of which much is already worked; these are :—

| | THICKNESS. | |
|-------------------------|------------|---------|
| | Ft. | Ft. In. |
| The Main Coal | 10 to | 12 0 |
| Little Coal | 3 „ | 4 0 |
| Cannel Coal | 3 „ | 5 0 |
| Coral Coal | | 3 6 |
| Craigie Coal | | 3 9 |
| Botten Coal | | 6 0 |

In the Dalmellington, Patna, and Littlemill districts, some extensive seams occur. At the Dalmellington Iron Works the Patna seams, three in number, and 21 feet thick, are chiefly used.

In the New Cumnock district some important seams are being wrought in a section at Colburn. There are nine seams, giving an aggregate thickness of 28 feet; and at Pathhead seven seams,

* Mr. John Geddes, M.E., Coal Commission Report, vol. i., page 76, 1871.

giving a thickness of 27 feet 11 inches. Other sections at Muirkirk and Lugar, important districts in the coal-field, give the following seams and thicknesses :—

| MUIRKIRK. | | LUGAR. | |
|---------------------------|-----------------------|-----------------------|-----------------------|
| | THICKNESS. Ft. In. | | THICKNESS. Ft. In. |
| Coke Yard Seam | 5 0 | Ell Coal | 3 0 |
| Ell Coal | 3 0 | Main Coal | 4 0 |
| Splint Coal | 2 4 | Coal | 3 6 |
| Seven-foot Coal | 8 0 | Main Coal | 4 0 |
| Nine-foot Coal | 9 4 | Coal | 2 4 |
| Soft Coal | 3 0 | Mussel Coal | 2 2 |
| Catchyburn Coal | 5 ft. to 9 0 | Coal | 2 7 |
| Macdonald Coal | 4 6 | Coal | 2 0 |

In the districts of Kilwinning, Dreghorn, and Kilmarnock, the section of coal is various ; at Kilwinning, nine seams, of a total thickness of 21 feet 9 inches ; at Dreghorn, 6 seams, 20 feet 7 inches ; and at Kilmarnock, nine seams, 28 feet 7 inches in thickness ; the Five-quarter coal, at Dreghorn, attaining a thickness of 4 feet 6 inches.

Of the coals of the Ayrshire coal-field, valuable alike for household purposes, for the manufacture of gas, and steam purposes, the annexed analyses of the coal raised at the Hurlford and Sker-rington collieries of Messrs. Gilmour & Co., and at the Eglinton Colliery of Mr. Archibald Kenneth, show the respective composition of the Main seam in each colliery, as follows :—

| Constituents. | Hurlford, &c. | Eglinton. |
|----------------------------|---------------|-----------|
| Carbon | 79·82 | 80·08 |
| Hydrogen | 5·82 | 6·50 |
| Nitrogen | ·94 | 1·55 |
| Sulphur | ·86 | 1·38 |
| Oxygen | 11·31 | 8·05 |
| Ash | 1·25 | 2·44 |
| Total | 100·00 | 100·00 |
| Yield of coke | 49·30 | 54·94 |
| Specific gravity | 1·241 | 1·25 |

Lesmahago Coal Basin, a detached area seven and a half miles from east to west and from north to south, belonging to the carboniferous limestone series. It is said that three-fourths of this area is stored with coal of second-class quality, giving, at

Ponfrich, an aggregate thickness of 53 feet, enclosed in a vertical section of 1,200 feet of strata. Several valuable seams of coal occur in this area, the coal being in good request, owing to its large yield of gas for illuminating purposes. Analyses of the Lesmahago and other Cannel coals will be found at page 259.

Other small areas of coal occur at Canobie, in Dumfriesshire; at Campbeltown, in Argyleshire; at Brora, in Sutherlandshire; and in the Isle of Skye, all of considerable importance in their respective districts.

The Brora coal-field appears to have been worked as far back as the year 1598, when the first pit was opened by the then Countess of Sutherland; the coal of the Brora area, it is understood, was extensively wrought, at an early period, chiefly in connection with salt manufacture, and was discontinued about the year 1832, probably because of its ceasing to be profitable after the duty was taken off salt. The coal of Brora is of oolitic age; the seam is 3 feet 6 inches thick, and it is generally regarded as the only deposit of the kind worked. It is a valuable coal in that northern district of Britain, and is found to be constituted as follows, the analysis being made from an average sample:—

RESULTS TABULATED.

| | |
|---------------------------|--------|
| Fixed carbon | 49·24 |
| Volatile matter | 26·50 |
| Sulphur | 6·40 |
| Moisture | 4·20 |
| Ash | 13·86 |
| | <hr/> |
| | 100·20 |

When coked, it yields 62·90 per cent., the ash contained in coke amounting to 21·71 per cent.; sulphur, 5·08 per cent.; specific gravity of coal, 1·38; and the approximate heating power, '685.

Production and Distribution of Coal.—The pages of the "Coal Commission Report" contain much interesting information, bearing on the early history of coal-mining in Scotland, of the Charters granted in successive reigns, from A.D. 1189, when the earliest record appears, of a grant to work coal to the Abbey of Newbattle by Sayer de Quinci, Earl of Winchester. Details are, however, absent showing the early development of the coal-fields

of Scotland. The earliest returns available, showing the number of collieries and the production of coal, commenced about the year 1854. Various estimates had appeared in previous years, prepared by experienced authorities conversant with the development of the coal-fields of Great Britain, but, at the best, they were but approximations. In the year 1854, Mr. Robert Williams, H. M. Inspector of Mines, made a careful inquiry, and found that 397 collieries were in active operation, winning coal, in that year, to the amount of 7,448,000 tons in Scotland. In the year 1855 there were 403 collieries, the output of coal amounting to 7,325,000 tons, showing a falling off, compared with the previous year, of 123,000 tons.

The great bulk of the production of 1855 was consumed in the numerous industries of Scotland. The blast furnaces reducing the ores of iron to a metallic state, consumed 2,152,800 tons; in the conversion of pig into malleable iron 367,200 tons were used; and in manufactures, steamboats, and the domestic consumption of Glasgow, 2,853,427 tons were employed, the remaining quantity, amounting to 1,951,573 tons, being distributed by railway and conveyed to ports of shipment for conveyance coastwise and for exportation, the former amounting to 530,971 tons, and the latter to 444,760 tons.

The coal-fields of Scotland are, for purposes of inspection, divided into an eastern and western division, the former under the inspection of Mr. Ralph Moore, and the latter under Mr. William Alexander. The following are the districts under the inspection of the above-named gentlemen, comprising coal areas in the shires named :—

EASTERN DIVISION.

Lanarkshire (East division).
Fifehire.
Clackmannanshire.
Haddingtonshire.
Edinburghshire.
Linlithgowshire.
Stirlingshire (East division).
Perthshire.
Sutherlandshire.

WESTERN DIVISION.

Lanarkshire (West division).
Ayrshire.
Stirlingshire (West division).
Dumbartonshire.
Renfrewshire.
Argyleshire.
Dumfriesshire.

Following the growth of the coal industries of Scotland, since the year 1855, the annexed abstract shows the number of collieries and the output of coal in each inspection district :—*

* Reports of H. M. Inspectors of Coal Mines.

| Year. | EASTERN DIVISION. | | WESTERN DIVISION. | |
|-------|-----------------------|------------|-----------------------|-----------|
| | Number of Collieries. | Coal. | Number of Collieries. | Coal. |
| | | Tons. | | Tons. |
| 1856 | 199 | 4,512,000 | 206 | 4,500,000 |
| 1857 | 210 | 4,598,000 | 215 | 5,613,473 |
| 1858 | 214 | 4,598,000 | 203 | 5,620,000 |
| 1859 | 219 | 4,750,000 | 194 | 5,530,000 |
| 1860 | 228 | 5,150,000 | 199 | 5,750,000 |
| 1861 | 226 | 5,225,500 | 198 | 5,855,000 |
| 1862 | 247 | 5,300,000 | 201 | 5,775,000 |
| 1863 | 270 | 5,250,500 | 212 | 5,850,000 |
| 1864 | 274 | 6,250,000 | 223 | 6,150,000 |
| 1865 | 274 | 6,400,000 | 223 | 6,250,000 |
| 1866 | 263 | 6,350,000 | 218 | 6,275,000 |
| 1867 | 263 | 7,897,368 | 218 | 6,228,575 |
| 1868 | 230 | 8,456,084 | 203 | 6,253,875 |
| 1869 | 211 | 7,879,500 | 201 | 6,537,650 |
| 1870 | 207 | 8,595,238 | 204 | 6,339,315 |
| 1871 | 216 | 8,883,926 | 204 | 6,564,365 |
| 1872 | 252 | 9,046,814 | 201 | 6,336,795 |
| 1873 | 260 | 10,142,039 | 239 | 6,715,733 |
| 1874 | 320 | 10,182,326 | 234 | 6,606,335 |
| 1875 | 334 | 11,419,619 | 232 | 7,177,888 |
| 1876 | 334 | 11,667,648 | 232 | 6,997,964 |
| 1877 | 305 | 11,452,373 | 222 | 6,867,701 |
| 1878 | 304 | 11,667,559 | 230 | 6,169,723 |
| 1879 | 361 | 11,300,567 | 312 | 6,169,360 |
| 1880 | 361 | 12,019,443 | 290 | 6,255,443 |

Summarising the above returns, the total coal produce of Scotland appears as follows in each year since 1855 :—

| Year. | Number of Collieries. | Coal. | Year. | Number of Collieries. | Coal. |
|-------|-----------------------|------------|-------|-----------------------|------------|
| | | Tons. | | | Tons. |
| 1855 | 383 | 7,325,000 | 1868 | 433 | 14,709,959 |
| 1856 | 405 | 9,012,000 | 1869 | 412 | 14,417,150 |
| 1857 | 425 | 10,211,473 | 1870 | 411 | 14,934,553 |
| 1858 | 417 | 10,218,000 | 1871 | 490 | 15,438,291 |
| 1859 | 413 | 10,300,000 | 1872 | 453 | 15,383,609 |
| 1860 | 427 | 10,900,000 | 1873 | 499 | 16,857,772 |
| 1861 | 424 | 11,081,000 | 1874 | 554 | 16,788,661 |
| 1862 | 448 | 11,076,000 | 1875 | 566 | 18,597,507 |
| 1863 | 482 | 11,100,500 | 1876 | 566 | 18,665,612 |
| 1864 | 497 | 12,400,000 | 1877 | 527 | 18,320,074 |
| 1865 | 497 | 12,650,000 | 1878 | 534 | 17,837,282 |
| 1866 | 481 | 12,625,000 | 1879 | 673 | 17,469,927 |
| 1867 | 481 | 14,125,943 | 1880 | 650 | 18,274,886 |

For comparison, it may be stated that the total amount of coal raised in Great Britain, in the year 1856, was 66,645,500 tons, increased to 84,042,698 tons in the year 1860; ten years later, 110,431,192 tons; and in the year 1880 to 146,969,409 tons, or 75 per cent. increase in a period of twenty years.

Of the coal raised in Scotland, in the last three years, the following table shows the quantities raised in each of the principal coal-producing districts:—

| Counties. | 1878. | 1879. | 1880. |
|------------------------------|-------------------|-------------------|-------------------|
| | Tons. | Tons. | Tons. |
| <i>The Western District—</i> | | | |
| Renfrew | 163,450 | 134,872 | 108,250 |
| Argyle | 105,596 | 107,111 | 113,411 |
| Ayr | 3,184,429 | 3,203,052 | 3,106,965 |
| Dumbarton . . . | 210,620 | 216,282 | 234,556 |
| West Lanark . . . | 2,253,660 | 2,250,504 | 2,399,840 |
| West Stirling . . . | 252,068 | 257,539 | 292,421 |
| <i>The Eastern District—</i> | | | |
| Clackmannan . . . | 273,213 | 271,664 | 268,090 |
| Edinburgh | 725,122 | 758,371 | 793,804 |
| Fife | 1,676,901 | 1,726,701 | 1,930,511 |
| Haddington | 221,639 | 233,276 | 243,302 |
| East Lanark | 7,683,595 | 7,135,416 | 7,627,159 |
| Linlithgow | 394,721 | 464,823 | 448,955 |
| East Stirling | 692,368 | 710,316 | 707,622 |
| Total | 17,837,282 | 17,469,927 | 18,274,886 |

In the eastern division of the coal-fields of Scotland, the Inspector in his report for the year 1880 gives some particulars showing the proportion of coal raised by the two methods of working coal in his district, namely, the “Long Wall” and “Stoop and Room;” and remarks, that taking the quantities raised by each method, there were 26 per cent. less accidents by the “Stoop and Room” than by the “Long Wall” system. The total output of the district in 1880 was 12,019,443 tons, of which quantity 5,884,296 tons were obtained by the “Long Wall,” and 6,185,147 tons by the “Stoop and Room” mode of working.*

Having thus far traced the output of the collieries in the eastern and western inspection districts, it will be interesting to summarise the returns and indicate the respective quantities produced in each county in Scotland in each of the above years, and, for comparison, the quantities raised in the year 1874; the details are as follows:—

* Reports of H. M. Inspectors of Mines, 1880, p. 192.

| Counties. | 1874. | 1878. | 1879. | 1880. |
|--|-------------|-------------|-------------|-------------|
| | Quantities. | Quantities. | Quantities. | Quantities. |
| | Tons. | Tons. | Tons. | Tons. |
| Lanarkshire . . | 9,461,692 | 9,937,255 | 9,385,920 | 10,026,999 |
| Ayrshire . . | 3,148,922 | 3,184,429 | 3,203,052 | 3,106,965 |
| Fife shire . . | 1,390,678 | 1,676,901 | 1,726,701 | 1,930,511 |
| Stirlingshire . | 948,664 | 944,436 | 967,855 | 1,000,043 |
| Edinburghshire | 567,998 | 725,122 | 758,371 | 793,804 |
| Linlithgowshire | 454,566 | 394,721 | 464,823 | 448,955 |
| Haddingtonshire | 193,964 | 221,639 | 233,276 | 243,302 |
| Dumbartonshire | 141,988 | 210,520 | 216,282 | 234,556 |
| Perth, Kinross, Clackmannan and Suther- landshire } | 197,774 | 273,213 | 271,664 | 268,090 |
| Benfrewshire . | 181,678 | 163,450 | 134,872 | 108,250 |
| Argyle and Dumfries . } | 100,749 | 105,596 | 107,111 | 113,411 |
| Total . . | 16,788,661 | 17,837,282 | 17,469,927 | 18,274,886 |

Mr. Ralph Moore, in his "Reports of the Eastern District of Scotland," gives some very interesting facts concerning the collieries in his inspection, and the production of coal, not only of the large companies, but also of individual firms. These facts appear in the annexed figures for the years 1874, 1878, and 1879, showing the number of mines of all kinds, shafts, collieries, pits, and companies working coal under the Coal Mines Regulation Acts, 1872, and the Metalliferous Mines Regulation Acts, 1875.

| | 1874. | 1878. | 1879. |
|-----------------------------|-------|-------|-------|
| | Nos. | Nos. | Nos. |
| Mines of all kinds | 366 | 348 | 361 |
| Shafts of all kinds | 744 | 695 | 686 |
| Collieries | 336 | 293 | 305 |
| Coal pits | 660 | 611 | 601 |
| Companies working Coal . . | 230 | 191 | 191 |

From these reports, the number of companies working coal shows that the collieries are gradually increasing in extent, and becoming larger. This is clearly apparent in the Inspector's returns for the years 1875 and 1876, which were as follows, showing that in the last-named year 25 companies, in the eastern district, raised upwards of 50 per cent. of the total production :—

| 1876. | TONS. | 1875. | TONS. |
|--------------------|-----------|--------------------|-----------|
| 1 firm raised over | 670,000 | 1 firm raised over | 630,000 |
| 1 " " | 410,000 | 1 " " | 440,000 |
| 3 firms " | 1,050,000 | 1 " " | 340,000 |
| 2 " " | 500,000 | 3 firms " | 900,000 |
| 1 firm " | 300,000 | 2 " " | 500,000 |
| 5 firms " | 1,000,000 | 4 " " | 800,000 |
| 7 " " | 1,050,000 | 7 " " | 1,050,000 |
| 5 " " | 600,000 | 14 " " | 1,680,000 |
| 22 " " | 1,760,000 | 18 " " | 1,440,000 |
| 34 " " | 1,380,000 | 23 " " | 900,000 |
| 135 " " | 5,900,000 | 144 " " | 5,760,000 |

The greatest quantity of coal, at this period, put out of a single shaft, was, in 1876, 136,000 tons, compared with 145,000 tons in the previous year, while the greatest quantity of coal put out of a pair of shafts in 1876 was 212,000 tons, compared with 210,000 tons in the previous year. In the year 1879 and previous year, the details under the same head were as follows :—

| 1879. | TONS. | 1878. | TONS. |
|---------------------|----------------|--------------------|----------------|
| 2 firms raised over | 400,000 each | 1 firm raised over | 480,000 |
| 1 firm " | 350,000 | 1 " " | 450,000 |
| 2 firms " | 300,000 each | 2 firms " | 350,000 each |
| 2 " " | 250,000 " | 1 firm " | 300,000 |
| 5 " " | 200,000 " | 2 firms " | 250,000 each |
| 8 " " | 150,000 " | 5 " " | 200,000 " |
| 7 " " | 120,000 " | 8 " " | 150,000 " |
| 18 " " | 80,000 " | 9 " " | 120,000 " |
| 39 " " | 40,000 " | 19 " " | 80,000 " |
| 107 " " | under 40,000 " | 37 " " | 40,000 " |
| | | 107 " " | under 40,000 " |

Distribution of Coal.—Very full and complete information, showing the distribution of coal, sent coastwise and exported to foreign countries, appears in the Parliamentary Returns (annual) of coal, cinders, and culm. From these returns the following facts have been prepared, showing the quantities thus distributed before the year 1800 :—

| Year. | Coastwise. | Exported. | Total. |
|-------|------------|-----------|---------|
| | Tons. | Tons. | Tons. |
| 1790 | 74,925 | 33,416 | 108,341 |
| 1791 | 82,446 | 36,679 | 119,125 |
| 1792 | 71,073 | 29,752 | 100,825 |
| 1793 | 67,396 | 20,062 | 87,458 |
| 1794 | 61,687 | 30,052 | 91,739 |
| 1795 | 56,014 | 20,107 | 76,121 |
| 1796 | 71,891 | 31,115 | 103,006 |
| 1797 | 52,745 | 19,431 | 72,176 |
| 1798 | 58,923 | 24,849 | 83,772 |
| 1799 | 52,029 | 11,838 | 66,863 |

The principal ports of shipment on the western coast of Scotland are Glasgow, Ayr, and Greenock. Irvine was also a shipping port of considerable importance from the year 1833 to the year 1864, since which latter year the port has disappeared from the list as a port of shipment. In the annexed abstract appear the aggregate quantities of coal shipped coastwise and exported from the western ports of Scotland in each of the years named:—

WESTERN PORTS OF SCOTLAND.

| Year. | Glasgow. | Irvine. | Ayr. | Greenock. |
|-------|----------|----------|---------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| 1830 | 3,167 | 5,847 | ... | 12,102 |
| 1835 | 85,382 | 150,127 | 54,021 | 14,533 |
| 1840 | 112,245 | 272,102 | 91,638 | 28,094 |
| 1845 | 96,351 | 215,383 | 81,892 | 23,886 |
| 1850 | 108,306 | 264,087 | 72,264 | 21,382 |
| 1855 | 136,818 | 312,882 | 64,426 | 27,300 |
| 1860 | 159,989 | 497,118 | 66,863 | 63,805 |
| 1865 | 205,364 | *280,616 | 126,597 | 92,684 |
| 1870 | 314,758 | ... | 102,668 | 145,863 |
| 1875 | 599,706 | ... | 279,499 | 248,368 |
| 1876 | 548,355 | ... | 285,014 | 178,772 |
| 1877 | 586,379 | ... | 332,686 | 162,320 |
| 1878 | 566,720 | ... | 384,846 | 150,254 |
| 1879 | 528,105 | ... | 362,530 | 137,435 |
| 1880 | 484,023 | ... | 311,660 | 123,931 |

Turning to the ports on the eastern coast of Scotland, the more important of which are Grangemouth, Borrowstowness, Kirkcaldy, and Leith, all of which have, in a greater or less degree, contributed to the distribution, coastwise and to foreign countries, the following figures show the quantities sent away in each of the years named. The other ports shipping coal on the eastern coast are those of Dundee, Granton, and Alloa, while on the western coast, in recent years, Troon and Ardrossan have become important ports of shipment. The two last-named ports shipped the annexed quantities in the four years ending 1880:—

| Year. | Troon. | Ardrossan. |
|-------|---------|------------|
| | Tons. | Tons. |
| 1877 | 551,045 | 247,005 |
| 1878 | 457,391 | 238,236 |
| 1879 | 502,476 | 287,867 |
| 1880 | 433,783 | 227,236 |

* Return for the year 1864.

EASTERN PORTS OF SCOTLAND.

| Year. | Grangemouth. | Borrowstowness. | Kirkcaldy. | Leith. |
|-------|--------------|-----------------|------------|---------|
| | Tons. | Tons. | Tons. | Tons. |
| 1830 | 1,670 | 15,344 | 2,550 | 2,872 |
| 1835 | 81,784 | 134,256 | 51,606 | 51,285 |
| 1840 | 92,487 | 169,947 | 63,137 | 42,959 |
| 1845 | 16,953 | 141,311 | 65,884 | 18,552 |
| 1850 | 26,373 | 116,991 | 84,943 | 13,843 |
| 1855 | 55,416 | 146,978 | 67,731 | 40,254 |
| 1860 | 64,208 | 276,327 | 117,597 | 42,289 |
| 1865 | 121,155 | 250,394 | 180,561 | 104,916 |
| 1870 | 111,490 | 293,308 | 264,971 | 117,494 |
| 1875 | 199,544 | 347,033 | 323,701 | 375,807 |
| 1876 | 207,051 | 386,599 | 342,302 | 336,611 |
| 1877 | 179,853 | 270,327 | 362,008 | 309,131 |
| 1878 | 174,526 | 277,249 | 431,103 | 201,276 |
| 1879 | 142,388 | 298,080 | 551,529 | 196,132 |
| 1880 | 126,883 | 325,153 | 545,925 | 215,404 |

The above figures indicate, in a decided manner, the development and distribution of the production of the collieries of Scotland during the past half century. Other ports, in late years, have contributed to increase the distribution of the coal, and in the following abstract, prepared from official returns, the total quantities of coal sent coastwise and to foreign countries appear. The same years as those in the two previous summaries have been selected for comparison, and side by side, as far as possible, the production of coal in Scotland has been given :—

| Year. | Coastwise. | Exported. | Total. | Produce of Scotland. |
|-------|------------|-----------|-----------|----------------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1830 | ... | 47,080 | ... | ... |
| 1835 | 557,043 | 71,671 | 628,714 | ... |
| 1840 | 723,534 | 156,792 | 880,326 | ... |
| 1845 | 530,388 | 465,173 | 1,095,561 | ... |
| 1850 | 463,123 | 336,453 | 799,576 | ... |
| 1855 | 530,578 | 436,888 | 967,466 | 7,325,000 |
| 1860 | 743,214 | 653,432 | 1,396,646 | 10,900,000 |
| 1865 | 863,291 | 983,255 | 1,846,546 | 12,650,000 |
| 1870 | 1,061,586 | 1,338,127 | 2,399,713 | 14,934,553 |
| 1875 | 1,408,352 | 2,283,745 | 3,692,097 | 18,597,507 |
| 1876 | 1,307,296 | 2,335,660 | 3,642,956 | 18,665,612 |
| 1877 | 1,278,703 | 2,063,770 | 3,342,473 | 18,320,074 |
| 1878 | 1,325,617 | 1,918,954 | 3,244,571 | 17,837,282 |
| 1879 | 1,422,073 | 2,012,783 | 3,434,858 | 17,469,927 |
| 1880 | 1,215,816 | 1,935,333 | 3,151,149 | 18,274,886 |

In the last-named year, the total quantity of coal sent coastwise in the United Kingdom was 12,061,183 tons; that exported

to foreign countries, 16,442,296 tons; the declared value of the exported coal amounting to £7,206,799; the total output of the collieries of the United Kingdom amounting to 194,008,228 tons, an increase of 1,400,862 tons on the previous year.

Railway Distribution.—In the early returns of coal conveyed by railway in Scotland, all minerals, comprising coal, ironstone, iron ore, limestone, &c., were included. In the year 1854 the following statement shows approximately the quantities of coal carried by the Caledonian Railway, received at the stations named, and amounting to 251,932 tons; the total quantity of all kinds of minerals, including coals, forwarded by the system in the same year, being set down at 404,168 tons. The details of coal carried appear as under:—

| STATIONS. | TONS. |
|------------------------|----------------|
| Edinburgh | 24,034 |
| Glasgow | 54,466 |
| Greenock | 54,024 |
| Carlisle | 4,751 |
| Barrhead | 49,163 |
| Pollockshaws | 10,982 |
| Holytown | 42,414 |
| Greenhill | 12,098 |
| Total | <u>251,932</u> |

It is not again until the year 1858 that returns are available; we then have the distribution of coal in Scotland for that year. The annexed statement shows the distribution under the respective heads; the total produce of Scotland in that year being 8,926,249 tons:—

| HOW DISTRIBUTED. | TONS. |
|---|------------------|
| Consumed in ironworks | 3,750,200 |
| Exported coastwise | 565,672 |
| Exported to foreign countries | 543,377 |
| Consumed in manufactories | 1,750,000 |
| Employed in steam vessels | 602,000 |
| Employed in locomotives and railways | 465,000 |
| Colliery consumption and domestic use | 1,250,000 |
| Total | <u>8,926,249</u> |

In the year 1867, and since, the coals carried by the several railway systems traversing the coal-fields have been regularly published; in this year the quantities carried were as follows:—

| RAILWAYS. | TONS. |
|-------------------------------------|-----------|
| Caledonian | 3,193,960 |
| North British | 2,739,940 |
| Glasgow and South Western | 1,738,787 |

Of the coal carried by the Caledonian railways, the coal-fields of Lanarkshire contributed 3,193,035 tons; Stirlingshire, 17,444 tons; and Renfrewshire, 48,481 tons; while of the coal conveyed by the North British railways, the great bulk was contributed by the Lanarkshire and Fifeshire coal-fields. Of the coal carried by the Glasgow and South-Western Railway, 897,999 tons were taken to the coast for shipment; 340,912 tons deposited at the several stations on the line; and 499,976 tons conveyed to ironworks.

In subsequent years, since 1869, the quantities by the several railways appear as follows :—

| Year. | Caledonian. | North British. | Glasgow and South Western. |
|-------|-------------|----------------|----------------------------|
| | Tons. | Tons. | Tons. |
| 1869 | 4,023,209 | 3,907,064 | 1,690,207 |
| 1870 | 4,648,665 | 3,197,001 | 1,841,571 |
| 1871 | 5,014,894 | 3,600,618 | 1,937,177 |
| 1872 | 5,229,093 | 3,797,249 | 2,084,894 |
| 1873 | 5,305,060 | 4,016,351 | 2,163,263 |
| 1874 | 5,443,525 | 3,841,856 | 2,042,358 |
| 1875 | 5,942,943 | 4,558,098 | 2,335,294 |
| 1876 | 6,106,495 | 4,693,068 | 2,225,318 |
| 1877 | 6,646,254 | 4,682,128 | 2,446,585 |
| 1878 | 6,319,498 | 4,615,407 | 2,097,825 |
| 1879 | 5,983,056 | 5,375,494 | 2,537,576 |
| 1880 | 6,142,584 | 5,753,779 | 2,493,192 |

Comparing the above returns of the Caledonian Railway for the years 1870, 1878, and 1880, the annexed abstract will show the respective increase in each of the coal-producing districts traversed by this railway :—

| Coal Fields. | 1870. | 1878. | 1880. |
|--|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| Lanarkshire | 4,400,585 | 5,988,915 | 5,736,794 |
| Stirlingshire | 17,732 | 61,545 | 81,599 |
| Edinburghshire | 173,991 | 88,135 | 122,016 |
| Renfrewshire | 566 | 9,508 | 1,237 |
| Ayrshire | ... | 73,175 | 74,512 |
| Linlithgowshire | ... | 65,048 | 86,770 |
| Seaborne coal shipped inland | 55,791 | 33,172 | 39,656 |
| Total | 4,648,665 | 6,319,498 | 6,142,584 |

The North British Railway exhibits in each of the same years an increase, though in a lesser degree than that of the Caledonian system. The details are as follows :—

| Coal Districts. | 1870. | 1878. | 1880. |
|---|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| Canobie. | 54,828 | 38,928 | 42,627 |
| Fifeshire | 944,483 | 1,339,225 | 1,639,094 |
| Monklands | 1,636,299 | 2,556,363 | 3,252,810 |
| Plashtets | 46,934 | 20,294 | 12,962 |
| The Lothians. | 428,183 | 564,338 | 720,589 |
| Other Collieries on } Border Section . } | 86,274 | 96,259 | 85,697 |
| Total coals carried | 3,197,001 | 4,615,407 | 5,753,779 |

Following up the comparison in the distribution by the Glasgow and South Western Railway, the annexed statement shows the quantities retained for home use, and sent for shipment, in each year since 1869 :—

| Year. | For Home Use. | For Shipment. |
|-------|---------------|---------------|
| | Tons. | Tons. |
| 1869 | 848,779 | 841,428 |
| 1870 | 944,170 | 897,401 |
| 1871 | 1,040,742 | 896,435 |
| 1872 | 1,095,281 | 989,613 |
| 1873 | 1,190,046 | 973,217 |
| 1874 | 1,129,806 | 912,552 |
| 1875 | 1,397,331 | 937,963 |
| 1876 | 1,308,305 | 917,013 |
| 1877 | 1,152,253 | 1,294,332 |
| 1878 | 939,758 | 1,158,027 |
| 1879 | 892,300 | 1,645,276 |
| 1880 | 927,537 | 1,565,655 |

Prices of Coal and Cost of Production.—In the western district of Scotland, in the year 1860, the average cost of getting a ton of coal did not exceed 2s. 8d. This did not include value of property, rent, and other charges. The average price per ton of coal at bank, in the same year, did not exceed 4s.; cartage, 6d. per ton per mile; railway charges, for short distances, 1s. per ton for six miles, and 1d. per mile for longer distances; the average price of coal in Glasgow at this period being about 8s. per ton. Since the “Coal Mines Regulation Act, 1872,” has been in operation, the annual reports of the inspectors give many

valuable details on both points, more especially prices and wages. Mr. Ralph Moore, in charge of the eastern district of Scotland, in his Report for the year ending 1874, states that in the two preceding years there were periods of great prosperity in the mining industries. A decline, however, set in about the beginning of 1874, continuing to the end of the year, when prices reached nearly an ordinary rate. Thus the market price of screened coals in Glasgow, in December, 1873, was 16*s.* per ton, compared with 8*s.* 9*d.* per ton in December, 1874; dross, 6*s.* per ton, compared with 1*s.* 6*d.* per ton; miners' wages, in 1873, varying from 9*s.* to 10*s.* per day, compared with 5*s.* to 6*s.* per day in 1874; while the cost of hewing coal in 1873, in December and January, 1874, was 3*s.* 4*d.* per ton, declining to 1*s.* 10*d.* per ton in December of the same year.

Prices in 1876 were somewhat lower, coals, in Glasgow, being quoted at from 6*s.* 8*d.* to 7*s.* per ton; wages at this period being 4*s.* 6*d.* per day. Mr. Moore, in his Report for 1876, gives some interesting details of the wages of two miners in Lanarkshire, the one of an average man, the other of a first-class man.

The first worked 299 days in the year, and sent 1,026 tons of coal to bank, receiving wages amounting to £71 5*s.* 5*d.*, exclusive of deductions, giving an average rate of wages of 4*s.* 9*d.* per day. The first-class miner worked 300 days, sending 1,150 tons of coal to bank, receiving £88 13*s.* 3*d.* wages, also exclusive of deductions, giving an average rate of wages of 5*s.* 11*d.* per day.

Notwithstanding the steady decline of prices and wages, the production of coal has been steadily maintained. In the year 1878 the highest price of Ell or household coal, free on board at Glasgow, was 9*s.* 3½*d.* per ton; splint coal, 8*s.*; main coal, 7*s.* 4*d.*; the lowest prices being 6*s.*, 6*s.* 6*d.*, and 5*s.* 6*d.* per ton respectively. Comparing with prices in 1880, highest of Ell coal, per ton, 9*s.* 0*d.*; splint coal, 9*s.* 0*d.*; and main coal, 8*s.* 3*d.* per ton; the lowest prices being 6*s.* 9*d.* and 5*s.* 9*d.* These prices include the railway dues. The actual prices realised at the pit's mouth would be about 2*s.* 6*d.* per ton less than the above quotations.

Miners' wages in 1878, in the beginning of the year, were nominally 4*s.* 6*d.* per day, falling, as the year advanced, to 3*s.* 9*d.* and 3*s.* 6*d.* per day, while in 1879 the average wages varied from 3*s.* 3*d.* to 3*s.* 9*d.* per day.

In the annexed summary appears the average rate per day of miners' wages in each year since 1855 :—*

| Year. | Miners' Wages. | Year. | Miners' Wages. |
|-------|---------------------|-------|---------------------|
| | <i>s.</i> <i>d.</i> | | <i>s.</i> <i>d.</i> |
| 1855 | 4 4 | 1867 | 4 9 |
| 1856 | 4 3 | 1868 | 3 9 |
| 1857 | 4 0 | 1869 | 3 9 |
| 1858 | 3 0 | 1870 | 4 0 |
| 1859 | 3 3 | 1871 | 4 6 |
| 1860 | 3 6 | 1872 | 7 3 |
| 1861 | 3 0 | 1873 | 8 6 |
| 1862 | 3 6 | 1874 | 6 6 |
| 1863 | 3 6 | 1875 | 5 0 |
| 1864 | 4 0 | 1876 | 4 6 |
| 1865 | 4 6 | 1877 | 4 3 |
| 1866 | 5 6 | 1878 | 3 3 |

Population employed in Coal-mining.—Previous to the year 1864, the information on this subject is more or less of an approximate character. In the year 1861, however, the Census returns show that in the eastern district of Scotland 18,091 persons were employed, and in the western district, in the same year, 17,795 persons, or a total of 35,886 persons employed in the collieries then in operation. In 1864, and subsequent years, the total number of male persons employed in the collieries of Scotland were as follows; † side by side, the total of coal raised in each year is given, and the average quantity raised per man :—

| Year. | PERSONS EMPLOYED. | | | Coal Raised. | Average per Man. |
|-------|-------------------|----------|--------|--------------|------------------|
| | Eastern. | Western. | Total. | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1864 | 21,150 | 18,073 | 39,223 | 12,700,000 | 323 |
| 1865 | 21,150 | 18,375 | 39,525 | 12,800,000 | 324 |
| 1866 | 21,200 | 20,046 | 41,246 | 12,034,638 | 292 |
| 1867 | 29,000 | 21,075 | 50,075 | 14,125,943 | 282 |
| 1868 | 29,000 | 21,160 | 50,160 | 14,709,959 | 293 |
| 1869 | 28,000 | 20,007 | 48,007 | 14,637,043 | 305 |
| 1870 | 27,330 | 19,654 | 46,984 | 14,934,553 | 317 |
| 1871 | 27,300 | 19,561 | 46,861 | 15,438,291 | 329 |
| 1872 | 30,000 | 20,639 | 50,639 | 15,383,609 | 303 |

Since the passing of the “Coal Mines Regulation Act, 1872,” which came into operation the following year, the numbers of

* Messrs. James Watson & Co., Glasgow.

† Returns of H.M. Inspectors of Coal Mines.

persons employed above-ground and under ground are separately given, distinguishing those engaged in coal mines from those employed in ironstone and shale workings. The numbers of persons working in coal mines, in the two districts of Scotland were as follows, with the total output of coal, and the average output per man in each of the same years :—

| Year. | EASTERN. | | WESTERN. | | Total. | Coal Raised. | Average per Man. |
|-------|---------------|---------------|---------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 29,880 | 5,854 | 19,365 | 3,426 | 58,525 | 16,857,772 | 288 |
| 1874 | 31,294 | 6,254 | 19,020 | 3,600 | 60,168 | 16,788,661 | 278 |
| 1875 | 29,321 | 6,080 | 17,507 | 3,489 | 56,397 | 18,597,507 | 330 |
| 1876 | 28,765 | 6,139 | 16,342 | 3,294 | 54,540 | 18,665,612 | 342 |
| 1877 | 27,422 | 5,798 | 15,516 | 3,332 | 52,068 | 18,320,074 | 351 |
| 1878 | 28,616 | 5,802 | 14,534 | 2,913 | 51,865 | 17,837,282 | 344 |
| 1879 | 29,289 | 5,831 | 14,899 | 2,812 | 52,831 | 17,469,927 | 330 |
| 1880 | 29,559 | 5,980 | 14,703 | 2,888 | 53,130 | 18,274,886 | 344 |

The returns of the number of persons employed in the coal mines of Scotland, in 1879, show an increase of 766 over 1878, although the quantity of coal produced shows a decrease of 367,355 tons. While comparing the average produce per man, an increase is shown from 1873 to 1877, since which date a falling off appears, due to strikes and restriction of output on the part of the miners. The respective ages of all persons employed in coal-mining in Scotland, in 1879, were as under :—*

| All Ages. | EASTERN. | | WESTERN. | | Total. |
|---------------------|---------------|---------------|---------------|---------------|--------|
| | Under Ground. | Above Ground. | Under Ground. | Above Ground. | |
| | Nos. | Nos. | Nos. | Nos. | Nos. |
| From 12 to 13 . . . | 224 | 2 | 119 | ... | 345 |
| „ 13 to 16 . . . | 2,973 | 351 | 1,498 | 156 | 4,978 |
| „ 13 to 16 . . . | ... | 81† | ... | 9† | 90† |
| Above 16 . . . | 26,092 | 4,847 | 13,282 | 2,606 | 46,827 |
| „ 16 . . . | ... | 550† | ... | 41† | 591 |
| Total . . . | 29,289 | 5,831 | 14,899 | 2,812 | 52,831 |

Resources and probable Duration of the Scotch Coal-fields.—Referring to the labours of the Royal Coal Commission, appointed in the year 1866 “ to investigate the probable quantity of

* H.M. Inspectors of Coal Mines Report.

† Females.

coal contained in the coal-fields of the United Kingdom, and to report upon the quantity of such coal which may be reasonably expected to be available for use," we have the following summary of results, showing the quantity of coal available for future use in the coal-fields of Scotland in 1870 :—*

SUMMARY.

| | TONS. |
|----------------------------|----------------------|
| Edinburgh | 2,153,703,360 |
| Lanarkshire | 2,044,090,216 |
| Fifeshire | 1,098,402,895 |
| Ayrshire | 1,785,397,089 |
| East Lothian | 86,849,880 |
| Firth of Forth | 1,800,000,000 |
| Dumfriesshire | 358,173,995 |
| West Lothian | 127,621,800 |
| Perthshire | 109,895,040 |
| Stirlingshire | 106,475,436 |
| Clackmannanshire | 87,563,494 |
| Dumbartonshire | 48,618,320 |
| Renfrewshire | 25,881,285 |
| Argyleshire | 7,223,120 |
| Sutherlandshire | 3,500,000 |
| Roxburghshire | 70,000 |
| Total | <u>9,843,465,930</u> |

The total here arrived at is the quantity available to a depth of 3,000 feet. Taking the production of the Scotch coal-fields in the same year, amounting to 14,934,553 tons, and assuming the same annual average output, the coal-fields would not be exhausted for 660 years.

The total quantity of coal raised in Scotland during the ten years ending 1879 amounts to 174,293,288 tons; this, deducted from the original estimate of 1870, leaves 9,669,172,642 tons, which, at the average production of the past ten years (17,429,328 tons) would afford supplies for the next 555 years, a period short by 105 years of the estimated duration from the year 1870.

* Mr. John Geddes' Report, vol. i. "Coal Commission Report," p. 71.

CHAPTER XIX.

THE COAL-FIELDS OF IRELAND.

Description—Northern (Bituminous) Group—Counties of Leitrim, Tyrone, and Antrim—Analyses of Coal—Southern (Anthracitic) Group, Leinster and Munster—Analyses of Coal—Production of Coal—Population employed in Coal Mining—Resources of Coal-fields.

The Coal-fields of Ireland.—The coal deposits of Ireland are divided by Professor Hull into two groups, the line of demarcation being drawn from Galway Bay on the west to Dublin Bay on the east. The coal-fields north of this line produce coal of a bituminous kind, those of the southern area being anthracitic in character.

The northern coal-fields are those of Leitrim in Connaught, and Tyrone and Antrim in Ulster. The southern coal-fields extend through the counties of Clare, Limerick, and Cork, stretching both to the north and south of the estuary of the river Shannon, and the Leinster coal-field, the most important in the south of Ireland, occupying an extensive tract in the Queen's County, Kilkenny, and Tipperary.

But little can be said relative to the coal of Ireland as compared with the richer deposits of England and Scotland. The time was when Ireland was two-thirds covered with coal-beds; now only a few patches or outliers are left as evidences of former wealth, nearly all the coal measures having been denuded from the limestone and other "bases," leaving the great central limestone plain of Ireland beneath the drift, a now coal-less tract. The coal-fields already named being all that remains of what was once a widely-spread and extensive formation, the lower portion only being left. The total production of coal in Ireland in 1880 was but 133,702 tons, the greater proportion of which was anthracitic, compared with 128,560,821 tons in England and Wales, and 18,274,886 tons in Scotland.

The output of coal and ironstone in Ireland being so limited, a general sketch of the more important areas in which they occur,

and of the seams and bands of ironstone wrought, together with analyses, will here suffice, referring our readers to the authors and their works, which treat in detail of the mineral resources of Ireland.*

Northern Group of Coal-fields.—The bituminous coals, as previously stated, are found in the northern group of the coal-fields of Ireland; of these the several tracts of the Leitrim coal-fields are of considerable importance, those of Aughabehy, Arigna, and the coal-basin of Altygowlan, being the most important, the last-named coal-field being separated from the former by the river Arigna, and both coal-fields lying to the west of Loch Allen. The general succession of strata on this district is as follows:—

Lower Coal Measures.
Millstone Grit.
Yoredale Beds.
Carboniferous Limestone.

In a section of strata at Kilronan, some two miles south of Aughabehy, in the lower coal measures, occur three seams of coal, one of which, 18 inches thick, known as the "Top Seam," is most valued. Towards the top of the series of coal measures of a maximum thickness of 453 feet, shale occurs, varying in thickness from 100 to 200 feet, and in this shale are found numerous bands of ironstone of a similar kind to that found amongst the Yoredale beds below.

In a section of strata sunk at Arigna to a depth of 111 feet, when the main seam of coal, 2 feet 6 inches thick, was reached, the annexed shows the rocks passed through, with their respective thicknesses, the iron ore here being found within 3 feet of the surface.

SECTION OF STRATA AT ARIGNA COLLIERIES.†

| | Ft. | In. |
|---------------------------|-----|-----|
| Surface | ... | ... |
| Bed of iron ore | ... | ... |
| Deep bog | 15 | 0 |
| Gravel | 30 | 0 |
| Slate | 27 | 0 |
| Rock | 24 | 0 |
| Slate | 15 | 0 |
| Coal seam | 2 | 6 |

* "Industrial Resources of Ireland," by Sir Robert Kane, M.D., 1844. Second Edition; "Report on the Connaught Coal-fields (Arigna) Districts," by Sir Richard Griffiths, presented to the Royal Dublin Society, 1818.

† By W. J. Hughes, Esq., C.E., deposited in Mining Record Office. Museum of Practical Geology.

Analyses of the Coal.—Sir Robert Kane, who has examined several varieties of coal raised in this and other districts in Ireland, describes the Aughabehy coal as follows:—"A rich black coal, easily broken. Its specific gravity, 1·274. When heated it gives off a good deal of inflammable gas, and leaves a light, porous, grey, coherent coke." Another, the "Rover" Coal, is thus referred to:—"This coal is rather brown in aspect, and has a remarkable tendency to split into cubical fragments. The specific gravity is 1·287. When ignited it gives off gas, but does not froth. Its coke is porous, slightly coherent. It contains less foreign matter than any of the other kinds." The chemical composition of these coals is as follows :—*

RESULTS TABULATED.

| Constituents. | Aughabehy. | Rover. |
|--------------------|------------|--------|
| Carbon | 79·69 | 81·04 |
| Hydrogen | 6·24 | 4·91 |
| Oxygen | 3·32 | 6·64 |
| Ash | 10·75 | 7·41 |
| | 100·00 | 100·00 |

It is thus seen that the Aughabehy is a much more bituminous coal than the Rover, which approaches nearer in its character to the anthracites of the south.

The Tyrone Coal-field.—Also producing bituminous coal, is situated north of the town of Dungannon in the county Tyrone, the village of Coal Island occupying the centre of the coal-field, a smaller district, the Annahone, having an area of above 320 acres. Mr. E. T. Hardman, of the Geological Survey of Ireland, who has examined this coal-field, observes, that although occupying but a small area, the coal measures are about 2000 feet thick, and contain from 22 to 24 seams, all of them of fair and some of them of excellent quality, varying in thickness from 10 inches to 9 feet.

Mr. Hardman gives the following section, showing the more important coals :—

* "Industrial Resources of Ireland," second edition, 1845, p. 24.

TABLE OF THE COALS AT PRESENT BEING WORKED.

Dungannon Coal Field.

| | | Ft. | In. |
|---|---|-----|---------|
| <i>Middle Coal Measures</i> (Coal Island series) | Annagher Coal | 9 | 0 |
| | Bone Coal | 2 | 10 |
| | Shining Seam | 3 | 0 |
| | Brackaville Coal | 5 | 0 |
| | Gortnaskea Coal (with 22 in. Cannel) . | 6 | 0 |
| | Beltiboy Coal | 3 | 0 |
| | Derry Coal | 3 | 6 to 5 |
| | Yard Coal | 3 | 0 |
| | Position uncertain . Greenagh Coal (with 14 in. Cannel) . | 4 | 6 |
| <i>Lower Coal Measures</i> (Drumglass series) | Main Coal of Drumglass . | 4 | 10 to 6 |
| | Lower „ „ . | 1 | 6 „ 2 |

Mr. Hardman accompanies his paper by a series of analyses of the following seams :—*

LOWER COAL MEASURES.

- No. 1. Main Coal or Drumglass Coal, Lurganboy (Top).
 „ 2. Main Coal, Lurganboy (Bottom).
 „ 3. Greenagh Soft Coal.
 „ 4. Greenagh Cannel Coal.

MIDDLE COAL MEASURES.

- No. 5. Derry Coal (Annagher Coal Island).
 „ 6. Beltiboy Coal, Gortnaskea.
 „ 7. Gortnaskea Coal.
 „ 8. Annagher Coal (Brackaville).

ANALYSES OF THE COALS OF THE DUNGANNON COAL-FIELD.

| Constituents | No. 1. | No. 2. | No. 3. | No. 4. | No. 5. | No. 6. | No. 8. |
|-----------------------|-----------|--------|--------|--------|--------|--------|--------|
| Volatile matter . . . | 48·00 | 37·19 | 43·40 | 52·87 | 26·43 | 49·40 | 45·62 |
| Coke { Fixed Carbon . | 47·43 | 51·53 | 39·80 | 34·18 | 55·57 | 48·17 | 52·46 |
| | Ash . . . | 4·57 | 11·28 | 16·80 | 12·95 | 18·00 | 2·43 |
| | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 |
| Water at 212° F. . . | 2·49 | 5·72 | 7·46 | 3·20 | .. | 4·30 | 9·89 |
| Sulphur | 2·90 | 1·65 | 1·94 | 1·94 | .. | 1·52 | 2·66 |
| Ash in Coke | 9·05 | 17·95 | 21·30 | 30·02 | 24·65 | 4·86 | 3·55 |
| Specific gravity . . | 1·295 | 1·385 | 1·452 | 1·396 | 1·499 | 1·266 | 1·250 |

The analysis of the Gortnaskea coal (No. 7) was only a partial one. The seam is six feet thick, including 22 inches of cannel at the top, the cannel giving 4·06 of ash, its specific gravity being 1·292. It is remarked of this coal that it is rare to find a cannel with such a small percentage of ash.

* "Proceedings of the Royal Irish Academy." Second Series, vol. ii., p. 529.

The above analyses give a very fair idea of the character of the coals of the Dungannon coal-field; and it will be seen that many of these bear favourable comparison with the best English coal in point of purity and heating power. They are all highly bituminous, and yield such a quantity of gaseous matter, that Mr. Hardman considers that any of them except the Derry Coal might be used with great advantage in Ireland for gas manufacture, with profit both to the colliery proprietor and the gas company.

The heating power of these coals is extremely high; 10 to 11 lbs. of water evaporated is considered very good work for 1 lb. of coal; nearly all the above give over 12 lbs., the best of them nearly 13 lbs.

Antrim Coal-field.—Situated at Ballycastle, at the northern extremity of Antrim, is found a small coal-field yielding coal of a bituminous character in quantities not exceeding a few thousand tons annually. It is recorded that the oldest colliery wrought in Ireland was at Ballycastle, where, during the year 1770, some miners exploring the levels broke through an old gallery, the walls of which were lined with stalactites, evidently of great age; and antique mining tools were found therein. The residents in the district had never heard of a tradition of the mine having been anciently worked, and the excavation therefore must have been made at a very remote period. About the year 1830 there were twelve coal-pits in this coal-field, four of which were then in operation, the coal seams being wrought to a considerable distance under the sea.

This coal-field is about four miles in length, and has an average width of $1\frac{1}{2}$ miles. Professor Hull gives the annexed section of the coal series at Ballycastle Bay, as ascertained at the mines now at work, as follows:—

| | Ft. | In. |
|---|-----|-----|
| <i>Top or First Coal (Splint Seam)</i> | 3 | 0 |
| Sandstones and shales | 30 | 0 |
| <i>Second Coal (Hawksnest Seam)</i> | 3 | 0 |
| Strata with black-band ironstone | 240 | 0 |
| <i>Third Coal (Main Seam)</i> | 4 | 0 |
| Strata with black-band ironstone below the main coal in some places) | 60 | 0 |
| Limestone | 8 | 0 |
| Strata (shales and sandstones) | 240 | 0 |
| Lower (black-band ironstone by boring) | 1 | 0 |
| Total | 589 | 0 |

The coal of the Ballycastle coal-field is thus described by Sir Robert Kane :—"Dull, black in colour ; its specific gravity, 1·279. On ignition it gives out much gas, frothed very much, and left a porous coke." Its constituents are as follows :—*

| | |
|---------------------------|--------|
| Volatile matter | 36·96 |
| Pure coke | 45·94 |
| Ashes | 17·10 |
| | <hr/> |
| | 100·00 |

One part of it gave 25 of lead, hence 100 parts of it corresponded to 71·4 of pure carbon. The coal is considered in its economical relations suitable for industrial purposes of all kinds where coal is employed.

Southern Group of Coal-fields.—The most important in the south of Ireland, yielding anthracite, is that of Leinster, comprising a great area of the county of Kilkenny, Queen's County, and a part of Carlow. A portion of the same coal-field extends into the county Tipperary, and is separated from the Kilkenny coal-field by an intervening neck of limestone. The Leinster coal-field is some 20 miles in length between Ballyroan on the north, and Gowran on the south, its greatest width at Castlecomer being about 14 miles. The isolated coal-field of Tipperary extends about 20 miles in length from Freshford to near Cashel, and is about six miles wide, the towns of Killenaule and New Birmingham occupying its centre. The following is given by Professor Hull as the general series of coal in the Castlecomer coal-basin. Some measures of ironstone also occur.†

| | Ft. | In. |
|--|-----|-----|
| Uppermost beds about | 12 | 0 |
| Peacock Coal | 1 | 10 |
| Strata | 45 | 0 |
| Stony Coal | 3 | 0 |
| Strata | 21 | 0 |
| Double Seam | 5 | 0 |
| Strata and shales | 120 | 0 |
| Three-foot or Old Colliery Coal | 3 | 0 |
| Strata | 180 | 0 |
| Five-foot Coal | 3 | 6 |
| Strata | 300 | 0 |
| Upper and Lower Towlerton Coals 1ft. 6in. to | 2 | 0 |
| Flag series, about | 650 | 0 |
| Black Shale series | 500 | 0 |
| Upper Carboniferous Limestone | | |

* "Industrial Resources of Ireland," second edition, p. 26.

† "Coal-fields of Great Britain," 4th edit., p. 327.

Analyses of the Coal.—The coal of the Slievardagh coal-field in the County Tipperary reported upon* is described as highly anthracitic. The specimen examined was obtained from the 8 feet vein at a depth of 25 yards from the surface, the vein itself having an inclination of 1 in 5, and situate in soft shale and sandstone, both easily worked. The mean composition of this coal is as follows per cent. :—*

| RESULTS TABULATED. | |
|----------------------------|--------------|
| Carbon | 80·03 |
| Hydrogen | 2·30 |
| Nitrogen | 0·23 |
| Sulphur | 6·76 |
| Oxygen } | 10·80 |
| Ash } | |
| | <hr/> 100·12 |
| Specific gravity | 1·59 |
| Coke per cent. | <hr/> 90·10 |

The average weight of a cubic foot of this coal is 62·8 lbs.; the space occupied by one ton 35·66 cubic feet; while 1 lb. of the coal will evaporate 9·85 lbs. of water from a temperature of 212° Fahr.

The coal of the Slievardagh district is worked by the Mining Company of Ireland, who raised 25,276 tons of anthracite in 1879, compared with 28,503 tons in 1880.

Sir Robert Kane,† who has examined specimens of the following coals raised in the Leinster and Munster coal-fields—

The Bushes Coal, Queen's County;
The Pollough Coal, Castlecomer;
The Sweet Vein, Kanturk, Munster—

remarks that “the anthracites have no tendency to froth or cake in coking. They give off little or no inflammable gas on being ignited, but usually the masses break up quite small, especially if the heat be suddenly applied. The ashes are almost always red, owing to oxide of iron remaining after the combustion of the pyrites, which the anthracite usually contains.”

By the ordinary analysis for carbon and ash these coals yielded:—

* First Report, “Coals suited to the Steam Navy,” p. 12.

† “Industrial Resources of Ireland,” 2nd edition, p. 27.

| Constituents. | Rushes. | Pollough. | Sweet Vein. |
|-----------------------|---------|-----------|-------------|
| Volatile matter . . . | 9.85 | 10.40 | 10.35 |
| Pure Carbon | 86.42 | 79.71 | 81.13 |
| Ashes | 3.73 | 9.89 | 8.52 |
| | 100.00 | 100.00 | 100.00 |

The pure anthracite of the same veins considered separately from ashes and sulphur giving the annexed results :—

| Constituents. | Rushes. | Pollough. | Sweet Vein. |
|--------------------|---------|-----------|-------------|
| Carbon | 93.53 | 92.37 | 94.39 |
| Hydrogen | 3.63 | 2.40 | 4.05 |
| Oxygen | 2.84 | 5.23 | 1.56 |
| | 100.00 | 100.00 | 100.00 |

The Rushes coal is generally considered as representing the usual composition of these varieties of coal.

The Munster Coal-field.—In this coal-tract is comprised a considerable area of the counties of Clare, Limerick, Cork, and Kerry; and in each of these counties coal has been discovered and worked, the most important localities being situated between the River Blackwater and Kanturk in the County Cork. The coal lies in a series of troughs, the hills usually striking from east to west, the strata dipping on either side north and south at considerable angles, often perpendicular. Sir Richard Griffiths gives the number of coal seams in this coal-field as six; of these, three of the most valuable are locally known as the Bulk Vein, Rock Vein, and the Sweet vein. Coal has been extensively worked in the Barony of Dunhallow, County Cork, also in Clare, but the seams of coal in the latter county, although extending over large areas, are comparatively thin, and the character of the coal is softer and more slaty than that obtained in the Kilkenny and Tipperary districts. On the contrary, the seams in the Dunhallow district, County Cork, vary from two to three feet in thickness, and produce anthracite of an excellent description. Analyses of these coals will be found with those of other coals in the Tipperary extension of the Leinster coal-field.

Production of Coal.—The total production of the Irish coal-fields is shown in the subjoined table, distinguishing the anthracitic and bituminous coal to the end of 1868 :—

| Year. | Collieries. | Anthracite. | Bituminous. | Total Coal. |
|-------|-------------|-------------|-------------|-------------|
| | Nos. | Tons. | Tons. | Tons. |
| 1856 | 22 | 96,220 | 40,415 | 136,635 |
| 1857 | 45 | 80,420 | 40,210 | 120,630 |
| 1858 | 47 | 79,500 | 41,250 | 120,750 |
| 1859 | 45 | 78,250 | 42,150 | 120,300 |
| 1860 | 46 | 70,250 | 49,175 | 119,425 |
| 1861 | 46 | 72,570 | 50,000 | 123,070 |
| 1862 | 46 | 73,000 | 54,500 | 127,500 |
| 1863 | 46 | 72,550 | 54,500 | 127,050 |
| 1864 | 41 | 70,000 | 55,000 | 125,000 |
| 1865 | 39 | 70,000 | 53,500 | 123,500 |
| 1866 | 39 | 68,750 | 55,000 | 123,750 |
| 1867 | 34 | 75,000 | 50,000 | 125,000 |
| 1868 | 34 | 74,500 | 52,450 | 126,950 |

From 1869 to 1880 the total quantity of coal raised is alone given, the separation of the two varieties not being satisfactory:—

| Year. | Collieries. | Total Coal. | Year. | Collieries. | Total Coal. |
|-------|-------------|-------------|-------|-------------|-------------|
| | Nos. | Tons. | | Nos. | Tons. |
| 1869 | 33 | 127,923 | 1875 | 53 | 127,950 |
| 1870 | 32 | 141,470 | 1876 | 55 | 124,936 |
| 1871 | 30 | 165,750 | 1877 | 49 | 138,722 |
| 1872 | 29 | 103,435 | 1878 | 50 | 121,975 |
| 1873 | 34 | 103,465 | 1879 | 47 | 129,000 |
| 1874 | 42 | 139,218 | 1880 | 30 | 133,702 |

Population employed in Coal Mining in Ireland.—In 1873 the total number of persons engaged in coal-mining amounted to 1,950, of whom 1,209 were engaged under, and 741 above ground. The details of recent years ending 1880 appear in the annexed summary :—*

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|---------------|--------|--------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 1,209 | 741 | 1,950 | 135,731 | 79 |
| 1874 | 1,120 | 531 | 1,651 | 139,213 | 84 |
| 1875 | 1,069 | 475 | 1,544 | 128,207 | 83 |
| 1876 | 946 | 419 | 1,365 | 125,195 | 90 |
| 1877 | 883 | 365 | 1,248 | 140,181 | 112 |
| 1878 | 841 | 381 | 1,222 | 122,051 | 100 |
| 1879 | 819 | 296 | 1,115 | 129,003 | 115 |
| 1880 | 777 | 294 | 1,071 | 133,702 | 124 |

* Reports of H.M. Inspectors of Mines.

In each of the same years the quantity of coal raised in each of the four provinces of Ireland was as follows, also the number of persons employed in each province :—

| Year. | CONNAUGHT. | | ULSTER. | | LEINSTER. | | MUNSTER. | |
|-------|------------|-----------------|---------|-----------------|-----------|-----------------|----------|-----------------|
| | Nos. | Coal. | Nos. | Coal. | Nos. | Coal. | Nos. | Coal. |
| 1873 | 376 | Tons. 11,021 | 391 | Tons. 18,105 | 777 | Tons. 61,425 | 406 | Tons. 45,180 |
| 1874 | 111 | 5,108 | 321 | 17,810 | 828 | 73,302 | 391 | 43,993 |
| 1875 | 84 | 4,772 | 261 | 15,869 | 866 | 66,876 | 333 | 40,684 |
| 1876 | 99 | 5,203 | 183 | 15,335 | 798 | 72,025 | 285 | 32,632 |
| 1877 | 78 | 6,477 | 180 | 15,398 | 713 | 88,095 | 277 | 30,211 |
| 1878 | 75 | 6,456 | 217 | 12,407 | 663 | 74,474 | 267 | 28,714 |
| 1879 | 88 | 9,600 | 165 | 17,066 | 624 | 77,061 | 238 | 25,276 |
| 1880 | 87 | 8,506 | 175 | 21,203 | 589 | 75,490 | 220 | 28,503 |

Resources of the Coal-fields of Ireland.—The investigation as to the quantity of coal remaining in the coal-fields of Ireland by the Royal Coal Commission was entrusted to the late Mr. J. B. Jukes, F.R.S. ; on that gentleman's decease, Professor Hull, who succeeded him as Director of the Geological Survey of Ireland, continued the inquiry with the assistance of Messrs. G. H. Kinahan and J. O'Kelly, officers of the survey. In the tabulated statement annexed showing the total quantities of coal unworked, and the net tonnage available for future use, the respective quantities are thus distributed amongst the several coal-fields :—*

| Districts. | Coal Unworked. | Coal available for use. |
|---|----------------|-------------------------|
| | Tons. | Tons. |
| 1. Ballycastle, County Antrim | 18,000,000 | 16,000,000 |
| 2. Tyrone (visible and concealed) | 36,950,000 | 32,900,000 |
| 3. Queen's County, Kilkenny, and Carlow (Leinster) | 86,202,000 | 77,580,000 |
| 4. Tipperary | 29,500,000 | 25,000,000 |
| 5. Clare, Limerick, and Cork (Mun- ster) | 23,000,000 | 20,000,000 |
| 6. Connaught (Ariena district) | 12,000,000 | 10,800,000 |
| Totals | 205,652,000 | 182,280,000 |

Taking the net tonnage of coal available for use and deducting therefrom the production of the ten years ending 1879, amount-

* "Coal Commission Report," vol. i., p. 78.

ing to 1,295,921 tons, there remains for future use 180,984,079 tons. Of the coal thus available it is generally assumed that the proportion of anthracite is two-thirds, that of bituminous coal being about one-third of the total quantity.

Prices of Coal at the Pit Mouth.—The prices of coal in the years 1879 and 1880 show but little variation; the average may be taken as about 11*s.* 10*d.* per ton—the highest price of anthracite £1 8*s.* 4*d.*, the lowest of bituminous coal 6*s.* 8*d.* per ton; the coal of the Leitrim district varying from 5*s.* to 10*s.* per ton. The Ballycastle district in the County Tyrone, slack, 4*s.*; coal, 10*s.* per ton. In the Leinster district slack sold for 5*s.*, and coal 15*s.* to 20*s.* per ton; the highest prices quoted being the produce of the collieries of the Mining Company of Ireland, situated in the Slievardagh district, 75 per cent. of their coal averaging in prices from 5*s.* to 8*s.* 4*d.* per ton, the remainder from 15*s.* to 28*s.* 4*d.* per ton in 1880.

CHAPTER XX.

THE COAL-FIELDS OF THE UNITED KINGDOM.

General Summary—Areas of Coal-fields—Production of England, Wales, Scotland, and Ireland—Distribution of Coal by Railway—Coal brought into London—Coal sent Coastwise and exported to Foreign Countries—Population employed in Coal Mining—Resources and probable duration of Coal-fields.

General Summary.—Having previously considered each coal-field in the United Kingdom, it only remains to summarize all available information under the following heads:—

I. Areas of the Coal-fields of the United Kingdom:—

| COAL-FIELDS. | AREA IN SQUARE MILES. |
|---|-----------------------|
| <i>England</i> , Durham and Northumberland | 796 |
| „ Yorkshire, Derbyshire and Nottinghamshire | 800 |
| „ Cumberland | 25 |
| „ Lancashire and Cheshire | 220 |
| „ Leicestershire | 15 |
| „ Warwickshire | 30 |
| „ Shropshire | 28 |
| „ North Staffordshire | 75 |
| „ South Staffordshire | 93 |
| <i>North Wales</i> , Anglesea | 90 |
| „ Denbighshire } | |
| „ Flintshire } | |
| <i>South Wales</i> , Monmouthshire 104 | 1,000 |
| „ Glamorganshire 518 | |
| „ Brecknockshire 74 | |
| „ Caermarthenshire 228 | |
| „ Pembrokeshire 76 | |
| Gloucestershire (Forest of Dean) | 34 |
| Somersetshire (Bristol). | 150 |
| <i>Scotland</i> | 1,720 |
| <i>Ireland</i> | 2,800* |
| Total Area | 7,876 |

II. Production of Coal in Great Britain.—Towards the close of the past century and previously, from careful estimates appearing in the pages of the Report of the Coal Commission, it is shown that the total production of the collieries of the kingdom in each of the following years amounted to:—

* Estimated area.

| YEAR. | QUANTITIES. |
|----------------|-----------------|
| 1660 | 2,148,000 tons. |
| 1700 | 2,612,000 „ |
| 1750 | 4,773,000 „ |
| 1770 | 6,205,400 „ |
| 1780 | 6,424,976 „ |

At this period the Durham and Northumberland coal-field furnished 25 per cent. of the total production. In the year 1785, and until the year 1800, the output of the collieries of the United Kingdom is given approximately as follows :—

| YEAR. | QUANTITIES. |
|----------------|-----------------|
| 1785 | 6,888,712 tons. |
| 1790 | 7,618,760 „ |
| 1795 | 10,681,728 „ |
| 1800 | 10,080,300 „ |

Advancing to the year 1816, it appears from evidence given before a Committee of the House of Lords, appointed to take into consideration the state of the coal-trade of the United Kingdom,* and on the authority of the eminent engineer, Mr. Buddle, that the quantity carried by canals and railways, in different parts of the kingdom, amounted to 4,078,508 chaldrons (the Newcastle chaldron being 53 cwt.).

The total production of the kingdom for the same year (1816), as given by Samuel Salt, in his “Statistics and Calculations,” amounted to 27,020,115 tons, in the following details :—

| COAL FIELDS. | TONS. |
|--|-------------------|
| Yorkshire | 2,563,626 |
| Derbyshire | 942,218 |
| Nottinghamshire | 494,665 |
| Leicestershire | 176,665 |
| Warwickshire | 431,849 |
| Staffordshire | 795,000 |
| Quantity that passed towards the Eastern seas | 5,404,023 |
| Quantity believed to pass towards the Western seas | 5,404,023 |
| Quantity carried by canal and railway | 10,808,046 |
| Total production in 1816 | <u>27,020,115</u> |

Between 1816 and 1854 many returns are met with, chiefly estimates of the probable quantities raised ; in the last-named year, however, the annexed return appears, showing the quantity of coal raised from the 2,897 collieries then in operation in the United Kingdom, producing 64,661,401 tons. The details of production are as follows :—

* Report of Select Committee, House of Lords, dated 15 June, 1829.

| Coal-fields. | Number of Collieries. | Production of Coal. | Coal-fields. | Number of Collieries. | Production of Coal. |
|--|-----------------------|---------------------|--|-----------------------|---------------------|
| <i>England—</i> | | Tons. | | | Tons. |
| Northumberland and Durham | 225 | 15,420,615 | Brought forward | 1,617 | 45,929,285 |
| Cumberland | 23 | 887,000 | <i>England—continued.</i> | | |
| Yorkshire | 276 | 7,260,500 | Gloucestershire | 87 | 1,492,366 |
| Derbyshire | 123 | 2,406,696 | Somersetshire | | |
| Nottinghamshire | 17 | 813,474 | Devonshire | | |
| Warwickshire | 15 | 255,000 | <i>Wales—</i> | | |
| Leicestershire | 11 | 439,000 | Anglesea, Flintshire, and Denbighshire | 60 | 1,143,000 |
| Staffordshire and Worcestershire | 516 | 7,500,000 | Monmouthshire | 246 | 8,500,000 |
| Lancashire | 333 | 9,080,500 | Glamorganshire | | |
| Cheshire | 30 | 786,500 | Pembrokeshire | | |
| Shropshire | 48 | 1,080,000 | <i>Scotland</i> | 368 | 7,448,000 |
| | | | <i>Ireland</i> | 19 | 148,750 |
| Carried forward | 1,617 | 45,929,285 | Total | 2,397 | 64,661,401 |

Since the year 1854 the production of coal, with the number of collieries, has been as follows, the produce of England, Wales, Scotland, and Ireland being separately distinguished, the output increasing upwards of two-fold since 1854.

STATEMENT SHOWING THE PRODUCTION OF COAL IN THE UNITED KINGDOM SINCE 1854:—

| No. of Collieries. | Year. | England. | Wales. | Scotland. | Ireland. | Total of the United Kingdom. |
|--------------------|-------|-------------|-------------|------------|----------|------------------------------|
| | | Tons. | Tons. | Tons. | Tons. | Tons. |
| 2,397 | 1854 | 47,421,651 | 9,643,000 | 7,448,000 | 148,750 | 64,661,401 |
| 2,613 | 1855 | 47,306,189 | 9,677,270 | 7,325,000 | 144,620 | 64,453,079 |
| 2,815 | 1856 | 49,043,215 | 9,965,600 | 7,500,000 | 136,635 | 66,645,450 |
| 2,871 | 1857 | 48,885,800 | 8,176,804 | 8,211,473 | 120,630 | 65,394,707 |
| 2,941 | 1858 | 47,545,861 | 8,417,789 | 8,926,249 | 120,750 | 65,008,649 |
| 3,009 | 1859 | 50,297,115 | 11,262,350* | 10,300,000 | 120,300 | 71,979,765 |
| 2,949 | 1860 | 64,117,460 | 8,905,313 | 10,900,500 | 119,425 | 84,042,698 |
| 3,052 | 1861 | 66,274,123 | 8,561,021 | 11,081,000 | 123,070 | 86,039,214 |
| 3,088 | 1862 | 62,125,383 | 8,309,455 | 11,076,000 | 127,500 | 81,638,338 |
| 3,160 | 1863 | 66,419,584 | 8,645,081 | 11,100,500 | 127,050 | 86,292,215 |
| 3,268 | 1864 | 71,327,873 | 8,935,060 | 12,400,000 | 125,000 | 92,787,873 |
| 3,256 | 1865 | 75,482,580 | 9,894,507 | 12,650,000 | 123,500 | 98,150,587 |
| 3,188 | 1866 | 77,423,351 | 11,458,443 | 12,625,000 | 123,750 | 101,630,544 |
| 3,258 | 1867 | 78,785,987 | 11,463,550 | 14,125,943 | 125,000 | 104,500,480 |
| 2,922 | 1868 | 76,959,748 | 11,344,500 | 14,709,959 | 126,950 | 103,141,157 |
| 2,852 | 1869 | 81,547,654 | 11,334,830 | 14,417,150 | 127,923 | 107,427,557 |
| 2,851 | 1870 | 83,726,369 | 11,628,800 | 14,934,553 | 141,470 | 110,431,192 |
| 2,760 | 1871 | 90,127,987 | 11,620,000 | 15,438,291 | 165,750 | 117,352,028 |
| 3,001 | 1872 | 97,878,524 | 10,131,720 | 15,383,609 | 103,463 | 123,497,316 |
| 3,527 | 1873 | 97,764,017 | 12,291,523 | 16,857,772 | 103,435 | 127,016,747 |
| 4,112 | 1874 | 95,529,867 | 12,610,185 | 16,788,061 | 139,213 | 125,067,916 |
| 3,933 | 1875 | 100,171,743 | 12,969,905 | 18,597,507 | 127,950 | 131,867,105 |
| 4,002 | 1876 | 100,373,692 | 14,180,586 | 18,665,552 | 124,936 | 133,344,766 |
| 3,770 | 1877 | 101,038,052 | 15,113,915 | 18,320,074 | 138,722 | 134,610,763 |
| 3,768 | 1878 | 99,500,027 | 15,148,582 | 17,837,282 | 121,975 | 132,607,866 |
| 3,757 | 1879 | 101,063,222 | 15,346,079 | 17,469,927 | 129,000 | 134,008,228 |
| 3,904 | 1880 | 112,434,790 | 16,126,031 | 18,274,886 | 133,702 | 146,969,409 |

* Including production of Monmouthshire.

† Including 4,000,000 tons wasted on fire-heaps.

‡ Including 2,404,000 tons wasted on fire-heaps.

Following the production of the coal-fields of the United Kingdom, the annexed details for the years 1860, 1870, and 1880, afford the required data for comparison, showing the output of the collieries of each coal-field in the years given:—

| Coal Fields. | 1860. | 1870. | 1880.* |
|---|--------------------|--------------------|--------------------|
| | Tons. | Tons. | Tons. |
| <i>England—</i> | | | |
| Northumberland, North and } South Durham . . . } | 18,244,708 | 27,613,539 | 34,913,508 |
| Cumberland } | 1,171,052 | 1,408,235 | 1,680,841 |
| Westmoreland } | ... | ... | 1,950 |
| Cheshire } | 750,500 | 929,150 | 681,000 |
| Lancashire, North and East } Lancashire, West . . . } | 11,350,000 | 13,810,600 | 19,120,294 |
| Yorkshire, North Riding . } | ... | ... | 5,270 |
| West Riding . . } | 9,284,000 | 10,606,604 | 17,468,536 |
| Derbyshire } | ... | 5,102,265 | 7,903,834 |
| Nottinghamshire } | 4,940,000 | 2,115,372 | 4,432,393 |
| Warwickshire } | 545,000 | 647,540 | 1,101,386 |
| Leicestershire } | 730,000 | 599,450 | 1,063,382 |
| Staffordshire, North and South, } and Worcestershire . . } | 7,648,300 | 13,230,062 | 13,734,800§ |
| Shropshire } | 850,500 | 1,343,300 | 905,000 |
| Gloucestershire, Somersetshire } | +5,603,400 | 1,955,910 | 1,953,732 |
| Monmouthshire } | ... | 4,364,342 | 5,039,549 |
| <i>Wales, North—</i> | | | |
| Flintshire, Denbighshire . } | 1,750,500 | 2,329,030 | 2,429,315 |
| <i>Wales, South—</i> | | | |
| Glamorganshire, Brecknock- } shire, Pembrokehire, and } Carmarthenshire . . } | 6,254,813 | 9,299,770 | 16,126,031 |
| <i>Scotland—</i> | | | |
| Eastern District } | 10,900,500 | 14,934,553 | 18,274,886 |
| Western District } | ... | ... | ... |
| <i>Ireland }</i> | 119,425 | 141,470 | 133,702 |
| Total of the United Kingdom | 184,042,698 | 110,431,192 | 146,969,409 |

III. Distribution of Coal by Railway.—Hitherto the quantities of coal carried from our several coal-fields by Railways have received attention; it is now desirable to follow up this inquiry by ascertaining the total quantities of coal carried by each of the great railway systems, giving the aggregate in each year, and with this view the following tables have been prepared, commencing with—

No. 1. North Eastern Railway System:—

* According to returns of H.M. Inspectors of Mines, 1880.

+ Including the produce of Monmouthshire.

‡ Including 4,000,000 tons wasted on fire heaps.

§ Including 1,429,000 tons the produce of Worcestershire in 1880.

| Year. | From Durham and Northumberland. | From Lancashire and Yorkshire. | Total. |
|-------|---------------------------------|--------------------------------|------------|
| | Tons. | Tons. | Tons. |
| 1854 | 2,571,064 | 338,777 | 2,909,841 |
| 1855 | 2,547,931 | 312,369 | 2,860,300 |
| 1856 | 1,753,045 | 287,144 | 2,040,189 |
| 1857 | 2,554,330 | 357,656 | 2,911,986 |
| 1858 | 2,402,011 | 341,375 | 2,743,386 |
| 1859 | 2,383,765 | 334,835 | 2,718,600 |
| 1860 | 2,575,303 | 412,097 | 2,987,400 |
| 1861 | 2,650,430 | 403,825 | 3,054,255 |
| 1862 | 3,826,590 | 391,097 | 3,217,687 |
| 1863 | 4,866,393 | 361,860 | 5,228,253 |
| 1864 | 5,744,501 | 456,320 | 6,200,821 |
| 1865 | 7,069,556 | 469,080 | 7,538,636 |
| 1866 | 7,350,956 | 527,887 | 7,878,843 |
| 1867 | 7,503,152 | 572,808 | 8,085,860 |
| 1868 | 7,357,266 | 606,688 | 7,963,954 |
| 1869 | 8,280,310 | 675,378 | 8,955,688 |
| 1870 | 8,999,784 | 866,422 | 9,866,206 |
| 1871 | 10,089,217 | 1,064,407 | 11,153,625 |
| 1872 | 10,486,168 | 1,134,543 | 11,620,711 |
| 1873 | 10,792,280 | 1,067,651 | 11,859,931 |
| 1874 | 10,689,846 | 1,105,021 | 11,794,867 |
| 1875 | 11,032,299 | 1,281,248 | 12,313,547 |
| 1876 | 10,535,438 | 1,240,645 | 11,776,083 |
| 1877 | 10,439,768 | 1,318,887 | 11,758,655 |
| 1878 | 9,907,829 | 1,344,318 | 11,252,147 |
| 1879 | 9,320,511 | 1,455,895 | 10,776,406 |
| 1880 | 11,661,676 | 1,583,942 | 13,245,618 |

The extent of the distribution of the Durham and Northumberland coal appears in the annexed statement showing the details of its movement in each of the years named :—

| Distribution. | 1860. | 1870. | 1880. |
|---|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| The quantity of Coal carried over the North-Eastern Railway for local consumption and land sale from the Durham and Northumberland Coal Fields, and which was distributed over the districts Berwick and Kelso in the North, Carlisle and Tebay in the West, and Leeds, Knottingley, Doncaster and Altofts in the South | 1,673,278 | 4,907,714 | 5,935,937 |
| Shipped at Hull, Coal . . . | 98 | ... | 101 |
| For North-Eastern Company's use | 43,780 | 362,866 | 610,364 |
| The quantity of Coal passed over the North-Eastern Railway to districts | | | |
| Carried Forward . . . | 1,717,156 | 5,270,580 | 6,546,402 |

| Distribution. | 1860. | 1870. | 1880. |
|--|-----------|-----------|------------|
| | Tons. | Tons. | Tons. |
| Brought Forward | 1,717,156 | 5,270,580 | 6,546,402 |
| South of Altofts, Knottingley, Doncaster and Leeds, and also of Coal to places North of Kelso and Berwick, and West of Morpeth, Hexham, Carlisle, and Tebay, being the entire through traffic of Coal | 149,552 | 703,715 | 398,257 |
| The quantity of Coke carried over the North-Eastern Railway for local consumption and land sale between Kelso and Berwick in the North, Carlisle and Tebay in the West, and Leeds, Knottingley, Doncaster, and Altofts in the South | 145,722 | 1,909,442 | 2,780,148 |
| Shipped at Hull, Coke | 166 | 93 | 31 |
| For North-Eastern Company's use, Coke | 169,870 | 128,276 | 7,012 |
| The quantity of Coke carried over the North-Eastern Railway to districts South of Altofts, Doncaster, Knottingley and Leeds, and to places North of Kelso and Berwick, and North and West of Morpeth, Hexham, Carlisle and Tebay, being the entire through traffic of Coke | 392,837 | 987,678 | 1,929,826 |
| Total carried, Coal and Coke | 2,575,303 | 8,999,784 | 11,661,676 |

The distribution of coal, the produce of Yorkshire and Lancashire collieries, in each of the same years, was as follows, over the North Eastern Railway system :—

| Distribution. | 1860. | 1870. | 1880. |
|---|---------|---------|-----------|
| | Tons. | Tons. | Tons. |
| The quantity of Coal carried over the North-Eastern Railway from Yorkshire and Lancashire Collieries for consumption at places on the North-Eastern Railway | 354,385 | 663,474 | *952,764 |
| For shipment at Hull, Coal | 57,502 | 184,602 | 572,835 |
| Do. Do. Coke | | 2,001 | 419 |
| Do. at Goole, Coal | | 11,778 | 57,031 |
| Do. at Selby, Coal | 210 | 4,567 | 893 |
| Total Coal and Coke | 412,097 | 866,422 | 1,583,942 |

* This quantity includes 203,560 tons carried for consumption to places off the North-Eastern system.

No. 2. Midland Railway System.—From the following returns since the year 1856, a remarkable development of the coal industries of those districts traversed by the system, appears, showing a five-fold increase.

Coal carried by the *Midland Railway System* in each year since 1856 :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1856 | 2,449,552 | 1869 | 6,532,521 |
| 1857 | 2,525,751 | 1870 | 7,370,987 |
| 1858 | 2,695,584 | 1871 | 8,255,469 |
| 1859 | 3,158,020 | 1872 | 8,963,170 |
| 1860 | 4,001,270 | 1873 | 9,891,661 |
| 1861 | 4,048,071 | 1874 | 9,615,186 |
| 1862 | 3,738,833 | 1875 | 10,627,117 |
| 1863 | 4,330,022 | 1876 | 10,057,896 |
| 1864 | 5,198,890 | 1877 | 10,384,244 |
| 1865 | 5,470,735 | 1878 | 11,063,877 |
| 1866 | 5,521,180 | 1879 | 12,078,084 |
| 1867 | 5,927,004 | 1880 | 12,383,910 |
| 1868 | 5,822,494 | | |

The annexed details of quantities carried by the *Midland system* in 1860, 1870, and 1880, exhibits clearly the increase in the movement of coal in each of those years :—

| Coal Districts. | 1860. | 1870. | 1880. |
|---------------------------|-----------|-----------|------------|
| | Tons. | Tons. | Tons. |
| Derbyshire } | 2,230,275 | 4,079,447 | 5,603,872 |
| Nottinghamshire . . . } | | 471,118 | 1,614,377 |
| Yorkshire } | 483,693 | 1,382,808 | 2,408,650 |
| Leicestershire } | 717,633 | 966,830 | 1,066,861 |
| Gloucestershire . . . } | 227,275 | 219,010 | 223,098 |
| South Wales } | | 4,730 | 660,872 |
| Durham } | 255,163 | 112,801 | 147,692* |
| South Staffordshire . . } | | 42,305 | 189,247* |
| Warwickshire } | 80,104 | 75,863 | 308,697 |
| Lancashire } | 7,127 | 16,075 | 130,216* |
| Somersetshire } | ... | ... | 19,626* |
| Cumberland } | ... | ... | 8,345* |
| Scotland } | ... | ... | 2,357* |
| Total } | 4,001,270 | 7,370,987 | 12,383,910 |

No. 3. London and North Western Railway.—The earliest return available, for the year 1854, shows that a total quantity

* Quantities received from other lines and carried over *Midland system*.

of coal was carried by this system, amounting to 1,960,238 tons; since 1856 the quantities have been as follows:—

LONDON AND NORTH WESTERN RAILWAY.

| Year. | Coal Carried. | Year. | Coal Carried. |
|-------|---------------|-------|---------------|
| | Tons. | | Tons. |
| 1856 | 2,241,541 | 1870 | 7,165,371 |
| 1857 | 2,468,451 | 1871 | 7,755,657 |
| 1859 | 2,721,000 | 1872 | 8,193,991 |
| 1862 | 2,861,667 | 1873 | 8,299,491 |
| 1863 | 3,756,111 | 1874 | 7,541,425 |
| 1864 | 3,179,910 | 1875 | 9,077,654 |
| 1865 | 6,032,578 | 1876 | 9,496,171 |
| 1866 | 4,639,461 | 1877 | 9,687,999 |
| 1867 | 5,887,003 | 1878 | 9,701,965 |
| 1868 | 5,658,071 | 1879 | 10,828,393 |
| 1869 | 6,488,207 | 1880 | 11,100,891 |

The details of the quantities carried in the years 1860, 1870, and 1880, from the coal-fields traversed by the London and North Western system being as follows:—

| Coal-fields. | 1860. | 1870. | 1880. |
|-----------------------------|-----------|-----------|------------|
| | Tons. | Tons. | Tons. |
| Lancashire | 1,411,000 | 4,967,785 | 7,024,080 |
| South Staffordshire | 94,000 | 665,720 | 1,511,099 |
| South Wales | 219,000 | 70,321 | 903,335 |
| North Wales | ... | 376,512 | 304,509 |
| Warwickshire | 54,000 | 187,931 | 306,252 |
| Yorkshire | 108,000 | 203,205 | 236,648 |
| Cheshire | 160,000 | 104,484 | 184,815 |
| North Staffordshire | ... | 60,833 | 79,595 |
| Shropshire | ... | 117,317 | 106,333 |
| Leicestershire | ... | ... | 44,838 |
| Derbyshire | 675,000 | 66,217 | 27,632 |
| Cumberland | ... | 345,046 | 371,755 |
| Total | 2,721,000 | 7,165,371 | 11,100,891 |

No. 4. The Great Northern Railway.—Commencing with the year 1857, when the total weight of coal carried by this system amounted to 968,125 tons; the quantity carried from Yorkshire was 895,767 tons, and from Derbyshire, 72,358 tons. Since 1857 the quantities carried are as follows:—

GREAT NORTHERN RAILWAY.

| Year. | Coal Carried. | Year. | Coal Carried. |
|-------|---------------|-------|---------------|
| | Tons. | | Tons. |
| 1857 | 968,125 | 1870 | 2,276,312 |
| 1860 | 985,588 | 1871 | 2,403,926 |
| 1861 | 1,076,673 | 1872 | 2,553,051 |
| 1862 | 1,068,917 | 1873 | 2,545,278 |
| 1863 | 1,148,681 | 1874 | 2,307,024 |
| 1864 | 1,751,105 | 1875 | 2,696,645 |
| 1865 | 2,097,809 | 1876 | 2,658,102 |
| 1866 | 2,212,893 | 1877 | 2,873,158 |
| 1867 | 2,343,755 | 1878 | 2,992,642 |
| 1868 | 2,113,290 | 1879 | 3,475,343 |
| 1869 | 2,121,541 | 1880 | 3,627,756 |

The total weight carried from each coal-field in the years 1860, 1870, and 1880, by the Great Northern Railway, will be seen in the annexed table :—

| Coal-fields. | 1860. | 1870. | 1880. |
|----------------------------------|---------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| Durham | ... | 524,695 | 210,083 |
| South Yorkshire | 181,560 | 551,348 | 863,575 |
| West Yorkshire | 611,112 | 443,261 | 971,074 |
| N. and S. Lincolnshire | ... | ... | 161,860 |
| Derbyshire | 159,412 | 573,261 | 896,636 |
| London N. Western | ... | ... | 35,917 |
| North Staffordshire | ... | ... | 13,547 |
| South Wales | ... | ... | 23,550 |
| Leicestershire | ... | 6,561 | 1,829 |
| Bedford | 33,504 | 177,186 | *449,685 |
| Total | 985,588 | 2,276,312 | 3,627,756 |

No. 5. The Great Western Railway.—The total quantity of coal carried in the year 1857 was 382,104 tons, from the following coal districts :—

| | |
|-------------------------|----------------|
| | TONS. |
| South Wales | 120,080 |
| North Wales | 93,985 |
| Vale of Neath | 24,772 |
| Radstock | 143,267 |
| Total | <u>382,104</u> |

The total quantities carried in later years being as follows :—

* Carried to London and North-Western Railway *via* Market Harborough.

| Year. | Coal Carried. | Year. | Coal Carried. |
|-------|---------------|-------|---------------|
| | Tons. | | Tons. |
| 1857 | 382,104 | 1873 | 5,411,105 |
| 1860 | 542,199 | 1874 | 5,546,865 |
| 1862 | 713,501 | 1875 | 5,469,506 |
| 1865 | 2,182,739 | 1876 | 6,053,806 |
| 1869 | 3,683,640 | 1877 | 6,412,798 |
| 1870 | 3,791,532 | 1878 | 5,938,534 |
| 1871 | 3,962,647 | 1879 | 6,481,342 |
| 1872 | 4,296,597 | 1880 | 6,909,968 |

The coal thus carried in the years 1860, 1870, and 1880, was derived from the following coal-fields traversed by the Great Western Railway system :—

| Coal-fields. | 1860. | 1870. | 1880. |
|-------------------------------|---------|-----------|-----------|
| | Tons. | Tons. | Tons. |
| South Wales | 204,082 | 2,850,412 | 5,384,411 |
| Forest of Dean | | | |
| Vale of Neath | | | |
| North Wales | 122,530 | 646,810 | 960,934 |
| Radstock | 185,363 | 294,310 | 258,482 |
| Bristol | 30,224 | ... | ... |
| South Staffordshire | ... | ... | 306,141 |
| Total . | 542,199 | 3,791,532 | 6,909,968 |

No. 6. Taff Vale Railway.—Total quantities of coal and coke conveyed over the Company's lines in each year since 1841 :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1841 | 41,669 | 1861 | 2,297,250 |
| 1842 | 114,516 | 1862 | 2,540,657 |
| 1843 | 152,100 | 1863 | 2,722,011 |
| 1844 | 187,740 | 1864 | 2,842,049 |
| 1845 | 265,040 | 1865 | 2,855,138 |
| 1846 | 294,175 | 1866 | 3,248,235 |
| 1847 | 360,324 | 1867 | 3,381,045 |
| 1848 | 502,029 | 1868 | 3,540,324 |
| 1849 | 530,145 | 1869 | 3,310,067 |
| 1850 | 594,222 | 1870 | 3,943,661 |
| 1851 | 612,716 | 1871 | 3,593,932 |
| 1852 | 711,692 | 1872 | 4,213,606 |
| 1853 | 874,362 | 1873 | 4,527,641 |
| 1854 | 1,025,145 | 1874 | 4,352,778 |
| 1855 | 1,155,904 | 1875 | 3,776,813 |
| 1856 | 1,394,394 | 1876 | 4,879,150 |
| 1857 | 1,468,527 | 1877 | 5,170,953 |
| 1858 | 1,445,157 | 1878 | 5,613,639 |
| 1859 | 1,759,422 | 1879 | 5,849,184 |
| 1860 | 2,132,995 | 1880 | 6,894,403 |

This railway, though inconsiderable in extent compared with the several systems previously referred to, exercises an important influence in the movement of coal in the eastern extremity of the South Wales Coal-field which it traverses. Its total length is but 86 miles, 28 miles of which are single lines, the remaining 58 being double. In the 86 miles above referred to is included those other lines leased or worked by the Taff Vale Company, which are as follows:—The Aberdare, Cowbridge, Dare Valley, Llantrissant and Taff Vale Junction, Penarth Extension, Penarth Harbour Dock and Railway, and the Rhondda Valley and Hirwain Junction Railways. The extent of the traffic of coal and coke will be seen in the annexed table for the four decennial periods ending 1880:—

| Railway Distribution. | 1860. | 1860. | 1870. | 1880. |
|---|---------|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| To Cardiff and Penarth Junction | 564,698 | 1,929,525 | 3,415,193 | 5,955,457 |
| Sold retail | 29,524 | 203,470 | 363,225 | 356,691 |
| To Quaker's Yard Junction | .. | .. | 11,050 | 135,419 |
| To Mountain Ash Junction | .. | .. | 6,685 | 4,006 |
| Conveyed over by other railways | .. | .. | 77,507 | 345,757 |
| To Brecon and Merthyr Junction | .. | .. | .. | 97,010 |
| To Walnut Tree Bridge Junction | .. | .. | .. | 63 |
| Totals | 594,222 | 2,132,995 | 3,943,661 | 6,894,403 |

No. 7. The Coal Consumed in the Metropolis, amounting to upwards of 13 per cent. of the total produce of Great Britain during the year 1880, was conveyed to London in the following proportions by sea, railway and canal in 1880 and previous years since 1823: that brought by sea being the produce of the Durham and Northumberland Coal-field:—

COAL BROUGHT INTO LONDON BY SEA, CANAL, AND RAILWAY SINCE THE YEAR 1823.

| Year. | Sea. | Canal. | Railway. | Total. |
|-------|-----------|--------|----------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| 1823 | 1,574,412 | 993 | ... | 1,575,405 |
| 1824 | 1,828,177 | 1,695 | ... | 1,829,872 |
| 1825 | 1,870,349 | 1,658 | ... | 1,872,007 |
| 1826 | 1,813,757 | 1,686 | ... | 1,815,443 |
| 1827 | 1,985,969 | 2,149 | ... | 1,988,118 |
| 1828 | 1,960,559 | 547 | ... | 1,961,106 |
| 1829 | 2,018,975 | ... | ... | 2,018,975 |
| 1830 | 2,079,275 | ... | ... | 2,079,275 |
| 1831 | 2,045,292 | 10,742 | ... | 2,056,034 |
| 1832 | 2,139,078 | 6,905 | ... | 2,145,983 |
| 1833 | 2,010,409 | 4,395 | ... | 2,014,804 |

COAL BROUGHT INTO LONDON SINCE 1823—*continued.*

| Year. | Sea. | Canal. | Railway. | Total. |
|-------|-----------|--------|-----------|------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1834 | 2,078,635 | 1,862 | ... | 2,080,497 |
| 1835 | 2,298,812 | 1,004 | ... | 2,299,816 |
| 1836 | 2,402,474 | 1,199 | ... | 2,403,673 |
| 1837 | 2,543,742 | 2,324 | ... | 2,546,066 |
| 1838 | 2,518,085 | 1,686 | ... | 2,519,771 |
| 1839 | 2,625,323 | 12,933 | ... | 2,638,256 |
| 1840 | 2,566,899 | 22,188 | ... | 2,589,087 |
| 1841 | 2,909,144 | 33,594 | ... | 2,942,738 |
| 1842 | 2,723,200 | 31,519 | ... | 2,754,719 |
| 1843 | 2,628,520 | 34,593 | ... | 2,663,113 |
| 1844 | 2,490,910 | 72,275 | ... | 2,563,185 |
| 1845 | 3,392,512 | 60,310 | 8,377 | 3,461,199 |
| 1846 | 2,920,376 | 21,872 | 11,698 | 2,953,946 |
| 1847 | 3,280,420 | 22,005 | 19,336 | 3,321,761 |
| 1848 | 3,418,340 | 19,918 | 37,888 | 3,476,138 |
| 1849 | 3,339,146 | 19,222 | 19,639 | 3,378,007 |
| 1850 | 3,553,304 | 29,479 | 55,095 | 3,637,878 |
| 1851 | 3,236,542 | 29,434 | 247,908 | 3,507,884 |
| 1852 | 3,330,428 | 33,913 | 377,907 | 3,742,248 |
| 1853 | 3,373,256 | 21,644 | 629,712 | 4,014,612 |
| 1854 | 3,399,561 | 32,153 | 945,056 | 4,376,770 |
| 1855 | 3,016,869 | 23,250 | 1,137,835 | 4,177,954 |
| 1856 | 3,119,884 | 25,401 | 1,246,299 | 4,391,584 |
| 1857 | 3,133,459 | 26,295 | 1,206,775 | 4,366,529 |
| 1858 | 3,266,446 | 20,244 | 1,190,521 | 4,477,191 |
| 1859 | 3,299,170 | 16,964 | 1,191,169 | 4,507,303 |
| 1860 | 3,573,377 | 19,593 | 1,477,545 | 5,070,515 |
| 1861 | 3,567,002 | 18,217 | 1,642,502 | 5,227,721 |
| 1862 | 3,442,402 | 11,651 | 1,513,296 | 4,967,349 |
| 1863 | 3,335,174 | 9,226 | 1,775,487 | 5,119,887 |
| 1864 | 3,116,703 | 8,902 | 2,342,440 | 5,468,045 |
| 1865 | 3,161,683 | 8,532 | 2,733,056 | 5,903,271 |
| 1866 | 3,033,193 | 10,176 | 2,969,896 | 6,013,265 |
| 1867 | 3,016,416 | 9,965 | 3,295,652 | 6,322,033 |
| 1868 | 2,918,230 | 9,527 | 2,979,333 | 5,907,090 |
| 1869 | 2,873,688 | 6,941 | 3,341,585 | 6,222,214 |
| 1870 | 2,993,710 | 7,301 | 3,758,089 | 6,759,100 |
| 1871 | 2,762,712 | 6,615 | 4,449,141 | 7,218,468 |
| 1872 | 3,548,918 | 8,236 | 4,999,268 | 7,556,422 |
| 1873 | 2,665,680 | 11,195 | 5,147,413 | 7,824,288 |
| 1874 | 2,727,719 | 5,962 | 4,689,785 | 7,423,466 |
| 1875 | 3,134,846 | 4,594 | 5,065,452 | 8,204,892 |
| 1876 | 3,273,442 | 4,696 | 5,173,297 | 8,451,375 |
| 1877 | 3,170,601 | 4,608 | 5,416,474 | 8,591,683 |
| 1878 | 3,198,309 | 2,977 | 5,593,290 | 8,794,576 |
| 1879 | 3,508,526 | 2,910 | 6,547,375 | 10,058,811 |
| 1880 | 3,714,708 | 4,470 | 6,196,310 | 9,915,488 |

The earliest account met with of coal brought to London by railway is for the year 1845, when 8,377 tons were conveyed into the Metropolis, increased in 1880 to 6,196,310 tons. The

annexed returns for the years 1860, 1870, and 1880, give the quantities carried by the several railway companies into London, to which are also appended the quantities brought by sea, and the ports from which received, in each of the said years : *—

| By Railway and Canal. | 1860. | 1870. | 1880. |
|---|------------|------------|-----------|
| | Tons. | Tons. | Tons. |
| London and North- Western Railway . } | 693,419 | 835,281 | 1,436,338 |
| Great Northern Railway | 502,813 | 978,049 | 949,740 |
| Great Western Railway | 63,944 | 470,853 | 1,055,609 |
| Great Eastern Railway . | 121,226 | 507,344 | 669,288 |
| Midland Railway . . | 58,490 | 923,660 | 1,999,668 |
| London and South- Western Railway } | 17,589 | 27,560 | 59,369 |
| South-Eastern Railway . | 14,585 | 10,482 | 20,196 |
| London, Chatham, and Dover Railway . } | 104 | 4,572 | 6,007 |
| London, Tilbury, and Southend . . } | 958 | 262 | 94 |
| Total . . . | 1,477,545† | 3,758,089‡ | 6,196,309 |
| Canals . . . | 19,593 | 7,301 | 4,471 |
| Total . . . | 1,497,138 | 3,765,390 | 6,200,780 |
| <i>By Sea.</i> | | | |
| Newcastle | 1,347,574 | 1,507,078 | 2,005,064 |
| Seaham | 210,418 | 107,798 | 225,914 |
| Sunderland | 977,519 | 769,243 | 948,151 |
| Middlesbro' | 61,183 | 72,830 | 17,809 |
| Hartlepool and West Hartlepool . } | 703,836 | 409,754 | 286,294 |
| Blyth | 40,986 | 3,562 | 200 |
| Scotland | 13,002 | 39,902 | 63,379 |
| Wales | 130,009 | 25,937 | 94,638 |
| Yorkshire | 45,230 | 40,966 | 22,632 |
| Duff | ... | ... | 230 |
| Small Coal | 25,047 | 8,432 | 41,956 |
| Culm | 1,902 | 444 | ... |
| Cinders | 16,671 | 6,962 | 6,070 |
| Colonial | ... | ... | 2,350 |
| Total | 3,573,377 | 2,993,710§ | 3,714,708 |
| Total by Rail, Canal, and Sea . . . } | 5,070,515 | 6,759,100 | 9,915,488 |

* From Mr. James R. Scott's "Coal and Coke Returns" published by the authority of the Corporation of London.

† Including 4417 tons carried by the Hereford and Luton Railway.

‡ Including 26 tons carried by the London and Brighton Railway.

§ Including 802 tons from Lancashire.

|| Including 21 tons of foreign coal.

No. 8. Coals, Cinders and Culm.—An account of the quantities shipped at the several ports of England, Scotland, and Ireland, coastways, since the year 1834, to other ports of the United Kingdom (from Parliamentary Returns):—

| Year. | England. | Scotland. | Ireland. | Total. |
|-------|------------|-----------|----------|------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1834 | 5,280,632 | 538,771 | 3,158 | 5,822,561 |
| 1835 | 5,558,345 | 557,043 | 2,605 | 6,117,993 |
| 1836 | 5,921,245 | 548,076 | 3,083 | 6,472,404 |
| 1837 | 6,538,906 | 547,680 | 4,105 | 7,090,691 |
| 1838 | 6,572,635 | 613,875 | 3,923 | 7,190,433 |
| 1839 | 6,521,577 | 699,348 | 2,088 | 7,223,013 |
| 1840 | 6,749,690 | 723,534 | 2,653 | 7,475,877 |
| 1841 | 7,020,289 | 627,060 | 2,550 | 7,649,899 |
| 1842 | 7,079,588 | 567,036 | 2,845 | 7,649,469 |
| 1843 | 6,906,316 | 539,156 | 1,612 | 7,447,084 |
| 1844 | 6,731,647 | 644,388 | 1,827 | 7,377,862 |
| 1845 | 8,191,772 | 530,388 | 1,308 | 8,723,468 |
| 1846 | 7,838,668 | 465,173 | 1,601 | 8,305,442 |
| 1847 | 8,442,567 | 431,308 | 724 | 8,874,599 |
| 1848 | 8,576,148 | 496,816 | 1,115 | 9,074,079 |
| 1849 | 8,082,200 | 469,918 | 588 | 8,552,706 |
| 1850 | 8,901,885 | 463,123 | 2,770 | 9,367,778 |
| 1851 | 8,319,956 | 496,106 | 476 | 8,816,538 |
| 1852 | 8,567,985 | 501,413 | 179 | 9,069,577 |
| 1853 | 8,594,063 | 476,767 | 154 | 9,070,984 |
| 1854 | 8,796,135 | 476,772 | 258 | 9,273,165 |
| 1855 | 8,322,403 | 530,578 | 161 | 8,853,142 |
| 1856 | 8,570,489 | 539,407 | 180 | 9,110,076 |
| 1857 | 8,934,906 | 598,569 | 201 | 9,533,676 |
| 1858 | 8,960,026 | 565,704 | 81 | 9,525,811 |
| 1859 | 9,536,913 | 570,790 | 130 | 10,107,833 |
| 1860 | 9,977,397 | 743,214 | 105 | 10,720,716 |
| 1861 | 10,266,228 | 726,249 | 120 | 10,992,597 |
| 1862 | 10,016,420 | 837,786 | 70 | 10,874,276 |
| 1863 | 9,634,888 | 753,244 | 120 | 10,388,252 |
| 1864 | 10,099,834 | 870,877 | ... | 10,970,711 |
| 1865 | 10,064,966 | 863,291 | ... | 10,928,257 |
| 1866 | 9,901,675 | 819,029 | 120 | 10,720,824 |
| 1867 | 10,295,042 | 1,004,348 | ... | 11,299,390 |
| 1868 | 9,652,234 | 923,001 | 40 | 10,575,275 |
| 1869 | 9,534,957 | 917,178 | ... | 10,452,135 |
| 1870 | 10,042,973 | 1,062,693 | ... | 11,105,666 |
| 1871 | 9,615,760 | 1,115,558 | ... | 10,731,318 |
| 1872 | 8,965,457 | 1,171,340 | ... | 10,136,797 |
| 1873 | 9,143,820 | 1,324,985 | ... | 10,468,805 |
| 1874 | 8,502,257 | 1,079,792 | ... | 9,582,049 |
| 1875 | 9,301,352 | 1,408,515 | ... | 10,709,867 |
| 1876 | 9,692,397 | 1,307,296 | ... | 10,999,693 |
| 1877 | 9,686,801 | 1,278,703 | 80 | 10,965,504 |
| 1878 | 8,732,399 | 1,325,698 | ... | 10,058,097 |
| 1879 | 10,623,380 | 1,421,743 | 330 | 12,045,453 |
| 1880 | 10,602,908 | 1,215,816 | 70 | 11,818,794 |

No. 9. Coal Exported to Foreign Countries.—From a Parliamentary paper published in the year 1831,* it appears that the total quantity of coals, cinders, and culm exported to foreign countries amounted to 237,657 tons; of this quantity 217,681 tons were conveyed in British ships, and 19,976 tons in the ships of foreign nations. In subsequent years, till 1829, the following quantities were annually sent out of the country, with the amount of duty paid thereon :—

| Year. | IN BRITISH SHIPPING. | | | IN FOREIGN SHIPPING. | | |
|-------|----------------------|--------|-------|----------------------|--------|-------|
| | Quantity. | Duty. | | Quantity. | Duty. | |
| | Tons. | £ | s. d. | Tons. | £ | s. d. |
| 1816 | 217,681 | 61,253 | 3 0 | 19,976 | 7,286 | 17 7 |
| 1817 | 220,811 | 50,262 | 16 5 | 32,330 | 10,301 | 15 11 |
| 1818 | 221,703 | 43,103 | 11 0 | 50,753 | 16,556 | 8 4 |
| 1819 | 202,156 | 37,654 | 1 6 | 36,084 | 11,208 | 6 5 |
| 1820 | 221,080 | 39,970 | 17 2 | 29,860 | 8,388 | 6 7 |
| 1821 | 236,085 | 43,506 | 4 9 | 26,884 | 7,405 | 8 4 |
| 1822 | 251,702 | 42,775 | 5 7 | 35,694 | 9,996 | 10 10 |
| 1823 | 217,256 | 34,550 | 14 8 | 36,741 | 9,470 | 0 1 |
| 1824 | 221,484 | 29,684 | 5 4 | 60,531 | 13,238 | 6 3 |
| 1825 | 235,298 | 29,774 | 5 5 | 77,948 | 13,646 | 16 4 |
| 1826 | 278,588 | 28,849 | 18 3 | 69,693 | 11,703 | 19 5 |
| 1827 | 288,071 | 30,008 | 13 4 | 80,608 | 15,173 | 15 11 |
| 1828 | 294,727 | 30,239 | 4 0 | 63,137 | 11,190 | 8 2 |
| 1829 | 283,574 | 29,143 | 4 1 | 87,696 | 14,739 | 11 11 |

The quantities of coals, cinders, and culm exported from the United Kingdom in the three years ending 1832, with the amount of duties received thereon, were as follows : †—

| Year. | Quantities. | Value. | | |
|-------|-------------|--------|----|----|
| | Tons. | £ | s. | d. |
| 1830 | 504,419 | 63,889 | 17 | 6 |
| 1831 | 510,831 | 55,237 | 5 | 10 |
| 1832 | 588,446 | 56,706 | 2 | 10 |

The duty levied on coals at this period to foreign countries was 3s. 4d. per ton in British ships, and 6s. 8d. per ton in other ships; small coals, cinders, and culm paying 2s. per ton in British ships, and 4s. per ton in other ships. In the year 1833 the total

* No. 287. "Account of the quantities of Coal exported to Foreign Countries." House of Commons paper, printed 25th March, 1831.

† *Ibid.*, No. 586. 29th July, 1833.

exports of coals, cinders, and culm amounted to 634,448 tons, the duty paid on the same amounting to £65,008 8s. 6d. The particulars are as follows :—

| Description. | Quantities. | Duty. | | |
|-----------------------|-------------|--------|----|----|
| | Tons. | £ | s. | d. |
| Coals | 409,665 | 41,677 | 1 | 0 |
| Small coals | 223,819 | 23,296 | 19 | 6 |
| Culm | 964 | 34 | 8 | 0 |
| Total | 634,448 | 65,008 | 8 | 6 |

Between the years 1833 and 1850, in which latter year the duty on coal exported to foreign countries and British settlements was wholly repealed, the exports were as follows :—

| Year. | Coals. | Cinders. | Culm. | Total. |
|-------|-----------|----------|-------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| 1834 | 609,756 | 3,654 | 1,845 | 615,255 |
| 1835 | 729,478 | 3,964 | 2,618 | 736,060 |
| 1836 | 910,773 | 5,191 | 904 | 916,868 |
| 1837 | 1,106,020 | 6,447 | 1,143 | 1,113,610 |
| 1838 | 1,303,384 | 9,693 | 632 | 1,313,709 |
| 1839 | 1,431,861 | 17,163 | 393 | 1,449,417 |
| 1840 | 1,592,283 | 13,783 | 247 | 1,606,313 |
| 1841 | 1,831,554 | 16,514 | 226 | 1,848,294 |
| 1842 | 1,975,280 | 23,434 | 790 | 1,999,504 |
| 1843 | 1,820,284 | 42,698 | 3,229 | 1,866,211 |
| 1844 | 1,698,391 | 49,389 | 6,391 | 1,754,171 |
| 1845 | 2,442,740 | 84,556 | 3,986 | 2,531,282 |
| 1846 | 2,432,382 | 95,554 | 3,172 | 2,531,108 |
| 1847 | 2,390,087 | 88,884 | 4,190 | 2,483,161 |
| 1848 | 2,699,468 | 82,908 | 2,924 | 2,785,300 |
| 1849 | 2,730,667 | 95,630 | 1,842 | 2,828,039 |
| 1850 | 3,211,619 | 137,348 | 2,913 | 3,351,880 |

Since the abolition of the duties on coal and cinders* in 1850, a greatly increased demand for British coal has arisen, the exports increasing from 3,351,880 tons in 1850 to 18,702,551 tons in 1880, showing an increase of upwards of 500 per cent. in a period of thirty years. In the annexed statement is given the total quantities exported, of coal, cinders, and culm, its declared value at the port of shipment, and the average value per ton in each year since 1850 :—

* The duty was wholly repealed by Act 13 & 14 Vict. c. 95. From 14th August, 1850.

| Year. | Quantities. | Value. | Price per Ton. | |
|-------|-------------|------------|----------------|----|
| | Tons. | £ | s. | d. |
| 1850 | 3,351,880 | 1,284,224 | 7 | 8 |
| 1851 | 3,468,545 | 1,302,473 | 7 | 6 |
| 1852 | 3,640,194 | 1,372,114 | 7 | 6 |
| 1853 | 3,935,062 | 1,604,591 | 8 | 2 |
| 1854* | 3,359,575 | 2,164,405 | 10 | 0 |
| 1855 | 5,061,762 | 2,505,326 | 9 | 9 |
| 1856 | 5,949,241 | 2,869,230 | 9 | 7 |
| 1857 | 6,821,750 | 3,264,098 | 9 | 7 |
| 1858 | 6,597,128 | 3,088,747 | 9 | 3 |
| 1859 | 7,082,029 | 3,315,279 | 9 | 4 |
| 1860 | 7,412,575 | 3,371,631 | 9 | 1 |
| 1861 | 7,934,832 | 3,652,164 | 9 | 2 |
| 1862 | 8,380,673 | 3,798,727 | 9 | 1 |
| 1863 | 8,342,500 | 3,752,308 | 9 | 0 |
| 1864 | 8,900,872 | 4,220,883 | 9 | 6 |
| 1865 | 9,283,214 | 4,496,567 | 9 | 8 |
| 1866 | 10,142,260 | 5,218,498 | 10 | 1 |
| 1867 | 10,565,829 | 5,488,945 | 10 | 5 |
| 1868 | 10,967,062 | 5,487,922 | 9 | 11 |
| 1869 | 10,744,945 | 5,165,668 | 9 | 7 |
| 1870 | 11,702,649 | 5,638,371 | 9 | 8 |
| 1871 | 12,747,989 | 6,246,133 | 9 | 11 |
| 1872 | 13,198,494 | 10,442,821 | 16 | 10 |
| 1873 | 12,617,566 | 13,188,551 | 20 | 11 |
| 1874 | 13,927,205 | 11,984,621 | 17 | 3 |
| 1875 | 14,544,916 | 9,658,088 | 13 | 3 |
| 1876 | 16,265,839 | 8,901,716 | 10 | 11 |
| 1877 | 15,420,050 | 7,844,486 | 10 | 2 |
| 1878 | 15,483,816 | 7,321,424 | 9 | 5 |
| 1879 | 16,442,296 | 7,206,799 | 8 | 10 |
| 1880 | 18,702,551 | 8,378,944 | 8 | 11 |

Considerable quantities of coal are annually shipped from the ports of Great Britain for the use of steamers engaged in the foreign trade. The shipments for the year 1874 were 3,140,383 tons. Since that date the quantities are as follows:—

| Year. | Tons. | Year. | Tons. |
|-------|-----------|-------|-----------|
| 1875 | 3,278,249 | 1878 | 4,018,010 |
| 1876 | 3,564,524 | 1879 | 4,401,120 |
| 1877 | 3,661,552 | 1880 | 4,926,076 |

Coal, Coke, Cinders and Manufactured Fuel exported from Great Britain, and the countries to which exported, in each of the years 1860, 1870, and 1880: †—

* Patent fuel not included between the years 1854 and 1860.

† According to "Trade and Navigation Returns." Manufactured fuel exported is included in the returns for 1880.

| Countries to which Exported. | 1860. | 1870. | 1880. |
|------------------------------|------------|------------|------------|
| | Tons. | Tons. | Tons. |
| Russia | 356,147 | 829,514 | 1,498,426 |
| Denmark | 418,163 | 695,704 | 860,373 |
| Sweden | ... | 385,763 | 1,317,274 |
| Prussia | 399,174 | 547,541 | ... |
| Hanse Towns | 539,477 | 800,240 | ... |
| Holland | 316,768 | 412,833 | 498,049 |
| France | 1,393,330 | 2,082,224 | 3,711,720 |
| Spain and Canaries | 452,436 | 584,310 | 895,239 |
| Turkey | 196,119 | ... | 289,152 |
| United States | 309,870 | 106,494 | ... |
| Italy (Sardinia) | ... | 387,165 | 1,531,009 |
| Brazil | ... | 271,573 | 359,193 |
| British India | ... | 426,575 | 854,784 |
| Germany | ... | ... | 2,239,947 |
| Egypt | ... | ... | 649,846 |
| Malta | ... | ... | 388,057 |
| Other Countries | 2,966,844 | 3,965,156 | 3,609,482 |
| Total | 7,348,328 | 11,495,092 | 18,702,551 |
| Declared Value | £3,321,539 | £5,506,890 | £8,378,944 |

No. 10. Patent Fuel Exported from Great Britain to foreign countries, with the declared value at port of shipment, and average value per ton. In the year 1854 the quantities exported amounted to 50,920 tons, of the value of £97,249, giving an average value of 14*s.* 10*d.* per ton. Since that date the returns are as follows: *—

| Year. | Quantities. | Value. | Average price per Ton. | Year. | Quantities. | Value. | Average price per Ton. |
|-------|-------------|---------|------------------------|-------|-------------|---------|------------------------|
| | Tons. | £ | s. d. | | Tons. | £ | s. d. |
| 1855 | 84,860 | 58,985 | 13 10 | 1868 | 129,258 | 85,397 | 13 2 |
| 1856 | 69,462 | 42,648 | 12 4 | 1869 | 156,520 | 97,878 | 12 6 |
| 1857 | 84,032 | 53,437 | 12 8 | 1870 | 198,377 | 123,742 | 12 0 |
| 1858 | 67,645 | 43,313 | 12 2 | 1871 | 198,115 | 125,034 | 12 1 |
| 1859 | 75,080 | 45,266 | 12 0 | 1872 | 207,241 | 189,335 | 18 3 |
| 1860 | 90,743 | 55,350 | 12 2 | 1873 | 278,410 | 317,878 | 22 10 |
| 1861 | 79,717 | 47,374 | 11 10 | 1874 | 309,894 | 310,917 | 20 0 |
| 1862 | 78,821 | 47,860 | 12 2 | 1875 | 253,331 | 203,681 | 16 1 |
| 1863 | 67,288 | 38,510 | 11 5 | 1876 | 231,968 | 164,738 | 14 2 |
| 1864 | 90,964 | 55,110 | 12 1 | 1877 | 205,511 | 114,313 | 11 1 |
| 1865 | 112,737 | 69,390 | 12 3 | 1878 | 221,867 | 118,730 | 10 8 |
| 1866 | 188,548 | 115,693 | 12 3 | 1879 | 356,776 | 181,196 | 10 2 |
| 1867 | 150,051 | 96,493 | 12 10 | 1880 | 385,993 | 197,360 | 10 3 |

* "Trade and Navigation Returns."

Population Employed in Coal-mining in the United Kingdom.

—All the early returns on this subject were careful estimates made by the Inspectors, each in his own district. Since 1872, when the “Coal Mines Regulation Act” came into operation, very complete returns have been published in the annual reports of H.M. Inspectors of Mines, in which the numbers engaged under and above ground are separately distinguished, together with the quantity of coal raised, which appear in the annexed table, to which is added the average production per man in each year :—

| Year. | PERSONS EMPLOYED. | | Total. | Coal Raised. | Average per Man. |
|-------|-------------------|------------------|---------|--------------|---------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 407,808 | 106,341 | 514,149 | 128,680,131 | 250 |
| 1874 | 428,611 | 110,218 | 538,829 | 126,590,108 | 235 |
| 1875 | 427,017 | 108,828 | 535,845 | 133,306,485 | 245 |
| 1876 | 409,229 | 105,303 | 514,532 | 134,125,166 | 266 |
| 1877 | 395,025 | 99,366 | 494,391 | 134,179,968 | 278 |
| 1878 | 382,979 | 92,350 | 475,329 | 132,612,063 | 279 |
| 1879 | 385,179 | 91,631 | 476,810 | 133,720,393 | 280 |
| 1880 | 391,381 | 93,552 | 484,933 | 146,969,409 | 303 |

These figures indicate the increased efficiency of the coal-miner in recent years. When, in 1873, the year of the Coal Famine, the average output per man was 250 tons per annum, a less number of persons were employed than in the succeeding year when the average fell to 235 tons per man, the diminished production being due to the larger amount of unskilled labour employed. Since 1874, however, the efficiency of the coal-miner has gone on increasing, till, in 1879, the average amounted to 280 tons, and in 1880 to 303 tons per annum.

Of the population employed in coal-mining, the annexed abstract will show the numbers and respective ages of all engaged under and above ground in the collieries of the United Kingdom in the year 1873, when the first return appeared, and for the years 1879 and 1880; the last-named year showing an increase of 8,123 persons employed in excess of the previous year, and an increase of 23 tons per man :—

| Ages. | 1873. Persons Employed. | 1879. Persons Employed. | 1880. Persons Employed. |
|-----------------------|----------------------------|----------------------------|----------------------------|
| | Nos. | Nos. | Nos. |
| <i>Under Ground—</i> | | | |
| From 10 to 12 . . | 1,202 | 446 | 428 |
| „ 12 to 13 . . | 11,309 | 4,881 | 4,868 |
| „ 13 to 16 . . | 45,931 | 35,993 | 36,162 |
| Above 16 . . | 349,366 | 343,859 | 349,923 |
| <i>Above Ground—</i> | | | |
| Males, 10 to 13 . . | 2,070 | 671 | 552 |
| Females, 10 to 13 . . | 31 | 9 | 10 |
| Males, 13 to 16 . . | 6,957 | 6,572 | 7,037 |
| Females, 13 to 16 . . | 790 | 502 | 354 |
| Males, above 16 . . | 91,110 | 79,546 | 81,323 |
| Females, above 16 . . | 5,383 | 4,331 | 4,276 |
| Total . . . | 514,149 | 476,810 | 484,933 |

Resources and Probable Duration of the Coal-fields of the United Kingdom.—The total quantity of coal ascertained by the Royal Coal Commission as available for future use, amounts, in the aggregate, to 146,180,285,398 tons. Of this quantity 90,207,285,398 tons exist at depths not exceeding 4,000 feet in known coal-fields, and 56,273,000,000 tons as the probable amount of coal, under Permian and other overlying formations, at depths of less than 4,000 feet; 40 per cent. being deducted for loss and other contingencies. The details of quantities under the first head, visible coal-fields, appear in the annexed table from the Coal Commission Report.* Side by side are given the quantities of coal remaining and available for future use from 1880, amounting to 79,015,613,038 tons, divided as follows in the visible coal-fields of the United Kingdom :—

| | TONS. |
|--------------------------------------|-----------------|
| England and Wales | 69,192,056,317 |
| Scotland | 9,669,172,642 |
| Ireland | 164,384,079 |
| Total known coal-fields | 79,015,613,038 |
| Concealed coal-fields | 56,273,000,000 |
| Total coal available, 1880 | 135,288,613,038 |

With these available resources, and an annual output of nearly 147 millions of tons, supplies are yet ensured for 920 years hence.

* Vol. I., p. 9. C. 435. 1871.

| Commission. | No. | Name of Coal-field. | Amount of Coal in statute tons, to depths not exceeding 4000 feet, and after the necessary deductions. | Amount of Coal remaining and available for future use from the year 1880. |
|--|------|--|--|---|
| | | | Tons. | Tons. |
| | | ENGLAND AND WALES. | | |
| Messrs. Vivian and Clark | 1 | South Wales | 32,456,208,913 | 32,302,046,783 |
| Mr. Dickinson | 2 | Forest of Dean | 265,000,000 | 257,623,705 |
| Mr. Prestwich | 3 | Bristol | 4,218,970,762 | 4,207,076,209 |
| Mr. Woodhouse | 4 | Warwickshire | 458,652,714 | 450,179,258 |
| Mr. Hartley | 5 | South Staffordshire | | |
| " | 6 { | Coalbrookdale and Forest of Wyre | 1,906,119,768 | 1,789,674,293 |
| " | 7 { | Clee Hills | | |
| Mr. Woodhouse | 8 | Leicestershire | 836,799,734 | 826,799,734 |
| Mr. Dickinson | 9 | North Wales | 2,005,000,000 | 1,986,229,493 |
| " | 10 | Anglesea | 5,000,000 | |
| Mr. Elliot | 11 | North Staffordshire | 3,825,488,105 | 3,784,377,741 |
| Mr. Dickinson | 12 { | Lancashire and Cheshire | 5,546,000,000 | 5,270,686,699 |
| Mr. Woodhouse | 13 | Midland | 18,172,071,433 | 17,928,908,710 |
| " | 14 | Black Burton | 70,964,011 | 70,964,011 |
| Messrs. Forster and Elliot | 15 { | Durham and Northumberland | 10,036,660,236 | 9,734,261,887 |
| " | 16 | Cumberland | 405,303,792 | 391,123,499 |
| | | SCOTLAND. | | |
| Mr. Geddes | 17 | Edinburgh | 2,153,703,360 | |
| " | 18 | Lanarkshire | 2,044,690,216 | |
| " | 19 | Fifeshire | 1,098,402,895 | |
| " | 20 | Ayrshire | 1,785,397,089 | |
| " | 21 | East Lothian | 86,849,880 | |
| " | 22 | Frith of Forth | 1,800,000,000 | |
| " | 23 | Dumfriesshire | 358,173,995 | |
| " | 24 | West Lothian | 127,621,800 | |
| " | 25 | Perthshire | 109,895,040 | |
| " | 26 | Stirlingshire | 106,475,436 | |
| " | 27 | Clackmannanshire | 87,563,494 | |
| " | 28 | Dumbartonshire | 48,613,320 | |
| " | 29 | Renfrewshire | 25,881,285 | |
| " | 30 | Argyleshire | 7,223,120 | |
| " | 31 | Sutherlandshire | 3,500,000 | |
| " | 32 | Roxburghshire | 70,000 | |
| | | IRELAND. | | |
| Professor Jukes * and Professor Hull . . . } | 33 | Ballycastle (Antrim Co.) | 16,000,000 | |
| " | 34 | Tyrone | 6,300,000 | |
| " | 35 | Leinster (Queen's Co.) | 77,580,000 | |
| " | 36 | Tipperary | 25,000,000 | |
| " | 37 | Munster (Clare, &c.) | 20,000,000 | |
| " | 38 | Connaught | 10,800,000 | |
| | | Total | 90,207,285,398 | 79,015,613,038 |

The details of coal remaining unwrought, as estimated by Professor Ramsay, and contained under the second head,

* The estimate of the quantity of coal in Ireland, commenced by Professor J. B. Jukes, F.R.S., was on the decease of that gentleman completed by Professor E. Hull, F.R.S., author of "The Coal Fields of Great Britain."

under Permian and other overlying formations, amounting to 56,273,000,000 tons, is as follows : *—

| Districts. | Under. | Square Miles. | Tons. |
|---|---------------------|---------------|----------------|
| Warwickshire | Permian | 73 | 2,165,000,000 |
| Warwickshire, south of Kingsbury . | New Red | 5 | 150,000,000 |
| Warwickshire, north of Atherstone . | " | 6 | 179,000,000 |
| Leicestershire, Moria District . . | Permian | 15 | 1,000,000,000 |
| Leicestershire, Coleorton District . | New Red | 25 to 28 | 790,000,000 |
| District between the Warwickshire and South Staffordshire Coal-field | Permian and New Red | 116 | 3,460,000,000 |
| District between South Staffordshire and Shropshire Coal-fields | " | 195 | 5,800,000,000 |
| Between the South Staffordshire and Coalbrookdale Coal-fields, to the Cheadle and North Staffordshire Coal-fields | " | 200 | 4,580,000,000 |
| East of the Denbighshire Coal-field . | " | 50 | 2,482,000,000 |
| West and South-West Border of the North Staffordshire Coal-field | " | 50 | 1,500,000,000 |
| Cheshire, West of the Kerridge | " | 9 | 62,000,000 |
| Cheshire, between Woodford Fault and Denton | " | 36 | 1,790,000,000 |
| Lancashire, East and West of Manchester | " | 30 | 350,000,000 |
| Lancashire, West of Eccles and Stretford, to Prescott, Runcorn, and Hale-on-the-Mersey . . | " | 130 | 3,883,000,000 |
| The Wirrell, the Mersey, and country to the North | New Red | 216 | 3,000,000,000 |
| Yorkshire, Derbyshire, and Nottinghamshire | Permian and New Red | 900 | 23,082,000,000 |
| Vale of Eden | " | 40 | 1,593,000,000 |
| Ingleton and Burton | " | 3 | 33,000,000 |
| Severn Valley | New Red Marl | 45 | 400,000,000 |
| Scotland | Permian | † | † |
| Ireland, Tyrone | New Red Marl | 4 | 27,000,000 |
| Total of concealed coal-fields | | | 56,273,000,000 |


* "Coal Commission Report," Vol. I., p. xi.

† No estimate.

THE
COAL AND IRON INDUSTRIES
OF
THE UNITED KINGDOM.

PART II.

IRON INDUSTRIES.



THE
COAL AND IRON INDUSTRIES
OF
THE UNITED KINGDOM.

PART II.
IRON INDUSTRIES.

INTRODUCTORY CHAPTER.

THE MINERALOGICAL CHARACTERS OF THE PRINCIPAL IRON ORES.

By FRANK RUTLEY, Esq., F.G.S.

THE principal ores of iron are oxides and carbonates, which frequently contain various impurities; the carbonates especially being often rendered impure by a large admixture of argillaceous matter.

Pure metallic iron is very seldom found, except in meteorites, and must be regarded as a mineralogical rarity.

Arsenic is derived from mispickel, the bisulphide and arsenide of iron, and sulphur is sometimes procured from pyrites, although native sulphur is the principal source of supply. Alum is also manufactured from pyritous shales, the pyrites by its decomposition and oxidation giving rise to sulphuric acid, which acts upon the shales and, with the addition of potash compounds, results in the formation of hydrous sulphate of alumina and potash.

The following ores, which are useful to the iron-smelter, are here briefly described:—

Oxides.

Magnetite, Hematite, Limonite, Göthite.

Carbonates.

Spathose Iron Ore or Chalybite, Clay Ironstones.

Magnetite (Fe_3O_4).—Approximate composition, Peroxide of Iron = 69, Protoxide of Iron = 31. The iron is sometimes partly replaced by a little magnesium or titanium. It crystallizes in the cubic system, commonly in the form of the octahedron or of

the rhombic dodecahedron. The cleavage is parallel to faces of the octahedron. It is also found in granular and massive conditions, and occasionally in the form of sand, in which case it is readily separated from foreign admixtures by means of magnets.

Magnetite is iron-black in colour and opaque. Its lustre is metallic or sub-metallic. The streak is black; the fracture sub-conchoidal; the hardness, 5·5 to 6·5 of Moh's scale, and the specific gravity, 4·9 to 5·2. It is strongly magnetic, and frequently shows polarity, but loses its magnetic properties when heated in the oxidising flame of the blow-pipe.

Magnetite is very difficultly fusible before the blow-pipe. With borax, in the oxidising flame, the bead is yellow when hot and colourless when cold. The addition of considerably more of the powdered mineral renders the bead red when hot and yellow when cold. In the reducing flame the bead becomes green (the colour of ordinary bottle glass).

Magnetite is soluble in hydrochloric acid. It becomes reduced by the action of organic matter to the condition of protoxide, which may be converted into the carbonate (Chalybite or Siderite). Further oxidation of magnetite results in the formation of hematite, the sesquioxide, which, in its hydrated condition, constitutes limonite.

Hematite, Sesquioxide of Iron (Fe_2O_3). Oxygen = 30, Iron = 70 per cent.—Titanium and magnesium sometimes replace part of the iron. Hematite occurs in massive, granular, columnar, stalactitic, reniform ("*Kidney ore*"), micaceous and earthy (*Reddle*) conditions. It also occurs crystallised (*Specular iron*) in the rhombohedral system, commonly in modified rhombohedrons. The cleavage is parallel to faces of the rhombohedron and to the basal plane, but is frequently indistinct. Hematite is, under ordinary conditions, opaque and dark steel-grey or iron-black, but in very thin scales or crystals it appears blood-red to orange-red by transmitted light. This may be well seen in the microscopic crystals which occur so plentifully in the Carnallite of Stassfurth. The fracture is sub-conchoidal or uneven, and the streak is cherry-red. The lustre is metallic and sometimes splendid, as in the specular varieties; but the impure and ochreous conditions have a dull or earthy appearance. The hardness ranges from 5·5 to 6·5, and the specific gravity from 4·2 to 5·3.

It is sometimes attractable by the magnet and at times shows magnetic polarity. Hematite occasionally contains a considerable admixture of argillaceous or siliceous impurities.

Before the blow-pipe it is infusible. When heated on charcoal in the reducing flame it becomes magnetic. In the borax bead it behaves like magnetite. It is soluble in strong hydrochloric acid.

Limonite.—Hydrous Sesquioxide of Iron, having the formula $2 \text{Fe}_2\text{O}_3, 3 \text{H}_2\text{O}$.—It occurs in stalactitic and mammillated forms with a radiating fibrous structure like that of the reniform varieties of hematite. It is usually of a brown colour, sometimes yellowish-brown, and has a rather dull sub-metallic or silky lustre, often with a shiny black coating. It is also met with in an earthy and porous condition, called bog-iron-ore or morass-ore, from its occurrence in swamps, and it is occasionally pisolitic in structure (pea-iron-ore). The earthy varieties also constitute brown and yellow ochres, which are employed as pigments. Impure argillaceous varieties are known as clay-ironstone, a name also used to designate the impure argillaceous varieties of chalybite, siderite or spathose iron.

Limonite may be distinguished from hematite by giving a yellowish-brown streak. The hardness of limonite is 5 to 5.5, and the specific gravity 3.6 to 4. It affords the usual iron reactions before the blow-pipe, and yields water when heated. Limonite is often associated with manganese ores.

Göthite.—Hydrous Sesquioxide of Iron, having the formula $\text{Fe}_2\text{O}_3, \text{H}_2\text{O}$.—It frequently contains some silica and manganese, and occasionally traces of phosphorus. The water usually amounts to about 10 or 11 per cent. It crystallizes in the rhombic system, generally in right rhombic prisms longitudinally striated and often tabular in form. It is likewise met with in fibrous, reniform, stalactitic, and earthy conditions. It is blackish-brown, yellowish or reddish in colour. The streak is brownish yellow, and the lustre adamantine. Göthite has a hardness of 5 to 5.5, and its specific gravity ranges from 4 to 4.4. It is often associated with limonite and hematite. Heated in the closed tube göthite gives off water and is converted into red sesquioxide. With the fluxes it affords the usual iron, and sometimes the manganese reaction. It is soluble in hydrochloric acid.

Franklinite.—A Sesquioxide of Iron and Manganese, with over 11 per cent. of oxide of zinc, is an important iron ore in America, but has not been met with in Great Britain.

Spathose Iron Ore (Chalybite, Siderite).—Carbonate of Iron (Fe CO_3).—Often with a little lime, magnesia and manganese. Crystallizes in the rhombohedral system, the common form being the rhombohedron, the faces of which often show a well-marked curvature, similar to that seen in crystals of pearlspar and dolomite, in which minerals the isomorphous substances, lime and magnesia, take the place of the peroxide of iron. Spathose iron ore also occurs in massive and crystalline-granular conditions, as in the ore from the Brendon Hills and Tintagel. Its colour is pale brown or yellowish, sometimes brownish-red and brownish-black. It is generally opaque, but occasionally crystals are translucent. It is brittle and the fracture is uneven, but it often breaks up along well-marked cleavage planes, which coincide with the faces of the rhombohedron. The lustre is pearly, sometimes vitreous. The hardness is 3·5 to 4·5, and the specific gravity, 3·7 to 3·9. Before the blow-pipe, alone, it blackens and becomes magnetic, and with the fluxes affords the usual iron reactions. In hot acids it effervesces rapidly, but is only slowly affected by them in the cold.

Clay Ironstone is an impure massive variety of the preceding mineral and, as its name implies, contains a considerable admixture of argillaceous matter. In the coal measures it occurs in bands, usually of a dark brownish or blackish colour, containing carbonaceous matter, and known as "black band," and also in nodules of spherical or lenticular form; frequently with rusty surfaces, and with a concentrically-zoned structure; while, at times, a curious structure, known as "cone in cone," is developed, in which case the block, when broken, reveals more or less regular cones lying side by side, their apices directed towards the same point and their surfaces marked by irregular transverse corrugations, and these cones contain other smaller ones, which may easily be detached or picked out when loosened by a blow. The clay ironstone of the Middle Lias commonly shows a fine oolitic structure, and in the Cleveland district constitutes a valuable ore, which, however, sometimes contains siliceous impurities. The pisolitic iron ore of Rosedale in Yorkshire consists in great part of carbonate of iron, but also contains a considerable amount of the magnetic oxide.

The titaniferous iron ores, although worked in other countries do not occur in the British Isles in sufficiently large deposits to

render them a matter of commercial interest. Titaniferous iron is of frequent occurrence as a constituent of many of our eruptive rocks, but it is disseminated through them in such minute crystals and grains that it needs no further mention in this work, and the same may be said of the microscopic crystals of magnetite which occur under similar conditions.

CHAPTER I.

DURHAM AND NORTHUMBERLAND IRON INDUSTRIES.

Ironstone of the Coal measures and analyses—Iron-ores of the Carboniferous Limestone and analyses—Production of Iron ore—Population employed in Iron Mining—Pig iron manufacture, early history—Production of Durham and Northumberland—Malleable Iron Works—Coal and Iron Ore used in Pig iron manufacture—Quantities of Iron ore employed and Sources of Supply.

Ironstone of the Coal Measures and Analyses.—The coal measures yield two kinds of ironstone known as "Clay Band" and "Black Band," the former is an argillaceous carbonate of iron generally occurring in nodular masses; the latter term is applied to bands of carbonaceous matter, largely mixed with carbonate of iron. Formerly, the first-named variety furnished nine-tenths of the iron produced in Great Britain; it does not, however, exist abundantly in the Great Northern, or Lancashire and Cumberland coal-fields. At present the Clay Bands and Black Bands furnish one-fourth of the annual produce of the pig-iron of the kingdom. The coal-fields in which they are extensively worked being Shropshire, Derbyshire, Yorkshire, North and South Staffordshire, South Wales, and Scotland, the ironstone being found in irregular nodules, interspersed through the clays and shales of the coal measures, and being often worked in conjunction with coal seams in the same pits.

Ironstone has been worked from time to time, though in inconsiderable quantities, in the Wear district; occurring in a continuous band above the seam of coal known as the High Main, and separated from it by a distance of 18 inches. This ironstone measure is $4\frac{1}{2}$ inches thick, and was formerly worked on Waldridge Fell for the Whitehill ironworks, and subsequently at Urpeth and its vicinity for the blast furnaces at Birtley, long since dismantled. At Wylam, upwards of forty years since, ironstone of very fair quality was obtained, yielding from 35 to 37 per cent of metallic iron, and at that time said to

cost 11s. 6d. per ton. This measure has a thickness of $10\frac{1}{2}$ inches, contained in four bands occurring in a section of four feet. Another measure is stated to have cost 7s. 6d. per ton for working; the ironstone yielding an average of 80 per cent. of metallic iron.

At Shotley Bridge, again, on the western edge of the coal-field, and consequently low down in the series, is a deposit of ironstone which has been far more extensively worked than any other seams found in the coal measures. According to a description given by the late Mr. William Cargill, in a working having a section of about 7 feet in height, from 12 to 15 inches of stone were obtained from six or seven bands, the ironstone costing from 7 to 8 shillings per ton. At a depth of $4\frac{1}{2}$ fathoms below it and lying above 20 inches of coal, is a bed of shale about 3 feet thick, containing from 6 to 7 inches of ironstone. The total yield of these two seams contained in an acre of ground has been estimated at 5,324 tons. At Stiddle Moor, near Bellingham, and at Ridsdale, ironstone, in the carboniferous limestone series, as well as in a few other localities (as at Brinkburn and Rothbury), has been wrought in recent years. The quantities obtained are, however, unimportant, not exceeding 5,000 tons per annum. Clay ironstone in smaller quantities occur frequently in the shales of the carboniferous limestone series of Northumberland; and at numerous places over the western moorlands there are slag heaps showing the sites of ancient furnaces. These are of very ancient date, some of them being believed to be Roman, charcoal being the fuel with which the ore was smelted. In a general sense, as has been already stated, the argillaceous ironstone of the coal measures in the Great Northern Coal-field contributes in a very small degree at the present time to the requirements of the 74 blast furnaces built in Durham and Northumberland, many of which have a height exceeding 100 feet, and of immense capacity, producing annually, when in full work, from 15 to 16 thousand tons of pig-iron, and sometimes even more.

The measures of ironstone existing in this coal-field are few and limited in extent. One of the many advantages possessed by Great Britain in the manufacture of iron arises from the number and variety of argillaceous and black band ironstones, which alternate with the beds of coal in many of its coal-fields, and, in consequence of which, the same localities, and, in many

instances, the same mineral working, frequently furnish both the ore and the fuel required to smelt it. These conditions as regards clay ironstone in the Durham and Northumberland coal-field do not exist, inasmuch as in this coal-field these measures of ironstone are almost absent; the same may be said of Lancashire, while in the coal-fields of Scotland, Yorkshire, Derbyshire, North and South Staffordshire, North and South Wales, and Shropshire, the ironstone measures are numerous, and afford an abundant supply of ironstone.

The yield of ironstone varies according to the thickness and regularity of the beds, and the regularity with which the nodules of ironstone are disseminated.

The ironstone of Ridsdale, Hareshaw, and from Consett, near Shotley Bridge, in the coal measures, previously referred to, have been examined by Dr. Richardson, with the following results:—

| Constituents. | Ridsdale. | Hareshaw. | Shotley Bridge. |
|---------------------------|-----------|-----------|-----------------|
| Iron. | 34·86 | 36·51 | 36·68 |
| Lime and magnesia | 9·00 | 11·90 | 4·65 |
| Clay | 14·00 | 7·15 | 15·05 |
| Loss by heat | 31·02 | 34·07 | 31·91 |

It would appear that the samples from which the above analyses were made, were perfectly clean and free from adhering shale, which will account for the difference of metal between the analyses and the actual yield in the furnace, which did not exceed 26 per cent.

Iron Ores of the Carboniferous Limestone, and Analyses.
—In Alston Moor, many of the mineral veins traversing the limestone contain a considerable quantity of a hydrated peroxide of iron, as well as amorphous carbonate of iron. These ores were formerly worked to a limited extent at Nent Head by the Messrs. Bell Brothers, and smelted at their works at Wylam. The iron obtained from these, as well as from similar ores of the same district, was of excellent quality; but unfortunately the supplies were too uncertain and the working too costly. The ore in the veins themselves was at one time a tolerably pure carbonate, yielding, perhaps, 80 per cent. or more of iron, but it gradually passed into carbonate of lime from which it was with difficulty distinguished. In the lead-mining district of Allen-

heads, sparry iron ores occur, both in the regular lodes and in the flats which insinuate themselves from them laterally into the limestone. "Adjoining Weardale this character is still more pronounced, and in the neighbourhood of Stanhope Burn the veins are so 'ridered'—so charged with the ore—that at a spot where several of them occur in close proximity, and interlacing 'strings' additionally enrich the ground. The whole surface has been removed from a large area by the Weardale Iron Company, and the rock absolutely quarried away, a considerable amount of lead ore being separated during the operation."* The ores raised by the above-named company are smelted at the Tow Law Iron Works, near Darlington. The following table gives the production and value of the Spathose ore raised in the Weardale district since the year 1870, the average price during the past few years being estimated at 12s. per ton:—

| Year. | Ore. | Value. |
|-------|---------|--------|
| | Tons. | £ |
| 1870 | 100,332 | 25,083 |
| 1871 | 88,449 | 22,112 |
| 1872 | 97,953 | 36,730 |
| 1873 | 99,393 | 39,813 |
| 1874 | 85,491 | 51,388 |
| 1875 | 34,828 | 21,626 |
| 1876 | 24,202 | 14,521 |
| 1877 | 51,344 | 30,806 |
| 1878 | 35,619 | 21,371 |
| 1879 | 16,679 | 10,007 |
| 1880 | 41,357 | 24,814 |

The ore is wrought in open quarry workings as well as mined in underground levels, and includes in these quantities some siliceous hematite.

Analyses of these ores. In the Iron Ores of Great Britain † appears the following, giving the composition of the Weardale ore. The first, from "West Level," made by Mr. John Spiller, is thus described:—

"An altered Spathose ore, in which the greater part of the carbonate of iron has been converted into hydrated peroxide, which in many places still shows the structure of the original ore. The portions which are undecomposed occur in irregular nodular-like form, of a pale brownish-grey colour; these are surrounded

* "Iron Ores of Great Britain," Part I., p. 19.

† Ibid, p. 55.

by a mass varying from crystalline to earthy, of which the colour is from a snuff-brown to a dark purplish-brown. The streak varies with the colour from yellowish to reddish-brown.

“A small quantity of fluor spar was attached to one side of the specimen, but was not included in the portion selected for analysis.”

RESULTS TABULATED.

| | |
|----------------------------------|--------|
| Peroxide of iron | 49.50 |
| Protoxide of iron | 10.77 |
| Protoxide of manganese | 3.06 |
| Alumina | 0.43 |
| Lime | 5.68 |
| Magnesia | 1.20 |
| Silica | 0.29 |
| Carbonic acid | 14.49 |
| Phosphoric acid | 0.01 |
| Suphuric acid | trace |
| Bisulphide of iron | 0.03 |
| Water hygroscoptic | 1.81 |
| „ in combination | 6.63 |
| Organic matter | trace |
| Insoluble residue | 6.90 |
| | <hr/> |
| | 100.80 |

INSOLUBLE RESIDUE.

| | |
|----------------------------|-------|
| Silica | 6.35 |
| Alumina | 0.41 |
| Peroxide of iron | 0.07 |
| Lime | 0.01 |
| Magnesia | 0.01 |
| Potash | 0.05 |
| | <hr/> |
| | 6.90 |

The total amount of metallic iron contained in this ore amounts to 48.02 per cent. A trace of lead was found in 400 grains of the ore.

Another variety of Weardale ore from the Rispey vein near Rookhope is thus described by Mr. A. Dick:—“Spathose ore: easily scratched by the file; lustre, semi-vitreous; colour, yellowish grey; streak, white; fracture, crystalline. Some portions are much darker than others. When a mass of the ore is digested in hydrochloric acid till all carbonates are dissolved, there remains a skeleton of quartz, having the shape and size of the original mass, containing casts of the crystals which have been dissolved. The dark-coloured parts of the ore leave a dark

skeleton, which, when exposed to the vapour of hydrofluoric acid till all silica is removed, leaves a small amount of matter, having a dark grey colour. When this is washed with hydrochloric acid and water, there remains a very small amount of black matter, which burns when heated in the air, and leaves no residue. It is therefore carbonaceous matter."

RESULTS TABULATED—ORE DRIED ABOVE 100° C.

| | |
|----------------------------------|--------|
| Protoxide of iron | 49·47 |
| Protoxide of manganese | 2·42 |
| Alumina | trace |
| Lime | 3·47 |
| Magnesia | 3·15 |
| Carbonic acid | 37·71 |
| Phosphoric acid | trace |
| Silica | 1·20 |
| Sulphuric acid | trace |
| Bisulphide of iron | 0·08 |
| Organic matter | trace |
| Insoluble matter | 3·77 |
| | <hr/> |
| | 101·27 |

The insoluble residue contained of silica 3·73 per cent., and of alumina containing a trace of iron 0·06 per cent.; the iron contained in the ore being equivalent to 38·56. In a note appended to the analysis it is stated that no metal precipitable by sulphuretted hydrogen from the hydrochloric acid solution of 1,000 grains of ore was detected.

Persons employed in Iron-mining in Durham.—Iron-mining has been chiefly confined to the district of Weardale, where a spathose and siliceous variety of hematite has long been wrought. The number of persons employed in 1854 amounted to 610. The quantity of ore raised at that time has not been recorded. In recent years the Reports of Her Majesty's Inspectors of Mines afford the necessary data, showing the numbers employed under and above ground, with the quantity of iron ore raised. These returns, it should be explained, only include those mines coming under the operation of the "Mines Regulation Act, 1872 and 1875," and do not include those workings above ground. The total output of the iron-mines of the county has already appeared under production of iron ore :—*

* Reports of H.M. Inspectors of Mines.

| Year. | PERSONS EMPLOYED. | | Total. | Iron Ore Raised. | Average per Man. |
|-------|-------------------|------------------|--------|------------------|---------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 266 | 47 | 313 | 55,981 | 178 |
| 1874 | 224 | 39 | 263 | 54,660 | 207 |
| 1875 | 195 | 29 | 224 | 45,317 | 202 |
| 1876 | 93 | 14 | 107 | 14,961 | 140 |
| 1877 | 118 | 21 | 139 | 31,858 | 229 |
| 1878 | 99 | 17 | 116 | 19,204 | 166 |
| 1879 | 63 | 10 | 73 | 8,508 | 116 |
| 1880 | 96 | 9 | 105 | 24,439 | 232 |

Pig Iron Manufacture.—In the Report of the British Association for the year 1863, at the Newcastle-upon-Tyne meeting, among the many interesting papers, appears one by Mr. Isaac Lowthian Bell, who gives a historical account of the manufacture of pig iron in the north of England, from which many of the following facts have been drawn.

Notwithstanding the varied character of the different ores of the district under review, and the want of indication of metallic contents of some, the property that even these have of “rusting” on exposure to air and moisture appears to have made known the existence of all at a very early period of our history. The labours of Hodgson, Wallis, and others, leave little doubt that the smelting or reduction of iron ore was carried on to a considerable extent in this part of the country during its occupation by the Romans. Vast heaps of iron scorix may be seen on the moors in the parishes of Lanchester and Chester-le-Street, in the county of Durham, and in the valleys of the Reed and the Tyne on the mountain limestone in Northumberland. It is remarkable that none of these are very remote from one or other of the Roman stations which are scattered over these two counties.

Hitherto all these smelting operations have reference to the small bloomery or hearth, in which a little ore was smelted by the use of charcoal, the fire being urged by the wind in exposed situations, or subsequently by rude bellows, that a “bloom” of malleable iron was obtained. The German colony of iron-workers at Shotley Bridge was established in the reign of William III., and at some time or other afterwards, a small high blast furnace, five or six feet in the boshes, was erected, the

remains of which, according to reliable information, are still visible. Wallis, in his *History of Northumberland*, published in 1769, mentions an iron work which existed some years previously at Lee Hall, near Bellingham, under the management of a Mr. Wood, who made a good deal of bar iron, but charcoal becoming scarce, he removed to Lancashire. Although bar iron only is mentioned, there is no doubt from the remains existing, that pig iron was also produced here. Charcoal iron was also smelted from some of the bands of clay ironstone at Bedlington, where the old calcining kilns were until recently visible. No iron, however, has, as far as can be ascertained, been made there for more than a century.

The inroads which iron-smelting and other metallurgical operations, &c., had made upon the forests were such, that in the reign of Queen Elizabeth four Acts of Parliament were passed, to restrict the consumption of timber in the manufacture of iron.

Towards the close of the last century, Mr. J. Cookson, who had recently purchased the Whitehill Estate, near Chester-le-Street, was the first to erect and work a blast furnace in the North of England with coal previously coked. The Whitehill furnace was 35 feet high, 12 feet across the boshes, and produced 25 tons of iron per week. The blast was supplied by a bellows worked by a water-wheel placed on Chester Burn. The iron made at the Whitehill furnace was used for colliery castings and Government ordnance. Frequent interruptions through want of water to drive the wheel led at length to the furnace being "gobbed" * and ultimately abandoned about the close of the last century.

Whatever advantages in point of materials any district might be possessed of, its power for turning them to profitable account depended, at that time, on the existence of a fall of water sufficient to drive the necessary blowing apparatus. The discoveries of Watt prevented the want of hydraulic power being any longer an impediment, and in a short time the obedient steam-engine was appointed to supply the necessary blast to iron furnaces.

Commencing with the present century: in the year 1800 the

* "Gobbed" or "Gobbing," a term in Metallurgy, the stopping of the blast furnace by the agglomeration of the charge within it.

Tyne Iron Company erected two blast furnaces at Lemington in Northumberland and a steam blowing-engine to impel the blast. The make of one of these furnaces in 1812 was 2,547 tons, when cold blast alone was employed, the ironstone used being obtained from the thin bands of the coal-measures of the district.

It was about this period that iron works were established at Newburn, some five miles distant from Newcastle-upon-Tyne, which in recent years have attained considerable importance. These works, now known as the Newburn Steel Works, are surrounded by much that is interesting: originally established about the year 1810 as a file manufactory by the father of the present proprietors, Messrs. John Spencer and Sons, it may be regarded as one of the oldest works in the North of England. Some of the plant put down at the period referred to yet remains, and is utilised; and an old overshot water-wheel which was originally the motive-power used, is still employed in turning a grinding-stone in the modern rolling-mill, which has taken the place of the original one. This firm, at an early period, in addition to other branches of industry, commenced the manufacture of steel by the cementation process, and in 1876 they went largely into the manufacture by the Siemens and Siemens Martin process. The three furnaces at present in operation are capable of producing 200 tons of steel per week, while two crucible furnaces of 24 pots each, equal to a production of 24 tons per week; in addition to which are also auxiliary coke crucibles of two pots each. This firm was originally the sole manufacturers of the volute springs, now so extensively used on railways as a buffer draw-spring, and still enjoys a high reputation.

The neighbourhood of Newburn possesses much of interest beyond its steel works. It was here that Stephenson lived for many years; Locke also sprung from that part, as did also the Hawthorns. Close alongside Newburn was the Wylam wagon way, which was the first plain plate railway line ever laid down. The first springs for railway purposes were made at these works, and for many years the surrounding firms were supplied with them, as well as many railways throughout the country. They were invented about the year 1847, by Mr. Baillie, also of Newcastle, who subsequently went out to Austria as chief of the state railways. At the period referred to the material employed was Swedish iron, but with the introduction of the Siemens Martin

process, a few years since, the firm were no longer dependent on other sources of supply.

The Lemington furnaces already referred to produced in the year 1823 some 2,379 tons of pig iron, from which it may be inferred that both furnaces were in blast but a part of the year. In the year 1825, iron rose in value to the unprecedented price of £12 per ton, and, a few years later, the Messrs. Perkins, Hunt, and Thompson, who were extensively engaged in coal-mining, erected two furnaces at Birtley, in Durham, near Chester-le-Street. These were put in blast in the year 1829, and in the following year produced 3,080 tons, the make of the Lemington furnaces the same year being 2,247 tons, or a total make of four furnaces in both counties of 5,327 tons. In the year 1831 the hot-blast was introduced into the works at Birtley, and in 1835 to those at Lemington, where, in the same year, was made 4,990 tons of iron, the cost of which, taken from the cost-book of the company, was as follows per ton of iron :—

| | £ | s. | d. |
|------------------------------|---|----|----|
| Ironstone | 1 | 18 | 1½ |
| Flux (chalk) | 0 | 2 | 7 |
| Coal (5 or 6 tons) | 0 | 7 | 0½ |
| Labour, &c. | 0 | 14 | 2½ |
| Sundries | 0 | 14 | 2 |
| Total | 3 | 16 | 1 |

The growing demand for iron about this period was such, that the ore obtained from the coal-measures was insufficient to meet the requirements of the iron master, and attention was directed to other sources of supply; these were found at Grosmont, near Whitby, and in 1836 a cargo of this stone was received at the works at Birtley. Subsequently attention was directed to the deposits of ironstone occurring in the mountain limestone. Ridsdale was the place selected, from the circumstance that coal could be obtained from a seam from 2 feet to 2½ feet thick, situated in the same geological formation. Before the year 1839, the Ridsdale Company put their first furnace in blast, increasing the number to three in the year 1841. In the same year another company sprung up at Hareshaw, working the same beds of ironstone and coal, and commenced operations with one furnace, subsequently adding two to the number. The iron produced at both of the above-named works was of a good quality; but the distance of the works from railways and markets added so considerably to

the cost of the iron that they could not compete with other works, and after a few years both works were closed and finally dismantled.

The Wylam furnace was put in blast in the year 1836. About the year 1840, Messrs. Bigge, Cargill, Johnson, and others, who had purchased from the projectors of the Ridsdale Works that concern, had their attention directed to the beds of ironstone described as lying in the coal-measures near Shotley Bridge. A pair of furnaces were speedily erected and put in blast; a larger company was formed, and an immense establishment constructed. Twelve blast furnaces were built, large rolling-mills, and all the necessary mines, mining villages, &c., followed in rapid succession. Until the year 1850, the furnaces went on devouring the iron ores found in the neighbourhood at an alarming pace, having in the meantime made extensive trials of those from the lead veins of Weardale. In the year 1850, the discoveries, in Cleveland promised relief from the impending famine, and in a very short time, in spite of a distance of about 50 miles, the ironstone of that district, with some hematite for a mixture, entirely superseded the ironstone lying adjacent to the furnaces.

The Walker Works of Messrs. Losh, Wilson and Bell, established about the year 1827 for the manufacture of bar iron, were enlarged in the year 1842, when the firm extended their operations by the erection of a blast-furnace for producing forge pig by smelting their mill furnace cinders with Whitby ironstone, and this was followed by a second furnace in the year 1844. These furnaces were the first ever built for smelting the recently discovered ironstone of Whitby.

About the year 1844, the Stanhope furnace, built by Mr. Cuthbert Rippon, was put in blast, and five others were erected at Tow Law by the Weardale Iron Company, for smelting the "rider ore" (carbonate and oxide of iron) from the lead veins. There is no doubt that owing to the extreme irregularity of this kind of material, immense labour and expense were at first incurred; and, as regards the quality of the produce, frequently with very unsatisfactory results. Better acquaintance, however, with the veins and their contents has enabled that firm to produce iron of a very high class; so good, indeed, as closely to resemble in composition and quality the celebrated German iron. For bar iron purposes it bears a high name, and has, like its prototype in Germany, been found well adapted for the manufacture of the

finer kinds of steel; an application, as is well known, confined exclusively to the purer descriptions of metal.

The Witton Park Works were erected in the year 1846, in the Auckland district, by the Messrs. Bolckow and Vaughan for smelting ironstone expected to be obtained in that vicinity. These hopes were not, however, realised, and the neighbourhood of Whitby was resorted to, as it had been by almost every furnace owner in the North.

To render available the bed of ironstone occurring in the mountain limestone, furnaces were erected at Brinkburn, and also at Haltwhistle; but after some experiments both works were abandoned. Again, at Bedlington, two furnaces were erected, to smelt the same ironstone formerly used at the Charcoal Works in that locality, with an admixture of Yorkshire stone, mill cinder, and other materials; but these, also, were only a short time in operation.

The following list will show the works existing and in operation in the year 1851 in both counties, with the number of furnaces built and in blast:—

NORTHUMBERLAND.

| Works. | Owners. | FURNACES. | |
|---------------------------|------------------------------|-----------|-----------|
| | | Built. | In Blast. |
| Hareshaw* | Hareshaw Iron Co. . . . | 3 | 0 |
| Ridsdale* | Ridsdale Iron Co.. . . | 3 | 0 |
| Tyne or Lemington | Tyne Iron Co. . . . | 2 | 2 |
| Walker | Loah, Wilson, & Bell | 2 | 2 |
| Witton Park | Bolckow & Vaughan. . . . | 4 | 3 |
| Wylam | Bell Brothers | 1 | 1 |
| | Total | 15 | 8 |

DURHAM.

| Works. | Owners. | FURNACES. | |
|-------------------------------|-------------------------|-----------|-----------|
| | | Built. | In Blast. |
| Birtley | Birtley Iron Co. . . . | 3 | 1 |
| Consett and Crookhall | Derwent Iron Co.. . . | 14 | 7 |
| Stanhope* | Weardale Iron Co. . . . | 1 | 1 |
| Towlaw | Weardale Iron Co. . . . | 5 | 2 |
| | Total | 23 | 11 |

* These iron works are situated in the Carboniferous Limestone District; the others on the Coal measures.

In the year 1830, as previously stated, the make of pig iron in the above counties was 5,327 tons. In the same year the make of pig iron in England and Wales was 615,917 tons, the yield of 333 furnaces; Scotland in the same year, with 27 furnaces, producing 37,500 tons. In 1839 the five furnaces in operation in the neighbourhood of Newcastle-upon-Tyne produced 13,000 tons, giving an average yield of 2,600 tons per furnace.

About the years 1840 and 1841, a general depression of trade came about, the quotations of pig iron being very low, and prices unremunerative. Happily this state of things was of brief duration, and in the year 1844 was succeeded by a period of activity, when a great expansion of the railway system of the United Kingdom took place, causing a large demand for iron of all kinds and producing better prices. The demand for iron continued, and caused inquiries for iron ore and stone to meet it; hence the exploration of old areas, and search for new ones, containing deposits of ironstone, resulting many years later in the discovery and development of the vast fields of argillaceous carbonates of the lias in the North Riding of Yorkshire, and the hydrated peroxides of Northamptonshire and Lincolnshire. The first-named district having since greatly supplemented the requirements of the furnaces of Durham and Northumberland.

During the years from 1844 to 1847, Parliament sanctioned the construction of 9,379 miles of railway in the United Kingdom. With this, increased activity ensued to such an extent that in the last-named year the furnaces of these two northern counties produced 99,840 tons of pig iron, the details of which, with the make of each works, appear as follows :—

NORTHUMBERLAND.

| Works. | FURNACES. | | Make of Pig-iron. |
|---------------------|-----------|-----------|-------------------|
| | Built. | In Blast. | |
| Hareshaw* | 3 | 2 | Tons. 8,320 |
| Ridsdale* | 3 | 2 | 8,320 |
| Tyne | 2 | 2 | 8,320 |
| Walker | 2 | 2 | 8,320 |
| Wylam. | 1 | 1 | 4,160 |
| Total | 11 | 9 | 37,440 |

* Furnaces erected in Carboniferous Limestone District.

DURHAM.

| Works. | FURNACES. | | Make of Pig Iron. |
|---------------------------|-----------|-----------|-------------------|
| | Built. | In Blast. | |
| Birtley | 3 | 2 | Tons. 8,320 |
| Consett and Crookhall . . | 14 | 7 | 29,120 |
| Stanhope * | 1 | 1 | 4,160 |
| Towlaw | 3 | 2 | 8,320 |
| Witton Park | 4 | 3 | 12,480 |
| Total | 25 | 15 | 62,400 |

In the same year the make of the furnaces of Great Britain was 1,999,608 tons, 433 furnaces being in blast of the total 623 built at that period. Scotland of this quantity with 89 furnaces made 539,968 tons, while England and Wales with 844 furnaces contributed 1,459,640 tons, giving an average of 4,620 tons per furnace. Advancing to the year 1852, Braithwaite Poole in his "Statistics of Commerce" gives the following details of the make of pig iron in that year in the several iron-making districts in Great Britain :—

| Districts. | FURNACES. | | | Pig Iron Made. |
|---------------------------|-----------|------|--------|----------------|
| | In. | Out. | Total. | |
| | Nos. | Nos. | Nos. | Tons. |
| Durham | 18 | 8 | 26 | 110,000 |
| Northumberland | 7 | 6 | 13 | 35,000 |
| North Staffordshire . . . | 17 | 4 | 21 | 90,000 |
| South Staffordshire . . . | 127 | 32 | 159 | 725,000 |
| North Wales | 6 | 7 | 13 | 30,000 |
| South Wales | 135 | 27 | 162 | 635,000 |
| Shropshire | 27 | 13 | 40 | 120,000 |
| South Wales, Anthracite . | 12 | 23 | 35 | 31,000 |
| Yorkshire and Derbyshire. | 35 | 7 | 42 | 150,000 |
| Scotland. | 113 | 31 | 144 | 775,000 |
| Total | 497 | 158 | 655 | 2,701,000 |

Comparing the returns of 1852 with those for 1847, the average increase in the make rose from 4,260 tons to 5,200 tons, showing an increase of 580 tons per furnace.

In the annexed table appears the number of furnaces in blast, and the make of pig in both counties in each year since 1856 :—

* Furnaces erected in Carboniferous Limestone district.

| Year. | DURHAM. | | NORTHUMBERLAND. | |
|-------|------------------------|-----------|------------------------|-----------|
| | Number of Furnaces. | Pig Iron. | Number of Furnaces. | Pig Iron. |
| | | Tons. | | Tons. |
| 1856 | 40 | 269,250 | 8 | 62,120 |
| 1857 | 35 | 284,500 | 6 | 63,250 |
| 1858 | 44 | 265,184 | 6 | 45,312 |
| 1859 | 46 | 370,339 | 6 | 31,500 |
| 1860 | 37 | 340,921 | 7 | 69,093 |
| 1861 | 32½ | 312,080 | 7 | 73,260 |
| 1862 | 33½ | 337,218 | 6 | 46,586 |
| 1863 | 47 | 468,318 | 7 | 40,916 |
| 1864 | 42 | 466,980 | 7 | 55,467 |
| 1865 | 47 | 476,767 | 7 | 49,290 |
| 1866 | 47 | 298,867 | 6 | 50,456 |
| 1867 | 39 | 477,834 | 3 | 31,027 |
| 1868 | 35½ | 499,592 | 1 | 17,495 |
| 1869 | 40 | 658,506 | 1 | 15,942 |
| 1870 | 50½ | 676,964 | 3 | 33,623 |
| 1871 | 47½ | 759,244 | 3 | 34,165 |
| 1872 | 49 | 760,172 | 4 | 38,766 |
| 1873 | 49½ | 799,573 | 4 | 44,807 |
| 1874 | 49 | 829,235 | 2 | 33,142 |
| 1875 | 53 | 786,206 | 2 | 22,870 |
| 1876 | 50½ | 806,706 | 1 | 16,466 |
| 1877 | 40 | 734,438 | 1 | * |
| 1878 | 33 | 660,323 | 1 | * |
| 1879 | 31 | 557,255 | 2 | * |
| 1880 | 30 | 750,262 | 2 | * |

It will be seen from the above statement that Northumberland is passing from the list of iron-making districts; most of the works are standing and many have been dismantled, indeed the only establishment now in operation is that of Sir William G. Armstrong and Co., at Elswick. Durham, on the other hand, has greatly augmented her resources.

In the annexed table appears the list of iron works in the past year, showing the number of furnaces built and in blast:—

NORTHUMBERLAND.

| No. | Name of Works. | Owners. | FURNACES. | |
|-----------------|------------------------------|-------------------------------|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Elswick, Newcastle-on-Tyne . | Sir W. G. Armstrong & Co. . | Nos. 2 | Nos. 2 |
| 2 | Walker, „ . . . | Bell, Brothers, Limited . . . | 2 | 0 |
| Total | | | 4 | 2 |

* Included in the return for Durham.

DURHAM.

| No. | Name of Works. | Owners. | FURNACES. | |
|-------|------------------------------------|---|-----------|-----------|
| | | | Built. | In Blast. |
| | | | Nos. | Nos. |
| 1 | Carlton, Stockton-on-Tees | The Carlton Iron Co., Limited | 3 | 3 |
| 2 | Port Clarence, Middlesbro'-on-Tees | Bell, Brothers, Limited | 12 | 12 |
| 3 | Consett, Durham | Consett Iron Co., Limited | 7 | 6 |
| 4 | Ferry Hill | { Rosedale and Ferry Hill Iron Co., Limited } | 10 | 0 |
| 5 | Jarrow-on-Tyne | Palmer's Iron Co., Limited | 3 | 3 |
| 6 | Middleton, Darlington | George Wythes & Co. | 4 | 0 |
| 7 | Norton, Stockton-on-Tees | Norton Iron Co., Limited | 6 | 0 |
| 8 | Vane and Seaham | Watson, Kipling & Co., Limited | 2 | 0 |
| 9 | South Durham, Darlington | South Durham Iron Co., Limited | 3 | 0 |
| 10 | Towlaw, Darlington | Weardale Iron Co., Limited | 4 | 0 |
| 11 | Tudhoe, Spennypoor | | 2 | 0 |
| 12 | Wear, Washington | Bell, Brothers, Limited | 1 | 0 |
| 13 | West Hartlepool | West Hartlepool Iron Co., Lim. | 3 | 0 |
| 14 | Witton Park, Bishop Auckland | Bolckow, Vaughan & Co., Lim. | 6 | 3 |
| 15 | Stockton, North Shore | Stockton Iron Furnace Co., Lim. | 3 | 0 |
| 16 | Tees Bridge, Stockton | Tees Bridge Iron Co., Limited | 3 | 3 |
| Total | | | 72 | 30 |

Malleable Iron Works and Coal used.—Mills and forges:—The production of the various forms of malleable iron in the north of England may be said to date from the middle of the last century. Coming down to more recent times, Mr. Isaac Lowthian Bell, in the year 1868, remarks,* "It is obvious that in a country where, comparatively speaking, there would be a considerable consumption of wrought iron, there was necessarily thrown into the market a corresponding quantity of old or scrap iron. With cheap fuel, and water power in sufficient quantity to drive small hammers, forges were erected at various suitable localities, such as Smallwell by Messrs. Crowley and Co.; Beamish and Lumley, by Messrs. Hawks; Bedlington, and at various other places." The last named works were projected about the year 1809; and it was at these works in the year 1820 that malleable iron rails were first rolled by the invention of a Mr. Birkenshaw. The works at Bedlington were laid down by a Mr. Longridge, the River Blythe supplying the necessary motive power.

The next stage in the manufacture of malleable iron, following the introduction of small hammers and forges, was the erection of slitting mills. It is stated by Mr. Stephen Hawks that these

* "British Association Papers on the Manufacture of Iron."

slitting mills were first used at the Gateshead Iron Works about the year 1772, and were brought from London, and probably were manufactured in Wales or in the Midland Counties. Slit rods, it appears, were first made in the north of England from hammered bars. The late Mr. William Losh, one of the founders of the firm of Losh, Wilson and Bell, erected a slitting mill near Newcastle; the iron he used was imported from Sweden; this was about the year 1800. Cort patented the rolling of bar iron in the year 1783, and Mr. Stephen Hawks in an old letter book of 1799, finds Mr. William Hawks writing:—"We will certainly roll the iron to the dimensions you mention;" so that probably rolling mills were introduced into the neighbourhood of Newcastle-upon-Tyne a very short time after their invention by Cort. In the year 1800 a small mill appears to have been erected at Lemington.

In the year 1827 Messrs. Losh, Wilson, and Bell, erected what was at that time considered in the North a powerful mill at Walker, capable of rolling from 80 to 100 tons of bars per week. Here, as at all the other works, old scrap iron, or common Welsh bars, cut up for re-rolling, were the raw materials used. This firm led the way in extending the operations to the puddling of pig iron, a process adopted by them in the year 1833. The rapid progress in Scotland of the manufacture of pig iron from black band ironstone by means of hot-blast, and the cheapness of coal on the Tyne, induced Messrs. Losh, Wilson, and Bell, to increase their rolling power. A second mill was erected in the year 1838, where rails of the largest dimensions, and tyre-bars for the wrought iron wheels, invented by Mr. Losh, were manufactured. The old house of Hawks and Company soon after added largely to their means of producing wrought iron. In this they were speedily followed by the Derwent Iron Company, who erected immense rolling-mills at Consett, near Shotley Bridge, and increased largely the capabilities of the Bishopwearmouth Iron Works which they had previously purchased. There would be in the district previous to the year 1850 about 300 puddling furnaces, capable of turning out about 150,000 tons of finished iron per annum.

The foregoing works and others, subsequently established from time to time, increased their appliances for producing the various forms of malleable iron, until, in the year 1862, there appear to

have been 17 works in operation, possessing an aggregate of 646 puddling-furnaces, the producing power of these works being estimated by competent authorities as being equal to the manufacture of 340,000 tons of finished iron, and probably the actual make during the year 1862 may have reached 300,000 tons. It further appears that in addition to the iron obtained by the puddling process, a considerable weight of iron is also manufactured in these works from old iron imported into the district from various parts of the kingdom.

Without going into details as to the precise date at which the several important works established in recent years were projected and erected, contributing so much to the welfare and prosperity of the north of England, the year 1872 may be taken as one of great prosperity. At this time there appear to have been 22 works in Northumberland and Durham, making the various forms of malleable iron, plates, rails, angles, sheets, &c., possessing 1189 puddling furnaces and 66 rolling mills, and at the Tudhoe Works of the Weardale Iron and Coal Co., Bessemer plant consisting of four convertors, each with a capacity of 50 cwts. In all these works in 1872 the ascertained quantity of coal employed was 1,259,000 tons. In the year 1873 the same works numbered 1194 puddling furnaces, the rolling mills and Bessemer convertors stood as in the previous year, the quantity of coal used in manufacture increasing to 1,264,000 tons.

In the year 1877 the number of works stood at 28, of which 22 were more or less actively employed, with 1819 puddling furnaces, and 89 rolling mills.

The British Iron Trade Association, in their report for the year 1877, give the total production of manufactured iron in Great Britain as 1,794,000 tons, of which quantity Northumberland, Durham, and Cleveland produced 405,000 tons; South Staffordshire, 365,000 tons; Scotland, 218,000 tons; Lancashire, 200,000 tons; Leeds, Bradford, Sheffield, and Rotherham, 266,000 tons; and other districts the remainder.

The production of 1878 and 1879 was somewhat in excess of the preceding year. The returns for the Durham and Cleveland districts in 1880 amounted to 508,000 tons, an increase of 200,000 tons over the production of 1879. In the year 1880 the works erected and in operation, with the names of proprietors and resources of mills and forges, were as follows :—

DURHAM AND NORTHUMBERLAND.

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-----------------|------------------------|---|----------------------------------|---------------------------|-----------------------|
| 1 | Auckland | Thomas Vaughan & Co. | Bishop Auckland | .. | .. |
| 2 | Whessoe | " | Darlington | .. | .. |
| 3 | Hartlepool | Hartlepool Rolling Mills Co., Limited | West Hartlepool | 34 | 2 |
| 4 | Jarrow | Palmer's Shipbuilding and Iron Co., Limited | Newcastle | 72 | 7 |
| 5 | Albert Hill | Darlington Iron Co., Lim. | Darlington | .. | .. |
| 6 | Springfield | " | " | .. | .. |
| 7 | Birtley | Birtley Iron Co. " | Chester-le-street | .. | .. |
| 8 | Consett | Consett Iron Co., Limited | Durham | 167 | 6 |
| 9 | Fence Houses | Hopper, Radcliffe, & Co. | Fence Houses | .. | .. |
| 10 | Gateshead | Hawks, Crawshaw, & Sons | Gateshead | 66 | 5 |
| 11 | Hive | John Elliot & Son | East Jarrow | .. | .. |
| 12 | Monkwearmouth | Samuel Tyzack & Co. | Sunderland | 27 | 2 |
| 13 | Tudhoe | Weardale Iron and Coal Co., Limited | Spennymoor | .. | .. |
| 14 | Skerne | Skerne Iron Works Co., Limited | Darlington | 72 | 4 |
| 15 | West Hartlepool | West Hartlepool Iron Co., Limited | Hartlepool | .. | .. |
| 16 | Rise Carr | Fry, Janson & Co. | Darlington | 32 | 3 |
| 17 | Stranton | Robert H. Charlton | West Hartlepool | .. | .. |
| 18 | Stockton | Stockton Malleable Iron Co., Limited | Stockton | 78 | 10 |
| 19 | Park | John Abbot & Co., Lim. | Gateshead | 32 | 3 |
| 20 | Albion (Felling Shore) | Felling Coal, Iron, and Chemical Co., Limited | " | .. | .. |
| 21 | Thornaby | W. Whitwell & Co. | Stockton | 31 | 5 |
| 22 | Carr House | Dunlop, Meredith, & Co., Limited | West Hartlepool | .. | .. |
| 23 | Walker | Bell, Brothers | Walker | .. | .. |
| 24 | Witton Park | Boickow, Vaughan, & Co., Limited | Stockton | 104 | 6 |
| 25 | South Hylton | Raine, Brothers | South Hylton | .. | .. |
| 26 | Richmond | R. Jaques & Co. | Stockton | 24 | 3 |
| 27 | West Stockton | West Stockton Iron Co., Limited | " | .. | .. |
| 28 | Stockton | R. S. Johnson & T. M. Reay | " | 22 | 3 |
| Total of County | | | | 761 | 69 |

In considering the resources of the mills and forges in the north of England, it appears that the majority of the works, employing about two-thirds of the puddling furnaces, are more or less dependent upon the open market for the purchase of all their materials, being exclusively finished iron works, without the adjuncts of blast furnaces, mines, or collieries; while the remaining works have the command of their own pig, and, in some cases, their own coal, which gives these latter works a more favourable basis for operation.

In the years 1872 and 1873 the quantities of coal used in the malleable iron works were approximately ascertained; since that date, however, the data available are not so complete as could be desired, in a great measure due to the general depression prevailing; however, it may be generally stated that in the north of

England each puddling furnace, when actively employed, consumes from 1,200 to 1,300 tons of coal, and will yield 500 tons of bars or rails per annum with the consumption of this quantity of fuel.

Coal and Iron Ore used in Manufacture.—In considering the question of the quantities of coal and ore used in the make of pig iron, it will be convenient to deal with the two districts collectively rather than make each the subject of a separate inquiry. About the year 1840 Mr. William Jessop, of the Butterley Iron Works, Derbyshire,* in his inquiry, ascertained that in each ton of pig iron made in those districts, $3\frac{1}{2}$ tons of coal were employed. The result of the Royal Coal Commission inquiry determined the average quantity employed throughout the country, all purposes included, did not exceed 3 tons, while the returns of later years to the Mining Record Office exhibit a still greater economy. In the year 1878 the average did not appear to exceed 45 or 46 cwts., in these districts, the average for Great Britain probably not exceeding 57 cwts. in the same year. The economy in the consumption of fuel has thus within a few years greatly increased, and since special interest now attaches to this subject it may be reasonably expected that the returns of each successive year will exhibit further economy in the coal used in this important branch of our iron manufactures.

In the table below appear the total quantities of pig iron made, and of coal and ironstone used in Durham and Northumberland in each year since 1872 :—

| Year. | Pig Iron. | Coal Used. | Iron Ore. |
|-------|-----------|------------|-----------|
| | Tons. | Tons. | Tons. |
| 1872 | 798,938 | 1,890,766 | 2,623,895 |
| 1873 | 844,380 | 1,949,447 | 2,870,791 |
| 1874 | 862,377 | 2,047,768 | 2,917,683 |
| 1875 | 809,076 | 1,908,240 | 2,784,428 |
| 1876 | 823,172 | 1,895,402 | 2,829,669 |
| 1877 | 734,438 | 1,656,056 | 2,407,834 |
| 1878 | 660,323 | 1,386,601 | 2,097,430 |
| 1879 | 529,559 | 1,161,587 | 1,487,202 |
| 1880 | 750,262 | 1,420,766 | 2,069,243 |

An examination of the above figures shows some interesting facts; thus, in the year 1872 and 1873, the average make of the

* For details of Mr. Jessop's return, see Appendix, pp. 835, 836.

furnaces was in the Durham District 15,574 tons and 16,071 tons respectively, compared with 18,366 tons in the year 1877, and 19,421 tons in the year 1878. The proportion of coal in 1872 to each ton of pig iron made was a consumption of $47\frac{1}{4}$ cwts., comparing favourably with the return of the years 1878 and 1879, when 42 cwts. of coal previously coked was the amount employed, all purposes included, in the production of each ton of pig iron.

The great bulk of the ironstone now smelted in the Durham furnaces is obtained from the Cleveland district; the other ores employed in admixture are obtained from the west coast hematites of Lancashire and Cumberland, the local ores from Wear-dale, and some small quantities from distant districts and foreign countries. The Cleveland ore so extensively used would, if alone employed, require 70 cwts. of raw uncalcined stone to produce 20 cwts. of pig iron, but with the admixture of foreign ores, rich in metallic iron, the actual quantities in 1872 and 1873 did not exceed from 67 to 68 cwts., while in the year 1878 the quantity, as shown by the figures above, amounted to but $63\frac{1}{2}$ cwts. of ironstone of all varieties to each ton of pig iron made.

The sources from whence the ores used in the years 1872 and 1873 were obtained were as follows. Side by side appear corresponding data for the four years ending 1880 :—

| Localities. | 1872. | 1873. | 1877. | 1878. | 1879. | 1880. |
|--------------------|-----------|-----------|-----------|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| Cleveland . . . | 2,100,000 | 2,392,000 | 1,972,395 | 1,642,149 | 1,253,850 | 1,603,905 |
| Cumberland . . . | 85,139 | 44,281 | 46,087 | 37,896 | 8,203 | 8,289 |
| Lancashire . . . | 58,096 | 37,821 | 10,897 | 19,992 | 2,753 | 23,904 |
| Northamptonshire | 20,000 | 25,000 | * | * | * | 1,106 |
| Weardale, &c. . . | 128,471 | 123,282 | 115,523 | 40,144 | 16,461 | 41,357 |
| Foreign ores . . . | 182,189 | 188,407 | 142,932 | 210,685 | 131,487 | 342,150 |
| Other ores . . . | 50,000 | 60,000 | 120,030 | 146,564 | 74,448 | 48,632 |
| Total . . . | 2,623,895 | 2,870,791 | 2,407,834 | 2,097,430 | 1,487,202 | 2,069,243 |

The last item, "other ores," includes ores derived from various localities not ascertained, also "purple ore," an oxide of iron, obtained from the metal extraction works, and containing from 62 to 67 per cent. of metallic iron.

* Quantities included under other ores.

The foreign ores enumerated above were received at the following ports in the years stated :—

| Ports. | 1872. | 1873. | 1877. | 1878. | 1879. | 1880. |
|------------------|---------|---------|---------|---------|---------|---------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| Berwick . . . | | 150 | | | | 70 |
| Hartlepool . . | 33,413 | 13,850 | 401 | 2,341 | 1,038 | 327 |
| Newcastle . . | 82,979 | 114,966 | 70,097 | 134,320 | 62,613 | 162,664 |
| Shields, North . | 9,562 | 15,044 | 6,987 | 6,618 | 5,171 | 12,770 |
| Shields, South . | 20,149 | 20,564 | 21,802 | 13,960 | 22,263 | 44,413 |
| Stockton . . . | 2,229 | 440 | 420 | 1,919 | 9,046 | 59,357 |
| Sunderland . . | 33,857 | 23,393 | 43,225 | 51,537 | 31,356 | 72,549 |
| Total . . . | 182,189 | 188,407 | 142,932 | 210,685 | 131,487 | 342,150 |

The total imports of iron ore into the United Kingdom in each of the same years with the declared value at the port of import being as follows, showing the high character of the ore—the value exceeding 20s. per ton :—

| Year. | Quantities. | Value. |
|-------|-------------|-----------|
| | Tons. | £ |
| 1872 | 576,264 | 671,926 |
| 1873 | 967,536 | 1,278,278 |
| 1874 | 754,147 | 1,021,481 |
| 1875 | 458,673 | 583,571 |
| 1876 | 672,235 | 795,516 |
| 1877 | 1,142,308 | 1,256,069 |
| 1878 | 1,173,411 | 1,162,851 |
| 1879 | 1,083,692 | 1,037,719 |
| 1880 | 2,634,401 | 2,792,717 |

Spain, in 1880, furnished the great bulk of the ores imported. The ore is of carboniferous limestone age, and is extensively developed in the Sommorrostro Mines, near Bilbao, as well as in other districts. The extent of the industry will be understood from the fact that during the year 1878 the total quantity of iron ore exported from the port of Bilbao amounted to 1,224,730 tons, of which quantity England received 856,088 tons and Scotland 47,445 tons, according to a Spanish official return. In the year 1870 the Spanish ores imported amounted to 179,088 tons, of the value of £146,717, compared with 99,816 tons, valued at £78,134, in the previous year. In subsequent years the total quantities and values of Spanish ore imported into Great Britain is recorded as under,* the diminished imports in the intervening

* Trade and Navigation Returns.

years being accounted for by the disturbed state of that country :—

| Year. | Quantities. | Value. |
|-------|-------------|-----------|
| | Tons. | £ |
| 1871 | 302,382 | 284,255 |
| 1872 | 631,134 | 705,441 |
| 1873 | 790,891 | 1,000,720 |
| 1874 | 541,963 | 665,614 |
| 1875 | 250,641 | 273,757 |
| 1876 | 522,383 | 556,756 |
| 1877 | 990,029 | 983,556 |
| 1878 | 1,088,862 | 1,021,455 |
| 1879 | 1,007,617 | 918,276 |
| 1880 | 2,278,962 | 2,270,462 |

Official returns recently published show that in the year 1880 the total iron ore exported from Bilbao amounted to 2,345,598 tons. Of this quantity 1,557,000 tons were conveyed to England, and 112,000 tons to Scotland, the remainder being sent coastways and exported to other countries. The first half of the year 1881, ending June, according to the Customs returns of Bilbao, show the iron ore industries to be in a flourishing state; up to that date 1,825,000 tons having been exported, the average prices delivered F. O. B. varying from 8·50 to 8·75 francs per ton.

CHAPTER II.

YORKSHIRE (WEST RIDING) IRON INDUSTRIES.

Ironstone of the Coal Measures—Analyses and Production of Ironstone—Pig Iron Manufacture—Early History—Annual Production—Works in operation—Bessemer Steel Works—Coal and Iron ore used in Manufacture of Pig Iron.

Yorkshire (West Riding) Ironstone Measures.—Independent of the coal seams, and interstratified with them, are numerous bands or seams of ironstone, in the northern divisions of the coal-field situate in the West Riding of Yorkshire. In the neighbourhood of Bradford and Leeds the mineral field is well developed, and has given rise to the establishments of Bowling, Low Moor, Bierley, and others. The more important of the ironstone measures in the districts above referred to are those of the White Bed Mine (Bierley); and the Black Bed Mine, or Low Moor bed of ironstone worked extensively between Low Moor and Leeds; there is however considerable irregularity in the thickness of these beds, and in the distribution of the nodules, and hence a variation in the yield of ironstone. The White Bed Mine at Bierley yields an average of 1,200 tons of ironstone per acre; the Low Moor Bed is much more productive. These beds of ironstone consist of a series of bands known as follows:—

WHITE BED MINE.

BIERLEY.
Top Flatta.
Low Flatta.
White Balls.
Middle Balls.
Low Measure.

BLACK BED MINE.

LOW MOOR.
Top Balls.
Flat Stone.
Middle Balls.
Rough Measure.
Low Measure.
Basset Stone.

Beneath these beds of ironstone of which the White Bed Mine is uppermost, lies a seam of coal not exceeding two feet in thickness, locally known as the "better bed," remarkably free from impurities, more especially iron pyrites, and consequently containing but a small percentage of sulphur, which renders it of

great value in the manufacture of iron. Beneath the "better bed" coal occurs a valuable seam of indurated fire clay, varying from two to three feet in thickness. This fire-clay furnishes a superior quality of fire-brick, and is also much used as a lining in the blast furnace.

Southwards, by Wakefield, Barnsley, Rotherham, and Sheffield, this mineral field is extremely rich in its ironstone and coal, to a depth of upwards of 300 yards. In the top of the series occurs the Barnsley Thick Coal, which varies in thickness from 6 feet to 9 feet 6 inches, and at the bottom occurs the Silkstone seam of coal 4 feet thick. Between the above named seams of coal are others of less thickness, and the following ironstone measures in descending order :—

1. *Swallow Wood Mine* (Milton).—Consisting of three bands, of Flatts, Balls, and Bottom Measures, and yielding about 1,500 tons of ironstone per acre.
Swallow Wood Coal.
2. *Lidgate Mine* (Milton).—Consisting of three bands, Flatts, Balls, and Bottom Measures, and yielding 1,800 tons of ironstone per acre.
3. *Tankersley Mine* (Milton).—Consisting of Top, Middle and Bottom Measures, and yielding from 2,000 to 3,400 tons of ironstone per acre.
Deep End Coal.
4. *Thorncliffe or Old Black Mine* (Parkgate).—Consisting of Balls, Holing Measures, in all 11 inches of ironstone, and yielding 1,500 tons of ironstone per acre.
Parkgate or Manor Coal.
5. *Thornecliffe, White Mine* (Parkgate).—Consisting of Flatts, Balls and Holing Measures, and yielding 1,500 tons of ironstone per acre.
Thorncliffe Thin Coal.
6. *Black or Clay Wood Mine* (Parkgate).—Consisting of Balls, Brown George, and Whetstone Measures.
Silkstone Coal.

Analyses of the Ironstones.—These clay ironstones, or argillaceous carbonates of iron, in the districts above referred to vary but little in their general character and composition; they have all been carefully examined and the results published in the "Memoirs of the Geological Survey."* The analyses were made by Mr. John Spiller, in Dr. Percy's Laboratory of the Royal School of Mines, by whom the several measures are thus described and the composition determined.

White Bed Mine—The sample examined consisted of equal weights of five specimens of this ironstone measure, described as

* "Iron Ores of Great Britain," Part I., 1856, pp. 66, 69.

a "clay ironstone of varying colour, from a light brown gray to black gray;" the shades deepening in intensity with the order of the specimens selected. Two of the samples exhibited a conchoidal fracture, had a closer texture, and were harder than the others; in another a vein of iron pyrites occurred.

Black Bed Mine, Low Moor.—The sample examined consisted of six specimens of this measure, in the proportion of equal weights; all the samples are described as "dark blackish gray clay ironstones," two varieties being harder than the rest, one variety showing thin films taking the form of shells and containing iron pyrites. The analyses exhibit the following constituents:—

RESULTS TABULATED.

| Constituents. | White Bed Mine. | Black Bed Mine. |
|------------------------------|-----------------|-----------------|
| Protoxide of iron . . . | 35·38 | 36·14 |
| Peroxide of iron . . . | 1·20 | 0·61 |
| Protoxide of manganese . | 0·94 | 1·38 |
| Alumina | 0·80 | 0·52 |
| Lime | 2·78 | 2·70 |
| Magnesia | 2·22 | 2·05 |
| Carbonic acid | 25·41 | 26·57 |
| Phosphoric acid . . . | 0·48 | 0·34 |
| Sulphuric acid | trace | trace |
| Bisulphide of iron . . | 0·18 | 0·10 |
| Water hygroscopic . . | 0·74 | 0·61 |
| „ combined | 1·11 | 1·16 |
| Organic matter | 0·23 | 2·40 |
| Insoluble residue . . . | 28·00 | 25·27 |
| | 99·47 | 99·85 |
| INSOLUBLE RESIDUE. | | |
| Silica | 19·13 | 17·37 |
| Alumina | 6·83 | 6·22 |
| Peroxide of iron . . . | 0·57 | 0·84 |
| Lime | 0·11 | trace |
| Magnesia | 0·07 | 0·12 |
| Potash | 0·78 | 0·65 |
| | 27·49 | 25·20 |
| Metallic iron | 28·76 | 29·12 |

A distinct trace of copper was detected in 500 grains of the White Bed Mine, while in 600 grains of the Black Bed Mine

none of the metals precipitable by sulphuretted hydrogen from the hydrochloric acid solution were found.

The ironstone measures in the southern division of the West Riding of Yorkshire worked at Parkgate, very similar to those above described of Bierley and Low Moor, have been also examined, the samples in each case consisting of equal weights of each ore: the composition of each mine being as follows:—*

RESULTS TABULATED.

| Constituents. | THORNCLIFFE. | | PARGATE. |
|-------------------------|-----------------|-------------|---------------------|
| | Old Black Mine. | White Mine. | Black or Clay Wood. |
| Protoxide of iron . . . | 41·77 | 39·38 | 39·87 |
| Peroxide of iron . . . | 1·96 | 1·24 | 0·53 |
| Protoxide of manganese. | 1·13 | 0·95 | 1·38 |
| Alumina | 0·68 | 0·82 | 0·74 |
| Lime | 2·65 | 2·26 | 2·12 |
| Magnesia | 3·71 | 3·72 | 2·64 |
| Carbonic acid | 31·39 | 29·38 | 28·47 |
| Phosphoric acid . . . | 0·75 | 0·47 | 0·69 |
| Sulphuric acid | trace | | trace |
| Bisulphide of iron . . | trace | trace | 0·05 |
| Water hygroscopic . . | 0·55 | 0·68 | 0·59 |
| „ combined | 1·15 | 1·41 | 1·21 |
| Organic matter | 0·86 | 0·54 | 0·83 |
| Insoluble residue . . . | 14·16 | 19·35 | 20·30 |
| | 100·56 | 100·20 | 99·42 |
| INSOLUBLE RESIDUE. | | | |
| Silica | 8·93 | 12·16 | 13·50 |
| Alumina | 4·21 | 5·60 | 5·39 |
| Peroxide of iron . . . | 0·43 | 0·45 | 0·77 |
| Lime | trace | trace | trace |
| Magnesia | 0·14 | 0·17 | 0·13 |
| Potash | 0·43 | 0·37 | 0·18 |
| | 14·14 | 18·75 | 19·97 |
| Metallic iron | 34·16 | 31·82 | 31·92 |

The average yield of the ironstones wrought in the West Riding of Yorkshire may be taken at 82 per cent. of metallic iron. These ores, before calcination takes place, are usually exposed to the air, when the adhering particles of shale disin-

* "Iron Ores of Great Britain," Part I., 1856, pp. 71 73, 75.

tegrate, and their removal is easily effected. In the operation of calcination they lose from one-third to one-fourth of their weight, the loss consisting of carbonic acid and water.

Thirty years ago the argillaceous ores of the coal measures furnished between 60 and 70 per cent. of the ores smelted in our iron works; since that period, with the development of the deposits in the carboniferous limestone of the West coast in Lancashire, and Cumberland, and of the Liassic and Oolitic formations in the North Riding of Yorkshire and Northamptonshire, new sources of supply have opened up, supplemented by the imports of valuable hematites from foreign countries, so much so, that the proportion of clay ironstone now employed does not exceed 36 per cent. compared with 60 or 70 per cent. in the year 1850. The clay ironstones available for reduction in 1879 amounted to 5,130,849 tons, other ores 9,248,886 tons; while the ores imported amounted to 1,085,045 tons, of the value of £1,050,167; making a total of 14,379,735 tons operated upon in the blast furnaces of the United Kingdom.

Production of Ironstone.—The earliest returns of the production of the ironstone measures in the West Riding of Yorkshire were published for the year 1855,* when the total quantity raised amounted to 255,000 tons. In the year 1856 the production was but 242,100 tons, of which quantity the collieries in the neighbourhood of Leeds produced 42,600 tons. In subsequent years the returns appear as follows :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1857 | 207,500 | 1865 | 575,000 |
| 1858 | 189,750 | 1866 | 357,000 |
| 1859 | 175,000 | 1867 | 579,000 |
| 1860 | 255,700 | 1868 | 785,028 |
| 1861 | 235,500 | 1869 | 230,905 |
| 1862 | 350,500 | 1870 | 307,717 |
| 1863 | 475,000 | 1871 | 407,997 |
| 1864 | 555,000 | 1872 | 466,305 |

These returns show great fluctuations, the year of greatest production being 1868, since which date a considerable falling off appears.

The details of production for the three years ending 1872 appear as follows :—

* Mineral Statistics of the United Kingdom.

| District or Mine. | 1870. | 1871. | 1872. |
|----------------------|---------|---------|---------|
| | Tons. | Tons. | Tons. |
| Bowling | 36,221 | 36,083 | 46,651 |
| Farnley | 14,000 | 25,983 | 26,759 |
| Kimberworth | 2,496 | 1,730 | ... |
| Low Moor. . . . | 68,000 | 75,437 | 80,000 |
| Thorncliffe | ... | ... | 15,497 |
| West Ardsey | 37,000 | ... | ... |
| White Horse | ... | 18,764 | 17,398 |
| Sundry Mines | 150,000 | 250,000 | 280,000 |
| Total | 307,717 | 407,997 | 466,305 |

Since 1872 the ironstone raised is seen in the following quantities, together with its value :—

| Year. | Quantities. | Value. |
|-------|-------------|---------|
| | Tons. | £ |
| 1873 | 407,388 | 122,216 |
| 1874 | 370,960 | 154,074 |
| 1875 | 353,582 | 159,089 |
| 1876 | 381,463 | 228,877 |
| 1877 | 402,746 | 241,647 |
| 1878 | 370,405 | 185,202 |
| 1879 | 321,789 | 160,894 |
| 1880 | 286,698 | 143,349 |

From the above it appears the average value of these argillaceous ores varied from 6*s.* per ton in 1873, increasing to 12*s.* per ton in 1877 and 1878, and since that date show a falling off to 10*s.* per ton.

Fig Iron Manufacture.—The early history of this industry is closely identified with the town of Bradford. Although evidence exists of the smelting of the argillaceous ores of the coal measures at a remote period, on a limited scale, yet it may be said in modern times to date from the year 1780 or 1781, when the Bowling Company purchased the Manor of Bowling, with its ancient hall, and laid the foundation of the works which in subsequent years have attained such a wide-spread reputation. The operations of the company in the early years of its existence were confined more especially to foundry and smith's work. It was not till the year 1788 that the furnaces erected under the superintendence of Mr. John Sturges, of Sandall, near Wakefield, were put in blast and the smelting of iron ore commenced. And here it will be interesting to note a few facts showing the magnitude

of the Bowling Works in the present day. These works comprise six cold blast furnaces, from which about 360 tons of pig iron are run per week, 5 refineries, 21 puddling furnaces, 40 heating furnaces, an extensive forge, a tyre mill for rolling steel and iron weldless tyres, one guide mill, one bar mill, with 15 in. rolls and tin plate mills.

The Bowling estate itself supplies almost all the coal and ironstone which the company consumes, its collieries extending five or six miles in various directions, and the main pits being connected together and with the iron works by tramways worked with wire ropes. The total length of these tramways is 21 miles, the number of pits 42, and the number of hands employed in them is more than 2,000. To work the pits 61 steam-engines are required, having cylinders varying from 7 to 70 inches in diameter; and to supply them with steam 81 boilers are required of from 10 to 50 horse power each. In the iron works are three blast engines, with blowing cylinders, varying from 76 to 84 inches in diameter; and 14 engines, of from 20 to 60 horse power, to give motion to the various machines, besides numerous small steam-engines driving separate machines, and pumping water for the boilers. The number of steam-hammers is 13, and helve hammers 2. The supply of steam is maintained by 33 boilers of from 20 to 50 horse power each. The number of hands employed at the iron works is upwards of 1,000, thus making a total of 3,000. There is also an extensive steel works for making crucible steel, having about 100 pot furnaces, besides furnaces on the Siemens and Siemens Martin principle, worked by the Siemens regenerative gas furnace.*

The distinguishing qualities of the Bowling iron are hardness with great pliability, homogeneity, and uniformity of texture, capability of withstanding the action of fire, and receiving a brilliant polish; these special qualities cause the iron to be in great request in the numerous industries abounding in Sheffield, where it is extensively employed. Mr. Wilcox, in his interesting paper referred to, concludes by remarking, "that works established in the infancy of the iron trade, and producing a superior quality of metal—quality being always preferred to quantity whenever the alternative presents itself—must naturally be dis-

* Mr. Joseph Wilcock's paper on "The Bowling Iron Works," British Association Reports, 1873. Bradford Meeting.

posed to conservatism. Besides, repeated experiences have proved the necessity of keeping to the original mode of working with the minerals and iron. It is rarely known to what purposes or tests, the iron may be put on leaving the premises, but it is known it will have to withstand usage such as common iron, or any other iron but charcoal iron perhaps could do, and it was for the latter that the Bowling iron was originally manufactured as a substitute."

Returning to the founding of the iron works in the West Riding of Yorkshire, as previously stated, the Bowling works were projected in the year 1780. The Low Moor works were established in the year 1790; and a writer in *London Society** gives the following interesting sketch of its founder, Mr. Joseph Dawson:—

"It was probably due more to the investigation and recommendation of Mr. Dawson than to anything else that the Low Moor enterprise was entered upon. Mr. Dawson was an intimate friend of Dr. Priestly, and a man of high scientific attainments. He had given much attention to metallurgy and chemistry, and had watched the progress of scientific discovery in regard to the working of iron with keen interest. He was a man of great vigour of mind and originality of character. In 1768 he was ordained minister of Upper Chapel, Idle; and was then in his twenty-ninth year, and had just been married. Born in very humble circumstances he was led to make energetic efforts to educate himself and attracted the notice of a gentleman, who generously took him by the hand and found the funds for the lad's educational training at the Daventry Academy. Mr. Dawson did not make a successful minister; his mind was too much occupied in scientific speculation, and in the promotion of his material prosperity. He established some coal mines on the hill-side near his chapel and worked them with profit. It was averred that his spiritual ministrations and his commercial engagements trenched so closely upon each other that he used frequently to be found paying his colliers their wages on the Sunday morning before service; after which he would slip into the little chapel and read to his handful of hearers a few pages from a sermon book that had previously been placed in readiness in the pulpit. He was a farmer as well as a colliery proprietor, and minister of the Gospel. His hens were penned in the chapel

* October, 1879.

grave-yard, and the fodder for his cattle was stowed away in a portion of the chapel itself. His duties and engagements were, indeed, of a multifarious character, and he was looked up to by the villagers for assistance and counsel in all kinds of difficulties. He was skilled in the profession of medicine, and was regularly called upon to prescribe for the benefit of his neighbours in times of sickness. It was no wonder that a man who had so many engagements apart from his ministry, should find his congregation gradually dwindling. The Sunday attendance in the chapel was sometimes not more than half a dozen, and so matters went on until the Low Moor enterprise began to occupy his thoughts, when he relinquished his spiritual charge and thenceforth was to all intents and purposes a man of business."

Following the Low Moor Works, those at Shelf, near Halifax, were projected about the year 1795, commencing the manufacture of pig iron; these works were acquired at a later period by the Low Moor Company, while in the year 1797 the Rotherham Works were established.

The make of pig-iron in the West Riding of Yorkshire in the year 1740 was but 1,400 tons, presumably charcoal iron, the yield of six furnaces. In the year 1788 there appears to have been one furnace making charcoal iron, and six furnaces making coke pig iron, the former producing 600 tons and the latter 4,500 tons, or a total of 5,100 tons in 1788. Another return gives the make of the Bowling furnaces, between the years 1795 and 1798, as about 2,000 tons per annum. The make of the Low Moor furnaces about the same period being 2,573 tons in 1795, and 2,658 tons in the year 1798; the works at Shelf in 1798 are stated to have made 3,442 tons, while those at Rotherham produced 3,000 tons.

The total make of pig iron in England and Wales in 1788 was 61,300 tons, of which 13,100 tons were charcoal pig and 48,200 tons coke pig iron.

The information arising out of the inquiry instituted in the year 1796, when Mr. Pitt proposed to levy a duty on coals at the pit's mouth, presents the following facts bearing on the make of pig iron at this period. The return referred to appears under three heads, the figures in the last column being accepted as the quantities produced. The names of the Yorkshire works, and the number of furnaces are also given with details of production:—

| Works. | Number of Furnaces. | Excise. | Supposed. | Exact. |
|---------------------|------------------------|---------|-----------|--------|
| | | Tons. | Tons. | Tons. |
| Bowling | 2 | 2,000 | 2,000 | 2,000 |
| Wibsey Moor | 2 | 2,000 | 2,000 | 2,500 |
| Shelf | 1 | 1,000 | 1,000 | 1,140 |
| Birkenshaw | 1 | 780 | 780 | 846 |
| Thorncliffe | 2 | 1,092 | 1,092 | 712 |
| Elsecar | 1 | 800 | 800 | 950 |
| Bretton | 1 | 250 | 250 | 250 |
| Holmes | 3 | 6,000 | 6,000 | 2,000 |
| Total | 13 | 13,922 | 13,922 | 10,398 |

Ten years later another return is available, giving the number of furnaces in the district as 26, of which 22 were in blast, making 27,646 tons of pig iron.

In the return for 1796 the total production of the furnaces of Great Britain as ascertained appears thus, giving an average per furnace of 1,000 tons per annum :—

| | Furnaces. | Pig Iron. |
|--------------------|-----------|-----------|
| | Nos. | Tons. |
| Excise | 124 | 167,311 |
| Supposed | 124 | 152,545 |
| Exact | 124 | 125,079 |

The following gives the works, furnaces, and owners, as well as the make of pig iron at each works in the year 1806 :—

| Works. | Owners. | FURNACES. | | Pig Iron Made. |
|--|----------------------|-----------|-----------|-------------------|
| | | Built. | In Blast. | |
| | | Nos. | Nos. | Tons. |
| Sheffield Park . . | Booth & Co. . . . | 1 | 1 | 1,905 |
| Chapel Town' and Swallow Hill . . } | Swallow & Co. . . . | 3 | 1 | 3,737 |
| Thorncliffe . . . | Chambers & Co. . . . | 2 | 2 | 2,500 |
| Bowling | Sturges & Co. . . . | 3 | 2 | 2,473 |
| Low Moor | Jarratt & Co. . . . | 4 | 4 | 5,143 |
| Shelf | Haydon & Co. . . . | 3 | 2 | 2,716 |
| Birkenshaw . . . | Emmett & Co. . . . | 1 | 1 | 612 |
| Renishaw | Appleby & Co. . . . | 1 | 1 | 975 |
| Elsecar | Darwen & Co. . . . | 2 | 2 | 2,495 |
| Bretton | Cook & Co. | 1 | 1 | 250 |
| Holmes and Milton. | Walker & Co. . . . | 3 | 3 | 3,000 |
| Calden | Emmett & Co. . . . | 1 | 1 | 1,040 |
| Fieldhead | Parker & Co. . . . | 1 | 1 | 800 |
| Total | | 26 | 22 | 27,646 |

The Renishaw Works clearly belong to Derbyshire, and diminish the make of pig iron in Yorkshire by 975 tons, giving a total of 26,771 tons, and the number of furnaces as 21, being an average of 1,275 tons per furnace.

The make of pig iron in Great Britain in the same year was 249,851 tons, there being 161 furnaces in blast, of the 216 furnaces built.

Not again until the inquiry instituted by the Government and presided over by Mr. F. Finch, in the years 1831-32, does any record appear indicating the progress of the iron industry. The result of Mr. Finch's inquiry does not show any great expansion of the iron trade since the year 1806, which will appear from the following returns of production for each of the years 1823 and 1830 in the Yorkshire furnaces:—

| Furnaces. | 1823. | | 1830. | |
|------------------------|------------------------|----------------------------|------------------------|----------------------------|
| | Number of Furnaces. | Pig Iron Made. Tons. | Number of Furnaces. | Pig Iron Made. Tons. |
| Bowling | 3 | 5,366 | 3 | 5,117 |
| Brierley | 1 | 2,450 | 2 | 4,590 |
| Chapel Town | 1 | 1,400 | 1 | 1,631 |
| Elsecar | 3 | 1,400 | 3 | 1,460 |
| Holmes | 3 | 2,000 | 3 | 1,000 |
| Low Moor | 4 | 6,200 | 4 | ... |
| Shelf | 3 | ... | 3 | 7,480 |
| Milton | 2 | 2,187 | 2 | 1,715 |
| Sheffield Park | 2 | 2,018 | 2 | 2,081 |
| Thorncliffe | 3 | 2,909 | 3 | 2,188 |
| Worsborough | 1 | 1,381 | 1 | 1,664 |
| Total | 26 | 27,311 | 27 | 28,926 |

The total make of pig iron in Great Britain in 1823* was 455,166 tons and 678,417 tons in 1830, the number of furnaces in each of the same years being respectively 266 and 372, showing an increase in seven years of 106 furnaces and 223,251 tons; the increase in Yorkshire being one furnace and 1,615 tons.

Advancing to the year 1839, Mushet† gives the make of 22 furnaces as 52,416 tons. In 1840 Mr. William Jessop, of the Butterley Iron Works, Derbyshire, ascertained that the Yorkshire furnaces,

* For details, see Appendix II., p. 834.

† Papers on "Iron and Steel," p. 421.

25 of which were in blast out of 32 built, made 56,000 tons of pig iron; the total make of pig iron in Great Britain the same year being 1,896,400 tons, the yield of 402 furnaces out of a total of 490 furnaces built. A few years later, in 1843, the returns show a falling off in production to the extent of 181,050 tons, the make in 1843 being 1,215,350 tons compared with 1,396,400 tons in 1840; the only districts in which an increase appears were those of Northumberland and North Staffordshire, amounting to but 16,000 tons. On the other hand in South Staffordshire the falling off was 106,900 tons, and in South Wales 47,650 tons in the period referred to, which was one of great commercial depression. With the development of our railway system about this time a new impulse was imparted to the iron industries throughout the land; for in 1847, the Yorkshire furnaces, 23 of which were in blast out of a total of 28 built, produced 67,600 tons, or an average of 8,073 tons per furnace; the make of the 433 furnaces in Great Britain, out of a total of 623 built, being 1,999,608 tons.

In the year 1851 the following list of works in operation in the northern and southern divisions of the West Riding of Yorkshire shows the resources of these establishments, cold blast being principally employed in the furnaces:—

| NORTHERN DIVISION. | | | SOUTHERN DIVISION. | | |
|--------------------|-----------|-----------|----------------------|-----------|-----------|
| Works. | FURNACES. | | Works. | FURNACES. | |
| | Built. | In Blast. | | Built. | In Blast. |
| Bowling . . . | Nos. 5 | Nos. 3 | Chapelton . . . | Nos. 2 | Nos. 1 |
| Bierley . . . | 4 | 3 | Elsecar and Milton . | 3 | 0 |
| Farnley . . . | 1 | 1 | Holmes . . . | 2 | 1 |
| Low Moor . . . | 3 | 1 | Parkgate . . . | 1 | 1 |
| New Begin . . . | 2 | 2 | Thorncliffe . . . | 4 | 2 |
| Shelf . . . | 1 | 0 | Worsborough Dale . | 1 | 0 |
| Total . . . | 16 | 10 | Total . . . | 13 | 5 |

The make of the furnaces in the northern division in 1851 was 25,000 tons, and in the southern division 40,000 tons, giving an aggregate of 65,000 tons or an average make per furnace of 4,333 tons.

Since the above list appeared, the works at Beeston Manor* and Thorpe Hall each commenced operations, the former in 1855 with one furnace; in 1865 the York Road and Hepworth Works, the former with two, and the latter with one furnace. In 1868 the furnaces at Ardsley, near Leeds, of the West Yorkshire Iron and Coal Company, limited, were blown in, and more recently the Atlas, Aireside, Charlton, and Tinsley furnaces.

Resuming with the production of pig iron in the West Riding of Yorkshire, the annexed summary shows the number of furnaces built and in blast in each year since 1851 :—

| Year. | FURNACES. | | Pig Iron Made. | Year. | FURNACES. | | Pig Iron Made. |
|-------|-----------|-----------|----------------|-------|-----------|-----------|----------------|
| | Built. | In Blast. | | | Built. | In Blast. | |
| | Nos. | Nos. | Tons. | | Nos. | Nos. | Tons. |
| 1851 | 29 | 15 | 65,000 | 1867 | 36 | 25 | 109,002 |
| 1854 | 28 | 21 | 73,444 | 1868 | 38 | 22 | 100,050 |
| 1855 | 32 | 23 | 90,840 | 1869 | 38 | 23 | 105,765 |
| 1856 | 34 | 23 | 96,200 | 1870 | 38 | 22 | 77,717 |
| 1857 | 36 | 25 | 117,000 | 1871 | 39 | 25 | 114,549 |
| 1858 | 33 | 24 | 85,936 | 1872 | 40 | 29½ | 148,636 |
| 1859 | 33 | 25 | 84,950 | 1873 | 40 | 30 | 151,511 |
| 1860 | 35 | 25 | 98,100 | 1874 | 44 | 31 | 163,856 |
| 1861 | 34 | 27 | 142,865 | 1875 | 50 | 37 | 267,153 |
| 1862 | 35 | 26 | 112,121 | 1876 | 49 | 34 | 235,451 |
| 1863 | 35 | 24 | 104,745 | 1877 | 48 | 30 | 229,027 |
| 1864 | 35 | 25 | 102,093 | 1878 | 48 | 29 | 219,547 |
| 1865 | 38 | 29 | 123,233 | 1879 | 49 | 31 | 218,805 |
| 1866 | 36 | 29 | 119,747 | 1880 | 47 | 33 | 306,560 |

In the last-named year the number of furnaces in operation in Great Britain, and the pig iron produced, was as follows :—

| | Number of Furnaces. | Pig Iron. |
|------------------|---------------------|-----------|
| | | Tons. |
| England | 378 | 5,752,683 |
| Wales | 76 | 947,550 |
| Scotland | 112½ | 1,049,000 |
| Total | 566½ | 7,749,233 |

From the above it appears that the average production per furnace in 1848 was 2,891 tons, increased to 3,924 tons in 1860, and 9,200 tons in the year 1880, when the following works were in operation in West Yorkshire, giving the number of furnaces built and in blast, as well as the owners :—

* Works now standing, 1881.

YORKSHIRE—WEST RIDING.

| No. | Name of Works. | Owners. | FURNACES. | |
|--------------------------------|-----------------------------------|---|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Atlas | John Brown & Co., Limited | Nos. 3 | Nos. 3 |
| 2 | West Yorkshire, Ardsley | West Yorkshire Iron and Coal Co., Limited | 5 | 3 |
| 3 | Beeston Manor, Ardsley | A. Harding & Co. | 0 | 0 |
| 4 | Bowling, Bradford | Bowling Iron Co., Limited | 6 | 2 |
| 5 | Elsecar, Barnsley | George Dawes | 4 | 4 |
| 6 | Milton, Barnsley | | 2 | 2 |
| 7 | Farnley, Leeds | Farnley Iron Co., Limited | 2 | 2 |
| 8 | Holmes | | | |
| 9 | Parkgate, Rotherham | Parkgate Iron Co., Limited | 6 | 6 |
| 10 | Low Moor, Bradford | | | |
| 11 | Bierley | Hird, Dawson, & Hardy | 8 | 5 |
| 12 | Charlton, Sheffield | Charlton Iron Co. | 2 | 0 |
| 13 | Thorncliffe, Sheffield | Newton, Chambers & Co. | 2 | 2 |
| 14 | York Road, Leeds | York Road Iron and Coal Co. | 2 | 1 |
| 15 | Aireside, Leeds | Aireside Hematite Iron Co. | 3 | 3 |
| 16 | Tinsley, Sheffield | William Cooke & Co., Limited | 2 | 0 |
| Total of West Riding | | | 47 | 33 |

Malleable Iron Works (Mills and Forges) and Steel Works.

—The manufacture of bar and other forms of iron has long been carried on in the West Riding of Yorkshire; indeed the works at Kirkstall are amongst the oldest in the kingdom, and they still prosper. A recent contribution to a scientific journal gives the following interesting account of these works:—Situated at Kirkstall Abbey, near Leeds, and from which there is no doubt but that the monks at that place many generations ago were acquainted with the manufacture of iron. The abbey was founded between the years 1147 and 1153 by monks of the Cistercian Order, whose house was not dissolved till the year 1540, its revenue at that time being assessed at from £8,000 to £10,000 per annum. In digging some foundations there was the most complete evidence met with, that iron had been made on the ground some hundreds of years ago; and there is an old water-wheel that used to work the helves upwards of two hundred years ago.

The works as they are now, were established in the year 1779, by the ancestors of the present owners, the Messrs. Butler, and are famous for the production of railway tyres, axles, and bars, and for hydraulic presses, for pressing iron and steel, one having

been made on the Haswell system, capable of exerting a pressure of something like 1,400 or 1,500 tons. The works are also known in connection with machines for straightening and planishing round bars; as well as steam-hammers on Naylor's system. The works of the Kirkstall Forge, it may be stated, cover an area of nearly fourteen acres, and when in full operation give employment to nearly one thousand hands. An interesting fact is stated by Mr. Butler of these works, that the Staffordshire iron trade in some measure sprang from them, inasmuch as two lads went from Kirkstall forge into Staffordshire, and there set up a small establishment, where they made bullet-iron. These lads it appears were the Thorneycrofts, a name so well known in connection with the Staffordshire iron trade. Again, it is stated of the firm of Messrs. Bolckow and Vaughan, that the father of the latter turned rolls at Kirkstall forge before going farther north. The Works and the Abbey are amongst the most interesting objects to be seen near Leeds, and showing the antiquity of the works in connection with the ruins, there is a cast-iron mullion to be seen in one of the windows, which must have been made centuries ago. At the present time there are in the immediate vicinity of Leeds and Bradford 14 extensive iron works, and in the districts of Sheffield and Rotherham 16 works, with an aggregate of 497 puddling furnaces and 129 rolling mills, of which the following is a list:—

LEEDS AND BRADFORD DISTRICT.

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-----------------------------|-----------------------|---|----------------------------------|---------------------------|-----------------------|
| 1 | Normanton . . . | { Normanton Iron & Steel } Co. | Normanton . . . | .. | .. |
| 2 | Hunslet Forge . . . | Coghlan & Dury . . . | Leeds | 25 | 5 |
| 3 | Clarence | Taylor, Brothers, & Co. . . | " | 17 | 5 |
| 4 | Farnley | Farnley Iron Co. | " | 16 | 5 |
| 5 | Kirkstall Forge . . . | The Kirkstall Forge Co. . . | " | 28 | 5 |
| 6 | Leeds | S. T. Cooper & Co. | " | 13 | 6 |
| 7 | Monk Bridge | Monk Bridge Iron Co. . . . | " | 27 | 6 |
| 8 | Thornhill | E. T. Ingham | " | 9 | 3 |
| 9 | Perseverance | J. Whitham & Son | " | .. | .. |
| 10 | Bowling | Bowling Iron Co., Ltd. . . . | Bradford | 20 | 4 |
| 11 | Low Moor | Hird, Dawson & Hardy . . . | " | 38 | 8 |
| 12 | Thornton Road . . . | Perkins, Son, & Barrett . . | " | 7 | 2 |
| 13 | Calder Vale | Samuel Whitham | Wakefield | .. | .. |
| 14 | Horbury Junction . . | { Horbury Junction Iron } Co., Limited | " | 13 | 2 |
| Total of District | | | | 213 | 51 |

SHEFFIELD AND ROTHERHAM DISTRICT.

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-----------------------------|---|--|----------------------------------|---------------------------|-----------------------|
| 1 | { Atlas Steel and Iron } { (Swinton). . . . } | John Brown & Co., Lim. | Sheffield . . . | 60 | 19 |
| 2 | Cyclops | Ch. Cammell & Co., Lim. | " . . . | 61 | 9 |
| 3 | Gremisthorpe | " . . . | " . . . | 0 | 1 |
| 4 | { Yorkshire Steel and } { Iron Works, Peni- } { stone } | " . . . | " . . . | 0 | 4 |
| 5 | Millsands | { Sheffield Forge and } { Rolling Mills Co., Lim. } | " . . . | 0 | 8 |
| 6 | Wortley | Thomas Andrews & Co. . | " . . . | 16 | 4 |
| 7 | Midland | Midland Iron Co., Lim. . | Rotherham . . . | 34 | 4 |
| 8 | { Phoenix Bessemer Steel } { Works } | Steel, Tozer, and Hamp- ton, Limited | Sheffield . . . | 0 | 4 |
| 9 | Park Gate | Park Gate Iron Co., Lim. | " . . . | 50 | 6 |
| 10 | Northfield | Neill, Johnson & Edgar . | " . . . | .. | .. |
| 11 | Elsecar | George Dawes | Barnsley . . . | 46 | 7 |
| 12 | Milton | " . . . | " . . . | .. | .. |
| 13 | Stockbridge | Samuel Fox & Co., Lim. | Sheffield . . . | 4 | 3 |
| 14 | Kelham | Kelham Rolling Mills Co. | " . . . | .. | .. |
| 15 | Tinsley Iron and Steel | William Cooke & Co., Lim. | " . . . | 26 | 5 |
| 16 | Charlton | Charlton Iron Works Co. | " . . . | .. | .. |
| Total of District | | | | 297 | 74 |

Coincident with the development of our railway system Sheffield more especially became the seat of many new branches of iron and steel manufacture, such as rails, tyres, axles, wheels, girders, railway waggons, and all forms of forgings and castings for fixed and rolling stock, armour plates, &c. In this neighbourhood are situated the gigantic establishments, the Atlas and Cyclops, which have for years exercised such an important influence in connection with the national defences of the empire. The Atlas works commenced operations about the year 1857, under the auspices of Messrs. John Brown and Co., who initiated the manufacture of those vast plates of iron which have in modern times contributed to the armoured covering of our iron-clads, besides other heavy iron and steel works. A few years later the Cyclops steel and iron works were founded by Messrs. Charles Cammell and Co., and these two firms stand unrivalled in the resisting power their armour plates offer to the heaviest ordnance directed against them. The Messrs. Cammell and Co. have other works on an extensive scale at Gremisthorpe and Penistone, at the former of which the manufacture of cast steel is carried on, also the manufacture of steel by the Siemens Martin process, while at the Penistone Works, known as the Yorkshire Steel and Iron Works, steel is made by the Bessemer process, which has rapidly extended of late years in the neigh-

bourhood of Sheffield and Rotherham. The following is a list of those important establishments, with the names of the firms and the number and capacity of the converters as they stood in the beginning of 1881 :—

| Works. | Situation. | Firms. | Converters. | Capacity. |
|---------------|------------|--|-------------|------------|
| | | | No. | Tons. Cwt. |
| Atlas . | Sheffield | John Brown & Co., Limited | { 4 | 7 10 |
| | | | { 2 | 10 0 |
| Bessemer . | " | Henry Bessemer & Co., Limited. | { 2 | 3 0 |
| | | | { 2 | 5 0 |
| Attercliffe . | " | Brown, Bailly, & Dixon, Limited | { 2 | 4 0 |
| | | | { 4 | 8 0 |
| Cyclops . | " | Charles Cammell & Co., Limited. . . . | { 4 | 4 0 |
| | | | { 2 | 8 0 |
| Phoenix . | " | Steel, Tozer, & Hampton, Limited | { 2 | 6 0 |
| | | | { 2 | 2 0 |
| Stockbridge | " | Samuel Fox & Co. . . . | 2 | 5 0 |
| Yorkshire . | " | Charles Cammell & Co., Limited | { 2 | 5 0 |
| | | | { 2 | 7 0 |

Coal and Iron Ore used in Manufacture.—In the year 1840, according to Mr. Porter, F.R.S.,* the quantity of pig iron made in Yorkshire was 56,000 tons, consuming 306,500 tons of coal in its manufacture, being an average of near five and a-half tons to each ton of pig iron made. In the year 1873, Mr. Joseph Wilcock,† chief engineer of Bowling iron works, states the following as the relative quantities of materials employed for producing one ton of "Bowling pig iron :"—

| MATERIALS. | Tons. | Cwts. | Qrs. | Lbs. |
|------------------------|-------|-------|------|------|
| Raw ore | 3 | 3 | 3 | 27 |
| Calcined ore | 2 | 7 | 1 | 26 |
| Limestone | 0 | 18 | 2 | 12 |
| Coke | 2 | 5 | 0 | 9 |

The raw ore containing 32 per cent. of metallic iron, increased to 42 per cent. by calcination. The coal employed is known to yield on the average 60 per cent. of coke, which would, converting the above named quantity into coal, give an average of 75 cwt. to each ton of pig iron made.

Since the year 1872 the quantities of coal and iron ore used in

* "Progress of the Nation," G. R. Porter, F.R.S.

† Paper read at Bradford Meeting of British Association for the Advancement of Science.

manufacture were as follows; the pig iron made also appears. The increased consumption of coal in the West Riding furnaces it will be remembered is due to the employment of cold blast, still extensively used in the district :—

| Year. | Pig Iron. | Coal Used. | Ore Used. |
|-------|-----------|------------|-----------|
| | Tons. | Tons. | Tons. |
| 1872 | 148,636 | 443,654 | 490,000 |
| 1873 | 151,511 | 493,976 | 499,000 |
| 1874 | 163,856 | 549,363 | 525,000 |
| 1875 | 267,153 | 695,557 | 825,000 |
| 1876 | 235,451 | 555,230 | 730,000 |
| 1877 | 229,027 | 635,712 | 712,500 |
| 1878 | 219,547 | 612,504 | 695,000 |
| 1879 | 218,805 | 556,775 | 692,000 |
| 1880 | 306,560 | 769,519 | 945,000 |

Taking the years 1872 and 1873 the average consumption of coal to each ton of pig iron made was 65 cwts., the average of the iron ore (uncalcined) being about 66 cwts. The economy in the use of coal is observable here as in other districts; thus, in 1877 the average was 55½ cwts.; in 1878 increased to 56 cwts.; while in the past year it did not exceed 50 cwts. throughout the district; in some of the works however a higher average was consumed. In the consumption of iron ore the proportion is fairly maintained, the returns not exhibiting the same fluctuations from year to year, as with the coal, due to the fact that as regards the iron ore the returns give the raw material while the coal used is occasionally recorded as coke, its equivalent in all cases being subsequently ascertained.

CHAPTER III.

YORKSHIRE—NORTH-RIDING (CLEVELAND DISTRICT) IRON INDUSTRIES.

Geology of—Analyses, production and average prices of Ore—Output of the more important Mines—Magnetic Iron ore of Rosedale—Mines in Cleveland District—Ironstone Mining—Distribution of Ironstone—Population employed in Iron Mining—Barrow's Views on the Mineral Resources of the district—Pig Iron Manufacture—Early history, production, distribution, and average prices of Cleveland pig—Coal and Ironstone used in manufacture—Malleable Iron and Steel Works—Production and average prices of rails, plates, bars, and angles—The Thomas Gilchrist process of Steel manufacture.

Yorkshire, North Riding (Cleveland District).—The existence of an iron ore on the North-Eastern coast of Yorkshire appears to have been long known; indeed the constant discovery of iron slag on the hills of Cleveland shows clearly that ores were worked in a remote antiquity. About thirty years since some local iron-masters began to employ the Cleveland ore, to supplement the supply of ores to their furnaces. It answered well, and when the increased demand for iron ore stimulated inquiry, it was found that the Cleveland Hills were full of iron. Then began that remarkable development of the district which can scarcely find a parallel in the history of any British industry. The area of the Cleveland Hills containing the deposits of iron ores, extend on the northern escarpment from Ormesby, near Middlesborough, to the coast, and southerly to the Eskdale and Rosedale valleys; the workable portion of the iron ore being found most fully developed in the north-west portion of the area, diminishing both in the thickness of the beds and the quality of the ore in the south and eastern part of the area.

The main ironstone seam of Cleveland occurs at the top of the "Middle Lias," or marlstone rock, and consists of a bed of ironstone with beds of shale above and below; a lower seam, known as the "Bottom Seam," of fair quality also occurs. This seam is comparatively unimportant in the area of greatest

development of the main seam, but acquires considerable importance in the neighbourhood of Grosmont, south-east of Whitby, where it contrasts favourably with that bed. At Eston, near Middlesborough, on its northern outcrop, the main seam attains its greatest thickness, varying from 12 to 17 feet. Throughout the main seam occurs the well known (*Pecten æquivalvis*), from which it is called *Pecten bed*.

The same strata in the south, in the neighbourhood of Grosmont, attain a thickness of 12 feet of ironstone, but with shaly partings of nearly 30 feet in thickness, the ironstone thinning out towards the south, where at Felixkirk, three miles north-east of Thirsk, it has been proved to exist in beds of six and seven inches, with shale partings of three feet.

The main seam at Upleatham is 13 feet in thickness and undivided; it however exhibits various appearances throughout the mass, not as separate bands, but one structure graduating into the other. In the Yorkshire Lias the following detailed section of the ironstone series at Upleatham is given, which may be generally regarded as a standard of reference.*

Top Block or Roof, 3 feet thick, consisting of:—

1. A brownish compact argillaceous ironstone with diffused oolitic green grains.
2. Rather more oolitic than No. 1, the argillaceous matter more diffused; small phosphatic nodular particles scattered through the mass.
3. Similar to No. 1 but more oolitic.
4. Sulphur bands.—A rock composed of oolitic grains, consisting chiefly of iron pyrites. An analysis gives 30·25 per cent. of sulphur—corresponding to 56·71 per cent. of bisulphide of iron.

(This band was formerly worked at Eston, and applied at the Chemical Works at Washington, and subsequently at Middlesborough as a substitute for ordinary pyrites. It generally separates in loose ground from the underlying main block in the process of mining, and when sound makes an excellent roof; but its extreme liability to disintegrate on the action of moist air necessitates caution in placing reliance upon it.)

Workable Main Seam, 10 feet thick, consisting of:—

5. Top part of main block.—A greyish to bluish stone colour, not uniform, somewhat compact, with pebble-like lumps of an earthy substance of a much lighter colour than the ore and zinc blende, occupying centres of the more argillaceous parts, very fossiliferous.

* "The Yorkshire Lias." Tate and Blake, p. 119.

6. Middle part of main block, about 5 feet thick.—A light blue stone, oolitic in structure, but the grains of variable size, with crystals of carbonate of iron and carbonate of lime. The dissolution of the crystals having left cavities in the stone, imparts a cinder-like aspect to this part of the seam by which it may easily be recognised.
7. Lower part of main block.—A greenish blue stone, rather close in texture, and of a finely oolitic structure. A strong parting separates it from the underlying stratum near the outcrop.
8. Bottom block of main seam, 2 feet thick.—A compact earthy splintery rock of a dark green colour, partaking of the character of a hard mudstone, and perfectly devoid of oolitic structure, which prevails in all the higher parts of the seam.
(Analysis shows it to be rich in alumina and silica, but the percentage of iron does not fall much below the average of that of the main block; it is however rejected by most iron smelters. It is called by the miners "black hard.")
9. A bed of shale 1 foot thick, which underlies and is called from the prevalence of *Rhynchonellæ*, which are occasionally aggregated in stony lumps, the "cockle bed." It yields as much as 21 per cent. of metallic iron, the other chief matter being alumina, silica, and lime.
10. Hard shale 4 feet.
11. Bottom seam of ironstone.—A dense blue clay ironstone, speckled with white and green—2 ft. 8 in. Fossils not abundant. *Pecten Aequitalvis* and others.
12. Shale.

The main seam, near Guisborough, at the Chaloner Mines, has a thickness of 13 feet; at the Normanby Mines, near Middlesborough, it is 11 feet; while at the Whitecliffe and the Liverton Mines, near Loftus, it is 9 feet 6 inches, with a shale parting in the middle. Again, at Ailesbury, near Swainby, it varies from 5 feet 6 inches to 6 feet 6 inches.

Below the Middle Lias, at the top of which is the ironstone main seam above referred to, succeeds the Lower Lias, and immediately above occur the shales of the Upper Lias, in which exist the beds of alum shale and jet, which have given rise to these important industries, of which Whitby may be regarded as the centre.

Above the Upper Lias, and situated at the base of the sandy estuarine beds of the Inferior Oolite, occurs the top seam of ironstone, known as the "Dogger bed," and which has, and still is, acquiring much importance from its highly magnetic character, in the Rosedale Abbey Mines, where the seam is upwards of

20 feet thick. This top seam is regarded as the equivalent of the Northampton sand, and yields a much higher percentage of metallic iron than that of the main seam of Cleveland. The Cleveland district has an area of not less than 500 square miles, and reliable authorities affirm that every acre of this vast area contains ironstone, though it remains to be proved what proportion is workable. The system of working is both by drifts from the outcrop and by shafts, which are sunk in places dependant upon the position of the ironstone, which is usually wrought by the bord and pillar system.

Analyses of the Ironstone.—The Cleveland ore of Eston, examined in Dr. Percy's laboratory in the Royal School of Mines by Mr. A. Dick, is thus referred to.* “Description: chiefly a carbonate of protoxide of iron; lustre, earthy; colour, greenish grey; streak, similar; fracture, uneven; showing here and there small cavities, some of which are filled with carbonate of lime. Throughout the ore are diffused irregularly a multitude of small oolitic concretions, together with small pieces of an earthy substance resembling the ore but lighter in colour. When a mass of the ore is digested in hydrochloric acid till all carbonates and soluble silicates are dissolved, there remains a residue having the form of the original mass of ore. It is extremely light, and falls to powder unless very carefully handled. It contains the oolitic concretions or else skeletons of them, which dissolve completely in dilute caustic potash, showing them to be silica in a soluble state. Under the microscope some of them are seen to have a central nucleus of dark colour and irregular shape, but none of them present any indication of organic structure or radiated crystallisation.”

“If the residue, after having been digested in caustic potash, be washed by decantation, there remains a small number of microscopic crystals; some of these, which are white, are quartz, and others, which are black and acutely pyramidal, consist chiefly of titanitic acid. Professor Miller, of Cambridge, succeeded in measuring some of the angles of the crystals containing titanitic acid, and found that they correspond to similar angles in anatase. The green colour of the ore seems to be due to a silicate con-

* Memoirs of the Geological Survey, “Iron Ores of Great Britain,” Part I., p. 95 (out of print).

taining peroxide and protoxide of iron, but this could not be exactly determined, because it was not found possible to dissolve out the carbonates without at the same time acting upon the silicate of iron. The constituents are as follows :—

RESULTS TABULATED.—ORE DRIED AT 100° C.

| | |
|---|--------|
| Protoxide of iron | 39·92 |
| Peroxide of iron | 3·60 |
| Protoxide of manganese | 0·95 |
| Alumina | 7·86 |
| Lime | 7·44 |
| Magnesia | 3·82 |
| Potash | 0·27 |
| Carbonic acid | 22·85 |
| Phosphoric acid | 1·86 |
| Silica soluble in hydrochloric acid | 7·12 |
| Sulphuric acid | trace. |
| Bisulphide of iron | 0·11 |
| Water in combination | 2·97 |
| Organic matter | trace. |
| Insoluble residue (of which 0·98 is soluble in dilute caustic potash) and consists chiefly of oolitic concretions | 1·64 |
| | <hr/> |
| | 100·41 |
| | <hr/> |
| Iron, total amount | 33·62 |

INSOLUBLE RESIDUE.

| | |
|---|--------|
| Silica | 1·50 |
| Alumina, with a trace of peroxide of iron | 0·10 |
| Titanic acid about | 0·03 |
| Lime | trace. |
| | <hr/> |
| | 1·63 |
| | <hr/> |

A note appended to this analysis states that “No metal precipitable by sulphuretted hydrogen from the hydrochloric acid solution of about 1,200 grains of ore was detected.”

Other analyses of the main seam of ironstone worked at the Normanby mines of Messrs. Bell Brothers, and situated to the south-east of Eston, and at the Upleatham mines of Messrs. J. W. Pease and Co., situated about three miles to the north-east of Guisborough, where it is found under the most favourable conditions as regards richness of metal, give the following constituents, the metallic iron contained in the Normanby ore amounting to 31·42 per cent., and the Upleatham ore yielding 31·97 per cent.:—

RESULTS TABULATED.

| Constituents. | Normanby. | Upleatham. |
|----------------------------------|-----------|------------|
| Protoxide of iron | 38·06 | 37·07 |
| Peroxide of iron | 2·60 | 4·48 |
| Protoxide of manganese | 0·74 | ... |
| Alumina | 5·92 | 12·37 |
| Lime | 7·77 | 4·67 |
| Magnesia | 4·16 | 2·69 |
| Carbonic acid | 22·00 | 23·46 |
| Silica | 10·36 | 10·63 |
| Sulphur | 0·14 | ... |
| Phosphoric acid | 1·07 | 1·17 |
| Water | 4·45 | 3·36 |
| | 97·27 | 99·90 |

The iron ore obtained from the Belmont Mines, near Guisborough, is very similar in character to the preceding, but from its greater density and compactness it would seem to have been derived from a lower measure. The ore employed at the South Bank Furnaces, Middlesborough-on-Tees, is described as: "A dull green, earthy, carbonate of iron, with silicate, containing abundance of small oolitic concretions, a few belemnite stems, and other fossil remains. Small crystals of quartz of zinc blende, and apparently also of titanite, were found in the specimen examined."*

The composition of these ores is represented by the following analyses:—

RESULTS TABULATED.

| Constituents. | Belmont. | South Bank. |
|---------------------------------|----------|-------------|
| Protoxide of iron | 39·00 | 43·02 |
| Peroxide of manganese | 3·50 | 2·86 |
| Protoxide of iron | 1·30 | 0·40 |
| Alumina | 7·46 | 5·87 |
| Lime | 7·44 | 5·14 |
| Magnesia | 3·82 | 5·21 |
| Carbonic acid | 23·06 | 25·50 |
| Phosphoric acid | 1·60 | 1·81 |
| Silica (soluble) | 9·46 | 7·12 |
| Silica as quartz | | |
| Titanic acid | ... | traces. |
| Sulphide of zinc | ... | |
| Water hygroscopic | 3·66 | 0·34 |
| Water in combination | | |
| Organic matter | ... | 0·15 |
| | 100·30 | 100·61 |

* "Papers: Cast-Iron Experiments," 1858, pp. 40 and 34.

The metallic iron contained in the Belmont ore amounts to 32·78 per cent., and in the Cleveland ore, employed in the South Bank Ironworks, then belonging to Messrs. Samuelson & Co., 35·46 per cent.; it being observed of the latter ore that it does not contain any appreciable amount of sulphur nor of heavy metals.

The ironstone raised at Hutton Low Cross, near Guisborough, was examined by Mr. Crowder. The samples selected of the ore from three parts of the bed, are described: (a) as grey, hard, compact and heavy, and with very few oolitic grains; (b and c), as a softer stone, uneven in fracture, and containing many oolitic grains.

RESULTS TABULATED.

| Constituents. | a. | b. | c. |
|------------------------------|--------|--------|--------|
| Protoxide of iron | 35·55 | 35·75 | 40·86 |
| Sesquioxide | 1·70 | 1·80 | 4·25 |
| Alumina | 3·79 | 4·95 | 3·44 |
| Lime | 4·20 | 7·39 | 3·80 |
| Magnesia | 1·12 | 2·98 | 3·70 |
| Sulphuric acid | trace. | 0·07 | 0·30 |
| Silica | 20·90 | 15·65 | 7·20 |
| Carbonic acid | 25·18 | 23·47 | 32·50 |
| Phosphoric acid | 2·66 | 5·05 | 0·96 |
| Bisulphide of iron | trace. | trace. | 1·60 |
| Water | 4·90 | 4·89 | 1·45 |
| | 100·00 | 102·00 | 100·06 |
| Iron, total amount | 28·84 | 27·45 | 34·75 |

An average analysis of the same ironstone, by Richardson, gives the constituents as under:—

RESULTS TABULATED.

| | |
|------------------------------|-------------------|
| Peroxide of iron | 42·08 |
| Protoxide of iron | 0·68 |
| Alumina | 10·40 |
| Lime | 5·48 |
| Magnesia | 1·84 |
| Silica | 14·00 |
| Sulphur | ... |
| Phosphoric acid | ... |
| Carbonic acid | 24·22 |
| Water | |
| | <hr/> 98·70 <hr/> |
| Iron, total amount | 33·09 |

Mr. John Pattinson, of the Clarence Ironworks, gives the following as the results of his examination of the Cleveland raw ironstone, and of the same ore after calcination : *—

| Constituents. | Raw Stone. | Calcined Stone. |
|----------------------------------|------------|-----------------|
| Protoxide of iron | 34·04 | ... |
| Peroxide of iron | 3·74 | 58·30 |
| Protoxide of manganese | 0·38 | 0·53 |
| Alumina | 9·32 | 13·07 |
| Lime | 5·08 | 7·12 |
| Magnesia | 3·65 | 5·12 |
| Carbonic acid | 20·09 | ... |
| Silica | 10·04 | 14·08 |
| Sulphur | 0·13 | 0·18 |
| Phosphoric acid | 1·13 | 1·59 |
| Organic matter | 0·36 | ... |
| Combined water | 2·53 | ... |
| Water expelled by drying at 212° | 9·50 | ... |
| | 99·99 | 99·99 |

The amount of metallic iron in the raw stone giving 29·09 per cent. ; concentrated in the calcined stone to the extent of 40·81 per cent., the loss by calcination being 28·71 per cent.

The magnetic ironstone of Rosedale has been wrought in two localities, namely, at Rosedale Abbey, East and West Mines, and at Sheriffs' Mines. The first two analyses are those of Mr. W. Crowder and Mr. J. Pattinson, and the third was made in the Clarence Laboratory of Messrs. Bell Brothers. The Rosedale Abbey stone is chiefly smelted at the Ferry Hill Ironworks, Durham, and to some extent as a mixture at other works. In quality the iron is stated to be like that which is obtained from the main beds of ironstone in Cleveland.

The Ingleby stone occurring among the oolitic rocks being thin and expensive to work has long since been abandoned. Mr. I. L. Bell states a few hundred tons were smelted without admixture at the Clarence Works. "The content of iron was verified as being superior to the ordinary Cleveland main seam, but the metal in quality did not differ from the usual make of the district."

* Transactions of South Wales Institute of Mining Engineers, vol. vi. p. 235.

RESULTS TABULATED.

| Constituents. | ROSEDALE ABBEY. | | Ingleby Stone. |
|----------------------------|-----------------|-------------|----------------|
| | Black Stone. | Blue Stone. | |
| Protoxide of iron | ... | 33·85 | 41·14 |
| Peroxide of iron | 64·90 | 32·67 | 7·07 |
| Peroxide of manganese . . | ... | 0·69 | 0·94 |
| Alumina | 9·25 | 3·15 | 4·71 |
| Lime | 3·53 | 2·86 | 3·32 |
| Potash | ... | ... | 0·20 |
| Magnesia | 0·99 | 1·59 | 3·34 |
| Silica | 5·70 | 6·95 | 7·37 |
| Loss by heat | 16·15 | ... | ... |
| Carbonic acid | ... | 10·36 | 26·00 |
| Phosphoric acid | ... | 1·41 | 1·36 |
| Bisulphide of iron | ... | 0·03 | 0·08 |
| Water | ... | 4·60 | 4·24 |
| | 100·52 | 98·16 | 99·77 |

The metallic iron contained in these ores amounts respectively to 45·43 per cent., 49·20 per cent., and 36·95 per cent. The Rosedale ore, employed some years since at the works of the Consett Iron Company in a calcined state, gave very satisfactory results: 632 tons 8 cwt. of calcined stone produced 344 tons 13 cwt. of pig-iron; and at the Park Gate Ironworks, near Rotherham, the raw stone was found to yield 45 per cent. of metallic iron.

The Pecten and Avicula beds of ironstone are worked by the Messrs. John and Thomas Bagnall, also the Dogger bed, at Grosmont. The two first-named beds are well developed at Grosmont Hall, about six miles south-west of Whitby, and one mile south-east of Eston, in the following section:—

SUCCESSION OF BEDS.*

| | Ft. | In. |
|--|-----|-----|
| 1. Shale and bands and doggers of ferro-argillaceous stone | 27 | 2 |
| 2. "Main" or "Pecten Seam" of Ironstone | 4 | 6 |
| 3. Shale and doggers | 31 | 0 |
| 4. "Bottom" or "Avicula Seam" | 3 | 9 |
| Total thickness | 66 | 5 |

These ironstones, examined by Mr. Charles Tookey, in Dr. Percy's laboratory, exhibit the following constituents: †—

* "The Yorkshire Lias," Tate and Blake, p. 147.

† Dr. Percy's Metallurgy, "Iron and Steel," p. 223.

RESULTS TABULATED.

| Constituents. | Avicula Bed. | Pecten Bed. | DOGGER BED. | | |
|----------------------------------|--------------|-------------|-------------|-------|-------|
| | | | a. | b. | c. |
| Protoxide of iron | 33·17 | 34·98 | 32·78 | 22·30 | 40·77 |
| Protoxide of manganese | 0·50 | 0·48 | 0·45 | 0·50 | 0·67 |
| Alumina | 3·92 | 3·20 | 1·18 | 2·10 | 1·32 |
| Lime | 11·90 | 11·96 | 6·44 | 11·80 | 4·08 |
| Magnesia | 4·52 | 4·51 | 4·58 | 3·96 | 5·34 |
| Carbonic acid | 28·00 | 29·20 | 26·13 | 24·40 | 31·80 |
| Phosphoric acid | 0·48 | 1·30 | 0·19 | 0·30 | 0·06 |
| Water | 3·65 | 3·30 | 2·80 | 3·20 | 2·70 |
| Ignited insoluble solution | 13·22 | 10·04 | 24·10 | 30·96 | 12·36 |
| | 99·36 | 98·97 | 98·65 | 99·52 | 99·10 |
| IGNITED INSOLUBLE SOLUTION. | | | | | |
| Silica | 9·42 | 8·00 | 18·12 | 23·10 | 8·80 |
| Iron, total amount | 25·80 | 27·21 | 25·50 | 17·34 | 31·71 |

In the following table will be found some of the more important localities in Cleveland in which ironstone is raised, and which has been examined, together with the name of the analyst and the amount of metallic iron :—

| Name of Mine. | Analyst. | Metallic Iron per cent. |
|----------------------------------|----------------------|-------------------------|
| Eston | Mr. A. Dick | 33·62 |
| Normanby | Mr. I. L. Bell | 31·42 |
| Upleatham | " | 31·97 |
| Belmont | Professor F. A. Abel | 32·78 |
| South Bank | " | 35·46 |
| Hutton Low Cross (a.) | Mr. W. Crowder | 28·84 |
| " " (b.) | " | 27·45 |
| " " (c.) | " | 34·75 |
| Hutton Low Cross | Mr. Richardson | 33·09 |
| Cleveland (Raw) | Mr. John Pattinson | 29·09 |
| " (Calced) | " | 40·81 |
| Rosedale (Black Stone) | Mr. I. Lowthian Bell | 45·43 |
| " (Blue Stone) | " | 49·20 |
| Ingleby Stone | " | 36·95 |
| Grosmont (Avicula Bed) | Mr. Charles Tookey | 25·80 |
| " (Pecten Bed) | " | 27·21 |
| Dogger Bed (a.) | " | 25·50 |
| " (b.) | " | 17·34 |
| " (c.) | " | 31·71 |
| Spa Wood | Thomas Allison | 31·00 |
| Kirkham | " | 34·00 |
| Sleight's Bridge | Mr. W. Crowder | 29·83 |
| Grosmont Tunnel | " | 28·60 |

Production of Ironstone.—Originally it appears that the ironstone of Cleveland was collected on the beach, and this was done from an early date. Mr. I. Lowthian Bell mentions * that for the Whitehill Furnace, built in 1745 and abandoned before the end of the last century, ironstone was gathered in Robin Hood's Bay and conveyed by water to Picktree-on-the-Wear, near Chester-le-Street, and carted from that place to the works. Soon after the year 1800 the Tyne Iron Company obtained ironstone in a similar way from the beach between Scarborough and Saltburn; and according to Bewick, in his work on the Cleveland ironstone, the firm commenced between the years 1815 and 1820 to tear up the stone from its bed at different parts of the coast. It is stated that the discovery of the ironstone was due to a Mr. Wilson, then a partner in the Tyne Iron Company's Works, who pointed out its position at Grosmont, about five miles from Whitby, about the year 1836.

The seam being $4\frac{1}{2}$ feet thick was cheaply worked, the stone sent down the railway and shipped at all seasons for the Tyne, where it would at that time cost about 9s. per ton. It is probable that ultimately as much as from 80,000 to 100,000 tons of it were annually smelted in the North-country furnaces.

The Whitby Stone Company commenced operations on the Grosmont Seam, known as the "Pecten Seam," and in May, 1836, sent their first cargo of 55 tons to the Birtley Ironworks. A second quantity was subsequently received by the same company but rejected; however the stone was again tried, and finally permanent contracts were entered into in 1838. About the same time this ironstone was also wrought at two villages, Kettleness and Staithes, the one about five and the other ten miles nearer the mouth of the Tees than Whitby; and about the year 1842 a blast furnace was erected at Walker, being the first specially constructed for smelting what was then known as Whitby or Yorkshire stone.

In the meantime, that is in the year 1840, Messrs. Bolckow & Vaughan established themselves as bar-iron manufacturers at the town of Middlesborough, and five or six years afterward, like others elsewhere before them, mistaken in the extent of local deposits of ironstone, were induced to erect four blast furnaces

* "Manufacture of Iron, Tyne, Wear, and Tees:" British Association Report, 1863.

on the South Durham Coal-field at Witton Park, about 25 miles west of their works at Middlesborough. A very short time sufficed to dispel the illusion, and about the year 1846 they also became dependent upon Whitby for their supplies of ore. The mineral was conveyed thence by vessel to their works on the Tees, unloaded, sent up by rail to Witton Park, and brought back to Middlesborough in the form of pig-iron; although a bed of stone identical with that from which it was worked lay within four miles of the wharf where they were unloading the sea-borne cargoes from Whitby. Previous to the ironstone being worked from the seams at Kettleness and Staithes, that which had been gathered on the beach consisted chiefly of water-worn masses. So far back as 1822 the series of beds of ironstone at Boulby were estimated by Young and Bird to have an aggregate thickness of 15 feet; but the main deposit itself appears to have been mistaken by those writers for limestone. Guided probably by detached masses which had fallen from the cliff along which it runs, the Great Cleveland ironstone was discovered about 1849 by John Roseby, a practical miner, in the valley of Skinningrove.

In September, 1850, the first ton of ironstone was worked from Eston Hill for trial at the Witton Park works. Previous to this the Valley of the Esk, and, to a small extent, the coast, furnished the necessary ironstone. Subsequently the quantity raised on the coast was increased a little in consequence of the seam near Skinningrove being recognised as containing more iron.

Commencing with the year 1854, when returns of production first appear, 650,000 tons of ironstone were raised in the Cleveland district, increased to 865,300 tons in 1855, and 1,148,488 tons in 1856. Additional quantities were obtained in each of the same years from the Esk Valley, and the coast, amounting in 1855 to 105,000 tons, and in 1856 to 98,124 tons; bringing up the total production of Cleveland in 1855 to 970,300 tons, and in 1856 to 1,246,612 tons. The detailed production of the mines for the year 1856 are thus given by Mr. John Marley in his paper.* This memoir contains much important matter, and gives an account of the ironworks then in operation, and the several mines in Cleveland from whence the works received their supply of ironstone:—

* "Memoir on Cleveland Ironstone, &c.," 1857.

| NAMES OF MINES. | QUANTITIES. |
|---------------------------------------|------------------|
| Eston | 568,156 tons. |
| Hutton Lowcrop or Codhill | 217,253 „ |
| Upleatham | 171,360 „ |
| Normanby | 131,675 „ |
| Belmont or Belmont Bank | 73,164 „ |
| Rosedale Cliff and Staithes | 23,500 „ |
| South of Staithes | 12,500 „ |
| Raithwaite | 5,916 „ |
| Sleight's Bridge | 11,250 „ |
| Eskdale Iron Company | 5,438 „ |
| Whitby Stone Company | 22,500 „ |
| “The Quarry,” Rosedale | 4,000 „ |
| Total | <u>1,246,612</u> |

In the following year (1857) seven new mines were in operation, increasing the production in that year to 1,414,155 tons, of which 7,500 tons was magnetic ore obtained from the deposits at Rosedale Abbey. In 1857 and subsequent years the production of the Cleveland Hills will be seen in the annexed table, with the number of mines producing ironstone in each year:—

| Year. | Number of Mines. | Ironstone Raised. | Year. | Number of Mines. | Ironstone Raised. |
|-------|------------------|-------------------|-------|------------------|-------------------|
| | | Tons. | | | Tons. |
| 1857 | 17 | 1,414,155 | 1869 | 16 | 3,094,678 |
| 1858 | 17 | 1,367,395 | 1870 | 17 | 4,072,888 |
| 1859 | 15 | 1,520,342 | 1871 | 21 | 4,581,901 |
| 1860 | 17 | 1,471,319 | 1872 | 31 | 4,974,950 |
| 1861 | 17 | 1,242,514 | 1873 | 35 | 5,617,014 |
| 1862 | 16 | 1,689,966 | 1874 | 35 | 5,614,322 |
| 1863 | 13 | 2,078,806 | 1875 | 39 | 6,121,794 |
| 1864 | 14 | 2,401,890 | 1876 | 36 | 6,562,000 |
| 1865 | 20 | 2,762,359 | 1877 | 33 | 6,284,545 |
| 1866 | 19 | 2,809,061 | 1878 | 29 | 5,605,639 |
| 1867 | 17 | 2,739,039 | 1879 | 29 | 4,750,000 |
| 1868 | 15 | 2,785,307 | 1880 | 29 | 6,486,654 |

Considerable difficulty stands in the way of getting the exact value of the ironstone raised in Cleveland, chief among them being the large proportion which is consumed in the furnaces of the mine owners, and in regard to which there is therefore no sale, and the further large proportion which is to be delivered under contracts made many years since and having many years to run, at prices which are no guide to the existing values. Ironstone was selling in Cleveland in 1860 at 6s. per ton, ten years later the average price was 5s., at which price it continued during 1871, rising in the following year to 7s. 6d. per ton, the highest average price ever reached. During 1874 it averaged 6s. per ton, and since that date has continued to fall.

In the year 1875 the question of value was carefully considered by "The Mine Owners' Association," and the average price given was 4s. per ton net at the mines. Again, in 1876, the average price was given as varying from 3s. 4d. to 3s. 9d. per ton; and in 1877, from 3s. to 3s. 6d. per ton; the same prices existing in 1878. When, in 1877, it became difficult to work the mines to advantage, and this, with a decreasing demand, led to the closing of many of them, prices again fell, and in 1879 the average prices given were from 2s. 9d. to 3s. 3d. per ton, increased in 1880 to from 3s. 3d. to 3s. 9d. per ton, these prices having been adopted as the nearest approach to the correct value that could be arrived at.

The detailed production of the mines in Cleveland in the year 1880 is given in the following statement, showing an increase over the previous year of 1,736,654 tons:—

| No. | Names of Mines. | Quantities. | | Value. | | |
|---|---------------------------------|-------------|-------|-----------|----|----|
| | | Tons. | Cwts. | £ | s. | d. |
| 1 | Ailesbury (Swainley) . . . | 66,042 | 0 | 1,135,164 | 12 | 0 |
| 2 | Belmont (Guisborough) . . . | 110,148 | 15 | | | |
| 3 | Boosbeck " . . . | 486,695 | 12 | | | |
| 4 | Brotton (Saltburn) . . . | 510,302 | 4 | | | |
| 5 | Chaloner (Guisborough) . . . | *260,000 | 0 | | | |
| 6 | Cragg's Hall " . . . | 257,491 | 18 | | | |
| 7 | Carlin How " . . . | 115,465 | 12 | | | |
| 8 | Cliff " . . . | 58,332 | 10 | | | |
| 9 | Eston (Middlesborough) . . . | 1,037,654 | 0 | | | |
| 10 | Grosmont (York) . . . | 134,671 | 0 | | | |
| 11 | Huntcliffe (Saltburn) . . . | 173,157 | 7 | | | |
| 12 | Lane Head (Rosedale) . . . | 3,109 | 16 | | | |
| 13 | Lingdale (Guisborough) . . . | 98,531 | 6 | | | |
| 14 | Lofthouse (Loftus) . . . | 584,049 | 16 | | | |
| 15 | Long Acres (Saltburn) . . . | 240,315 | 0 | | | |
| 16 | Normanby (Middlesborough) . . . | 160,405 | 6 | | | |
| 17 | Ormesby " . . . | 144,609 | 12 | | | |
| 18 | Kirkleatham (Redcar) . . . | 92,615 | 7 | | | |
| 19 | Park Pit . . . | 393,787 | 6 | | | |
| 20 | Port Mulgrave and Grinklo . . . | 170,576 | 0 | | | |
| 21 | Rosedale West . . . | 6,079 | 0 | | | |
| 22 | Slapewath (Guisborough) . . . | 47,114 | 18 | | | |
| 23 | Spa " . . . | 108,055 | 19 | | | |
| 24 | Spa Wood " . . . | 15,271 | 9 | | | |
| 25 | Skelton (Marske) . . . | 117,182 | 19 | | | |
| 26 | Skelton North (Saltburn) . . . | 247,735 | 3 | | | |
| 27 | Stanghow (Saltburn) . . . | 29,541 | 16 | | | |
| 28 | Upleatham (Marske) . . . | 794,886 | 15 | | | |
| 29 | Sundry Mines . . . | 22,826 | 12 | | | |
| Total of North Riding of } Yorkshire . . . } | | 6,486,654 | 18 | 1,135,164 | 12 | 0 |

* Estimated.

As showing the extent of production in some of the mines wrought for a quarter of a century, the following have been selected, viz., Eston, Normanby and Upleatham, giving the total output in each year since 1856 :—

| Year. | Eston. | Normanby. | Upleatham. |
|-------|-----------|-----------|------------|
| | Tons. | Tons. | Tons. |
| 1856 | 568,156 | 131,575 | 171,360 |
| 1857 | 562,473 | 159,898 | 171,366 |
| 1858 | 507,265 | 166,785 | 190,306 |
| 1859 | 638,620 | 204,260 | 265,524 |
| 1860 | 613,391 | 186,152 | 391,410 |
| 1861 | 565,285 | 83,471 | 288,191 |
| 1862 | 608,420 | 235,758* | 433,139 |
| 1863 | 633,206 | 140,348 | 573,613 |
| 1864 | 639,404 | 148,417 | 689,940 |
| 1865 | 685,980 | 139,417 | 719,998 |
| 1866 | 710,156 | 147,213 | 753,022 |
| 1867 | 665,975 | † | 840,577 |
| 1868 | 715,248 | 169,769 | 872,335 |
| 1869 | 761,594 | † | 892,771 |
| 1870 | 831,787 | 215,615 | 959,648 |
| 1871 | 532,821 | 256,023 | 1,034,530 |
| 1872 | † | 254,272 | 811,579 |
| 1873 | 705,228 | 221,485 | 711,360 |
| 1874 | 569,240 | 224,821 | 585,416 |
| 1875 | 571,621 | 238,107 | 640,905 |
| 1876 | 581,978 | 199,254 | 662,200 |
| 1877 | 592,478 | 238,152 | 613,744 |
| 1878 | 557,982 | 228,430 | 732,139 |
| 1879 | 540,749 | 239,098 | 714,075 |
| 1880 | 1,037,654 | 160,405 | 794,886 |

The mines above referred to belong respectively to Messrs. Bolckow & Vaughan, Messrs. J. W. Pease & Co., and Messrs. Bell Brothers, who also possess many other mines in the district.

During the past few years the mines in the neighbourhood of Saltburn-by-the-Sea and Guisborough have produced ironstone in the following quantities :—

SALTBURN-BY-THE-SEA.

| Year. | Brotton. | Cragg's Hall. | Huntcliffe. | Skelton. | North Skelton. | South Skelton. |
|-------|----------|---------------|-------------|----------|----------------|----------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1872 | 392,783 | 196,508 | 180,473 | ... | 166,419 | 4,034 |
| 1873 | 375,334 | 169,507 | 173,221 | 157,755 | 165,279 | 133,492 |
| 1874 | 337,783 | 198,000 | 184,425 | 158,636 | 157,755 | 182,253 |
| 1875 | 384,436 | 217,539 | 145,487 | 148,776 | 137,133 | 314,237 |
| 1876 | 403,309 | 179,639 | 121,613 | 206,003 | 278,097 | 437,872 |
| 1877 | 458,163 | 175,211 | 166,326 | 20,549 | 297,193 | 379,112 |
| 1878 | 481,631 | 171,992 | 190,716 | ... | 191,732 | 236,582 |
| 1879 | 410,334 | 167,675 | 198,895 | 10,029 | 201,843 | 133,403 |
| 1880 | 510,302 | 257,492 | 173,157 | ... | 247,736 | 117,182 |

* Including Skelton.

† Included in other returns.

Those named around Guisborough being as follows, in each of the years since 1872 :—

| Year. | Boosbeck. | Chaloner. | Slapewath. | Spa. | Spa Wood. | Belmont. |
|-------|-----------|-----------|------------|---------|-----------|----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1872 | ... | 15,831 | 47,547 | ... | ... | 181,068 |
| 1873 | 4,785 | 100,513 | 52,000 | ... | ... | 134,965 |
| 1874 | 133,316 | 150,393 | 25,000 | ... | ... | 172,805 |
| 1875 | 222,637 | 207,694 | 51,368 | 111,861 | 83,536 | 161,185 |
| 1876 | 237,978 | 207,894 | 73,298 | 91,270 | 69,301 | 117,000 |
| 1877 | 265,870 | 234,995 | 78,001 | 75,662 | 45,303 | 57,301 |
| 1878 | 288,210 | 322,332 | 80,542 | 60,825 | 83,536 | 8,967 |
| 1879 | 318,659 | 261,392 | 26,236 | 64,556 | 3,698 | 34,352 |
| 1880 | 486,695 | 260,000 | 47,119 | 108,056 | 15,271 | 110,148 |

Other mines have exceeded the output of many of the above, notably the Kirkleatham at Redcar, the Loftus at Lofthouse, and the Liverton at the same place.

The Rosedale Abbey Estate, which has acquired some celebrity from its possession of rich and extensive deposits of magnetic iron ore, occurring in pockets, has an area of 5,530 acres, of which 2,890 acres are under cultivation. Of this estate a writer in the *Newcastle Chronicle* says: "Not until the North Yorkshire and Cleveland Railway had been transferred to the North-Eastern in 1859, and the latter company began to carry out to completion the line by extending it from Stokesley to Grosmont, and by forming the Rosedale Branch to Ingleby a year after the date last named, was there any likelihood of enlarged mineral traffic from the dale. In 1861 the Rosedale Branch was completed, and from that date, for years, the mineral output of the mines began to increase." This development appears in the following table, the output of the year 1857 amounting to 7,500 tons :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1861 | 79,786 | 1871 | 314,394 |
| 1862 | 219,123 | 1872 | 303,205 |
| 1863 | 224,889 | 1873 | 560,668 |
| 1864 | 297,580 | 1874 | 473,140 |
| 1865 | 250,000 | 1875 | 383,914 |
| 1866 | 230,382 | 1876 | 383,827 |
| 1867 | 178,227 | 1877 | 344,487 |
| 1868 | 210,082 | 1878 | 234,150 |
| 1869 | 269,595 | 1879 | 25,592* |
| 1870 | 317,000 | 1880 | 9,188 |

* Mines closed in March, 1879, and operations resumed by a new company in 1880, when the above quantity was raised, the value at the pits being about 3s. per ton put in trucks.

The ironstone mines of Cleveland, their situation and proprietors, were as follows in the year 1881 :—

CLEVELAND AND WHITBY DISTRICT.

| No. | Name of Mine. | Situation. | Name of Proprietor or Company. | Name of Manager or Agent. |
|-----|---------------------------------|----------------------------|--|---------------------------|
| 1 | Allesbury . . . | Swainby . . . { | Carlton Iron Ore Co., Limited . . . | { Robt. Bell. |
| 2 | Huntcliff . . . | Saltburn-by-the-Sea . | Bell Brothers, Limited | { Thomas Bell, junr. |
| 3 | Cliff . . . | " . . . | " . . . | { A. L. Steavenson. |
| 4 | Carlin How . . . | " . . . | " . . . | " . . . |
| 5 | Normanby . . . | Middlesbro' . . . | " . . . | " . . . |
| 6 | Park, in Cleveland . | Skelton . . . | " . . . | " . . . |
| 7 | Skelton . . . | Marske-by-the-Sea . | " . . . | " . . . |
| 8 | Chaloner . . . | Guisborough . . . { | Bolckow, Vaughan & Co., Limited . . . | { Thomas Lee. |
| 9 | Eaton . . . | Middlesbro'-on-Tees . | " . . . | { J. Thompson. |
| 10 | Longacres . . . | Saltburn . . . | " . . . | { George Robinson. |
| 11 | Skelton, North . . . | " . . . | " . . . | " . . . |
| 12 | Cragg's Hall . . . | " . . . | J. W. Pease & Co. . . | Wm. France. |
| 13 | Lingdale . . . | Guisborough . . . | " . . . | Christopher Heslop. |
| 14 | Lofthouse . . . | Loftus . . . | " . . . | Wm. France. |
| 15 | Tocketts . . . | Guisborough . . . | " . . . | Wm. Walton. |
| 16 | Upleatham . . . | Marske-by-the-Sea . | " . . . | W. Moore. |
| 17 | Whitecliffe . . . | Saltburn . . . | " . . . | William France. |
| 18 | Liverton . . . | Loftus . . . | Liverton Ironstone Co., Limited . . . | { G. Lee. |
| 19 | North Loftus . . . | Saltburn . . . | Skinningrove Iron Co., Limited . . . | { Francis Fox. |
| 20 | Port Mulgrave and Grinkle . . . | Near Saltburn-by-the-Sea . | Palmer's Shipbuilding and Iron Co., Lim. . . | { J. Westray. |
| 21 | Rosedale Abbey, East . | Pickering . . . { | Rosedale and Ferryhill Iron Co., Limited, Martin Morrison, manager . . . | { A. S. Palmer. |
| 22 | " West . . . | " . . . | " . . . | { John Rosecamp. |
| 23 | " Sheriff . . . | " . . . | " . . . | { Charles Parkin. |
| 24 | Grosmont . . . | Grosmont (York) . . . { | Charles and Thomas Bagnall, junr. . . | { W. Armstrong. |
| 25 | Brotton . . . | Saltburn Brotton . . . | Morrison & Co. . . | { Francis Lord. |
| 26 | California . . . | Grosmont . . . | " . . . | { D. W. Dixon. |
| 27 | Belmont . . . | Guisborough . . . { | Weardale Iron and Coal Co., Limited . . . | { Thos. Allison. |
| 28 | Spawood . . . | " . . . | " . . . | " . . . |
| 29 | Kirkleatham . . . | Redcar . . . { | Kirkleatham Ironstone Co. . . | { William Walker. |
| 30 | Boosbeck . . . | " . . . | Stevenson, Jaques & Co. . . | " . . . |
| 31 | Slapewath . . . | Guisborough . . . | B. Samuelson & Co. . . | Wm. Charlton. |
| 32 | Ormesby . . . | Middlesboro' . . . | Cargo Fleet Iron Co. . . | William Walker. |
| 33 | Skelton, South . . . | Saltburn . . . { | The Owners of Clay Lane Iron Works . . . | { John Thompson. |
| 34 | Spa . . . | Guisborough . . . | Gjers, Mills & Co. . . | John Tate. |
| 35 | Lane Head . . . | Rosedale Abbey . . . | Robt. Hansell . . . | Robt. Hansell. |
| 36 | Wintergill . . . | Egton Lythe . . . | J. Foster and Son . . . | " . . . |
| 37 | Stanghow . . . | Saltburn . . . | Stanghow Ironstone Co. . | E. Hamilton. |

Having considered the vast deposits of ironstone in the Cleveland district, it will now be a fitting time to refer generally to some of the difficulties met with in ironstone mining, and of the machinery employed to aid the miner in the operation. A writer in the *Colliery Guardian*,* well acquainted with the district and quoting from Mr. A. L. Steavenson's interesting paper "Ironstone Mining in Cleveland," † says that, "owing to the irregular

* Nov. 26th, 1880.

† "Journal of the Iron and Steel Institution," 1874, p. 329.

character of the strata in some parts and the configuration of the country in others, the mining of these immense deposits of ironstone is carried on under various conditions. At the outcrop of the main seam at Eston it is 300 feet above the level of the sea, and dips thence at the rate of three inches to the yard until it is 100 feet below sea level under the centre of the hill, whence it rises as rapidly till it crops out again at the other side of the hill, not to mention several faults or dislocations of considerable magnitude. In other parts, such as at the Kilton Winning, large feeders of water, amounting sometimes to 1,000 gallons per minute, make both sinking and working an operation of more than ordinary difficulty. Perhaps the largest feeders of water have been encountered at the North Skelton Mines. At a depth of 64 fathoms the 'Top seam' was reached, 3 feet 6 inches thick, but even at that depth the water had to be forced at the rate of 3,000 gallons, or nearly 15 tons a minute. Incidentally it may be observed, that towards the end of 1880 the depth attained at this mine exceeded 720 feet, when the ironstone was reached and is now worked."

"When the extraction of ironstone began in 1850 at Eston it was only necessary to uncover the outcrops and then quarry it out in large quantities, but as the covering increased in thickness as the working proceeded, drifting became necessary; and ultimately as the water feeders increased deep shaft sinking had to be adopted. Both drifts and shafts are now extensively in use, the expediency of adopting the one or the other being determined by the nature of the local circumstances. The getting of the ironstone is mostly accomplished by blasting, and for this purpose gunpowder is the best explosive. Many other kinds of explosives have been tried, but the oldest is still considered the best. The operations of the miners are facilitated by the occurrence, often at short distances apart, of joints called 'backs.' The mode of operation is as follows: Cylindrical holes are drilled, varying from two to five feet deep. The boring of these holes is the chief work of the miners, less skilled men being employed to break up the stone and fill it into waggons. A good miner can drill a hole of 5 feet in an hour. Different kinds of machines have been tried for the purpose of drilling these holes, but none of them have been so successful as to entirely supersede hand labour. Probably 15,000 tons of gunpowder are consumed yearly in blasting the ironstone

of Cleveland. The use of such large quantities of this explosive adds considerably to the impurity of the atmosphere in the mines ; hence various mechanical appliances are generally employed to improve the ventilation."

The importance of suitable machinery to aid the miner in his labour of getting the ironstone is a point of especial interest. Mr. Windsor Richards recently, in his address to the members of the Cleveland Institution of Engineers, remarks, "There is no industry of more importance to this district than that of the ironstone mining, and the economical production of ironstone can scarcely be over-rated when it is remembered that about $3\frac{1}{4}$ tons are necessary for the manufacture of a ton of pig-iron. Machinery has already been introduced for winning the stone, and its improvement and extension are well worthy of careful attention." Mr. Richards continues his observations by the following interesting sketch of rock drills and their adoption at the North Skelton Mines. He says, "I believe that Mr. William Walker, of Salthurn, was the first to introduce machinery into the Cleveland mines. He adopted the ordinary rotary spiral drill, driven by a pair of small engines worked by compressed air. Before deciding on the kind of drill to be adopted at the North Skelton Mines, where the ironstone is extra hard, he carefully investigated many of the rock drills in use, and finally determined upon the percussive system, the drills being of simple forms, requiring such slight repairs as can be effected by the ordinary blacksmith at the mine. At the North Skelton Mines there are at present seven machines at work, which are distributed over certain districts. Each district consists of ten working places. A direct-acting horizontal engine, fixed on the surface, having 20-inch steam and 22-inch air cylinders, 4-feet stroke, supplies air to the machines at a pressure of about 70 lbs. per square inch. The engine is sufficiently powerful to work twelve machines. The compressed air is forced down the shaft and along the main roads, east and west, in 6-inch pipes. The pipes along the roadway are 4-inch diameter. The machines have 2-inch and the working places 1-inch wrought-iron galvanised pipes. At present each machine only produces about 50 tons of ironstone per shift of eight hours, but a machine has occasionally got 75 tons, and in a few instances 96 and even 107 tons in eight hours. For 50 tons of ironstone got, about 25 holes 1 inch in

diameter have to be bored to a depth varying from 3 feet to 5 feet, according to the hardness of the stone, or about 100 feet depth of ironstone pierced per machine per eight hours. After being placed in position the drill bores the stone at the rate of 16 inches per minute, or a hole 4 feet deep can be readily made in six minutes, including the time for changing the drills; whereas an ordinary miner would take fully sixty minutes to put in a hole 4 feet deep by 'tamping' or 'jumping' with a bar in the usual way; so that the machine does easily the hardest and most fatiguing work of the miner. One machine employs two miners and a boy, who attend to the drilling and blasting, and four labourers, who break up and fill the stone into the tubs or waggonettes. Ironstone mining by machinery is comparatively new in the district, and the miners have not yet got well into the way of using it; but there can be no doubt that with ordinary diligence one machine can produce from 70 tons to 80 tons of stone per eight hours' shift. The kind of machine adopted at North Skelton is that known as the 'Burleigh,' the principal parts of which are the cylinder, piston, the cradle, with guide stays in which the cylinder travels, and the drills. The piston travels backwards and forwards at a rate which gives 300 blows per minute, and for eighteen blows given it revolves once. The cylinder moves along the cradle, and is fed by a screw worked by hand, automatic gear for this purpose having been found so far unsuitable, owing to the various degrees of hardness of the stone to be bored. As soon as the drill has been fed in the 2-feet length of screw it is withdrawn, and a longer drill substituted. Drills are made of different lengths, and the points of various forms. The half-moon shapes are very suitable for the first and second drills to a depth of 3 feet. The air exhausted from the machines has a beneficial effect in ventilating the working places. The success of this machine, or, indeed, of any other, depends upon the handiness and simplicity of the carriage on which it is mounted. The carriage has received very careful attention from Mr. Chisholm, the engineer of the mine, and is very ingeniously arranged and well adapted for its work. The carriage must be constructed so that it can be very quickly brought up to its work, and be quickly removed to another working place. It must allow the drills to work at any angle, and to drill at any point of the working face."

Distribution of Cleveland Ironstone.—The great bulk of the ironstone raised in the Cleveland Hills is reduced to the metallic state in the furnaces of Cleveland and those of Durham and Northumberland, ample facilities for its transport being afforded chiefly by the North-Eastern Railway and its numerous branches. The total quantities of Cleveland ore carried in each year by the above-named railway include those hematite ores carried from the north-west coast of Lancashire and Cumberland, and other districts, while the annexed statement, showing for a few years the quantities used in the furnaces of Durham and Cleveland, and the total quantities of all kinds of iron ore carried by the North-Eastern Railway, will indicate generally the distribution of the ironstone :—

| Year. | Cleveland Furnaces. | Durham Furnaces. | Total carried by North Eastern Railway. |
|-------|---------------------|------------------|---|
| | Tons. | Tons. | Tons. |
| 1872 | 2,955,000 | 2,100,000 | 4,652,052 |
| 1873 | 2,920,000 | 2,392,000 | 4,928,458 |
| 1874 | 2,980,500 | 2,280,000 | 4,904,279 |
| 1875 | 3,296,824 | 2,050,852 | 5,305,113 |
| 1876 | 3,524,962 | 2,030,000 | 5,426,576 |
| 1877 | 3,980,770 | 1,972,395 | 5,547,821 |
| 1878 | 3,850,045 | 1,642,149 | 4,999,448 |
| 1879 | 3,380,015 | 1,253,850 | 4,190,050 |
| 1880 | 4,463,229 | 1,603,905 | 5,785,724 |

Considerable quantities of iron ore will also have been carried direct from the mines to the furnaces without passing over the North-Eastern system.

Population Employed in Iron Mining.—Until the year 1873 our information of the number of persons employed in the North Riding of Yorkshire or Cleveland district was not accurately known. In 1873 it was, for the first time, ascertained that the number of persons engaged in iron mining amounted to 9,350, of whom 6,947 were engaged in underground operations, and 2,403 above ground ; producing * 5,435,233 tons of ironstone, or an average of 581 tons per person. Since 1873 the numbers employed, the ironstone raised, and average output per man, have been as follows :—

* Reports of H.M. Inspectors of Mines.

| Year. | PERSONS EMPLOYED. | | Total. | Ironstone Raised. | Average per Man. |
|-------|-------------------|---------------|--------|-------------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 6,947 | 2,403 | 9,350 | 5,435,233 | 581 |
| 1874 | 7,571 | 2,274 | 9,845 | 5,428,487 | 551 |
| 1875 | 7,660 | 2,128 | 9,788 | 6,085,541 | 623 |
| 1876 | 7,810 | 2,041 | 9,851 | 6,564,101 | 667 |
| 1877 | 6,983 | 1,586 | 8,569 | 6,289,745 | 735 |
| 1878 | 5,654 | 1,137 | 6,791 | 5,316,477 | 784 |
| 1879 | 6,031 | 1,128 | 7,159 | 4,714,535 | 695 |
| 1880 | 6,500 | 1,472 | 7,972 | 6,441,783 | 808 |

In the last named year there were 44 iron mines in the district comprising 53 separate pits or drifts, but of the mines 8 were standing, compared with 18 in the previous year.

Resources of the Cleveland Ironstone District.—According to Bewick, who first directed attention to this subject, the estimated area of the main bed of Cleveland ironstone was 420 square miles, and taking the average yield per acre at 20,000 tons, he estimated the contents at 5,000,000,000 tons. In 1863 Mr. I. Lowthian Bell, in his paper on "The Manufacture of Iron," read before the British Association,* basing his calculation on the researches of Messrs. Hugh and J. T. Taylor and T. Young Hall, &c., estimated the resources of the Durham and Northumberland Coal-field at six thousand million tons for future use, so that there is sufficient fuel in the one district—reserving it for that purpose exclusively—to smelt the ironstone of the main seam of the other. The subject was again considered in the year 1871 by the "Iron Ore Committee of the Iron and Steel Institute," who reported as follows. They said, "It is now tolerably well known that after leaving the Eston Hills, the ironstone in which has occupied three square miles, the district from which the chief supply of stone is to come for the next century comprises a length of nearly six miles from the vicinity of Guisborough, south-east to the coast, with an average width of four miles. It has been proved that over the greater part of this area the main seam occurs in an unbroken state, varying in workable thickness from 9 to 13 feet, and having about the same

* "British Association Papers, 1863," p. 60.

per centage of metallic iron throughout. Towards the south the stone does get slightly leaner however, by from one to two per cent., and it also steadily thins off; but for the purposes of this estimate the whole district may be taken collectively, and the stone regarded as uniform throughout. The total area of this tract, including the Eston Hills, is 27 square miles, or 17,280 square acres. It is calculated that from the discovery of the Cleveland ironstone to the end of 1870, the total quantity of stone smelted has been 45,000,000 tons, which at 30,000 tons per acre, gives 1,500 acres worked out in twenty years, of which the greater portion has been in the locality a few miles of Middlesborough. The present rate of working is at the rate of 150 acres per annum, and this will be rapidly increased. But the mining-field under notice yet contains say, 16,000 acres untouched, so that at the rate of extraction prevailing in 1870 there is a supply of stone, in this part of Cleveland alone, sufficient to last 100 years, without taking into consideration the iron ores of Rosedale and other places outside the locality in question. But there is every reason to believe that beyond the boundaries of this known district the main seam extends underneath the whole country as far as Whitby and the Valley of the Esk, although it is impossible to speak with any certainty as to the changes that may occur in the quality or thickness of the seam in the direction indicated."

Now, accepting the estimates of the "Iron Ores Committee" and making necessary deductions for production of the past ten years, the acreage now available (1880) would not exceed 14,000 acres of the main seam of Cleveland, which at the present rate of exhaustion would afford supplies for seventy years to come.

Recently the resources of the Cleveland district have been treated in an exhaustive paper read before the Cleveland Institution of Engineers, Middlesborough,* and the results arrived at generally coincide with those of the Iron Ores Committee as to the contents of the main seam. Mr. Barrow's investigations are embodied in the following account. He says:—

"There are, in Cleveland, two distinct classes of iron-stone, the better being blue, very oolitic, and comparatively free from aluminous matter, yielding about 30 per cent., or rather more,

* By Mr. George Barrow, F.G.S., of the Geological Survey of England and Wales.

of metallic iron; the second-class stone is of a dull yellowish tinge, not so oolitic, and contains alumina in place of the iron, which is lost, 28 or 29 per cent. being as much iron as is usually extracted from it. This deterioration in quality of the stone is accompanied by a serious drawback to its being cheaply worked, for, towards (slightly below) the middle of the seam, a band of shale gradually comes in, thickening in a southerly direction till it reaches its maximum thickness of 2 feet, which is the amount of shale between the upper and lower parts of the main seam at Grosmont, the seam being quite unworkable in that district.

"In order to fix the limits of the good stone, it is necessary to know its outcrop, and also the line marking the limit of the shale band in the middle of the seam. The former I have carefully mapped out on the six-inch maps of the district. The limit of the shale band, in the middle of the seam, may be roughly described by a line joining the road at Spa Wood, near Guisborough, to the north side of South Skelton shaft, thence on to Hummersea on the coast, a little more than a mile east of Skinningrove Beck. All the good stone lies north of that line in an area consisting of three distinct parts: Eston, Upleatham, and the Skelton and Huntcliffe district.

"Commencing with the Eston outlier, Eston may be considered as consisting of Eston Royalty proper, and the smaller Royalties of Normanby, Ormesby, and Dunsdale, calculating the seam as of so many 'foot-acres,' i.e., acres one foot in thickness.

"Eston, then, consists of 24,000 foot-acres, very nearly. The specific gravity of the stone is about 2.6, and, as a cubic-foot of water weighs 1,000 ounces, a foot of stone weighs 2,600 ounces, and an acre one foot thick weighs 3,610 tons. Hence we have roughly 86,640,000 tons in Eston Royalty.

"Similarly, there are 2,300 foot-acres in Normanby, and 8,300,000 tons of stone. Also in Ormesby there are 720 foot-acres and 2,600,000 tons of stone. There are 900 foot-acres in Dunsdale, or 3,250,000 tons of stone. In order to tell how long these mines will last, it is necessary next to know the average amount of stone taken yearly out of each, and the total taken.

"In consequence of the Mining Record Office returns, prior to 1865, being incomplete, it is obvious that the total obtained from this source of information will be much under the mark, in the case of Eston, Upleatham, and Normanby, as in 1865 they were

in full swing, turning out almost as much stone as at present. Still, I shall make the calculation from 1865, making a small allowance for cases when considerably more stone has been taken than is represented by this total."

"From such information, then, we arrive at the following result:—The yearly output of Eston is 800,000 tons; of Normanby, 225,000 tons; of Ormesby, 75,000. The total of iron-stone removed in Eston, 16,000,000 tons; in Normanby, 5,000,000 tons; in Ormesby, 500,000 tons. Now, if we deduct the total taken out from the whole of the stone in a mine, and take away at least one-tenth for loss in working, we have for the quantity now left—

| | TONS. |
|----------------------|------------|
| In Eston | 60,000,000 |
| „ Normanby | 2,500,000 |
| „ Ormesby | 1,800,000 |

Hence, dividing these totals by the average yearly output, we find, for the continued duration of each mine,—

| | |
|----------------------|-----------|
| For Eston | 75 years. |
| „ Normanby | 8 „ |
| „ Ormesby | 15 „ |

"Proceeding in a similar way for the Upleatham district, the total stone amounts to 10,000 foot-acres, or 36,100,000 tons. The yearly output is 700,000 tons, and the total taken out considerably over 12,000,000 tons, so that its duration will be some 30 years, or rather less—between 25 and 30.

"The area of good stone left in Skelton and Huntcliffe districts consists of 48,000 foot-acres, or 173,280,000 tons. The yearly output is about 1,800,000 tons, and the total output 24,190,000 tons, or more. Hence the workable quantity left is about 145,000,000 tons, which would, at this rate, last 80 years. But, taking into consideration the increased call 30 years hence, 60 years would be a fair limit to put to the duration of the stone.

"Now, the main seam in the poorer districts may be said to consist of a strip 13 miles long, by about $2\frac{1}{2}$ miles wide. South of this the seam is very poor and thin, and consists of 4 feet of stone, with a two-feet shale parting in the middle. Before it would pay to work this, other seams will be wrought; in fact, these seams will be worked before many years, because, though

thin, their quality is better than any, except the very best stone. The total amount in this strip, then, of the inferior stone, which pays to work now in fairly good times, is, roughly, 375,480,000 tons, and, at the present rate of output, would last some 130 years; but this period would be much lessened, as in 30 years the output would be more than doubled to compensate for the exhaustion of the Upleatham and other mines."

Mr. Barrow subsequently considers, in detail, the district in which the main seam occurs, where it is at present regarded as almost valueless, "and defines the area of the poorer stone 13 miles long and $2\frac{1}{2}$ miles broad, as extending in a line roughly drawn from Kildale, south of Guisborough, to Kettleness, north of Whitby, as its southern boundary. At Kildale, the section of the seam consists of 4 feet of stone, with a shale parting of 14 inches, and again, on the Commondale shaft the seam may be said to consist of three-two's. At Grosmont, the seam has become so thin as to be almost unrecognisable. It must be borne in mind that this bed is in all cases of a decidedly poor quality, and so up to Kettleness, where the average yield is 26.5 per cent. of iron. South-east of Kettleness iron has not been seen or proved.

"Taking into consideration the poverty of the seam in Hawkser, south of Whitby, where the seam is represented by a few doggers, it is evident it will not be used as a source of iron for many years to come, if ever. Coming to the consideration of the other seams of ironstone in Cleveland not usually worked, examining the main seam at Eston, it would be found, at the base as at present worked, to consist of a greenish, shaly stone, having a rather mottled appearance. Before reaching the south or east face of the hill, a shale-band comes in between the oolitic stone and green stone, but only the oolitic was taken up in a long drift which was made some time ago on the Chaloner property, the shale and underlying shelly bed being left. The shelly bed is contained over a very large area, and is in fact the Pecten seam at Grosmont, and in future it would be far safer to restrict the term to this bed, calling the thick, blue stone usually found the main seam. It is usually of a poor quality, yielding about 27 per cent. of iron, or slightly less. It is difficult to estimate the amount of ironstone in this seam, because it varies very much according to presence or absence of the shaley streaks. It probably cannot be worked separately under Eston, nor in the

Upleatham district, but at the Old Hutton mines it seems to have been taken near the outcrop, its thickness being 3 feet 6 inches, at a depth of about 4 feet from the base of the seam.

"Again, at Kildale the shale is 2 feet 6 inches thick, and this belt is exposed at Spa Wood railway cutting, where its thickness is 4 feet. At Huntcliffe, and at Brotton, it is very thin, but at Longacres Pit it is 3 feet thick. At Grosmont its thickness varies from 2 feet 4 inches to 2 feet 6 inches of stone, with a shale parting in the upper part. Calculating that it covered an area of 50 square miles, with an average thickness of 2 feet 6 inches, it was estimated that there should be a total of 400,000,000 tons of ironstone from this seam, which was, however, of poor quality, and not always reliable. About 5 feet 6 inches below the Pecten seam occurs a bed of stone, remarkable for its uniform thickness and its good quality. In many places, such as Normanby and Brotton, it seemed to be equally rich in iron with the main seam, its thickness usually being about from 1 foot 10 inches to 2 feet. It maintains this thickness over a very large area, being 2 feet 6 inches at Kildale; 1 foot 10 inches at Guisborough; and 2 feet 2 inches at Hob Hill.

"On the coast at Staithes the seam shows signs of thinning, being about 1 foot 8 inches, so that they might put its south-eastern limit about three; but it continues some distance in the Stokesley range of hills, being worked for some time in the Ingleby Mine, after the main seam had been abandoned. The estimated area of this seam would be about 60 square miles, with an average thickness of 2 feet. It is mostly a clean stone, and will yield a total of about 380,000,000 tons of first-class stone.

"Below this seam is the 'Avicula' seam so well known at Grosmont. The avicula seam is very permanent, but its thickness varies very much over the whole of Cleveland, ranging from 3 feet at Grosmont, to as little as 1 foot 6 inches at Staithes, its average yield of iron being about 27 per cent. This seam also extends into the Stokesley Hills down Bilsdale, but it would be hazardous to say that it could be worked for a great distance from any given point. Its estimated area would extend over 100 square miles, and the probable amount of stone would be somewhere about 600,000,000 tons, probably more, but its working, except where it could easily be proved first, would be very venturesome. This concludes the account of the seams of ironstone in the liassic

beds, and it only remains to consider those ironstone seams in the oolitic beds. Of these there are but two, one being the Dogger, or top bed, and the other the Eller Rock. The Dogger occurs at the top of the Alum shale, and as a general rule it may be defined as a sandy ironstone or a ferruginous, impure limestone. It is always remarkable for the so-called pebbles in it. At Eston, Upleatham, Guisborough, &c., it may be practically said to be non-existent.

"From the peak at Robin Hood's to Runswick Bay, on the coast all along Eskdale, Glaisdale, Muske, Esk, &c., it is a highly siliceous, oolitic ironstone, varying from 2 feet to 16 feet thick. It has often been tried at Eskdale, Grosmont, and Muske Esk, but has always failed. About Staithes, Boulby, Huntcliffe, and Liverton, the Dogger consists of a hard band of very fine clay ironstone, containing about 40 per cent. of iron, resting upon a ferruginous marl, often containing as little as 25 or 26 per cent. One of the most characteristic features of the top bed is its fickleness, being unreliable for any great distance. The percentage of impurity in the two marly beds will determine whether this seam can ever be worked, and the same remarks will apply to Huntcliffe, where the section is much the same. At Boulby Alum Works the seam is slightly thinner, but presents the same general characteristics; at Grinkle Park the seam is very thin and sandy; it is apparently absent at North Skelton Shaft, and is entirely wanting at the Hagg Alum Works, near Saltburn. The area, over which this seam may possibly be worked in Cleveland at some future time, is between four and five square miles, its average thickness being 8 feet 6 inches. In the Stokesley Hills the main seam occurs in cuticular patches, lying in eroded hollows in the alum shale. In all cases it contains much lime and silica, which in Bilsdale has been burnt for lime.

"At Limekiln Bank, over Swainby, it becomes 28 feet thick, valueless as a source of iron, and at Catcliff Bank, near North Allerton, the seam attains, in one place, a thickness of nearly 20 feet, but there are shaly partings in it, and most of the ironstone is of poor quality; in fact, it is of no value as iron ore. In Rosedale, however, a wedge of ironstone, formed similarly to that referred to in Bilsdale, occurs, in which all the lime has been probably replaced by iron, and where a rich iron ore has been found, but its extent has not hitherto been ascertained."

Fig Iron Manufacture.—The ironstone deposits of Cleveland

were first developed about the year 1850, and the smelting of the stone in the district soon followed, and so rapidly, that in the year 1855 there were 23 furnaces built, 21 of which were in blast and produced 84,500 tons of pig-iron. The early furnaces erected in the district varied in height from 42 to 50 and 55 feet, their capacity varying from 5,000 to 6,000 feet; about the year 1861 furnaces of greatly increased capacity were erected at the Thornaby Ironworks by Mr. William Whitwell, three in number, each of a cubical capacity of 12,778 feet; these furnaces were 60 feet in height and 20 feet diameter in the boshes. Considerable economy was secured in the consumption of fuel in manufacture by these larger furnaces, so much so, that in 1866 the Messrs. Hopkins, Gilkes & Co., at their Tees Side Ironworks, erected two furnaces, each 75 feet in height and 24 feet in the boshes, and a capacity of 20,000 cubic feet.

The results attained by these large furnaces were so encouraging that still larger ones were erected, one having a height of 105 feet, and a cubical capacity of 41,150 feet. But it has since been determined that with these extraordinary dimensions the limit of economical working has been exceeded.

In the year 1855, above referred to, the works and firms in operation, with the number of furnaces built and in blast, were as follows, the make of pig-iron being, as previously stated, 84,500 tons:—

| No. | Name of Works. | Name of Firm. | FURNACES. | |
|---------|------------------|------------------------|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Tees . . . | Gilkes, Wilson & Co. . | 4 | 4 |
| 2 | Eston . . . | Bolckow & Vaughan . | 6 | 6 |
| 3 | Cleveland . . . | T. L. Elwen & Co. . | 3 | 2 |
| 4 | Middlesborough . | Cochrane & Co. . . | 3 | 3 |
| 5 | Ormesby . . . | Bolckow & Vaughan . | 4 | 3 |
| 6 | South Bank . . | B. Samuelson & Co. . | 3 | 3 |
| Total . | | | 23 | 21 |

Several new works were projected and commenced about this period. The works of the Clay Lane Iron Company began the manufacture of pig-iron, towards the close of 1858, with one furnace, blowing in a second in the following year. The Tees Side furnaces of Messrs. Snowden & Hopkins followed in 1859,

and in 1860 the furnaces of the Whitby Iron Company were put in blast; the total number of furnaces built in the district at this time being 33, of which number 25 were in blast, the works previously established in the mean time adding to their number of furnaces, and thus increasing their resources for production in the future.

The works at Normanby, of Messrs. Jones, Dunning & Co., commenced operations, in 1861, with two furnaces, followed in 1863 by the Grosmont Works, of Messrs. Charles and Thomas Bagnall, with two furnaces in the early part of the year; and the Newport Works, of Messrs. B. Samuelson & Co., with three furnaces in August of the same year.

The works at Cargo Fleet, of Messrs. Swan, Coates, & Co., were completed towards the close of 1865, and in June, 1866, two furnaces were blown in. These were succeeded by the Linthorpe Works, of Messrs. Lloyd & Co., where four furnaces were blown in about August of the same year. In the following year the Glaisdale Works, of Messrs. Firth & Hodgson, and situated near Whitby, were put in operation. Other works followed: the Ayresome, of Messrs. Gjers, Mills & Co., in 1870; the Carlton, of the Industrial Iron Company, and the Norwegian, of the Titanic Iron Ore Company, with one furnace; and those at Ayresome and Carlton with two each in the same year, when the total number of furnaces in the Cleveland district was 74, of which number 67 were in blast, producing in that year 916,970 tons of pig-iron.

In 1871 the Lackenby Iron Company, with two furnaces, commenced the manufacture of pig-iron, a third being in course of erection; and in 1873 the Coatham Works, of Messrs. Downey & Co., with two furnaces; these were followed, in 1874, by the Acklam Works, of Messrs. Stevenson, Jaques & Co., with four furnaces; the Loftus, Redcar, and Stockton Ironworks; and in 1875 by the Thornaby Ironworks, of Messrs. William Whitwell & Co., each with two furnaces. The Loftus Ironworks have recently been acquired by a new company, and are now known as the Skinningrove Works, the company being incorporated on the 8th June, 1880, since which date a few changes of proprietorship have occurred in other works. In the annexed table is given the numbers of furnaces built and in blast, the make of pig-iron, and the average yield per furnace in each year since 1855:—

| Year. | FURNACES. | | Pig-Iron made. | Average per Furnace. |
|-------|-----------|------------------|----------------|----------------------|
| | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Tons. |
| 1855 | 23 | 21 | 84,500 | 4,024 |
| 1856 | 31 | 23 | 179,400 | 7,800 |
| 1857 | 32 | 23 | 179,838 | 7,816 |
| 1858 | 30 | 20 | 189,320 | 9,466 |
| 1859 | 30 | 23 | 216,127 | 9,400 |
| 1860 | 33 | 25 | 248,665 | 9,946 |
| 1861 | 33 | 26 | 234,656 | 9,025 |
| 1862 | 32 | 28 | 283,398 | 10,121 |
| 1863 | 42 | 33 | 315,197 | 9,551 |
| 1864 | 47 | 41 | 409,106 | 9,979 |
| 1865 | 65 | 53 $\frac{1}{2}$ | 486,421 | 9,011 |
| 1866 | 67 | 55 $\frac{1}{2}$ | 546,091 | 9,839 |
| 1867 | 67 | 50 $\frac{1}{2}$ | 640,892 | 12,699 |
| 1868 | 69 | 50 | 699,494 | 13,989 |
| 1869 | 69 | 51 | 766,410 | 15,027 |
| 1870 | 74 | 67 | 916,970 | 13,686 |
| 1871 | 75 | 70 | 1,029,885 | 14,713 |
| 1872 | 81 | 73 $\frac{1}{2}$ | 1,122,114 | 15,215 |
| 1873 | 78 | 76 | 1,156,431 | 15,216 |
| 1874 | 97 | 85 | 1,158,471 | 13,629 |
| 1875 | 87 | 73 | 1,240,243 | 16,990 |
| 1876 | 86 | 75 | 1,261,013 | 16,813 |
| 1877 | 89 | 75 | 1,374,582 | 18,314 |
| 1878 | 90 | 67 | 1,358,442 | 20,275 |
| 1879 | 90 | 70 | 1,210,091 | 17,287 |
| 1880 | 91 | 72 | 1,666,156 | 23,141 |

The apparent want of constancy in the average yield per furnace in 1879 is due to the fact of several of the furnaces being but partially in operation during that year. Bearing upon the production per annum per furnace of this district, Mr. Windsor Richards, recently in his address to the Cleveland Institution of Engineers, refers to the Cleveland furnaces in these words; he says, "Some years ago this district took the lead in blast furnace construction and practice, and may still be proud of its best examples of blast furnace plant, but latterly few improvements have been made. In 1876 the output of Cleveland pig-iron per furnace per week amounted to 330 tons; in 1877, to 317; in 1878, to 406 tons; and in 1879, to 417 tons; and this year (1880) the output will be about 427 tons, showing but small progress. Some few furnaces in the district have made regularly over 500 tons per week. The manufacture of Bessemer pig-iron, Spiegeleisen, and ferro-manganese, is becoming a large industry

in Cleveland. Before 1876 there was no separate account kept of Bessemer pig-iron made in the Cleveland district. Since that date the production has been as follows:—

| YEAR. | TONS. |
|----------------|---------|
| 1876 | 125,000 |
| 1877 | 200,000 |
| 1878 | 339,131 |
| 1879 | 274,939 |

“The falling off in 1879 was owing to the Durham miners’ strike, and bad trade, and this year (1880) it will probably be 500,000 tons. The total production of the blast furnaces of the North of England district will probably reach the enormous total of 2,490,000 tons.”

Mr. W. Richards gives some interesting details showing the efficiency of the metallurgical operations at the Consett Ironworks in Durham, and says: “A blast furnace practice, in the manufacture of Bessemer pig-iron, worthy of imitation, is that of Mr. William Jenkins, of Consett, who, at my request, furnished me with the following information, and the results show what I believe to be the best blast furnace in England. The figures are for eight consecutive weeks in hematite pig-iron:—Iron produced, 6,454 tons 13 cwts.; average per week, 806 tons 17 cwts.; 53 per cent. of the make being No. 1 quality. Coke used per ton of iron made, 19·21 cwts. The furnace is 55 feet high, 20 feet diameter at the bosh; 8 feet hearth; 7 tuyeres; 4-inch muzzles; blast, 4½ lbs. pressure per square inch. There are four Whitwell stoves, 22 feet diameter, 28 feet 6 inches high, each stove having a heating surface of 8,200 feet; temperature of the blast averages 1,200 deg. Fahr. Mr. Jenkins attributes these good results to the better distribution of the blast, large hearth, better lines of furnace, and good heat.” According to Mr. W. Richards, the average yield of the furnaces of the Cleveland district has been as follows during the ten years ending 1879; output per annum per furnace—

| Year. | Tons. | Year. | Tons. |
|-------|--------|-------|--------|
| 1870 | 14,491 | 1875 | 17,653 |
| 1871 | 15,196 | 1876 | 18,693 |
| 1872 | 15,146 | 1877 | 20,045 |
| 1873 | 15,148 | 1878 | 20,645 |
| 1874 | 16,009 | 1879 | 20,016 |

It only remains to append the following list of works and owners, with the number of furnaces built and in blast in the year 1880 :—

| No. | Name of Works. | Owners. | FURNACES. | |
|-----------------------------|---------------------------------|---|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Acklam, Middlesbro' | Stevenson, Jaques & Co. . . . | 4 | 4 |
| 2 | Ayresome, Middlesbro'-on-Tees | Gjers, Mills & Co. | 4 | 4 |
| 3 | Cargo Fleet, " " | Cargo Fleet Iron Co. | 5 | 4 |
| 4 | Clay Lane, Easton Junction . . | Owners of Clay Lane Ironworks . | 6 | 3 |
| 5 | Coatham, Middlesbro' | Downey & Co. | 2 | 2 |
| 6 | Middlesbro' | Bolckow, Vaughan & Co., Lim. { | 3 | 3 |
| 7 | Easton (Iron and Steel) . . . } | | 11 | 11 |
| 8 | Glaisdale (Yarm) } | South Cleveland Ironworks Co. { Limited | 3 | .. |
| 9 | Grosmont, Whitby | Chas. and Thos. Bagnall, jun. . | 3 | 2 |
| 10 | Lackenby, Middlesbro' | Downey & Co. | 3 | 3 |
| 11 | Linthorpe " " | Edward Williams | 6 | 3 |
| 12 | Skinningrove " " | The Skinningrove Iron Co., Lim. | 2 | 2 |
| 13 | Newport, Middlesbro' | B. Samuelson & Co. | 8 | 8 |
| 14 | Normanby, " " | Jones, Dunning & Co. | 3 | 3 |
| 15 | Ormesby, " " | Cochrane & Co. | 4 | 4 |
| 16 | Redcar | Walker, Maynard & Co. | 4 | 4 |
| 17 | South Bank, Middlesbro' | Bolckow, Vaughan & Co., Lim. . | 8 | 8 |
| 18 | Tees, Middlesbro' | Wilson, Pease & Co. | 5 | 5 |
| 19 | Tees Side, " " | Tees Side Iron & Engine Works { Co. | 4 | 4 |
| 20 | Thornaby, Stockton | William Whitwell & Co. | 3 | 3 |
| Total of North Riding . . . | | | 91 | 80 |

Distribution of Cleveland Pig-Iron.—The pig-iron is widely distributed at home and abroad, and is increasing yearly. The total quantities shipped to foreign countries, and to other parts of the United Kingdom, from the port of Middlesborough during the four years ending 1880, were as follows :— *

| Year. | Foreign. | Coastwise. | Total. |
|-------|----------|------------|---------|
| | Tons. | Tons. | Tons. |
| 1877 | 321,946 | 460,390 | 782,336 |
| 1878 | 337,559 | 422,480 | 760,339 |
| 1879 | 395,658 | 419,905 | 815,563 |
| 1880 | 495,638 | 464,943 | 960,581 |

The foreign countries receiving the shipments in each of the same years appear in the annexed statement :—

* Cleveland Iron Masters' Association Returns, 5 Jan., 1881.

| Countries. | 1880. | 1879. | 1878. | 1877. |
|-------------------------|---------|---------|---------|---------|
| | Tons. | Tons. | Tons. | Tons. |
| Germany | 110,611 | 106,681 | 96,801 | 90,368 |
| Holland | 69,684 | 68,732 | 72,930 | 67,660 |
| France | 68,085 | 53,809 | 61,297 | 68,946 |
| Belgium | 73,144 | 44,565 | 50,270 | 41,620 |
| Sweden | 12,487 | 8,776 | 10,162 | 11,290 |
| Norway | 5,385 | 7,758 | 6,763 | 12,763 |
| Spain | 18,695 | 23,223 | 12,311 | 9,377 |
| Portugal | 6,328 | 10,250 | 11,592 | 4,901 |
| Russia | 33,454 | 22,060 | 9,000 | 7,199 |
| Denmark | 4,243 | 3,162 | 1,883 | 3,720 |
| Italy | 1,645 | 2,967 | 3,495 | 3,987 |
| Jersey | ... | 75 | 80 | ... |
| India | 250 | ... | 270 | 125 |
| Japan | 900 | ... | 550 | ... |
| China | 300 | ... | ... | ... |
| Austria | 140 | 600 | ... | ... |
| B. N. America | ... | 1,000 | 205 | ... |
| U. S. America | 90,087 | 42,000 | ... | ... |
| Egypt | 200 | ... | ... | ... |
| Total | 495,638 | 395,658 | 337,559 | 321,946 |

The shipment coastwise, and the respective ports receiving the same, were as follows in each of the same years :—

| Ports. | 1880. | 1879. | 1878. | 1877. |
|-----------------------|---------|---------|---------|---------|
| | Tons. | Tons. | Tons. | Tons. |
| Scotland | 283,463 | 285,846 | 330,554 | 317,249 |
| Wales | 88,204 | 70,267 | 58,740 | 60,339 |
| Newcastle | 52,332 | 35,492 | 30,716 | 48,478 |
| Other ports | 39,944 | 28,300 | 32,470 | 34,324 |
| Total | 464,943 | 419,905 | 422,480 | 460,390 |

Average Price of Cleveland Pig-Iron.—Following the pages of those journals devoted to the progress of the iron trade, evidence is afforded of the very low prices of pig-iron in recent years. In 1873 the highest price that Cleveland pig attained in the market was reached, namely, £5 9s. 2d., since which date it has receded, till in July, 1879, it was sold (No. 8) at 32s. per ton. An improvement appears in 1880, when the average of the year's quotations shows an increase of nearly 10s. per ton. The variations in previous years were as follows :—

| Year. | Average. | | | Highest. | | | Lowest. | | |
|-------|----------|----|----|----------|----|----|---------|----|----|
| | £ | s. | d. | £ | s. | d. | £ | s. | d. |
| 1868 | 2 | 3 | 2 | 2 | 9 | 6 | 2 | 3 | 0 |
| 1869 | 2 | 5 | 9 | 2 | 10 | 0 | 2 | 3 | 0 |
| 1870 | 2 | 10 | 3 | 2 | 13 | 0 | 2 | 7 | 6 |
| 1871 | 2 | 9 | 8 | 3 | 5 | 0 | 2 | 6 | 6 |
| 1872 | 4 | 17 | 1 | 5 | 15 | 0 | 3 | 5 | 0 |
| 1873 | 5 | 9 | 2 | 6 | 5 | 0 | 4 | 7 | 6 |
| 1874 | 3 | 10 | 11 | 4 | 7 | 6 | 3 | 0 | 0 |
| 1875 | 2 | 14 | 6 | 2 | 19 | 0 | 2 | 9 | 0 |
| 1876 | 2 | 7 | 10 | 2 | 13 | 6 | 2 | 5 | 0 |
| 1877 | 2 | 2 | 1 | 2 | 6 | 0 | 2 | 5 | 0 |
| 1878 | 1 | 18 | 2 | 2 | 1 | 0 | 1 | 14 | 6 |
| 1879 | 2 | 1 | 2 | 2 | 15 | 0 | 1 | 16 | 6 |
| 1880 | 2 | 10 | 6 | 3 | 9 | 0 | 2 | 2 | 0 |

The lowest price previous to 1878 was in 1868, when the average was but £2 8s. 2d.; and it is only necessary to add that the average price in 1879 increased, owing to the sudden impulse imparted to the iron trade in the last quarter of the year, when prices rose from 38s. to 55s. per ton.

Coal and Ironstone used in Manufacture.—Mr. Windsor Richards, who has carefully considered the question of fuel used in manufacture, and who has followed its economy, says, that “the improvements most conspicuous in recent blast furnace practice are to be found in the better means adopted for heating the blast in the Cowper and Whitwell firebrick stoves. It is difficult,” he adds, “to ascertain the amount of coke consumed to make a ton of Cleveland iron, as blast furnace managers are very reticent on this point, but there is little doubt that the consumption of coke has of late years increased and is increasing, and the matter is so important to us as a district in the severe competition we have to contend with, that the following details, describing the alterations recently made in these stoves, to render them efficient and economical, will be interesting” :—

“The Cowper stove is made much higher than formerly, so giving largely-increased heating surface, which reduces the temperature of the escaping gases at the chimney valve to about 400 degrees Fah., after having been on gas for three hours, thus utilising to the fullest practicable extent the waste gases of the former. The stoves are now made up to 25 feet diameter and 54 feet high, and have the enormous heating surface of 75,000 feet. With two such stoves to a large furnace the heat may be kept on

for four hours, with a loss of heat not exceeding 150 degrees. The combustion chamber, or flame flue, has been moved from the centre to the side of the stove, whereby the whole surface of the brickwork is rendered effective for absorbing and giving up heat. The gas is admitted at the bottom of this combustion chamber, and is split up into three parts so as to attain a more complete mixture of air and gas, which, in the increased diameter of the chamber, enables more gas to be consumed, giving a better flame to the centre of the flue. The simple means adopted of clearing the dust from the stove during tapping time (the man-hole floors are hinged, and can, by the aid of a long lever, be readily opened and closed) and the sudden letting out of the compressed air through these openings clears away some of the dust. Any dust which may be lodged in the stove can be got down by light charges of gunpowder fired through the 'sight-holes.' If these simple expedients are regularly attended to the stove can be kept continuously at work for many months together. There is also a specially constructed down-comer for the gas, with a contrivance for trapping some of the dust, and so prevent it from entering the stove. The bricks used in the regenerator are made larger than formerly, the size now preferred being 2 inches by 5 inches by 12 inches. There are also tiles placed over the very many passages to distribute the products of combustion equally over the whole regenerator. By these means the blast may be readily heated up to 1,500 degrees Fah. The hot-air valve, which used to be very troublesome in these stoves when they were first designed, now works very well, and without any water for keeping it cool."

Mr. W. Richards further remarks, in reference to the Whitwell stoves, that at several works which he lately visited—Cockeril, in Belgium; Denain, in France, and Millom—he noticed that the Whitwell stoves are being increased in height. Mr. Massicks, of Millom, has raised a set of stoves for one furnace from 28 feet to 40 feet, and finds that the temperature of the escaping gases from the 40 feet stoves, taken at the chimney valve, is 360 degrees Fah., and that of the 28 feet stove, taken under exactly similar circumstances, is 495 degrees Fah. Both of these were taken after having been on gas for three hours. This alteration, by increasing the heating surface, gives greater regularity of work in the blast furnace. These stoves are now being built

15 feet, 18 feet, and 22 feet diameter, by 40 feet, 50 feet, and 60 feet high, according to circumstances; and in America Whitwell's stoves are being constructed 21 feet in diameter and 70 feet high, each stove having 30,900 feet of heating surface. The advantages of these high stoves are increased heating surfaces, more perfect combustion, and reduced number of stoves, consequently reduced space and cost per furnace. The gases enter the large combustion chamber, where they are mixed with hot air, drawn by a new arrangement through the bottom brick-work of the stove. The flame rises to the top of the combustion chamber, then descends three smaller chambers at the same time, where it is mixed with more warm air; it again ascends through two or three chambers at a time, and finally descends the three or four remaining chambers, having been mixed with air at each ascent and descent. It then escapes at the chimney valve at a very low temperature, say from 800° to 400° Fahr. Doors allow access for the scrapers for removing the dust from the walls of the chambers, and other doors, six in number, allow of the dust which has fallen from the walls being readily removed from the bottom of the stove. This scraping and cleaning of the stove need not occupy more than six hours every three or four months, and there is no necessity for cooling down the stove for cleaning, for directly the blast is shut off the operation of cleaning can be immediately commenced. There is a disadvantage in having several firebrick stoves working into one large main flue leading to a single chimney, as it necessitates the stoppage of the whole of the blast furnaces during the time the main flue is being cleaned. Perhaps a better arrangement would be to erect a wrought-iron chimney for each stove, just high enough to convey the waste gases over the heads of the men charging the blast furnaces. The chimney could be secured to the stove itself, and the waste heat is so low that no damage would result to the plates of the chimney.

The united improvements of these hot-air stoves in recent years, and the adjustment of the blast furnace to the largest capacity, consistent with economy, for smelting the ore of Cleveland, have mainly contributed to economy in the use of fuel. In 1860 the consumption of fuel was an average of 38 cwts. of coke, or 63 cwts. of coal per ton of iron, the coal yielding 60 per cent. of coke. As

a matter of general practice, Mr. I. Lowthian Bell * says "that a capacity of 12,500 cubic feet, with air at 1,000° Fahr., is regarded as effecting all that can be hoped for in reducing the coke required for the blast furnace. Other considerations connected with labour, &c., have led many ironmasters to think that a furnace 80 feet high, with a diameter of 25 feet, and containing therefore 25,000 cubic feet, when supplied with air at 1,000 degrees Fahr., is as economical a form as can be devised for smelting the ironstone of Cleveland. The weekly make of a furnace of the above dimensions is said to be 400 tons."

Following the consumption of fuel in the manufacture of pig-iron, the annexed statement gives, for the nine years ending 1880, the pig-iron made and the coal and ironstone used in its manufacture :—

| Year. | Pig-Iron Made. | Coal Used. | Ore Used. |
|-------|----------------|------------|-----------|
| | Tons. | Tons. | Tons. |
| 1872 | 1,122,114 | 2,533,781 | 3,493,000 |
| 1873 | 1,156,431 | 2,643,997 | 3,489,383 |
| 1874 | 1,158,471 | 2,896,177 | 3,504,660 |
| 1875 | 1,240,243 | 2,875,357 | 3,740,300 |
| 1876 | 1,261,013 | 2,923,870 | 3,807,800 |
| 1877 | 1,374,582 | 3,220,616 | 4,339,907 |
| 1878 | 1,358,442 | 2,934,634 | 4,234,017 |
| 1879 | 1,210,091 | 2,589,660 | 3,699,108 |
| 1880 | 1,666,156 | 3,611,543 | 5,044,420 |

An analysis of these figures shows that in 1872 and 1873 each ton of pig-iron consumed 46 cwts. of coal; in 1876 and 1877 it was slightly above this average, while in 1878 and 1879 the average was about $41\frac{3}{4}$ and $42\frac{3}{4}$ cwts. of coal respectively to each ton of pig-iron made. In 1872 the average of the kingdom was 51 cwts. of coal to each ton of iron made, compared with 44 cwts. in the year 1880, showing economy to the extent of 7 cwts. of coal to each ton of iron made, equivalent to a saving of nearly 14 per cent. in a period of nine years.

The average amount of metallic iron in the ores of Cleveland is about 30 per cent., and where the ore alone is employed 70 cwts. of raw stone is required to each ton of pig-iron. The ironstone is previously calcined in suitable kilns—the mineral

* "Notes on the Progress of the Iron Trade."—*The Iron and Coal Trade Review* June 7th, 1878.

being thus concentrated, 100 tons of raw stone yielding on calcination from 70 to 75 per cent. of metal, and even more. In the calcination of the ironstone, in Gjer's calcining kilns, largely employed in the district, having a capacity of 5,500 cubic feet, about one ton of coal slack is required for each 20 tons of ironstone, while in kilns of larger capacity the consumption of fuel is reduced to one ton per 25 tons of ironstone.

As previously stated, 70 cwts. of raw Cleveland stone is required for each ton of pig-iron made; considerable quantities of richer ores are, however, employed; these are the hematites of the west coast, and of Spain, containing from 50 to 60 per cent., and even more, of metallic iron, which, when used in admixture with the Cleveland stone, greatly diminishes the quantity of ore employed in making each ton of iron, which does not exceed from 60 to 62 cwts.

Referring to the question of fuel and ore used in the Cleveland furnaces, it only remains to add that the coke employed is obtained from the Durham coal-field, the iron ore employed, as already stated, being derived from various localities; the great bulk being obtained in the district.

Of the iron ore thus employed, the statement below, prepared from numerous sources, will show approximately the quantities used, and from whence derived, in each year since 1872:—

| Year. | Cleveland Ironstone. | Cumber- land Ore. | Lancashire Ore. | Foreign Ore. | Other Ores. | Total Iron Ore used. |
|-------|-------------------------|----------------------|--------------------|-----------------|----------------|-------------------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1872 | 2,955,000 | 32,498 | 17,502 | 58,000 | 430,000 | 3,493,000 |
| 1873 | 2,920,000 | 32,629 | 30,250 | 64,280 | 442,224 | 3,489,383 |
| 1874 | 2,980,500 | 57,668 | 11,210 | 49,379 | 404,903 | 3,504,660 |
| 1875 | 3,296,824 | 32,438 | 10,000 | 27,523 | 373,515 | 3,740,300 |
| 1876 | 3,524,962 | 38,736 | 21,600 | 94,269 | 108,233 | 3,807,800 |
| 1877 | 3,980,770 | 40,087 | 25,945 | 133,562 | 159,543 | 4,339,907 |
| 1878 | 3,850,045 | 37,578 | 25,430 | 178,982 | 135,982 | 4,234,017 |
| 1879 | 3,380,015 | 37,896 | 31,694 | 112,247 | 137,256 | 3,699,108 |
| 1880 | 4,463,229 | 35,298 | 22,646 | 430,212 | 93,035 | 5,044,420 |

The quantities in the column "other ores" include ores from various localities, Cornwall, Devonshire, &c.; also forge and mill cinder from the malleable-iron works and "purple ore."

Malleable Ironworks and Steelworks.—The Middlesborough Bar Ironworks were projected by the Messrs. Bolckow & Vaughan about the year 1840, and twenty years later consisted of

70 puddling furnaces and 6 rolling mills. In the year 1852 these works turned out no less than 56,000 tons of plate, rails, and other kinds of finished iron, including angle-iron of all sizes. In 1860 the works and their resources were as follows, giving an aggregate of 116 puddling furnaces and 16 rolling mills :—

| Name of Works. | Name of Firm. | Number of Puddling Furnaces. | Number of Rolling Mills. |
|-------------------|--|------------------------------|--------------------------|
| Middlesbro' . . . | Bolckow & Vaughan . | 70 | 6 |
| Tees | { Gilkes, Wilson, Pease } & Co. | 5 | 6 |
| Tees Side | Hopkins & Co. . . . | 41 | 4 |
| | Total | 116 | 16 |

Recently, in the pages of the *Colliery Guardian*,* appeared an interesting account of the finished iron trade of Cleveland, from which many of the following facts and figures are drawn. The puddling furnace and the rolling mill inevitably followed in the train of the blast furnace, and as the number of the latter multiplied so also did the former increase. During the decade 1860—1870 the height and economy of the blast furnace was the all-absorbing question in the district, and after came that of mechanical puddling. In 1870 there were 20 works in Durham and 11 in Cleveland, with a total of 1,582 puddling furnaces and 97 rolling mills, of which 529 puddling furnaces and 30 rolling mills were in Cleveland, the remainder being in Durham, giving an average of 51 puddling furnaces and 3 rolling mills to each concern.

The works and firms in operation in 1870 were as follows :—

| Name of Works. | Name of Firm. | Situate. | Puddling Furnaces. | Rolling Mills. |
|-------------------|----------------------------------|-------------|--------------------|----------------|
| North Yorkshire . | North Yorkshire Iron Co., Lim. . | Middlesbro' | Nos. 58 | Nos. 1 |
| Cleveland . . . | Bolckow & Vaughan | " | } 175 | 8 |
| Middlesbro' . . . | " " | " | | |
| Witton Park . . . | " " | " | | |
| Tees Side | Hopkins, Gilkes & Co., Limited . | " | 102 | 5 |
| Newport | Fox, Head & Co. | Stockton | 54 | 2 |
| Stockton | Stockton Malleable Iron Co. . . | " | 56 | 5 |
| Thornaby | William Whitwell & Co. . . . | " | 31 | 3 |
| Yorkshire | Richardson, Dack & Co. . . . | " | 9 | 2 |
| Westbourne . . . | John Holdsworth & Co. . . . | " | 21 | 1 |
| West Stockton . . | West Stockton Iron Co. . . . | " | 23 | 3 |
| | Total of District | | 529 | 30 |

* 17th December, 1880, p. 971.

About this time, and until 1873, trade was in a buoyant state, but the resources for manufacture also increased, several new works being projected; however, towards the close of the last-named year prices began to decline, and this told heavily upon the department of trade in the district; indeed, no other department and no other district felt it so heavily. Towards the close of 1879 only one-half of the works for the manufacture of finished iron were in operation. Of the works in this district and Durham 22 were standing in 1879, representing a total of 1,328 puddling furnaces, and in October, 1879, Mr. Wm. Whitwell gave the following as the condition of these furnaces:—

| | FURNACES. |
|--|--------------|
| Failed and not since restarted | 821 |
| Pulled down for steelworks | 67 |
| Standing possibly temporarily | 432 |
| Working | 830 |
| Total furnaces | <u>2,160</u> |

The depression in the finished iron trade was decisively shown in 1876, when there was a great falling off in the production. In 1877 this was made manifest by a decrease in the number of works employed in that department of the trade. Not the least remarkable feature of the trade is the fact that the production of finished iron decreased while that of pig-iron increased.

There is no means of ascertaining correctly the quantity of finished iron made annually, statistics not being collected in this branch of the iron trade. There is, however, one reliable source of information. Since the year 1872 the firms on the north-east coast, that are associated with the Board of Arbitration for the district under review, have given annual returns of their production. It is believed that between the years 1872 and 1877 the firms in association produced nine-tenths of the total finished iron in the district, but since 1877, owing to some large firms having withdrawn from that board, the statistics issued under its auspices are said now to represent only three-fourths of the total production.

From the returns of the Board of Arbitration, in each of the following years, will be seen the proportion of the several varieties of finished iron, and the fluctuations to which each of these branches of the trade has been subject:—

| Year. | Rails. | Plates. | Bars. | Angles. | Total. |
|-------|---------|---------|---------|---------|---------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1872 | 330,000 | 194,857 | 82,653 | 63,967 | 671,477 |
| 1873 | 356,884 | 182,151 | 87,368 | 48,843 | 675,246 |
| 1874 | 291,520 | 196,099 | 100,157 | 54,450 | 642,226 |
| 1875 | 270,828 | 190,757 | 111,800 | 45,369 | 618,754 |
| 1876 | 118,615 | 189,611 | 97,133 | 57,930 | 463,289 |
| 1877 | 40,425 | 236,195 | 84,844 | 73,738 | 435,202 |
| 1878 | 25,973 | 280,754 | 93,937 | 105,178 | 505,842 |
| 1879 | 8,460 | 217,121 | 76,848 | 61,114 | 363,543 |
| 1880 | 27,414 | 316,720 | 71,377 | 92,897 | 508,434 |

The branch of the finished iron trade that has shown the greatest diminution is the manufacture of iron rails, and Mr. Edw. Williams, President of the Iron and Steel Institute, explained the cause of the decay of the industry clearly in a recent address, when he said: "That for rail making the puddling forge has disappeared, and it is highly improbable that it will return. The place of it has been entirely taken by the Bessemer pit, which, in principle, general arrangement, and the most minute details, remains as it came from the hands of the inventor, and seems scarcely to admit of much improvement.

"If it be true that iron rails are doomed to ultimate disuse, it is no less true that the present year has witnessed the beginning, in Cleveland, of the manufacture of steel rails from its own native iron, the cheapest in the world. The basis of a new industry has been laid in this department of the trade under the most favourable auspices. The firm of Messrs. Bolckow & Vaughan, who were the pioneers of the Cleveland iron trade, and who now produce one-third of the total quantity of the iron produced in the district, have also taken the lead in the establishment of steel works. In the year 1877 they opened the Eston Steelworks, which had been about eighteen months in course of construction. They were started especially for the manufacture of steel rails, and for that purpose Spanish hematite was imported in considerable quantities. Since then the discovery of the basic process of dephosphorisation last year, and its successful application more recently at the above-named works, will probably prove the commencement of a new and more promising era in the history of the finished iron trade of Cleveland."

The successful issue of the experiments made in this direction

are thus referred to by Mr. E. W. Richards, in his address to the Institution of Cleveland Engineers, in November, 1880.

The Thomas-Gilchrist Process.—He said: "A short history and description of a process which has created so much interest in the metallurgical world during the last two years will no doubt be of interest to you. Messrs. Thomas and Gilchrist made numerous experiments on a small scale at the Blaenavon Iron-works, where they were assisted by the manager, Mr. Edward P. Martin, and they tried also a couple of casts in a large converter at Dowlais. They prepared a paper, giving very fully the results of their experiments, with analyses, which was intended to be read at the autumn meeting of the Iron and Steel Institute in Paris in 1878; but so little importance was attached to it, and so little was it believed in, that the paper was scarcely noticed, and it was left unread till the spring meeting in London in 1879. Mr. Sidney Thomas first drew my particular attention to the subject at Creusot, and we had a meeting a few days later in Paris to discuss it, when I resolved to take up the matter, provided I received the consent of my directors. The consent was given, and on the 2nd of October, 1878, accompanied by Mr. Stead, of Middlesborough, I went with Mr. Thomas to Blaenavon. Arrived there, Mr. Gilchrist and Mr. Martin showed me three casts in a miniature cupola, and I saw sufficient to convince me that iron could be dephosphorised at a high temperature. I visited the Dowlais Works, where Mr. Menelaus informed me that the experiments with the large converter had failed, owing to the lining being washed out. We very quickly erected a pair of 30 cwt. converters at Middlesborough, but were unable for a long time to try the process, owing to the difficulties experienced in making basic bricks for lining the converter and making the basic bottom. The difficulties arose principally from the enormous shrinkage of the magnesian limestone when being burnt in a kiln with an up-draught, and of the failure of the ordinary bricks of the kiln to withstand the very high temperature necessary for efficient burning. The difficulties were, however, one by one surmounted, and at last we lined up the converters with basic bricks, when, after much labour, many failures, disappointments, and discouragements, we were able to show some of the leading gentlemen of Middlesborough two successful operations on Friday, April 4th, 1879. The news of this success spread

rapidly far and wide, and Middlesborough was soon besieged by the combined forces of Belgium, France, Prussia, Austria, and America. We then lined up one of the 6-ton converters at Eston, and had fair success. The next meeting of the Iron and Steel Institute in London, under the presidency of Mr. Edward Williams, was perhaps the most brilliant and interesting ever held by the Institute. Messrs. Thomas and Gilchrist's paper was read, and the explanations and discussions by other members of the Institute were listened to with marked attention. Directly the meeting was over, Middlesborough was again besieged by a large array of Continental metallurgists, and a few hundred-weights of samples of basic bricks, molten metal used, and steel produced were taken away for searching analysis at home. Our Continental friends were of an inquisitive turn of mind, and, like many other practical men who saw the process in operation, only believed in what they saw with their own eyes and felt with their own hands—and were not quite sure then, and some are not quite sure even now. We gave them samples of the metal out of the very nose of the converter. Our method of working at that time was to charge the additions of oxide of iron and lime at the same time into the converter, and pour the molten metal upon them. The quantity of additions varied from 15 to 25 per cent. on the metal charged, according to the amount of silicon in the pig-iron used. We soon found that the oxide of iron was unnecessary; besides, it cooled the bath of metal, and we afterwards used lime additions only. After about three minutes under blow, a sample of metal was taken from the converter, quickly flattened down under a steam hammer, and cooled in water. The fracture gave clear indications of the malleability of the iron. When the bath was sufficiently dephosphorised to give a soft ductile metal, the spiegel was added. Other firms have taken up the manufacture of steel on the basic system, notably the Hoerde Company, in Westphalia, and Messrs. Brown, Bayley & Dixon, of Sheffield. Very interesting papers on the subject have been read by Messrs. Pink and Messenez and Messrs. Holland and Cooper. On Monday, the 23rd of August last, I visited the Hoerde Works with a few friends, and saw two successful casts in a small converter. Imitating the good example set me, and having good friends in Messrs. Messenez and Pink, I took a sample of the remelted pig as it was running from the cupola to the converter,

and a sample of dephosphorised metal and of the steel. Mr. Cook's analysis is: Re-melted pig—Combined carbon, 2·75; manganese, ·50; silicon, ·9; sulphur, ·31; phosphorus, 1·51. This analysis agrees with that given by Mr. Messenez in his paper read before the Institute. The metal, after three minutes' after-blow, gave phosphorus, ·13, and a further 25 seconds gave phosphorus ·10; carbon, a trace; manganese, ·17; sulphur, ·12. At this stage of the operation a large quantity of slag was poured out of the converter, and then the spiegel was added. The steel contained carbon, ·19; manganese, ·57; sulphur, ·10; phosphorus, ·10. The steel worked well under the steam hammer. The slag was of the following composition:—Iron, 10·20; lime, 46·94; silica, 9·67; phosphoric acid, 9·70. On Thursday, the 20th August, I visited the Rhenish Steelworks with several members of the Iron and Steel Institute, and the samples brought home were analysed by Mr. Cook, who shows re-melted metal to contain—Combined carbon, 2·90; manganese, 1·10; silicon, ·46; sulphur, ·16; phosphorus, 2·03. The after-blow was very long, being nearly 4½ minutes before the first sample was taken, and a further three-quarters of a minute before the second sample was taken—in all five minutes. The carbon lines appeared on the spectroscope in a few seconds after the converter was turned up. The steel contained:—Carbon, ·28; manganese, ·56; sulphur, ·08; phosphorus, ·08—the metal, before the addition of the spiegel, having P, ·07. In a second cast the steel gave—C, ·27; M, ·40; S, ·07; P, ·10. The slag here is not passed off before the spiegel is added. The sample of slag analysed by Mr. Cook is almost identically the same as that given above from the Hoerde Works. Another cast, made when about 150 members of the Institute were present, contained, I am informed, P, ·13. It was most difficult to get near the workmen who were testing the samples, so great was the crush and the desire to obtain a piece of metal, and the wonder was that the metal was so well blown and so low in phosphorus, considering the circumstances under which the operation was conducted. At the meetings of the Institution in December last I mentioned that Messrs. Bolckow, Vaughan & Co., Limited, were about to erect some large converters at the Cleveland Steelworks of a size and form which they expected would enable them to overcome some of the difficulties which they experienced when working with the old converters on the basic system."

Mr. Richards next directed attention to a new converter ; continuing, he said : " This converter is concentric, whilst the old converters are eccentric. During the operation of blowing, the lime and the metal are lifted by the force of the blast, and when that force is somewhat expended the materials fall again on to the bottom in the new form, whilst in the old form some portions would cling to the nose. The ' concentric ' form has also another advantage ; it gives a much larger area of floor to work in, by enabling the metal to be poured into the converter when turned on its side with the nose pointing away from the converter ladle crane, just the contrary of the present practice. On the 18th October last this converter was set to work on the basic system, and was quite successful, answering the purpose well, and showing no more symptoms of gathering at the outlet than when making ordinary steel. Our plan of operation is exceedingly simple. The converter, as is usual, is first heated up with coke so as to prevent the chilling of the metal. Then a measured quantity of well-burnt lime, about 16 per cent. of the weight of molten metal, mixed with a small quantity of coal or coke, is charged into the converter, and blown till the lime is well heated. The molten metal is then poured on the lime additions, the blast of 25 lbs. pressure is turned on, and the carbon lines disappear in about ten minutes ; then after about $2\frac{1}{2}$ minutes over-blow the converter is turned down, and a small sample just made, which is quickly beaten into a thin sheet under a small steam hammer, cooled in water, broken in two pieces, and the fracture shows to the experienced eye whether the metal is sufficiently ductile. If it is not so, then the blowing is prolonged, after which the spiegel is added, and is now being poured into the ladle, not into the converter. For the basic process the initial bath should be low in silicon, because silicon fluxes and destroys the lining, and causes waste of metal ; it should be low in sulphur, so that the metal may not be red short. Nearly one-half the sulphur is eliminated by the basic process. In order to work economically the metal should be taken direct from the blast furnace, so as to avoid, first, the cost of re-melting in a cupola ; and, second, to avoid further contact of the metal with the sulphur and impurities of the coke. It is not an easy matter to accomplish, in a blast furnace, the manufacture of a metal low in silicon and at the same time low in sulphur. It would, no doubt, very much help to

keep sulphur low if maganese was added in the blast furnace, but maganese is a costly metal. At present we have succeeded in making a mottled Cleveland iron with 1 per cent. of silicon and '16 sulphur, and white iron with '5 silicon and '25 sulphur, which, taken direct from the blast furnace, have both made excellent steel. But we have another method of operating, which relieves us from the necessity of making a particular quality of Cleveland pig-iron. We call this second mode of working the transfer system, because we transfer the metal from the acid to the basic converter. The transfer system enables us to take any grey iron direct from the blast furnace to the converter without any consideration as to the per centage of sulphur, which is always low in grey iron. This grey metal is poured into a converter with a silicious lining, and desiliconised, when, after say twelve or fifteen minutes' blowing in the ordinary manner, it is poured out of the converter into the ladle, and poured again from the ladle into a converter lined with dolomite, taking care that the highly silicious slag is prevented from entering the basic-lined converter. Then in the second converter it is only necessary to add sufficient lime for the absorption of the phosphorus of the metal, and the blowing then need not occupy more time than is necessary for the elimination of the phosphorus, say about three minutes. This mode of operation will no doubt give the basic lining and bottom a much longer life, but we have not yet been long enough at work to obtain the necessary experience to determine which is the better system of working, but both are good and effective, and have given excellent results. I have thus summed up in ten minutes what has taken about two years of constant work, and the expenditure of large sums of money, to accomplish. I am now able to say that the basic process has been brought to a technical and commercial success at the Cleveland Steelworks of Messrs. Bolckow, Vaughan & Co. One feature in this new process seems to have been lost sight of by those who have written on the subject, namely, the possibility or otherwise of being able to eliminate phosphorus before the carbon flame drops, so as to avoid the after-blow. Few give any hope of this being accomplished, but when we remember that few gave any hope of the basic process, or any other process, being successful in eliminating phosphorus at the high temperature of the Bessemer converter, we should not abandon research or relax efforts. It

has been said, over and over again, that the basic process was a failure, and would never succeed. It is a grand trait in the character of our Englishmen, that of not knowing when they are beaten. If the after-blow could be avoided, the wear of the lining and bottoms would be very much reduced. We know already that the basic lining will not be anything like so enduring as the acid lining, so special means have been adopted to quickly change a converter. An overhead steam-travelling crane, capable of lifting sixty tons, is being erected, so that directly a converter lining has worn out the crane will remove the worn converter out of the way, and bring in a re-lined one dried and ready for working. A very ingenious plan for quickly changing the converter, without removing the trunnion, is that patented by Mr. Holley, the well-known American engineer and metallurgist. The converter, freed from the trunnion, is lowered to the floor by means of the hydraulic ram. Then a re-lined and dried converter is placed on a four-wheeled bogie, and ran from the repairing and drying shed into position on the top of the hydraulic ram, which is placed directly under the trunnion. The water is turned on, and the converter is raised into position, and is then fastened by a dozen cotters to the trunnion, and is thus got very quickly ready for work."

The following is a list of the malleable-iron works in Cleveland in 1880, with the number of furnaces and mills in operation :—

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-------------------|-----------------------|--|----------------------------------|---------------------------|-----------------------|
| 1 | Ayrton Rolling Mills | Jones Bros. & Co., Lim. | Stockton-on-Tees | 29 | 2 |
| 2 | Bowesfield | Bowesfield Iron Co. | " | 33 | 3 |
| 3 | Britannia | Dorman, Long & Co. | Middlesbro' | 60 | 1 |
| 4 | Erinus | Erinus Iron Co., Lim. | " | .. | .. |
| 5 | Easton Grange | Easton Grange Iron Co. | " | .. | .. |
| 6 | North Yorkshire | { North Yorkshire Iron Co., Limited | Stockton-on-Tees | .. | .. |
| 7 | Carlton | The Carlton Iron Co., Lim. | " | .. | .. |
| 8 | Cleveland | Bolckow & Vaughan | " | .. | 5 |
| 9 | Middlesbro' | " | " | .. | 1 |
| 10 | Tees Side | { Hopkins, Gilkes & Co., Limited. 11 Danks's | " | 80 | 4 |
| 11 | Newport | Fox, Head & Co. | " | 46 | 4 |
| 12 | Yorkshire | { South Yorkshire Iron Co., Limited | " | .. | .. |
| 13 | Westbourne | John Holdsworth & Co. | " | 22 | 2 |
| 14 | West Marsh | Dorman, Long & Co. | " | 20 | 2 |
| 15 | Hull | { East Riding Malleable Ironworks | Hull | .. | .. |
| 16 | Imperial (South Bank) | Jackson, Gill & Co., Lim. | " | 38 | 3 |
| 17 | Star | Star Rolling Mills Co. | Middlesbro' | .. | .. |
| Total of District | | | | 328 | 25 |

Considering the consumption of fuel in these works, it was ascertained that in the year 1872 some 640,000 tons of coal were used, increased to 660,000 tons in the following year; since that date the fuel consumed annually in these works in Cleveland has fallen off considerably, and in the year 1879 did not exceed 405,000 tons. It has been observed that when the manufacture of iron rails in Cleveland saw its best days, that district produced, it is estimated, nearly one-third of the rails made in the United Kingdom. The success which has attended the process of dephosphorising Cleveland iron brings it within the bounds of possibility that that district may before long occupy as prominent a position in the manufacture of steel rails as of old it held in the iron rail trade. Already the leading firm is reported to be producing steel at the rate of 150,000 tons per annum, nearly double the total quantity produced last year in the whole district, and if that is mostly made into rails, the revival of that industry is as rapid as was the decline of the iron rail trade.

Prices of Malleable Iron and Puddlers' Wages.—These have been subject to great fluctuations; the average prices of rails, plates, bars, and angles, in 1879, were about one-half of the prices current in 1873, and wages showed a corresponding fluctuation. From the Board of Arbitration returns in each year since 1872 the average selling prices of iron, including rails, plates, angles, and bars, were as follows; and side by side appears the average puddlers' wages, in each of the same years :—

| Year. | Average Selling Price. | | | Average Puddlers' Wages | |
|-------|------------------------|----|----|-------------------------|----|
| | £ | s. | d. | s. | d. |
| 1872 | 9 | 0 | 3 | 11 | 6 |
| 1873 | 11 | 9 | 1 | 13 | 0 |
| 1874 | 10 | 9 | 5 | 11 | 7 |
| 1875 | 8 | 1 | 0 | 9 | 4 |
| 1876 | 7 | 2 | 2 | 8 | 3 |
| 1877 | 6 | 15 | 3 | 8 | 3 |
| 1878 | 6 | 2 | 7 | 7 | 8 |
| 1879 | 5 | 8 | 6 | 7 | 0 |
| 1880 | 6 | 3 | 9 | 7 | 9 |

The highest price reached was in the year 1873, when puddlers' wages were 13s. 3d. during nine months of that year.

Prices fell in the following year, and wages increased somewhat. The rate of wages changed four times in 1874, and three times in 1875. During 1876 and 1877 it remained stationary, since which, in 1878 and 1879, the tendency was downwards. However, in the first half of 1880 the wages of puddlers gave an average of 8s. 3d., while the realised prices per ton fell to £5 5s. 6d.

Following the prices of each variety of iron since the year 1872, the annexed statement, based upon the returns of the Board of Arbitration, will indicate those of plates, bars, and angles, which were as follows :—

| Year. | Plates. Average. | | | Bars. Average. | | | Angles. Average. | | |
|-------|---------------------|----|----|-------------------|----|----|---------------------|----|----|
| | £ | s. | d. | £ | s. | d. | £ | s. | d. |
| 1872 | 10 | 6 | 1 | 9 | 16 | 4 | 9 | 1 | 11 |
| 1873 | 12 | 6 | 1 | 12 | 5 | 3 | 11 | 11 | 1 |
| 1874 | 11 | 6 | 4 | 10 | 15 | 7 | 10 | 11 | 10 |
| 1875 | 8 | 14 | 9 | 8 | 9 | 8 | 8 | 3 | 6 |
| 1876 | 7 | 9 | 9 | 7 | 1 | 8 | 7 | 0 | 4 |
| 1877 | 6 | 19 | 8 | 6 | 16 | 2 | 6 | 8 | 1 |
| 1878 | 6 | 6 | 9 | 6 | 4 | 6 | 5 | 13 | 2 |
| 1879 | 5 | 10 | 10 | 5 | 8 | 11 | 5 | 1 | 3 |
| 1880 | 6 | 9 | 5 | 6 | 7 | 9 | 5 | 14 | 9 |

From the annual Report of the British Iron Trade Association, for the year 1879, some very interesting facts are obtained, showing the average prices, in each of the above years, of iron rails, as compared with steel rails, the former being, in 1872, £9 6s. per ton, compared with £4 18s. 3d. in 1879; while steel rails were, in 1872, current at £13 17s. 6d. per ton against £5 2s. 6d. per ton in 1879. The average prices are as follows :—

| Year. | Price of Iron Rails. | | | Price of Steel Rails. | | | Difference. | | |
|-------|----------------------|----|----|-----------------------|----|----|-------------|----|----|
| | £ | s. | d. | £ | s. | d. | £ | s. | d. |
| 1872 | 9 | 6 | 0 | 13 | 17 | 6 | 4 | 11 | 6 |
| 1873 | 11 | 4 | 4 | 15 | 10 | 0 | 4 | 5 | 8 |
| 1874 | 8 | 9 | 0 | 9 | 17 | 6 | 1 | 8 | 6 |
| 1875 | 6 | 19 | 6 | 8 | 7 | 6 | 1 | 8 | 0 |
| 1876 | 6 | 0 | 10 | 7 | 2 | 6 | 1 | 1 | 6 |
| 1877 | 5 | 15 | 3 | 6 | 7 | 6 | 0 | 12 | 3 |
| 1878 | 5 | 2 | 1 | 5 | 12 | 6 | 0 | 9 | 11 |
| 1879 | 4 | 18 | 3 | 5 | 2 | 6 | 0 | 4 | 3 |
| 1880 | 6 | 3 | 4 | 7 | 7 | 6 | 1 | 4 | 2 |

CHAPTER IV.

CUMBERLAND IRON INDUSTRIES.

Description of Iron Ore Deposits around Whitehaven—Alston Moor—Eakdale and Millom—Analyses, production and distribution of Ore—Population employed in Iron Ore Mining—List of Iron Mines—Pig-Iron Manufacture—Charcoal Furnaces, their Early History—Steelworks—Ironworks—Pig-Iron made—Coal and Ore used in Manufacture—Works in 1880—Malleable-Iron Works and Coal employed.

Iron Ore of the Carboniferous Limestone.—By far the largest proportion of the Cumberland hematite occurs in the Carboniferous or Mountain Limestone. Around Whitehaven, where the carboniferous formation is well developed, it consists in its lowest part of about 250 feet of massive limestone, in immediate contact with that division of the Lower Silurian system known as the Skiddaw Slates. Above this massive limestone are a number of thin beds of limestone, shale, and sandstone or "Whirlstone," making together a series of about 150 feet thick; these beds are followed by a succession of sandstones and shales varying in thickness from 180 to 300 feet. The hematite occurs chiefly on two horizons, one in the lower massive limestone and the other in the thin beds of limestone and shale. Although the ore is often found in large irregular deposits in the limestone, and occasionally in the form of fissures, it is more commonly spread out in the shape of flat deposits, following more or less closely the general dip of the beds, this inclination being usually about 12° or 18° to the west, or filling caverns in the limestone. In thickness the ore deposits vary from 30 feet to 100 feet and upwards; a deposit sometimes suddenly enlarges or diminishes in thickness, thus producing what the miners call "rolls"; the deposits are frequently cut off by faults. In some cases, as in the Cleator Mines, the body of ore is divided into distinct masses by pillars of rock extending from sole to roof. The roof is generally hard, and consequently large excavations are rendered

possible without much artificial support. Although the forms of the deposits are very irregular, it has been remarked that they correspond in their extension with the direction of the magnetic meridian, but this has no relation to the run of the deposits. Some of the deposits of ore occupy a large superficial area; that at Parkside, for example, and the adjoining mines, where the deposit was above 70 feet thick, extending over about 60 acres.

At the mines of the Crossfield Iron Ore Company near Whitehaven, the iron ore is found in the mountain limestone, in faults or dislocations, running north and south, although it is also found lying in irregular masses and preserving a marked parallelism, with a bearing of about 12° N.W.

The distribution of the ore deposits is very irregular, and their existence is only determined by borings, which have to be made almost at random. In the Whitehaven district the ore is distributed over an area extending about eight miles, from south-west to north-east, with an average width of one mile. At Millom the ore-bearing limestone occupies an area of only about one and a half square miles, or between 900 and 1,000 acres.

In addition to the deposits of the mountain limestone, there are veins of hematite in the Lower Silurian rocks of Cumberland; in some cases these occur in the Skiddaw slates, as at Kelton and Knockmurton; in others, in the series of green slates, as at Dunnerdale; and in others again, in the Coniston limestone, as at Waterblean. Nor should mention be omitted of veins of hematite in the granite of Eskdale. For the most part these veins in the older rocks have a general north and south trend, with a dip varying in direction and degree; whilst in thickness the ore, though often but a few inches, may reach as much as 12 or 14 feet. The geological position of the Cumberland hematites has been well described by Mr. P. Wurzburger, of Dalton in Furness, and by Mr. J. D. Kendall, from whose valuable papers the foregoing facts have been gathered.

The iron ore of Cumberland is exclusively of that kind which is known mineralogically as red hematite; it is chemically an anhydrous peroxide of iron (ferric oxide), containing about 70 per cent. of iron, but the ore is, of course, rarely, if ever, found in a state of chemical purity. Most of the Cumberland hematite is of the hard variety known as "blast ore," although in some places, as at Kelton and the adjoining mines, the soft varieties are

found. The hard hematite occasionally occurs in masses presenting a finely lobed surface, whence the name "Kidney ore;" whilst, in rare cases, brilliant lenticular crystals of "specular iron ore" have been found. Associated with the hematite the following minerals occur:—quartz, calcspar, brown spar, heavy spar, peroxide of manganese, and iron pyrites. The red hematites of Whitehaven, in Cumberland, and Ulverstone, in Lancashire, are by far the richest raised in the United Kingdom. The ore, since the introduction of the Bessemer process, has been in great demand, from the high character and purity of the pig iron produced from it, and it is largely exported into other iron-making districts in the kingdom, where it is extensively employed in admixture with other ores, giving an improved quality of iron. Brown hematite has, from time to time, been wrought at Alston Moor and at Nenthead, in the limestone at Kilhope Fell. This limestone bed corresponds with the Fell Top limestone of the district, which, in this locality, becomes ferruginous, probably owing to its being intersected by a considerable number of small veins carrying iron "riders." The brown hematite ore occurring in this limestone varies from 3 to 7 feet thick, and is of good quality. At Nenthead, in the little limestone of the district, a bed of brown hematite occurs, about 7 feet in thickness; the quality of the ore, however, is very variable. Similar ore is met with in the Silly Hole, Manor House, and Nenthead veins of Alston Moor.

In Eskdale, some seven miles from the terminus of the Ravenglass and Eskdale Railway, in the Manor of Birker, at Ore Gap, some lodes of brown hematite are known to occur. The district was examined a few years since by Mr. Robert Woodley, of the Birker Moor Iron Mines, who reports as follows: "That in Yeasty Rigg Gill, out of Green Hole Glen, 1,400 feet above the level of the sea, there are two large and powerful hematite lodes in the Ash rocks and felstone, one on each side of the Gill. On the west slope, the first lode, some 50 feet wide, is visible at the surface, and can be traced by outcrop and excavations for about three-quarters of a mile through Ore Gap to the Keswick side of the mountain. It takes a course a few degrees west of south. The second lode, on the eastern slope of the Gill, is equally large, and bears a little west of north, forming a junction with the first lode in the Gill, whence they pass together

through a wide gap in the Fell, very appropriately called Ore Gap, which is 2,600 feet above the sea level, and situated between Bow Fell and Sea Fell Pikes."

"In this gap the united lodes have thrown up to the surface a curious back of hematite of the finest quality, composed of hard blue, kidney and puddle ore many fathoms in width and at least 300 fathoms in length from the junction of the lodes. A deep trench has been driven across this magnificent deposit, and pits have been opened on either side of it, showing the beds of hard ore embedded with the soft decomposed hematite. As the lodes forming this deposit are traceable in the glen called "Green Holes," at a level 1,200 feet below Ore Gap, the cubic contents of this deposit must be reckoned by millions of tons; for a deposit only 100 fathoms in length by 20 fathoms in breadth would yield 500,000 tons for every 10 fathoms in depth, reckoning only 8 tons of ore to each cubic yard. And the upper part of this deposit can be worked on the most extensive scale by open cutting, and broken and loaded into trucks, and sent by a self-acting incline to the foot of the mountain in Green Holes, at a cost not exceeding 2s. 6d. per ton. About 100 fathoms on the east side of this deposit a great lode of 20 or 30 feet in width, enters the mountain through a great fissure above Angle Tarn, and throws up to the surface another bank of hard blue hematite. This lode, which bears a little east of north, forms a junction with the two first named lodes about the middle of Yeasty Rigg Gill. A fourth lode, coming from the Rest Gill, and bearing south of east, forms a junction with the two largest lodes at the southern end of Yeasty Rigg Gill, where its broad red back is visible, showing every appearance of being rich in iron. This can be worked with the greatest facility by a series of levels driven into the fell just above Green Holes, whence also as many as twenty levels can be driven into the above-mentioned lodes below the surface-workings."

Another interesting feature in Mr. Woodley's report of the Eskdale district, comprises a recommendation for the development of the iron ore deposits by a line of railway through the fell land to connect with the Ravenglass and Eskdale line.

Analyses of the Cumberland Ore.—The hematite of the Whitehaven district, as previously stated, occurs in the carboniferous limestone, near the outcrop or surface of the slaty

rocks upon which that formation rests. The ores raised at Cleator Moor, rich in metallic iron and valuable for the manufacture of steel, are thus described * by Mr. A. Dick:—

“Compact red hematite; easily scratched by a file; lustre, earthy; colour, purplish grey; streak, bright red; fracture, uneven; containing cavities lined with crystals of specular iron, and containing, in some cases, quartz.”

The first analysis consisted of a sample composed of a mixture of the above ore and of another variety, thus described, resembling the former: “It is harder, being scarcely scratched by a file, more lustrous and darker in colour, the cavities contain more quartz, but the substance of the ore seems purer.” The second analysis, given also of hematite from Cleator Moor, is very similar in character, but does not contain quartz visibly diffused through it. The sample examined is also a mixture of varieties, the one compact, the other unctuous, more lustrous, and redder in colour than the compact variety. The constituents of the two samples are as follows:—

RESULTS TABULATED—ORE DRIED ABOVE 100° C.

| Constituents. | No. 1. | No. 2. |
|------------------------------|--------|--------|
| Peroxide of iron | 95·16 | 90·36 |
| Protoxide of manganese . . . | 0·24 | 0·10 |
| Alumina | ... | 0·37 |
| Lime | 0·07 | 0·71 |
| Phosphoric acid | trace | trace |
| Sulphuric acid | trace | trace |
| Bisulphide of iron | trace | 0·06 |
| Magnesia | ... | 0·06 |
| Insoluble residue | 5·68 | 8·54 |
| | 101·15 | 100·20 |

INSOLUBLE RESIDUE.

| | | |
|---|------|-------|
| Silica | 5·66 | 7·05 |
| Alumina (containing a trace of iron) | 0·06 | 1·06 |
| Peroxide of iron | ... | 0·19 |
| Lime | ... | trace |
| | 6·72 | 8·30 |

The metallic iron contained in these ores were equivalent to 66·60 and 63·25 per cent. respectively; it being further remarked

* “Iron Ores of Great Britain,” Part I, pp. 60, 62. (Out of print.)

that a trace of lead was detected in 400 grains of the first sample of ore and in 500 grains of the second.

The hematite of Eskdale has been examined by Mr. Watson, of Braystones, who gives analysis of a sample from Ore Gap, as follows :—

RESULTS TABULATED.

| | |
|------------------------------|--------|
| Peroxide of iron | 94·00 |
| Oxide of manganese | 1·20 |
| Silica | 4·00 |
| Magnesia | trace |
| Moisture | 0·80 |
| | <hr/> |
| | 100·00 |

Production of Iron Ore.—In the year 1849 there appears to have been in the Whitehaven district thirteen mines, producing hematite amounting to 100,000 tons: the details are as follows * :—

| Firm. | Number of Mines. | Quantities. |
|---------------------------------|------------------|-------------|
| | | Tons. |
| Messrs. Ainsworth & Co. | 2 | 30,000 |
| Messrs. Hill & Co. | 4 | 20,000 |
| Mr. John Lindow | 3 | 20,000 |
| Messrs. Tulk & Ley | 2 | 15,000 |
| Messrs. Atwood & Co. | 2 | 15,000 |
| Total | 13 | 100,000 |

The total quantity of iron ore produced from the mines of the United Kingdom in the same year was but 500,000 tons, contributed as follows from the several hematite producing districts :—

| District. | Number of Mines. | Quantities. |
|-------------------------------|------------------|-------------|
| | | Tons. |
| Lancashire | 17 | 182,000 |
| Cumberland | 13 | 100,000 |
| Forest of Dean | 8 | 95,000 |
| Cornwall, Somerset, and Devon | 17 | 118,000 |
| Isle of Man | 2 | 2,500 |
| Ireland | 1 | 1,500 |
| Scotland | 2 | 1,000 |
| Total | 60 | 500,000 |

* "Braithwaite Poole, Report to the Directors of the Lancaster and Carlisle Railway on Iron Ore." 1850.

The estimated value of this ore set down at the works of the consumer was not less than 20s. per ton.

In subsequent years the returns show a large increase, amounting in 1855 to 200,788 tons; increasing in 1856 to 259,167 tons, and in 1857 to 323,812 tons; the distribution of which was as follows in 1856 and 1857 :—

| Destination. | 1856. | 1857. |
|-------------------------|---------|---------|
| | Tons. | Tons. |
| South Wales | 124,630 | 163,354 |
| Staffordshire | 26,768 | 36,758 |
| Scotland | 15,865 | 22,377 |
| Newcastle, &c. | 51,470 | 44,489 |
| France | 817 | 323 |
| Ironworks | 39,617 | 56,511 |
| Total | 259,167 | 323,812 |

The only ironworks in operation in Cumberland in the year 1857 were those of Seaton, Harrington and Cleator Moor, in which hematite ore alone was employed. The annexed summary gives the output of the mines of Whitehaven and the value of the ore in each year since 1858 :—

| Year. | Quantities. | Value. |
|-------|-------------|-----------|
| | Tons. | £ |
| 1858 | 331,544 | 182,349 |
| 1859 | 400,306 | 220,168 |
| 1860 | 466,851 | 256,768 |
| 1861 | 472,095 | 259,650 |
| 1862 | 533,120 | 306,544 |
| 1863 | 690,083 | 414,083 |
| 1864 | 784,174 | 489,008 |
| 1865 | 678,831 | 441,240 |
| 1866 | 706,505 | 459,228 |
| 1867 | 709,037 | 478,600 |
| 1868 | 725,248 | 489,542 |
| 1869 | 848,974 | 594,281 |
| 1870 | 1,014,143 | 760,606 |
| 1871 | 976,874 | 1,074,561 |
| 1872 | 954,505 | 1,193,121 |
| 1873 | 1,021,690 | 1,277,115 |
| 1874 | 901,667 | 1,115,685 |
| 1875 | 935,360 | 701,520 |
| 1876 | 1,082,812 | 806,278 |
| 1877 | 1,081,256 | 762,656 |
| 1878 | 1,082,924 | 713,885 |
| 1879 | 933,369 | 513,586 |
| 1880 | 1,148,246 | 914,377 |

The condition and importance of the iron ore industries of Cumberland appear in the relative prices of the ore from time to time. Glancing generally at the above quantities and values in 1858, the figures give an average price of 11*s.* per ton; this average is fairly maintained for a few years. With the prosperity of the iron industries in the year 1870, the values of these ores show a great increase, the average price showing 15*s.* per ton. In succeeding years this is exceeded; thus, in the year 1873, one of great commercial prosperity, these ores realised 25*s.* per ton, receding to 24*s.* 9*d.* in the following year, and to 15*s.* per ton in the year 1875, since which date the same average prices have ruled with little variation until 1880, when an increased value appears.

In the year 1880 the following mines were producing ore, in the quantities and values given, to which is appended the distribution by railway and ship in the same year:—

| Name of Mine. | Quantities. | | Value. | | | |
|---|-------------|-------|---------|----|----|--|
| | Tons. | Cwts. | £ | s. | d. | |
| Bigrigg (Leconfield) Wyndham Pit | 14,179 | 0 | 10,698 | 0 | 0 | |
| " Lady Pit . . . | 27,846 | 0 | 21,000 | 0 | 0 | |
| Birks (Frizington) | 6,192 | 15 | 4,334 | 8 | 0 | |
| Cleator Moor (Leconfield) York Pit | 28,287 | 0 | 19,700 | 18 | 0 | |
| " " James Pit | 1,514 | 0 | 1,060 | 0 | 0 | |
| Cleator (5 Pits) " . . . | 40,286 | 0 | 32,680 | 10 | 0 | |
| Crossfield (8 Pits) " . . . | 98,000 | 0 | 78,400 | 0 | 0 | |
| Crossgill (Maryport H. Iron Co.) | 16,237 | 0 | 12,207 | 10 | 0 | |
| Dyke Nook | 731 | 0 | 456 | 17 | 0 | |
| Egremont | 12,738 | 0 | 11,782 | 0 | 0 | |
| Ehen (Egremont) | 19,850 | 0 | 17,372 | 10 | 0 | |
| Eakett and Salter | 47,567 | 0 | 37,053 | 6 | 0 | |
| Eakett (Eakett Iron Ore Co.) . . . | 45,000 | 0 | 38,250 | 0 | 0 | |
| Eakett (Postlethwaite) | 40,192 | 0 | 32,153 | 0 | 0 | |
| Goose Green (Frizington) | 12,436 | 0 | 10,948 | 0 | 0 | |
| Gillfoot Park (Egremont) | 72,880 | 5 | 58,304 | 0 | 0 | |
| Gutterley (Maryport Hematite } Iron Co.) | 6,850 | 0 | 5,479 | 10 | 0 | |
| High House (Frizington) | 64,978 | 0 | 45,484 | 12 | 0 | |
| Hodbarrow | 343,194 | 0 | 240,236 | 0 | 0 | |
| Holebeck and Rattenrow | 5,957 | 0 | 3,872 | 1 | 0 | |
| Jacktrees No. 3 Pit (Carron Co.) . . | 3,133 | 0 | 2,349 | 15 | 0 | |
| " No. 2 Pit (Carron Co.) . . | 21,534 | 0 | 16,160 | 0 | 0 | |
| Kelton and Knockmurton | 47,705 | 18 | 47,705 | 0 | 0 | |
| Lonsdale Nos. 2 & 3 (S. & J. Lindow) | 6,175 | 0 | 4,631 | 5 | 0 | |
| Longlands (S. & J. Lindow) | 15,616 | 0 | 11,712 | 0 | 0 | |
| Montreal | 210,894 | 0 | 158,170 | 10 | 0 | |
| Murton | 950 | 0 | 712 | 0 | 0 | |
| Carried forward | 1,210,922 | 18 | 922,903 | 12 | 0 | |

| Name of Mine. | Quantities. | | Value. | | |
|--|-------------|-------|-----------|----|----|
| | Tons. | Cwts. | £ | s. | d. |
| Brought forward . . . | 1,210,922 | 18 | 922,903 | 12 | 0 |
| Mowbray . . . | 35,660 | 0 | 26,745 | 0 | 0 |
| Moor Row (Moor Row Mining Co.) . . . | 16,638 | 0 | 17,955 | 0 | 0 |
| (Maryport H. Iron Co.) . . . | 24,137 | 0 | 24,137 | 0 | 0 |
| Nabb Gill . . . | 7,812 | 0 | 5,275 | 0 | 0 |
| Park Side (Frizington). . . | 11,303 | 0 | 8,477 | 5 | 0 |
| Park (Bain & Co.) . . . | 3,283 | 0 | 2,463 | 0 | 0 |
| Salter Hall . . . | 38,100 | 0 | 30,480 | 0 | 0 |
| Sir John and Bigrigg (S. & J. Lindow). . . | 13,798 | 0 | 10,937 | 10 | 0 |
| Scalelands . . . | 1,500 | 0 | 1,200 | 0 | 0 |
| Winder (Frizington) . . . | 33,000 | 0 | 29,700 | 0 | 0 |
| Winder Gill . . . | 3,886 | 0 | 3,108 | 0 | 0 |
| Woodend (Bain & Co.) . . . | 45,902 | 0 | 34,426 | 0 | 0 |
| Whicham (Silcroft) . . . | 26,830 | 0 | 22,805 | 0 | 0 |
| Wyndham (Egremont) . . . | 18,669 | 0 | 14,001 | 5 | 0 |
| Total of Cumberland . . . | 1,491,440 | 18 | 1,154,613 | 12 | 0 |

CUMBERLAND ORE CARRIED BY THE FURNESS RAILWAYS.

| | TONS. | TONS. |
|---|---------|-----------|
| For shipment at Barrow-in-Furness . . . | 5,665 | |
| ,, Whitehaven . . . | 52,504 | |
| | | 58,169 |
| By rail sent away to Durham, &c. . . | 66,722 | |
| ,, to furnaces in district . . . | 911,297 | |
| | | 978,019 |
| Total of Cumberland ore carried . . . | | 1,036,188 |

CUMBERLAND ORE SHIPPED FROM WHITEHAVEN.

| TO | TONS. |
|--------------------------------|--------|
| Cardiff . . . | 8,859 |
| Newport . . . | 21,102 |
| Ditton Brook . . . | 790 |
| Runcorn . . . | 145 |
| Garston . . . | 2,256 |
| Liverpool . . . | 338 |
| Bowling . . . | 250 |
| Glasgow . . . | 272 |
| Swansea . . . | 193 |
| Total shipments . . . | 34,205 |
| Shipped from other ports . . . | 52,692 |

Iron Ore Deposits at Millom.—Resembling the flat deposits of the Whitehaven district is the large deposit of Hodbarrow Mines near Millom. Overlaid for the greatest part by limestone, it is from east to west about 470 yards long by 170 to 240 yards in width, the thickness of the ore being in the eastern part from 72 to 90 feet. The dip of the deposit is at an angle of 12° to the west. At some distance to the north-west a second deposit is being

explored which is probably connected with the first one, and is, perhaps, of still greater dimensions. The second deposit is overlaid by loose masses of drift. Since the year 1864 the Hodbarrow Mines at Millom have yielded hematite in the following quantities and values :—

| Year. | Quantities. | Value. |
|-------|-------------|---------|
| | Tons. | £ |
| 1864 | 78,993 | 39,496 |
| 1865 | 117,330 | 70,397 |
| 1866 | 131,542 | 78,925 |
| 1867 | 181,504 | 90,752 |
| 1868 | 201,380 | 120,828 |
| 1869 | 198,705 | 139,093 |
| 1870 | 174,943 | 122,460 |
| 1871 | 207,146 | 227,860 |
| 1872 | 211,771 | 264,713 |
| 1873 | 203,791 | 254,739 |
| 1874 | 201,663 | 252,078 |
| 1875 | 202,817 | 152,112 |
| 1876 | 271,098 | 189,768 |
| 1877 | 270,195 | 202,645 |
| 1878 | 274,962 | 185,599 |
| 1879 | 293,637 | 161,500 |
| 1880 | 343,194 | 240,236 |

Cumberland in the year 1878 stood as the second most important iron ore producing district in the kingdom, Cleveland being the first, with a production of 5,605,640 tons of argillaceous carbonate of iron, of the value of £910,789, or an average varying from 9s. to 9s. 6d. per ton of stone at the mines.

In the following summary the total ore produced in Cumberland appears, showing the yield of each district since 1869 :—

CUMBERLAND IRON ORE.

| Year. | Whitehaven District. | Hodbarrow District. | Alston Moor and other Mines. | Total. |
|-------|----------------------|---------------------|------------------------------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| 1869 | 848,974 | 198,705 | 140 | 1,047,819 |
| 1870 | 1,014,143 | 174,943 | 32,217 | 1,221,303 |
| 1871 | 976,874 | 207,146 | 118,683 | 1,302,703 |
| 1872 | 954,505 | 211,771 | 2,000 | 1,168,276 |
| 1873 | 1,021,690 | 203,791 | 4,345 | 1,229,826 |
| 1874 | 901,667 | 201,663 | 16,332 | 1,119,662 |
| 1875 | 935,360 | 202,817 | 9,791 | 1,147,968 |
| 1876 | 1,082,812 | 271,098 | ... | 1,353,910 |
| 1877 | 1,081,246 | 270,195 | ... | 1,351,441 |
| 1878 | 1,082,924 | 274,963 | ... | 1,357,887 |
| 1879 | 933,369 | 293,637 | ... | 1,227,006 |
| 1880 | 1,148,248 | 343,194 | ... | 1,491,440 |

The hematitic ores of Cumberland have from an early period been extensively raised for shipment to the ironworks of Yorkshire, Staffordshire, and North and South Wales. In quality these ores may be considered as the best in the kingdom, and the supplies which these districts are calculated to produce are very great. The large per centage of metallic iron which they contain, from 60 to 65 per cent. and even more, and their superior quality, enables them to bear the cost of transport to distant places, where the ore is in great request.

The returns of individual mines were not obtainable until the year 1872, since which date the details have been regularly published.* The detail of distribution of the (Whitehaven) Cumberland ore for a few years will show generally its destination:—

| Destination. | 1868. | 1870. | 1872. | 1874. |
|---------------------------------|---------|-----------|---------|----------|
| | Tons. | Tons. | Tons. | Tons. |
| South Wales, by ship . | 162,811 | 195,639 | 107,554 | 113,191† |
| Staffordshire | | | | |
| Lancashire } by ship | 26,287 | 18,401 | 561 | ... |
| North Wales | | | | |
| Lancashire | 4,108 | 84,367 | 113,901 | 101,321 |
| Carnforth and Millom { | | | | |
| Scotland, by rail . . . | 107,580 | 107,457 | 68,489 | 69,402 |
| „ by ship | 31,358 | 36,993 | 6,532 | ... |
| Newcastle and | | | | |
| Middlesborough } by rail | 141,054 | 155,433 | 85,139 | 63,385 |
| districts | | | | |
| Workington, Maryport, | | | | |
| Harrington, and } . | 252,050 | 414,522 | 572,329 | 554,368 |
| Cleator districts | | | | |
| Total of Whitehaven ore . . . } | 725,248 | 1,014,143 | 954,505 | 901,667 |

In subsequent years the distribution of the ore of Whitehaven is obtained from returns furnished by the Whitehaven, Cleator and Egremont Railway Company. This company was amalgamated in 1877 with the London and North-Western Railway, and in June, 1878, became the joint property of it and the Furness Company, from which date it has been worked jointly. The details of distribution in each year appear as follows since 1876:—

* For which see "Mineral Statistics of the United Kingdom," by Robert Hunt, F.R.S.

† This quantity includes all shipments in 1874.

‡ Including 1,311 tons sent to France.

| How Distributed. | 1876. | 1877. | 1878. | 1879. | 1880. |
|---------------------------------|-----------|-----------|-----------|---------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| Whitehaven shipments | 167,529 | 143,061 | 88,961 | 71,864 | 52,692 |
| " Lonsdale Iron Co. | 88,392 | 103,758 | 95,468 | 102,003 | 131,977 |
| Cleator Moor | 46,135 | 37,987 | 50,192 | 61,093 | 70,674 |
| Distington | .. | .. | .. | 4,790 | 43,020 |
| Parton | 25,377 | 3,769 | .. | 2,970 | 28,557 |
| Harrington | 56,858 | 80,162 | 80,036 | 73,594 | 109,623 |
| Workington | 268,520 | 249,299 | 271,671 | 269,153 | 415,320 |
| Maryport | 169,732 | 252,799 | 249,746 | 237,219 | 229,616 |
| Scotland | 146,723 | 121,013 | 49,859 | 19,746 | 44,548 |
| Carnforth and Furness | 73,191 | 127,187 | 1,466 | 583 | 4,185 |
| Barrow and Millom | .. | .. | 102,845 | 22,723 | 74,033 |
| South of Carnforth | 24,674 | 35,072 | 22,263 | 30,653 | 19,713 |
| East Coast, <i>via</i> Carlisle | 48,936 | 62,709 | 226 | 20 | .. |
| " <i>via</i> Penrith | .. | .. | 39,268 | 4,628 | 10,431 |
| Total | 1,117,067 | 1,216,816 | 1,052,001 | 901,339 | 1,234,389 |

In the year 1878 the Hodbarrow ore was distributed as follows :
 Shipped at the Company's private harbour, 121,914 tons ; to
 Millom Ironworks, 61,539 tons ; carried by Furness Railway,
 87,069 tons ; the remaining 4,440 tons being disposed of
 locally.

The following presents a complete list of the iron mines of
 Cumberland, their situation, and the names of the proprietors
 working the same in the year 1881 :—

CUMBERLAND IRON MINES.

| Name of Mine. | Situation. | Name of Proprietor or Company. |
|--------------------|---|---|
| Birks, 3 Pits | Whitehaven | Joseph Fearon |
| Bigrigg | { Egremont, Friz- ington, and Cleator } | S. and J. Lindow |
| Gutterly | | |
| Lonsdale | | |
| Longlands | | |
| Bigrigg | | |
| Wyndham Pit | | |
| Lady Pit | Whitehaven | Lord Leonfield |
| Cleator Moor | | |
| York Pit | | |
| Crowgarth | | |
| Cleator, 4 Pits | " | Cleator Iron Ore Co. |
| Crossfield, 8 Pits | " | Crossfield Iron Ore Co. |
| Montreal | " | John Stirling |
| Dyke Nook | Frizington | Dyke Nook Mining Co. |
| High House, 4 Pits | St. Bees, Carnforth | Fletcher & Hodgetts |
| Crossgill | Frizington | Samuel Wagstaff Smith |
| Egremont | Whitehaven | Egremont Iron Ore Co. |
| Ehen | Egremont | Ehen Mining Co. |
| Eskdale | Ravenglass | { Whitehaven Iron Mines Co., Limited |

CUMBERLAND IRON MINES—*continued.*

| Name of Mine. | Situation. | Name of Proprietor or Company. |
|----------------------------------|---------------------------------|--|
| Eskett, 3 Pits . . . | Whitehaven . . . | Eskett Iron Ore Co. |
| Salter and Eskett, 3 } Pits } | " . . . | { Salter and Eskett Park Mining Co. |
| Eskett, Postlethwaite . | " . . . | J. Postlethwaite, junr. |
| Frizington Parks, 2 Pits | Frizington . . . | James Bain & Co. |
| Goose Green . . . | " . . . | " " |
| Woodend . . . | Egremont . . . | " " |
| Hodbarrow, 7 Pits . . | Holborn Hill . . . | { The "Hodbarrow Mining Co. |
| Holebeck and Ratten- } row } | " . . . | { The Dalmellington Iron Co. |
| Kelton . . . | Lamplugh . . . | W. David & Co. |
| Millom . . . | Millom . . . | George J. Eveson |
| Winder . . . | Frizington . . . | Winder Iron Ore Co. |
| Mowbray, 1 Pit . . . | " . . . | { Mowbray Iron Ore Co., Limited |
| Moor Row . . . | { Moor Row, White- } haven } | Moor Row Mining Co. |
| Nabb Gill . . . | Eekdale . . . | { Whitehaven Iron Mining Co. |
| New Parkside . . . | Whitehaven . . . | { New Parkside Iron Mining Co., Limited |
| Parkside, 7 Pits . . . | " . . . | { The Parkside Iron Mining Co. |
| Salter Hall . . . | Cleator Moor . . . | Thos. Dixon & Co. |
| Steel End . . . | " . . . | Steel End Mining Co. |
| Waterblean, 1 Pit . . | Green Roads, Millom | G. J. Eveson |
| Winder . . . | Millom . . . | — |
| Winderhill . . . | Winder . . . | { Maryport Hematite Iron Co. |
| Wyndham . . . | Egremont . . . | { Wyndham Mining Co., Limited |
| Yeathouse . . . | Whitehaven . . . | Yeathouse Mining Co. |

Population employed in Iron Mines in Cumberland.—The coal-field of Cumberland is barren of those argillaceous ores of iron which are found so abundantly in Staffordshire and other coal-fields, a very thin band only being found near the Parkside Mine. On the other hand, their absence is more than compensated for by the red hematite deposits of iron ore in the carboniferous limestone. As recently as the year 1854, the number of persons employed in Cumberland in iron mining did not exceed 369. In later returns, and until the "Metalliferous Mines Regulation Act, 1872," came into operation, those employed in coal and iron mines were not separately distinguished. Since the year

1873 reliable returns are available,* showing the numbers employed under and above ground, also the output of the mines, and the average produce of ore per man; the details are as follows:—

| Year. | PERSONS EMPLOYED. | | Total Employed. | Hematite Ore Raised. | Average per Man. |
|-------|-------------------|---------------|-----------------|----------------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 3,438 | 1,004 | 4,442 | 917,452 | 206 |
| 1874 | 4,108 | 1,179 | 5,287 | 1,204,802 | 227 |
| 1875 | 4,217 | 1,345 | 5,562 | 1,130,201 | 205 |
| 1876 | 4,620 | 1,803 | 6,423 | 1,377,412 | 215 |
| 1877 | 4,826 | 1,551 | 6,377 | 1,478,338 | 232 |
| 1878 | 4,502 | 1,467 | 5,969 | 1,322,028 | 221 |
| 1879 | 4,088 | 1,393 | 5,481 | 1,223,338 | 223 |
| 1880 | 4,880 | 1,620 | 6,500 | 1,525,064 | 234 |

Pig Iron Manufacture.—The earliest facts bearing on this industry in Cumberland appears in Hutchinson's† history of that county, in which it is stated that "between Workington and Seaton, on the banks of the Derwent, are considerable iron-works, planned and built under the direction of that eminent engineer, the late Thomas Spalding, of Whitehaven, in the year 1763. They have two blast furnaces for the smelting of iron ore, a mill for slitting and rolling of bar iron, a double forge for refining and drawing of bar iron, a foundry, with several small furnaces, wherein they make cannon and cast-iron works of all sorts, a boring mill for boring cannon, cylinders, &c., a grinding house and turning house and many other conveniences for carrying on a very extensive iron manufactory. These works are carried on under the firm of Spedding, Hicks and Company." In the year 1796, two years after the publication of the volume from which the above is extracted, a return to Parliament, on the authority of Dr. M'Nab, shows that at that time there were two blast furnaces in operation, named Bearpot and Duddon, the latter, no doubt, being in the occupation of the ancestors of the present proprietors, Messrs. Harrison, Ainslie & Co.

The early history of the iron industries of Millom present some interesting features. The Huddlestons, of Millom Castle, had one or more charcoal blast furnaces near a stream still known

* Reports of H.M. Inspectors of Mines.

† "History and Antiquities of Cumberland." Hutchinson, Carlisle, 1794.

as Furnace Beck, and about a mile north-east from the castle, where, when the site had been ploughed, slag and pieces of iron were found. At Duddon Bridge a charcoal furnace is standing which is used from time to time as charcoal can be obtained, as are also those at Newland and Backbarrow, both in Furness. A fourth exists at Warsash in Hampshire, near Southampton, and a fifth at Lorn in Argyleshire. The Backbarrow furnace was in operation in the year 1745, also the Duddon, both furnaces being marked on Speed's Map of Cumberland, and they had probably been at work for years previously. These furnaces belonged to the family of Lathom, of Broughton in Furness, from whom they passed early in the present century to the old established firm of Harrison, Ainslie & Co., by whom they are still owned. Mr. Thomas Massicks, who has gleaned many important facts connected with the district, possesses, it is said, a pig of the iron made in Millom, and branded A.D. 1788, which was found doing duty as a lintel in a cottage at Hodbarrow. These are the only charcoal furnaces traced in the Millom district; and Mr. Massicks is of opinion that no part of the vast deposits of Hodbarrow were touched till about fifty years ago, when a small quantity was worked near the shore, and that the Huddlestons were partly supplied from a small vein in limestone close by, the remainder being brought from Furness.

The production of charcoal pig iron at the works of Bearpot and Duddon in 1796 was 2,080 tons and 1,664 tons, or a total of 3,744 tons. These charcoal furnaces, except the Bearpot, are still in existence, and in the year 1855 produced 16,574 tons of charcoal pig from hematite ore. The demand for this quality of iron at the period was considerable, it being extensively used in Birmingham for saddlers' ironmongery, where it was smelted in crucibles and run into small moulds; these castings were subsequently decarbonised by being placed in layers, with powdered hematite ore, in cylindrical pans, and exposed to a sufficient heat in suitable ovens, until all became malleable. The iron thus made has a wide reputation, and is only inferior to the best charcoal iron of Sweden, Russia and Norway. Blooms and bars were made at the Backbarrow works in Lancashire in 1855; the manufacture was, however, discontinued, through the failure of wood for making the charcoal.

In the year 1851 the production of pig iron in Cumberland was very limited, being confined to the Cleator Iron Company, near Whitehaven, who had three furnaces in operation, and the small charcoal furnaces already referred to. The make of pig iron in 1854 did not exceed 20,000 tons; about the year 1857 the works at Harrington of Mr. C. H. Plevins and those at Seaton of the Messrs. Smith and Co., were put in blast; in the following year the works of the Workington Iron Company commenced the make of hematite pig, with two furnaces. And in the year 1863 the West Cumberland Iron and Steel Company blew in three furnaces. Again, in the year 1870, the Maryport, Millom and Solway Companies commenced operations. At this period there were 33 furnaces built, of which 24 were in blast, making 255,178 tons of pig iron. Other works followed, at Moss Bay and Workington, in 1872, while the works of Parton commenced active operations in the year 1874. The Journal of the Iron and Steel Institute gives ample details in its pages, not only of the Cumberland ironworks, but of others throughout the kingdom; those of the west coast springing up in recent years so rapidly have a special interest, and the following account will show generally their extent and appliances. "In the works of the West Cumberland Hematite Iron and Steel Company, the largest and, in many respects, the most modern establishment in the Workington district, there are here six blast furnaces, each 55 feet in height, and varying from 18 to 21 feet in the diameter of the boshes, or widest part. The furnaces are blown by a pair of beam engines, having a blowing cylinder of 8 feet in diameter, and a steam cylinder of 3 feet 8 inches in diameter; the stroke of the piston being 8 feet 6 inches, and the engine working at the rate of 20 revolutions per minute. The oldest furnaces of the company were erected about the year 1860, in which year the blast engines were also erected. The blast furnaces are all fitted with the bell mouth and hopper apparatus, patented by Head, Wrightson & Co., for the utilization of the waste gases, which are conducted to the heaters and boilers in the usual way. The hoists used for the elevation to the top of the furnaces of the raw materials are also on a principle patented by Mr. Wrightson of the above-named firm, and well known both in the Cleveland district, where it has been extensively adopted, also in Wales, Staffordshire, and, more recently, in Scotland.

“ Within a few miles of their furnaces the West Cumberland Company are working a coal royalty, which produces a quality of coal suitable for the manufacture of coke. This coal is brought to the blast furnaces in its raw state, and on either side of the yard separating the blast furnaces from the steel works of the company there are a large number of coke ovens at work. The coke is said to be of good quality, although it must come far short of the South Durham coke, seeing that the latter is always preferred for any special brand, and that there are other firms in the district that use no other. The production of the West Cumberland blast furnaces averages from 200 to 250 tons per week each. The general character of their arrangements is very much similar, apart from height and capacity, to those built in the Cleveland district. The company possess manifest advantages in the near proximity to the sea, which is within one hundred yards of the furnaces, and furnishes an illimitable tip for the slag, a boon which many ironmasters, occupying a more insular situation, and therefore, at a great loss in disposing of their waste vitreous produce, would highly appreciate.

“ The steel works of the West Cumberland Company are separated by a distance of some three hundred yards from the blast furnaces, part of the intervening space being occupied with a small forge and workshop. With the exception of the works of the Barrow Company, these are undoubtedly the finest steel works on the west coast. Here there are found Bessemer convertors in operation, two having a capacity of 8 tons, and other two of 6 tons each. The operation of casting the ingots of steel is performed here in the ordinary way. In the subsequent processes, however, the rails are drawn out in lengths of 48 feet, and then in their red-hot state they are brought to a guillotine and cut into lengths of 21 feet each; so that for every two rails there are only two crop ends. In some cases it is found possible to draw out lengths of from 60 to 64 feet, thus allowing only two crop ends for three rails; but in general practice it is found better to keep to the shorter and more wieldy length of 48 feet.

“ The Moss Bay Company's iron and steel works, situated near Workington, may be referred to as possessing all the modern improvements, and it was at these works that the appliances now nearly universally employed for utilizing the waste gases were first introduced into this district. A forge is attached to these

works, where a puddling furnace on a new principle is employed, patented by Mr. Kirk, the manager. These new furnaces work with a consumption of not more than $15\frac{1}{2}$ cwt. of coal to the ton of puddled bar."

In the table below appears the number of furnaces built and in blast, with the make of pig iron in each year since 1857 :—

| Year. | FURNACES. | | Pig Iron Made. | Average per Furnace. |
|-------|-----------|-----------------|----------------|----------------------|
| | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Tons. |
| 1857 | 8 | 6 | 30,515 | 5,083 |
| 1858 | 8 | 5 | 26,264 | 5,253 |
| 1859 | 12 | 7 | 50,097 | 7,157 |
| 1860 | 12 | 8 | 87,950 | 10,993 |
| 1861 | 12 | 8 | 55,165 | 6,895 |
| 1862 | 12 | 7 | 103,455 | 14,779 |
| 1863 | 14 | 10 | 106,090 | 10,609 |
| 1864 | 15 | 11 | 141,033 | 12,821 |
| 1865 | 15 | 9 | 107,430 | 11,935 |
| 1866 | 17 | 12 | 136,343 | 11,362 |
| 1867 | 17 | $8\frac{3}{4}$ | 109,839 | 12,553 |
| 1868 | 17 | 8 | 116,864 | 14,608 |
| 1869 | 17 | 9 | 129,107 | 13,234 |
| 1870 | 27 | 24 | 255,178 | 10,632 |
| 1871 | 34 | $28\frac{3}{4}$ | 336,569 | 11,707 |
| 1872 | 37 | $33\frac{1}{4}$ | 440,575 | 13,250 |

The variation in the average yield of the furnaces, it should be stated, is due to the circumstance of some of the furnaces being in blast but a part of the year. In considering the quantity of coal used in the manufacture of pig iron, the average amount used about the year 1869 was 60 cwt., subsequently it was determined by inquiries specially made, that in the year 1873 the average did not exceed 51 cwt. in Great Britain; while in this district, where the Durham coke is extensively employed, the average did not exceed 47 cwt., all purposes included; and in all cases where coke was returned its equivalent in coal has been taken.

Coal and Iron Ore used in Manufacture.—In the year 1872 inquiries were first instituted with a view of ascertaining the quantities of fuel and ore used in the manufacture of pig iron. The results appear in the annexed table giving the number of furnaces built and in blast in Cumberland, the make of pig iron, and the coal and iron ore employed :—

| Year. | FURNACES. | | Pig Iron Made. | Coal Used. | Ore Used. |
|-------|-----------|-----------|----------------|------------|-----------|
| | Built. | In Blast. | | | |
| | Nos. | Nos. | Tons. | Tons. | Tons. |
| 1872 | 37 | 33½ | 440,575 | 1,077,783 | 850,500 |
| 1873 | 39 | 33½ | 456,877 | 1,079,118 | 865,172 |
| 1874 | 51 | 30½ | 390,840 | 1,010,125 | 738,490 |
| 1875 | 51 | 31½ | 486,112 | 1,089,000 | 846,000 |
| 1876 | 47 | 25 | 436,887 | 936,929 | 783,456 |
| 1877 | 50 | 26½ | 538,156 | 1,027,869 | 956,834 |
| 1878 | 51 | 27 | 542,904 | 1,019,957 | 976,059 |
| 1879 | 51 | 27½ | 531,638 | 1,005,497 | 930,247 |
| 1880 | 51 | 40 | 790,343 | 1,604,097 | 1,475,280 |

In the year 1872 the coal used in pig iron manufacture, all purposes included, was 49 cwts. to each ton of pig iron made, compared with 47½ cwts. in the following year; successive years show improved economy. Taking the years 1879 and 1880 the average varies between 38 and 40 cwts.

The works and furnaces in operation in Cumberland during the year 1880 were as follows; producing, as stated, 790,343 tons of pig iron suitable for the manufacture of steel:—

CUMBERLAND.

| No. | Name of Works. | Owners. | FURNACES. | |
|-------------------------------|---|---|-----------|-----------|
| | | | Built. | In Blast. |
| | | | Nos. | Nos. |
| 1 | Derwent | Derwent Hæmatite Iron Co., Lim. | 3 | 3* |
| 2 | Duddon | Harrison, Ainslie, & Co. | 1 | 0 |
| 3 | { Harrington Hæmatite, } Whitehaven | James Bain & Co. | 4 | 3 |
| 4 | Lonsdale, Whitehaven | Lonsdale Hæmatite Iron & Steel Co. | 4 | 4† |
| 5 | Lowther, Workington | Lowther Hæmatite Iron Co., Lim. | 3 | 2 |
| 6 | Maryport | Maryport Hæmatite Iron Co. | 6 | 6 |
| 7 | Millom | { Cumberland Iron Mining & } Smelting Co., Limited | 6 | 5 |
| 8 | Moss Bay, Workington | { Moss Bay Hæmatite Iron & } Steel Co. | 4 | 3 |
| 9 | Parton, Whitehaven | Parton Hæmatite Iron Co., Lim. | 2 | 1‡ |
| 10 | Solway Hæmatite, Maryport | Solway Hæmatite Iron Co., Lim. | 4 | 2§ |
| 11 | { West Cumberland Iron and } Steel, Workington | West Cumberland Iron & Steel } Co., Limited | 6 | 5* |
| 12 | { Whitehaven Hæmatite, Cleator } Moor | Whitehaven Hæmatite Iron Co., } Limited | 4 | 3 |
| 13 | Workington | Workington Iron Co., Limited | 4 | 3 |
| Total of Cumberland | | | 51 | 40 |

* One furnace for six months.

† One furnace for seven and a half months.

‡ Another furnace for six weeks.

§ A third furnace for three months.

|| One furnace a part of the year only.

As to the ore employed, all varieties included give an average in 1872 and 1873 of about 38 cwts., compared with 36 cwts. in recent years. The great bulk of the ore reduced in the Cumberland furnaces is the produce of the district, the other ores imported and used in admixture were derived from the following sources in each year since 1875:—

| | 1875. | 1876. | 1877. | 1878. | 1879. | 1880. |
|----------------|---------|---------|---------|---------|---------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| Hæmatite . . | 809,703 | 740,710 | 906,991 | 914,475 | 890,456 | 1,360,410 |
| Foreign . . | 15,178 | 23,500 | 28,776 | 29,000 | 16,308 | 79,424 |
| Irish . . | 21,119 | 14,029 | 17,487 | 18,633 | 15,791 | 28,206 |
| Other ores . . | .. | 5,217 | 3,580 | 13,951 | 7,692 | 17,240 |
| Totals . | 846,000 | 783,456 | 956,834 | 976,059 | 930,247 | 1,475,280 |

The Irish aluminous ore is used with considerable advantage as a flux in the smelting of the hæmatite, as it contains from 20 to 35 per cent. of alumina, and from 35 to 40 per cent. of metallic iron; there was also employed a small amount of forge and mill cinder, containing from 40 to 70 per cent. of metallic iron.

Malleable Iron and Steel Works.—In the year 1872 there were five works engaged in the manufacture of malleable iron, employing 83 puddling furnaces and 11 rolling mills, to which should be added the Bessemer Works of the West Cumberland and the Moss Bay Iron and Steel Companies, situated near Workington. The coal used in the above works in the years 1872 and 1873 amounted to from 100,000 to 110,000 tons, whereas the total quantity of coal employed in the malleable iron works of Cumberland in 1880 and two preceding years has not exceeded 35,000 tons per annum. The following is a list of the works, with the number of puddling furnaces and rolling mills in operation in the year 1880:—

| Name of Works. | Name of Firm. | Puddling Furnaces. | Rolling Mills. |
|-----------------------|--|-----------------------|-------------------|
| | | Nos. | Nos. |
| West Cumberland . . | { West Cumberland Iron & } Steel Co., Limited . . } | 0 | 3 |
| Derwent Rolling Mills | Moss Bay H. Iron & Steel Co. | 13 | 2 |
| New Yard | Kirk Brothers & Co. . . | 7 | 1 |
| Marsh Side . . . | " " | 8 | 1 |
| Ellen Rolling Mills . | Penton, Hampton, & Jackson | *13 | 2 |
| | Total | 41 | 9 |

* Works standing.

The four first named works are situated near Workington, and the last near Maryport, which has been standing for some years.

The production of Bessemer steel in the Cumberland works in the year 1879 amounted to 127,163 tons of ingots, increased in 1880 to 140,869 tons of ingots, showing an increase of 13,706 tons of ingots over the previous year. The production of Bessemer steel rails in 1879 amounted to 103,969 tons, and in 1880 to 114,096 tons, showing an increase of 10,127 tons in the last-named year. The total output of Bessemer steel rails in Great Britain in the years 1879 and 1880, according to the annual reports of the British Iron Trade Association for those years, being respectively 519,718 tons, and 739,910 tons, giving an increased production in 1880 of 41 per cent. over the previous year.

CHAPTER V.

LANCASHIRE IRON INDUSTRIES.

Description of Iron Ore deposits in Furness—Analyses, production and distribution of Ore—Iron Mines in Lancashire—Population employed in Iron Mining—Pig Iron Manufacture—Early history—Barrow and Wigan Coal and Iron Co.'s Works—Production of Pig Iron—List of Iron Works—Malleable Iron and Bessemer Steel Works, and Coal employed—Mersey Steel Works—Coal and Iron Ore used in Pig Iron Manufacture—Sources of Iron Ore.

Lancashire. Iron Ore Deposits. Carboniferous Limestone.

—So closely do the iron ores of North Lancashire resemble those of Cumberland, both in their mineralogical character and in their mode of occurrence, that little need be added to what already has been said on the deposits of similar character in the adjoining county of Cumberland. Whilst the Cumberland hæmatite is for the most part a hard ore, the predominating mineral in the Furness district is a soft hæmatite, often containing, however, embedded pieces of a compact variety; most of this soft ore is used for fettling puddling furnaces. It is notable that many of the irregular deposits of ore in the carboniferous or "Mountain Limestone" of Furness extend upward to the level of the limestone, and are overlain merely by deposits of drift; from such a mode of occurrence it may be naturally inferred that the denudation which the ore-bearing rocks have suffered has removed the upper portions of the deposits, and that the drift was accumulated upon the exposed surface of ore. Some of these mineral deposits in Furness are of considerable extent; for example, the ore worked at Park, and at the Roanhead Mines, forms a deposit extending for upwards of 500 yards in length, its width varying from 120 to 240 yards.

As in the Whitehaven district, so in Furness, the ore is not confined to irregular deposits in the limestone, but is found also in more or less regular fissures, which generally have a north-west and south-east strike, with a dip to the south-west. Thus the mines at Stank, which are the deepest in the Furness district,

are worked upon one of these fissures of hæmatite, dipping 45° to the south-west; this is known to extend for a length of more than 500 yards, and is in part as much as 30 yards in width. Mr. P. Wurzbürger gives further interesting details of the deposits in this district in his paper read before the Barrow-in-Furness meeting of the Iron and Steel Institute, in August, 1874.

Analyses of the Ore.*—The hæmatite of the Lindal Moor Mines, near Ulverstone, of Messrs. Harrison, Ainslie, and Company, and worked extensively, has been examined by Mr. John Spiller, who described it as follows:—"The sample was selected from a large quantity of ore, consisting of fragments of various degrees of hardness, the majority of which were of the hard compact variety, deep grayish purple in colour, and covered with a brownish red unctuous powder; there were also small quantities of fibrous hæmatite and specular iron, together with quartz and a little earthy matter."

RESULTS TABULATED.

| | |
|----------------------------------|---------------|
| Peroxide of iron | 94.23 |
| Protoxide of manganese | 0.23 |
| Alumina | 0.51 |
| Lime | 0.05 |
| Magnesia | trace. |
| Phosphoric acid | minute trace. |
| Sulphuric acid | 0.09 |
| Bisulphide of iron | 0.03 |
| Water, hygroscopic | 0.39 |
| Water, combined | 0.17 |
| Insoluble residue | 5.18 |
| Total | <u>100.88</u> |

INSOLUBLE RESIDUE.

| | |
|-------------------------------------|-------------|
| Silica | 4.90 |
| Alumina | 0.12 |
| Peroxide of iron and lime | traces. |
| Total | <u>5.02</u> |

The total amount of metallic iron contained in the ore being equivalent to 65.98 per cent., a distinct trace of arsenic being detected in 1680 grains of the ore.

The hæmatite raised at Gilbrow,* also near Ulverstone, examined by Mr. A. Dick, is thus referred to:—"Description.—Red hæmatite; unctuous; easily scratched by the file; lustre,

* "Iron Ores of Great Britain," Part I., p. 66.

sub-metallic; colour, purplish red; streak, bright red; fracture, uneven and minutely crystalline; pieces of carbonate of lime and other minerals occur in it, which getting coloured by the powder, cannot be seen until the specimen is washed. Total amount of metallic iron contained in the ore is equivalent to 60·55 per cent."

RESULTS TABULATED.—ORE DRIED ABOVE 100° C.

| | |
|----------------------------------|---------------|
| Peroxide of iron | 86·50 |
| Protoxide of manganese | 0·21 |
| Lime | 2·77 |
| Magnesia | 1·46 |
| Carbonic acid | 2·96 |
| Phosphoric acid | trace. |
| Sulphuric acid | 0·11 |
| Insoluble residue | 6·55 |
| Total | <u>100·56</u> |

INSOLUBLE RESIDUE.

| | |
|--|-------------|
| Silica | 6·18 |
| Alumina containing a trace of iron | 0·30 |
| Total | <u>6·48</u> |

A whitish metal, precipitable by sulphuretted hydrogen from the hydrochloric acid solution, was found. The quantity obtained from 500 grains of ore was so small that it could not be identified.

The poorer ores in the Furness district average 45 per cent. of metallic iron, while 50 per cent. of iron are found in similar ores in the Whitehaven district. The following series of analyses, by Richards, shows the constituents of some of the best hæmatite ores of Barrow-in-Furness, employed in making Bessemer pig-iron in the Barrow Works:—

| Constituents. | Park. | Whitriggs. | Mouzell. |
|----------------------------------|--------|------------|----------|
| Peroxide of iron | 94·88 | 83·33 | 83·94 |
| Alumina | 0·07 | 0·75 | 0·70 |
| Protoxide of manganese | 0·04 | 0·08 | 0·28 |
| Lime | 0·34 | 4·10 | 0·85 |
| Magnesia | trace. | 0·15 | 0·09 |
| Water | 0·47 | 1·97 | 2·28 |
| Phosphoric acid | 0·03 | ... | 0·03 |
| Sulphuric acid | ... | trace. | ... |
| Carbonic acid | ... | 2·53 | ... |
| Silica | 4·55 | 6·59 | 12·46 |
| Total | 100·38 | 99·50 | 100·63 |

The Park ore gives 66·42 per cent. of metallic iron, the Whitriggs and Mouzell yielding respectively 58·33 and 58·76 per cent. The ore used at Askam has the following composition:—

| | |
|-----------------------------|---------------|
| Peroxide of iron | 83·00 |
| Silica | 15·50 |
| Carbonate of lime | trace. |
| Moisture | 1·50 |
| Total | <u>100·00</u> |

And yielding of metallic iron 58·10 per cent. It may be remarked, regarding these ores, that the harder variety is invariably used in the manufacture of hæmatite pig-iron, and is therefore called blast ore. The average yield of the Lancashire hæmatite may be taken as 64 per cent.

The following are analyses of other ores smelted at the Barrow Hæmatite Iron and Steel Company's works, and obtained from the localities named:—

| Constituents. | Lindal Moor (Blast Ore). | Lindal Cote (Puddling Ore). | Lindal Moor (Puddling Ore). | Dalton (Blast Ore). | Newton (Blast Ore). |
|----------------------------------|-----------------------------|--------------------------------|--------------------------------|------------------------|------------------------|
| Sesquioxide of iron | 78·61 | 77·24 | 86·20 | 67·14 | 77·64 |
| Phosphoric acid | 0·03 | ... | ... | ... | ... |
| Phosphorus | 0·01 | ... | ... | ... | trace. |
| Sulphuric acid | 0·04 | ... | 0·04 | ... | trace. |
| Carbonic acid | ... | 4·19 | 1·43 | 4·45 | trace. |
| Silica | 0·04 | 0·09 | 0·08 | ... | 0·01 |
| Alumina | trace. | 0·24 | 0·43 | 0·25 | 0·15 |
| Protoxide of manganese | 0·24 | 0·11 | trace. | 0·08 | 0·13 |
| Lime | 0·57 | 6·00 | 2·23 | 6·02 | 1·09 |
| Magnesia | 0·19 | 0·41 | 0·59 | 0·15 | 0·14 |
| Water | 2·02 | 2·82 | 3·35 | 1·80 | 3·08 |
| Insoluble residue | 18·31 | 9·07 | 6·50 | 19·77 | 17·94 |
| Total | 100·06 | 100·17 | 100·85 | 99·66 | 100·18 |
| INSOLUBLE RESIDUE. | | | | | |
| Silica | 16·11 | 7·27 | 5·58 | 19·09 | 15·44 |
| Alumina | 1·67 | 1·47 | 0·58 | 0·51 | 2·13 |
| Lime | 0·03 | 0·08 | 0·05 | 0·12 | 0·06 |
| Magnesia | 0·05 | trace. | trace. | trace. | trace. |
| Total | 17·86 | 8·82 | 6·21 | 19·72 | 17·63 |
| Metallic Iron | 55·03 | 54·07 | 60·34 | 47·00 | 54·35 |

Production of Hæmatite.—Taking a retrospective view of the iron trade in Barrow and the Furness district in the beginning of this century, it appears, according to the books of the Harbour Trustees, that the total quantity of ore sent from the port of Barrow, in the year 1800, was but 1,200 tons, compared with 146,000 tons in the year 1849, when Mr. Braithwaite Poole made a report on iron ore to the Directors of the Lancaster and Carlisle Railway Company. At this period, according to the above report, there appears to have been, in Great Britain, 60 mines in operation, the output of ore amounting to 500,000 tons per annum, and employing miners, bankmen, carters, and others, to the number of nearly 3,000 men, while the value of the ore thus raised annually was estimated to reach £500,000. The mines and firms raising hæmatite, in Lancashire, in 1849, were as follows, producing in the Furness district 182,000 tons, of an average of 64 per cent. of metallic iron:—

| No. | Mines. | Proprietors. | Tons. |
|-----|-------------------|--------------------------------|---------|
| 3 | Lindal Moor . . . | Harrison, Ainslie, and Co. . . | 55,000 |
| 3 | Cross Gates . . . | Town and Rawlinson . . . | 42,000 |
| 4 | Lindal Cote . . . | Ulverstone Mining Co. . . | 29,000 |
| 3 | Mouzell . . . | Schneider, Davis, and Co. . . | 25,000 |
| 1 | Haulme . . . | Charles Kennedy . . . | 12,000 |
| 2 | Stainton . . . | George Huddleston . . . | 12,000 |
| 1 | Elliscales . . . | George Ashburner . . . | 7,000 |
| 17 | | Total . . . | 182,000 |

Of this quantity 146,000 tons were shipped at Barrow, 33,000 tons disposed of by the Ulverstone Canal, the remaining 3,000 tons being consumed in the district in the works of Messrs. Harrison, Ainslie, and Co. The distribution of the ore was as follows:—

| DISTRIBUTION. | TONS. |
|---------------------------------|----------------|
| South Wales | 87,000 |
| Staffordshire | 84,000 |
| Furness district | 3,000 |
| Yorkshire | 3,000 |
| North Wales and Salop | 2,000 |
| Scotland | 2,000 |
| Newcastle and Durham | 1,000 |
| Total of Furness Ore | <u>182,000</u> |

The average selling price at Barrow at this period was 10s. 6d. per ton; the cost of getting and other incidental charges being shown in the annexed items:—

| | <i>s.</i> | <i>d.</i> |
|--|-----------|-----------|
| Royalty | 1 | 6 |
| Working | 2 | 6 |
| Propwood | 1 | 0 |
| Interest of value of stock | 1 | 0 |
| Carriage (cartage) | 1 | 4 |
| Railway to Barrow | 1 | 9 |
| Profit, including mining risks, bad debts, &c. | 1 | 5 |
| | <hr/> | |
| Selling price at Barrow, per ton | 10 | 6 |

The cost of carriage from Barrow to South Staffordshire by canal and railway appears in the following items, long weight of 2,400 lbs. to the ton:—

| BY SEA AND CANAL. | | <i>s.</i> | <i>d.</i> |
|---|--|-----------|-----------|
| Freight from Barrow to Ellesmere Port | | 2 | 6 |
| Charges wharfage and portorage at ditto | | 1 | 3 |
| Town dues | | 0 | 3 |
| Canal charges (say to Spring Vale) * | | 7 | 0 |
| Loss of ore by laying in open wharves at 2½ per cent. | | 0 | 3 |
| | | <hr/> | |
| Total long weight | | 11 | 3 |

| BY RAILWAY. | | <i>s.</i> | <i>d.</i> |
|---|--|-----------|-----------|
| Freight from Barrow to Fleetwood or Poulton | | 1 | 6 |
| Charges, wharfage and portorage at ditto | | 0 | 9 |
| Railway charges (say to Golds Hill) † | | 8 | 0 |
| Short weight v. long weight = 1-14th | | 0 | 9 |
| | | <hr/> | |
| Total long weight | | 11 | 0 |

Five years later, in 1854, the united production of the Lancashire and Cumberland mines amounted to 579,924 tons. Most of the mines producing this ore have since acquired a high reputation, on account of the vast deposits discovered, and the superior character of the metal produced therefrom, more especially since the introduction of the Bessemer process. The ore raised in 1854 was distributed thus:—to the Newcastle district, 6,785 tons; North Wales, 13,880 tons; South Staffordshire, principally by the London and North-Western Railway, 300,000 tons; and

* Mr. George Jones' Iron Works, near Wolverhampton.

† Messrs. Bagnall & Sons' Iron Works, near Tipton. These two works being at an average distance.

by ship coastwise to South Wales, 150,000 tons; showing how great was the demand at this time for these ores, to augment the supplies to other iron-making districts, the high per centage of metallic iron they contained enabling them to bear a considerable cost for transport to remote districts.

In subsequent years the production of the Lancashire mines is separately distinguished from those of Cumberland, amounting in the year 1855 to 336,829 tons, the total output of the mines of Great Britain the same year being 9,558,741 tons. The only ironworks existing in Lancashire at this period being those of Messrs. Harrison, Ainslie and Co., at Newland and Backbarrow, previously referred to, where the ores obtained from their Lindal Moor mines were smelted and pig-iron made with charcoal.

In the annexed table is shown the output of Lancashire hæmatite, in each year since 1855 :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1855 | 336,829 | 1868 | 767,625 |
| 1856 | 464,853 | 1869 | 784,507 |
| 1857 | 592,390 | 1870 | 871,938 |
| 1858 | 438,456 | 1871 | 931,048 |
| 1859 | 445,046 | 1872 | 909,077 |
| 1860 | 520,829 | 1873 | 975,826 |
| 1861 | 519,180 | 1874 | 914,357 |
| 1862 | 559,391 | 1875 | 834,484 |
| 1863 | 658,642 | 1876 | 908,664 |
| 1864 | 691,421 | 1877 | 993,012 |
| 1865 | 607,439 | 1878 | 984,781 |
| 1866 | 685,726 | 1879 | 976,822 |
| 1867 | 667,356 | 1880 | 1,266,503 |

In considering the value of these ores it may be stated that in the year 1871 and the two following years prices ranged from 19s. 9d. per ton in 1871, to 28s. 6d. per ton in 1872; and even this was eclipsed in the year 1873, when prices rose to 32s. per ton. In subsequent years prices have gradually diminished, thus, in the year 1878, the following are a few of the more important quotations of Lancashire ore delivered in trucks at the pits; Lindal Moor, 15s.; Askham, 14s. 6d.; Roundhead, 13s. to 14s.; the lowest price quoted being 10s. 9d. per ton.

The average price of ore in 1878, through and through, was 12s. 6d. per ton compared with 13s. 6d. in 1880. In the an-

nexed table appears the output of each iron mine in Lancashire in the year 1880, with the value of the ore:—

| Name of Mine. | Quantities. | | Value. | | |
|---|-------------|-------|---------|----|----|
| | Tons. | Cwts. | £ | s. | d. |
| Askham (Furness Iron and Steel Co.) | 2,303 | 0 | 1,381 | 16 | 0 |
| Dalton | 45,468 | 0 | 27,280 | 8 | 0 |
| Dalton (Myles Kennedy) . . . | 7,236 | 0 | 4,532 | 10 | 0 |
| Elliscales | 22,908 | 15 | 13,744 | 16 | 0 |
| Highfield | 6,462 | 0 | 4,696 | 10 | 0 |
| Lindal Cote, Eure pits, &c. . . | 29,998 | 0 | 20,247 | 13 | 0 |
| Lindal Moor (Furness Iron and Steel Co.) | 16,031 | 0 | 10,820 | 12 | 0 |
| Lindal Moor, Whitriggs and Gilbrow | 257,696 | 0 | 173,944 | 16 | 0 |
| Lindal and Ousby | 1,831 | 0 | 1,098 | 12 | 0 |
| Lindal-in-Furness (Wigan Coal and Iron Co.) | 644 | 0 | 386 | 8 | 0 |
| Mouzell | 92,597 | 0 | 53,264 | 5 | 0 |
| Newton (Barrow H. S. Co.) . . | 1,858 | 0 | 1,300 | 0 | 0 |
| Old Hills | 3,575 | 0 | 2,502 | 10 | 0 |
| Park | 305,415 | 0 | 213,790 | 0 | 0 |
| Stank | 127,910 | 0 | 89,538 | 10 | 0 |
| Pennington (Parkside Mining Co.) | 29,326 | 0 | 20,528 | 0 | 0 |
| Roanhead and Askham | 218,363 | 0 | 152,854 | 0 | 0 |
| Stainton (Stainton Mining Co.) . | 4,304 | 19 | 3,013 | 10 | 0 |
| Whitriggs (Barrow H. S. Co.) . | 43,335 | 0 | 30,334 | 10 | 0 |
| Yarlside (Parkhouse) | 49,242 | 0 | 35,700 | 0 | 0 |
| Total of Lancashire | 1,266,503 | 14 | 860,959 | 6 | 0 |

Since the year 1872 the mines of the Barrow Hæmatite Steel Company have produced ore in the following quantities:—

| Year. | Newton. | Old Hills. | Park. | Stank. | Whitriggs. | Stainton. |
|-------|---------|------------|---------|---------|------------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1872 | 6,300 | * | 262,305 | 6,052 | 10,965 | 1,770 |
| 1873 | 4,339 | * | 283,496 | 13,246 | 16,185 | 2,347 |
| 1874 | 5,234 | 2,296 | 270,469 | 22,285 | 14,252 | 2,721 |
| 1875 | 6,254 | * | 245,045 | 50,891 | 19,981 | 2,043 |
| 1876 | 5,626 | 4,338 | 232,374 | 67,420 | 27,471 | 111,875 |
| 1877 | 6,200 | 3,441 | 219,462 | 77,151 | 29,902 | 229 |
| 1878 | 5,269 | 6,417 | 208,329 | 110,917 | 29,961 | 1,400 |
| 1879 | 1,656 | 2,632 | 226,107 | 114,936 | 30,445 | 727 |
| 1880 | 1,858 | 3,575 | 305,415 | 127,910 | 43,335 | ... |

In the annexed table the Roanhead Mines, the property of Messrs. Denney and Co., the Lindal Moor of Messrs. Harrison,

* Included in Whitriggs.

Ainslie and Co., and the Askham, Lindal Moor and Dalton Mines of the Furness Iron and Steel Company, produced ore in the following quantities since the year 1872 :—

| Year. | Askham. | Lindal Moor. | Dalton. | Roanhead, &c. | Lindal Moor. |
|-------|---------|--------------|---------|---------------|--------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1872 | 5,718 | 4,407 | ... | 170,769 | 158,341 |
| 1873 | 25,881 | 45,005 | ... | 199,017 | 153,138 |
| 1874 | 23,679 | 32,749 | 29,154 | 187,455 | 160,474 |
| 1875 | 16,571 | 8,138 | 8,616 | 131,210 | 167,049 |
| 1876 | 11,215 | 13,276 | 5,334 | 129,508 | 193,040 |
| 1877 | 10,050 | 10,787 | 13,996 | 134,670 | 219,812 |
| 1878 | 10,154 | 12,346 | 28,406 | 134,464 | 224,389 |
| 1879 | 8,795 | 15,368 | 47,315 | 138,452 | 225,827 |
| 1880 | 2,303 | 16,031 | 45,468 | 113,551 | 257,696 |

The average prices in 1879 from these mines varied from 10s. to 15s. 6d. per ton, and in 1880 about 13s. 6d. per ton.

Distribution of the Ore.—Except some inconsiderable quantities of ore carried in a few localities to the ironworks by road, the great bulk of the ore is distributed by the Furness Railway, either to Barrow for shipment to other ports, or by rail to Yorkshire, Staffordshire, &c., and to the ironworks of the county.

The earliest return published for the year 1855 gives the annexed account of the distribution of ore in that year :—

| DISTRIBUTION OF THE ORE. | | QUANTITIES. |
|--|--|-------------|
| | | Tons. |
| Shipped at Barrow | | 313,797 |
| „ to Scotland | | 1,470 |
| „ for Yorkshire, &c. | | 1,500 |
| By rail to Yorkshire, Staffordshire, and Wales | | 17,711 |
| Consumed in district | | 2,351 |
| Total production in 1855 | | 336,829 |

Lancashire, with her valuable resources of rich red hæmatite, was not destined to remain a repository only for the supply of other districts; as time rolled on a remarkable development took place, and in due course some of the best arranged smelting works were established, and a great industry was created, absorbing in 1880 nearly three-fourths of all the ore raised. This will appear in the annexed table, showing the respective quantities sent by ship, rail, and to the iron furnaces of the district in each of the years since 1856, by the Furness Railway :—

| Year. | By Ship. | By Rail. | To Furnaces. | Total. |
|-------|----------|----------|--------------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| 1856 | 461,303 | ... | 3,550 | 464,853 |
| 1857 | 574,952 | 14,729 | 2,709 | 592,390 |
| 1858 | 367,568 | 69,028 | 1,950 | 438,456 |
| 1859 | 305,136 | 130,896 | 9,014 | 445,046 |
| 1860 | 259,477 | 181,712 | 79,640 | 520,829 |
| 1863 | 238,882 | 205,701 | 204,059 | 658,642 |
| 1866 | 163,725 | 188,701 | 333,300 | 685,726 |
| 1869 | 96,322 | 177,630 | 510,555 | 784,507 |
| 1871 | 74,732 | 253,478 | 602,838 | 931,048 |
| 1873 | 73,164 | 239,669 | 662,993 | 975,826 |
| 1875 | 63,926 | 118,459 | 628,230 | 810,615 |
| 1876 | 65,423 | 105,677 | 662,566 | 833,666 |
| 1877 | 42,657 | 97,767 | 762,412 | 902,836 |
| 1878 | 25,356 | 120,737 | 733,387 | 879,480 |
| 1879 | 30,981 | 95,200 | 787,745 | 913,926 |
| 1880 | 50,557 | 139,328 | 939,858 | 1,129,743 |

The following account gives the details of the distribution of the ore by rail and ship in the year 1880 :—

| | TONS. | TONS. |
|---|---------|-----------|
| <i>Shipped at Barrow to</i> South Wales | 12,102 | |
| „ Lancashire, North Wales, &c. | 20,552 | |
| „ Scotland | 16,542 | |
| „ Foreign Parts | 1,361 | |
| | | 50,557 |
| <i>Shipped at Ulverstone Canal</i> | ... | |
| <i>By rail to</i> Lancashire, Yorkshire and Staffordshire | 139,328 | |
| „ furnaces in district | 939,858 | |
| | | 1,079,186 |
| <i>Total by sea and rail</i> | | 1,129,743 |

Beyond the above quantities, 136,760 tons of ore were conveyed to the ironworks by road, compared with 62,896 tons in 1879.

Examining the quantities appearing under the respective heads in the above table, some interesting facts appear, deserving of attention. Already the increased consumption of the blast furnaces has been referred to: a glance at the quantities carried to the shipping ports and sent coastwise to distant iron districts, shows a remarkable decline from 574,952 tons in the year 1857 to 25,356 tons in the year 1878. The quantities sent out of the district by rail on the other hand has not varied to any great extent since the year 1859, except between the years 1871 and 1873, which will ever be remembered in the history of the coal

and iron industries as a time of great prosperity; thus, in 1859 the ore sent out of the district reached 130,896 tons, compared with 253,478 tons in the year 1871, and 233,238 tons in the year 1872, since which the quantities sent away show little variation.

The diminished export of ore from the Furness deposits to other districts, where it was in great request, has been to some extent accounted for by the additional imports from foreign countries, particularly from Spain, amounting in the year 1880 to 2,278,962 tons, of the value of £2,270,462, giving an average of 20s. per ton; the total imports of iron ore the same year being 2,632,601 tons of the value of £2,789,929.

Examining the distribution of the Furness ore, the following figures for a few years will show the falling off to those districts formerly receiving it in considerable quantities by both sea and rail:—

| Destination. | 1868. | 1873. | 1878. | 1880. |
|---|---------|---------|---------|---------|
| <i>By Sea.</i> | Tons. | Tons. | Tons. | Tons. |
| South Wales | 78,338 | 50,777 | 11,750 | 12,102 |
| Lancashire and North } Wales | 47,339 | 18,194 | 7,098 | 20,552 |
| Scotland | 4,365 | 4,138 | 5,731 | 16,542 |
| Foreign Parts | 130 | 55 | 777 | 1,361 |
| <i>By Rail.</i> | | | | |
| Lancashire, Yorkshire, } &c. | 82,978 | 198,911 | 120,737 | 139,328 |
| Scotland | 350 | 2,937 | ... | ... |
| Newcastle, Stockton, &c. | 48,057 | 37,821 | ... | ... |
| Total | 261,557 | 312,823 | 146,093 | 189,885 |

Recent explorations of the iron ore deposits of Furness have disclosed some interesting facts, showing that they are far more important and extensive than was formerly considered. The Mouzell Mine, near Dalton-in-Furness, was surrendered to the owner in December, 1877, by the Barrow Hæmatite Iron and Steel Company. Subsequent explorations, conducted by the manager for the owner, have resulted in the discovery of an extensive basin at least 70 yards in length, and varying in width from 30 to 40 yards, and in depth from 20 to 30 yards.

The mines, situation, proprietors or companies and chief agents, now in operation in Lancashire, are as follows:—

| No. | Name of Mine. | Situation. | Name of Proprietor or Company. | Name of Manager or Agent. |
|-----|-------------------------|----------------------|--|---------------------------|
| 1 | Askam | Askam-in-Furness . . | { *Furness Iron and Steel Co., Limited . | { Henry Mellon. |
| 2 | Crossgates | Near Dalton | " | " |
| 3 | Dalton | " | " | " |
| 4 | Lindal Moor | Ulverston | " | " |
| 5 | Martin | " | " | " |
| 6 | Goldmire | " | " | " |
| 7 | Pennington | " | " | " |
| 8 | Plumpton | " | " | " |
| 9 | Thwalte Flatt . . . | Dalton | " | " |
| 10 | Stainton | " | { Barrow Hæmatite Steel Co., Limited . | { William Kellett. |
| 11 | Newton | " | " | " |
| 12 | Park | " | " | " |
| 13 | Old Hills | " | " | " |
| 14 | Whitriggs | " | " | " |
| 15 | Pennington | Lindal | Parkside Mining Co. . | George Scoular. |
| 16 | Urawick | " | " | " |
| 17 | Stank | Dalton | { Barrow Hæmatite Steel Co., Limited . | { William Kellett. |
| 18 | Stainton | " | { The Stainton Mining Co. | { James Garstang |
| 19 | Bercume | Ulverston | Rigg & Co. | Brogden. |
| 20 | Mouzell | Dalton | John Clegg | Captain Goldy. |
| 21 | Dalton | " | Myles Kennedy | James Ashworth. |
| 22 | Elliscales | " | Elliscales Mining Co. . | Miles Kennedy. |
| 23 | { Lindal Cote, Eure | " | The Ulverston Mining Co., Limited | Joseph Askew. |
| 24 | { Fiza and Crossgates | " | Harrison, Ainslie, & Co. | { J. G. Brogden. |
| 25 | { Glibrow and Whitriggs | " | " | Edmund Ray. |
| 26 | Highfield | Dalton | { Cumberland Iron Mining and Smelting Co., Limited . | { Thomas Massicks. |
| 27 | Longlands | " | Duke of Buccleuch . . | Edward Wadham. |
| 28 | Roanhead and Askam | " | Kennedy Brothers . . . | Myles Kennedy. |
| 29 | Urawick | Ulverston | Begbie & Co. | H. D. V. Begbie. |
| 30 | Lindal and Ousby . . | Little Urawick . . . | { Lindal and Ousby Iron Ore Co., Llm. . | { Hy. Postlethwaite. |
| 31 | Yarlside | Dalton | { Thos. Storey and Wm. Boulton | { Wm. Boulton. |

Population employed in Ironstone Mining.—The earliest return published for the year 1878 shows that of 3,222 persons employed in Lancashire in the Hæmatite Iron Mines 1,890 were employed underground, and 1,332 above ground, producing 852,064 tons of iron ore. These returns refer only to those mines under the operation of the "Metalliferous Mines Regulation Act, 1872;" the total iron ore produced in Lancashire in the same year was 928,174 tons, the difference, 76,110 tons, being the output of mines not coming under the operation of the above-named Act.

The annexed table, constructed from the Annual Reports of H.M. Inspectors of Mines, gives the total numbers of persons employed under ground and above ground in each of the years, with the total output and average produce per man :—

* In liquidation.

| Year. | PERSONS EMPLOYED. | | Total Employed. | Iron Ore Raised. | Average per Man. |
|-------|-------------------|---------------|-----------------|------------------|------------------|
| | Under Ground. | Above Ground. | | | |
| 1873 | 1,890 | 1,332 | 3,222 | Tons. 852,064 | Tons. 264 |
| 1874 | 2,135 | 1,462 | 3,597 | 934,234 | 260 |
| 1875 | 1,812 | 1,275 | 3,087 | 882,840 | 286 |
| 1876 | 1,950 | 1,247 | 3,197 | 858,894 | 268 |
| 1877 | 2,061 | 1,162 | 3,223 | 913,060 | 283 |
| 1878 | 2,194 | 1,121 | 3,315 | 906,994 | 273 |
| 1879 | 2,008 | 1,140 | 3,148 | 979,659 | 311 |
| 1880 | 2,807 | 1,426 | 4,233 | 1,188,543 | 280 |

The steady working of the ironstone miner is apparent in these returns, showing an increase in the eight years of 16 tons per man, equivalent to 7 per cent.

Pig Iron Manufacture.—As far back as the year 1788 evidence appears of the existence of small furnaces in Lancashire, where iron ore was smelted with the aid of charcoal; these were situated and known as the Newland, Backbarrow, and Leighton furnaces, and their production is recorded in the year named as 2,100 tons, or 700 tons per furnace. Another return for the year 1796 records the make of the two first named as 700 tons, and the Leighton furnace as 780 tons, or an aggregate for that year of 2,180 tons, being an increase of 80 tons in six years.

The total make of pig iron in 1788 was of charcoal pig iron 13,100 tons, and of coke pig iron 48,200 tons, giving an aggregate of 61,300 tons to England and Wales; and a further sum of 7,000 tons to Scotland, of which 1,400 tons were charcoal pig and 5,600 tons coke pig iron, making in all 68,300 tons. Again, in 1796, according to the return prepared by Dr. Macnab and presented to a committee of the House of Commons, the details of which return will be found in another page, the total make of the furnaces of Great Britain amounted to 125,079 tons, of which 3,780 tons were charcoal pig and 121,299 tons coke pig iron.

In 1806 the Leighton furnace was alone in operation; as far as can be ascertained the make of pig iron for that year was 780 tons, as in the year 1796. Some years later Mr. David Mushet ascertained that the quantity of charcoal iron made in Lancashire did not exceed 800 tons; this was about the year 1839, the works producing this quantity being those at Newland and at

Backbarrow, as previously stated, of Messrs. Harrison, Ainslie, and Co., the firm having others at Duddon in Cumberland, at Lorn near Bunawe in Argyleshire and at Warsash in Hampshire; these furnaces still exist, though only in operation at intervals, and are the only remaining charcoal furnaces in Great Britain. The firm above-named was, until the year 1858, the only one in Lancashire making pig iron; it was in that year that the Wigan Coal and Iron Company, at their works at Kirkless Hall, Ince, near Wigan, put two furnaces in blast, the make of pig iron in Lancashire at this period was 2,840 tons, which includes the charcoal iron made at the furnaces of Messrs. Harrison, Ainslie, and Co. The Messrs. Schneider and Hannay, in the year 1859, at their works at Barrow put three furnaces in blast, increasing the number in the county to seven, the aggregate make of which in the same year amounted to 26,491 tons. Advancing to the year 1860 the Wigan Company put another furnace in blast, making 10 built in the county, of which eight were in operation, producing 81,250 tons of coke and charcoal pig iron. About this time other works already projected commenced; the Carnforth Hematite Iron Company in the year 1866 blew in two furnaces; the Ditton Brook Company three in the year 1868; and the Furness Iron and Steel Company the same number in the year 1871.

The Darwen Iron Company commenced operations in the year 1874 with two furnaces; and the Outwood Iron Company at Outwood, near Ratcliffe, with one furnace the same year; while in the year 1875 the North Lonsdale Hematite Iron Company added two furnaces to the district, bringing the total number of those erected up to 50, of which 31 were in blast.

Returning to the production of charcoal pig iron in Lancashire, an occasional return is met with showing the quantities made. In the year 1857 the works at Newland and Backbarrow produced 1,233 tons; in 1859 the same works produced 720 tons. The make of these furnaces since that date is included in the yield of the Lancashire furnaces, but it is estimated that the make of charcoal pig iron in Lancashire is not less than 1,400 or 1,500 tons per annum.

Since the year 1860 the number of furnaces built, and in blast, the pig iron made, and the average yield of the furnaces have been as follows:—

| Year. | FURNACES. | | Pig Iron made. | Average per Furnace. |
|-------|-----------|-----------|----------------|----------------------|
| | Built. | In Blast. | | |
| | No. | No. | Tons. | Tons. |
| 1860 | 10 | 8 | 81,250 | 10,156 |
| 1861 | 12 | 10 | 109,377 | 10,937 |
| 1862 | 14 | 11 | 138,563 | 12,597 |
| 1863 | 17 | 11½ | 164,110 | 14,270 |
| 1864 | 17 | 13½ | 195,460 | 14,478 |
| 1865 | 24 | 16½ | 204,925 | 12,420 |
| 1866 | 25 | 19 | 268,680 | 14,141 |
| 1867 | 25 | 19 | 318,801 | 16,780 |
| 1868 | 28 | 22½ | 325,367 | 14,460 |
| 1869 | 30 | 27 | 436,662 | 16,173 |
| 1870 | 33 | 27 | 422,728 | 15,656 |
| 1871 | 41 | 34 | 520,359 | 15,300 |

A brief description of the Barrow Hematite Works and of the Kirkless Hall Works will indicate the magnitude and extent of these important metallurgical establishments.* "At the works of the Barrow Hematite Steel Company there are altogether 16 blast furnaces, 14 of which are built in a single row, while the remaining two are distant about half a mile. The weekly production of the blast furnaces averages 5,500 to 6,000 tons; but it is always calculated that two or three furnaces are out for alteration or repairs." The average height of the furnaces is about 63 feet, some of them being 62 feet and others 65 feet high. The first furnaces, built in 1859, were only 45 feet high; but these furnaces have recently been raised to 62 feet. The average consumption of fuel is one ton of coke per ton of pig iron made. The ore, which is obtained at the Company's own Mines, near Ulverston, averages 60 per cent. of metal. The consumption of limestone is about 9 cwts. per ton of iron made. The blast is heated to a temperature of 900° to 1,100°, according to the quality of the iron required. Each furnace is fitted with six tuyeres, the diameter of the nozzles being 3½ inches to 4 inches. The larger furnaces have a bosh of 20 feet diameter, and the smaller ones a bosh of 19 feet. The blast is partly heated by Cowper's and partly by Gjers's stoves. The engines that blow the blast are a remarkable feature of the ironworks. There are three beam and 18 grasshopper engines. Of the latter kind, not less than 10 are in one engine-house, which is said to be the largest engine-house in the world. With the exception of the

* "Journal of the Iron and Steel Institute," 1874, p. v. appendix.

buildings that contain the beam engines all the engine-houses are built parallel with the blast furnaces on the contrary side from the pig iron beds. The beam engines have double-acting high-pressure steam cylinders, 48 inches diameter and 9 feet stroke, the blowing cylinder being 72 inches diameter. The hoists are inclined planes, and are worked by special engines, there being a separate engine for each of the six inclines that are attached to the 14 furnaces. The hoist engines are of the ordinary reversing kind, worked by frictional gearing. The drum is 12 feet diameter, and the cylinders of the engines are 16 inches, with two feet length of stroke. Most of the engines have been made by Perry and Sons, of Bilston. All the furnaces are fitted up with the apparatus for the utilization of the waste gases, which are sufficient to supply all the heaters and boilers without any other fuel. The blast furnaces are distant about 200 yards from the steel works, the intervening space being occupied by sidings and filling sheds, and a spacious cast-iron bridge, spanning the whole of these sidings, connects the one department with the other. The steel works are in three large bays or roofs, each 700 feet in length. The pig iron on being brought from the blast furnaces is stored here in rather a peculiar manner; the first cast of the week is put down in a row of perhaps 150 to 200 yards in length, and the next day's cast is placed on the top of the first day's, and so on to the end of the week, when the pigs are cleared from top to bottom of the heap, thus giving a week's average of the iron, and preserving a uniform consistency and quality of steel.

"The productive capacity of the steel works is 3,500 tons per week. Rails constitute the principal branch of manufacture, there being three large rail mills, one plate mill, and one smaller mill for merchant steel. There are 18 convertors at work, and 12 steam hammers made by John Musgrave and Sons, of Bolton. One of the rail mills is driven by a Ramsbottom reversing engine. The other rail mills are on the three-high principle, and are worked by beam engines, supplied by Hick, of Bolton, while an ordinary horizontal engine, with a 40 inch cylinder, works the merchant mill. The total engine power of the works is equal to 4,000 horse power. Most of the boilers are of the ordinary Cornish pattern, but there are also 13 of Howard's patent boilers fired by "Vickers' mechanical appliance." It has been estimated that the Barrow furnaces produce upwards of a quarter of a

million tons of pig iron annually with a consumption of upwards of 870,000 tons of coal, and 470,000 tons of hematite.

"The Ironworks of the Wigan Coal and Iron Company at Kirkless consist of 10 blast furnaces, 5 being 65 feet high, and 5 80 feet high. Two of these latter are of recent construction, and are built upon the most improved principle. The furnaces have closed tops, and the gas is conveyed by a tube 8 feet in diameter to 18 double-flued boilers, 28 feet long and 7 feet 6 inches in diameter, which stand opposite the engine-house. The Wigan Company manufacture their own coke from the slack raised from their pits. At present there are 460 coke ovens, but the number is insufficient to supply the requirements of the furnaces. For some time past the slack after being washed has been crushed, which makes the coke much harder than formerly, and enables the furnaces to turn out more iron than under the old system. The crushing machines are of special construction, and were designed by the coke works manager. They are simple in design, and do their work regularly and efficiently. The works have ample waterway and railway accommodation. The canal immediately adjoins the works on one side, and they are also connected by private railways with the London and North-Western and Lancashire and Yorkshire Railways. The ore is brought in the railway waggons and emptied into bunkers running the whole length of the furnaces. The ore is taken from the bunkers in barrows, and with the coke and other materials used in the manufacture of iron is hoisted to the top of the furnaces by four vertical engines. About 400 men are employed at the furnaces, which manufacture four special brands, viz., the Kirkless foundry and forge, and the hematite and mes-selmoun brands. The engine-house stands at the end of the row of blast furnaces and is 100 feet long, 56 feet wide, and 70 feet high, with a tower 100 feet high. There are three pairs of compound engines, the high pressure cylinders being placed on one side of the building and the low pressure on the other, each pair being connected by a 36 foot beam. The high pressure cylinders are 45 inches, and the low pressure 66 inches in diameter, with a 12 foot stroke. The blowing cylinders, of which there are six, are each 100 inches in diameter. The steam pressure is 45 lbs., and the blast 8 lbs.

"The Wigan Coal and Iron Company have produced as much as 2,500,000 tons of coal and 150,000 tons of pig iron per annum.

The seams worked by the company include one of Cannel Coal, and also the well known Hartley Mine, and other portions of the Lancashire coal beds. The coking coal obtained from this district contains a certain percentage of sulphur, which if not removed or greatly reduced would render the coke unfit for producing the best marks of Bessemer pig, which forms the staple product of the company, and this has led to the extensive employment of coal washing machinery as already mentioned. The coal, after being crushed by crushing rollers, is lifted by elevators, and delivered into washing chambers or bashes, in each of which the water is made to rise and fall rapidly by the action of a piston working in a cylinder connected with the chamber, this piston being 36 inches in diameter, and making 150 strokes per minute. The length of stroke is $3\frac{1}{2}$ inches. The coal rests on perforated copper sieves, and by the pulsating action of the water the good coal is washed over the edges of the sieves, while the pyrites being heavier, remain in the latter, and are removed at suitable intervals. The loss by washing is about 10 per cent., and the washed coal is coked in eight ton ovens, the coking process occupying five days. The iron ore used consists principally of the well known red hematite of the Ulverstone district, but a percentage of argillaceous Belfast ore is also employed for the purpose of bringing some alumina into the charge, thus forming a flux. Limestone is also added, the proportion of this latter material used when making Bessemer iron being very considerable."

Resuming with the production of pig iron in Lancashire the following shows the results attained since the year 1871 :—

| Year. | FURNACES. | | Pig Iron made. | Average per Furnace. |
|-------|-----------|------------------|----------------|----------------------|
| | Built. | In Blast. | | |
| | No. | No. | Tons. | Tons. |
| 1872 | 41 | 34 $\frac{1}{2}$ | 524,041 | 15,080 |
| 1873 | 44 | 36 | 529,271 | 14,702 |
| 1874 | 47 | 33 | 488,672 | 15,800 |
| 1875 | 50 | 31 | 558,780 | 18,025 |
| 1876 | 50 | 30 | 552,984 | 18,432 |
| 1877 | 50 | 33 | 684,189 | 20,733 |
| 1878 | 50 | 30 | 616,255 | 20,542 |
| 1879 | 49 | 36 | 631,343 | *17,537 |
| 1880 | 49 | 37 | 750,884 | 20,294 |

* The falling off in the average yield of the furnaces in 1879 is due to the fact that six of the furnaces were only in blast for a few months.

The furnaces of Lancashire work with great regularity, and when fully employed produce from 400 to 460 tons of iron weekly, of a quality suitable for conversion into steel by the Bessemer process. A glance at the returns of the past few years confirms the above statement. The following details illustrate clearly the proportion of the several parts of a furnace of the Furness Iron and Steel company at Askham, 67 feet in height, the capacity of which is 13,100 cubic feet:—

| DESCRIPTION. | DIMENSIONS. |
|---------------------------------------|------------------|
| Height of furnace | 67 ft. |
| Diameter at boshes | 19 " |
| " throat | 18 " |
| " hearth | 7 " |
| Heating surface | 5,500 sq. ft. |
| Number of tuyeres | 6 |
| Area of blast inlet | 76 sq. in. |
| Pressure of blast at engine | 2½ lbs. |
| " " tuyeres | 3 " |
| Area of gas inlet | 18 sq. ft. |
| Diameter of charging bell | 12 ft. 6 in. |
| Weekly make of iron | 400 to 460 tons. |

The works and furnaces built and in operation in the year 1880 were as follows:—

LANCASHIRE.

| No. | Name of Works. | Owners. | FURNACES. | |
|---------------------------|------------------------------|--|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Barrow Hematite Iron & Steel | Barrow Hematite Steel Co., Lim. | 14 | 13 |
| 2 | Carnforth | Carnforth Hematite Iron Co., Limited | 6 | 4 |
| 3 | Darwen | Darwen Iron Co., Limited . . . | 2 | 2 |
| 4 | Ditton Brook, Widnes . . . | Ditton Brook Iron Co., Limited . | 6 | 3 |
| 5 | Askam, Askam-in-Furness . . | Furness Iron & Steel Co., Lim. . | 4 | 3½ |
| 6 | Kirkless Hall, Ince . . . | Wigan Coal & Iron Co., Lim. . | 10 | 6 |
| 7 | Newland Ulverston . . . | Harrison, Ainslie, & Co. . . | 2 | 1½ |
| 8 | Backbarrow, " . . . | | | |
| 9 | North Lonsdale, Ulverston . | North Lonsdale Iron and Steel Co., Limited . . . | 4 | 3 |
| 10 | Outwood, Ratcliffe . . . | Outwood Iron Co., Lim. . . . | 1 | 1 |
| Total of Lancashire . . . | | | 49 | 37 |

Mills and Forges, and Steel Works.—In the year 1873 there were in Lancashire 23 malleable and six steel works, these latter making steel by the Bessemer process; the resources of the above 23 works numbered 350 puddling furnaces and 81 rolling

mills, the Bessemer plant amounting to 42 convertors of a united capacity equal to 228 tons, the annual consumption in all the above works in the year 1873 being estimated from reliable sources as 330,000 tons of coal. Already a brief account in a previous page described the Barrow Iron and Steel Works, the next most extensive steel works in the district are those of the Mersey Steel and Iron Company,* "situated near Liverpool, and covering an area of about eleven acres. These works comprise a plant of five pairs of six ton convertors, three pairs being arranged in one group, the other two pairs, each pair being placed by itself. Formerly the Mersey Steel and Iron Company were large steel manufacturers, and they were extensively engaged in the production of puddled steel prior to the development of the Bessemer process. For the past two years or so, however, they have discontinued the manufacture of steel rails, and their Bessemer plant has only been occasionally worked for the manufacture of the steel used for making the bars they are now using in the production of steel forgings."

"The ingot moulds used are all close-topped, and run from the bottom in groups, generally eight in a group. The central git used is of small diameter and is higher than the tops of the surrounding ingot moulds. The blowing engines connected with the Bessemer plant are contained in two engine-houses, one large engine-house adjoining the group of three pairs of convertors containing a pair of horizontal blowing engines by Messrs. Rothwell and Co., of Bolton, and also the engines for supplying water to the hydraulic cranes, &c., and three smaller blowing engines. In the other engine-house connected with the Bessemer department of the works, there is a pair of horizontal engines made by Galloways, of Manchester, which have piston valves on the blowing cylinders. To enable any pair of convertors to be blown from either engine, the air ways of the two engine-houses are connected."

"In the mill department there is a three high cogging-mill, a two high reversing rail mill used for bars, angles, and bull-headed rails. A new forge is now, however, in course of construction, to which the latter will be ultimately removed, and where also a three high cogging mill, driven by a pair of horizontal engines, and a two high reversing train driven by a pair of

* "Journal of the Iron and Steel Institute," 1879, p. 621.

vertical reversing engines, have been fitted up. Adjoining the forge are two machine shops, separated by the offices which stand between them—the one containing a good heavy plant of tools adapted for sharpening large forgings, such as stern posts, &c.—and includes an exceptionally large planing machine with two tables, which can either be run together or separately. The other machine shop is specially laid out for dealing with large crank shafts and contains an excellent plant for this purpose, including large lathes, and one of Messrs. Craven Brothers' crank pin turning lathes, in which the shaft to be turned is stationary, the tool being carried round it. The whole shop is commanded by a fine travelling crane worked by a fast running rope. In this division of the works, besides the forge and machine shops, there is a range of Siemens gas producers and a group of nine Lancashire steam boilers, for supplying steam to the steam hammers, &c. Passing through a tunnel another similar group of boilers is reached, these being adjacent to the engines of the steel works, but the steam pipes being connected, so that either division of the works can be supplied with steam from either group of boilers. The following is a list of the steel works employing the Bessemer process in Lancashire, distinguishing the number and capacity of the converters " :—

| Name and Situation of Works. | Number of Convertors. | Capacity of Convertors. |
|---|-----------------------|-------------------------|
| | | Tons. Cwts. |
| Carnforth Hematite Iron Co., Carnforth . . | 2 | 6 0 |
| Bolton Iron and Steel Co., Bolton . . | 4 | 5 0 |
| Manchester, Sheffield, and Lincolnshire Rail- way Co., Gorton Works, near Manchester . | 4 | 3 10 |
| Mersey Steel and Iron Works, Toxteth Park, Liverpool . . | 10 | 6 0 |
| Manchester Steel and Railway Plant Co., Gib- raltar Works, Newton Heath, Manchester . | 4 | 3 0 |
| Barrow Hematite Steel Co., Barrow . . | 8 | 7 0 |

A careful examination of the quantity of fuel consumed in the iron and steel works in Lancashire for a few years, gives the following results. These figures are obtained from a large number of returns since the year 1871, and to render them available for comparison, the number of puddling furnaces and rolling mills in operation is given for each of the same years :—

| Year. | Puddling Furnaces. | Rolling Mills. | Coal Used. |
|-------|-----------------------|-------------------|------------|
| | No. | No. | Tons. |
| 1873 | 350 | 81 | 330,000 |
| 1874 | 376 | 69 | 348,000 |
| 1875 | 434 | 69 | 465,455 |
| 1876 | 421 | 78 | 380,000 |
| 1877 | 389 | 77 | 363,125 |
| 1878 | 285 | 68 | 376,193 |
| 1879 | 353 | 82 | 542,247 |
| 1880 | 373 | 86 | 599,740 |

This description of the iron industries of Lancashire would be incomplete without the following list of mills and forges in the year 1880, which brings the information up to date:—

LANCASHIRE.

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-----------------|------------------------------|--|-------------------------------------|---------------------------------|-----------------------------|
| 1 | Atherton Quay | Monks, Hall, & Co., Ldn. | Warrington | 26 | 3 |
| 2 | Albion, Aspull | Edward Hale | Wigan | 22 | 3 |
| 3 | Atlas Forge | Thomas Walmisley & Sons | Bolton | 16 | 12 |
| 4 | Barrow | Barrow Hematite Steel Co., Limited | Ulverston | 0 | 4 |
| 5 | Bewsey | The Pearson and Knowles Coal and Iron Co., Ldn. | Warrington | 127 | 14 |
| 6 | Dallam | " | " | | |
| 7 | Moss Side | " | Wigan | | |
| 8 | Bolton | Bolton Iron and Steel Co., Limited | Bolton | 0 | 5 |
| 9 | Bradford | Richd. Johnson and Nephew | Manchester | 27 | 4 |
| 10 | Carnforth | Carnforth Hematite Iron Co. | Carnforth | 0 | 3 |
| 11 | Garston | Liverpool and Garston Steel and Iron Co. | Garston | .. | .. |
| 12 | Gidlow | Thomas Gidlow | Wigan | .. | .. |
| 13 | Gibraltar | Railway Steel and Plant Co., Limited | Manchester | .. | .. |
| 14 | Globe | John Summers | Stalybridge | 10 | 3 |
| 15 | Gorton | M. S. and Lincolnshire Railway Co. | Manchester | 1 | 3 |
| 16 | Hartford Forge | Platt Brothers & Co., Limited | Oldham | 8 | 3 |
| 17 | Ince Hall | Ince Hall Rolling Mills Co., Limited | Wigan | 24 | 4 |
| 18 | Mersey | Mersey Steel and Iron Co., Limited | Liverpool | 6 | 6 |
| 19 | Openshaw | Ashbury Railway Carriage and Iron Co., Limited. | Manchester | 22 | 3 |
| 20 | Park Bridge | H. Lees & Sons | Ashton | 8 | 3 |
| 21 | Pendleton | William Barmingham & Co., Limited | Manchester | 22 | 4 |
| 22 | Perseverance, Pendle- ton | Maybury, Marston, and Sharpe | Pendleton | 18 | 3 |
| 23 | Preston | North of England Rail- way Carriage and Iron Co. | Preston | .. | .. |
| 24 | Wigan Rolling Mills | The Wigan Rolling Mills Co., Limited | Wigan | 12 | 3 |
| 25 | White Cross | White Cross Wire and Iron Co., Limited | Warrington | 24 | 3 |
| Total of County | | | | 373 | 86 |

Coal and Iron Ore used in Manufacture.—The total quantity of pig iron made in the furnaces of Lancashire in the year 1872 was 524,041 tons, consuming in its manufacture 911,869 tons of coal and 998,000 tons of ore of all varieties. Since that year the following quantities show approximately the consumption of coal and iron ore in the manufacture of the crude metal:—

| Year. | Pig Iron. | Coal Used. | Iron Ore Used. |
|-------|-----------|------------|----------------|
| | Tons. | Tons. | Tons. |
| 1873 | 529,271 | 1,108,192 | 1,020,000 |
| 1874 | 488,672 | 930,849 | 895,130 |
| 1875 | 558,780 | 956,033 | 1,040,000 |
| 1876 | 552,984 | 991,377 | 1,029,000 |
| 1877 | 684,189 | 1,069,443 | 1,250,400 |
| 1878 | 616,255 | 1,044,114 | 1,143,351 |
| 1879 | 631,343 | 1,167,408 | 1,144,155 |
| 1880 | 750,884 | 1,362,154 | 1,344,093 |

An analysis of the above return for the year 1878 shows the actual quantity of coal used to each ton of pig iron made as averaging 42 cwts., all purposes included; this quantity is the equivalent of the coke, which is alone used in the Lancashire furnaces, where great economy is also secured in the utilization of the waste gases. Of the hematite smelted in Lancashire in the same year, Lancashire furnished 720,000 tons, Cumberland 128,960 tons, foreign ores principally from Spain and Elba 47,881 tons, and 123,209 tons made up of Cornish, Staffordshire red mine, the aluminous ores of Ireland, forge and mill cinder from the malleable iron works, and purple ore from the metal extraction works. The hematite ore was in the proportion of about 32 cwts. and of the other ores employed 7 cwts., in all 39 cwts. nearly of all kinds of ore to each ton of pig iron made, the proportion of coal as already stated being about 42 cwts.

In the following statement the source from whence the ore employed is derived appears, showing approximately the respective quantities:—

| Description of Ore. | 1876. | 1877. | 1878. | 1879. | 1880. |
|-------------------------|-----------|-----------|-----------|-----------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| Hematite (Local) . . . | 862,870 | 1,028,426 | 946,351 | 965,580 | 1,226,163 |
| Irish Ore | 25,000 | 39,804 | 28,000 | 28,460 | 16,093 |
| Foreign Ores | 28,000 | 36,900 | 35,000 | 24,538 | 34,669 |
| Other Ores, &c. | 112,530 | 165,270 | 134,000 | 123,577 | 67,168 |
| Total | 1,029,000 | 1,250,400 | 1,143,351 | 1,144,155 | 1,344,093 |

The hematite includes the produce of both Lancashire and Cumberland, the average produce of which may be taken as from 64 to 66 per cent. of metallic iron. It only remains to be observed that in recent years the quantity of ore employed, of all kinds, has not exceeded 37 cwts. to each ton of pig iron made. In the consumption of coal a marked economy appears in Lancashire; thus while in the year 1873 the average of coal used was 42 cwts., the returns for the years 1879 and 1880 show the average as not exceeding 37 cwts. and 36 cwts. of coal respectively to each ton of pig iron made in those years.

In some districts a far greater quantity is used, notably in those where cold blast iron is made, as in the West Riding of Yorkshire, where, in the year 1878, the average was 56 cwts., and in Scotland where raw uncoked coal is chiefly employed,—though not to such an extent as formerly,—49½ cwts. appear as the average, while in Lancashire as in Cumberland the rich Durham coke being principally employed the diminished consumption appears in the average of 36 cwts. in Lancashire and 39 cwts. in Cumberland to each ton of pig iron made in the year 1880.

CHAPTER VI.

CHESHIRE IRON INDUSTRIES.

Description of the Engineering and Metallurgical Works of the London and North-Western Railway, Crewe.

The Iron and Steel Industries.—The great engineering and metallurgical works of the London and North-Western Railway at Crewe call for a brief notice. They have the reputation of being the largest in the world, comprising steel works in which the Bessemer and Siemens processes for the manufacture of steel are employed on a large scale. The Crewe works were projected in 1843 for the purpose of repairing the locomotives of what was at one time the Grand Junction Railway; some years later machinery for the manufacture of rails was introduced, and when in the year 1857 the amalgamation of the Northern with the North-Eastern division of the system took place, the works at Crewe became the centre of the locomotive and carriage departments of the northern division of the line. In 1864 works were erected for the manufacture of steel by the Bessemer process, and about 1870 an open hearth steel-making plant was added, which has since been largely used in the production of steel for locomotive purposes.

Upwards of 2,000 locomotives have been made at the Crewe works, and as many as 146 in one year. No other works in the world have made and used steel so extensively for railway purposes. The works as a whole cover an area of 27 acres, and employ over 5,000 hands. The Bessemer Steel Converting Works consist of four 5-ton convertors. The pig-iron is first melted in an ordinary cupola, to which the air is supplied by a Roots Blower, whence it is run into one of the converting vessels; the air is supplied to the converting vessels by a pair of horizontal blowing engines of 440 horse-power. The cogging mills, tyre-rolling mills, plate-rolling mills, merchant mills, and mills for rolling spring steel, &c., possess all the modern improvements

and are complete in every mechanical arrangement. The boiler department is a very important branch of the works; here a building 300 feet long and 107 feet wide is devoted to the manufacture of boilers for locomotive and stationary purposes, the material employed being steel.

The great requirements of the London and North-Western Railway may be gathered from the extent of its permanent way, and the rolling stock necessary for the efficient carrying out of its passenger, mineral, and general traffic. It was recently stated by Mr. F. W. Webb, the manager of these works: That if the engines and tenders of the Company were extended in line they would reach a distance of 18 miles; the carriages would occupy 30 miles, and the waggons 180 miles, or nearly the distance between the works at Crewe and London. The resources of the Company are such that on a recent occasion they had turned out a complete engine, ready for the steam, in the short time of 25 hours and a half.

CHAPTER VII.

DERBYSHIRE IRON INDUSTRIES.

Description of Ironstones of the Coal Measures—Analyses and production of Ironstone—Pig Iron Manufacture in Derbyshire and Nottinghamshire—Early History of the Industry—Production and Works in operation—Malleable Iron Works in 1811—Puddling Furnaces and Rolling Mills in recent years and Coal consumed—Coal and Iron Ore used in Pig Iron Manufacture—Districts furnishing Iron Ore.

Ironstones of the Coal Measures.—The southern extension of the Great Midland Coal-field, in the counties of Derby and Nottingham, like the northern division in the West Riding of Yorkshire, is equally rich in its resources of coal measure ironstone; but while the beds of coal throughout the area present more or less regularity in regard to thickness and production, the measures of ironstone, on the other hand, exhibit much irregularity in thickness, frequently thinning out within comparatively short distances. In the northern division of the Great Midland Coal-field, in the West Riding of Yorkshire, the two principal seams of coal, at the top and bottom of the coal-measures, are known as the "Barnsley" and the "Silkstone" seams, between which are distributed, interstratified with less important seams, numerous measures or bands of ironstone, especially the Low Moor beds immediately north of Leeds.

The principal seams of coal in the Wentworth district, near Rotherham, have a thickness, the former varying from 6 feet to 9 feet 6 inches, while the latter is four feet. In Derbyshire the "Barnsley" and "Silkstone" seams are identified respectively as the "Top Hard" and "Black Shale," or Clod Coal, the first-named seam at Staveley, near Chesterfield, being 6 feet, and the latter 5 feet thick. Between these seams of coal in Derbyshire, as in Yorkshire, the more important measures of ironstone occur. In Derbyshire these measures are known as "Rakes," in which the ironstone is distributed in the form of nodules, frequently lying in such thickness as only to be wrought

to advantage by open workings, or, as they are locally called, "Bell Pits." Where such a mode of working is adopted a considerable production of ironstone is secured. The following are the more important ironstone measures in Derbyshire, occurring in descending order between the "Top Hard" and "Black Shale" seams of coal:—

The uppermost of these measures is known as the "*Buff or Cement Rake*" in the Alfreton district, consisting of three bands in a section of 9 feet, and yields 1,800 tons of ironstone per acre. The "*Pinder Park Rake*" at Staveley, also consisting of three bands in a section of 6 feet, yields of ironstone 2,000 tons per acre, while the "*Brown Rake*" at Butterley, in the Alfreton district, yields 2,500 tons per acre.

The "*Black Rake*" measure also in the same district and below the "*Brown Rake*," consisting of five courses or bands, yields 2,000 tons per acre.

The "*Dog Tooth Rake*" next occurs, consisting at Staveley of 5 measures in a section of $8\frac{1}{2}$ feet, and yielding 2,000 tons of ironstone per acre. This important measure, well exposed in a section at Unstone near Dronfield, shows the annexed succession of strata with Gray Shale and ironstones of the open workings in that neighbourhood:—

SUCCESION OF STRATA.

| | Ft. | In. |
|--|-----|-----|
| Dog Tooth measure | 24 | 0 |
| Bearstone or band of cone-in-cone structure | 0 | 9 |
| Shales | 9 | 0 |
| Blueish bind with two courses of ironstone | 4 | 0 |
| Coal | 1 | 2 |
| Hardfloor with <i>Stigmaria</i> abundant, very similar to Ganister | 1 | 0 |
| Fire clay | 4 | 0 |
| Coal | 1 | 9 |

At Butterley this same ironstone is known as "*Wallis's Rake*," south of which it does not prove. Below occurs the "*Nodule Rake*," at Morley Park, yielding 1,600 tons per acre; south of Clay Cross it is known as the "*Dog Tooth Rake*," below which the most productive ironstone measure in the district occurs, the "*Black Shale Rake*" consisting of 16 bands. In the neighbourhood of Chesterfield these bands are divided into top and bottom measures by 12 feet of bind. The Black Shale Rake here yields from 4,000 to 7,000 tons of ironstone per acre. Another measure

below, known as the "*Striped Rake*," at Kirk Hallam, yields 2,500 tons per acre.

The "*Black Shale*" coal occurs some 16 feet below, having a thickness of five feet, below which and before the millstone grit is reached, a series of beds occurs, known as the Ganister series, of considerable thickness. In the upper part of this series, and before the Kilburne coal is reached, are some bands of ironstone, principally worked in the districts of Morley Park and Alfreton; they are known as the "*Green Close Rake*" and the "*Holly Close Rake*," yielding from 1,000 to 1,200 tons per acre. The "*Black*," or "*Kellands Rake*," at Morley Park, and the "*Yew Tree Rake*," yielding respectively 3,000 tons and 1,000 tons per acre.

Below the Kilburne coal which here occurs appear the "*Honeycroft Rake*" and the "*Civilly Rake*," the former consisting of 8 bands, and at Stanton yielding 6,000 tons, the latter of 5 bands, and yielding in the same neighbourhood 4,000 tons of ironstone per acre; while the "*Dale Moor Rake*," a measure of 5 bands occurring below the Furnace Coal (a seam 2 feet 3 inches thick), yields 3,000 tons per acre of ironstone.

The total thickness of the measures above enumerated is 1,600 feet, to which may be added 400 feet for the strata occupying the several seams of coal and ironstone.

Analyses of the Ironstone.—Very complete analyses of the ironstone measures worked in Derbyshire, in the Butterley and Staveley districts, have been published in the Memoirs of the Geological Survey of Great Britain.* The "*Brown Rake*" of Butterley is described as follows, and generally illustrates the character of the other measures of the district:—"Colour, pale brownish-grey, inclined to red in some parts from peroxidation; very thin seams of a bluish shale are irregularly interstratified with the ore; fracture usually rough." A second variety of the same measure is described as "Colour blackish-grey, of various degrees of intensity, in irregular bands parallel to the plane of stratification. The ore containing an abundance of fossil shells incrustated with ochrey peroxide of iron." These ores, and others in the annexed table, in the Butterley district, consisted of equal weights of two ores selected for analysis, and are thus constituted:—

* "Iron Ores of Great Britain," Part I. (out of print), 1856.

RESULTS TABULATED.

| Constituents. | Brown Rake. | Brown Rake. | Black Rake. |
|----------------------------|-------------|-------------|-------------|
| Protoxide of iron | 37·99 | 35·74 | 33·56 |
| Peroxide of iron | 1·04 | 1·26 | 1·66 |
| Protoxide of manganese . . | 1·51 | 1·23 | 0·96 |
| Alumina | 0·41 | 0·47 | 0·73 |
| Lime | 4·53 | 2·94 | 3·02 |
| Magnesia | 3·30 | 2·70 | 2·81 |
| Carbonic acid | 29·92 | 26·74 | 25·63 |
| Phosphoric acid | 0·80 | 0·66 | 0·79 |
| Sulphuric acid | trace. | trace. | trace. |
| Bisulphide of iron | 0·06 | 0·05 | 0·26 |
| Water hygroscopic | 0·74 | 0·68 | 0·74 |
| „ combined | 1·47 | 1·49 | 1·51 |
| Organic matter | 1·42 | 0·76 | 1·57 |
| Insoluble residue | 18·35 | 24·83 | 26·46 |
| | 99·54 | 99·55 | 99·70 |
| INSOLUBLE RESIDUE. | | | |
| Silica | 10·04 | 16·07 | 17·13 |
| Alumina | 5·16 | 6·62 | 7·76 |
| Peroxide of iron | 0·45 | 0·92 | 0·60 |
| Lime | 0·06 | 0·07 | 0·15 |
| Magnesia | 0·07 | 0·26 | 0·25 |
| Potash | 0·55 | 0·66 | 0·74 |
| | 16·33 | 24·60 | 26·53 |
| Metallic iron | 30·60 | 29·32 | 27·61 |

A note appended to these analyses states that in the first a trace of reddish metal, too small to examine, was detected in 1,200 grains of the ore, while as regards the others, distinct traces of lead and copper were found in 600 grains of the one and 700 grains of the other.

The measures wrought in the Stanton district are thus described :—"The Swallow Wood Rake" easily scratched, light drab in colour, one sample a shade darker; all have a rough non-crystalline fracture, and are readily reduced to powder. The sample analysed consisted of equal weights of three of the ores.

The "Honeycroft Rake," of Stanton, examined by Mr. John Spiller, consisting of eight bands of the measure, the sample taken for analysis consisting of equal weights of the several ores.

The "Civilly Rake" and the "Dale Moor Rake," the former

consisting of five measures and the latter a similar number, equal parts of each in weight being taken for analyses. The results given are as follows :—*

RESULTS TABULATED.

| Constituents. | Swallow-wood Rake. | Honeycroft Rake. | Civilly Rake. | Dale Moor Rake. |
|-------------------------|--------------------|------------------|---------------|-----------------|
| Protoxide of iron . . . | 33·72 | 40·01 | 33·31 | 39·55 |
| Peroxide of iron . . . | ... | 1·60 | 1·47 | 2·71 |
| Protoxide of manganese | 1·01 | 1·26 | 2·18 | 1·60 |
| Alumina | 0·67 | 0·58 | 0·95 | 1·14 |
| Lime | 3·99 | 2·78 | 2·32 | 3·32 |
| Magnesia | 5·43 | 2·88 | 2·44 | 2·85 |
| Carbonic acid | 28·64 | 29·72 | 24·83 | 28·63 |
| Phosphoric acid . . . | 0·41 | 0·34 | 0·62 | 1·12 |
| Sulphuric acid | trace. | trace. | trace. | trace. |
| Bisulphide of iron . . | 0·13 | 0·09 | 0·13 | 0·05 |
| Water hygroscopic . . | 0·57 | 0·45 | 0·70 | 0·51 |
| „ combined | 0·87 | 1·12 | 1·87 | 1·24 |
| Organic matter | 0·36 | 1·38 | 1·85 | 1·14 |
| Insoluble residue . . . | 23·55 | 17·84 | 27·42 | 15·80 |
| | 99·35 | 100·05 | 100·09 | 99·56 |
| INSOLUBLE RESIDUE. | | | | |
| Silica | 16·02 | 11·19 | 17·24 | 10·22 |
| Alumina | 5·74 | 5·33 | 7·90 | 4·51 |
| Peroxide of iron . . . | 0·79 | 0·70 | 1·22 | 0·78 |
| Lime | trace. | trace. | | 0·06 |
| Magnesia | 0·06 | 0·17 | 0·27 | 0·03 |
| Potash | 0·47 | 0·34 | 0·49 | 0·48 |
| | 23·08 | 17·73 | 27·12 | 16·08 |
| Iron, total amount . . | 28·79 | 32·73 | 27·79 | 33·20 |

Notes appended to these analyses state that none of the metals, precipitable by sulphuretted hydrogen from the hydrochloric acid solution, were detected in 560 grains of ore of the Swallow Wood Rake ; minute traces of copper were found in the other samples, with the addition of zinc blends in the Dale Moor Rake.

The “Dog Tooth Rake,” extensively worked in the neighbourhood of Staveley, is also reported upon in the “Iron Ores of Great Britain.” The ironstones are described as of the same colour, light brownish-grey, rough in fracture, easily scratched

* “Iron Ores of Great Britain,” Part I., pp. 78, 90, 92, and 94.

by a steel point. Another variety contains a few shells irregularly diffused. The second analysis of the ironstone of the same measure, described as a "Clay ironstone," consisting of two samples, both light brownish-grey in colour, and containing abundance of fossil shells, which in the case of one sample are large and confusedly packed together, though generally lying parallel to the plane of stratification; while in the other they occur as a more irregular deposit made up in part, apparently, of fragments of shells. The hardness of the ore is such that they are not easily scratched by a steel point; fracture compact and irregular, the surface of fracture being influenced by the position of the contained shells. In each analysis the sample consisted of a mixture of the two ores in equal weights:—*

RESULTS TABULATED.

| Constituents. | Dog Tooth Rake. Staveley. | Dog Tooth Rake. Staveley. |
|----------------------------------|------------------------------|------------------------------|
| Protoxide of iron | 38·97 | 28·27 |
| Peroxide of iron | 0·88 | 1·01 |
| Protoxide of manganese | 1·09 | 1·02 |
| Alumina | 0·38 | 0·33 |
| Lime | 1·58 | 13·94 |
| Magnesia | 4·62 | 9·18 |
| Carbonic acid | 30·14 | 37·61 |
| Phosphoric acid | 0·48 | 0·74 |
| Sulphuric acid | trace. | trace. |
| Bisulphide of iron | 0·05 | 0·04 |
| Water hygroscopic | 0·64 | 0·18 |
| „ in combination | 1·02 | 0·73 |
| Organic matter | 0·30 | 0·92 |
| Insoluble Residue | 19·10 | 6·39 |
| | 99·25 | 100·36 |
| INSOLUBLE RESIDUE. | | |
| Silica | 11·90 | 3·55 |
| Alumina | 5·55 | 1·98 |
| Peroxide of iron | 0·59 | 0·41 |
| Lime | 0·04 | trace. |
| Magnesia | 0·20 | 0·09 |
| Potash | 0·67 | 0·16 |
| | 18·95 | 6·19 |
| Metallic iron | 31·34 | 22·98 |

* "Iron Ores of Great Britain," Part I., pp. 86, 88.

A note appended to the first analysis states that a minute trace of copper was found in 630 grains of the ore, and that a minute trace of a white metal, too small to examine, was found in the second in 460 grains of the ore.

Taking an average of the amount of metallic iron contained in the foregoing analyses, 29·15 per cent. will fairly represent the yield of the ironstone of Derbyshire. In the annexed table is given the several ironstone measures above enumerated, the analyst, and percentage of metallic iron in each :—

| Ironstone Measures. | Analyst. | Iron per Cent. |
|--|------------------|----------------|
| Brown Rake (Butterley) . . . | Mr. John Spiller | 30·60 |
| Brown Rake " " " | " | 29·32 |
| Black Rake " " " | " | 27·61 |
| Swallow Wood Rake (Stanton) . . | " | 26·79 |
| Honeycroft Rake " " | " | 32·73 |
| Civilly Rake " " " | " | 27·79 |
| Dale Moor Rake " " " | " | 33·20 |
| Dog Tooth Rake (Staveley) . . . | " | 31·34 |
| Dog Tooth Rake " " " | " | 22·98 |

Production of Ironstone.—The yield of the ironstone measures of Derbyshire has been as follows since the year 1855 :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1855 | 409,500 | 1868 | 368,440 |
| 1856 | 392,400 | 1869 | 352,072 |
| 1857 | 350,000 | 1870 | 384,865 |
| 1858 | 328,950 | 1871 | 492,973 |
| 1859 | 325,500 | 1872 | 307,183 |
| 1860 | 387,500 | 1873 | 365,127 |
| 1861 | 396,520 | 1874 | 239,292 |
| 1862 | 345,450 | 1875 | 218,132 |
| 1863 | 350,500 | 1876 | 199,908 |
| 1864 | 325,600 | 1877 | 206,247 |
| 1865 | 350,000 | 1878 | 175,260 |
| 1866 | 329,500 | 1879 | 146,341 |
| 1867 | 350,000 | 1880 | 150,248 |

The quantity raised in the year 1880 amounted to 150,248 tons, of the average value of 10s. per ton. The quantities raised in 1873 and 1874 (the last detailed returns published), when the average value was 12s. per ton, was obtained in the localities named are given on the next page :—

| District or Mine. | 1873. | 1874. |
|-----------------------|-------------|-------------|
| | Quantities. | Quantities. |
| | Tons. | Tons. |
| Alfreton | 14,854 | ... |
| Blackwell | ... | 300 |
| Butterley | 71,165 | 55,439 |
| Clay Cross | ... | 794 |
| Morley | 13,353 | ... |
| Benishaw | 10,500 | ... |
| Biddings | ... | 13,754 |
| Staveley | 173,664 | 19,511 |
| Sheepbridge | 12,446 | 13,077 |
| Wingerworth | 14,771 | ... |
| West Hallam | 18,917 | 2,417 |
| Sundry pits | 35,457 | 134,000 |
| Total | 365,127 | 239,292 |

Derbyshire (including Nottinghamshire): Pig Iron Manufacture.—The smelting of the ores of iron in Derbyshire with coke dates from about the year 1780; previously numerous small bloomeries existed in various districts, where cast and bar iron were made with charcoal, but these gradually disappeared, and in the year 1788 the last ceased working. The blast at these works was secured by means of a water-wheel. With the use of coal or coke a great change took place in the form and construction of the blast-furnace; hitherto when charcoal was employed, they were square in form, subsequently those erected were circular and of increased height and capacity. With these changes came most opportunely the improvement in the steam-engine by Mr. James Watt, which our ironmasters were not slow in adopting, and thus considerably and in a very short period increased the productive power of their establishments.

In the year 1740 there appear to have been two furnaces in Derbyshire, making charcoal pig iron to the amount of 550 tons or 225 tons per furnace. The first furnace erected in Derbyshire in which coke was exclusively employed in the make of pig iron was at Morley Park in the year 1780, where also a few years later the steam-engine was successfully introduced, in working the blast the original proprietor being a Mr. Francis Hurt; these works were succeeded in the same year by two others situated at Chesterfield, known as the Griffin, or New Brampton, and the Stone Gravel, located on the Chesterfield Canal. The first-named works were projected by Messrs. E. Smith and Co., and the latter by Messrs. Smith and Armitage. The works at Winger-

worth followed by Mr. Joseph Butler, and in 1786 the Staveley Works commenced operations by Messrs. Ward and Low. In 1788 works were established at Dale Abbey by Messrs. English and Co., which a few years later were dismantled and subsequently pulled down. The year 1792 was marked by the establishing of the Butterley and Renishaw Works by Messrs. Outram & Co., at Eckington, and Messrs. Appleby & Co. at Alfreton, and these were succeeded by others; the Alfreton Works by Messrs. Oakes, Edwards, & Co., at one time known as the Somercotes Works, and situated on the banks of the Cromford Canal; the Hasland, or Grass Hill, by Mr. John Brocksop, and in 1799 the Duckmanton (or Adelphi) Works by Messrs. Smith & Co.; the two last-named works have long since been abandoned and dismantled. It was at the Somercotes Works above referred to that Mr. David Mushet introduced his system of making coke on a large scale for the blast furnace, known as the "Close Way," as distinguished from the old method in use at the beginning of the present century, of making a large heap of coals, which being set fire to, were subsequently extinguished by a stream of water when the coking was complete.

The make of charcoal pig iron in Derbyshire in the year 1788 by the only remaining charcoal furnace at Wingerworth, is stated to have been 300 tons. In the same year 7 furnaces producing coke pig iron in Great Britain made 4,200 tons, giving an average per furnace of 600 tons.

Advancing to the inquiry instituted by Dr. MacNab for the year 1796, it appears that the make of pig iron in Derbyshire in that year amounted to 9,656 tons. The following is a list of the works then in operation, with the number of furnaces and the yield of pig iron :—

| Works. | Furnaces. | Pig Iron. |
|---------------------------|-----------|-----------|
| | | Tons. |
| Butterley. | 1 | 936 |
| Chapel | 1 | 1,456 |
| Chesterfield | 1 | 940 |
| Dale Abbey | 1 | 443 |
| Little Brampton | 2 | 1,560 |
| Morley Park | 1 | 728 |
| Renishaw. | 2 | 705 |
| Staveley | 1 | 761 |
| Park | 1 | 853 |
| Wingerworth | 1 | 1,274 |
| Total | 12 | 9,656 |

The total make of pig iron in Great Britain was, according to MacNab's inquiry, 125,079 tons, there being in the same year 124 furnaces in operation.

Farey, in his "Survey of Derbyshire," written in the beginning of the present century, gives a very complete account of the works and furnaces built and in operation in the year 1806, with the individual production of coke pig iron in each works as follows :—

| Works. | FURNACES. | | Pig Iron Made. |
|----------------------------------|-----------|-----------|----------------|
| | Built. | In Blast. | |
| Alfreton | 1 | 1 | Tons. 1,450 |
| Butterley | 2 | 2 | 1,766 |
| Chesterfield (Griffin) | 3 | 2 | 1,700 |
| „ (Stone Gravel) | 2 | 1 | 700 |
| Dale Abbey | 1 | ... | ... |
| Duckmanton | 2 | 1 | 900 |
| Hasland | 1 | 1 | 723 |
| Morley Park | 1 | 1 | 700 |
| Renishaw | 2 | 1 | 975 |
| Staveley | 1 | 1 | 596 |
| Wingerworth | 2 | 1 | 819 |
| Total | 18 | 12 | 10,329 |

The make of coke pig iron in Great Britain in 1806 was 250,406 tons, and of charcoal pig iron 7,800 tons, giving a total production of 258,206 tons of pig iron, which, when compared with the production of the year 1788, shows an increase fourfold.

The Butterley Company about the year 1811, extended their powers of production by the erection of the Codnor Park Works with two blast furnaces, to which a third was added in the year 1825. This Company has long been celebrated for its massive and magnificent castings, examples of which may be seen in the iron bridge over the River Thames at Vauxhall, the colonnade in front of the Opera House in the Haymarket, and in numerous bridges and roofs in the West India and other docks; while north of the Tweed, the bridge at Leith Harbour and others, and lock-gates on the Caledonian Canal may be referred to. The next account of pig iron manufacture in Derbyshire is for the years 1828 and 1880, prepared by Mr. Frederick Finch, who ascertained that the make of 15 furnaces in the year 1828 amounted to 14,088 tons; and in the year 1880, of 18 furnaces, to 17,999

tons, showing an increase in the seven years of 8,961 tons or 28 per cent.

The details of Mr. Finch's returns for Derbyshire appear in the annexed statement, with the number of furnaces in each works, and the make of pig iron :—

| Works. | 1823. | | 1830. | |
|---------------------|-----------|-----------|-----------|-----------|
| | Furnaces. | Pig Iron. | Furnaces. | Pig Iron. |
| | | Tons. | | Tons. |
| Alfreton | 2 | 2,690 | 2 | 2,950 |
| Brampton | 2 | 1,807 | 2 | 1,245 |
| Butterley | 3 | 2,639 | 3 | 3,981 |
| Calow | 1 | ... | 1 | 123 |
| Codnor Park | 2 | 2,096 | 3 | 2,455 |
| Duckmanton | 1 | 1,091 | 1 | 1,446 |
| Morley Park | 1 | 544 | 2 | 1,428 |
| Renishaw | 2 | 2,120 | 2 | 2,810 |
| Staveley | 1 | 1,051 | 2 | 1,561 |
| Total | 15 | 14,038 | 18 | 17,999 |

Advancing to the year 1839, when Mr. David Mushet gave the production of pig iron as 1,248,781 tons, the make of 378 furnaces; the Derbyshire furnaces, of which 14 were in blast, produced 84,872 tons. Again in the years 1840 and 1849, the respective production amounted to 1,396,400 tons and 1,215,350 tons, of which Derbyshire contributed respectively 81,000 tons and 25,750 tons.

The late Mr. Samuel H. Blackwell, in the year 1851 entered very fully into the iron making resources of the United Kingdom, and furnished the following list of works in Derbyshire, the number of furnaces built and in blast, and the production of pig iron, amounting to 60,000 tons :—

| Works. | FURNACES. | | Works. | FURNACES. | |
|--------------------|-----------|-----------|-------------------|-----------|-----------|
| | Built. | In Blast. | | Built. | In Blast. |
| Alfreton | 3 | 2 | Newbold | 1 | 1 |
| Brimington Moor . | 1 | 1 | Renishaw | 2 | 1 |
| Butterley | 3 | 2 | Stanton | 3 | 2 |
| Codnor Park . . . | 2 | 2 | Staveley | 4 | 2 |
| Clay Cross | 2 | 1 | Unstone | 1 | 1 |
| Duckmanton . . . | 1 | 0 | West Hallam . . . | 2 | 1 |
| Morley Park . . . | 2 | 2 | Wingerworth . . . | 2 | 1 |

The average yield of the furnaces at this period was 3,158 tons per annum.

In subsequent years the production of the Derbyshire furnaces appears as follows, and for comparison it will be convenient to give side by side the production of the furnaces in the West Riding of Yorkshire (which occurs within the area of the northern division of the Great Midland Coal-field of Yorkshire, Derbyshire, and Nottinghamshire) :—

| Year. | FURNACES. | | DERBYSHIRE. | W. RIDING OF YORKSHIRE. |
|-------|-----------|-----------|-------------|-------------------------|
| | Built. | In Blast. | Pig Iron. | Pig Iron. |
| | | | Tons. | Tons. |
| 1855 | 33 | 24 | 116,550 | 90,840 |
| 1856 | 33 | 26 | 106,960 | 96,200 |
| 1857 | 34 | 25 | 112,160 | 117,000 |
| 1858 | 34 | 28 | 131,577 | 85,936 |
| 1859 | 36 | 27 | 139,250 | 84,950 |
| 1860 | 37 | 23 | 125,850 | 98,100 |
| 1861 | 37 | 24 | 129,715 | 142,865 |
| 1862 | 44 | 32 | 131,005 | 112,121 |
| 1863 | 42 | 31 | 170,026 | 104,745 |
| 1864 | 43 | 31 | 174,743 | 102,093 |
| 1865 | 41 | 34 | 189,364 | 123,233 |
| 1866 | 42 | 33 | 199,867 | 119,747 |
| 1867 | 43 | 30 | 160,028 | 109,002 |
| 1868 | 42 | 28 | 159,312 | 100,050 |
| 1869 | 43 | 31 | 188,353 | 105,765 |
| 1870 | 43 | 30 | 179,772 | 77,717 |
| 1871 | 46 | 38 | 270,485 | 114,549 |
| 1872 | 46 | 38 | 283,375 | 148,636 |
| 1873 | 47 | 39 | 296,468 | 151,511 |
| 1874 | 50 | 38 | 301,687 | 163,856 |
| 1875 | 51 | 38 | 272,065 | 267,153 |
| 1876 | 54 | 35 | 300,719 | 235,451 |
| 1877 | 53 | 47 | 328,203 | 229,027 |
| 1878 | 55 | 38 | 306,141 | 219,547 |
| 1879 | 53 | 35 | 291,455 | 218,805 |
| 1880 | 54 | 40 | 366,792 | 306,560 |

Taking the average yield of the furnaces in Derbyshire, a steady increase appears; thus, in 1855, the average was 4,856 tons, increased to 5,428 tons in 1860, and 5,570 tons in 1865; again, in 1870, the average was 5,992 tons; in 1875, 7,160 tons, and in 1880, 9,169 tons, comparing favourably with the year 1851, when the average was but 3,158 tons per furnace.

The respective works and firms, with the numbers of furnaces built and in blast in the year 1880, were as follows :—

DERBYSHIRE.

| No. | Name of Works. | Owners. | Furnaces built. | Furnaces in blast. |
|-----------------|-------------------------------------|---|-----------------|--------------------|
| 1 | Alfreton | James Oakes & Co. | 3 | 3 |
| 2 | Butterley, Alfreton | The Butterley Co. | 3 | 1 |
| 3 | Codnor Park | George Dawes | 4 | 2 |
| 4 | Clay Cross | The Clay Cross Co. | 3 | 3 |
| 5 | Denby, Derby | George Dawes | 4 | 3 |
| 6 | Morley Park, Belper | Henry Cathrow Disney | 2 | 0 |
| 7 | Newbold, Chesterfield | Newbold Iron and Coal Co. | 1 | 0 |
| 8 | Renishaw, Eckington | F. R. Appleby & Co. | 3 | 3 |
| 9 | Sheepbridge, Chesterfield | { Sheepbridge Coal and Iron } Co., Limited * | 6 | 5 |
| 10 | Stanton, Nottingham | Stanton Iron Works Co. | 8 | 7 |
| 11 | Staveley, Chesterfield | { Staveley Coal and Iron Co., } Limited | 8 | 7 |
| 12 | West Hallam, Ilkeston | West Hallam Coal and Iron Co. | 2 | 1 |
| 13 | Wingerworth, Chesterfield | Wingerworth Iron Co., Limited | 3 | 3 |
| 14 | Erewash Valley, Ilkestone | Erewash Valley Iron Co. | 4 | 2 |
| Total | | | 54 | 40 |

Mills and Forges.—Farey, in his “Survey of Derbyshire,” published in 1811, states that “Until about forty years ago (1771) small furnaces and bloomeries, heated by charcoal, were alone used, for the making of either cast or bar iron in these districts. At Wingerworth one of these charcoal furnaces continued in some use, blown by means of a water-wheel, until the year 1784; this work, or others on the site of it, having been used for more than 180 years; and at Walley in Bolsover another was used until about the year 1770.” Farey gives a list of 23 localities, where he had observed the slag and remains of old bloomeries and charcoal furnaces, and he further supplements the list by another, of the forges and puddling works where bar iron was made in Derbyshire and adjoining counties as follows :—†

MILLS AND FORGES IN DERBYSHIRE.

Alderwasley, near Wirksworth (two formerly); Francis Hurt.
 Brightside, near Attercliffe, Yorkshire; late Swallow & Co.
 Bugsworth, in Glossop.
 Chapel-en-le-Frith.
 Chapel Mill-town.
 Chesterfield (New Brampton); Ebenezer Smith & Co.
 Clay Mills, near Burton (on the Dove), Staffordshire.
 Codnor Lower Park (now erecting); Butterley Co.
 Killamarah; Joseph Butler.
 Makeney in Duffield (disused).
 Rotherham; Walker & Co.
 Sheffield Town; Samuel Smith & Co.
 ” Shelton & Co.
 Staveley; Ward & Barrow.
 Wichnor, near Burton, Staffordshire; Thornywell & Co.
 Winshall, in Stapenhill (disused).

* Two furnaces building.

† Farey’s “Derbyshire,” 1811, vol. i., p. 403.

Farey* further adds that at "most of the above works they have large rolling and slitting apparatuses, for making plate iron, or bars of different sizes, down to the smallest nail rod; besides which, there are rolling and slitting mills for such purposes in Derbyshire, in All Saints in Derby, and at Burrowash in Ockbrook."

For many years these works have been as follows, with the respective firms, while, from time to time, their powers of production have been increased in the number of puddling furnaces and rolling mills to meet the demands of trade. These works stood as under in the year 1880:—

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-----------|---------------------|--|----------------------------------|---------------------------|-----------------------|
| 1 | Butterley . | The Butterley Co. . | Alfreton . . . | 40 | 7 |
| 2 | Railway (Litchurch) | Eastwood, Swingler & Co. | Derby . . . | 36 | 2 |
| 3 | Victoria . . | Thomas Firth & Sons { Sheepbridge Coal and Iron Co., Limited } | " . . . | 17 | 3 |
| 4 | Whittington . . | | Chesterfield . . | 8 | 2 |
| 5 | Sheepbridge . . | | " . . . | | |
| Total . . | | | | 101 | 14 |

Of the coal consumed in these malleable iron works the quantities in each of the years 1872 and 1873 did not exceed 130,000 tons, including all the purposes where coal was employed. In recent years the following quantities show the consumption, all purposes included:—

| Year. | Coal Used. | Year. | Coal Used. |
|-------|------------|-------|------------|
| | Tons. | | Tons. |
| 1873 | 130,000 | 1877 | 85,000 |
| 1874 | 96,350 | 1878 | 80,487 |
| 1875 | 90,879 | 1879 | 82,466 |
| 1876 | 83,989 | 1880 | 90,178 |

Coal and Iron Ore used in Manufacture.—Taking up inquiries on this subject with the year 1840, when Mr. William Jessop of the Butterley Ironworks made a searching investigation on the subject, it was ascertained that four tons of coal were employed in the manufacture of each ton of pig iron. At this period the average quantity used in Great Britain was $3\frac{1}{2}$ tons of

* "General View of the Agriculture and Minerals of Derbyshire." John Farey, 1811.

coal to each ton of pig iron. The total quantity of coal used in Derbyshire in the year 1840 was 129,000 tons in the manufacture of 31,000 tons of pig iron. It is recorded in the pages of the Royal Coal Commission, that in the year 1869 the quantity did not exceed 3 tons, while in the year 1872 it had further diminished to 58 cwts. of coal to each ton of pig iron. The total quantities of coal and iron ore used in each year since 1872 appears as follows, together with the quantities of pig iron made:—

| Year. | Pig Iron. | Coal Used. | Iron Ore Used. |
|-------|-----------|------------|----------------|
| | Tons. | Tons. | Tons. |
| 1872 | 283,375 | 821,833 | 745,560 |
| 1873 | 296,468 | 865,350 | 775,000 |
| 1874 | 301,687 | 905,951 | 788,500 |
| 1875 | 272,065 | 779,100 | 715,648 |
| 1876 | 300,719 | 777,772 | 774,824 |
| 1877 | 328,203 | 869,368 | 875,573 |
| 1878 | 306,141 | 793,028 | 833,109 |
| 1879 | 291,455 | 765,821 | 799,280 |
| 1880 | 355,603 | 935,913 | 1,027,657 |

Thus, in the year 1872, when the average consumption of coal in Great Britain in the manufacture of iron was 51 cwts. to the ton; the average in the Derbyshire furnaces was about 58 cwts. The increased economy of coal since that date has been considerable, the average in 1877 being 53 cwts., in 1878 but 51½ cwts.; while in the year 1879 it shows an increase, the average being 52½ cwts. In the same way the average coal used throughout the kingdom in iron-making compares favourably in each of the same years, decreasing from 51 cwts. in the year 1872 to 44½ cwts. in the year 1878, and about 43 cwts. in the year 1880, when the total quantity of coal used in the smelting of iron ore in Great Britain was 16,682,629 tons.

The bulk of production of the clay ironstone measures of Derbyshire is smelted in the furnaces of Derbyshire. The ironstone when used in the raw state requires 54 cwts. to each ton of pig iron made, the Derbyshire stone containing from 22·98 to 33·20 per cent, of metallic iron. Large quantities of iron ore are imported into the country to meet the requirements of the ironmaster, principally from Northamptonshire and Lincolnshire, and also from more distant places not separately ascer-

tained. These ores being more rich in metallic iron than the native-mine, are in good request and are advantageously employed.

The iron ores employed in the furnaces in the year 1874 and two preceding years were derived from the following districts :—

| Districts. | 1872. | 1873. | 1874. |
|----------------------------|---------|---------|---------|
| | Tons. | Tons. | Tons. |
| Derbyshire | 317,560 | 320,000 | 305,350 |
| Northamptonshire | 290,500 | 308,700 | 313,924 |
| Lincolnshire | 1,500 | 2,500 | 3,326 |
| Other places | 136,000 | 143,800 | 165,900 |
| Total | 745,560 | 775,000 | 788,500 |

The ores in the last-named quantities are probably derived from Lancashire and Cumberland.

The Derbyshire ironstone, by calcination, may be said generally to lose about one-third of its weight, and it appears that as early as the beginning of the present century, according to Farey,* “that this system of concentrating the metal in the ore was carried out in Derbyshire at Somercotes, and some other works, where the ore was roasted in kilns similar to lime-kilns, with considerable saving of time and of coals, but, it is said, with some increased loss of ore, in being crushed to pieces in passing through the kiln, to what happens in the open heaps, like coke-heaps, in which it is usually wasted; for pieces of roasted iron ore smaller than peas cannot be admitted into the furnace for fear of choking it. The small ore thus sifted out is called *Minion* and is thrown away, or used for making paths in gardens, &c., in which situation it sets hard and firm.”

Returning to the quantities of iron ore supplied to the blast furnaces of Derbyshire, the annexed table gives the districts furnishing the same, and the approximate quantities :—

| Districts. | 1876. | 1877. | 1878. | 1879. | 1880. |
|----------------------------|---------|---------|---------|---------|-----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| Derbyshire | 220,000 | 238,900 | 215,000 | 180,000 | 165,000 |
| Northamptonshire | 494,402 | 514,803 | 521,308 | 507,226 | 696,903 |
| Lincolnshire | 6,508 | 8,760 | 7,783 | 7,434 | 11,826 |
| Other places | 53,914 | 113,110 | 89,018 | 104,620 | 153,928 |
| Total | 774,824 | 875,573 | 833,109 | 799,280 | 1,027,657 |

* Farey's "Derbyshire," vol. i., p. 401.

CHAPTER VIII.

NOTTINGHAMSHIRE AND WARWICKSHIRE IRON INDUSTRIES.

Ironstone of the Coal Measures—Analyses and Production.

Nottinghamshire.—*Production of Ironstone.*—The quantities raised from the ironstone measures in Nottinghamshire have not at any time been considerable; in 1874 there were but 228 tons returned, the value of £186 being given. Since that date the returns have been as follows, with the values in each year:—

| Year. | Quantities. | Value. |
|-------|-------------|--------|
| | Tons. | £ |
| 1875 | 11,750 | 7,543 |
| 1876 | 15,406 | 9,243 |
| 1877 | 16,986 | 10,191 |
| 1878 | 12,250 | 6,125 |
| 1879 | 20,000 | 10,000 |
| 1880 | 2,264 | 1,132 |

These values show an average price per ton, in 1875, of 12*s.* 9*d.*, receding to 12*s.* in 1877, since which date 10*s.* has been the average.

Warwickshire.—*Analysis of Ironstone.*—The argillaceous ores obtained from this coal-field vary like others in the percentage of iron which they contain. The ironstone obtained from the Bedworth district, near Coventry, may be taken as characteristic of the best description of ores of this class. The annexed analysis shows the composition of the Bedworth ironstone above referred to.*

* Mr. S. H. Blackwell's "Iron making Resources of the United Kingdom." Lecture, Society of Arts, 1851, p. 151.

RESULTS TABULATED.

| | |
|--|---------------|
| Carbonate of iron | 79.19 |
| Carbonate of manganese | 1.45 |
| Carbonate of lime | 5.85 |
| Carbonate of magnesia | 6.30 |
| Alumina | 0.50 |
| Silica | 4.85 |
| Phosphoric acid | 0.71 |
| Water, bituminous matter, and loss | 1.15 |
| | <u>100.00</u> |

These argillaceous ores usually contain from 30 to 35 per cent., the better varieties ranging as high as 40 per cent., and are but in little demand when found to contain less than from 25 to 30 per cent. of metallic iron. The above example gives 37.88 per cent.

Production of Ironstone.—But little information on this subject appears before the year 1858. In that year the quantity of ironstone obtained amounted to 29,500 tons, valued at £11,060, giving an average of about 9s. per ton. In subsequent years the argillaceous ore of Warwickshire yielded the following quantities and value :—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1859 | 30,500 | 10,500 | 1870 | 17,500 | 6,125 |
| 1860 | 19,500 | 5,025 | 1871 | 34,075 | 15,570 |
| 1861 | 15,250 | 4,000 | 1872 | 43,375 | 16,246 |
| 1862 | 14,750 | 3,678 | 1873 | 43,837 | 26,302 |
| 1863 | 12,500 | 3,150 | 1874 | 92,214 | 39,528 |
| 1864 | 15,750 | 3,939 | 1875 | 97,456 | 48,720 |
| 1865 | 16,500 | 4,128 | 1876 | 92,838 | 46,419 |
| 1866 | 18,750 | 4,687 | 1877 | 79,965 | 47,979 |
| 1867 | 15,500 | 3,878 | 1878 | 57,222 | 28,611 |
| 1868 | 14,795 | 3,698 | 1879 | 16,214 | 8,107 |
| 1869 | 15,000 | 3,750 | 1880 | 36,972 | 18,486 |

For many years the average price of these ores did not exceed 5s. per ton; about 1870 they rose to 7s., and in 1874 to 10s. per ton, since which date they have shown but little variation.

CHAPTER IX.

SHROPSHIRE IRON INDUSTRIES.

Ironstone of the Coal Measures—Description—Analyses—Production of Ironstone—Yield of Measures and Cost of Working—Pig Iron Manufacture—Early History—Darby's successful application of Coke in the blast furnace at Coalbrook Dale Works—Production of Pig Iron—Malleable Iron Works—Introduction of Rolling Mills at Coalbrook Dale—Coal consumed in Malleable Iron Works—Coal and Iron Ore used in Pig Iron Manufacture—Districts supplying Iron Ore.

Shropshire Ironstone Measures.—The upper part of the strata of this coal-field, it appears, is remarkably wanting in workable seams of coal and ironstone. The first ironstone reached in depth is the "Top" or "Chance Pennystone," occurring with much irregularity, but possessing a strong, general resemblance to the Main Pennystone, which lies about 200 feet deeper.* The table of strata shows the order of occurrence, in the neighbourhood of Donnington Wood, of the coal and ironstone seams :—

| STRATA. | Ft. In. |
|--|---------|
| <i>Chance Pennystone.</i> | |
| Fungous Coal | 3 0 |
| <i>Blackstone.</i> | |
| <i>Brick Measure.</i> | |
| <i>Ballstone.</i> | |
| Top Coal | 5 6 |
| Three-quarter Coal | 2 0 |
| Double Coal | 5 10 |
| <i>Yellow Stone.</i> | |
| Yard Coal | 3 0 |
| <i>Blue Flats.</i> | |
| <i>White Flats.</i> | |
| <i>Main Pennystone.</i> | |
| Sulphur Coal | 7 0 |
| Clunch Coal | 3 0 |
| Two-feet Coal | 2 0 |
| Clod Coal | 2 4 |
| Little Flint Coal | 2 0 |
| <i>Crawstone, Madeley Wood.</i> | |
| <i>Black Flats (position not given).</i> | |

* "Iron Ores of Great Britain," Part IV., p. 241.

One of the most interesting features in the Shropshire ironstone measures is the great variety of fossil remains preserved in the interior of the nodules, exceeding in this respect those of most other districts. The following are the principal ironstone measures, in descending order, with the yield of ironstone per acre.

The Blackstone measure, an ironstone of dull lustre and irregular fracture, but having smooth, shining, and very black surfaces above and below the nodules, is highly valued in the district as one of the materials for making the "best best" cold blast iron; and the measure yields an average of 1,500 tons to the acre. The next measure, the "Brick," is one of secondary importance, existing in the form of flat cakes of a rich brown, with their surfaces very smooth, and of a chocolate colour. Planes of cleavage run very regularly through them, dividing them into brick-like masses, very like the White Flats of South Staffordshire, while a lower measure, the "*Ballstone*," possesses a brownish-grey colour, and when broken gives a conchoidal fracture; like the Blackstone, it is extensively used in the make of the best cold blast iron.

The "Yellowstone" measure occurs below the Ballstone in lumpy, irregular nodules, with white powdery spots, yielding, when well developed, 1,200 tons of ironstone to each acre, and is used alike for both hot and cold blast iron.

The Blue Flats measure is irregular in its occurrence, the nodules are of a brownish-grey colour, and exist interstratified with an indurated clay, yielding 1,600 tons of ironstone to the acre, obtained twenty years ago at a cost of 16s. per ton, whilst the cost of getting, at the same period, did not exceed from 8s. to 11s. per ton.

The White Flats measure.—The ironstone nodules of this measure is of a brownish-grey colour; this measure is rich in fossils, of shells, teeth, spines, crustaceans, and plants. The measure yields about 1,500 tons per acre, but does not command so high a price as those already mentioned.

The Pennystone measure is a remarkable series of nodules, yielding, where well developed, from 2,200 to 2,600 tons per acre. It is found, however, to thin out in its passage to the southern part of the coal-field, but is no longer wrought to any considerable extent. The Pennystone nodules are generally small,

brown, and with an irregular fracture, frequently containing calc spar in thin films filling cracks of contraction, as well as a white powder, which is sometimes sulphate of baryta, at others hydrous silicate of alumina. The lowest measure in the series is the *Crawstone* ironstone, and was formerly worked in the southern part of the coal-field. It was said to make an unusually strong iron, and in appearance has a singular brownish look, rough-grained nodules occurring embedded in a finely-granular sandstone, and is no longer accounted an ore of importance. Mr. W. W. Smyth, referring to these ironstones, remarks:—"The extensive piles in which the ironstone is stacked at the surface, in order to allow it by weathering to be easily freed from shale, allow of an easy inspection of large quantities of it; and perhaps nothing is more striking than the evidence that when in a soft state it has been pierced by burrowing worms, which have left heaps of excretions at the doors of their dwellings. The surface, indeed, of some of the flat nodules, diversified by those little mounds, and by tracks and small markings of many kinds, reminds one strongly of the muddy or silty flats on some of our own shores. The tubular cavities are now filled, sometimes with earthy matter and sometimes with zinc blende, a metallic mineral which in a brilliantly crystalline state often accompanies the vegetable remains."

Analyses of the Ironstone.—The ironstones of Shropshire have been very fully examined and described in the "Memoirs of the Geological Survey of Great Britain," Part IV., in which will be found a description of the coal-field,* followed by a series of analyses made in the Royal School of Mines in Dr. Percy's laboratory, and from which many of the above facts have been taken; the analyses having been made by Mr. John Spiller.

The Black Flats is thus described:—Clay ironstone, easily scratched by a steel point; colour, dark grey; fracture, sub-conchoidal; structure, minutely crystalline. The specimen contains a small quantity of white clay, distributed in the cavities of contraction.

The Blue Flats of Donnington Wood, and the White Flats of the same locality, are somewhat similar in character, the former containing veins of clay irregularly disposed, and the latter permeated in some parts by veins of shale. The results of examination appear in the annexed table:—

* "Iron Ores of Great Britain," Part IV., pp. 242, 245, 246.

RESULTS TABULATED.

| Constituents. | Black Flats. | Blue Flats. | White Flats. |
|-------------------------------------|--------------|-------------|--------------|
| Protoxide of iron | 48·28 | 46·30 | 44·33 |
| Protoxide of manganese | 0·82 | 0·82 | 1·00 |
| Peroxide of iron | | | 1·06 |
| Alumina | 0·67 | 0·48 | 0·92 |
| Lime | 2·26 | 2·30 | 2·86 |
| Magnesia | 1·83 | 2·01 | 1·97 |
| Carbonic acid | 32·98 | 31·68 | 30·92 |
| Phosphoric acid | 0·26 | 0·50 | 0·70 |
| Sulphuric acid | 0·10 | 0·11 | 0·06 |
| Bisulphide of iron | 0·19 | 0·08 | 0·01 |
| Water hygroscopic | 0·24 | 0·28 | 0·35 |
| Water combined | 0·62 | 0·81 | 0·95 |
| Organic matter | 0·62 | 0·62 | 0·38 |
| Ignited insoluble residue | 11·19 | 13·24 | 14·35 |
| | 100·06 | 99·23 | 99·86 |
| IGNITED INSOLUBLE RESIDUE. | | | |
| Silica | 7·36 | 8·23 | 9·90 |
| Alumina | 3·50 | 3·78 | 3·60 |
| Peroxide of iron | 0·53 | 0·69 | 0·56 |
| Lime | 0·08 | trace | 0·12 |
| Magnesia | trace | 0·07 | trace |
| Potash | 0·10 | 0·33 | 0·24 |
| | 11·57 | 13·10 | 14·42 |
| Metallic iron | 37·92 | 36·49 | 35·61 |

It is observed that none of the metals, precipitable by sulphuretted hydrogen from the hydrochloric acid solution, were detected in 820 grains of the Black Flats ore, while a minute trace of a reddish metal, probably copper, though too small to identify, was detected in 480 grains of the White Flats ore.

The Pennystone of Donnington Wood is thus described:—“Nodular clay ironstone, easily scratched by a steel point; colour, pale brownish-grey; fracture, sub-conchoidal; structure, compact. The nodule has veins of contraction, filled with white crystals of sulphate of baryta, and a white pulverulent form of the same substance; side by side appear analyses of the same measure at Madeley Court, and of the Crawstone, at Madeley Wood.”

RESULTS TABULATED.

| Constituents. | Pennystone. Donnington Wool. | Pennystone. Madeley Court. | Crawstone. |
|--|------------------------------------|----------------------------------|------------|
| Protoxide of iron | 45.08 | 44.19 | 51.45 |
| Peroxide of iron | 0.55 | ... | ... |
| Protoxide of manganese | 1.69 | 0.99 | 0.54 |
| Alumina | 0.43 | 0.41 | 0.43 |
| Lime | 2.95 | 1.63 | 2.13 |
| Magnesia | 4.11 | 3.40 | 0.42 |
| Carbonic acid | 34.04 | 32.02 | 33.31 |
| Phosphoric acid | 0.46 | 0.29 | 0.23 |
| Silica soluble in hydrochloric acid | 0.57 | 0.37 | ... |
| Sulphuric acid | trace | 0.06 | ... |
| Bisulphide of iron | 0.48 | 0.43 | 0.02 |
| Water hygroscopic | 0.30 | 0.45 | 0.19 |
| Water combined | 0.72 | 1.31 | 0.54 |
| Organic matter | 0.23 | 0.42 | 0.67 |
| Ignited insoluble residue | 8.32 | 13.50 | 9.60 |
| | 99.93 | 99.47 | 99.53 |
| IGNITED INSOLUBLE RESIDUE. | | | |
| Silica | 5.66 | 7.75 | 6.83 |
| Alumina | 1.96 | 4.64 | 2.42 |
| Peroxide of iron | 0.26 | 0.55 | 0.43 |
| Lime | 0.16 | 0.14 | trace |
| Magnesia | 0.09 | 0.08 | trace |
| Potash | trace | 0.33 | 0.16 |
| | 8.13 | 13.49 | 9.84 |
| Metallic iron | 35.63 | 34.75 | 40.27 |

A minute trace of a white malleable metal, too small in quantity to identify, was found in 300 grains of the ore in the second Pennystone; and a trace of lead was found present in the Crawstone ore in the form of galena.

Of other argillaceous ironstones raised in Shropshire,* the following analyses, by Mr. Edward Riley, of the "Light Clod," and "Dark Clod," obtained at Billingsley Colliery, at Bridgnorth, will show the general character of the ironstone raised in the Forest of Wyre. The smelting of these ironstones, it has been stated, was formerly an industry in this neighbourhood previous to the introduction of railways, and it is said that the iron produced was of very good quality:—

* "Colliery Guardian," 28th November, 1879, p. 858.

RESULTS TABULATED.

| Constituents. | Light Clod. | Dark Clod. |
|--|-------------|------------|
| Silica | 9.99 | 9.87 |
| Carbonate of iron | 73.82 | 74.72 |
| Alumina | 06.02 | 6.20 |
| Carbonate of manganese | 1.13 | 1.16 |
| „ of lime | 1.16 | 3.25 |
| „ of magnesia | 2.21 | 2.15 |
| Sulphate of Baryta | 3.25 | trace |
| Phosphoric acid | 0.21 | 0.30 |
| Combined water | 1.00 | 1.66 |
| Moisture | 0.66 | 0.72 |
| Sulphur | | 0.03 |
| Sulphate of lime | trace | trace |
| Small quantity of potash and organic matter | | |
| | 99.44 | 100.06 |
| Loss by calcination | 36.20 | 28.64 |
| Iron in calcined ore | 48.33 | 50.60 |
| Metallic iron | 35.66 | 36.01 |

Production of Ironstone.—The great bulk of the ironstone employed in the Shropshire furnaces is obtained from the coal measures of the coal-field; these, in the year 1855, were chiefly obtained from Donnington Wood and its vicinity, and from the neighbourhood of Madeley Wood, Madeley Court, &c., and amounted to 865,000 tons. In subsequent years the production of ironstone appears as follows:—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1857 | 325,000 | 1869 | 318,483 |
| 1858 | 150,500 | 1870 | 337,627 |
| 1859 | 197,589 | 1871 | 415,972 |
| 1860 | 165,500 | 1872 | 408,425 |
| 1861 | 223,400 | 1873 | 430,725 |
| 1862 | 225,400 | 1874 | 303,959 |
| 1863 | 247,200 | 1875 | 240,568 |
| 1864 | 454,000 | 1876 | 239,183 |
| 1865 | 273,810 | 1877 | 270,733 |
| 1866 | 285,907 | 1878 | 321,328 |
| 1867 | 250,000 | 1879 | 300,391 |
| 1868 | 278,541 | 1880 | 226,721 |

The value of the ironstone delivered at the pit's bank in the year 1857, was about 5s. per ton on the average; in the year 1866, according to a writer in the *Colliery Guardian*, the

average cost of extracting in the Blue Flat ironstone varied, according to circumstances, from 7*s.* to 10*s.* per ton; during the same year the White Flats ironstone cost from 9*s.* to 11*s.* per ton; and the Pennystone, from 6*s.* to 9*s.* per ton. During the years from 1872 to 1876, the average price at the pit's bank varied from 10*s.* to 12*s.*, while during the past few years the average price may be taken at 10*s.* per ton. The following details of individual districts show the production in the years named :—

| Districts. | 1875. | 1874. | 1873. |
|-------------------------|---------|---------|---------|
| | Tons. | Tons. | Tons. |
| Haycop | ... | 620 | ... |
| Ketley | 7,673 | 9,322 | 9,014 |
| Lilleshall | 92,160 | 87,558 | 102,530 |
| Madeley Court | 17,752 | 18,335 | 21,414 |
| Madeley Wood | ... | 29,902 | ... |
| Quinta | ... | 20 | ... |
| Sandback | ... | 960 | ... |
| Wombridge | 10,556 | 7,242 | 8,234 |
| Dawley | ... | ... | 35,679 |
| Coalbrookdale | ... | ... | 23,026 |
| Old Park | ... | ... | 10,828 |
| Pack Moor | 9,000 | ... | ... |
| Copple, &c. | 120 | ... | ... |
| Calcotts, &c. | 3,307 | ... | ... |
| Sundry mines | 100,000 | 150,000 | 220,000 |
| Total | 240,568 | 303,959 | 430,725 |

Yield of Ironstone and Cost of Production.—The principal ironstone measures worked in Shropshire in 1836, according to Thomas Smith,* were as follows, showing the thickness and cost per ton of working, and the yield of ironstone per square yard :—

| Ironstone Measures. | Thickness. | Yield per Yard. | Cost of Getting per Ton. |
|----------------------------|------------|-----------------|--------------------------|
| | Yds. Ft. | Tons. Cwts. | £ s. d. |
| Pennystone | 2 0 | 0 4 | 0 6 3 |
| Black ironstone | 1 1 | 0 8 | 0 2 7 |
| Brick measure | 5 1 | 0 6 | 0 3 7 |
| Ball stone | 3 0 | 0 5 | 0 4 4 |
| Yellow ironstone | 3 0 | 0 5 | 0 2 0 |
| Blue Flats | 2 0 | 0 6 | 0 4 2 |
| White Flats | 2 0 | 0 4 | 0 6 7 |
| Penny ironstone | 8 0 | 1 4 | 0 5 0 |
| Total | 26 2 | 3 2 | 1 14 6 |

* "Miner's Guide," 1836, p. 128.

The average yield per square yard of the eight measures giving 62 cwt. ; the cost of getting each ton of ironstone being 8s. 1½d., this including dead work, 2s. 6d., and royalty, 1s. per ton. The total produce per acre of the measures giving 13,794 tons of ironstone; the royalty, 1s. per ton; and per acre, £689 14s.; the average getting of each man daily amounting to 24 cwt. 3 qrs.; and in the week of five days, 6 tons 3 cwt. 2 qrs.

Fig Iron Manufacture.—The early history of this industry is intimately associated with Shropshire and especially with the Coalbrookdale Ironworks. When, in the beginning of the last century, the exhaustion of our forests and woodlands was imminent, occasioned by the demand for the necessary charcoal fuel, attention was directed to the useful application of coal in the blast furnace. The difficulties, however, were considerable, and it was not until Mr. Abraham Darby, between the years 1730 and 1735, at the Coalbrookdale Works, successfully solved the problem, that the use of coal, previously coked, came into use in the reduction of the ores of iron in the blast furnace.

The new era opened out by Darby's success in the application of coke renders this a fitting place to give the following account of his early attempts :—*

"Young Abraham Darby entered upon the management of the Coalbrookdale Ironworks about 1730. As the supply of charcoal was fast failing, Abraham Darby attempted to smelt with a mixture of raw coal and charcoal, but did not succeed. Between 1730 and 1735 he determined to treat pit coal as his charcoal burners treated wood. He built a fire-proof hearth in the open air, piled upon it a circular mound of coal, and covered it with clay and cinders, leaving access to just sufficient air to maintain slow combustion. Having thus made a good stock of coke, he proceeded to experiment upon it as a substitute for charcoal. He himself watched the filling of his furnace during six days and nights, having no regular sleep, and taking his meals at the furnace top. On the sixth evening, after many disappointments, the experiment succeeded, and the iron ran out well. He then fell asleep in the bridge-house at the top of his old-fashioned furnace so soundly that his men could not wake him, and carried him to his house a quarter of a mile distant."

* Percy's Metallurgy, "Iron and Steel," p. 888.

It may also be mentioned that it was at the above-named works that Mr. Abraham Darby's father had previously introduced the art of casting iron, and that at a later period the first iron bridge constructed in this country was successfully carried out, and is that which at the present time spans the river Severn at the thriving town of Ironbridge.

Darby, in the year 1785, having succeeded in making pig iron with coke, experienced a new difficulty, that of securing blast of sufficient pressure to ensure the complete utilisation and combustion of the hard dense coke in the furnace, and it was not until a quarter of a century later that his difficulty was overcome by the introduction of powerful blowing machinery, in which Smeaton led the way, followed by Watt and others. In the year 1740, when the total production of pig iron in England and Wales was but 17,350 tons, the yield of 59 furnaces, that of the six furnaces then in operation in Shropshire was 2,100 tons, 12 per cent. of all made; the average yield of each furnace being 350 tons. In the year 1754 the ironworks at Horsehay were established by Mr. Abraham Darby, of Coalbrookdale, already referred to, and two years later the first furnace was blown in. It is recorded that from 20 to 22 tons of coke pig iron were made weekly, and such was its superior quality that it met with a ready sale. Advancing to the year 1788, when the total production of pig iron was 61,800 tons, of which 13,100 tons was charcoal pig, and 48,200 tons coke pig, the make of the Shropshire furnaces was as follows:—

| Description. | Furnaces. | Pig Iron. |
|-------------------------|-----------|-----------|
| | Nos. | Tons. |
| Coke iron | 21 | 23,100 |
| Charcoal iron | 3 | 1,800 |
| Total | 24 | 24,900 |

The fact of the Shropshire furnaces at this period contributing upwards of 40 per cent. of the iron made in England and Wales shows the importance of the district as a seat of iron manufacture.

Towards the close of the last century additional light was thrown on the progress of the iron trade of the country by the

inquiries of a Committee of the House of Commons, presided over by William Manning, Esq., M.P. From the investigations of this committee, and the authority of Dr. H. G. Macnab, who represented the iron trade, we learn that in the year 1796 the production of pig iron in Great Britain was 125,079 tons, of which Shropshire contributed 32,969 tons, nearly 25 per cent. of all made at this period. In the annexed table appear the works in operation in 1796 in Shropshire, the number of furnaces, and their production :—

| Works. | Number of Furnaces. | Pig Iron Made. | Average per Furnace. |
|---------------------------|------------------------|----------------|-------------------------|
| | | Tons. | Tons. |
| Benthall | 1 | 1,334 | 1,334 |
| Brosley | 1 | 1,076 | 1,076 |
| Coalbrookdale | 3 | 2,660 | 886 |
| Donnington Wood | 2 | 3,323 | 1,661 |
| Horsehay | 1 | 1,458 | 1,458 |
| Jackfield | 2 | 1,820 | 910 |
| Ketley | 3 | 5,069 | 1,689 |
| Light Moor | 3 | 3,499 | 1,166 |
| Madeley Wood | 1 | 1,856 | 1,856 |
| Old Park | 3 | 5,952 | 1,984 |
| Snedshill | 2 | 3,367 | 1,683 |
| Wiley | 1 | 1,555 | 1,555 |
| Total | 23 | 32,969 | 1,433 |

Thus while in the year 1740 the average make per furnace was 294 tons, it increased in the year 1796 to 1,433 tons, from which fact it will be seen that the furnaces will have been reconstructed and their capacity greatly increased. In 1796, when the production of the Shropshire furnaces was 32,969 tons, the only other iron making districts in Great Britain exceeding this was South Wales, producing 34,101 tons ; Scotland following with 15,186 tons ; South Staffordshire with 13,210 tons ; the West Riding of Yorkshire with 10,898 tons ; Derbyshire with 9,656 tons ; North Staffordshire with 1,959 tons ; and the charcoal furnaces of Sussex with 173 tons. The beginning of the present century was marked by the establishment of several new works, an increase in number and capacity of the furnaces and production of pig iron. Thus in the year 1806 we have the subjoined details of works, furnaces built, and in blast, and make of pig iron in Shropshire, showing an increase of 21,997 tons in a period of ten years, equal to 66 per cent. :—

| Works. | FURNACES. | | Pig Iron Made. |
|-----------------------|-----------|-----------|----------------|
| | Built. | In Blast. | |
| | Nos. | Nos. | Tons. |
| Barnets Leasow . . . | 2 | 1 | 574 |
| Benthall | 1 | 1 | 1,294 |
| Billingsley | 2 | 0 | ... |
| Broseley | 1 | 1 | 1,450 |
| Calcott | 5 | 1 | 2,269 |
| Clee Hill | 1 | 1 | 303 |
| Coalbrookdale . . . | 2 | 2 | 2,962 |
| Cornbrook | 1 | 1 | 292 |
| Donnington Wood . . | 3 | 2 | 3,400 |
| Horsehay | 2 | 2 | 3,834 |
| Light Moor | 3 | 3 | 5,601 |
| Ketley | 4 | 2 | 7,510 |
| Madeley Wood | 2 | 2 | 2,951 |
| New Hadley | 2 | 2 | 3,612 |
| Old Park | 4 | 4 | 8,359 |
| Queenswood | 1 | 1 | 2,605 |
| Snedshill | 3 | 2 | 3,950 |
| Willey | 1 | 0 | ... |
| Wrockwardine | 2 | 2 | 4,000 |
| Total | 42 | 30 | 54,966 |

The total production of pig iron in Great Britain, in the same year, was 243,851 tons, distributed as follows :—

| Districts. | FURNACES. | | | Pig Iron Made. |
|----------------------|-----------|-----------|------|----------------|
| | Built. | In Blast. | Out. | |
| | Nos. | Nos. | Nos. | Tons. |
| England | 140 | 105 | 35 | 149,163 |
| Wales, North | 4 | 3 | 1 | 2,981 |
| „ South | 45 | 35 | 10 | 68,867 |
| Scotland | 27 | 18 | 9 | 22,840 |
| Total | 216 | 161 | 55 | 243,851 |

Shropshire at this period contributed upwards of 20 per cent. of the iron produced in the kingdom, while the average make of her blast furnaces had increased from 1,433 tons in the year 1796 to 1,832 tons in the year 1806.

Advancing to the years 1831—32, when an inquiry was conducted for the Government by Mr. F. Finch, it was ascertained by that gentleman that in the years 1823 and 1830 the furnaces in operation, and the make of pig iron in Shropshire, were as follows :—

| Works. | 1823. | | 1830. | |
|----------------------|------------------------|-------------------|------------------------|-------------------|
| | Number of Furnaces. | Pig Iron Made. | Number of Furnaces. | Pig Iron Made. |
| | | Tons. | | Tons. |
| Broseley | 2 | ... | 2 | 270 |
| Barnets Leasow . . . | 2 | 2,755 | 2 | 1,316 |
| Benthall | 1 | ... | 1 | ... |
| Calcotts | 2 | 1,833 | 2 | ... |
| Coalbrookdale . . . | 2 | ... | 2 | ... |
| Dawley Castle . . . | 2 | 4,925 | 2 | 4,312 |
| Donnington | 3* | 8,074 | 5 | 15,110 |
| Horsehay | 3 | 4,854 | 3 | 6,833 |
| Hadley | 2 | 2,080 | 2 | ... |
| Ketley | 3 | 4,984 | 3 | 5,763 |
| Light Moor | 3 | 6,052 | 3 | 6,194 |
| Madeley Wood . . . | 3 | 2,475 | 3 | 3,471 |
| Old Park | 4 | 6,900 | 4 | 15,300 |
| Snedshill | 2 | 2,786 | 2 | 317 |
| Wombridge | 2 | 5,084 | 3 | 7,134 |
| Wrockwardine . . . | 2 | 5,121 | 2 | ... |
| Stirchley | ... | ... | 4† | ... |
| Lawley | ... | ... | 1 | 3,073 |
| Langley | ... | ... | 2 | 4,325 |
| Total | 38 | 57,923 | 48 | 73,418 |

The aggregate production of pig iron in the year 1823, in the works of Great Britain, was 454,866 tons, increased in the year 1830 to 678,417 tons, equal to an increase of 50 per cent., while in the works of Shropshire the increase between the same years was 15,495 tons, or 26 per cent.

It was between the above-named years (in 1828) that the Hot Blast, the invention of Mr. James B. Neilson, was introduced; and returns in subsequent years show the important influence exercised in increased production, more especially in Scotland. Later the system was adopted in England and Wales, though but partially in some districts, as for example the West Riding of Yorkshire, North Staffordshire, South Wales, and in this district, where some of the works still employ cold blast in the furnace, producing iron of a superior quality, which is in great request.

The next return is for the year 1839, on the authority of

* Two furnaces were built at Donnington in 1828, in the place of the two at Wrockwardine which were blown out.

† The quantity made in 1830 is included in the Old Park return.

Mr. Robert Mashet,* who states that of the 84 furnaces built in Shropshire at that date 29 were in blast, and produced 80,940 tons, giving an average yield to each furnace of 2,791 tons. Again, in 1840 we find, from Mr. William Jessop's inquiries, that of the total furnaces built 24 were active, and produced 82,750 tons of pig iron, consuming in its manufacture 409,000 tons of coal, the average yield per furnace being 3,448 tons of iron, with an average of nearly 5 tons of coal to each ton of iron made.

The returns a few years later show a falling off not only in Shropshire, but in nearly all the iron-making districts of Great Britain—Northumberland and North Staffordshire excepted. Thus in 1848 the production had fallen to 1,215,850 tons, compared with 1,896,400 tons in the year 1840; the make of the Shropshire furnaces being respectively, in each of the same years, 76,200 tons and 82,750 tons. This falling off was due to depression of trade, which was general throughout the industries of the country, and continued from 1840 to 1845, when a reaction set in, due to the extension of the railway system, leading to increased demand for iron of all kinds and more remunerative prices.

The results of these changes appear in the returns for the year 1847, when of the 628 furnaces built in Great Britain 438 were in operation, and produced 1,999,608 tons of pig iron, of which the 28 furnaces in blast in Shropshire, out of a total of 84 built, yielded 88,400 tons, or an average of 3,157 tons per furnace.

The iron industries of the country since 1847 have bounded forward at a rapid pace, to meet the many requirements to which iron is now so universally applied; not only in the structural arrangements of our public buildings, railway, and naval engineering works, but also the many other works of national importance to which it is now so generally adapted.

In the year 1852 Mr. Braithwaite Poole, in his "Statistics of Commerce," gives the production of pig iron in Shropshire as 120,000 tons, giving an average of 4,444 tons for each of the 27 furnaces in blast, compared with 3,157 tons per furnace in the year 1847. In 1852 the same authority gives the total production of pig iron in Great Britain as 2,701,000 tons, the make of 497 furnaces then in operation, out of a total of 655 furnaces built.

* "Papers on Iron and Steel," p. 421.

Advancing to the year 1854, of the 34 furnaces erected in Shropshire 28 were in blast, the production of pig iron amounting to 124,800 tons, being an average of 4,457 tons per furnace. In the annexed table will be found the number of furnaces built, in blast, and the make of pig iron in Shropshire in each year since 1855 :—

| Year. | FURNACES. | | Pig Iron Made. | Year. | FURNACES. | | Pig Iron Made. |
|-------|-----------|-----------|----------------|-------|-----------|-----------|----------------|
| | Built. | In Blast. | | | Built. | In Blast. | |
| | Nos. | Nos. | Tons. | | Nos. | Nos. | Tons. |
| 1855 | 34 | 26 | 121,680 | 1868 | 29 | 24 | 145,159 |
| 1856 | 35 | 27 | 109,722 | 1869 | 29 | 23 | 197,443 |
| 1857 | 31 | 26 | 117,141 | 1870 | 29 | 22 | 112,300 |
| 1858 | 32 | 25 | 101,016 | 1871 | 25 | 19 | 129,467 |
| 1859 | 37 | 30 | 149,480 | 1872 | 29 | 22 | 133,046 |
| 1860 | 32 | 26 | 145,200 | 1873 | 29 | 21 | 135,149 |
| 1861 | 31 | 22½ | 140,791 | 1874 | 28 | 20 | 126,055 |
| 1862 | 31 | 23 | 125,981 | 1875 | 26 | 20 | 120,996 |
| 1863 | 31 | 22 | 135,557 | 1876 | 25 | 16 | 106,711 |
| 1864 | 30 | 22¾ | 130,666 | 1877 | 23 | 14 | 102,180 |
| 1865 | 29 | 23 | 117,343 | 1878 | 28 | 11 | 80,965 |
| 1866 | 29 | 23 | 121,161 | 1879 | 23 | 7 | 60,790 |
| 1867 | 29 | 22 | 123,604 | 1880 | 24 | 12 | 88,338 |

During the past few years Shropshire shows a decrease in this branch of industry. Of the ironworks it may be remarked that the Lilleshall and Haybridge companies' works, and those at Madeley Court, are the most recently established. These works are of considerable magnitude, the first named, at Prior's Lee, having four furnaces, and the Lodge Wood works five furnaces, making cold blast pig iron. These works are situated near Shiftnall, and possess, in addition to the furnaces, extensive foundries and engineering establishments, where locomotives for colliery purposes are made on a large scale. The works of the Haybridge Company are also situated near Shiftnall, while those of Madeley Court are situated near Ironbridge.

The year of greatest production appears to have been in 1869, when of the 29 furnaces in the Shropshire works, the 23 in blast produced 197,443 tons, compared with 88,338 tons in 1880, when of the 24 furnaces in the district but 12 were in operation.

The following table shows the names of the works, firms, and furnaces built and in operation during the year 1880 in Shropshire :—

| Works. | Owners. | FURNACES. | |
|------------------------------|--|-----------|-----------|
| | | Built. | In Blast. |
| Hinkshay, Shiffnall . . . | Haybridge Iron Co., Lim. | Nos. 2 | Nos. 0 |
| Light Moor and Dawley Castle | { Coalbrookdale Iron Co., } Limited . . . } | 4 | 1 |
| *Ketley, Wellington . . . | Ketley Co. | | |
| Lodge Wood, Shiffnall . . . | Lilleshall Co. | 5 | 3 |
| Prior's Lee, Shiffnall . . . | " | 4 | 3 |
| Madeley Wood, Ironbridge . . | Madeley Wood Co. . . . | 3 | 3 |
| Madeley Court | William Orme Foster . . | 3 | 2† |
| Old Park | Edward Cheney | 3 | 0 |
| | Total | 24 | 12 |

Malleable Ironworks, Mills, and Forges.—The earliest works established in Shropshire were those of the Coalbrookdale Iron Company, projected about the year 1753. They are situated at Horshay, near Wellington, and comprise forges and rolling mills. When, in 1783 Mr. Henry Cort introduced his system of rolling iron, the works were considerably enlarged and rolling mills erected. The site of the Dale was originally selected for the erection of an iron foundry, on account of the facilities it afforded for water power by the rapid descent of its brook into the river Severn. Water power has, however, long since been almost entirely superseded by steam in these old-established works, which are said to have been in the family of the present proprietors for nearly 180 years, during which period they have been greatly extended. The locality is described as a picturesque and once sequestered valley, now busy with the life and labour of those employed in the foundries and workshops of the company, the latter buildings occupying the larger portion of the bottom of the Dale, while the slopes of the hills are occupied by coppice and field, and by the houses and gardens of the workmen employed. A local authority in 1856 estimated the annual production of finished iron at these works at 15,000 tons, consisting of bars of all sizes and sections.

It was at Coalbrookdale, it appears, that Cort first systematically conducted the processes of puddling and of drawing out

* Works recently dismantled.

† One furnace a part of the year only.

the puddled balls through grooved rolls. Dr. Percy, in referring to Cort's claim, says : " With respect to the invention of grooved rolls, it has been maintained that Cort's claim is invalidated by the old patent granted to John Payne in 1728," and follows with an extract from the specification relating to grooved rolls : " The improvement in the manufacture of iron consists in putting certain ingredients into fusion with pig or sow-iron ; videlecit, the ashes of wood and other vegetables, all kinds of glass and sandever, common salt, argile, kelp, and potash, slegg or cinders from iron furnaces and forges ; proportionable parts of the said ingredients being put into fusion, or melted with pig, sow, or other brittle iron, which will make the like change as charcoal does in the fire called the finery in common forges, and will render the same into a state of malleability, as to bear the stroke of the hammer, to draw it into barrs or other forms at the pleasure of the workman, and those or other barrs being treated in the same melted ingredients in a long hott arch or cavern, as hereafter is described ; and those or other barrs are to pass between two large metal rollers (which have proper notches or furrows upon their surfass), by the force of my engine hereafter described, or other power, into such shapes and forms as shall be required." The engine consisted of a large vane wheel, hung in a frame in the side of a building, the pressure of the in-current of air being directed upon the extremities of the vanes.

Dr. Percy further adds, " That something very like grooved rolls is here described cannot be denied ; but there is not, so far as I am aware, the slightest evidence to show that Payne ever attempted to carry out his scheme into practice. Indeed, the proposal to work the notched rolls by such a wheel as is specified, pretty clearly shows that Payne was not aware of the power needed to drive any machinery equivalent to puddle rolls."

Following the establishing of the Coalbrookdale works, about the year 1783, those at Ketley are amongst the oldest in the county, indeed, it might be said in the kingdom, and it was here the first iron railway was laid down towards the close of the last century ; the Ketley Works are well known in the commercial world for the high character of their manufacture, bars, hoops,

* Metallurgy, " Iron and Steel," p. 635.

and wire rods. Recently, however, these old-established works were closed, and in 1879 dismantled.

The Snedshill and the Coalbrookdale Iron Companies are generally regarded as the largest manufacturers of malleable iron in Shropshire, possessing considerable resources for manufacturing and producing plates, wire rods, and hoops of the best varieties. The first named works were originally founded by Messrs. Samuel Horton and William Simms, and at the present time exist under the management of the Snedshill Bar-iron Company. The annexed list, the latest published (1880), shows the works existing, their owners, together with the number of mills and forges in operation :—

| Works. | Owners. | Situation. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|----------------------------|---------------------------------|------------|---------------------------|-----------------------|
| Castle, Hadley . | Messrs. Nettlefolds | Wellington | 27 | 3 |
| Horsehay . . . | Coalbrookdale Iron Co. . . . | " | 36 | 5 |
| Stirchley . . . | Haybridge Iron Co. | " | 14 | 2 |
| Eagle, Hollings- wood } | The Eagle Iron Works Co., Lim. | " | 18 | 3 |
| Trench, Hadley . | The Shropshire Iron Co., Lim. . | " | 32 | 3 |
| Shropshire . . . | " | " | | |
| Wombridge . . . | Wombridge Iron Co., Limited . | " | 10 | 3 |
| Haybridge . . . | Haybridge Iron Works Co., Lim. | " | 10 | 1 |
| Old Park* . . . | Old Park Iron Co. | Shifnal | .. | .. |
| Snedshill . . . | Snedshill Iron Co. | " | 36 | 4 |
| Total of County . . . | | | 183 | 24 |

The pig iron employed in these works is chiefly furnished by the blast furnaces of the district, those of Snedshill being supplied by the Lilleshall Company's furnaces in Shropshire, who also supply the Shelton Bar-iron Company's works, situated at Hanley, North Staffordshire; while the Coalbrookdale Company's works at Horsehay are supplied from their own Light Moor and Dawley Castle furnaces.

The Haybridge Iron Company, a few years since, added a new feature to the manufacturing industries of the county by the introduction of suitable machinery for the manufacture of nails, an industry previously carried on at these works by the aid of hand labour.

The coal employed in the malleable ironworks of Shropshire in the years 1872 and 1873 amounted to 160,000 tons in each year, giving an average consumption of coal to each puddling

* Works standing.

furnace of 900 tons, and, taking the quantity of coal necessary to convert the pig into finished iron of various forms at 50 cwt., there would appear to have been about 64,000 tons of finished iron produced in the works of Shropshire in each of the above years. In recent years the consumption of coal in these works has been approximately ascertained as follows :—

| Year. | Coal. | Year. | Coal. |
|-------|---------|-------|---------|
| | Tons. | | Tons. |
| 1872 | 160,000 | 1876 | 138,000 |
| 1873 | 160,000 | 1877 | 134,500 |
| 1874 | 154,000 | 1878 | 139,780 |
| 1875 | 146,000 | 1879 | 141,329 |

The quantity consumed in these works in 1880 amounted to 158,992 tons.

Coal and Iron-ore used in Manufacture.—Mr. David Mushet, in his papers on “Iron and Steel,” states that four tons of coke was the quantity of fuel employed in the year 1810 for each ton of pig iron made in Great Britain. In Shropshire it was ascertained, about the year 1840, by Mr. William Jessop, of the Butterley Ironworks, that the quantity of pig iron made was 82,750 tons, consuming in its manufacture 409,000 tons of coal, or nearly five tons of coal to each ton of pig iron made. Mr. William Jessop further ascertained that the total quantity of pig iron made in Great Britain the same year amounted to 1,896,400 tons, consuming 4,877,000 tons of coal, or an average of $3\frac{1}{2}$ tons of coal to each ton of pig iron manufactured.

The inquiry instituted by the Royal Coal Commission shows that in the year 1869 the quantity of coal employed in making a ton of pig iron in Great Britain did not exceed three tons, and subsequent inquiries, instituted by the Mining Record Office, show that in Shropshire, in the years 1871 and 1872, it amounted to the same average quantity, while taking the iron-making districts of the kingdom in the same year the average did not exceed 51 cwts. of coal to each ton of pig iron made.

In the year 1872 and following years, the production of pig iron in Shropshire, together with the quantities of coal and ore used in its manufacture, will be found in the annexed statement :—

| Year. | Pig Iron. | Coal Used. | Ore Used. | AVERAGE PER TON. | |
|-------|-----------|------------|-----------|------------------|-------|
| | | | | Coal. | Ore. |
| | Tons. | Tons. | Tons. | Cwts. | Cwts. |
| 1872 | 133,046 | 398,197 | 385,000 | 60 | 57 |
| 1873 | 135,149 | 407,876 | 390,000 | 60 | 58 |
| 1874 | 126,055 | 394,094 | 364,500 | 62 | 57 |
| 1875 | 120,996 | 370,000 | 350,000 | 61 | 57 |
| 1876 | 106,711 | 334,738 | 307,500 | 63 | 57 |
| 1877 | 102,180 | 276,241 | 293,000 | 54 | 57½ |
| 1878 | 80,965 | 222,876 | 231,060 | 55 | 57 |
| 1879 | 60,790 | 156,507 | 153,198 | 51 | 50½ |
| 1880 | 88,338 | 249,254 | 218,650 | 56 | 49½ |

The Shropshire ore yields an average of 36 per cent. of metallic iron, other ores used to a limited extent giving a higher yield; North Staffordshire ores, 36½ per cent.; Northampton ores, 40 per cent.; while ores used in small quantities, chiefly hematite, yield probably not less than 50 per cent. of metallic iron. The ores used in Shropshire in each of the following years were obtained from the districts named:—

| Districts. | 1873. | 1875. | 1879. | 1880. |
|-------------------------|---------|---------|---------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| Shropshire | 306,500 | 268,000 | 136,839 | } 218,650 |
| North Staffordshire . . | 6,500 | 7,200 | 6,380 | |
| Northamptonshire . . | 50,000 | 40,300 | 3,890 | |
| Other districts | 27,000 | 34,500 | 7,089 | |
| Total | 390,000 | 350,000 | 153,198 | 218,650 |

It has not been found possible to determine the respective quantities of ore furnished by various districts in 1880 as in previous years; it is, however, known that of the 218,650 tons of ore reduced in the blast furnaces of Shropshire, the approximate quantity of ironstone supplied by the district amounted to not less than 200,000 tons.

CHAPTER X.

NORTH STAFFORDSHIRE IRON INDUSTRIES.

Description and Analyses of the Ironstones of the Coal Measures—Churnet Valley Ore and Analysis—Production and Distribution by Canal and Railway—Pig Iron Manufacture—Early History—Apedale and Silverdale Iron Works—Furnaces in Blast and Production of Pig Iron—Malleable Iron Works and Coal used—List of Works in 1880—Coal and Iron Ore used in Manufacture—Districts furnishing Ore.

Description and Analyses of the Ores.—The ironstones of North Staffordshire are very fully described in the "Iron Ores of Great Britain," Part IV., by Prof. W. W. Smyth, F.R.S., and complete analyses are published by Dr. Percy, F.R.S., made in his laboratory in the Royal School of Mines, in the same Memoir. The more important are the following :—

The "Red Shag," Shelton Colliery, Hanley and Apedale, Newcastle.—Clay-iron ore ; colour, dark brown to black ; structure, compact, with reddish brown flattened impressions of fossil shells.

"Gutter Mine," Shelton Colliery, Hanley.—This ore is "composed of alternate layers of clay, ironstone, coaly matter and fossil shells ; the clay-ironstone predominating towards the middle of the specimen." It readily cleaves in the direction of the plane of stratification, the shells thus displayed bearing the evidence of compression in a direction perpendicular to the plane of cleavage. A small quantity of zinc blende was found in the ore.

"Red Mine," Apedale, is a clay-iron ore, consisting of thin layers ; colour, various shades of dark brown ; structure, compact. Minute crystals of galena and zinc blende occur, sparingly diffused through the ore.

Analyses of these ores and the "Bassy Mine" appear in the annexed table. That of the "Gutter Mine" by Mr. John Spiller, the others by Mr. A. B. Dick :—

RESULTS TABULATED—ORE DRIED AT 100° C.

| Constituents. | Red Shag. | Gutter Mine. | Red Mine. | Bassy Mine. |
|-------------------------------------|-----------|--------------|-----------|-------------|
| Protoxide of iron | 46·53 | 34·22 | 50·73 | 45·53 |
| Peroxide of iron | ... | 0·68 | 0·45 | 5·00 |
| Protoxide of manganese | 2·54 | 2·87 | 1·86 | 1·74 |
| Alumina | 0·97 | 0·23 | 0·26 | 0·32 |
| Lime | 2·41 | 11·91 | 2·52 | 2·91 |
| Magnesia | 1·39 | 1·44 | 1·26 | 2·13 |
| Carbonic acid | 30·77 | 32·52 | 33·89 | 32·12 |
| Phosphoric acid | 0·69 | 0·87 | 0·73 | 0·86 |
| Sulphuric acid | 0·04 | 0·12 | 0·08 | 0·08 |
| Bisulphide of iron | 0·34 | 0·35 | 0·30 | 0·37 |
| Water | 1·47 | 0·98 | * | 2·29 |
| Organic matter | 10·46 | 8·93 | 6·41 | 5·20 |
| Ignited insoluble residue | 2·27 | 4·57 | 0·72 | 1·95 |
| Total | 99·88 | 99·69 | 99·21 | 100·50 |
| IGNITED INSOLUBLE RESIDUE. | | | | |
| Silica | 1·93 | 3·13 | 0·38 | 1·36 |
| Alumina | 0·25 | 1·12 | 0·32 | 0·42 |
| Peroxide of iron | 0·05 | 0·33 | ... | 0·06 |
| Lime | 0·03 | } traces. | 0·03 | ... |
| Potash | 0·20 | | 0·14 | 0·05 |
| Magnesia | ... | | ... | ... |
| Total | 2·46 | 4·58 | 0·87 | 1·89 |
| Metallic iron | 36·39 | 27·33 | 39·84 | 39·13 |

It is further observed, in reference to the foregoing analyses, that no metal precipitable by sulphuretted hydrogen from the hydrochloric acid solution was detected in 750 grains of the Red Shag iron ore; while in the "Gutter Mine" distinct traces of lead and copper were detected in 760 grains of the ore. Again, in the "Red Mine" and "Bassy Mine" no metals precipitable under similar conditions were detected in 680 grains of the former and 1,180 grains of the last named ore.

The ironstone is calcined at the mine's mouth with inferior coal. Before the operation it varies in richness from 34 to 58 per cent. of protoxide of iron and afterwards runs as high as 90 per cent. of the peroxide. The following will show the general conditions of the raw and calcined ores of the "Red

* Undetermined.

Shag" and "Red Mine" ironstones already referred to and in extensive use in North Staffordshire. The following analyses are by Mr. W. H. Merritt, Associate of the Royal School of Mines:—

| Constituents. | RED SHAG. | | RED MINE. | |
|----------------------------------|-----------|-----------|-----------|-----------|
| | Raw. | Calcined. | Raw. | Calcined. |
| Peroxide of iron | ... | 91.50 | ... | 92.52 |
| Protoxide of iron | 45.30 | ... | 50.90 | ... |
| Peroxide of manganese | ... | 4.12 | ... | 2.44 |
| Protoxide of manganese | 2.23 | ... | 1.76 | ... |
| Alumina | 0.32 | 0.55 | 0.73 | 0.59 |
| Silica | 0.50 | 0.86 | 1.13 | 0.79 |
| Lime | 0.64 | 1.10 | 2.07 | 1.79 |
| Magnesia | 0.20 | 0.34 | 0.80 | 0.94 |
| Sulphide of iron | 0.32 | ... | 1.10 | ... |
| Phosphoric Acid | 0.90 | 1.53 | 0.62 | 0.93 |
| Combined water | 1.07 | ... | 0.12 | ... |
| Carbon | 18.60 | ... | 8.75 | ... |
| Carbonic acid | 29.92 | ... | 33.02 | ... |
| Total | 100.00 | 100.00 | 100.00 | 100.00 |
| Metallic iron | 35.40 | 64.05 | 39.58 | 64.77 |
| Metallic manganese | 1.72 | 2.97 | 1.35 | 1.75 |

The other important measures of North Staffordshire reported upon in the "Iron Ores of Great Britain," are the following:—

"Cannel Mine," Apedale.—A clay ironstone; colour, dark grey; fracture, subconchoidal; structure, compact. The ore is intersected by very thin veins of carbonate of lime.

"Pennystone," Shelton Colliery.—A clay ironstone; colour, brown; structure, compact. And containing crystals of zinc blende.

The **"Deep Mine"** and **"Chalky Mine"** ironstone measures, at the Folly and Shelton Collieries, are described as clay iron ores, greyish black and dark brown in colour; structure, compact. And containing minute crystals of zinc blende and pyrites, as well as hydrated silicate of alumina and carbonate of lime.

The analysis of the Cannel Mine ironstone is by Mr. John Spiller, the others by Mr. A. Dick:—

NOTE.—A general description of the foregoing ironstone measures of North Staffordshire, their thickness and order of occurrence, will be found in Part I., pp. 142, 143.

| Constituents. | Cannel Mine. | Penny-stone. | Deep Mine. | Chalky Mine. |
|-----------------------------------|--------------|--------------|------------|--------------|
| Protoxide of iron | 41·80 | 46·35 | 48·33 | 51·07 |
| Peroxide of iron | ... | 3·00 | ... | ... |
| Protoxide of manganese | 2·16 | 1·61 | 2·99 | 2·36 |
| Alumina | 0·53 | 0·30 | 0·41 | 0·54 |
| Lime | 5·07 | 1·93 | 1·52 | 1·74 |
| Magnesia | 3·03 | 2·24 | 1·19 | 1·10 |
| Carbonic acid | 32·40 | 32·46 | 32·76 | 33·63 |
| Phosphoric acid | 1·40 | 0·67 | 0·87 | 1·12 |
| Sulphuric acid | trace. | trace. | trace. | trace. |
| Bisulphide of iron | 0·04 | 0·15 | 0·19 | 0·17 |
| Water hygroscopic | 0·36 | 1·43 | 0·85 | 0·99 |
| Water combined | 0·71 | | | |
| Organic matter | 0·79 | 2·95 | 1·17 | 1·24 |
| Ignited insoluble residue | 10·81 | 7·29 | 9·28 | 5·18 |
| Total | 99·10 | 100·38 | 99·56 | 99·14 |
| IGNITED INSOLUBLE RESIDUE. | | | | |
| Silica | 7·32 | 5·78 | 6·25 | 3·02 |
| Alumina | 3·28 | 1·22 | 2·41 | 1·93 |
| Peroxide of iron | 0·20 | 0·11 | 0·21 | 0·12 |
| Lime | 0·04 | ... | ... | ... |
| Magnesia | trace. | ... | ... | ... |
| Potash | 0·09 | 0·18 | 0·22 | 0·28 |
| Total | 10·93 | 7·29 | 9·09 | 5·35 |
| Metallic iron | 32·64 | 38·29 | 37·83 | 39·88 |

Near the base of the coal measure series, and in the neighbourhood of Froghall, Ipstones, and Consall, the valuable Churnet Valley ore occurs; a calcareous iron ore accidentally discovered some twenty-five years ago by a Mr. Bishop, a Cornishman, while a search was being prosecuted by explorations in depth for a seam of coal.

This Churnet Valley ore exists in a very irregular seam, varying in thickness from 6 to 20 inches, and embedded in the red shales of the lower coal measures; it is really a limestone highly impregnated with hydrated peroxide of iron, and though its area is limited it has, in past years, furnished large supplies of ironstone, which have recently considerably diminished, and its ultimate exhaustion may at no distant period be expected. The Churnet Valley ore is not calcined previous to its reduction, but is employed in admixture with other ores; the large amount of lime-

stone it contains (14·61 per cent.) rendering it valuable as a flux.

The Froghall ore occurring in the neighbourhood of Cheadle is thus described by Mr. A. Dick. "Calcareous hematite; colour, brownish red; structure, compact and homogeneous; a vein of calcareous spar occurs in it." The following results tabulated show its composition:—*

RESULTS TABULATED.—ORE DRIED AT 100° C.

| | |
|-------------------------------------|--------------|
| Peroxide of iron | 52·83 |
| Protoxide of manganese | 0·81 |
| Lime | 14·61 |
| Magnesia | 5·70 |
| Carbonic acid | 18·14 |
| Phosphoric acid | 0·32 |
| Sulphuric acid | 0·28 |
| Silica | trace. |
| Water | 4·75 |
| Organic matter | 1·30 |
| Ignited insoluble residue | 0·04 |
| Total | <u>98·78</u> |
| Metallic iron | 36·98 |

By passing sulphuretted hydrogen through the hydrochloria acid solution of 450 grains of ore and reducing the precipitate before the blowpipe, a minute trace of whitish metal was obtained. It was too small in quantity to be identified.

The argillaceous ironstone of North Staffordshire is calcined on an extensive scale, by which the metallic iron is concentrated, the bulk considerably reduced, and in this state it is largely exported to South Staffordshire to supply the furnaces of that district. The siliceous and argillaceous ironstones of the district lose in weight by calcination from 80 to 36 per cent.; the yield of metallic iron in the calcined state being 65 per cent. The "Black Band," or carbonaceous ironstone, loses by calcination from 50 to 60 per cent., and even more by weight, while the metallic iron, in the calcined state, yields by analysis nearly 70 per cent. This high percentage of metallic iron is not, however, secured practically in the blast furnace in the process of smelting.

Production and Distribution of Ironstone.—In the year 1855 the ironstone raised in North Staffordshire amounted to 512,000

* "Iron Ores of Great Britain," p. 291.

tons of which 210,500 tons were sent into South Staffordshire. The argillaceous ore sent away is chiefly calcined, losing by the operation about one-third of its weight, in which form it yields, on reduction, 65 per cent. in the blast furnace. Since 1856 the yield of the mines has been as follows, distinguishing as far as possible the calcareous ores from the ores of argillaceous carbonate, the average value of which may be taken at 7s. per ton :—

| Year. | Hydrated Oxide. | Calcareous Hematite. | Total. |
|-------|--------------------|-------------------------|---------|
| | Tons. | Tons. | Tons. |
| 1856 | ... | ... | 520,000 |
| 1857 | 349,947 | 300,000 | 649,000 |
| 1858 | 349,000 | 350,000 | 699,000 |
| 1859 | 349,000 | 275,000 | 624,000 |
| 1860 | 482,729 | 250,500 | 733,229 |
| 1861 | 349,195 | 150,000 | 499,195 |
| 1862 | 500,834 | 145,500 | 646,334 |
| 1863 | 541,059 | 140,750 | 681,809 |
| 1864 | 297,000 | 285,750 | 582,750 |
| 1865 | 550,491 | 275,000 | 825,491 |
| 1866 | 462,371 | 149,872 | 612,243 |
| 1867 | 544,509 | 250,000 | 794,509 |

In subsequent years the returns include raw and calcined stone not always reduced to the same equivalent, namely, raw stone ; it will therefore be more convenient to follow the returns of distribution by railway and canal indicating the movement of ironstone in the district and to places beyond.

Few districts possess greater facilities for the transport of minerals than that of North Staffordshire, traversed by the Trent and Mersey Navigation and the North Staffordshire Railway.

The annexed statement gives the total quantities of iron ore, calcined and raw, carried by the above-named canal and railway in each of the years since 1861, increasing from 349,198 tons in 1861 to 481,673 tons in the year 1880. The respective quantities carried in each of those years being thus distinguished :—

| How Distributed. | 1861. Quantities. | 1880. Quantities. |
|-----------------------------------|----------------------|----------------------|
| | Tons. | Tons. |
| Trent and Mersey Navigation . . . | 231,965 | 101,356 |
| North Staffordshire Railway . . . | 117,233 | 380,317 |
| Total | 349,198 | 481,673 |

| Year. | Canal. | Railway. | Total. |
|-------|---------|----------|---------|
| | Tons. | Tons. | Tons. |
| 1861 | 231,965 | 117,233 | 349,198 |
| 1862 | 292,515 | 208,319 | 500,834 |
| 1863 | 203,800 | 337,259 | 541,059 |
| 1864 | 280,648 | 250,061 | 536,709 |
| 1865 | 263,933 | 286,558 | 550,491 |
| 1866 | 283,637 | 328,606 | 612,243 |
| 1867 | 225,806 | 318,703 | 544,509 |
| 1868 | 192,657 | 316,406 | 509,063 |
| 1869 | 215,796 | 380,098 | 595,894 |
| 1870 | 207,118 | 438,036 | 645,154 |
| 1871 | 221,452 | 509,055 | 730,507 |
| 1872 | 213,246 | 559,958 | 773,204 |
| 1873 | 198,368 | 464,983 | 663,351 |
| 1874 | 153,161 | 368,558 | 521,719 |
| 1875 | 149,605 | 363,746 | 513,351 |
| 1876 | 120,606 | 345,647 | 466,253 |
| 1877 | 108,413 | 333,504 | 441,917 |
| 1878 | 92,209 | 308,466 | 400,675 |
| 1879 | 75,864 | 299,030 | 374,894 |
| 1880 | 101,356 | 380,317 | 481,673 |

These returns give the output of ironstone, while a reference to the following table shows the proportion of calcined to uncalcined stone, and gives the quantities used in the district. The value of the latter in the years 1872 and 1873 was 12*s.* per ton, and in the year 1880 but 10*s.* per ton :—

| Distribution. | 1861. | 1864. | 1867. | 1870. | 1873. | 1877. | 1879. | 1880. |
|--|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| <i>Trent and Mersey Navigation.</i> | | | | | | | | |
| Calcined Ironstone exported. | 103,791 | 109,159 | 137,681 | 111,108 | 108,939 | 61,354 | 53,123 | 68,167 |
| Calcined Ironstone used in District. | 15,436 | 23,874 | 14,618 | 48,063 | 37,421 | 28,725 | 12,547 | 7,802 |
| Uncalcined Ironstone sent out of District. | 112,739 | 147,615 | 73,507 | 47,347 | 52,008 | 18,334 | 10,194 | 25,387 |
| Total by Canal | 231,965 | 280,648 | 225,806 | 207,118 | 198,368 | 108,413 | 75,864 | 101,356 |
| <i>North Staffordshire Railway.</i> | | | | | | | | |
| Calcined Ironstone exported. | 68,884 | 125,715 | 190,430 | 207,098 | 342,072 | 190,655 | 180,898 | 246,043 |
| Uncalcined Ironstone „ | 11,438 | 12,853 | 7,156 | 13,167 | 13,846 | 10,281 | 7,276 | 12,014 |
| Calcined Ironstone conveyed to local Stations. | 32,693 | 116,594 | 120,159 | 125,403 | 107,543 | 131,798 | 108,739 | 12,303 |
| Uncalcined Ironstone ditto. | 4,218 | 899 | 958 | 2,368 | 1,722 | 770 | 2,117 | 229 |
| Total by Railway . . . | 117,233 | 256,061 | 318,703 | 438,036 | 464,963 | 333,504 | 299,030 | 380,317 |
| Total by Canal and Railway. | 349,198 | 536,709 | 544,509 | 645,154 | 663,351 | 441,917 | 374,894 | 481,673 |

Fig Iron Manufacture.—The earliest evidence of the manufacture of pig iron in North Staffordshire is afforded by a return to Parliament in the year 1796, when it was ascertained the only works existing at that time were those at Apedale of

Messrs. G. Parker and Co., and Silverdale of Mr. R. Sneyd, the furnace at Apedale producing 2,100 tons and that at Silverdale 2,600 tons, or a total of 4,700 tons; the total production of pig iron in the furnaces of Great Britain the same year being 183,407 tons.

In the year 1806 the Apedale furnace produced 1,400 tons and the Silverdale 1,010 tons, a total of 2,410 tons. In subsequent returns for many years the production of the district is included in that of South Staffordshire. When, in the year 1839, the make of the seven furnaces then in operation in North Staffordshire was ascertained, it amounted to 18,200 tons, and in 1840 to 20,500 tons. Between 1839 and 1848 several works were established, and when in the last-named year a Parliamentary return appeared, the works and firms, with the furnaces built and in blast, were as follows :—

| Works. | Owners. | FURNACES. | | Pig Iron. |
|----------------|-------------------------|-----------|-----------|-----------------|
| | | Built. | In Blast. | |
| Apedale . . | E. E. Heathcote . . . | 4 | 4 | Tons. 18,720 |
| Etruria . . | Earl Granville . . . | 3 | 2 | 7,280 |
| Kidsgrave . . | Thomas Kinneraley . . | 3 | 3 | 13,520 |
| Lane End . . | W. H. Sparrow . . . | 3 | 2 | 8,320 |
| Madeley . . | Thomas Firminstone . . | 2 | 1 | 4,160 |
| Silverdale . . | R. Sneyd . . . | 2 | 2 | 7,280 |
| Tunstall . . | Williamson Brothers . . | 2 | 2 | 6,240 |
| | Total . . . | 19 | 16 | 65,520 |

Comparing the average production per furnace in the year 1848 with previous years we have the annexed results. In 1848 the average was 4,095 tons; in 1840 but 2,600 tons; while in 1796 the average did not exceed 1,566 tons.

The next return available is for the year 1852, when the number of furnaces in North Staffordshire increased to 21, of which 17 were in blast, producing 90,000 tons of pig iron, giving an average make per furnace of 5,296 tons. Mr. Braithwaite Poole, in his "Statistics of Commerce" for the same year, gives the total production of pig iron in Great Britain as 2,701,000 tons, there being 655 furnaces built at that time, of which 497 were in blast.

Mr. Merritt, in his paper on the "North Staffordshire Coal

and Iron District," * refers the average height of the blast furnaces of this district to from 50 to 70 feet, and that those using coal will not stand a greater height than the latter, to which most of the new furnaces are being raised, and as the coal causes a little coking in the hearth, a process is in some places resorted to which is seldom met with elsewhere. The furnace is found to work better if the sides and bottom of the hearth are cleaned once in every turn of twelve hours, and this is done by running in long bars to loosen the crust, which is then blown out with the steam generated from a bar which is dipped in water before it is thrust into the furnace.

Since the year 1854 the following figures have been published showing the number of furnaces built and in blast, with the total make of pig iron, and side by side appears the average make per furnace :—

| Year. | FURNACES. | | Pig Iron made. | Average per Furnace. |
|-------|-----------|-----------|----------------|----------------------|
| | Built. | In Blast. | | |
| | No. | No. | Tons. | Tons. |
| 1854 | 28 | 21 | 104,000 | 4,952 |
| 1855 | 28 | 20 | 101,500 | 5,375 |
| 1856 | 28 | 20 | 130,560 | 6,528 |
| 1857 | 28 | 23 | 134,057 | 5,827 |
| 1858 | 28 | 22 | 135,308 | 6,136 |
| 1859 | 29 | 23½ | 143,500 | 6,106 |
| 1860 | 31 | 25 | 146,950 | 5,878 |
| 1861 | 32 | 23½ | 187,700 | 7,987 |
| 1862 | 33 | 23 | 184,450 | 8,020 |
| 1863 | 33 | 25½ | 176,504 | 6,854 |
| 1864 | 35 | 25 | 217,996 | 8,680 |
| 1865 | 35 | 27 | 206,268 | 7,640 |
| 1866 | 35 | 28½ | 210,335 | 7,432 |
| 1867 | 35 | 23 | 202,332 | 8,800 |
| 1868 | 36 | 25 | 229,913 | 9,196 |
| 1869 | 37 | 27 | 231,913 | 8,589 |
| 1870 | 43 | 36½ | 303,378 | 8,311 |
| 1871 | 35 | 31 | 268,300 | 8,655 |
| 1872 | 36 | 30½ | 275,925 | 8,973 |
| 1873 | 39 | 31 | 283,103 | 9,132 |
| 1874 | 39 | 28 | 273,501 | 9,739 |
| 1875 | 39 | 26 | 241,398 | 9,284 |
| 1876 | 37 | 25 | 213,569 | 8,543 |
| 1877 | 35 | 25 | 255,383 | 10,215 |
| 1878 | 35 | 24 | 231,534 | 9,648 |
| 1879 | 35 | 23½ | 210,374 | 9,335 |
| 1880 | 36 | 23½ | 225,023 | 9,943 |

* Read before the New York Meeting of the American Institute of Mining Engineers, February, 1880. See "Colliery Guardian," 19th March, 1880, p. 448.

In the last named year, the works and firms in operation, with the number of furnaces built and in blast, were as follows:—

NORTH STAFFORDSHIRE IRON WORKS.

| Name of Works. | Owners. | FURNACES. | |
|--|--------------------------------|-----------|-----------|
| | | Built. | In Blast. |
| Apedale, Newcastle . . . } | Stanier and Co. | No. 6 | No. 2 |
| Silverdale " . . . } | | 2 | 2 |
| Biddulph Valley | Robert Heath and Sons . . . | 4 | 4 |
| Norton and Ravensdale . . | " | 4 | 2 |
| Chatterley, Tunstall . . . | Chatterley Iron Co., Limited . | 3 | 1* |
| Clough Hall, Kids Grove . . | Kinnersley and Co. | 4 | 4 |
| Goldendale, Stoke | Williamson Brothers | 4 | 2 |
| Lane End, Longton | Thos. Goddard and Son . . . | 2 | 0 |
| Shelton, Hanley | The Earl Granville | 5 | 4½ |
| Longton Hall | J. and A. Glover | 2 | 2 |
| Total of North Staffordshire | | 36 | 23½ |

Malleable Ironworks, Mills, and Forges.—The most extensive of these in North Staffordshire are the Messrs. Robert Heath and Sons', situated at Biddulph Valley, Norton and Ravensdale, near Tunstall, possessing an aggregate of 154 puddling furnaces and 13 rolling mills. These works, when fully employed, are capable of producing from 1,500 to 1,600 tons of finished iron per week. The works of the Shelton Bar Iron Company are also of considerable magnitude, possessing upwards of 90 puddling furnaces and 8 rolling mills. The proprietor of these works is the Earl Granville, also chief owner of Lilleshall works in Shropshire, which establishment furnishes the best forge pig, largely employed in the Shelton Works. The works of North Staffordshire are justly celebrated for the superior quality of their plates, which are largely employed in our shipbuilding industries. In the manufacture of these the best Shropshire forge and hematite pig of the west coast is advantageously used.

In the year 1861 the only mills and forges in North Staffordshire were those of Messrs. Heath, the Shelton Bar Iron Company, and the Silverdale, of Messrs. F. Stanier & Co., possessing in the aggregate 139 puddling furnaces and 14 rolling mills. We have no indication of the state of activity in these works beyond the number of puddling furnaces and rolling mills in operation from

* One furnace for five months only.

year to year, together with the actual quantities of coal consumed in manufacture. The details under these heads are as follows, since the year 1870 :—

| Year. | Works. | Puddling Furnaces. | Rolling Mills. | Coal Used. |
|-------|--------|-----------------------|-------------------|-------------------|
| 1870 | 8 | 406 | 38 | Tons. *350,500 |
| 1871 | 8 | 429 | 40 | *380,000 |
| 1872 | 8 | 446 | 41 | 460,000 |
| 1873 | 8 | 425 | 41 | 465,000 |
| 1874 | 9 | 454 | 42 | 369,801 |
| 1875 | 9 | 444 | 38 | 303,924 |
| 1876 | 9 | 433 | 39 | 299,235 |
| 1877 | 10 | 443 | 39 | 300,129 |
| 1878 | 10 | 385 | 38 | 295,184 |
| 1879 | 10 | 405 | 37 | 326,299 |
| 1880 | 10 | 350 | 34 | 314,015 |

The annexed table presents a complete list of the works in operation in the last named year, together with the number of puddling furnaces and rolling mills engaged in the manufacture of the various firms of bar and merchant iron. The works of Messrs. Heath possessing very powerful appliances for the manufacture of anchors :—

| Name of Works. | Name of Firm. | Situated. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|--|--|-----------|---------------------------------|-----------------------------|
| Biddulph Valley . . . | Robert Heath and Sons . . | Tunstall | 40 | 3 |
| Norton | " " . . . | " | 65 | 7 |
| Ravensdale | " " . . . | " | " | " |
| Chesterton† | Chesterton Coal and Iron Co., Limited | " | " | " |
| Chatterley† | Chatterley Iron Co. | " | " | " |
| Clough Hall, Kids Grove . | Kinnersley and Co. | Stoke | 56 | 5 |
| Shelton | Shelton Bar Iron Co. | " | 87 | 8 |
| Berry Hill | William Bowers | " | 22 | 2 |
| Cliff Vale | Joseph Bell and Son | " | 24 | 3 |
| Silverdale and Knutton . | Stanier and Co. | " | 56 | 6 |
| Total of North Staffordshire | | | 350 | 34 |

In the southern part of Staffordshire the same year there were 125 works, with 1,625 puddling furnaces and 311 rolling mills, consuming approximately 1,667,600 tons of coal.

Coal and Iron Ore used in Manufacture.—An interesting

* Estimated quantities.

† Works standing.

statement, published in the year 1796, gives the following details of the quantity of coal consumed in raising coal, ironstone, and iron ore from the mine, and in the final completion of one ton of iron in rods for the manufacturer : *—

| PURPOSES TO WHICH APPLIED. | Tons. | Cwts. |
|--|-------|-------|
| Small coal in the blowing engine | 1 | 3 |
| " to torrify the raw material | 0 | 11 |
| " to work the hammer engine | 0 | 18 |
| " to work the mill engine | 1 | 0 |
| Large coal coked to be used in furnace | 8 | 5 |
| " to refine the pig iron | 1 | 2 |
| " in puddling furnace | 1 | 3 |
| " in the heating furnaces | 1 | 15 |
| " in the mill furnaces | 0 | 7 |
| " in workmen's houses | 1 | 5 |
| " in steam engines to draw the mine and draw the ironstone and coal | 0 | 19 |
| " consumed in pitmen's houses | 0 | 12 |
| Total | 19 | 0 |

From the above items it is estimated that the quantity of coal employed in the manufacture of a ton of pig iron was little short of 10 tons. In the year 1810 it appears, on the authority of Mr. Mushet, that the quantity did not exceed 5 tons. Again, in the year 1840, it is stated on the authority of Mr. William Jessop, of the Butterley Ironworks, that the quantity did not exceed 4 tons 1 cwt.

In the year 1854 a carefully written paper by Mr. John Hedley, of the Silverdale Works, on the "North Staffordshire Coal-fields," gives the following as the proportion of coal employed in those works in the manufacture of a ton of pig iron; namely, 42½ cwt. of coal, and 18 cwt. of slack, coked for the furnaces, with a further 19 cwt. of slack for the hot blast apparatus and blast engine, or a total of 74½ cwt. of coal to each ton of pig iron made.

Already the make of pig iron in North Staffordshire has been given. Since the year 1872 the quantities of coal and ironstone used in the manufacture of pig iron have been ascertained, and afford reliable data for comparison; the quantities under each head appear in the annexed table :—

* Macnab. "Observations on the Coal Trade, &c., 1801," p. 69.

| Year. | Pig Iron. | Coal used. | Iron Ore Used. |
|-------|-----------|------------|----------------|
| | Tons. | Tons. | Tons. |
| 1872 | 275,925 | 817,753 | 723,400 |
| 1873 | 283,103 | 830,119 | 779,000 |
| 1874 | 273,501 | 820,514 | 752,600 |
| 1875 | 241,398 | 703,000 | 627,823 |
| 1876 | 213,569 | 525,387 | 562,348 |
| 1877 | 255,383 | 578,428 | 664,210 |
| 1878 | 231,534 | 530,594 | 612,326 |
| 1879 | 210,374 | 430,432 | 556,312 |
| 1880 | 225,023 | 434,171 | 569,334 |

In the year 1872 the quantity of coal used in the production of each ton of pig iron, all purposes in the operation included, where heat was required, gave an average of 59 cwt., and in the following year the average was somewhat less, indicating a watchful economy in the consumption of fuel.

Following the consumption of iron ore in each of the same years, 1872 and 1873, in the make of pig iron, the above quantities give an average of 52½ cwt. of raw uncalcined stone to each ton of pig iron obtained from the blast furnace; the greater proportion of the ore employed being native mine of the district. Other ores are also used in admixture, which are imported into the district, and the annexed statement will show approximately the places from which the ores were obtained:—

| Source of Supply. | 1872. | 1873. | 1876. | 1879. | 1880. |
|---------------------------|---------|---------|---------|---------|----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| North Staffordshire . . . | 559,000 | 602,594 | 385,000 | 363,200 | 364,280 |
| Oxfordshire | 3,200 | 357 | .. | .. | .. |
| Northamptonshire . . . | 4,000 | 4,333 | 25,337 | 18,216 | .. |
| Lincolnshire | 13,450 | 11,326 | | | |
| Various places | 143,760 | 160,390 | 152,011 | 174,696 | 205,054* |
| Total | 723,400 | 779,000 | 562,348 | 556,312 | 569,334 |

Of the ore derived from "various places" there is reason to believe that some portion of this quantity in each year is the produce of the district, the remainder being furnace mill cinder, containing a large percentage of metallic iron and some hematite from Lancashire.

With regard to the cost of production, it is stated that coal could be mined in 1877 in North Staffordshire at a little over

* Including some ore from Northamptonshire and Lincolnshire.

4*s.* per ton, and the ironstone from about 3*s.* to 3*s.* 6*d.* per ton. The work of getting is let out at so much per ton (averaging in 1877 from 2*s.* to 3*s.* per ton), the contractor employing miners whose daily wages average 4*s.* In the same manner, by taking the immediate wages at the blast furnace into consideration, a ton of pig iron could be produced at a little over 4*s.* a ton for labour. It will be remembered that wages have gone down since 1877, and if they have not yet reached the old figure, these approximate prices would have to be reduced still more to arrive at the present cost of production in this district.

An average charge of a furnace is as follows, the first being the quantities used for Red Shag alone, and the second for a mixture of Red Mine (raw giving 50 per cent.) and Lean Mine (raw giving 35 per cent.).

| FIRST. | | SECOND. | |
|---------------------|-----------|---------------------|-----------|
| Materials. | Cwt. Qrs. | Materials. | Cwt. Qrs. |
| Coal | 29 0 | Coal | 22 2 |
| Ore | 29 0 | (Red Mine | 19 1 |
| Limestone | 2 2 | (Lean Mine | 16 2 |
| Flue cinder | 1 3 | Limestone | 5 0 |
| | | Flue cinder | 2 1 |

The consumption per ton of pig iron is practically as follows : Coal, 35 cwt. 3 qrs. ; ironstone, 34 cwt. ; limestone, 8 cwt. 2 qrs. and flue cinder, 4 cwt. 2 qrs.*

* "Transactions of the American Institute of Mining Engineers," Vol. VIII., p. 333.

CHAPTER XI.

SOUTH STAFFORDSHIRE AND WORCESTERSHIRE IRON INDUSTRIES.

Description of Ironstone Measures of Coal Field—Analyses and Production of Ironstone—Pig Iron Manufacture—Early History—Sturtevant, Ravenson, and Dudley's experiments in the Use of Coal previously coked—Production of Pig Iron—Coal and Iron Ore used in Manufacture—Calcination of Ores in Clamps and Kilns—Works in operation in 1880—Malleable Iron Works in 1880, coal used—Prices of Finished Iron.

Ironstone Deposits.—The measures yielding ironstone exist abundantly in this coal-field, with their associated beds of shale, in which fossils are found in great profusion. Professor Jukes, in his Introduction to Part II. of the "Iron Ores of Great Britain," remarks that it is the middle part of the coal-field which has ever been largely productive of ironstone, and in a general section of strata gives the following measures of ironstone and the varying thickness of the strata in which they occur:—

| No. | General Section of Ironstone Measures. | Thickness. |
|-------|--|------------|
| | | Feet. |
| I. | Brooch Binds | 7 to 20 |
| II. | Pins and Pennyearth | 6 „ 30 |
| III. | Broad Earth, Catch Earth, &c. | 6 „ 14 |
| IV. | Pouncill Batt, Blacktery, and Whitory | 2 „ 8 |
| V. | Gubbin, called "Little" or "Top" | 2 „ 8 |
| VI. | New Mine or White Ironstone | 2 „ 10 |
| VII. | { Measures containing Pennystone, Ironstone, } called also Bluestone or Cakes | 10 „ 25 |
| VIII. | { Measures containing the Fire-clay balls, iron- } stone occasionally | 2 „ 40 |
| IX. | Getting Rock Ironstone (occasional) | 4 „ 5 |
| X. | Poor Robin Ironstone | 3 „ 5 |
| XI. | Rough Hills White Ironstone (occasional) | 2 „ 19 |
| XII. | Gubbin and Balls Ironstone | 0 „ 10 |
| XIII. | Blue Flats Ironstone | 2 „ 9 |
| XIV. | Silver Threads | 4 „ 7 |
| XV. | Diamonds | 2 „ 3 |

It must not, however, be supposed that all these measures are found vertically one under the other in any one part of the coal-

field. The uppermost are known only in the southern extremity, where they dip to the south. The lowest are either altogether absent there, or do not contain the measures which, a few miles further north, are rich in ironstone. Towards the north, on the other hand, the lowest measures "crop out" or rise towards the surface, and it is therefore not possible that the upper measures should be found there. The section given above is compiled partly from the examination of the southern, partly of the middle, and partly of the northern part of the district, the object being to enumerate every important measure of ironstone and its relative position in the coal-field.

Professor Jukes * gives the following description of the above-named ironstone measures, which it will be convenient to take in the order of occurrence :—

I. Brooch Ironstone, or Binds—are beds of clay or shale beneath the Brooch coal, containing ironstone to the south-west of Dudley, where the measures average about 7 feet in thickness.

II. Pins and Pennyearth.—These measures take their name from the form of the nodules in which the ironstone occurs. The "Pins" being small, round or cylindrical, and the "Penny-earth," small, flattish nodules, like pennypieces.

III. The "Ten-foot Stone," and "Backstone."—Known also as the Broad Earth, &c., so called from lying immediately above or on the back of the "Thick Coal," in the neighbourhood of Brierley Hill.

IV. The "Whitery," or Grains.—These are merely occasional ironstone measures, consisting of light and dark coloured clunch, a term applied to course tough clay of the coal measures. These measures are sometimes absent, and where they contain most ironstone rarely exceed 6 or 8 feet in thickness.

V. Gubbin.—Sometimes called the "Little," or "Top," or "Thick Coal Gubbin," is one of the most important and widely diffused of the ironstone measures of this coal-field, and yields an average of 1,500 tons per acre, the thickness of the measures varying in different places from 2 to 9 feet.

VI. New Mine Ironstone, or Whitestone.—This is another widely diffused ironstone; it is a light coloured ironstone, occurring in large nodules lying in a bed of clay, which is called

* "Iron Ores of Great Britain," Part II., p. 108.

"clunch," "clod," or "binds," according to its minor varieties. The layers of nodules vary from 2 to 4 feet, and the whole measure from 2 to 10 feet in thickness, the most usual being from 4 to 5 feet. Professor Jukes gives several interesting sections, at Wolverhampton, Bilston, Dudley and Kingswinford, in which these measures occur and from which the above average thicknesses are derived.

VII. *Pennystone Bluestones*, or "*Cakes*."—The measures in which this ironstone lies are dark clay, sometimes black, the ironstone occurring in flat, round nodules of a dark colour. In the district of Dudley, to the south-west, ironstone has rarely if ever been found on this horizon, or below it, while it is well-known towards Oldbury, under the names of "*Cakes*," or "*Bluestone*," and between Wolverhampton and Walsall as *Pennystone*.

VIII. "*Fire-Clay Balls*."—This measure is variable and capricious, and the ironstone irregular in its occurrence, and in the form of balls, hence the name, and resting on the fire-clay coal. In the Stow Heath and Priestfield Collieries, between Bilston and Wolverhampton, where there are many pits within the space of half a mile, these measures vary from a seam of clay 2 or 3 feet in thickness to a mass of sandstone 39 feet thick, with a little fire-clay above and below it.

IX. "*Getting Rock Ironstone*."—This measure, occurring below a bed of fire-clay, varying from 2 to 10 feet in thickness, sometimes contains ironstone worth working in certain localities. It appears to be confined to the neighbourhood of Stow Heath, Ettingshall, Deepfields, and Bradley, and does not always occur even there.

X. "*Poor Robin*."—This ironstone is more widely diffused and persistent than that of the *Getting Rock*; the measure is sometimes 3 and 4 feet thick.

XI. "*Rough Hills Whitestone*."—This ironstone is confined to the district between Bilston and Wolverhampton. At Parkfields the measures are 19 feet thick, containing 11 bands of ironstone from 1 to 6 inches thick, making a total of 32 inches of ironstone. Elsewhere it is not so fully developed, not exceeding 3 or 4 feet thick, with not more than from 6 to 8 inches of ironstone.

XII. "*Gubbin and Balls*."—This measure contains good workable ironstone, occurring principally between Wolverhampton and Walsall and around Bilston. At Chillington Colliery the

thickness of the measures is nearly 7 feet, with 4 bands of ironstone, giving a total thickness of 23 inches.

XIII. "*Blue Flats*."—This ironstone is so called from the flat pavement-like form in which it occurs. At Park Hall, just south of Wolverhampton, in a section of 8 feet 9 inches of measures, are 4 bands of ironstone, giving an aggregate thickness of 16 inches; while at Ryecroft, near Walsall, the measures are found in a thickness of 18 inches, with 2 bands of ironstone each 3 inches thick.

XIV. "*Silver Threads*."—This measure occurs in the district around Walsall, varying from 4 to 7 feet thick, composed of 2 or 3 bands of ironstone, varying from 1 to 4 inches in thickness, and so named from the little threads of shining spar, which traverse the ironstone.

XV. "*Diamonds*."—This ironstone, the lowest in the series, is confined, like the Silver Threads, as a workable ironstone, to the district west of Walsall, where it occurs from 2 to 4 feet thick, and contains 2 bands of ironstone varying from 2 to 4 inches in thickness.

Analyses of the Ironstone.—In the "Iron Ores of Great Britain," Part II., from which the account of the principal ironstone measures are taken, also appear complete analyses of no less than 80 of the ironstones wrought in the South Staffordshire coal-field. These analyses were made in Dr. Percy's laboratory, and subsequently published in the Memoirs above referred to. It will be sufficient, however, to give a description and analysis of some of the more important and characteristic ironstones of the several districts. Those selected in the Dudley district are thus described:—

The "Grains," (No. IV. of General Section). By Mr. A. Dick.—"Clay iron ore; colour, greyish black; structure, compact and homogeneous. The ore is covered in some places with a thin layer of yellowish white matter."

"Gubbin Ironstone," (No. V. of General Section). By Mr. A. Dick.—"Clay iron ore; colour, greyish black; structure, compact and homogeneous. It contains thin veins of white and reddish brown matter, in which zinc-blende, galena, and copper pyrites occur."

"Fire-Clay Balls," (No. VIII. of General Section). By Mr. A. Dick.—"Fine grained, crystalline, carbonate of protoxide of

iron; colour, greyish brown. It contains veins of calc spar and white pulverulent silicate of alumina, in which occur small, white, crystalline, globular concretions, consisting of carbonate of lime and magnesia.

RESULTS TABULATED.*

| Constituents. | Grains. | Gubbin. | Fire Clay Balla. |
|-----------------------------------|---------------|--------------|------------------|
| Protoxide of iron | 54·12 | 45·86 | 47·87 |
| Protoxide of manganese . . | 2·05 | 0·96 | 1·12 |
| Alumina | 0·78 | 0·42 | 0·43 |
| Lime | 2·21 | 1·17 | 1·00 |
| Magnesia | 0·62 | 1·65 | 1·27 |
| Potash | trace | ... | ... |
| Carbonic acid | 35·25 | 31·02 | 30·96 |
| Phosphoric acid | 0·69 | 0·21 | 0·07 |
| Sulphuric acid | trace | trace | 0·08 |
| Silica | 2·11 | 0·42 | ... |
| Bisulphide of iron | 0·40 | 0·10 | 0·17 |
| Water | 1·07 | 1·08 | 1·18 |
| Organic matter | 1·36 | 0·90 | 0·41 |
| Ignited insoluble residue . | ... | 15·90 | 15·95 |
| Total | 100·66 | 99·69 | 100·51 |
| IGNITED INSOLUBLE RESIDUE. | | | |
| Silica | ... | 10·26 | 10·52 |
| Alumina | ... | 5·44 | 5·02 |
| Peroxide of iron | ... | 0·40 | 0·33 |
| Lime | ... | 0·20 | 0·13 |
| Magnesia | ... | 0·20 | ... |
| Potash | ... | ... | 0·38 |
| Total | 3·43 | 16·50 | 16·38 |
| Metallic iron | 42·26 | 35·99 | 37·47 |

In a note appended to the analysis of the "Grains," it is stated no separate examination of the insoluble residue was made; and further, that no metal precipitable by sulphuretted hydrogen from the hydrochloric acid solution was detected in 900 grs. of this ore, 500 grs. of the Gubbin, or 750 grs. of the Fire-clay ore.

In the Darlaston district the measures examined by Mr. Charles Tookey, from the Rough Hay Colliery, are thus described:—

"*Rough Hill Whitestone*," (No. XI. of General Section).—"Clay iron ore; colour, brown; structure, compact and homo-

* "Iron Ores of Great Britain," Part II., pp. 120, 123, 139.

geneous. Veins of hydrated silicate of alumina, peroxide of iron and copper pyrites occur in it."

"*Gubbin and Balls*," (No. XII. of General Section).—"Clay iron ore; colour, greyish black; structure, compact. It is seamed with greyish white silicate of alumina, in which minute crystals of zinc-blende, iron pyrites and copper pyrites occur."

"*Silver Threads*," (No. XIV. of General Section).—"Clay iron ore; colour, greyish brown; the ore is irregularly seamed, with numerous veins of calcspar, coated with drab coloured ferruginous matter."

"*Diamonds*," (No. XV. of General Section).—"Clay iron ore; colour, dark grey; structure, compact and homogeneous. It contains veins of calcspar and silica of alumina, in which galena, zinc-blende, copper pyrites and iron pyrites occur."

RESULTS TABULATED.

| Constituents. | Rough Hill Whitestone. | Gubbin and Balls; Gubbin. | Silver Threads. | Diamonds. |
|----------------------------|---------------------------|------------------------------|--------------------|-----------|
| Protoxide of iron . . . | 46.56 | 49.30 | 40.39 | 40.01 |
| Peroxide of iron . . . | 2.80 | 3.61 | 2.38 | 2.46 |
| Protoxide of manganese. | 0.65 | 0.86 | 0.75 | 0.75 |
| Alumina | 0.70 | 0.34 | 0.19 | 0.46 |
| Lime | 1.13 | 0.69 | 7.30 | 2.58 |
| Magnesia | 1.18 | 0.45 | 2.16 | 2.70 |
| Silica | 0.54 | 0.23 | 0.18 | 0.27 |
| Potash | 0.23 | 0.09 | 0.07 | 0.19 |
| Carbonic acid | 30.08 | 32.05 | 33.35 | 29.13 |
| Phosphoric acid . . . | 0.38 | 0.23 | 0.22 | 0.21 |
| Bisulphide of iron . . | 0.13 | 0.13 | 0.11 | 0.06 |
| Sulphide of zinc . . . | ... | 1.27 | ... | ... |
| Water | 1.07 | 0.66 | 0.93 | 1.11 |
| Organic matter | 0.50 | 0.54 | 0.80 | 1.06 |
| Ignited insoluble solution | 13.77 | 9.42 | 10.52 | 18.77 |
| Total | 99.72 | 99.87 | 99.35 | 99.76 |
| IGNITED INSOLUBLE RESIDUE. | | | | |
| Silica | 7.72 | 5.99 | 6.56 | 13.45 |
| Alumina | 4.70 | 2.71 | 3.08 | 4.22 |
| Peroxide of iron . . . | 0.39 | 0.21 | 0.37 | 0.59 |
| Lime | 0.11 | 0.17 | 0.04 | 0.08 |
| Magnesia | 0.15 | 0.07 | 0.06 | 0.14 |
| Potash | 0.82 | 0.21 | 0.26 | 0.18 |
| Total | 13.89 | 9.36 | 10.37 | 18.66 |
| Metallic iron | 38.56 | 41.06 | 33.44 | 33.28 |

The presence of copper was distinctly proved in 800 grains of the "Rough Hill Whitestone" ore. In the "Gubbin and Balls," and the "Silver Threads," no metal precipitable by sulphuretted hydrogen from the hydrochloric acid solution was detected in 400 grains of the former and 800 grains of the latter; while in the "Diamonds" traces of lead and copper were found in the hydrochloric acid solution of 800 grains of ore.

There is also an ironstone known as "Brown Stone," occurring in the neighbourhood of Bloxwich, some three miles north of Walsall, not previously referred to, which is described as a "Clay iron ore; colour, various shades of light brown; structure, compact. Veins of white pulverulent and grey crystalline substances occur in it, containing traces of galena and copper pyrites." The analysis of this ore, by Mr. A. Dick, gives the following results:—*

RESULTS TABULATED.—ORE DRIED AT 100° C.

| | |
|----------------------------------|--------|
| Protoxide of iron | 46·14 |
| Protoxide of manganese | 1·40 |
| Alumina | 3·53 |
| Lime | 3·43 |
| Magnesia | 2·13 |
| Potash | 0·41 |
| Carbonic acid | 32·04 |
| Phosphoric acid | 0·61 |
| Sulphuric acid | trace. |
| Silica | 8·63 |
| Bisulphide of iron | 0·10 |
| Water | 0·94 |
| Organic matter | 0·98 |
| | <hr/> |
| | 100·34 |
| | <hr/> |
| Metallic iron | 35·95 |
| Clay after ignition | 13·38 |

It is stated in reference to this analysis that no metal precipitable by sulphuretted hydrogen from the hydrochloric acid solution of 550 grains of the ore was detected.

Of the ironstone measures examined and published in the "Iron Ores of Great Britain," Part II., some thirty analyses appear; and from these the following abstract has been prepared showing the relative proportion of protoxide of iron, phosphoric acid and metallic iron contained in each sample examined; preceding which is given the name of each measure and the analysts who examined it.

* "Iron Ores of Great Britain," Part II., p. 164.

IRONSTONE MEASURES OF SOUTH STAFFORDSHIRE.

| Clay Iron Ores. | Analyst. | Protoxide of Iron. | Phosphoric Acid. | Metallic Iron. |
|---|------------------|--------------------|------------------|----------------|
| Brooch, Corngreaves | John Spiller . | 43·81 | 0·83 | 34·35 |
| Pins, Dudley | Allan Dick . | 45·35 | 0·46 | 35·74 |
| Penny Earth, Dudley | " . | 37·69 | 0·66 | 29·42 |
| Grains, Dudley | " . | 54·12 | 0·69 | 42·26 |
| Gubbin, Dudley | " . | 46·30 | 0·74 | 36·14 |
| Gubbin, Rubble, Dudley | " . | 40·28 | 0·30 | 31·70 |
| Whitestone Bind, Dudley | John Spiller . | 30·96 | 0·26 | 24·88 |
| Bottom Whitestone, Dudley | " . | 48·63 | 0·31 | 37·45 |
| Whitestone, Darlaston | Charles Tookey . | 33·92 | 0·35 | 28·87 |
| Cakes or Bluestone, Dudley | Allan Dick . | 50·60 | 0·23 | 39·71 |
| " | " . | 43·65 | 0·15 | 34·88 |
| Fire-clay Balls, Dudley | " . | 46·39 | 0·11 | 36·56 |
| " | " . | 47·87 | 0·07 | 37·47 |
| Poor Robin's, Bunker's Hill | " . | 49·61 | 0·34 | 39·62 |
| Rough Hill Whitestone, Darlaston } (good sample) | " . | 44·20 | 0·66 | 34·53 |
| " (bad sample) | " . | 33·19 | 0·50 | 26·01 |
| Rough Hill Whitestone, Rough Hay, } Darlaston | Charles Tookey . | 46·56 | 0·38 | 38·56 |
| Gubbin and Balls, Bunker's Hill Colliery | Allan Dick . | 39·51 | 0·31 | 31·34 |
| " | " . | 52·04 | 0·21 | 40·84 |
| Blue Flats, Darlaston | Charles Tookey . | 42·34 | 0·25 | 34·41 |
| Silver Threads, Darlaston | " . | 40·39 | 0·22 | 33·44 |
| Diamonds, Darlaston | " . | 40·01 | 0·21 | 33·28 |
| " | Allan Dick . | 41·90 | 0·22 | 32·87 |
| Brownstone, Bloxwich | " . | 46·14 | 0·61 | 35·95 |

From these and other analyses of the argillaceous ores of the district, it has been ascertained that 34·75 per cent. represents the average yield of metallic iron.

Production of Ironstone.—The production of ironstone in South Staffordshire was returned as follows, in each of the years named:—

| Year. | Tons. | Year. | Tons. |
|-------|---------|-------|---------|
| 1859 | 959,000 | 1870 | 450,000 |
| 1860 | 785,700 | 1871 | 705,665 |
| 1861 | 727,500 | 1872 | 640,950 |
| 1862 | 700,500 | 1873 | 584,325 |
| 1863 | 850,000 | 1875 | 715,451 |
| 1864 | 948,500 | 1876 | 645,288 |
| 1865 | 659,500 | 1877 | 636,243 |
| 1866 | 599,000 | 1878 | 587,874 |
| 1867 | 525,000 | 1879 | 483,507 |
| 1868 | 340,578 | 1880 | 362,773 |

For a few years the individual returns of ironstone were published, those for the year 1873 are at hand and were as follows; since 1875 the aggregate production is alone recorded:—

| District or Mine. | Quantities. | Value. |
|------------------------------|-------------|------------|
| | Tons. | £ s. |
| Barbor's Field | 11,011 | 6,006 12 |
| Barn Farm | 2,690 | 1,560 0 |
| Birchill's Hall | 6,206 | 3,723 12 |
| Bradley | 1,897 | 1,138 4 |
| Cannock Chase | 350 | 210 0 |
| Coppy Hall | 9,189 | 5,513 8 |
| Deans | 5,287 | 3,172 4 |
| Friar Park | 5,614 | 3,368 8 |
| Grace Mary | 2,645 | 1,587 0 |
| Granville | 3,695 | 2,217 0 |
| Haden Hall | 6,480 | 3,888 0 |
| Hatherton | 8,298 | 4,978 16 |
| Jervoise | 2,122 | 1,273 4 |
| Moxley | 1,880 | 1,128 0 |
| New Cross | 15,503 | 9,301 16 |
| Old Hall | 7,100 | 4,260 0 |
| Parkfields | 5,073 | 3,043 16 |
| Priestfields | 3,735 | 2,241 0 |
| Princes End | 3,118 | 1,870 16 |
| Pearson | 2,125 | 1,275 0 |
| Riddings | 2,168 | 1,300 16 |
| Roughwood | 7,045 | 4,227 0 |
| Stow Heath | 9,404 | 5,640 0 |
| Shut End | 11,312 | 6,787 4 |
| Tansey Green | 3,971 | 2,382 12 |
| Tipton Moat | 2,073 | 1,243 16 |
| Tipton Moat | 6,374 | 3,824 8 |
| Wednesbury | 5,232 | 3,139 4 |
| Wednesbury Oak | 4,000 | 2,400 0 |
| Yeatham | 5,541 | 3,324 12 |
| Sundry pits | 73,191 | 43,914 12 |
| „ (estimated) | 350,004 | 210,000 0 |
| Total of South Staffordshire | 584,325 | 349,941 10 |

The value of these ironstones, between 1860 and 1870, varied from 5*s.* to 6*s.* and 7*s.* 6*d.* per ton; the average price in 1880 being 10*s.* per ton.

Fig Iron Manufacture.—The history of the manufacture of iron may be regarded as of two distinct periods—the one extending from the earliest times when charcoal was alone employed; the other commencing with the successful application of coal previously coked, and dating about the year 1735. In the early part of the 17th century the rapid devastation of our forests occasioned great scarcity in the supply of charcoal to our furnaces, so much so, that three-fourths of the blast furnaces in the kingdom came to a standstill; it was at this period that

attention was directed to the use of coal previously coked. In 1612 we find Simon Sturtevant, and again in 1613 ^{John} Raven^{son}, working towards this end; they were unsuccessful; in 1620, however, the use of mineral fuel was proved practicable in the reduction of the ores of iron, and we find Dud Dudley, the founder of the noble house of Dudley, to whom a patent was granted in the same year for smelting iron ore with pit or sea coal, to have so far succeeded as to have made 3 tons of pig iron from a furnace in a week with coke. Dud Dudley, in his book ^{A natural} "Metallum Martis," published in 1665, gives an interesting ^{Son of} account of his labours and the difficulties encountered by him. ^{5th Lord} His works were swept away by a great flood; he further tells us that they were repaired, and at a subsequent period riotously destroyed, and he himself utterly ruined by adhering to the royal cause, which disturbed society in those days. With this historical reference we advance to the year 1735, when the successful application was carried out by Mr. Abraham Darby, of Shropshire, at the Coalbrookdale Works, and from this period may be dated the first great improvement in the manufacture of pig iron.

In the year 1740, when the production of charcoal pig iron amounted to 17,350 tons, there existed in South Staffordshire 2 furnaces, and a like number in Worcestershire, producing 1,700 tons of pig iron: the two former making 1,000 tons and the latter 700 tons. Advancing to the year 1788 the manufacture of pig iron with charcoal appears to have been discontinued and coke substituted; for we find 3 furnaces in operation in South Staffordshire, producing 2,400 tons of coke pig iron.

The total production of pig iron at this period in England and Wales was:—

| Description. | Furnaces. | Tons. |
|-------------------------|------------|--------|
| Charcoal iron | Nos. 24 | 13,100 |
| Coke iron | 53 | 48,200 |
| Total | 77 | 61,300 |

Some twenty years after the successful application of coal by Darby in the reduction of the ores of iron in the furnace, a new impulse was given to this industry by Smeaton's invention, in

which he applied, with great advantage, his blowing cylinders, worked by water-wheels or by the atmospheric steam engine; the first of these was erected by him at the Carron Ironworks in Scotland in 1760. This means of increasing the power of the blast in the furnaces was quickly followed by increased production of pig iron.

Again, towards the close of the last century a new era in the manufacture of iron arose, when the steam engine, the invention of James Watt, was made general in its application to the purposes both of pumping water from mines and for increasing the intensity of the blast. Cort's inventions, for which he obtained patents in 1783 and 1784, formed another important step in the manufacture of wrought from pig iron, the first for puddling, by which pig iron is rendered malleable, and the second for substituting rollers for the forge hammer for drawing out the balls of malleable iron into bars. The foregoing advantages, together with the high price of foreign iron, largely imported, caused our manufacture to nearly double itself between the years 1788 and 1796, to which latter year attention is now directed. The return for 1796 was prepared for the House of Commons, when Mr. Pitt had it in contemplation to impose a tax on coal at pit's mouth, and the returns were obtained from three sources—the Excise authorities, calculation, and lastly, the quantities really made. The works then existing in South Staffordshire and Worcestershire, with the number of furnaces and make of each works are stated as follows, giving an average yield per furnace of 937 tons :—

| Works. | Number of Furnaces. | Excise. | Calculated. | Actual. |
|-----------------------|------------------------|---------|-------------|---------|
| | | Tons. | Tons. | Tons. |
| Bilston | 2 | 2,340 | 2,340 | 1,429 |
| Bradley | 3 | 3,640 | 3,000 | 1,920 |
| Brierley | 1 | 1,300 | 1,300 | 1,046½ |
| Deepfield | 2 | 2,600 | 2,600 | 2,526 |
| Dudley Port | 1 | 1,040 | 1,040 | 869 |
| Gospel Oak | 1 | ... | ... | 1,613 |
| Graveyard | 1 | 1,260 | 1,336 | 213 |
| Level | 1 | 1,560 | 1,560 | 1,391 |
| Tipton | 2 | 2,082 | 2,080 | 2,203 |
| Total | 14 | | | 13,210½ |

In the same year, 1796, the production of Great Britain, of

124 furnaces, amounted to 125,079 tons, of which South Staffordshire contributed upwards of 10 per cent. The returns for the year 1806 show a considerable increase, the 105 furnaces in blast in that year in Great Britain yielding 243,851 tons of pig iron, the production of South Staffordshire being 47,592 tons, or an increase of nearly 400 per cent., when compared with the returns for 1796. The following statement shows the individual production of the ironworks in 1806, with the respective numbers of furnaces built and in operation :—

| Works. | FURNACES. | | Pig Iron. |
|----------------------|-----------|-----------|-----------|
| | Built. | In Blast. | |
| | Nos. | Nos. | Tons. |
| Blower's Green . . . | 1 | 1 | 2,436 |
| Bilston | 3 | 2 | 3,550 |
| Bradley | 3 | 2 | 2,566 |
| Brierley Hill . . . | 1 | 1 | 817 |
| Brierley | 2 | 0 | ... |
| Caponfield | 2 | 2 | 4,600 |
| Deepfield | 2 | 2 | 3,680 |
| Dibsdale Bank . . . | 1 | 1 | 300 |
| Dudley Port | 1 | 1 | 1,196 |
| Golden Cross | 1 | 1 | 184 |
| Gornal Wood | 1 | 1 | 432 |
| Graveyard | 2 | 1 | 1,274 |
| Gospel Oak | 2 | 2 | 4,667 |
| Level | 3 | 2 | 3,351 |
| Mill Field | 2 | 2 | 5,000 |
| Moorcroft | 2 | 1 | 1,955 |
| Netherton | 2 | 1 | 1,500 |
| Oldbury and Tipton . | 3 | 3 | 4,500 |
| Park Head | 1 | 1 | 1,404 |
| Rough Hill | 2 | 2 | 3,000 |
| Toll End | 2 | 1 | 1,200 |
| Wednesbury | 1 | 0 | ... |
| Total | 40 | 30 | 47,592 |

The production of Shropshire and South Wales alone exceeded that of South Staffordshire at this period, the former yielding 54,966 tons, the latter 68,867 tons, while that of Scotland was but 22,840 tons of pig iron. The next return from which information is obtained was prepared for the Government by Mr. F. Finch, formerly member for Walsall, and refers to the production in the years 1823 and 1830, when the number of furnaces in blast and the quantity of pig iron made in this district was as follows :—

SOUTH STAFFORDSHIRE.

| — | Furnaces. | 1823. | | 1830. | |
|----|---------------------------|---------------------------------|-------------------|---------------------------------|-------------------|
| | | Total Number of Furnaces. | Pig Iron Made. | Total Number of Furnaces. | Pig Iron Made. |
| | | | Tons. | | Tons. |
| 1 | Bradley | 2 | 4,195 | 2 | 4,194 |
| 2 | „ Lower | 1 | 1,920 | 1 | 2,113 |
| 3 | Birch Hills | 2 | ... | 2 | ... |
| 4 | Barbor's Field | ... | ... | 2 | 5,720 |
| 5 | Bilston | 4 | 7,696 | 4 | 4,680 |
| 6 | „ Brook | 2 | 4,345 | 2 | 3,771 |
| 7 | Broadwaters | 2 | ... | ... | 6,368 |
| 8 | Brettell Lane | ... | ... | 2 | 2,949 |
| 9 | Brierley Hill | 2 | 4,348 | 2 | ... |
| 10 | Blower's Green | 2 | 5,348 | 2 | 5,257 |
| 11 | Buffery | 3 | 6,551 | 3 | 5,246 |
| 12 | „ Old | 1 | 2,646 | 1 | 2,158 |
| 13 | Cotham | ... | ... | ... | ... |
| 14 | Coseley | 2 | 5,200 | 3 | 10,140 |
| 15 | Caponfield | 2 | ... | 2 | ... |
| 16 | Chillington | ... | ... | 2 | 6,240 |
| 17 | Corbyn's Hall | ... | ... | 4 | 7,350 |
| 18 | Dudley Port | 1 | 2,340 | 1 | 2,340 |
| 19 | „ | ... | ... | 2 | 4,060 |
| 20 | Deepfield | 2 | ... | 2 | ... |
| 21 | Deepdale | 1 | 2,084 | 1 | 1,634 |
| 22 | Dudley Wood | 4 | 10,467 | 4 | 8,664 |
| 23 | Eagle | 2 | 4,900 | 2 | 6,656 |
| 24 | Fiery Holes | 1 | ... | 1 | 1,634 |
| 25 | Glebe | 1 | ... | 1 | ... |
| 26 | Gospel Oak | 2 | 5,312 | 4 | 6,840 |
| 27 | Gold's Green | 2 | 4,888 | 3 | 9,412 |
| 28 | Graveyard | 1 | ... | 1 | ... |
| 29 | Gornal Wood | 1 | 1,671 | 1 | ... |
| 30 | Horseley | 2 | 4,308 | 2 | 4,680 |
| 31 | Hale Fields | 1 | 2,454 | 1 | 2,454 |
| 32 | High Fields | 2 | ... | 2 | ... |
| 33 | Lea Brook | 1 | ... | 1 | ... |
| 34 | Leys | ... | ... | 2 | 4,160 |
| 35 | Leval | 4 | 6,464 | 4 | ... |
| 36 | „ Old | 1 | 2,072 | 1 | 1,028 |
| 37 | Mill Fields | 4 | 6,768 | 4 | 8,112 |
| 38 | Moorcroft | 2 | 3,700 | 2 | 4,791 |
| 39 | Netherton | 2 | 1,406 | 2 | 5,033 |
| 40 | Oldbury | 2 | 2,600 | 2 | 5,720 |
| 41 | Old Park | 1 | 2,600 | 2 | 5,280 |
| 42 | Priestfield | 3 | 3,664 | 3 | 4,897 |
| 43 | Parkfield | ... | ... | 4 | 9,500 |
| 44 | Parkhead | 1 | 2,289 | 1 | 2,468 |
| 45 | Rough Hills | 2 | ... | 2 | ... |
| | Carried forward | 71 | 112,236 | 92 | 164,549 |

SOUTH STAFFORDSHIRE—*continued.*

| — | Furnaces. | 1823. | | 1830. | |
|----|----------------------|---------------------------|------------------|---------------------------|------------------|
| | | Total Number of Furnaces. | Pig Iron Made. | Total Number of Furnaces. | Pig Iron Made. |
| | Brought forward . | 71 | Tons. 112,236 | 92 | Tons. 164,549 |
| 46 | Russell's Hall . . . | ... | ... | 2 | 2,080 |
| 47 | Stow Heath . . . | ... | ... | 3 | 5,408 |
| 48 | Toll End . . . | 3 | 5,075 | 3 | 6,112 |
| 49 | Tipton Company . . | 3 | 5,640 | 3 | 3,515 |
| 50 | Tipton . . . | 1 | 2,040 | 1 | 2,040 |
| 51 | Union . . . | ... | ... | 2 | 4,650 |
| 52 | Wednesbury Oak . . | 2 | 6,240 | 3 | 7,684 |
| 53 | Willingsworth . . | ... | ... | 3 | 5,704 |
| 54 | Wolverhampton . . | ... | ... | 2 | 3,200 |
| 55 | Walbrook . . . | 1 | 2,359 | 2 | 2,886 |
| 56 | Windmill End . . . | ... | ... | 2 | 3,776 |
| | Total . . . | 81 | 133,590 | 118 | 211,604 |

Showing an increase in seven years of 37 furnaces and 79,014 tons of pig iron, or an increase of 58 per cent. The average yield per furnace in 1823 being 1,640 tons, compared with 1,793 tons in 1830. The works at Barbor's Field were erected between the years 1826 and 1828, and the undermentioned as follows :—

| Works. | Year. | Works. | Year. |
|----------------------|----------|--------------------|----------|
| Brettle Lane . . . | 1825 | Stow Heath . . . | 1824 and |
| Chillington . . . | 1829 | Union . . . | 1825 |
| Corbyn's Hall . . . | 1825 and | Willingsworth . . | 1828 |
| Dudley Port . . . | 1829 | Wolverhampton . . | 1827 and |
| Levels . . . | 1824 | Windmill End . . . | 1828 |
| Parkfield . . . | 1828 | | 1824 and |
| Russell's Hall . . . | 1825 and | | 1826 |
| | 1827 | | 1825 |

We have now reached a period when the hot blast was coming into use; this invention of Mr. Neilson was first successfully employed in the furnaces of Scotland, and gradually extended into other iron-making districts.

In 1830, when the production of South Staffordshire was 211,604 tons, Scotland produced but 37,500 tons; while the total make of the furnaces in Great Britain did not exceed 652,417 tons.

The number of furnaces built and in blast, the make of pig iron, and the average yield per furnace appear in the annexed table :—

SOUTH STAFFORDSHIRE AND WORCESTERSHIRE.

| Year. | FURNACES. | | Production of Pig Iron. | Average make per Furnace. |
|-------|-----------|-----------|----------------------------|------------------------------|
| | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Tons. |
| 1840 | 135 | 116 | 407,150 | 3,510 |
| 1847 | 139 | 77 | 320,320 | 4,070 |
| 1851 | 148 | 105 | 600,000 | 5,714 |
| 1852 | 159 | 127 | 725,000 | 5,693 |
| 1854 | 175 | 145 | 743,600 | 5,128 |
| 1855 | 178 | 146 | 754,000 | 5,164 |
| 1856 | 171 | 147 | 777,171 | 5,287 |
| 1857 | 180 | 153 | 657,295 | 4,300 |
| 1858 | 186 | 147 | 597,809 | 4,067 |
| 1859 | 184 | 123 | 475,300 | 3,864 |
| 1860 | 181 | 108 | 469,500 | 4,347 |
| 1861 | 182 | 114 | 395,650 | 3,470 |
| 1862 | 191 | 107 | 610,220 | 5,703 |
| 1863 | 200 | 110 | 691,157 | 6,283 |
| 1864 | 176 | 106 | 628,973 | 5,934 |
| 1865 | 172 | 114 | 692,627 | 6,075 |
| 1866 | 167 | 112 | 532,625 | 4,755 |
| 1867 | 177 | 91 | 515,638 | 5,666 |
| 1868 | 172 | 89 | 532,234 | 5,980 |
| 1869 | 164 | 95 | 569,562 | 5,995 |
| 1870 | 171 | 114 | 588,540 | 5,163 |
| 1871 | 163 | 108 | 725,716 | 6,720 |

Coal and Iron Ore used in Manufacture.—Since the year 1872, information under both these heads is available; it will, therefore, be convenient to tabulate the returns of production of pig iron in each year since that date, and follow with the quantities of coal and iron ore of all kinds employed; the returns are as follows:—

| Year. | FURNACES. | | Pig Iron Made. | Coal Used. | Iron Ore, &c., Used. |
|-------|-----------|-----------|-------------------|------------|-------------------------|
| | Built. | In Blast. | | | |
| | Nos. | Nos. | Tons. | Tons. | Tons. |
| 1872 | 145 | 107 | 673,470 | 1,932,509 | 1,800,000 |
| 1873 | 142 | 99 | 673,397 | 1,968,580 | 1,800,000 |
| 1874 | 154 | 81 | 452,400 | 1,309,216 | 1,195,600 |
| 1875 | 155 | 76 | 474,540 | 1,353,850 | 1,268,000 |
| 1876 | 147 | 65 | 465,946 | 1,262,962 | 1,235,000 |
| 1877 | 146 | 57 | 428,276 | 1,032,419 | 1,123,500 |
| 1878 | 147 | 55 | 392,949 | 917,106 | 1,005,900 |
| 1879 | 140 | 44 | 325,780 | 743,006 | 830,500 |
| 1880 | 137 | 45 | 384,556 | 878,581 | 984,500 |

In the beginning of the present century the average quantity of coal required in the manufacture of a ton of pig iron was ten tons. About the year 1810, Mr. R. Mushet states, in his valuable papers on iron and steel, that half this quantity enabled the ironmaster to produce a ton of pig iron. After the introduction of the hot blast by Mr. J. B. Neilson, the economy in the consumption of fuel becomes more apparent, for we learn that in the year 1840, on the authority of Mr. William Jessop, that the quantity did not exceed 8 tons 17 cwt. in the works of South Staffordshire; while the average used in Great Britain the same year was but 4 tons 1 cwt., compared with 10 tons in the year 1800. In the year 1869 the Royal Coal Commission reported on this important question, and ascertained that a further economy had been secured, 3 tons of coal only being required.

In the years 1871 and 1872 the average quantity of coal used in South Staffordshire was about 58 cwt. In the furnaces of Great Britain in each of the same years the average was 51 cwt.; while in Scotland, where raw uncoked coal is principally used, 55 cwt. of coal was required to each ton of pig iron made.

In most of our iron making districts the waste gases are utilised and great economy secured; here, however, in South Staffordshire, but few furnaces were provided with gas saving apparatus (these arrangements are now being more generally employed), and hence the increased consumption of coal with other districts comparatively.

Of the coal employed in iron making, the "Thick Coal" and the Heathen Coal are the most important, the former giving, when coked, 54 per cent., with 0·31 of sulphur and 4·18 of ash; the latter between 40 and 45 per cent. of coke, 0·51 of sulphur, and 4·58 of ash; while generally, in the district, the coal is used partly raw and partly coked.

The "Native Mine," or clay ironstone of the coal measures of this district, if alone employed, would require from 54 to 55 cwt. of raw uncalcined ore, to each ton of pig iron made, a smaller quantity being required when richer ores used in admixture are employed. It was ascertained approximately, that in the years 1872 and 1873 the quantity of iron ore of all kinds used in the manufacture of 673,470 tons of pig iron was 1,800,000 tons in each year, the following districts furnishing quantities in the proportion given:—

| DISTRICTS. | TONS. |
|---------------------------------|------------------|
| South Staffordshire | 600,000 |
| North Staffordshire | 550,000 |
| Lancashire | 55,000 |
| Northamptonshire | 230,000 |
| Oxfordshire | 19,000 |
| Various ores | 206,000 |
| Forge and mill cinder | 140,000 |
| Total Ore | <u>1,800,000</u> |

The quantity classed as "various ores" includes ores from Wales, Warwickshire, Gloucestershire, Cleveland, and elsewhere, but it has not been possible to distinguish the proportion received from each district. As previously stated the "Native mine" of this district yields an average of 84·75 per cent. of metallic iron, compared with the ironstone of North Staffordshire, which gives 86·50 per cent., and the Churnet Valley ore nearly 87 per cent. The Northamptonshire and Oxfordshire ores, hydrated peroxides so valuable in admixture with the coal measure ores as a flux, their siliceous character not being injurious, yield 40 per cent. of metallic iron, the hematite of Lancashire about 64 per cent., and the forge and mill cinders probably not less than 50 per cent. These cinders are largely employed in the production of common hot-blast pig, while the best mine pig, for which Staffordshire is so justly celebrated, is made from "Native mine," and other selected ores, coal previously coked, and cold air in the blast furnace.

In the calcination of the ironstone two modes are practised, namely, in clamps and kilns. In clamp calcining it is customary first to spread a layer of coal in lumps upon the ground and on this to raise the heap of ironstone, interspersing coal occasionally, and then to cover the surface of the heap with slack. In the calcination of "black band," the carbonaceous matter it contains is sufficient to effect the operation. The "heaps," or "clamps" are made from 6 to 8 feet high, and vary considerably in area, sometimes having an area of half an acre.

In the operation, as in brickmaking, the calcined stone is being removed from one end while the heap is being freshly made at the other end. The heap being ignited burns through in a smouldering way, emitting a good deal of smoke, a little flame breaking through the surface in places. An ordinary-sized clamp takes about three weeks to become thoroughly calcined, and at the end

of this time it is found to be reduced to about one half its original bulk.

For calcining in kilns an ordinary open kiln, like a common egg-shaped lime-kiln, is sometimes used; but for the most part iron cup-shaped kilns, made of iron plates lined with fire-brick, are employed. They are about 24 feet in height, and so arranged that while the ore and fuel can be fed in continuously above, the calcined ore is discharged at the bottom, either upon a raised platform or directly into the waggons that are to carry it away. The kiln once ignited, all that is necessary is from time to time to throw in a layer of coal on the top of a charge of stone.

The forge and mill cinder often used as a material for the smelting of pig iron and producing a variety of iron known as "cinder iron," which is made to some extent in South Staffordshire, calls for a brief notice. The "tap cinder,"* as described by Dr. Ballard, "is the slag drawn out from puddling furnaces in which pig iron has been made into malleable iron. It consists mainly of protoxide of iron and siliceous matter, the latter partly derived from the bricks with which the reverberatory furnace is lined. In fact, it is the bath of 'fettle,' rich in peroxide of iron, which in the process of puddling has given up its excess of oxygen to oxidise the carbon, silicon, sulphur, and phosphorus which the pig iron contains, and which have, in the process of puddling, to be, as far as practicable, removed. The tap cinder, in order to fit it again for use in fettling, requires that the iron it contains should be peroxidised."

In either case the "tap cinder" requires calcination when it is employed for "fettling," that is, for lining puddling furnaces. With the object above described the calcination is performed in what is termed a "bull dog" kiln, the resulting material going under the technical designation of "bull dog." A bull dog kiln is constructed very much like a Scotch brick-kiln, 9 or 10 feet high, with side walls, having opposite fire openings at intervals, and the tap cinder to be calcined is first built up at the bottom so as to form channels or passages from the fire openings on one side to those on the other. The cinder, broken up, is then filled in with alternating layers of coal up to the top of the kiln. The ends are bricked up and the kiln lighted. It burns out in about

* Local Government Board. Eighth Report, 1878-79, p. 238.

a week. The fire should not be too fierce or the tap cinder merely melts down and may then form a hard mass which can scarcely be extracted except by blasting. When the kiln has gone out, the calcined material or "bull dog" is found in a coherent mass, which has to be broken down with a pick. For making cinder iron it is usual to calcine the cinder in a large clamp or heap, frequently 25 feet high, and containing many thousand tons. The heap is made much in the same way, with coal at the bottom and interspersed, as an ironstone clamp; the average consumption of fuel being about 6 or 7 cwt. to each ton of cinder, the heaps usually burning out in about a fortnight.

The most recent statement showing the works, furnaces built and in blast in South Staffordshire, appears as follows for the year 1880:—

SOUTH STAFFORDSHIRE.

| No. | Name of Works. | Owners. | FURNACES. | |
|-----|-------------------------------|---|-----------|-----------|
| | | | Built. | In Blast. |
| | | | Nos. | Nos. |
| 1 | Barbor's Field, Bilston | Barbor's Field Co. | 2 | 1 |
| 2 | Bovereux, " | Thomas Holcroft | 2 | 1 |
| 3 | Deepfields, " | Deepfields Iron Co. | 3 | 0 |
| 4 | The Brook, " | The Brook Furnaces Iron Co. | 3 | 0 |
| 5 | Herbert Park, " | David Jones & Sons | 1 | 0 |
| 6 | Prior Field, " | H. B. Whitehouse & Son | 3 | 3* |
| 7 | Millfield, " | W. and J. S. Sparrow & Co. | 3 | 1 |
| 8 | Spring Vale, " | Alfred Hickman | 4 | 4† |
| 9 | Capponfield, " | John Bagnall & Sons, Limited | 3 | 1 |
| 10 | { Horseley Fields, Wolver- | Osier Bed Iron Co. | 3 | 0 |
| | { hampton | | | |
| 11 | Old Park, " | { Wolverhampton and Stafford- | 3 | 0 |
| | | { shire Banking Co. | | |
| 12 | Chillington, " | Chillington Iron Co., Limited | 4 | 0 |
| 13 | Gold's Hill, West Bromwich | John Bagnall & Sons, Limited | 3 | 2‡ |
| 14 | Crookhay, " | H. O. Firmstone | 4 | 0 |
| 15 | Corbyn's Hall, Dudley | Wm. Matthews & Co., Limited | 3 | 1§ |
| 16 | Netherton, " | M. and W. Graisebrook | 2 | 1 |
| 17 | " | J. H. Pearson | 2 | 2 |
| 18 | Parkhead, " | Phillips and McEwen | 2 | 1 |
| 19 | Woodside, " | Cochrane & Co. | 2 | 2 |
| 20 | Windmill End, " | Sir Horace St. Paul, Bart. | 3 | 1 |
| 21 | Buffery, " | John Jones & Son | 1 | 1 |
| 22 | Old Hill, " | N. Hingley & Sons | 2 | 1 |
| 23 | Corngreaves, " | The New British Iron Co. | 6 | 2 |
| 24 | Old Level, " | James Holcroft | 2 | 0 |
| 25 | New Level, Brierley Hill | Earl of Dudley | 5 | 3 |
| 26 | Coneygre, Dudley Port, Tipton | " | 3 | 1 |
| | Carried forward | | 74 | 29 |

* One furnace for ten months.

† One furnace for three months.

‡ One furnace for eight months.

§ One furnace for six months.

SOUTH STAFFORDSHIRE—continued.

| No. | Name of Works. | Owners. | FURNACES. | |
|------------------------------|---|---|-----------|-----------|
| | | | Built. | In Blast. |
| | Brought forward . . . | | Nos. 74 | Nos. 29 |
| 27 | Lays, Dudley Port, Tipton . . | W. and G. Firmstone . . . | 3 | 1 |
| 28 | Shut End, Dudley . . . | John Bradley & Co. . . . | 4 | 1 |
| 29 | Corbyn's Hall, New Dudley . . | Bromley Coal and Iron Co. . | 4 | 0 |
| 30 | Broadwaters, Wednesbury . . | Samuel Groucutt & Sons . . | 3 | 1 |
| 31 | { Darlaston Steel and Iron, } Wednesbury . . . | Darlaston Iron and Steel Co., Lim. | 1 | 0 |
| 32 | Priestfields, New, Willenhall . | William Ward & Sons . . . | 2 | 0 |
| 33 | Rough Hills, Wednesbury . . | Addenbrook, Smith, & Pidecock | 3 | 1 |
| 34 | Old Park, " . . . | { Patent Shaft and Axletree Co., } Limited . . . | 3 | 0 |
| 35 | Willingsworth, " . . . | Willingsworth Iron Co. . . . | 2 | 1 |
| 36 | Moxley, " . . . | David Rose | 2 | 0 |
| 37 | Hatherton, Walsall . . . | George and Richard Thomas . | 2 | 0 |
| 38 | Pelsall, " . . . | Pelsall Coal and Iron Co. . . | 2 | 1 |
| 39 | Green Lane, " . . . | Walsall Iron Co. | 2 | 1 |
| 40 | Bentley, " . . . | Chillington Iron Co. | 2 | 0 |
| 41 | Willenhall, " . . . | The Willenhall Furnaces, Lim. . | 3 | 2* |
| 42 | Castle, " . . . | Castle Coal and Iron Co., Lim. . | 2 | 0 |
| 43 | Tipton Green, Tipton . . . | Roberts & Co. | 4 | 3 |
| 44 | Hange (Tivdale), " . . . | Round Brothers | 2 | 1 |
| 45 | Horseley, " . . . | { John Colbourn & Sons . . . | 4 | 1 |
| 46 | Park Lane, " . . . | Thos. Turley & Sons | 2 | 1 |
| 47 | Coseley Moor, " . . . | Philip Williams & Sons . . . | 2 | 1 |
| 48 | Wednesbury Oak, " . . . | G. H. Hickman | 1 | 0 |
| 49 | Groveland, Smethwick . . . | W. and E. Onions | 2 | 0 |
| 50 | Brades Hall, " . . . | Thomas Crew | 2 | 0 |
| 51 | Park Lane | { Stour "Valley Coal and Iron } Co., Limited | 3 | 0 |
| 52 | Union Valley | Thomas Crew | 1 | 0 |
| 53 | Stonefield | | | |
| Total of South Staffordshire | | | 137 | 45 |

Malleable Iron Works:—Bessemer Steel Works, and Coal employed.—The malleable iron works of this district are by far the most numerous, and the manufacture the most varied, of the iron producing districts of Great Britain, including heavy iron works for railways, pit chains, cables, anchors, and the different forms of iron fashioned from the rolling and slitting mills. The great importance of the district will be understood from the annexed table, showing the number of works in South Staffordshire in each year since 1863, with their aggregate power of production, appearing in the number of puddling furnaces and rolling mills, in each of the years named; and for comparison the total number in Great Britain in each of the same years:—

* One furnace for four months.

| Year. | SOUTH STAFFORDSHIRE. | | | GREAT BRITAIN. | | |
|-------|----------------------|-----------------------|-------------------|----------------|-----------------------|-------------------|
| | Works. | Puddling Furnaces. | Rolling Mills. | Works. | Puddling Furnaces. | Rolling Mills. |
| | Nos. | Nos. | Nos. | Nos. | Nos. | Nos. |
| 1863 | 118 | 1,821 | 226 | 223 | 5,013 | 654 |
| 1865 | 118 | 2,116 | 224 | 252 | 6,407 | 730 |
| 1867 | 115 | 1,801 | 283 | 254 | 6,009 | 831 |
| 1869 | 110 | 1,700 | 282 | 245 | 6,243 | 859 |
| 1871 | 122 | 2,037 | 320 | 267 | 6,841 | 866 |
| 1872 | 125 | 2,155 | 329 | 276 | 7,311 | 1,015 |
| 1873 | 124 | 2,145 | 327 | 287 | 7,264 | 939 |
| 1874 | 123 | 2,073 | 320 | 298 | 6,803 | 866 |
| 1875 | 131 | 2,046 | 329 | 314 | 7,575 | 909 |
| 1876 | 129 | 2,009 | 342 | 312 | 7,159 | 942 |
| 1877 | 125 | 1,936 | 338 | 300 | 6,796 | 935 |
| 1878 | 127 | 1,684 | 303 | 312 | 5,125 | 830 |
| 1879 | 126 | 1,589 | 306 | 312 | 5,455 | 846 |
| 1880 | 125 | 1,625 | 311 | 314 | 5,134 | 855 |

The process of puddling may be briefly stated as consisting of the conversion of pig iron into malleable iron. This is effected by one or more operations, which are necessarily of an oxidising nature, the object being to eliminate from the cast iron the carbon in the form of carbonic oxide gas, and the silicon, sulphur, phosphorus, and other foreign bodies in the form of oxidised products, which pass either partially or wholly into the scoræ or cinder. The pig iron is either subjected to a preliminary decarburisation in the oxidising blast hearth, or refinery, and the operation thus commenced afterwards completed in the oxidising air-furnace, or puddling furnace, or the complete conversion of the crude iron is effected by one operation in the puddling furnace by the process called "boiling." This process was first introduced in the Bloomfield Works of Mr. Joseph Hall, of Tipton, about the year 1811, and consists essentially in the decarburisation of the pig iron by contact with oxidised compounds of iron, whereby carbonic oxide is produced below the surface of the molten metal and in escaping causes the appearance of ebullition or boiling.

The Bessemer steel works of the district are represented by the Old Park Works at Wednesbury, consisting of four converters, each of a capacity of three tons.

The following is a complete list of the works in South Staffordshire and East Worcestershire in the year 1880, with the number of puddling furnaces and rolling mills :—

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-----------------------|--|---|----------------------------------|---------------------------|-----------------------|
| 1 | Brick House . . . | R. Williams & Co. . . | West Bromwich . . | 7 | 2 |
| 2 | Bromford . . . | Jno. Dawes & Sons . . | " . . . | 63 | 7 |
| 3 | Hall End . . . | J. T. and W. E. Johnson . . | " . . . | 9 | 2 |
| 4 | Ridgacre . . . | " . . . | " . . . | 15 | 2 |
| 5 | Waterloo . . . | " . . . | " . . . | 12 | 1 |
| 6 | Crook Hay . . . | W. and G. Firnstone . . | " . . . | 13 | 2 |
| 7 | Witton Lane . . . | Roberts & Co. . . | " . . . | 11 | 2 |
| 8 | Excelsior . . . | Thos. P. Allen & Co. . . | " . . . | 9 | 1 |
| 9 | Eagle . . . | Eagle Coal and Iron Co. . . | " . . . | 15 | 2 |
| 10 | Staffordshire . . . | Star Iron and Tin Plate Co. . . | " . . . | .. | .. |
| 11 | Providence . . . | Bridge, Gill, & Bridge . . | " . . . | 22 | 2 |
| 12 | Roway . . . | Edward Page & Sons . . | " . . . | 20 | 3 |
| 13 | Stour Valley . . . | { Patent Nut and Bolt Co., Limited . . . } | " . . . | 10 | 1 |
| 14 | Dunkirk . . . | { Thos. Jordan and P. Pearson . . . } | " . . . | 9 | 3 |
| 15 | Wellington . . . | Allen & Holden . . . | " . . . | 11 | 2 |
| 16 | Gold's Hill, New . . | Thomas Davis & Co. . . | " . . . | 12 | 2 |
| 17 | Bush Farm . . . | John J. Bowater & Sons . . | " . . . | .. | .. |
| 18 | Richmond . . . | Samuel Downing . . . | " . . . | 10 | 2 |
| 19 | Albion . . . | Edward Hall . . . | " . . . | .. | .. |
| 20 | " . . . | Albion Sheet Iron Co. . . | " . . . | .. | .. |
| 21 | Britannia . . . | Britannia Iron Co. . . | " . . . | 10 | 1 |
| 22 | Atlas . . . | Parkes and Parkes . . . | " . . . | 10 | 3 |
| 23 | Rabone Bridge . . . | Rabone Bridge Iron Co. . . | Smethwick . . . | .. | .. |
| 24 | Excelsior . . . | { South Staffordshire Joint Stock Co. . . } | " . . . | 7 | 1 |
| 25 | Anchor . . . | Batson and Ratcliffe . . | " . . . | 6 | 1 |
| 26 | District . . . | District Iron and Steel Co. . . | " . . . | 20 | 4 |
| 27 | Cape Town . . . | W. R. Brookes . . . | " . . . | 7 | 2 |
| 28 | Crown . . . | Thos. L. Nicklin . . . | " . . . | 11 | 3 |
| 29 | London and Lion . . | London Works Iron Co. . . | " . . . | 9 | 3 |
| 30 | Vulcan . . . | Parkes . . . | " . . . | .. | .. |
| 31 | Regents Grove . . . | Beard and Eberhard . . | " . . . | 13 | 6 |
| 32 | Sandwell . . . | Lones, Vernon, & Holden . . | " . . . | 16 | 3 |
| 33 | { Monner Lane and Batman's Hill . . } | Monner Lane Iron Co. . . | Willenhall . . . | 24 | 8 |
| 34 | Spring Bank . . . | Catherine Tipper . . . | " . . . | .. | 1 |
| 35 | Dixon's Green . . . | Frederick Cresswell . . | Dudley . . . | 11 | 1 |
| 36 | Dudley Port . . . | Plant and Fisher . . . | " . . . | 20 | 4 |
| 37 | Groveland . . . | G. H. Hickman . . . | " . . . | .. | .. |
| 38 | Netherton . . . | Noah Hingley & Sons . . | " . . . | 41 | 4 |
| 39 | Shut End . . . | Jno. Bradley & Co. . . | " . . . | 23 | 0 |
| 40 | Globe . . . | Tivdale Iron Co. . . | Tipton . . . | .. | .. |
| 41 | Tivdale . . . | " . . . | " . . . | .. | .. |
| 42 | Alpha . . . | Joshua Wilkinson & Sons . . | " . . . | 8 | 2 |
| 43 | Bloomfield . . . | Wm. Barrows & Sons . . | " . . . | 58 | 8 |
| 44 | Crown . . . | Edward Bayley . . . | " . . . | 7 | 2 |
| 45 | Church Lane . . . | Hoddell and Whitehouse . . | " . . . | 13 | 1 |
| 46 | Albert . . . | John Gittings & Co. . . | " . . . | 10 | 2 |
| 47 | Gospel Oak . . . | Tipton Iron and Wire Co. . . | " . . . | .. | .. |
| 48 | Summer Hill . . . | W. Millington & Co. . . | " . . . | 5 | 4 |
| 49 | Wednesbury Oak . . | Philip Williams & Sons . . | " . . . | 22 | 5 |
| 50 | Portfield . . . | James and Chas. Holcroft . . | " . . . | 13 | 4 |
| 51 | Lea Brook . . . | Chillington Iron Co., Lim. . . | " . . . | .. | .. |
| 52 | Brades (Iron and Steel) | Wm. Hunt & Sons . . . | Oldbury . . . | 3 | 4 |
| 53 | Ebenezer . . . | Thomas Perry . . . | " . . . | 12 | 3 |
| 54 | Park Lane . . . | F. R. Simpson & Co. . . | " . . . | 9 | 1 |
| 55 | Great Bridge . . . | { Great Bridge Iron and Steel Co., Limited . . } | Great Bridge . . . | 24 | 2 |
| 56 | Sheep Wash . . . | Stonecutter and Co. . . | " . . . | .. | .. |
| 57 | Gothersley . . . | William Finemore . . . | Stourbridge . . . | .. | 2 |
| 58 | Bromley . . . | John Raybould . . . | " . . . | 16 | 2 |
| 59 | Broadwaters . . . | Hatton, Sons, & Co. . . | " . . . | 27 | 7 |
| 60 | Leys . . . | Brown and Freer . . . | " . . . | 32 | 7 |
| 61 | Hyde . . . | H. O. Fernestone . . . | " . . . | 20 | 7 |
| 62 | Stourbridge . . . | Jno. Bradley & Co. . . | " . . . | .. | .. |
| 63 | Whittington . . . | James Williams & Co. . . | " . . . | 8 | 3 |
| 64 | Swindon . . . | E. F. and W. Baldwin . . | " . . . | .. | .. |
| Carried forward . . . | | | | 773 | 149 |

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|---|-------------------------|---|----------------------------------|---------------------------|-----------------------|
| | Brought forward | | | 773 | 149 |
| 65 | Bank Field . . . | S. Groucutt & Sons . . . | Bilston . . . | 21 | 4 |
| 66 | Bradley Field . . . | " . . . | " . . . | 23 | 4 |
| 67 | Bilston Mill and Forge | W. & J. S. Sparrow & Co. | " . . . | 26 | 3 |
| 68 | Bradley Tin Plate . . . | Hatton, Sons, & Co. . . | " . . . | 6 | 4 |
| 69 | Bradley, New . . . | Gitting and Tolley . . . | " . . . | 11 | 1 |
| 70 | Deepfields . . . | Geo. Tinn & Co. . . | " . . . | 20 | 7 |
| 71 | Bridge . . . | David Jones & Sons . . . | " . . . | " | " |
| 72 | Herbert's Park . . . | " . . . | " . . . | " | " |
| 73 | Regent . . . | George Onions . . . | " . . . | 9 | 3 |
| 74 | Stonefield . . . | Bilston Iron Co. . . | " . . . | " | " |
| 75 | Factory . . . | " . . . | " . . . | 18 | 5 |
| 76 | Ettingshall . . . | The Barbor's Field Co. . . | " . . . | " | " |
| 77 | Moxley . . . | Thos. and Chas. Wells . . . | " . . . | " | " |
| 78 | Bradley Hall . . . | J. E. East & Co. . . | " . . . | 3 | 1 |
| 79 | Capponfield . . . | Chillington Iron Co., Lim. . . | " . . . | " | " |
| 80 | Brockmop . . . | Budd & Co. . . | Brierley Hill . . . | 2 | 6 |
| 81 | Delph . . . | { Delph Forge and Roll- ing Mills Co. . . | " . . . | " | " |
| 82 | Harts Hills . . . | Hingleys and Smith . . . | " . . . | 34 | 4 |
| 83 | Round Oak . . . | Earl of Dudley . . . | " . . . | 55 | 5 |
| 84 | New Level . . . | " . . . | " . . . | " | " |
| 85 | Brettle Lane . . . | Thos. Webb & Sons . . . | " . . . | 10 | 2 |
| 86 | Brockmoor . . . | Jno. Bradley & Co. . . | " . . . | " | " |
| 87 | Brierley . . . | " . . . | " . . . | 10 | 8 |
| 88 | Corngraves . . . | New British Iron Co. . . | " . . . | 60 | 3 |
| 89 | Providence . . . | Joseph Penn & Co. . . | " . . . | 7 | 1 |
| 90 | Old Level . . . | Henry Hall . . . | " . . . | 16 | 2 |
| 91 | Cradley . . . | S. Evers & Sons . . . | " . . . | 16 | 3 |
| 92 | Monnmoor . . . | E. T. Wright & Sons . . . | Wolverhampton . . . | 25 | 6 |
| 93 | Mars . . . | Geo. Adams & Sons . . . | " . . . | 25 | 6 |
| 94 | Minera Iron and Steel | Isaac Jenks & Sons . . . | " . . . | 12 | 5 |
| 95 | Beaver . . . | " . . . | " . . . | 7 | 3 |
| 96 | Swan Gardens . . . | John Lynaught . . . | " . . . | 24 | 7 |
| 97 | Horweley Fields . . . | Ostler Bed Iron Co. . . | " . . . | 12 | 3 |
| 98 | Chillington . . . | Chillington Iron Co., Lim. . . | " . . . | 62 | 12 |
| 99 | Horweley Fields . . . | E. P. and W. Baldwin . . . | " . . . | 3 | 1 |
| 100 | Cleveland . . . | Cleveland Iron Co. . . | " . . . | 10 | 1 |
| 101 | Manor . . . | Stephen Thomson . . . | " . . . | 10 | 2 |
| 102 | Birchills . . . | James Bissell . . . | Walsall . . . | 13 | 1 |
| 103 | Birchills Hall . . . | { Birchills Hall Iron Co., Limited . . . | " . . . | 12 | 4 |
| 104 | Staffordshire . . . | Bunch & Sons . . . | " . . . | 12 | 6 |
| 105 | Pelsall . . . | { Pelsall Coal and Iron Co., Limited . . . | " . . . | 42 | 6 |
| 106 | Victoria (Pleck) . . . | Henry Mills & Sons . . . | " . . . | 6 | 1 |
| 107 | Cyclops . . . | { John Russell & Co., Limited . . . | " . . . | 17 | 2 |
| 108 | Cormorant . . . | Harrison, Hopkins, & Harrison . . . | " . . . | 11 | 2 |
| 109 | Churchbridge . . . | W. Gilpin, sen., & Co. . . | " . . . | 8 | 2 |
| 110 | Darlaston Green . . . | { Darlaston Coal and Iron Co., Limited . . . | Darlaston . . . | " | " |
| 111 | King's Hill . . . | " . . . | " . . . | " | " |
| 112 | Old Park . . . | { Patent Shaft and Axle- tree Co., Limited . . . | Wednesbury . . . | 38 | 4 |
| 113 | Monway Iron and Steel | " . . . | " . . . | " | " |
| 114 | Brunswick . . . | " . . . | " . . . | " | " |
| 115 | Bull's Bridge . . . | W. Molineux & Co. . . | " . . . | 48 | 5 |
| 116 | Monway . . . | John Marshall & Co. . . | " . . . | 7 | 2 |
| 117 | Bull's Bridge . . . | Southan, Bradley, & Co. . . | " . . . | 5 | 2 |
| 118 | Victoria . . . | David Rose . . . | " . . . | 10 | 3 |
| 119 | Toll End . . . | Jno. Bagnall & Sons, Lim. . . | Tipton . . . | " | " |
| 120 | Lea Brook . . . | " . . . | " . . . | 66 | 7 |
| 121 | Gold's Hill . . . | " . . . | West Bromwich . . . | " | " |
| 122 | Imperial . . . | " . . . | Wednesbury . . . | " | " |
| 123 | Hinksford . . . | T. and G. Hall . . . | King's Winford . . . | " | " |
| 124 | Cookley . . . | Jno. Knight & Co. . . | Kidderminster . . . | 16 | 4 |
| 125 | Wilden . . . | E. P. and W. Baldwin . . . | Stourport . . . | 5 | 5 |
| Total of South Staffordshire and Worcestershire . . . | | | | 1625 | 311 |

Coal used in Malleable Iron Works.—In considering the question of the consumption of coal in the malleable iron and steel works of this district, although great care has been taken to ascertain the quantities used, it is only possible to arrive at an approximate result. It may, however, be generally stated that the average quantity of coal used annually in a puddling furnace in this district, working regularly throughout the year, (deduced from numerous returns,) varies between 800 and 900 tons, or an aggregate annual consumption of not less than 1,600,000 tons in 1863, increased to nearly 2,000,000 tons from 1871 to 1876, and a diminished consumption since that period. These quantities include fuel used in the tin-plate works, as well as the fuel employed for all purposes where heat is required. The total coal employed in these works in 1879 was 1,567,600 tons, and in 1880 it amounted to 1,656,958 tons.

Prices of Finished Iron.—It is scarcely necessary to describe the general qualities of Staffordshire iron. These are well known to every one engaged in the iron trade. Forty years ago an eminent authority, in writing on the characteristic differences between the cast iron made in different parts of Great Britain, observed that "the Staffordshire metal runs remarkably fluid and makes fine sharp castings. The Welsh is strong, less fluent, but is said to produce bar iron of superior quality. The Derbyshire iron also forms excellent castings, and may be worked with care into very good bar iron. The cast iron produced in Staffordshire and Shropshire generally commands a higher price than the irons of other districts, except some of the best brands of the West Riding of Yorkshire."

The highest price ever attained in South Staffordshire for finished iron was £16 a ton, a price which it commanded in the summer of 1872. Its lowest point was £7 10s., which it stood at for barely two months in 1879, and which it has again touched. It has also previously approached the latter figure. In 1863 and two previous years its average price was £7 15s., and again in 1868—69 it sold at that price. Till 1872 what might be termed its normal price was between £8 and £9 a ton. The average price of Welsh bars, excepting the years 1872 and 1873, has been from £5 5s. to £6 6s. a ton. The greatest variation in prices took place during the last ten years, as appears from the following account of them for that period :—

PRICES OF SOUTH STAFFORDSHIRE MARKED IRON.

| Date. | Rise or Fall. | Price per Ton. | Number of Weeks Duration. |
|----------------------------|---------------|----------------|---------------------------|
| January 1, 1871 | ... | £ 8 0 | 35 |
| September 7, 1871 | Rise 10 | 8 10 | 25 |
| October 15, 1871 | " 10 | 9 0 | 5 |
| January 1, 1872 | " 40 | 11 0 | 5 |
| February 3, 1872 | " 20 | 12 0 | 10 |
| April 11, 1872 | " 10 | 12 10 | 3 |
| May 16, 1872 | " 10 | 13 0 | 5 |
| June 20, 1872 | " 20 | 14 0 | 1 |
| June 27, 1872 | " 20 | 15 0 | 2 |
| July 11, 1872 | " 20 | 16 0 | 12 |
| October 3, 1872 | Fall 40 | 14 0 | 4 |
| October 31, 1872 | " 40 | 12 0 | 11 |
| January 16, 1873 | Rise 20 | 13 0 | 4 |
| February 13, 1873 | " 20 | 14 0 | 4 |
| March 13, 1873 | " 40 | 16 0 | 16 |
| July 3, 1873 | Fall 40 | 14 0 | 52 |
| July 8, 1874 | " 40 | 12 0 | 13 |
| October 7, 1874 | " 20 | 11 0 | 38 |
| July 7, 1875 | " 20 | 10 0 | 42 |
| April 26, 1876 | " 20 | 9 0 | 71 |
| September 7, 1877 | " 10 | 8 10 | 54 |
| September 17, 1878 | " 20 | 7 10 | 7 |
| November 6, 1879 | Rise 10 | 8 0 | 7 |
| December 31, 1879 | " 20 | 9 0 | 13 |
| April 30, 1880 | Fall 20 | 8 0 | 22 |
| October 6, 1880 | " 10 | 7 10 | still current. |

This account of the market value of the finished iron of South Staffordshire indicates that it is used for special purposes. These purposes are almost innumerable. It has hitherto been regarded as an indispensable material for making the best quality of goods. There is scarcely any description of finished iron, excepting, of course, mild steel, that is not produced in South Staffordshire; from boiler-plates and rails, down to the most delicate and fanciful wares to be found in the ironmonger's shop. Of late years mild steel has come into competition with it for the heavier class of goods produced there, such as rails, boilers, girders, &c. But for many other purposes Staffordshire pig is still indispensable, such as ironmongery, chains, tin plates, gun barrels, nails, and similar articles.*

* *Colliery Guardian*, March 4, 1881, p. 331.

CHAPTER XII.

NORTHAMPTONSHIRE IRON INDUSTRIES.

Geology of the Ironstone Deposits of the Northampton Sand—Analyses, Production, and Distribution of Ironstone—Iron Mines in 1880—Pig Iron Manufacture—Early History—Direct Process (Dr. C. W. Siemens' Patent) for making Iron and Steel at Towcester—Iron Works in operation in 1880—Production of Pig Iron—Coal and Ironstone used in Pig Iron Manufacture.

Northamptonshire Ironstone Deposits.—The “Northampton sand,” a subdivision of the Lower Oolitic formation, in which those vast deposits of ironstone occur, reposes upon the Upper Lias Clay, and is composed of ferruginous sands, sandstones, and in some places assumes a concretionary character, in the form of a thin coating of ironstone, inclosing loose sand. In the neighbourhood of the iron-bearing districts the following table shows the superposition, in descending order, of the strata:—

Alluvium.

Gravel of the New and Ise Valleys.

Oxford Clay.

Cornbrash (Blue Limestone and clay).

Great Oolite (White Limestone and clay).

Northampton Sands (Iron Sand and Sandstones, the equivalent of the Stonesfield Slate).

Upper Lias Clay.

In the Upper Lias Clay there are numerous brick yards, in which brick-making is extensively carried on; lower in the geological series occurs the “Marlstone,” or “Middle Lias,” and the Lower Lias Clay below; while above the Northampton sand in the southern part of the county occurs the Great Oolite, consisting of light coloured limestones and clays, and higher still the Cornbrash and Oxford Clay. The beds of ironstone vary in thickness from 4 to 18 feet and even more, and with an equally varying “over-burden,” in some localities but a few feet; while at Cogenhoe and Woodford, the former a few miles from Northampton on the line to Peterborough, and the latter between

Thrapston and Kettering, it exceeds 20 feet, and in these places the stone was formerly mined by underground workings. At Cogenhoe the bed of ironstone is well defined, and has a thickness of 5 feet, the over-burden being composed of a loose reddish earth, associated with sand, in which fossils occur in abundance to a depth of 14 feet, and beneath this is a stratum of pure white sand (at times coloured with peroxide of iron), and having the appearance of chalk; the ironstone bed below has a slight dip to the north-east. The stone here obtained is very compact, and gives on analysis 42 per cent of metallic iron. At Gayton, to the west of Northampton, near Blisworth, the ironstone is from 10 to 14 feet thick, the over-burden being but a few feet, while at Easton Neston, near Towcester, it varies from 6 inches to 3 feet. Near Northampton, at Hunsbury Hill, the ironstone attains a thickness of from 12 to 14 feet, and with a covering of 5 feet, consisting of soil 2 feet, and 3 feet of fine white sand and marl below. In the north of the county and on the borders of Leicestershire, the bed of ironstone is well defined, extending for several miles along the Midland Railway to Finedon, and thence to Wellingborough, and as far as Blisworth and Gayton, and on to the town of Northampton. At Duston, near Northampton, stone is found fully 16 feet thick, and this is exceeded on some estates as previously stated, notably those at Woodford of Mr. Arbuthnot, and at Cranford, on the estate of Sir John Robinson, bart.; again, at Islip, between the last-named place and Thrapston. At Islip the ironstone is extensively wrought and smelted in the furnaces of the same name; the ironstone obtained in these districts is of very good quality. In other localities the stone is not so rich, it also varies considerably in weight, according to the richness, density, or other general character of the stone. A cubic yard of ironstone in "*situ*" with shale and adhering rock will weigh about 24 cwts.; but to weigh that it must be clean, and entirely free from sand, walls, dirt, &c. It will therefore be apparent that ironstone varying so much in thickness and containing numerous "faults," such as walls of sand and clay, that the actual yield or weight of the stone as it lies, cannot be accurately determined. Near the Midland Railway at Wellingborough, where the ironstone has been vigorously worked by the Messrs. Butlin & Co., it appears that one field of 9 acres, in which the thickness of the

bed of ironstone varied from 12 feet, 6 feet of which was solid rock, the remainder containing a good deal of "siftings" gave 98,286 tons of ironstone, an average of nearly 11,000 tons per acre, but some parts of the same field gave over 12,000 tons per acre. These facts will, so far as the ironstone is concerned, show conclusively its value in some districts, and its production per acre as well. The great seam of ironstone in Cleveland, be it remembered, yields 20,000 tons per acre. In another field, worked by the same firm at Wellingborough, the ironstone is from 15 to 16 feet thick, and some varieties of stone from this seam selected for analysis have given nearly 50 per cent. of metallic iron. The stone is worked from the surface as a quarry, and an interesting matter connected with the working of the ironstone at Wellingborough, is, as soon as it is got the land is made good again, and fit for agricultural purpose. In one tract of ground, now in a state of cultivation, no less than 200,000 tons of ironstone was obtained, and yet its appearance would not suggest that it had been disturbed. For the transport of the stone ample facilities are provided, trucks bringing coals to the iron works are quickly unloaded, and as quickly charged with ironstone at the mines or quarries, and moved on to the railway siding for exportation or otherwise.

Seeing that many of the old districts on which dependence was formerly placed for the supply of iron ore are gradually being exhausted, Northamptonshire is evidently destined to become an important iron-making centre. This appears in the increased activity from year to year, and the production, which in 1880 amounted to 1,550,108 tons, compared with 107,985 tons in the year 1857.

Analyses of the Ironstone.—The ironstone raised at Heyford and Wellingborough, and examined at the Royal Arsenal at Woolwich,* are thus described:—Heyford ore: "Ochrey brown ironstone, hydrated peroxide of iron from the same district, and similar in general character to the ore from Wellingborough. The sample analysed was an average of the two specimens received." The Wellingborough ore: "Three samples of the ochrey brown ironstone of the district were forwarded. They were of various degrees of hardness and density, though all consisted principally

* "Cast Iron Experiments," Parliamentary Return, No. 497, June, 1858.

of hydrated peroxide of iron. An average sample was prepared for the purpose of analysis." The results are thus tabulated :—

| Constituents. | Heyford. | Wellingborough. |
|-------------------------------|----------|-----------------|
| Peroxide of iron | 56·20 | 76·00 |
| Protoxide of iron | trace. | trace. |
| Oxide of manganese | 0·20 | 0·40 |
| Alumina | 2·43 | 2·30 |
| Carbonate of lime | 0·49 | 0·41 |
| Carbonate of magnesia | 0·17 | 0·11 |
| Phosphoric acid | 0·84 | 1·03 |
| Water hygroscopic | 1·16 | 1·80 |
| Water in combination | 9·74 | 12·40 |
| Insoluble residue | 29·07 | 5·33 |
| | 100·30 | 99·78 |
| Metallic iron | 39·34 | 53·20 |

In neither ore does there appear to have been any appreciable amount of sulphur discovered, the insoluble residue in the Weedon ore consisting of quartz, soluble silica, and a little mica, and the Wellingborough silica almost entirely, with a trace of mica.

The Wellingborough ore raised by the Messrs. Butlin, Bevan, & Co., and smelted at the East-end and Irthlingborough Iron Works (the former long since dismantled), has been examined in Dr. Percy's laboratory in the Royal School of Mines, and is thus described :—"The ore consists essentially of earthy hydrated sesquioxide of iron. It is oolitic in structure, and ochre-brown in colour, the insoluble residue consisted almost entirely of silicious oolitic concretion, but on dissolving these in potash a small amount of residue was left, containing a quartzose sand, scales of mica, and minute spherical particles of magnetic oxide of iron. The ore contains numerous marine shells, and occurs in the Northampton sand, which lies at the base of the Great Oolite, and is the geological equivalent of the Stonesfield slate. A trace of copper was detected in 600 grains of the ore."

Other ores from the neighbourhood of Wellingborough show the following chemical constituents. The first analysis was made by Mr. John Spiller, the second and third by Mr. Edward Riley, and yield respectively of metallic iron 37·00 per cent., 24·09 per cent., and 35·37 per cent. The amount of phosphoric acid contained in each ore being respectively 1·26 per cent., 1·47 per cent., and 1·28 per cent. :—

RESULTS TABULATED.

| Constituents. | First. | Second. | Third. |
|------------------------------------|--------|----------|--------|
| Sesquioxide of iron | 52·20 | 34·41 | 50·31 |
| Protoxide of iron | trace. | trace. | trace. |
| Protoxide of manganese | 0·51 | 0·27 | 0·51 |
| Alumina | 7·13 | 6·19 | 7·25 |
| Lime | 7·13 | 25·68 | 11·76 |
| Magnesia | 0·57 | 0·85 | 0·62 |
| Silica | 1·60 | 0·89 | 0·22 |
| Carbonic acid | 4·92 | 18·45 | 7·98 |
| Phosphoric acid | 1·26 | 1·47 | 1·28 |
| Sulphuric acid | ... | 0·07 | ... |
| Bisulphide of iron | 0·03 | 0·30 | 0·17 |
| Water hygroscopic and combined | 11·37 | 6·97 | 11·00 |
| Ignited insoluble matter | 13·55 | 5·82 | 9·33 |
| | 100·27 | 101·37 | 100·43 |
| INSOLUBLE RESIDUE. | | | |
| Silica | 11·56 | 5·80 | 8·58 |
| Alumina | 0·26 | } 0·21 { | 0·27 |
| Sesquioxide of iron | 0·66 | | 0·22 |
| Lime | 0·33 | 0·04 | 0·16 |
| Magnesia | 0·11 | 0·02 | trace. |
| Potash | ... | ... | 0·11 |
| | 12·02 | 6·07 | 9·34 |
| Metallic iron | 37·00 | 24·09 | 35·37 |

The prevailing mineral characters of the clays and sands of the formation containing the ferruginous beds are very fully described by Prof. J. W. Judd,* in his memoir, "The Geology of Rutland, &c.," in which work an interesting chapter appears, "On the Conditions under which the Northampton Sand was deposited."

Other samples † of these ironstones, examined by Mr. A. Dick, consisting of an inner and outer portion respectively of a lump of Northamptonshire ore, are thus described, and give the following results :—

"The inner portion, it will be observed, consists for the most part of carbonate of protoxide of iron, and the outer portion of hydrated sesquioxide, the latter having been clearly derived from the former by atmospheric action :—

* "Geology of Rutland," p. 128.

† Percy's "Metallurgy of Iron and Steel," p. 209.

RESULTS TABULATED.

| Constituents. | Inner Portion. | Outer Portion. |
|-------------------------------------|----------------|----------------|
| Sesquioxide of iron | ... | 38·04 |
| Protoxide of iron | 33·29 | 10·54 |
| Protoxide of manganese | 1·11 | 0·69 |
| Alumina | 4·62 | 12·35 |
| Lime | 0·50 | trace. |
| Magnesia | 7·96 | 4·13 |
| Potash | ... | ... |
| Silica | 1·99 | 1·96 |
| Carbonic acid | 24·79 | 0·16 |
| Phosphoric acid | 0·22 | 0·26 |
| Sulphuric acid | trace. | trace. |
| Bisulphide of iron | 0·13 | 0·13 |
| Water combined | 0·54 | 6·92 |
| Organic matter | 0·08 | 0·19 |
| Ignited insoluble residue | 24·09 | 24·61 |
| | 99·32 | 99·98 |
| INSOLUBLE RESIDUE. | | |
| Silica | 17·50 | 21·28 |
| Alumina | 3·27 | 2·67 |
| Sesquioxide of iron | 3·31 | ... |
| Lime | trace. | trace. |
| Magnesia | 0·81 | 0·22 |
| Potash | 0·20 | 0·38 |
| | 25·09 | 24·55 |
| Metallic iron | 28·28 | 34·83 |

It is further remarked that no metal precipitated by sulphuretted hydrogen was detected in a solution of 880 grains of the ore of the inner portion. On the contrary, extremely minute traces of copper and lead were detected in a solution of 744 grains of the ore of the outer portion, so that these metals appear to have been communicated to the ore by water from without.

The ironstone worked in the neighbourhood of Blisworth, where the deposit attains considerable thickness, shows the following constituents; the samples submitted for examination were selected from unweathered portions of the bed, from the upper and lower parts, and the analysis made by the late Mr. David Forbes, F.R.S. An average sample of the stone worked at Blisworth by Messrs. Bevan & Co. shows the results stated; the stone yielding 40 per cent. of metallic iron.

| Constituents. | Lower Portion. | Upper Portion. | Blisworth Stone. |
|---------------------------------|----------------|----------------|------------------|
| Protoxide of iron | 40·93 | 49·58 | 57·79 |
| Sesquioxide of iron | 6·14 | 5·67 | ... |
| Bisulphide of manganese | ... | 0·96 | ... |
| Protoxide of iron | 0·16 | 0·16 | 0·70 |
| Alumina | 8·08 | 1·56 | 2·03 |
| Lime | 3·47 | 3·24 | 0·40 |
| Magnesia | 2·21 | 0·46 | 0·52 |
| Carbonic acid | 22·32 | 34·64 | ... |
| Phosphoric acid | 1·99 | 0·44 | 1·20 |
| Potash | 0·19 | ... | ... |
| Soda | 0·27 | ... | ... |
| Sulphur | trace. | ... | trace. |
| Silica | 9·04 | 2·16 | 11·40 |
| Organic matter | ... | trace. | ... |
| Water | 4·92 | 1·56 | ... |
| Loss by calcination | ... | ... | 26·02 |
| Total | 99·72 | 100·43 | 100·06 |

The specific gravity at 60° Fahr. was found to be 3·401; and an examination by the microscope showed it to consist almost entirely of two mineral constituents, the one crystalline and colourless, being chiefly carbonate of iron, and the other of a green colour, probably silicate of alumina and iron. Whether the green colour is due to it or the presence of phosphate of iron is not decided, but it appears probable that a green silicate does exist in the mineral.

The ironstone raised at Brixworth and Thrapston, the former examined by Dr. Noad, F.R.S., the latter by Dr. Percy, F.R.S., show the following constituents. The ore was dried by exposure in a finely pounded state in the air of the private room of the laboratory.

| Constituents. | Brixworth. | Thrapston. |
|-----------------------------|------------|------------|
| Peroxide of iron | 64·20 | 64·72 |
| Silica | 14·80 | 11·40 |
| Magnesia | 1·72 | 0·53 |
| Alumina | ... | 3·49 |
| Lime | ... | 3·96 |
| Phosphoric acid | 0·892 | 2·06 |
| Sulphur | ... | 0·07 |
| Oxide of manganese | 2·80 | ... |
| Loss by calcination | ... | 15·16 |
| Water | 15·40 | ... |
| Total | 99·812 | 101·39 |

The material selected for the analysis of the Brixworth stone was obtained from the cutting of a vertical groove in the face of the rock, extending from the top to the entire depth. The yield of metallic iron from this stone was 48·98 per cent., the Thrapston ore giving 45·31 per cent.

The ironstone in the neighbourhood of Easton Neston, near Towcester,—where the bed has an average thickness of 6 feet, dipping slightly to the east,—is described as hard and compact, and has been found very suitable for reduction by the Siemens process. Several analyses of this ore made in the laboratory of the Towcester Iron Ore Co. give the following results. The analyses were made by Mr. H. Le Neve Foster, the last sample of ore (No. 5) being previously calcined :—

| Constituents. | No. 1. | No. 2. | No. 3. | No. 4. | No. 5. |
|-------------------------|--------|--------|--------|--------|--------|
| Peroxide of iron . . . | 54·10 | 50·70 | 52·04 | 51·00 | 66·60 |
| Protoxide of iron . . . | trace. | trace. | trace. | 2·00 | ... |
| Protoxide of manganese. | trace. | 0·11 | 2·23 | 0·20 | trace. |
| Lime | ... | ... | ... | 1·70 | ... |
| Alumina | 12·70 | 14·10 | 8·76 | 10·00 | 15·13 |
| Silica | 12·30 | 15·30 | 16·30 | 14·00 | 11·90 |
| Phosphoric acid . . . | 2·15 | 2·10 | ·24 | 1·50 | 1·37 |
| Sulphur | trace. | trace. | 0·33 | trace. | ·62 |
| Carbonic acid and water | 19·80 | 16·30 | 19·50 | 19·60 | 3·50 |
| Total | 101·05 | 98·61 | 99·40 | 100·00 | 99·12 |
| Metallic iron | 37·90 | 35·50 | 37·43 | 37·20 | 46·67 |

The ironstone in the southern part of the county near Culworth, worked but to a limited extent, gives the following results on analysis :—

RESULTS TABULATED.

| | |
|-----------------------------|--------|
| Peroxide of iron | 60·89 |
| Lime | 1·12 |
| Alumina | 2·80 |
| Magnesia | trace. |
| Phosphoric acid | 1·27 |
| Sulphuric acid | trace. |
| Sand and silicate | 19·96 |
| Moisture and combined water | 13·04 |
| Loss, &c. | 0·92 |

Total 100·00

N N

The equivalent of metallic iron contained in the above peroxide was 42·62 per cent., other analyses of the same stone, made at Birmingham, gave 44·16 per cent.; at Oxford, 43·07 per cent.; and in London, 42·80 per cent., showing an average of 43 per cent.

The ore raised by the Cogenhoe Iron Ore Company gives from 43 to 48·50 per cent. of metallic iron, the latter, of which the annexed is an analysis, giving in the calcined state 55·25 of metallic iron :—*

RESULTS TABULATED.—ORE DRIED AT 212° FAHR.

| | |
|------------------------------|--------------|
| Peroxide of iron | 69·29 |
| Oxide of manganese | 1·02 |
| Alumina | 3·08 |
| Lime | 1·65 |
| Magnesia | 1·08 |
| Sulphur | 0·07 |
| Phosphoric acid | 0·53 |
| Sulphuric acid | 0·43 |
| Silicious matter | 10·80 |
| Combined water | 12·03 |
| Total | <u>99·97</u> |

The following analysis, by Dr. Voelcker, F.R.S., of a friable portion of the Northamptonshire iron ore, obtained from a locality situated near Blisworth, shows a great reduction in the quantity of iron, and a considerable increase in the earthy constituents :—

RESULTS TABULATED.†

| | |
|---|----------------|
| Protoxide of iron | 0·875 |
| Sesquioxide of iron | 21·280 |
| Phosphoric acid | 1·030 |
| Sulphuric acid | 0·219 |
| Silica, lime, alumina, magnesia, &c., not separately determined | 76·596 |
| Total | <u>100·000</u> |

In the following appears a summary of the amount of metallic iron contained in the ironstone of the mines named, and in each case where known the name of the analyst is given :—

* The Author was favoured with this analysis by Mr. M. C. Cohen, of the Cogenhoe Iron Ore Company, who is also working the iron ore deposits at Caythorpe in Lincolnshire.

† 'Geology of Rutland,' p. 127.

| Mine. | Analyst. | Metallic Iron. |
|-------------------------------|-------------------------------|----------------|
| Blisworth | Dr. Percy | 40·00 |
| " | Mr. Harris | 40·00 |
| Brixworth | Dr. Noad | 43·93 |
| Culworth | | 43·00 |
| Duston | | 40·00 |
| Burton Latimer | | 35·00 |
| Cogenhoe | | 43·00 |
| " | | 48·50 |
| Desborough | | 38·00 |
| " | Dr. Percy | 36·79 |
| Gayton | | 42·00 |
| Heyford | Mr. Judkins | 39·34 |
| Hardingstone | Mr. A. Dick | 52·05 |
| Northamptonshire Ore* | " | 28·28 |
| " | " | 34·83 |
| Thrapston | Dr. Percy | 36·79 |
| Weedon | Woolwich Arsenal | 39·34 |
| Wellingborough | " | 53·20 |
| " | Mr. John Spiller | 37·00 |
| " | Mr. Edw. Riley | 35·37 |
| Woodford | Dr. Percy | 44·00 |
| Towcester | Mr. H. Le Neve Foster | 37·90 |
| " | " | 35·50 |
| " | " | 37·43 |
| " | " | 37·20 |
| " | " | 46·67 |

Production and Distribution of Ironstone.—Dr. Percy relates the following incident showing the circumstances under which the working of the ironstone deposits of the Northampton sand was resumed in modern times:—"The introduction of the Northamptonshire ore is only of recent date. Not long previous to the International Exhibition of 1851, Colonel (now General) Arbuthnot called upon me in Birmingham, where I then resided, and requested my opinion on the specimen of the ore which he left with me. I found it to contain a sensible quantity of sesquioxide of iron and a very large amount of silicious sand. I made no quantitative examination of it; and certainly the specimen in question did not prepossess me in its favour. However, I referred the Colonel to my friend, Mr. S. H. Blackwell, of Dudley, who visited the locality of the ore in order to examine it *in situ*. He obtained samples much richer in iron than that which was placed in my hands. He prosecuted inquiries on the subject with his usual energy, and the result has been the discovery of an

* Locality not stated.

extensive deposit of ore, which has since been smelted in large quantities in South Staffordshire, Derbyshire, and South Wales."*

The deposits in the neighbourhood of Blisworth and Weedon in the year 1855 produced 74,084 tons, increased to 91,592 tons in the year 1856; of this quantity 1,592 tons was sent out of the district by canal, and 90,000 tons by rail. Again, in the year 1857 the yield increased to 107,985 tons; of this quantity 29,550 tons were smelted in the iron works of the county, the remainder being distributed by the London and North-Western and Midland Railways; since that date the output of the mines of Northamptonshire has been as follows :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1857 | 107,985 | 1869 | 540,259 |
| 1858 | 140,485 | 1870 | 887,020 |
| 1859 | 130,098 | 1871 | 914,435 |
| 1860 | 95,664 | 1872 | 1,174,211 |
| 1861 | 113,129 | 1873 | 1,412,255 |
| 1862 | 116,718 | 1874 | 1,056,478 |
| 1863 | 126,578 | 1875 | 1,085,898 |
| 1864 | 335,787 | 1876 | 1,161,130 |
| 1865 | 364,349 | 1877 | 1,049,806 |
| 1866 | 476,981 | 1878 | 1,189,443 |
| 1867 | 416,765 | 1879 | 1,211,406 |
| 1868 | 449,116 | 1880 | 1,550,103 |

The ironstone is widely distributed, its silicious character rendering it useful as an admixture with the argillaceous ores of the coal measures. The great bulk is sent away to South Wales, Derbyshire, and South Staffordshire, bearing a carriage-rate by railway of from 2s. 6d. to 7s. 6d. according to distance. Like the ironstone of North Lincolnshire it is easily wrought, and is put into railway waggons at the mines at prices varying from 2s. 6d. to 4s. per ton, according to quality. The Midland Railway carried ironstone out of the county as follows in each of the years :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1869 | 319,696 | 1875 | 774,560 |
| 1870 | 397,903 | 1876 | 775,700 |
| 1871 | 535,099 | 1877 | 862,468 |
| 1872 | 681,798 | 1878 | 898,384 |
| 1873 | 845,763 | 1879 | 846,352 |
| 1874 | 793,048 | 1880 | 1,009,143 |

* Percy's "Metallurgy of Iron and Steel," p. 225.

The destination of the ore thus distributed does not here appear; however, the following figures show the quantities carried by the Midland Railway from their respective stations in each of the later years given below :—

| Stations. | 1877. | 1878. | 1879. | 1880. |
|--------------------|---------|---------|---------|-----------|
| | Tons. | Tons. | Tons. | Tons. |
| Desborough | 91,948 | 119,527 | 103,220 | 104,186 |
| Rushton | 101,325 | 116,153 | 138,677 | 123,498 |
| Grunston | ... | ... | 17,365 | 117,107 |
| Kettering | 1,265 | 33,793 | 69,879 | 39,879 |
| Melton | ... | 54,826 | 61,266 | ... |
| Cranford | 43,682 | 53,955 | 58,981 | 90,243 |
| Twywell | 169,970 | 143,034 | 103,451 | 125,385 |
| Thrapston | 13,400 | 19,709 | 14,623 | 14,078 |
| Isham | 6,914 | 2,915 | 143 | 103 |
| Wellingborough . . | 406,005 | 336,604 | 258,462 | 376,520 |
| Irchester | 27,959 | 17,868 | 18,285 | 18,144 |
| Total | 862,468 | 898,384 | 846,352 | 1,009,143 |

In the annexed table appears the quantities of ironstone raised from a few of the more extensive workings in the county, which will generally show how largely the ironstone is wrought in the neighbourhood of Blisworth by the Messrs. G. E. Bevan & Co., and others :—

| Year. | Blisworth. | Gayton. | Duston. | Towcester. |
|-------|------------|---------|---------|------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1870 | 59,424 | 74,866 | 45,330 | ... |
| 1871 | 64,354 | 51,578 | 52,713 | ... |
| 1872 | 83,514 | 33,961 | 150,722 | ... |
| 1873 | 81,107 | 76,675 | 180,934 | 7,953 |
| 1874 | 72,672 | 22,823 | 93,907 | 6,000 |
| 1875 | 39,534 | 51,677 | 53,983 | 43,571 |
| 1876 | 25,559 | 68,417 | 54,550 | 57,684 |
| 1877 | 20,258 | 72,940 | 50,136 | 35,800 |
| 1878 | 16,114 | 63,865 | 13,492 | 12,719 |
| 1879 | 12,868 | 65,608 | 18,024 | 16,499 |
| 1880 | 52,350 | 73,350 | 95,540 | 51,050 |

The ironstone raised at Blisworth, Gayton, and Duston, is sent away in considerable quantities by canal and railway to the Midland iron districts and to South Wales.

The mines in the neighbourhood of Wellingborough worked by Messrs. Butlin, Bevan & Co., have yielded ironstone in the following quantities in each of the years named :—

| Year. | Welling- borough. | Ringstead. | Ircheater. | Dean and ChapterLands. | Wollaston. |
|-------|----------------------|------------|------------|---------------------------|------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1870 | 180,127 | ... | ... | * | ... |
| 1871 | 152,585 | ... | ... | 89,266 | ... |
| 1872 | 65,914 | 43,498 | 46,961 | 114,868 | ... |
| 1873 | 175,263 | 60,058 | 100,532 | 87,504 | ... |
| 1874 | 118,579 | 19,641 | 81,721 | 80,538 | ... |
| 1875 | 87,380 | 22,461 | 47,749 | 58,945 | 66,460 |
| 1876 | 127,324 | 11,040 | 33,915 | 67,487 | 73,681 |
| 1877 | 111,620 | 10,839 | 28,062 | 32,776 | 84,468 |
| 1878 | 65,633 | 14,454 | 17,999 | 26,906 | 110,931 |
| 1879 | 37,945 | 5,398 | 17,329 | 3,539 | 68,907 |
| 1880 | 67,482 | 21,326 | 16,684 | † | 112,555 |

Considerable quantities of ironstone are raised in the neighbourhood of Wellingborough, beyond the above, by the Stanton Ironworks Co., who also work stone at Desborough, given below. The Newbridge Iron Co. at Newbridge and Ringstead have for some years produced stone as follows :—

| Year. | STANTON IRON WORKS CO. | | NEWBRIDGE IRON CO. | |
|-------|------------------------|-------------|--------------------|------------|
| | Wellingborough. | Desborough. | Newbridge. | Ringstead. |
| | Tons. | Tons. | Tons. | Tons. |
| 1870 | 5,175 | 104,060 | ... | ... |
| 1871 | ... | 113,370 | 52,450 | ... |
| 1872 | ‡149,953 | 127,427 | 70,000 | 43,498 |
| 1873 | ... | 150,000 | 108,535 | § |
| 1874 | ... | 150,000 | ... | ... |
| 1875 | 93,362 | 90,439 | 56,157 | 24,178 |
| 1876 | 113,538 | 71,824 | 54,335 | 22,246 |
| 1877 | 112,000 | 62,700 | 60,430 | 17,289 |
| 1878 | 110,000 | 79,000 | 59,490 | 17,688 |
| 1879 | 101,350 | 68,459 | 69,494 | 11,640 |
| 1880 | 101,070 | 66,167 | 77,699 | 21,326 |

The other mines to refer to are those lying between Thrapston, Kettering, and Finedon, where the Glendon Iron Ore Co. are large raisers of ironstone, principally consumed in their own furnaces. The table below gives the quantities raised in the mines named, the Glendon return including stone raised at Finedon and Burton Latimer :—

* Included in Wellingborough.

† Worked out.

‡ Including Ironstone raised from other works in the district of Wellingborough.

§ Included in Newbridge.

| Year. | Ilalip. | Woodford. | Cranford. | Glendon Iron Co. |
|-------|---------|-----------|-----------|------------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1870 | 25,000 | 129,913 | 21,712 | 95,964 |
| 1871 | 60,771 | 64,281 | 19,549 | 96,910 |
| 1872 | 35,700 | 73,502 | 21,920 | 98,148 |
| 1873 | 37,500 | 79,898 | 21,585 | 118,328 |
| 1874 | 35,000 | 69,735 | 20,786 | 96,264 |
| 1875 | 63,833 | 54,580 | 27,897 | 81,828 |
| 1876 | 65,000 | 58,359 | 27,000 | 100,000 |
| 1877 | 50,000 | 57,371 | 30,000 | 125,000 |
| 1878 | 50,000 | 50,000 | 40,000 | 130,000 |
| 1879 | 81,495 | ... | 56,091 | 160,000 |
| 1880 | 77,666 | ... | 89,671 | 159,100 |

The mines in operation in 1880 were as follows, producing 1,550,103 tons, of the value of £231,359, and exceeding the output of the previous year by 338,697 tons:—

| No. | District or Mine. | Character of Ore. | Quantities. | | Value. | | |
|----------------------------|---|-------------------|-------------|-------|---------|----|----|
| | | | Tons. | Cwts. | £ | s. | d. |
| 1 | Blisworth (Bevan & Co.) | { Hydrated oxide | 52,350 | 0 | 7,852 | 10 | 0 |
| 2 | Brixworth | | 28,621 | 0 | 3,577 | 7 | 6 |
| 3 | Cranford | | 89,671 | 0 | 11,209 | 0 | 0 |
| 4 | Cransley | | 105,780 | 0 | 14,547 | 0 | 0 |
| 5 | { Desborough (Stanton Iron Works Co.) | { | 66,167 | 0 | 9,097 | 19 | 3 |
| 6 | " (F. V. Smith) | | 18,725 | 0 | 3,276 | 0 | 0 |
| 7 | " (W. C. Wheldon) | | 18,000 | 0 | 2,500 | 0 | 0 |
| 8 | Ditchford (Butlin, Bevan, & Co.) | | 38,632 | 0 | 5,298 | 3 | 0 |
| 9 | Duston | " | 96,640 | 10 | 11,942 | 5 | 0 |
| 10 | Easton Neston | " | 51,050 | 0 | 7,657 | 10 | 0 |
| 11 | Finedon Road Bridge | " | 89,167 | 0 | 13,875 | 0 | 0 |
| 12 | Finedon (Glendon Iron Co.) | " | 20,000 | 0 | 4,000 | 0 | 0 |
| 13 | Burton Latimer | " | 9,600 | 0 | 1,900 | 0 | 0 |
| 14 | Glendon | " | 129,600 | 0 | 25,920 | 0 | 0 |
| 15 | Gayton (H. W. Wheldon) | " | 19,262 | 0 | 2,939 | 0 | 0 |
| 16 | Gayton (Heyford Iron Co.) | " | 54,088 | 0 | 9,465 | 8 | 0 |
| 17 | Irchester (Butlin, Bevan, & Co.) | " | 16,684 | 0 | 2,294 | 1 | 0 |
| 18 | Ilalip | " | 77,666 | 0 | 15,533 | 4 | 0 |
| 19 | Hunbury Hill | " | 18,849 | 0 | 2,356 | 2 | 6 |
| 20 | Newbridge | " | 77,699 | 0 | 9,712 | 7 | 6 |
| 21 | Ringstead (Newbridge Iron Co.) | " | 13,612 | 0 | 1,857 | 18 | 0 |
| 22 | Ringstead (Butlin, Bevan, & Co.) | " | 21,326 | 0 | 2,932 | 6 | 0 |
| 23 | Spratton | " | 46,420 | 0 | 5,802 | 10 | 0 |
| 24 | Thrapston | " | 14,240 | 0 | 1,780 | 0 | 0 |
| 25 | { Wellingboro' (Butlin, Bevan, & Co.) | { | 67,482 | 0 | 9,278 | 15 | 0 |
| 26 | { Wellingboro' (Stanton Iron Works Co.) | | 101,070 | 0 | 15,160 | 0 | 0 |
| 27 | Wollaston (Butlin, Bevan, & Co.) | | 112,555 | 0 | 15,476 | 0 | 0 |
| 28 | Warren Hill | | 47,647 | 0 | 7,118 | 11 | 0 |
| 29 | Sundry Pits | " | 50,000 | 0 | 7,500 | 0 | 0 |
| Total of Northamptonshire. | | | 1,550,103 | 10 | 231,358 | 17 | 9 |

The iron mines of Northamptonshire, their situation, proprietors and chief agents, are contained in the annexed list at the present time (1881):—

| No. | Name of Mine. | Situation. | Name of Proprietor or Company. | Name of Manager or Agent. |
|-----|----------------------------|----------------------------------|--|---------------------------|
| 1 | Blisworth . . . | Blisworth . . . | G. E. Bevan and Co., Lim. | Richard P. Jones. |
| 2 | Brixworth . . . | Brixworth . . . | Attenborough and Co. . . | Richard Timms. |
| 3 | Burton Latimer. | Kettering . . . | Glendon Iron Co. . . | George E. Checkland. |
| 4 | Cranford . . . | " . . . | Staveley Coal and Iron Co., Limited | J. P. Cramp. |
| 5 | Cransley . . . | " . . . | Cransley Iron Co., Limited | George Bond. |
| 6 | Cogenhoe . . . | Northampton | Cogenhoe Iron Ore Co. . . | Henry Westlake, Sec. |
| 7 | Desborough . . . | { Market Har- borough . . . } | Stanton Iron Works Co. . . | John Wallis. |
| 8 | " . . . | " . . . | G. Crompton, Managing Director | M. C. Cohen. |
| 9 | " . . . | " . . . | W. C. Wheldon . . . | John Hickman. |
| 10 | Ditchford . . . | Irthlingborough. | F. V. Smith . . . | W. C. Wheldon. |
| 11 | Duston . . . | Northampton | Butlin, Bevan, & Co. . . | F. V. Smith. |
| 12 | Easton Neston . . | Towcester . . . | Henry Higgins . . . | Lewis W. Perrin. |
| 13 | Finedon . . . | Kettering . . . | Easton Estate and Mining Co., Limited | James Saunders. |
| 14 | { Finedon Road Bridge } | Finedon . . . | Glendon Iron Co. . . | Sydney J. Bates. |
| 15 | Gayton . . . | Blisworth . . . | Rixon & Co. . . | George E. Checkland. |
| 16 | " . . . | " . . . | Henry W. Wheldon . . . | James Rixon. |
| 17 | Glendon . . . | Kettering . . . | Heyford Iron Co., Limited | Henry W. Wheldon. |
| 18 | Hunsbury Hill . . | Northampton. | Glendon Iron Co. . . | William Smith. |
| 19 | Irchester . . . | Irchester . . . | Hunsbury Hill Coal and Iron Co., Limited; F. Lenton, Secretary | George E. Checkland. |
| 20 | Islip . . . | Thrapston . . . | Butlin, Bevan, & Co. . . | J. P. Cramp. |
| 21 | Newbridge . . . | Twywell . . . | Islip Iron Co. . . | Thos. Pressland. |
| 22 | Raunds . . . | Thrapston . . . | Newbridge Iron Ore Co. . . | Lewis W. Perrin. |
| 23 | Ringstead . . . | Ringstead . . . | The Raunds Iron and Limestone Quarries Co. . . | Edward H. Clarke. |
| 24 | Spratton . . . | Brixworth . . . | Butlin, Bevan, & Co. . . | Lew's W. Perrin. |
| 25 | Stanton Gate . . . | Wellingborough. | Newbridge Iron Ore Co. . . | Edward H. Clarke. |
| 26 | Thrapston . . . | Thrapston . . . | Attenborough & Co. . . | Richard Timms. |
| 27 | Warren Hill . . . | Kettering . . . | Stanton Iron Works Co. . . | John Hickman. |
| 28 | Wellingborough. | Wellingborough. | Thrapstone Iron Ore Co., Limited | John Griffin. |
| 29 | Woodford . . . | Thrapston . . . | Kettering Iron and Coal Co., Limited | George C. Latimer. |
| 30 | Wollaston . . . | Wellingborough. | Butlin, Bevan, & Co. . . | Herbert Sartoris. |
| 31 | | | Stanton Iron Works Co. . . | F. W. Preston. |
| 32 | | | Arthur Arbuthnot . . . | Lewis W. Perrin. |
| | | | Butlin, Bevan, & Co. . . | |

Pig Iron Manufacture.—The first works established in Northamptonshire were those of Messrs. Butlin at Wellingborough projected by Mr. William Butlin of that firm, an engineer of some eminence, who carried out under his own supervision all the details of construction, and in the beginning of the year 1852 commenced the manufacture of pig iron, from the ironstone of the district, a sample of which it appears was deposited in the Northampton Museum. The Heyford Works succeeded, in the year 1857, under the auspices of Messrs. Pell & Co.; there were then two furnaces in operation at Wellingborough and one at Heyford, the make of pig iron amounting to 11,500 tons. In the

year 1866 the Glendon Iron Company blew in their first furnace at Finedon, increasing the number to three in the year 1869. In the year 1867 the Irthlingborough furnaces were put in blast and these possess some interesting features : the furnace casings, instead of being riveted as is usual, are put together by bolts, so that the fastenings are more secure and easier joined together and taken to pieces, effecting a saving in labour which more than compensates for the extra cost of the bolts. The boilers at these works are 30 feet in length and 6 feet in diameter. The blast engine for one furnace is worked with the average daily consumption of 28 cwts. of slack. The great economy gained by the boilers is attributed to the setting, which is a wheel shaft, the flues of which are increased in size as they approach the shaft, with a stack $3\frac{1}{2}$ times the length of the boiler, the combustion is therefore complete without the loss of temperature in the shaft, which varies from 350° to 400° Fahr., and there is little or no smoke made.

The Stowe Iron Works near Weedon commenced operations about the year 1867 ; in the year 1871 the works at Islip, near Thrapston, of Mr. C. H. Plevins, were projected, followed by the works of the Northampton Coal, Iron, and Waggon Company, at Hunsbury Hill, in the year 1873, and the Towcester Works a year or two later. The Towcester Works are situated about 4 miles from Blisworth, consisting of two rotatory furnaces and the necessary plant for making iron and steel by the direct process, according to the patent of Dr. C. W. Siemens. By this system, even with the ordinary ores found in the locality, a crystalline iron of great purity as well as toughness is produced. The bars have been sold in Staffordshire and at Sheffield at a high price, being considered equal to Swedish bar as regards toughness and purity. The mode of working appears to be simple, as described by Dr. Siemens himself. A mixture of pulverulent ores combined with fluxing materials and reducing agents in suitable proportions, and of this from 4 to 5 tons are charged from a platform into the heated chamber to the depth of some 12 or 15 inches. Before charging the mixture some coke dust, or anthracite powder, is spread over the bottom and sides of the chamber for the protection of its silica lining. The heat of the furnace is thereupon raised to a full welding heat, care being taken that the flame is as little oxidising as possible. The result is a powerful superficial action upon the mixture, causing simultaneous reduction of the

ore and fusion of the earthy constituents. In the course of about two hours a thick skin of malleable iron is formed all over the surface of the mixture, which on being withdrawn by means of hooks, is consolidated and cleared of cinder under a hammer, and rolled out in the same heat into rough sheets or bars, to be cut up and finished in the refinery furnace or charcoal hearth; one skin being removed, the furnace is closed again, and in the course of one hour and a half another skin is formed, which, in its turn, is removed and shingled, and so on until, after 3 or 4 removals, the furnace charge is nearly exhausted. A fresh charge is then added, and the same operation repeated. The shingled metal so produced forms an excellent melting material for the open hearth or the Siemens-Martin process.

At Wellingborough it was at one time intended to roll the iron made there into bars, and for this purpose a large establishment was projected by Messrs. Hipkins & Sons, of West Bromwich, to be called the Wellingborough Bar Iron Company. Considerable progress was made with the erection of the works, plant and machinery were prepared, and puddling furnaces erected, but operations never actually commenced, and the buildings with their lofty chimney-stacks and flues still stand in close proximity to the Irthlingborough Iron Works of Messrs. Butlin and Co.

The iron works of the Cransley Ironstone Company, situated near Kettering, were projected about the year 1875, and in 1877 the works of the Kettering Iron and Coal Company at Warren Hill, situated about 2 miles from Kettering, were begun.

The works of the district have of late years considerably extended their plant; those of the Glendon Company, the most extensive in the county, have now 5 furnaces in operation, drawing the necessary ironstone from pits situated near the works; the plant of the company is at once extensive and complete, there being two powerful engines for the blast, one of them, made by the Lilleshall Company, being something like 150 horse-power, having 12 revolutions per minute. At the Glendon Works the gases from the furnaces are utilised for the stoves and boilers, and recently some new pits have been opened in close proximity to the works, affording an abundant supply of ironstone to the furnaces.

Near the Finedon Works an establishment has been recently erected, with the necessary appliances for the manufacture of glass bottles from the slag of the blast-furnaces; the works of

late have been standing, but a large number of bottles were made, thus demonstrating practically the process. Slag bottle manufacture would appear to be a profitable one, seeing that the necessary material can be had without cost, the iron-masters being but too glad to get the slag taken away from their works.

The works and companies, with the number of furnaces built and in blast in the year 1880, were as follows :—

| Name of Works. | Owners. | FURNACES. | |
|---------------------------------------|---|-----------|-----------|
| | | Built. | In Blast. |
| Cransley, Kettering . . . | Cransley Iron Co., Limited | *2 | 2 |
| Finedon, Wellingborough . . | Checkland and Fisher . . | *5 | 5 |
| Irthlingborough " . . . | Thomas Butlin and Co. . . | 3 | 2 |
| Heyford, Weedon . . . | Heyford Iron Co., Limited | 3 | 2 |
| Hunsbury Hill, Northamp- ton . . . | Hunsbury Hill Coal and Iron Co., Limited . . } | 2 | 2 |
| Islip, Thrapston . . . | Islip Iron Co. | 4 | 2 |
| Stowe, Weedon . . . | William M'Clure | 2 | 0 |
| Kettering . . . | Kettering Iron and Coal Co., Limited . . } | 2 | 2 |
| Total . . . | | 23 | 17 |

Resuming with the year 1858, the following table gives the make of pig iron, the number of furnaces built and in blast, and their average yield; the figures in the last column are subject to revision, inasmuch as in some years a few of the furnaces were but partially in blast :—

| Year. | FURNACES. | | Pig Iron Made. | Average Make of Furnace. |
|-------|-----------|-----------|-------------------|-----------------------------|
| | Built. | In Blast. | | |
| 1858 | 3 | 3 | Tons. 9,750 | Tons. 3,250 |
| 1859 | 4 | 3 | 12,800 | 4,266 |
| 1860 | 4 | 3 | 7,595 | 2,532 |
| 1861 | 4 | 3 | 7,730 | 2,576 |
| 1862 | 4 | 3 | 13,471 | 4,490 |
| 1863 | 5 | 3 | 14,590 | 4,863 |
| 1864 | 5 | 3 | 13,323 | 4,441 |
| 1865 | 5 | 4 | 14,700 | 3,675 |
| 1866 | 9 | 6 | 19,174 | 3,195 |
| 1867 | 9 | 5 | 25,184 | 5,035 |
| 1868 | 8 | 6 | 35,584 | 5,930 |
| 1869 | 8 | 7 | 41,500 | 5,928 |
| 1870 | 10 | 10 | 43,166 | 4,316 |
| 1871 | 12 | 9 | 60,512 | 6,723 |

* One building.

Since the year 1871 information is available, showing the quantity of coal and of ironstone used in the manufacture of pig iron; in Northamptonshire practically it is found that 60 cwts. of raw stone and a like amount of coal, previously coked, is employed in the production of each ton of pig iron; the coal includes all necessary for heating purposes, such as engine-fires, blowing-engines, &c.

In the year 1872 and since, the quantities of pig iron made and of coal and iron used were as follows, together with the furnaces built and in blast:—

| Year. | FURNACES. | | Pig Iron Made. | Coal Used. | Ironstone Used. |
|-------|-----------|-----------|----------------|------------|-----------------|
| | Built. | In Blast. | | | |
| | | | Tons. | Tons. | Tons. |
| 1872 | 12 | 9 | 59,424 | 183,523 | ... |
| 1873 | 16 | 10 | 58,480 | 169,592 | 175,000 |
| 1874 | 18 | 14 | 53,760 | 152,138 | 159,280 |
| 1875 | 18 | 12 | 80,689 | 177,883 | 229,636 |
| 1876 | 20 | 11 | 84,916 | 212,093 | 241,958 |
| 1877 | 20 | 13 | 106,948 | 268,124 | 296,379 |
| 1878 | 20 | 15 | 138,370 | 345,681 | 391,687 |
| 1879 | 23 | 17 | 165,317 | 428,557 | 453,460 |
| 1880 | 23 | 17 | 178,714 | 470,165 | 528,501 |

The proportion existing in the above years between the iron made and material used, show the economy that has been secured; thus, in the year 1871, the coal and ore used, as already stated, was 60 cwts. of each to the ton of iron. In subsequent years less has been required, till in 1877 and 1878 the quantity did not exceed 50 cwts. of coal and from 56 to 57 cwts. of ironstone to each ton of pig iron. Gas-saving apparatus has hitherto been introduced into the metallurgical works of Northamptonshire to a very limited extent; if it had been adopted a still greater economy would have been attained. Glancing at the returns of production, it will be seen that within a period of 10 years the make of pig iron has increased upwards of threefold, and a saving has been effected of 10 cwts. of coal, equivalent to 18 per cent. on each ton of pig iron made.

The fuel chiefly employed in the furnaces of Northamptonshire is obtained from the South Yorkshire coal-field, that formerly used at the Wellingborough Works was Barnsley coal, an average sample of which, without being previously coked, contained of

sulphur 0·65 per cent. ; of ash, 4·76 per cent, the ash consisting of shale, silicate of alumina, with a little protoxide of iron and traces of lime and magnesia.

Coke made from Barnsley coal and used at the Heyford Iron Works was found to contain 0·52 per cent. of sulphur, and 6·58 per cent. of ash.*

Considering the ironstone of Northamptonshire, and its reduction in the smelting works, various opinions have in recent years appeared relating to its character and the quality of the iron obtained therefrom ; Mr. William Butlin of the Irthlingborough Iron Works near Wellingborough, who originally developed the ironstone deposits of the county and initiated the manufacture of pig iron thus defends the character of the industries in terms so cogent that they are reproduced here,† being worthy of consideration ; he says :—

“ These ores (brown hematite) are widely distributed through the county, are rich in iron, and vary considerably in their composition, but if smelted scientifically are capable of producing an excellent metal both for the foundry and the forge.”

“ It has been said of a certain district ‘ that the iron is made by brute force ; ’ this is somewhat sarcastic, but it is to be feared the same remark might apply to this county.

“ It is true good iron is made from these ores, but the larger proportion is very inferior, and it is the irregular quality produced which brings down the market price and brands it with a name it does not deserve—‘ common iron.’

“ If good work is to be done, and the greatest advantage taken of what Nature has placed within our reach, it is highly important to have a good knowledge of the composition of the foreign matter in the ores, which, when melted together, constitute cinder, and the knowledge of the circumstances under which the most favourable results can be obtained. The fusibility of earthy compounds depends upon their chemical relations, and the greatest degree of fusibility that need be desired can be produced by means of clay, silice, and lime.

“ We have argillaceous, silicious, and calcareous ores, and not unfrequently the various kinds are found in one and the same quarry. We have also an excellent limestone, admirably adapted

* For detailed Analyses of Coal of the Barnsley District, see Part I., p. 39.

† “ Iron and Coal Trades Review,” Dec. 3, 1880, p. 666.

for fluxing the ores, both as regards its physical structure and chemical composition."

Mr. W. Butlin subsequently refers to the suitability of the Northamptonshire pig iron for forge purposes, and its conversion into iron for hoops, sheets, and smaller sizes of bars, when the ores are judiciously selected and skilfully treated, and says:—"Iron is iron; it is not, however, pure metal with which we have to deal, but with the iron of commerce, containing many impurities more or less injurious, the quality depending pretty much on what is associated with it. The matrix, too, in the ore from which the iron is produced has also an important influence on the practical working of the metal in the puddling furnaces. Hence it is found advantageous to mix iron from different localities to improve the quality. The same rule applies to the puddling furnace as to the blast furnace. Iron made from argillaceous ores is mixed with those made from silicious and calcareous ores. Now Northamptonshire has an advantage in mineral deposits which few iron-making districts possess. As before stated, argillaceous, silicious, and calcareous ores are found in close proximity, and it requires only scientific selection and careful manipulation to make excellent forge-iron, having all the requisite fluxing elements and constituents in one pig without any other admixture for producing iron of the best quality and adapted for making hoops, sheets, and small sizes of bars, &c.

"Iron, however, when made from tender, friable ores, such as we have in this county, is not suited for manufacturing the larger sizes of iron; metal from more refractory ores is needed, that will stand the higher temperature required in heavy puddling." In conclusion, Mr. W. Butlin suggests the puddling of Northampton iron in the Casson-Darmoy patent gas furnace, which is admirably adapted for the conversion of iron from fusible compounds. "With mild treatment and the use of the furnace," he adds, "iron can and will be manufactured of a quality and at a price alike profitable to the smelter and iron-master."*

* "Iron and Coal Trades Review," Dec. 17, 1880, p. 717.

CHAPTER XIII.

LINCOLNSHIRE IRON INDUSTRIES.

Ironstone Deposits—Geology of North Lincolnshire—Scunthorpe, Frodingham—Analyses, Production, and Distribution of Ironstone—Mines in Operation in 1880—Pig Iron Manufacture—Production since 1864—Coal and Ore used in Pig Iron Manufacture.

Lincolnshire Ironstone Deposits.—A quarter of a century since the extensive deposits of iron ore, known as “hydrated oxide,” and now extensively worked, were comparatively unknown. These deposits, now in process of rapid development, have given rise to the important, thriving, and increasing mining centres of Frodingham and Appleby, near Brigg.

Ironstone is also worked in other districts of Lincolnshire, as at Kirton-Lindsey, some eight miles north-east of Gainsborough, on the Manchester, Sheffield, and Lincolnshire Railway; at Caythorpe, some seven miles north of Grantham; at Claxby, between Market Rasen and Caistor, by the West Yorkshire Coal and Iron Company; and at Monk’s Abbey and Greetwell, near the City of Lincoln, by the Mid-Lincolnshire Iron Company. Ironstone, it appears, was extensively worked in olden times in South Lincolnshire, but at present no workings are carried on in that division of the county.

The districts in the north-western area of the county, now extensively worked for ironstone, may be described as being within the area bounded on the north by the river Humber, on the west by the river Trent, and on the east by the river Ancholme. Within this area the geological formations dip in a direction from west to east, forming three principal escarpments, with long, sloping plains between them; the westernmost scarp is capped with Lower Lias, the middlemost with Lincolnshire limestone, and the easternmost is the chalk wold. These latter elevations are characteristic features of the country; the middle

escarpment, or limestone ridge, is also known as the "Cliff," and runs in a direction nearly due south from the river Humber to Lincoln, and even further southwards. The wold or easternmost escarpment tends south-east, towards Boston and the Wash, while the westernmost escarpment is the least continuous of the three.

The rocks of North Lincolnshire dip in a direction from west to east, and comprise liassic and oolitic strata, occurring in the following descending order, as given by the Rev. J. E. Cross, M.A., F.G.S., in his paper read before the Geological Society of London.*

Cornbrash and Great Oolite Clay.
Lincolnshire Limestone.
Upper Lias Clay.
Marlstone; "Rhynchonella bed."
Capricornus Clay.
"Pecten Bed" Ironstone.
Lower Lias; Scunthorpe Ironstone.
Bucklandi Beds.
Infra Lias (Rhœtic).
Keuper Marls.

The Keuper marls, the lowest of the above series of strata in the north-western area of Lincolnshire, occupies the bed of the river Trent. It appears that a few years since some sinkings were put down here for the piers of a railway bridge, and that they all went through this formation. Above the Keuper marls occur a series of clays, containing *Ammonites angulatus* and *Ammonites Johnstonei*; both these ammonites appear in the lowest beds, but the first-named has a higher range in the series of clays through a zone of, say, 150 feet or more. Upon these angulatus beds repose a series of limestones and clays, distinguished by the presence of *Ammonites Bucklandi*. In these and the angulatus beds, occur the vast deposits of ironstone which are worked at Scunthorpe. The bed containing this deposit attains in some places a thickness of 27 feet, and is found cropping out at the surface, and it extends over a large area. The ironstone is wrought in open workings, as in Northamptonshire, and, having a slight "over burden" easily removed, is worked inexpensively.

This important ironstone deposit, covering the whole wide

* "Journal of the Geological Society," vol. xxxi., 1875.

plain of the village of Scunthorpe, is described as commencing below with a hard limestone band, and, in somewhat similar bands above, most of the fossils lie. These are intercalated with softer bands of a darker brown colour and rubbly texture, intermingled with a brown earthy deposit. The Lincolnshire ironstone, it may be observed, differs widely from the Cleveland ironstone, and is in fact on a much lower geological horizon. As already stated, the Scunthorpe ironstone occurs in the lower part of the Lower Lias, an occurrence which is believed by Mr. Cross to be almost unique in this country.

The Lower Lias clay previously referred to, in which occurs the massive seam of ironstone, has in North Lincolnshire a thickness of 90 feet; no openings, however, of any importance have hitherto been made in depth.

Superimposed on the Lower Lias series is the Middle Lias, in which there is a seam of ironstone 4 feet in thickness, in which *pectens* occur in profusion, and hence it has been designated the "Pecten Ironstone." The junction between the Lower and Middle Lias is represented by a thickness of some 66 feet, consisting of blue clay, containing throughout in the centre of cement nodules a characteristic species, the *Ammonites maculatus* (Capricornus of Schlotheim). At Santon, in a railway cutting, a good section of this clay is exposed, capped by a thin bed not exceeding 18 inches in thickness, containing a confused mass of broken belemnites and other shells, together with many coprolites and much pyrites, the whole of a bright green colour.

The seam of ironstone occurring in the marlstone or Middle Lias is sometimes called the "Rhynchonella bed," from the circumstance that fossils of that genus occur therein in great profusion; the lias bed is described as consisting of a hard, light-grey limestone, weathering to brown, and seems to contain *Ammonites spinatus* towards the lower part, and *A. communis* and *serpentinus* in the upper. Above the Rhynchonella bed occurs the Upper Lias, hitherto but little explored; it has an average thickness of 60 feet, and consists chiefly of a blue shale, but showing no trace throughout the north-western district of the overlying Upper Lias sands.

Extending away to the east, and above the Upper Lias upon which it rests, appears the middle escarpment previously referred

to, occupied by the Inferior Oolite, which in this district is often termed the Lincolnshire limestone. It has an average thickness of 36 feet, including its partings of clay. Next above occurs the Great Oolite, consisting of limestones and clays, the latter in parts of a bright green colour, some 40 feet in thickness, and the representative no doubt of some subdivision of the oolite series. But one other formation, the "Cornbrash," remains to be referred to. The Cornbrash occupies the surface away to the east till the alluvial deposits of the river Ancholine are reached. The foregoing will show generally the occurrence and succession of the strata of the liassic and oolitic formations in North Lincolnshire, and the position of the ironstone deposits, for a more detailed account of which reference should be made to the Rev. J. A. Cross's paper in the "Journal of the Geological Society of London." *

Frodingham, the centre of the iron-mining district of North Lincolnshire, is situated on the Manchester, Sheffield, and Lincolnshire Railway, which connects it with the ports of Hull and Grimsby. Although ironstone is obtained elsewhere in the county, it is here that the manufacture of pig iron is carried on. About twenty-three years since attention was directed to the deposits by the Messrs. W. H. and G. Dawes, of the Milton and Elsecar Ironworks, Barnsley, in the West Riding of Yorkshire. This firm constructed a railway, from the river Trent to the outcrop of the bed, to facilitate the shipment of ironstone to their works. The ironstone seam is covered by a deposit of drift of varying thickness, being shifted about by high winds, so that the land, from an agricultural point of view, is of little value. Before the discovery and development of the ironstone deposits the district was little more than barren moorland, the village itself at that time being but a hamlet; of late years it has become a town of some importance, and is still steadily extending, while the value of the land has greatly increased. Mr. George Dove, junr., who some years since carefully examined the district, says that "the bed, which is almost entirely free from faults, inclines gently to the east, but where it is now being worked at, and within one and a-half miles of the outcrop, the amount of 'bareing' required is very small, in no place exceeding 3 feet. The labour

* Vol. xxxi., 1875, p. 115.

employed in raising the stone is of the commonest and most unskilled description, blasting only being required in getting the stronger portions of the bed; the whole operation is simply one of quarrying." Mr. Dove further adds that the deposit is not of very regular formation; it consists of bands of stone, some consolidated, others unconsolidated, of various appearances, mechanical conditions, and compositions, which are again broken up by bands of ferruginous limestone of varying thicknesses.

Before proceeding to consider the production of ironstone in this locality, the other districts of Lincolnshire, in which local deposits of ironstone occur, may be briefly referred to, not only of those deposits occurring in strata already referred to, but also in other geological formations of more recent age.

In South Lincolnshire the marlstone rock (Middle Lias) was formerly worked, as also was the ironstone of the Northampton sand; the latter is of the age of the Inferior Oolite. A band of good ironstone, occurring at the base of the "Upper Estuarine Series," was also wrought in ancient times. Some years back ironstone was worked at Overton, near Peterborough, in Northamptonshire, in the "Great Oolite Clay," which is the equivalent of the Forest Marble of the South of England; the workings have, however, been long since abandoned, on account of the great thickness of bareing necessary to be removed before the stone was reached.

A brown iron ore of oolitic structure, forming a bed $6\frac{1}{2}$ feet thick, occurs in the Tealby Series or Middle Neocomian, occurring at Tealby, some four miles north-east of Market Rasen, and is much valued for admixture with the argillaceous ores of Yorkshire and the calcareous ores of Lincolnshire. Ironstone is also wrought at Caythorpe, near Grantham, South Lincolnshire (a hydrated oxide); in the year 1880 the quantity raised amounted to 73,680 tons, put in trucks at the workings at an average price of 8s. per ton. This ore is said to contain 31 per cent. of metallic iron, from 18 to 20 per cent. of lime, and from 1.25 to 1.50 per cent. of manganese; is in good demand, and meets with a ready sale.

To those interested in the subject of the occurrence of the ironstone deposits in the liassic and oolitic rocks, the recent work of Professor Judd, F.G.S.,* will possess especial interest. In this

* "Geology of Rutland," Professor J. W. Judd, 1875.

important contribution to geological science the author fully discusses the classification and correlation of the Jurassic rocks of the Midland district or counties of England, including Rutland and parts of Lincoln, Leicester, Northampton, Huntingdon, and Cambridge.

Analyses of the Ironstone.—The stone raised in the Frodingham district, like that in other localities in Lincolnshire, has been fully investigated and its constituents determined by Mr. George Dove, junr., of the Redbourn Hill Iron Works, from whose interesting paper on the “Frodingham Iron-fields” * the following are selected. In the various mines worked on Mr. R. Winn's estate the yield of metallic iron varies according to portions of the seam used; the working face of the quarry, from which the samples were taken, has a thickness of 16 feet, increasing to 18 feet and even more. The seam is divided by Mr. Dove into 11 distinct bands; the iron exists in the form of peroxide; the seam has a maximum thickness of 27 feet, the bands of which it is composed vary in thickness from 9 inches to 3 feet 6 inches, many of them, however, containing stone of very inferior quality, a sort of ferruginous limestone, which it is always desirable to reject. The top band of the seam is described as mechanically very small and friable, resembling in appearance brown, ferruginous sandstone, highly oxidised and tolerably dry, the other bands containing a large amount of moisture :—

RESULTS TABULATED.

| Constituents. | Top Band. | Second Band. | Fourth Band. | Sixth Band. | Eighth Band. |
|--------------------------------------|-----------|--------------|--------------|-------------|--------------|
| Peroxide of iron . . . | 61·79 | 48·71 | 47·14 | 47·36 | 41·14 |
| Protoxide of manganese . . . | 2·70 | 3·05 | 1·72 | 2·09 | 0·79 |
| Silica | 10·77 | 12·85 | 11·95 | 13·00 | 24·40 |
| Alumina | 6·38 | 3·85 | 4·08 | 4·85 | 6·62 |
| Lime | 1·79 | 9·58 | 11·45 | 10·60 | 8·18 |
| Magnesia | 1·10 | 2·51 | 2·97 | 3·02 | 2·10 |
| Sulphur | 0·08 | 0·06 | 0·10 | 0·07 | 0·04 |
| Phosphoric acid | 1·46 | 1·12 | 0·87 | 0·82 | 1·12 |
| Combined water | 14·43 | 12·47 | 12·40 | 11·90 | 10·70 |
| Carbonic acid | traces | 6·15 | 6·87 | 6·74 | 5·28 |
| Total | 100·50 | 100·35 | 99·55 | 100·45 | 100·37 |
| Metallic iron, dried stone | 43·25 | 34·10 | 33·00 | 33·15 | 28·80 |
| „ wet stone | 38·94 | 30·47 | 29·44 | 27·08 | 25·04 |
| Moisture | 9·97 | 10·65 | 10·79 | 18·32 | 13·04 |

* “Journal of the Iron and Steel Institute,” 1876.

Some parts of the great seam are highly manganiferous ; these bands do not appear in the face of the workings from which the above samples were taken for analysis, but appear in another part of the quarry ; these also have been examined by Mr. Dove ; the one sample, consisting of scales of peroxide of manganese, taken of the manganiferous ironstone band, occurring about 13 feet from the top of the bed ; the second sample, from that part of the band, appearing about 7 feet from the top of the bed ; and the third, an average sample of the band itself. The annexed show the results :—

| Constituents. | 1. | 2. | 3. |
|---------------------------|-------|--------|--------|
| Peroxide of iron | 23·71 | 38·07 | 39·36 |
| Peroxide of manganese . . | 32·82 | 11·40 | 3·80 |
| Silica | 14·00 | 18·80 | 24·67 |
| Alumina | 3·09 | 5·01 | 5·41 |
| Lime | 9·46 | 6·38 | 6·83 |
| Magnesia | ... | 2·82 | 2·27 |
| Sulphur | 0·02 | 0·04 | 0·06 |
| Phosphoric acid | *... | 0·52 | 0·56 |
| Combined water | *... | 14·37 | 13·27 |
| Carbonic acid | *... | 3·02 | 3·90 |
| Total | ... | 100·43 | 100·13 |
| Iron in dried stone . . . | 16·60 | 26·65 | 27·55 |
| Moisture | 10·04 | 21·32 | 16·41 |

From an examination of these analyses the variable composition of the bed will be understood. Mr. Dove further adds that the greatest care is necessary in the selection of the stone before it is charged into the furnace ; and further, that unless this selection be properly understood and attended to, serious disorganization of the working of the furnace must inevitably result.

The seam in the neighbourhood of Brigg, a few miles to the south-east of Frodingham, has been reported upon by Mr. Charles Tookey, of the Royal School of Mines, giving the following results ; for comparison is appended side by side analysis of the Northamptonshire ore, from the neighbourhood of Wellingborough :—

* Not estimated.

| Constituents. | Lincolnshire, Brigg. | Northamptonshire, Wellingboro'. |
|--------------------------------|-------------------------|------------------------------------|
| Sesquioxide of iron | 58·10 | 50·31 |
| Protoxide of iron | ... | trace |
| Peroxide of iron | ... | ... |
| Protoxide of manganese . . | 0·88 | 0·51 |
| Alumina | 3·00 | 7·25 |
| Lime | 4·15 | 11·76 |
| Magnesia | 0·96 | 0·62 |
| Carbonic acid | 1·08 | 7·98 |
| Phosphoric acid | 1·40 | 1·28 |
| Silica | ... | 0·22 |
| Bisulphide of iron | ... | 0·17 |
| Water hygroscopic and combined | 16·46 | 11·00 |
| Ignited insoluble residue . . | 13·75 | 9·33 |
| Total | 99·78 | 100·43 |
| Metallie iron | 40·67 | 35·37 |

The above residue of the Brigg ironstone is made up of 11·70 per cent. of silica, of which 7·45 per cent. was in combination, and 4·25 per cent. existed as sand, the remaining 1·95 per cent. consisting of alumina and lime.

The ironstone raised at Monk's Abbey, and at Greetwell, near the city of Lincoln, worked by the Mid-Lincolnshire Iron Company, is in great request by the ironmasters of the Frodingham district, who use the stone in admixture with the Frodingham ore, in proportions varying from one-eighth to one-quarter, and with the most satisfactory results, both as regards the regularity of the working of the furnace and low consumption of fuel which are obtained. Since its introduction the difficulties formerly existing in the excess of lime in the native ore has been much lessened. The following is an analysis of the ore:—

MID-LINCOLN STONE.

| | |
|-----------------------------------|---------------|
| Peroxide of iron | 60·91 |
| Manganese | traces |
| Alumina | 5·47 |
| Lime | 1·60 |
| Magnesia | 0·06 |
| Phosphoric acid | 1·02 |
| Sulphur | 0·03 |
| Insoluble matter | 15·80 |
| Carbonic acid and water | 15·35 |
| Total | 100·24 |

The equivalent of metallic iron contained in this stone is 42·64 per cent., the insoluble matter consisting of 18·24 per cent. of silica and 2·56 per cent. of alumina. A clay obtained at Santon has sometimes been used in admixture with the ores of the northern districts of Lincolnshire, but, commercially, it does not appear to have succeeded so well as with a certain proportion of the stone obtained near the city of Lincoln.

Comparing the constituents of the Frodingham stone with that of Cleveland the results show favourably in an analysis of the latter, published in the "Iron Ores of Great Britain," Part I. Phosphoric acid gives 1·86 per cent., and protoxide of iron 39·92 per cent. Some of the better varieties of Lincolnshire stone, examined by Mr. John Pattinson, of Newcastle-upon-Tyne, give the following results:—

| Constituents. | No. 1. | No. 2. | No. 3. |
|-------------------------|--------|--------|--------|
| Peroxide of iron . . . | 67·00 | 72·14 | 57·86 |
| Protoxide of iron . . . | nil | nil | nil |
| Protoxide of manganese | 0·31 | 0·62 | 0·24 |
| Alumina | 4·20 | 3·47 | 7·10 |
| Lime | 1·82 | 1·73 | 2·92 |
| Magnesia | 0·36 | 0·34 | 0·69 |
| Carbonic acid | 1·27 | 0·23 | 1·67 |
| Silica | 9·87 | 8·00 | 14·17 |
| Sulphur | 0·02 | 0·03 | trace |
| Phosphoric acid . . . | 0·70 | 0·57 | 0·80 |
| Combined water . . . | 12·10 | 11·24 | 10·24 |
| Moisture | 2·17 | 1·59 | 4·29 |
| | 99·82 | 99·96 | 99·98 |
| Metallic iron | 46·90 | 50·50 | 40·05 |

Mr. J. Roseby, who has long been identified with the development of the ironstone of the district, expresses his opinion favourably, stating that a very fine quality of iron, suitable for almost any purpose to which that metal is applied, could be easily produced; all that would be required being care in the selection of the stone.

Production and Distribution of Ironstone.—The development of the North Lincolnshire ironstone deposits commenced about the year 1858 in the neighbourhood of Scunthorpe, the property of Mr. Rowland Winn, M.P., whose name, with the names of the Messrs. Dawes previously referred to, are so intimately associated with the early history and subsequent

progress of this the most recently discovered ironstone-field in the kingdom. The stone raised at Frodingham and sent out of the county in the year 1859 was smelted at the Milton and Elsecar Works in Yorkshire, in admixture with the clay iron ores of the coal measures of that district, and were found to work well in the furnaces, producing iron of good quality.

The output in the year 1859 did not exceed 2,000 tons, increasing in the following year to 16,192 tons, and in the year 1861 to 32,709 tons. In succeeding years the returns of production appear as follows:—

| Year. | Ironstone. | Year. | Ironstone. |
|-------|------------|-------|------------|
| Nos. | Tons. | Nos. | Tons. |
| 1861 | 32,709 | 1871 | 217,767 |
| 1862 | 50,323 | 1872 | 256,149 |
| 1863 | 69,618 | 1873 | 350,281 |
| 1864 | 74,619 | 1874 | 463,239 |
| 1865 | 124,958 | 1875 | 573,336 |
| 1866 | 175,720 | 1876 | 573,374 |
| 1867 | 192,213 | 1877 | 508,749 |
| 1868 | 200,699 | 1878 | 683,685 |
| 1869 | 220,524 | 1879 | 695,326 |
| 1870 | 216,829 | 1880 | 1,154,584 |

The great bulk of production is obtained from the Frodingham district, which includes the stone dug in the Scunthorpe area, where it was first raised. Other deposits discovered at Claxby, and first opened out by Mr. W. Firth, of Leeds, are now largely worked and sent into Yorkshire for the Ardsley Main Works, which belong to the West Yorkshire Iron and Coal Co. The details of production, with the value of the ore, appear below for the year 1880:—

| District or Mine. | Quantities. | Value. |
|-------------------------------------|-------------|-------------|
| | Tons. Cwts. | £ s. d. |
| Caythorpe | 73,680 14 | 11,002 1 9 |
| Claxby, Caistor | 27,500 0 | 4,125 0 0 |
| Crosby, Frodingham | 89,130 7 | 13,369 11 0 |
| Greetwell, Lincoln | 77,638 0 | 15,527 12 0 |
| Gunbrose, Parkgate Iron Co. | 145,899 0 | 21,884 17 0 |
| Glebe | 47,165 0 | 7,074 15 0 |
| Frodingham Iron Co. | 145,642 0 | 21,846 6 0 |
| Trent Iron Co. | 148,138 0 | 22,220 14 0 |
| North Lincolnshire Iron Co. | 357,353 0 | 53,602 19 0 |
| Appleby Iron Co. | | |
| Redburn Hill | | |
| Normanby, Crosby | 42,438 0 | 6,365 14 0 |
| Total | 1,154,584 1 | 177,019 9 9 |

The ironstone worked in the neighbourhood of the City of Lincoln contains silica in considerable quantity, and on this account is valuable in admixture with the Frodingham stone, which is calcareous. The annexed figures for a few years show the quantity raised of the siliceous ores from Lincoln, conveyed to, and used in, the ironworks of North Lincolnshire since the year 1874 :—

| Year. | Tons. | Year. | Tons. |
|-------|--------|-------|---------|
| 1874 | 40,888 | 1878 | 92,264 |
| 1875 | 80,890 | 1879 | 76,908 |
| 1876 | 96,443 | 1880 | 77,638* |
| 1877 | 97,977 | | |

Distribution of the Ironstone.—The districts of North Lincolnshire, in which the iron mines are mainly situated, are traversed by the Manchester, Sheffield, and Lincolnshire Railway, affording facilities for the transport of the ironstone to the north, while a branch of the same system, the Trent and Ancholme Line, puts the district in communication with Barnsley, South Yorkshire, the West Riding of Yorkshire, Derbyshire, and Nottinghamshire; the distance from Barnsley not exceeding 35 miles.

In the year 1864 the above-named railway carried out of the county 25,363 tons, increased to 28,469 tons in the year 1865. In later years the following quantities were received by the Manchester, Sheffield, and Lincolnshire Railway Company, and distributed in districts remote from Lincolnshire :—

| Year. | Frodingham. | Holton-le-Moor. | Lincoln. | Total. |
|-------|-------------|-----------------|----------|---------|
| | Tons. | Tons. | Tons. | Tons. |
| 1867 | 86,587 | ... | ... | 86,587 |
| 1872 | 138,279 | 61,097 | ... | 199,376 |
| 1873 | 205,677 | 78,489 | ... | 284,176 |
| 1874 | 141,289 | 42,731 | 40,888 | 224,908 |
| 1875 | 217,630 | 45,328 | 80,890 | 343,848 |
| 1876 | 164,101 | 47,037 | 96,443 | 307,581 |
| 1877 | 172,265 | 23,195 | 97,977 | 293,437 |
| 1878 | 188,209 | 18,015 | 92,264 | 298,488 |
| 1879 | 150,298 | 2,565 | 76,908 | 229,771 |
| 1880 | 262,359 | 21,937 | 73,948 | 358,244 |

The value of the ironstone at the pits, put into trucks, varies,

* Of the value of £15,627, or 4s. per ton.

according to quality, from 2*s.* 9*d.* to 3*s.* and 3*s.* 3*d.* per ton, the ironstone also bearing a moderate charge for transport. In recent years it has been used in works near Middlesborough, and at Wingerworth and other iron works in Derbyshire, and even in Lancashire.

The annexed list shows the localities of the mines, their proprietors and managers, in the year 1880 :—

| No. | Name of Mine. | Situation. | Name of Proprietor or Company. | Name of Manager or Agent. |
|-----|-------------------|--------------------|--|--|
| 1 | Appleby . . . | Brigg . . . | Cliff & Sons | F. Walsham |
| 2 | Claxby . . . | Market Rasen . . . | W. Yorkshire Iron and Coal Co. | Dr. England |
| 3 | Caythorpe . . . | Grantham . . . | M. C. Cohen | M. C. Cohen |
| 4 | Normanby . . . | Frodingham . . . | William Cook & Co., Limited . . . | C. F. Roseby |
| 5 | Frodingham . . . | Brigg . . . | Charles Winn . . . | John Roseby |
| 6 | " . . . | " . . . | Cliff & Sons | F. Walsham |
| 7 | Gunbrose . . . | " . . . | Park Gate Iron Co., Limited . . . | George Reed |
| 8 | Greetwell . . . | Lincoln . . . | { Mid. Lincolnshire Iron Co. ; W. J. Roseby, Man. Partner } | R. Ramsden |
| 9 | Monks Abbey . . . | " . . . | " . . . | " . . . |
| 10 | Trent . . . | Scunthorpe . . . | Mrs. W. H. Dawes . . . | J. H. Dawes |
| 11 | Glebe . . . | Frodingham . . . | Staveley Coal and Iron Co. Lim. | { Charles Markham, Man. Director. } |

Pig Iron Manufacture.—This industry in North Lincolnshire is of comparatively recent date. About the year 1862 the Messrs. Dawes, of the Milton and Elsecar Iron Works, near Barnsley, laid down and erected the Trent Iron Works. The same firm had previously been engaged in the development of the ironstone deposits of the district, which were conveyed to the works near Barnsley, above named, and smelted in admixture with the argillaceous ores of the coal measures, producing a quality of iron suitable for mill, forge, and foundry purposes. The Trent Works commenced operations in 1863. In the year 1866 the Frodingham Iron Company, situated at Scunthorpe, were started by Messrs. Cliff and Hurst, and in the year 1867 this firm had two furnaces in blast. The North Lincolnshire Iron Company followed about the same date with one furnace, blowing in a second furnace in the year 1871. The next metallurgical works projected were those of the Lincolnshire Iron Smelting Company and the Redbourn Hill Iron and Coal Company, the former about the year 1872, and the latter more recently, in the year 1874, the last works established being those of the Appleby Iron Company, who commenced operations about the year 1877.

The Lincolnshire furnaces vary considerably in size and

capacity ; those of the Trent Company, erected in 1862 and 1863, are 40 feet high and 14 feet in diameter at the boshes ; others erected by the same firm in the year 1875 are 60 feet high and 18 feet in the boshes. Those of the Frodingham Company vary from 63 to 65 feet in height, having a diameter at the boshes of 18 feet. The furnaces of the North Lincolnshire Iron Company, erected in 1865 and 1867, are 70 feet and 52 feet in height, and 20 feet in the boshes ; the furnaces erected by the same company in the year 1875 being 60 feet in height and 20 feet 9 inches in the boshes.

The most capacious furnaces in the district are those of the Redbourn Hill Iron and Coal Company, 75 feet in height and 20 feet diameter in the boshes. The furnaces of the Lincolnshire Smelting Company are 70 feet in height and 20 feet diameter in the boshes, while those of the Appleby Iron Company are 62 feet in height and 18 feet diameter in the boshes.

The Redbourn Hill furnaces, the largest in the district, possess some interesting features, designed by Mr. Dobbs, of Middlesborough, and constructed so as to deal with the excess of moisture contained in the ironstone. The arrangements are thus described : " The gas may be taken off either at the top or at a point 22 feet lower down, and the arrangement is to take off at the lower point sufficient gas to supply the stoves and boilers, and then to allow the surplus gas to pass through the material above the point, and to escape, with the moisture driven off, through an escape-pipe fixed on the upper gas box." The plan appears to work well ; the lower flue, however, requires attention, as it is quickly choked with dust, and renders frequent cleaning necessary. In the open-topped furnaces of the district the gas is taken off at distances varying from 8 to 15 feet from the top, and with sufficient draft of chimney enough can be obtained to do away entirely with the use of coal at either stoves or boilers. The stoves employed throughout the district are of the ordinary Cleveland type, and the temperature obtained varies from 800° to 1000° Fahr.

The first ton of pig iron was cast, in the year 1864, at the Trent Works ; in the same year the united production of Lincolnshire and Northamptonshire amounted to 22,823 tons, increased in the following year to 25,728 tons. In subsequent years the furnaces built and in blast, and the make of pig iron,

in Lincolnshire, was as follows till the year 1871, to which is appended the average yield per furnace :—

| Year. | FURNACES. | | Pig Iron Made. | Average per Furnace. |
|-------|-----------|-----------|----------------|----------------------|
| | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Tons. |
| 1864 | 5 | 3 | 9,600 | 3,200 |
| 1865 | 5 | 3 | 11,028 | 3,676 |
| 1866 | 6 | 3 | 13,765 | 4,588 |
| 1867 | 6 | 5 | 25,579 | 5,116 |
| 1868 | 6 | 5 | 33,999 | 6,780 |
| 1869 | 6 | 5 | 33,768 | 6,752 |
| 1870 | 6 | 4 | 31,690 | 7,922 |
| 1871 | 7 | 4 | 30,122 | 7,530 |

Coal and Iron Ore used in Manufacture.—The fuel employed is Durham coke, and coke obtained from the South Yorkshire coal-field, analyses of which will be found in each of those coal-producing districts.

In the following table appears the number of furnaces built and in blast, the make of pig iron, and the quantities of coal and ore used in its manufacture, in each year since 1871 :—

| Year. | FURNACES. | | Pig Iron. | Coal Used. | Ore Used. |
|-------|-----------|-----------|-----------|------------|-----------|
| | Built. | In Blast. | | | |
| | Nos. | Nos. | Tons. | Tons. | Tons. |
| 1871 | 7 | 4 | 30,122 | 84,000 | 106,000 |
| 1872 | 9 | 7 | 36,989 | 105,658 | 130,000 |
| 1873 | 13 | 9 | 52,076 | 142,236 | 188,050 |
| 1874 | 15 | 8 | 67,260 | 167,188 | 253,596 |
| 1875 | 21 | 14 | 111,683 | 303,000 | 393,000 |
| 1876 | 21 | 16 | 125,198 | 297,676 | 454,836 |
| 1877 | 21 | 10 | 116,857 | 265,232 | 428,459 |
| 1878 | 21 | 11 | 125,043 | 270,050 | 453,053 |
| 1879 | 21 | 14 | 131,678 | 261,395 | 465,818 |
| 1880 | 21 | 15 | 207,704 | 481,807 | 790,819 |

The above figures show a varying average ; in the year 1871 there were 56 cwts. of coal, and in 1872, 57 cwts. to each ton of pig iron made, while in 1878 the quantity did not exceed 43 cwts., a saving in seven years of 13 cwts. of coal in each ton of iron made. This economy is mainly due to the more extensive use of Durham coke, and the utilization of the waste gases. The

foregoing figures are actual returns, and include all coal used in all processes carried out in the works. In the close-topped furnaces of the district it has been determined, all conditions being favourable, the furnace in good working order, that the consumption of Durham coke does not exceed 24 cwts., and even less. This would be equivalent to from 34 to 35 cwts. of coal in the furnace, the remainder being otherwise employed in the works. Again, in the open-topped furnace, using the same class of coke, from 27 to 28 cwts. are employed, equivalent to 40 cwts., taking in each case the yield at 70 per cent., while in the same type of furnace using the South Yorkshire coke the consumption is found to be from 30 to 32 cwts., equal to from 49 to 51 cwts. of coal, the latter yielding of coke 62 per cent.

The ironstone, which is chiefly employed in the raw state, requires from 70 to 71 cwts., owing to the lime it contains; when calcined in clump and exposed to the weather it decrepitates, and it has been suggested that this result might be got over if the stone was charged hot from the calcining kiln to the furnace. The amount of moisture contained in the raw stone varies with the season, amounting in the winter months to 30 per cent., greatly increasing the consumption of fuel. As already stated, the Lincoln stone is used in admixture with the Frodingham stone; the Santon clay (worked at Santon, some four or five miles from Brigg), also referred to, is occasionally used as a fluxing material. Its composition is as follows, containing 4·75 per cent. of iron :—

SANTON CLAY.

| | |
|------------------------------------|--------------|
| Silica | 50·10 |
| Alumina | 22·72 |
| Peroxide of iron | 6·78 |
| Lime | 4·28 |
| Magnesia | 1·56 |
| Water and organic matter | 14·33 |
| Total | <u>99·77</u> |

CHAPTER XIV.

NORTH WALES IRON INDUSTRIES.

Iron Ore Deposits of Denbighshire and Flintshire—Analyses and Production of Iron Ore—Population employed in Iron Mining—Succession of Strata in Denbighshire—Pig Iron Manufacture—Early History—Production—Works in Operation in 1880—Malleable Iron Works—Coal and Iron Ore used in Pig Iron Manufacture.

Iron Ore Deposits.—Some ten years since a discovery was made of a rich argillaceous iron ore, consisting of 6 or 7 bands of a dark ironstone on the out-crop of the Ruabon coal-field at Trefechan, and some 90 or 100 yards below the Llwynenion or Half-yard coal of that district. This ironstone does not appear to have been wrought to any extent, though it has been known to yield iron of very good quality. On an adjoining property near Trefechan, it is stated that these ores were successfully reduced by a former proprietor who, between the years 1811 and 1824, produced some 80,000 tons of pig iron from ores raised there, some specimens of the iron referred to showing a curiously close-grained structure.

In Flintshire, at the Cwm Mountain, near Prestatyn, a deposit of red hematite occurs, about $1\frac{1}{2}$ miles south-east of the far-famed Talargoch lead mine. The ore here occurs almost entirely as a breccia of angular fragments, cemented by crystalline carbonate of lime. It fills very irregular lodes in the carboniferous limestone, and extends also in an irregular form between the limestone and underlying Silurian rocks to a short distance from the lodes.

In the neighbouring hill, Moel Hirradug, several small deposits have been worked, some, it is supposed, at a very early date. The ore occurs in "pockets," produced by the sudden widening out of small joints in the carboniferous limestone. These deposits have

been worked since the year 1870, and appear to contain both nickel and cobalt: an average assay giving cobalt 2·05 per cent., nickel 0·75 per cent, with oxide of iron. Other deposits have been worked at Caerwys, and at Gled-lôm, near Ysceifiog, and in all these cases the iron ore is found in the lowest beds of the limestone.

A number of similar pockets are being worked in the small patch of limestone near Bodfari. They are here connected with a system of strong joints, having a west-north-west direction.

Analyses of the Ironstone.—The argillaceous ores of Denbighshire contain from 80 to 96 per cent. of metallic iron. The ironstone raised at Trefechan gives 86·31 per cent. of metallic iron, and on calcination 51·54 of metallic iron. A complete analysis of this ironstone, by Mr. John Collins of Bolton, exhibits the following constituents:—

RESULTS TABULATED.

| | |
|------------------------------------|---------------|
| Metallic iron | 36·31 |
| Manganese | 1·31 |
| Magnesia | 3·39 |
| Lime | 3·03 |
| Alumina | 0·79 |
| Water | 0·98 |
| Carbonic acid | 33·06 |
| Phosphoric acid | 1·09 |
| Sulphuric acid | trace |
| Ignited insoluble matter | 20·06 |
| Total | <u>100·00</u> |

It is said of this ironstone that it is unusually free from impurities and comes comparatively clean from the mine, requiring but little preparation for the calcining heap.

Production of Ironstone.—The great bulk of the ironstone smelted in the furnaces of North Wales is obtained from the ironstone measures of the Denbighshire coal-field in the neighbourhood of Ruabon. The quantity raised in the year 1855 amounted to 65,820 tons; hematite ores raised in the same year in the neighbourhood of Rhyl and Cwm Mountain in Flintshire amounting to 1,820 tons. In the years 1856 and 1857 the total quantities of all kinds of iron ore and stone were respectively 65,914 tons and 70,874 tons, the details of production being as follows in each of those years:—

| Collieries and Mines. | 1856. Quantities. | 1857. Quantities. |
|-----------------------------|----------------------|----------------------|
| | Tons. | Tons. |
| Afon Eitha | 367 | 367 |
| Brymbo | 29,558 | 30,715 |
| Bryn Mally | 1,648 | 1,500 |
| Broughton | 82 | 90 |
| Coed Poeth | 1,890 | 1,800 |
| Cwm Mountain (Hematite) . . | ... | 1,650 |
| Dolydd | 200 | 350 |
| Ffrwd | 6,000 | 6,000 |
| Llwynenion | 1,200 | 1,150 |
| Nannerch | ... | 1,080 |
| Plasissa | 6,397 | 7,142 |
| Quinta | 50 | ... |
| Trafynant | 1,500 | 1,430 |
| Vron | 37 | 100 |
| Ruabon | 16,985 | 17,000 |
| Total | 65,914 | 70,374 |

Smaller quantities obtained from other collieries in 1856 make the total 70,000 tons; and 20,000 tons, in 1857, brings the total yield for that year up to 90,374 tons. The production of iron ore of all kinds in North Wales since 1858 has been as follows:—

| Year. | Denbigh- shire. | Flintshire. | Carnarvon- shire. | Sundry Mines. | Total North Wales. |
|-------|--------------------|-------------|----------------------|------------------|-----------------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1858 | 48,935 | 3,590 | 1,650 | 35,000 | 88,575 |
| 1859 | 38,822 | 3,500 | 1,750 | 39,000 | 87,073 |
| 1860 | 85,000* | ... | 97 | ... | 85,097 |
| 1861 | 82,500 | 4,000 | ... | ... | 86,500 |
| 1862 | 51,700 | 2,456 | ... | ... | 54,156 |
| 1863 | 27,550 | 732 | ... | ... | 28,282 |
| 1864 | 23,750 | 5,377 | ... | ... | 29,127 |
| 1865 | 97,500 | 750 | ... | ... | 98,250 |
| 1866 | 55,690 | 992 | ... | ... | 56,682 |
| 1867 | 43,582 | 500 | ... | ... | 44,082 |
| 1868 | 35,813 | 500 | ... | ... | 36,313 |
| 1869 | 33,431 | 62 | ... | ... | 33,493 |
| 1870 | 59,140 | 100 | ... | ... | 59,240 |
| 1871 | 51,887 | ... | ... | ... | 57,887 |
| 1872 | 23,045 | 4,730 | ... | ... | 27,775 |
| 1873 | 25,000 | 3,860 | ... | 9,426 | 38,286 |
| 1874 | 41,157 | 1,070 | ... | ... | 42,227 |
| 1875 | 39,907 | 2,277 | ... | ... | 42,184 |
| 1876 | 40,952 | ... | ... | ... | 40,952 |
| 1877 | 41,711 | 498 | ... | ... | 42,209 |
| 1878 | 43,082 | 378 | ... | ... | 43,460 |
| 1879 | 38,936 | 392 | ... | ... | 39,328 |
| 1880 | 41,413 | 1,603 | ... | ... | 43,016 |

* Including produce of Flintshire.

The great bulk of ironstone raised in North Wales is of the variety known as argillaceous carbonate. The average value of the ore in the year 1870 was about 7s. per ton, increased to 14s. per ton in 1872, receding in 1875 to 10s. per ton, since which date it has remained with but little variation.

Population employed in Iron Mining in Flintshire.—In the mines raising hematite in two or three localities in Flintshire, the following were the numbers employed in each year since 1873, and although the numbers are small and the produce of iron ore unimportant, it cannot but be interesting to note up all information bearing on the subject:—*

| Year. | PERSONS EMPLOYED. | | Total. | Iron Ore Raised. | Average per Man. |
|-------|-------------------|---------------|--------|------------------|------------------|
| | Under Ground. | Above Ground. | | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| 1873 | 46 | 15 | 61 | 4,730 | 77 |
| 1874 | 36 | 9 | 45 | 4,716 | 104 |
| 1875 | 19 | 4 | 23 | 1,069 | 46 |
| 1876 | 2 | ... | 2 | 26 | 13 |
| 1877 | 2 | 12 | 14 | 498 | 35 |
| 1878 | 9 | 4 | 13 | 378 | 29 |
| 1879 | 4 | 9 | 13 | 232 | 18 |
| 1880 | 9 | ... | 9 | 950 | 105 |

The Denbighshire iron furnaces are chiefly supplied by the ironstone measures of the coal-field. In the year 1851 when, as already stated, the late Mr. Samuel H. Blackwell exhibited in the Great Exhibition a most interesting series of iron ores, illustrating the iron making resources of the United Kingdom, the ironstone measures of Denbighshire were thus referred to, showing the following succession of strata in section:—

| STRATA. | THICKNESS. |
|--|------------|
| | Ft. In. |
| Three-yard Coal | 9 0 |
| Brassey Coal | 2 3 |
| Upper-yard Ironstone; four irregular courses averaging about | 0 7 |
| Upper-yard Coal | 2 6 |
| Red Coal Ironstone Balls. | |
| Red Coal | 1 6 |
| Stone Coal Ironstone; four courses. | |
| Stone Coal. | 2 9 |
| Half-yard Coal | 1 6 |

* H.M. Inspectors of Mines Reports.

| STRATA (continued). | THICKNESS. Ft. In. |
|--|-----------------------|
| <i>Two-yard Coal Ironstone.</i> | |
| <i>Lower-yard Ironstone.</i> | |
| <i>Lower-yard Coal</i> | 3 0 |
| <i>Wall and Bench Ironstone</i> ; six courses, equal to 12½ in., lying in about 7 ft. of ground. | |
| <i>Wall and Bench Coals</i> | 3 0 |
| <i>Llwynenion Ironstones</i> ; fifteen courses, averaging 30 in., all worked with the coal in three lifts; will yield from 8,000 to 9,000 tons per acre. | |
| <i>Llwynenion Coal</i> | 1 6 |

Production of Pig Iron.—As far back as the year 1740, the reduction of the ores of iron appears to have been carried on in North Wales in Denbighshire. The returns of production for that year show the existence of two blast furnaces, yielding 550 tons of pig iron, the total make of the 59 furnaces in operation in England and Wales at that time being 17,350 tons, giving an average yield per furnace of 294 tons. Advancing to the year 1788, when the aggregate production of pig iron in England and Wales amounted to 61,300 tons, of which 13,100 tons were charcoal iron, and 48,200 tons coke pig iron, the former the yield of 24 and the latter of 53 furnaces, North Wales at this period does not appear to have had any share in the manufacture. Later, in the year 1796, Denbighshire appears to have had five furnaces in operation, yielding 6,230 tons of pig iron. The details of production were the result of an inquiry instituted by the House of Commons, at the time that Mr. Pitt proposed to levy a tax on coal, to be paid, without exception, at the pit's mouth, a measure subsequently abandoned. The works in operation in 1796, with the make of each, is recorded as follows :—

| WORKS. | TONS. |
|-----------------------|--------------|
| Brymbo | 884 |
| Brymbo Gate | 728 |
| Pentroba | 1,560 |
| Penyvyron | 1,498 |
| Buabon | 1,560 |
| Total | <u>6,230</u> |

The total production of pig iron in Great Britain in 1796, according to the returns of the Excise authorities, is set down at 167,311 tons. Subsequent inquiries showed the quantities actually made not to have exceeded 125,080 tons; even this is a considerable advance on the production of 1788. In the beginning of the present century (1806), the two principal ironworks

in Denbighshire were those of Ruabon of Messrs. Rowland & Co., and those of Brymbo of Mr. S. Wilkinson; the Ruabon furnace producing 1,463 tons of pig iron, and the Brymbo, 462 tons, the last named works being in operation but a part of the year. The total make of pig iron in Great Britain in 1806 being 243,851 tons, the yield of 161 furnaces.*

Not again until the years 1823 and 1830 are returns available. In the last named year Mr. F. Finch, in his inquiry carried out for the Government, ascertained that the make of 7 furnaces in North Wales in 1823 was 13,100 tons of pig iron, increased in 1830 to 12 furnaces and 25,000 tons, showing an increase of 12,000 tons in 7 years. Mr. H. Scrivener * gives the following as the number of furnaces and make of pig iron in the years named :—

| Year. | Furnaces. | Pig Iron Made. |
|-------|-----------|----------------|
| | Nos. | Tons. |
| 1825 | 7 | 13,100 |
| 1826 | 7 | 15,756 |
| 1828 | 12 | 25,168 |

Advancing to the year 1839, when Mr. David Mushet made his inquiry, the production of Great Britain was 1,248,781 tons, there being at that period 20 furnaces in North Wales, of which 13 were in blast, making 33,800 tons of pig iron, giving an average of 2,600 tons per furnace.

Mr. Porter,† in the year 1840, gave the make of North Wales as 26,500 tons, and the make of the kingdom the same year, 1,396,400 tons. Again, in 1847, a return to Parliament gives the number of furnaces in North Wales as 11, of which 5 were active, producing 16,120 tons of pig iron; the details are as under :—

| Works. | Furnaces. | Pig Iron Made. |
|---------------------------|-----------|----------------|
| | Nos. | Tons. |
| Brymbo | 2 | 6,240 |
| British Company | 1 | 5,200 |
| Coed Talon | 1 | 1,560 |
| Plasiassa | 1 | 3,120 |
| Total | 5 | 16,120 |

* For details see Appendix II., p. 834.

† "Progress of the Nation," by G. R. Porter, F.R.S.

The total make of pig iron in the kingdom the same year was 1,999,568 tons, the make of 433 furnaces. In the year 1852 the production increased to 2,701,000 tons. The only works of which we have any account at this period in North Wales are those of Brymbo, with two furnaces, and Ruabon, with three furnaces. Advancing to the year 1854 the resources of production had greatly increased, there being at that date 7 works in North Wales, with an aggregate of 11 furnaces, 9 of which were active, producing 32,900 tons of pig iron, giving an average of 3,633 tons per furnace. The works and companies in 1854 were as follows :—

| Name of Works. | Owners. | FURNACES. | |
|--------------------|------------------------------|-----------|-----------|
| | | Built. | In Blast. |
| | | Nos. | Nos. |
| Brymbo | The Brymbo Co. | 2 | 2 |
| Coed Talon | Oakley & Co. | 1 | 0 |
| Ffrwd | Sparrow & Co. | 1 | 1 |
| Leeswood | Oakley & Co. | 2 | 1 |
| Ruabon | New British Iron Co. | 3 | 3 |
| Plasissa | Samuel Gilkes | 1 | 1 |
| Plaskynaston . . | Moss and Luker | 1 | 1 |
| | Total | 11 | 9 |

In Great Britain at this period the total production of pig iron amounted to 3,069,838 tons, the make of 555 furnaces, of which 307 were in England, 130 in Wales, and 118 in Scotland. The details are as under :—

| DISTRICTS. | QUANTITIES. |
|---|------------------|
| | Tons. |
| Northumberland, Durham, and North Yorkshire | 275,000 |
| Cumberland and Lancashire | 20,000 |
| Yorkshire (West Riding) | 73,444 |
| Derbyshire | 127,500 |
| Staffordshire | 847,600 |
| Shropshire | 124,800 |
| Gloucestershire | 21,990 |
| North Wales | 32,900 |
| South Wales | 750,000 |
| Scotland | 796,604 |
| Total production in 1854 | <u>3,069,838</u> |

In subsequent years the number of furnaces built and in blast in North Wales, with the make of pig iron, and the average make per furnace, will be found in the annexed table :—

| Year. | FURNACES. | | Make of Pig Iron. | Average per Furnace. |
|-------|-----------|-----------------|-------------------|----------------------|
| | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Tons. |
| 1855 | 11 | 8 | 31,420 | 3,927 |
| 1856 | 10 | 9 | 47,682 | 5,298 |
| 1857 | 14 | 6 | 37,049 | 6,174 |
| 1858 | 13 | 6 | 28,150 | 4,692 |
| 1859 | 13 | 6 | 26,980 | 4,496 |
| 1860 | 14 | 8 | 49,360 | 6,142 |
| 1861 | 12 | 5 | 46,658 | 9,331 |
| 1862 | 13 | 5 | 31,719 | 6,344 |
| 1863 | 13 | 7 | 51,076 | 7,296 |
| 1864 | 14 | 8 | 51,108 | 6,388 |
| 1865 | 14 | 7 | 51,874 | 7,410 |
| 1866 | 10 | 5 | 25,515 | 5,103 |
| 1867 | 9 | 5 | 32,843 | 6,568 |
| 1868 | 9 | 4 | 37,046 | 9,261 |
| 1869 | 8 | 6 | 38,530 | 6,421 |
| 1870 | 8 | 6 | 42,695 | 7,116 |
| 1871 | 8 | 5 | 41,893 | 8,378 |
| 1872 | 8 | 4 $\frac{1}{2}$ | 41,464 | 8,728 |
| 1873 | 9 | 5 | 42,773 | 8,554 |
| 1874 | 9 | 6 | 51,868 | 8,644 |
| 1875 | 9 | 6 | 55,099 | 9,183 |
| 1876 | 11 | 4 | 32,723 | 8,181 |
| 1877 | 11 | 3 $\frac{1}{2}$ | 26,715 | 7,630 |
| 1878 | 11 | 3 | 23,091 | 7,697 |
| 1879 | 11 | 3 | 18,953 | 6,317 |
| 1880 | 10 | 7 | 57,812 | 8,259 |

The above returns in the years 1874 and 1875 include the production of the Mostyn Coal and Iron Co., Flintshire, who have two furnaces, which were in blast in those years, and continued in operation till March, 1876, since which date they have been standing. The yield of the Mostyn Works in 1872 and 1873 was respectively 13,228 tons and 24,690 tons, which are included in the above returns for those years. The works and furnaces in North Wales in the year 1880 were as follows :—

| No. | Name of Works. | Owners. | FURNACES. | |
|--|------------------------|---------------------------------|-----------|-----------|
| | | | Built. | In Blast. |
| | | | Nos. | Nos. |
| <i>Denbighshire—</i> | | | | |
| 1 | Brymbo | Brymbo Iron Co. | 3 | 2 |
| 2 | Ffrwd, Wrexham | James Sparrow & Son | 3 | 2 |
| 3 | Ruabon | New British Iron Co. | 2 | 1 |
| <i>Flintshire—</i> | | | | |
| 1 | Mostyn | Mostyn Coal and Iron Co., Lim.. | 2 | 2 |
| Total of Denbighshire and Flintshire . | | | 10 | 7 |

Malleable Ironworks.—There are five of these establishments in North Wales, situated at Ruabon and Wrexham, in Denbighshire, possessing considerable resources for the manufacture of the various forms of iron. The works of the New British Iron Co., at Ruabon, contain 34 puddling furnaces and 4 rolling mills; the Broughton Hall Works, near Wrexham, 10 furnaces and 2 rolling mills; the Pontysylle Works of Messrs. Hyde, Jones and Mackay, 13 furnaces and 1 rolling mill; the Stansty Works of Messrs. Forrest and Co., 6 furnaces and 1 mill; and the Llay Hall Works at Ruabon, where fire-bricks are also manufactured. When in active operation it is estimated that the consumption of coal would not be less than from 60,000 to 70,000 tons per annum. For some years past much inactivity has prevailed in these works, and the returns for 1880 show that all were standing except the Ruabon Works of the New British Iron Company, which establishment had 13 puddling furnaces in operation out of a total of 30, and 4 rolling mills, the consumption of fuel probably not exceeding 16,000 tons of coal.

Coal and Iron Ore used in Manufacture.—It appears, on the authority of Mr. G. R. Porter,* that the coal used in 1840 in the make of 26,500 tons of pig iron in Denbighshire was 110,000 tons, giving an average of 4 tons 3 cwt. to each ton of pig iron made.

In the year 1872 and since, the quantities of coal and ore used in the works in North Wales in pig iron manufacture were as under:—

| Year. | Pig Iron. | Coal Used. | Iron Ore Used. |
|-------|-----------|------------|----------------|
| | Tons. | Tons. | Tons. |
| 1872 | 41,464 | 185,000 | ... |
| 1873 | 42,773 | 187,278 | 143,973 |
| 1874 | 51,868 | 140,942 | 127,023 |
| 1875 | 55,099 | 144,652 | 139,540 |
| 1876 | 32,723 | 83,188 | 66,385 |
| 1877 | 26,715 | 59,669 | 51,717 |
| 1878 | 23,091 | 48,249 | 47,234 |
| 1879 | 18,953 | 35,804 | 39,500 |
| 1880 | 57,812 | 139,328 | 130,676 |

An examination of the above returns for the years 1872 and 1873 shows a consumption of upwards of 4 tons of coal to each

* "Progress of the Nation."

ton of pig iron made. In 1875 it did not exceed 50 cwt. of coal and 51 cwt. of iron ore in the Denbighshire furnaces, while in the Flintshire Works at Mostyn, where hematite chiefly was smelted, the average did not exceed 41 or 42 cwt. of coal and ore to each ton of pig iron made. The ores employed include argillaceous ores of the district Pottery Mine, North Staffordshire, hematite from Lancashire and Spain, and Northampton ore.

The proportion of coal and ore used in 1880 to each ton of pig iron made was respectively 49 cwt. of coal and 45 cwt. of ore, compared with 50 cwt. of coal and 51 cwt. of ore in 1875; while in recent years it appears that hematite ores have been more extensively employed than formerly.

CHAPTER XV.

SOUTH WALES AND MONMOUTHSHIRE IRON INDUSTRIES.

Ironstones of the Coal Measures—Order of Occurrence—Description and Analyses—Iron Ore Deposits of the Carboniferous Limestone, Whitchurch, Mwyndy, Hendy, and Wenvoe—Production and Analyses—Pig Iron Manufacture—Early History—Monmouthshire, Brecknockshire and Glamorganshire—Account of Cyfarthfa Works—Anthracite Pig Iron—Early History—Production of Pig Iron in Bituminous and Anthracite Coal districts since 1855—Mills and Forges and Bessemer Steel Works and Coal employed—Coal and Iron Ore used in Pig Iron Manufacture in South Wales.

The Clay Ironstones.—Formerly the ironworks of South Wales depended almost entirely upon the clay ironstones of the coal measures (argillaceous carbonates of iron): these in recent years have become more expensive to raise, as they recede further from the outcrop. At one period two-thirds of the ironstone used in the blast furnaces of Great Britain were obtained from the coal measures, now the quantities do not exceed one-third of all the ironstone raised in the kingdom.

The late Mr. Samuel Blackwell, of Dudley,* in his report of the iron ores of the kingdom, divides the South Wales coal-field into several districts, in each of which, sections are given distinguishing the strata, the seams of coal, and measures of ironstone, and the principal iron-works. The districts are enumerated as follows:—

The Eastern Outcrop.

The North-Eastern Outcrop.

The Northern Outcrop.

The Central Anticlinal District.

The Western or Anthracite District.

Southern Outcrop.

Eastern Outcrop.—In the district on the eastern edge of the coal basin, the ironstone measures hitherto wrought are at Blaenavon, known as the “Soap Vein Mine,” 6 inches thick, and in

* Catalogue of the Great Exhibition of 1851, Vol. I., p. 150.

descending order, the "Black Pins," "The Three-quarter Balls," the "Meadow Vein Mine," or Pwl Llaca, and two others of less importance, known as the "Spotted Vein Mine," and the "Bottom Vein Mine." It may be observed that these measures rarely exceed 5 or 6 inches in thickness, and that they are richer in metallic iron on the east, and become less so on the west, although the measures increase in thickness in that direction.

North-Eastern Outcrop.—In this district a great development of the ironstone measures appears; at Coalbrook Vale occurs the "Soap Vein Mine," a measure of four courses, equal to 7 inches, and yielding an average of about 2,000 tons of ironstone per acre. Below occurs a vein of black band very locally distributed and not generally worked. The "Soap Vein" coal, a seam of 15 inches, intervenes between the "Black Band" seam and the "Black Pins" ironstone. This measure consists of ten irregular courses of nodules in about 15 feet of ground, and yields of ironstone about 4,500 tons per acre. Next in descending order occurs the "Elled Coal," 3 feet 4 inches thick, and the "Big Vein Coal," 5 feet 6 inches thick. The next measure, the "Three-quarter Balls," consisting of three courses, two of which are irregular, yield an average of about 1,200 tons per acre, the measure reposing on the "Three-quarter Coal," with which it is worked. The coal seams below are as follows; the

| | Ft. | In. |
|-----------------------------------|-----|-----|
| <i>Bwdellog Coal</i> | 2 | 10 |
| <i>Engine Vein Coal</i> | 3 | 2 |
| <i>Yard Coal</i> | 3 | 8 |

Below is the 'Old Coal, 5 feet 6 inches thick, with which it is worked, a measure of black band of good quality but limited in area, and regarded as an important measure in the neighbourhood of Beaufort and Nanty-Glo.

The succeeding measures in the district before the bottom coal is reached are the "Spotted Pins," at Coalbrook Vale, consisting of two courses of $4\frac{1}{2}$ inches in 4 feet of ground, yielding about 1,200 tons per acre. The "Little Pins," Nanty-Glo, of two courses, equal to 5 inches in 3 feet of ground, and yielding about 1,400 tons. The "Red Vein," at Coalbrook Vale, of three courses, equal to $6\frac{1}{2}$ inches, and yielding 1,800 tons per acre. The lowest measure in this section, at Nanty-Glo, known as the "Big Vein," and worked with the Bottom Coal, consisting

of two courses, equal to 6 inches, and yielding per acre about 1,700 tons.

The beds of coal in this division of the coal-field are all bituminous, while those of the ironstones are principally argillaceous; but some important beds of black band, or carbonaceous ironstone, are also worked.

Northern Outcrop.—A well defined section of the measures at Dowlais, from the "Gwrid Mine," at the top of the series, to the "Bottom Rosser Mine," exhibits a thickness of about 320 yards. It is remarked by Mr. Blackwell in this section, that in the last 100 yards there are five workable beds of coal, varying from 2 feet to 9 feet thick, and 62 distinct courses of ironstone, varying from 1 to 5 inches thick, many of which, however, are not necessarily worked. The measures of coal and ironstone succeed, each in descending order, as follows:—

SUCCESSION OF STRATA.

Gwrid Mine.

Soap Vein.—Three courses, equal to 6 inches and worked with Soap Vein Coal.

Upper Black Pins.—Three courses, equal to 4 inches.

Lower Black Pins.—One course, equal to 3 inches.

Yard Coal, 3 ft. 6 in.

Upper Four-foot Coal, 3 feet.

Dowlais Big Coal, 8 feet.

Black Pin Soap Vein.—Five courses, equal to 11 inches, about seventeen yards beneath Big Coal.

Ras Las Coal, 7 ft. 9 in.

Brass Vein Mine.—Two courses, 3½ inches, lying immediately on Brass Vein Coal.

Brass Vein Coal, 2 feet.

Little Pins.—Eight courses, equal to 16 inches.

Three Coals, 3 feet.

Little Vein.—One course, equal to 5 inches lying over Little Vein Coal.

Little Vein Coal, 3 feet.

Big Blue Vein.—Three courses, equal to 8½ inches, lying 4 feet above Lower Four-foot Coal, 9 ft. 3 in.

Spotted Vein.—Three courses, equal to 13 inches, in 8 feet of ground, and lying about 5 yards below Lower Four-foot Coal.

Red Vein.—Four courses, equal to 11½ inches, in 8 feet of ground, and about five yards underneath "Spotted Vein."

Little Blue Vein.—Six courses, equal to 14 inches, in about 12 feet of ground.

Jenkin Pins.—Eight courses, equal to 12 inches, in about 10 feet of ground.

Lumpy Vein.—Three courses, equal to 6½ inches, in about 6 feet of ground, and worked with Lumpy Vein Coal, 1 ft. 3 in.

Top Rosser Mine.—One course, equal to 5 inches.

Bottom Rosser Mine.—Three courses, equal to 8 inches, in about 5 feet of ground.

In the district of the above section are established the important ironworks of Dowlais, Cyfarthfa, Aberdare, Rhymney, Gadlys, and others.

Central Anticlinal District.—In the neighbourhood of Llynvi and Cwm Avon occur two important seams of black band, the upper consisting of one course, equal to 20 inches, and worked also at Maesteg; while the lower black band consists of one course of 12 inches. These beds are about 22 yards apart, and for extent of area and general quality are the most important black bands in the South Wales coal-field. At Cwm Avon the black band averages 7 inches, while at Oakwood, the same measure attains a thickness of 22 inches. The coal and mine vein at the bottom of the Llynvi section has a thickness of 27 inches, and between it and the upper black band intervene some 13 seams of coal, varying from 16 inches to 7 feet, besides numerous measures of ironstone; some of the measures at the outcrop being dug in patches or open works.

In the Cwm Avon series the total thickness of the section from the Wernddu Seam to the Lower Four-foot Seam is about 800 yards, in which occur 19 seams of coal, varying from 14 inches to 9 feet, and 10 distinct courses of ironstone.

Western or Anthracite District.—The following section presents clearly the order of occurrence and the thickness of the more important ironstone measures in the Ystalyfera and the Ywiscedwin districts, where the beds of coal are exclusively anthracitic:—

SUCCESSION OF STRATA.

| | Ft. In. |
|---|---------|
| <i>Blackband, Ystalyfera.</i> —Fourteen inches thick, very local; yields about 2,750 tons per acre. | |
| <i>Black Pins, Ystalyfera.</i> —Two courses, equal to 8 inches; yields about 2,400 tons per acre. | |
| <i>Soap Vein, Ystalyfera.</i> —Three courses, equal to 10 inches; yields about 2,750 tons per acre. | |
| Soft Vein Coal. | |
| <i>Penny-Pieces, Ystalyfera.</i> —Three courses, with scattered balls; yields about 3,600 tons per acre. | |
| Penturin Coal | 3 0 |
| <i>White Pins, Ystalyfera.</i> —Sometimes called Coedfalds Mine; four courses, about 16 inches, in 14 feet of ground; yields about 4,800 tons per acre. | |
| White Vein Coal | 1 6 |
| <i>Black Vein Mine, Ystalyfera.</i> —Two courses, equal to 8 inches; yields about 2,400 tons per acre. | |
| Black Vein Coal | 4 0 |

SUCCESSION OF STRATA (*continued*).

| | Ft. | In. |
|---|-----|-----|
| <i>Little Vein Mine, Ystalyfera</i> .—Ten courses, in 18 feet of ground, got with Little Vein Coal; yields 7,400 tons per acre. This is the most important measure of ironstone in this district. | | |
| Little Vein Coal | 3 | 0 |
| <i>Billets, Ystalyfera.</i> | | |
| <i>Harnlo Mine, Ystalyfera</i> .—Two courses. | | |
| Harnlo Coal | 2 | 0 |
| <i>Big Vein, Ystalyfera</i> .—Two courses, equal to 6 inches; yielding 1,800 tons per acre, when worked by level; if worked in patches 16 feet of ground, all interspersed with stone. | | |
| Big Vein Coal | 5 | 6 |
| Black Vein Coal | 2 | 0 |
| <i>Brass Vein, Ystalyfera</i> .—Five courses, in 13 feet of ground; yielding 3,500 tons per acre. | | |
| Brass Vein Coal | 4 | 0 |
| Three-Coal Vein | 3 | 0 |
| Bryalvey Vein Coal | 3 | 0 |
| <i>Little Brass Mine, Yniscedwyn.</i> | | |
| Little Brass Vein | 2 | 0 |
| Middle Vein Coal | 2 | 6 |
| <i>Cwm Fit Mine, Yniscedwyn</i> .—Three courses. | | |
| Lower Vein Coal | 3 | 0 |
| <i>Little Blue Vein, Yniscedwyn.</i> | | |
| <i>Big Blue Vein</i> | „ | |
| <i>Gnappog Mine</i> | „ | |
| <i>Pin Mawr Mine</i> | „ | |

In reference to the measures of the above series Mr. Blackwell remarks, that they bear the appearance of having been subjected to an extremely high temperature; which has been, in all probability, the cause of the conversion of its beds of coal into anthracite.

Southern Outcrop.—A remarkable series of coal and ironstone measures are developed in this area of the coal-field; the following exhibit their order and thickness:—

| SECTION OF STRATA. | THICKNESS. | |
|----------------------------|------------|-----|
| | Ft. | In. |
| Rock Vein | 4 | 0 |
| Double Vein | 4 | 0 |
| Little Vein | 3 | 0 |
| Bridge Vein | 1 | 6 |
| Lantern Vein | 5 | 0 |
| Small Bodur Coal | 5 | 0 |
| Great Bodur Vein | 8 | 0 |
| Sooty Vein | 5 | 6 |
| North Vawr Vein | 12 | 0 |
| South Vawr Vein | 4 | 4 |
| Second Vawr Vein | 3 | 0 |
| Third Vawr Vein | 5 | 6 |
| Slattog Vein | 2 | 0 |
| Six-feet Vein | 6 | 0 |

| SECTION OF STRATA (<i>continued</i>). | | THICKNESS. |
|---|---|------------|
| | | Ft. In. |
| <i>Nine-foot Balls, Cefn Cwse.</i> —Four courses, equal to 9 inches. | | |
| South Nine-foot Coal | . | 9 0 |
| <i>Nine-foot Balls, Cefn Cwse.</i> —Seven courses, equal to 17 inches. | | |
| Fiery Vein Coal | . | 4 0 |
| <i>Fiery Vein Ironstone, Cefn Cwse.</i> —Six courses, equal to 14 inches. | | |
| Five Quarter Vein | . | 4 6 |
| Great Gribbur Vein | . | 6 0 |

Next follows an interesting section of ironstone measures at Cefn Cwse, 18 in number, before the Small Gribbur coal is reached :—

| | |
|--|-----|
| <i>Gribbur Balls.</i> —Two courses, equal to 6 inches. | |
| <i>Upper Spotted Vein.</i> —Two courses, equal to 4 inches. | |
| <i>Spotted Balls.</i> —Two courses, equal to 4 inches. | |
| <i>Middle Spotted Vein.</i> —Two courses, equal to 8½ inches. | |
| <i>Lower Spotted Vein.</i> —Two courses, equal to 4½ inches. | |
| <i>Variegated Pin.</i> —Two courses, equal to 5½ inches. | |
| <i>Yellow Vein and Balls.</i> —Two courses, equal to 8 inches. | |
| <i>Upper Red Vein.</i> —Two courses, equal to 3 inches. | |
| <i>Upper Red Vein Balls.</i> —Two courses, equal to 6 inches. | |
| <i>Lowest Red Vein.</i> —Two courses, equal to 4 inches. | |
| <i>Pin Rhybur Balls.</i> —One course, equal to 3 inches. | |
| <i>Black Balls.</i> —Two courses, equal to 3 inches. | |
| <i>Double Balls.</i> —Two courses, equal to 6 inches. | |
| <i>Black Pins.</i> —One course, equal to 3 inches. | |
| <i>Upper Blue Vein.</i> —One course, equal to 4 inches. | |
| <i>Blue Vein Balls.</i> —Two courses, equal to 4 inches. | |
| <i>Lower Blue Veins.</i> —Two courses, equal to 3 inches. | |
| <i>Lumpy Balls.</i> —One course, equal to 5 inches. | |
| <i>Pin Garu Balls.</i> —Two courses, equal to 8 inches. | |
| Small Gribbur Coal | 2 9 |

Analyses of the Ironstone.—The argillaceous ores of South Wales, like those of other coal-fields in the kingdom, are well represented in Mr. Samuel Blackwell's collection of iron ores previously referred to. Analyses of a large number of these have been made, and the results published in the "Memoirs of the Geological Survey," under the title of "The Iron Ores of Great Britain." From these analyses the following selection has been made, and will illustrate the composition and character of some of the important measures referred to in the several districts of the coal-field. These analyses, it should be stated, were made in the laboratory of the Royal School of Mines, under the care of Dr. Percy.

The ironstones on the eastern outcrop, at Blaenavon, known as the "Black Pins," "Three-Quarter Balls," and "Spotted Vein Mine," exhibit the following constituents, as determined by Mr. A. Dick :—

ORE DRIED AT 100° C.

| Constituents. | Black Pins. | Three-quarter Balls. | Spotted Vein Mine. |
|----------------------------------|-------------|----------------------|--------------------|
| Protoxide of iron | 41·22 | 36·10 | 45·22 |
| Protoxide of manganese | 1·07 | 0·76 | 1·05 |
| Alumina | 0·59 | 0·48 | 0·58 |
| Lime | 2·89 | 1·07 | 1·63 |
| Magnesia | 3·38 | 4·52 | 3·04 |
| Carbonic acid | 30·07 | 27·33 | 31·58 |
| Phosphoric acid | 0·76 | 0·18 | 0·38 |
| Sulphuric acid | trace | trace | trace |
| Bisulphide of iron | 0·15 | 0·11 | 0·71 |
| Water | 1·21 | 1·06 | 0·66 |
| Organic matter | 0·82 | 0·79 | 0·64 |
| Insoluble residue | 17·27 | 27·58 | 14·50 |
| Total | 99·43 | 99·98 | 99·99 |
| INSOLUBLE RESIDUE. | | | |
| Silica | 11·60 | 19·90 | 9·46 |
| Alumina | 4·29 | 6·09 | 4·20 |
| Peroxide of iron | 0·45 | 0·60 | ... |
| Lime | ... | 0·35 | ... |
| Magnesia | 0·30 | ... | 0·20 |
| Potash | 0·48 | 0·71 | 0·56 |
| Total | 17·12 | 27·65 | 14·42 |
| Metallic iron | 32·44 | 28·55 | 35·48 |

It is further remarked that a minute trace of copper was detected in the hydrochloric acid solution of 900 grains of ore of the "Black Pins;" while minute traces of copper and lead were detected in similar solutions of 870 grains of the "Three-Quarter Balls," and 905 grains of ore of the "Spotted Vein Mine." * The word mine, it may be observed, is commonly used in South Wales for ore.

The "Black Pin Mine" (Middle Pin), Pontypool, examined by Mr. E. Riley, is thus described: "Clay ironstone, easily scratched by a steel point; colour, blackish grey; fracture, subconchoidal; surface of fracture, rough. A very thin vein of carbonate of lime occurs in the sample analysed." A distinct trace of copper was detected in 234 grains of the ore. The results appear as follows:—

* "Iron Ores of Great Britain," Part III., pp. 183, 185, 186.

RESULTS TABULATED.*—ORE DRIED AT 100° C.

| | |
|--|--------------|
| Protoxide of iron | 26·98 |
| Protoxide of manganese | 0·49 |
| Alumina | 1·19 |
| Lime | 3·11 |
| Magnesia | 4·13 |
| Carbonic acid | 23·40 |
| Phosphoric acid | 0·35 |
| Silica, soluble in hydrochloric acid | 0·50 |
| Bisulphide of iron | 0·52 |
| Water in combination | 0·78 |
| Organic matter | 0·82 |
| Insoluble residue | 36·51 |
| Total | <u>98·78</u> |

INSOLUBLE RESIDUE.

| | |
|----------------------------|--------------|
| Silica | 27·41 |
| Alumina | 7·69 |
| Peroxide of iron | 0·73 |
| Lime | 0·22 |
| Magnesia | 0·42 |
| Potash | 1·18 |
| Soda | 0·16 |
| Total | <u>37·81</u> |

This ore, as appears from the above results, is not rich in metallic iron, yielding but 21·49 per cent.; clay, after ignition, giving 26·16 per cent.

The Black Band measures of Pontypool and Abercarne, examined by Mr. W. Ratcliffe and Mr. A. Dick, the former giving the following description of the Abercarne measure: "Colour, brownish grey; compact; containing thin seams of coal and films of pyrites in some of the joints," show the annexed results. The Abercarne variety giving 36·49 per cent. of metallic iron; the Pontypool, 24·90 per cent.:—

It is observed of the Black Band, Pontypool, that the combined water could not be determined owing to the large amount of tarry matter evolved when the ore was heated sufficiently to expel the water combined with the clay. Of hygroscopic water, however, it was found that in an analysis of 47·08 grains of this ore, the loss of water at 100° centigrade amounted to 0·29 grains.

* "Iron Ores of Great Britain," Part III, p. 191.

| Constituents.* | Black Band, Pontypool.† | Black Band, Abercarn. |
|--------------------------------|----------------------------|--------------------------|
| Protoxide of iron | 31·74 | 43·37 |
| Sesquioxide of iron | ... | 4·10 |
| Oxide of manganese | ... | 1·50 |
| Protoxide of manganese | 1·06 | ... |
| Alumina | 7·75 | 6·05 |
| Lime | 3·84 | 3·00 |
| Magnesia | 3·51 | 0·25 |
| Potash | 1·12 | 0·32 |
| Carbonic acid | 25·03 | 30·50 |
| Sulphuric acid | trace | 1·56 |
| Phosphoric acid | 0·35 | traces |
| Silica | 16·97 | 2·80 |
| Bisulphide of iron | 0·48 | ... |
| Hygroscopic water | ... | 0·27 |
| Combined water | ... | 0·31 |
| Organic matter | 8·50 | 6·25 |
| Total | 100·35 | 100·28 |

Traces of silver and copper were detected in 600 grains of the Pontypool Black Band.

North-Eastern Outcrop.—The ironstones of this district are well represented in the measures worked at the Cwm Celyn and Blaina Ironworks in Monmouthshire. The principal ironstones, taken in ascending order, in the section, are as follows:—Red Vein, Spotted Vein, Black Pins, and Soap Vein.† The analyses were made as far back as the year 1860 by Dr. Noad, F.R.S., for Messrs. Levick and Simpson, the then proprietors of the above-named ironworks.

It is observed in reference to the constituents of these measures that "Metallic sulphides are very unusual in the ironstones of this eastern extremity of the coal-field, remarkably so as compared with the ironstones of central England." On the other hand, these measures frequently contain quartz, and, more rarely, but yet in comparative abundance, Hatchettine and Millerite, or sulphide of nickel, substances not observed in the analogous deposits of our midland and northern coal-fields.

* Iron Ores of Great Britain, Part III., pp. 192–3.

† For detailed section of these measures, see page 193 of the "Iron Ores of Great Britain;" where also will be found descriptive notes on the ironstones of this and surrounding districts by Mr. W. Smyth, F.R.S.

| Tabulated Results of Analysis. | RED VEIN MEASURES. | | | |
|---|--------------------|-------------|---------------------|------------|
| | Red Vein. | Black Vein. | "Jack" in Red Vein. | Grey Vein. |
| Silica | 8·31 | 4·600 | 8·130 | 15·240 |
| Alumina, insoluble in hydrochloric acid | 3·13 | 2·000 | 2·220 | 3·300 |
| Alumina soluble in hydrochloric acid | 2·52 | 3·600 | 5·150 | 2·700 |
| Carbonate of iron | 73·79 | 80·220 | 51·120 | 70·500 |
| Carbonate of lime | 2·95 | 4·650 | 19·800 | 1·980 |
| Carbonate of magnesia | 3·80 | 2·910 | 11·880 | 3·000 |
| Protoxide of manganese | 0·92 | 1·020 | · | · |
| Phosphoric acid | 0·53 | 0·427 | · | 0·217 |
| Sulphuric acid | traces | trace | · | trace |
| Bisulphide of iron | 0·17 | 0·123 | · | 0·119 |
| Potash | 0·48 | · | · | · |
| Organic matter and water | 2·36 | · | · | · |
| | 98·96 | 99·550 | 98·300 | 97·956 |
| Loss by roasting | 24·00 | 30·700 | 30·40 | 28·00 |
| Metallic iron | 35·625 | 38·75 | 24·65 | 34·00 |

| Tabulated Results of Analysis. | BLACK PIN MEASURES. | | | SOAP VEIN MEASURES. | |
|--|---------------------|----------|-------------|---------------------|-------------------|
| | Black Pin. | Red Pin. | Yellow Pin. | Top Soap Vein. | Bottom Soap Vein. |
| Silica | 12·000 | 15·400 | 25·200 | 20·000 | 9·540 |
| Alumina insoluble in hydrochloric acid | 4·000 | 5·000 | 8·200 | 5·000 | 4·460 |
| Alumina soluble in hydrochloric acid | 1·150 | 3·520 | 8·200 | 2·850 | 2·500 |
| Carbonate of iron | 71·700 | 57·990 | 48·300 | 59·610 | 77·340 |
| Carbonate of lime | 2·640 | 3·450 | 1·200 | 4·500 | ... |
| Carbonate of magnesia | 4·230 | 8·580 | 6·000 | 4·800 | 0·900 |
| Protoxide of manganese | 1·420 | 0·640 | 0·327 | ... | 0·530 |
| Phosphoric acid | 0·482 | 0·750 | 0·214 | 0·424 | 0·576 |
| Sulphuric acid | trace | trace | trace | trace | trace |
| Bisulphide of iron | trace | 0·241 | 0·124 | 0·246 | 0·192 |
| Potash | 0·489 | 0·450 | 0·389 | 0·444 | 0·530 |
| Organic matter and water | 1·645 | 2·340 | 1·320 | 1·442 | 2·240 |
| | 99·756 | 98·361 | 99·474 | 99·316 | 98·808 |
| Loss by roasting | 28·00 | 26·80 | 22·70 | 25·20 | 29·90 |
| Metallic iron | 34·60 | 28·00 | 23·30 | 28·75 | 37·30 |

The following ironstones worked in the Blaenavon district, and employed at the Blaenavon Ironworks,* by Messrs. Thomas, exhibit the annexed results. They are thus described:—

1. *Black Pins*.—A nodular form of clay ironstone, having cracks of contraction partly filled with a white crystalline substance, composed of the carbonates of iron, lime and magnesia.

2. *Pwl Llaca*.—A clay ironstone, brownish grey in colour, and homogeneous. The seam measures $2\frac{1}{2}$ inches barely.

3. *Bottom Vein*.—A clay ironstone, light brownish grey in colour, homogeneous. The seam measures 3 inches.

4. *Ball Mine*.—Brownish grey clay ironstone, containing a few very thin seams of limespar.

5. *Grey Vein*.—A clay ironstone, brownish grey in colour, with very rough surface of fracture. The seam measures 2 inches.

| Constituents. | Black Pins. | Pwl Llaca. | Bottom Vein. | Ball Mine. | Grey Vein. |
|--------------------------|-------------|------------|--------------|------------|------------|
| Protoxide of iron . . . | 47·02 | 47·60 | 42·04 | 51·28 | 39·80 |
| Oxide of manganese . . . | 1·00 | 0·46 | 0·87 | 1·11 | 1·17 |
| Lime | 2·57 | 0·77 | 1·03 | 0·78 | 2·41 |
| Magnesia | 3·23 | 2·30 | 2·51 | 0·53 | 3·30 |
| Carbonic acid | 34·30 | 32·90 | 29·52 | 33·32 | 30·04 |
| Phosphoric acid . . . | 0·92 | 0·71 | 0·90 | 0·74 | 1·02 |
| Bisulphide of iron . . | 0·25 | 0·08 | 0·06 | 0·06 | 0·05 |
| Water hygroscopic . . | 0·34 | 0·32 | 0·36 | 0·18 | 0·54 |
| Water in combination . | 1·58 | 1·28 | 2·00 | 1·67 | 2·12 |
| Organic matter | 0·40 | 0·30 | 0·30 | 0·35 | 0·45 |
| Clay ignited | 8·63 | 13·60 | 20·87 | 10·33 | 19·40 |
| | 100·24 | 100·32 | 100·46 | 100·35 | 100·30 |
| Metallic iron | 36·77 | 37·32 | 33·20 | 40·12 | 31·45 |

The Northern Outcrop.—A series of the ironstones raised and smelted at the extensive ironworks at Dowlais,† Merthyr Tydfil, was analysed for the proprietors by Mr. Edward Riley, who has determined the constituents of the following measures:—

The Dowlais Rosser Vein Mine.—This ironstone is above the Lower Rosser Vein, and occurs in balls, with a very stony appearance and fracture. The sample was taken as an average:—

* See return to House of Commons, "Cast Iron Experiments," report made to War Office, 29th July, 1858, p. 148.

† See for detailed section the "Iron Ores of Great Britain," p. 200.

SOLUBLE IN ACIDS.

| | GRAINS. |
|----------------------------------|---------|
| Silica | 0·27 |
| Protoxide of iron | 41·03 |
| Alumina | 0·23 |
| Protoxide of manganese | 0·55 |
| Lime | 2·83 |
| Magnesia | 3·11 |
| Carbonic acid | 28·49 |
| Moisture | 0·57 |
| Combined water | 1·36 |
| Phosphoric acid | 0·70 |
| Organic matter | 0·07 |

INSOLUBLE IN ACIDS.

| | |
|----------------------------|-------|
| Silica | 13·08 |
| Alumina | 5·56 |
| Peroxide of iron | 0·41 |
| Lime | 0·17 |
| Magnesia | 0·25 |
| Potash | 0·86 |

Total 99·54

Metallic iron 32·18

The Dowlais Spotted Vein Mine.—This measure consists of three bands of ironstone, but that to which the analysis refers is only the lower band, consisting of large balls or roundish nodules, termed “riders,” which sometimes amount to 10 or 12 inches in thickness. They are often very cavernous, and exhibit in abundance crystals of quartz, carbonate of iron, and millerite, or sulphide of nickel. The yield of metallic iron of this measure is, in the calcined state, 53·6 per cent. Its constituents are as follows:—

RESULTS TABULATED.

| | |
|----------------------------------|-------|
| Silica | 8·38 |
| Alumina | 5·79 |
| Peroxide of iron | 76·61 |
| Red oxide of manganese | 1·21 |
| Lime | 3·13 |
| Magnesia | 3·96 |
| Phosphoric acid | 0·57 |
| Potash | 0·87 |
| Sulphur | 0·06 |

Total 100·58

Another measure, the “Gŵr Hyd Mine,” is of considerable value, the top vein of which is argillaceous, described as a “hard stone of a brownish hue and with granular fracture. The bottom vein of this Gŵr Hyd Mine is a black band ironstone containing sufficient carbonaceous matter to effect its calcination without the

aid of additional fuel. The top and bottom veins of the Gwr Hyd Mine yield as follows:—the first named giving of metallic iron 30·33 per cent., increased in the bottom or black band vein, to 37·80 per cent.

Central Anticlinal District.—The ironstones of this district are illustrated by analysis of the Sulphury Mine, Cwm Avon. This measure occurs between the Finery and the Sulphury seams of coal, and enjoys a high repute as a good ore. It consists of three courses averaging about 7 inches in thickness together. The top vein is a rough granular stone, of blackish grey tint, showing, on fracture, vertical lines of carbonate of lime and iron. The middle is very similar, showing also occasional crystals of blackish quartz in the cavities. The bottom vein is more compact, and breaks with irregularly angular fracture.

RETURNS TABULATED.—ORE DRIED AT 100° C.

| | |
|----------------------------------|--------------|
| Protoxide of iron | 40·30 |
| Protoxide of manganese | 1·03 |
| Alumina | 1·43 |
| Lime | 1·44 |
| Magnesia | 2·77 |
| Carbonic acid | 28·23 |
| Phosphoric acid | 0·88 |
| Sulphuric acid | trace |
| Bisulphide of iron | 0·09 |
| Water | 0·74 |
| Organic matter | 0·29 |
| Insoluble residue | 22·48 |
| Total | <u>99·68</u> |

INSOLUBLE RESIDUE.

| | |
|----------------------------|--------------|
| Silica | 14·43 |
| Alumina | 6·47 |
| Peroxide of iron | 0·34 |
| Magnesia | 0·17 |
| Potash | 0·82 |
| Total | <u>22·23</u> |

The metallic iron amounted to 31·63 per cent., and a trace of copper was detected in 800 grains of the ore.

The above analysis, and the following, in the Western district, were made by Mr. A. Dick, who describes the “White Pins,” Ystalyfera, sometimes called the Coedfaldia Mine, as follows:—“This measure consists of balls and pins, or roundish nodules and flat courses; although called white they are generally of a dark grey colour, and have frequent cracks, filled with carbonate of lime

and iron, which in the iron fracture give a vertical lenticular section :—

RESULTS TABULATED.—ORE DRIED AT 100° C.

| | |
|----------------------------------|--------------|
| Protoxide of iron | 29·34 |
| Protoxide of manganese | 0·73 |
| Alumina | 0·96 |
| Lime | 0·84 |
| Magnesia | 5·63 |
| Carbonic acid | 24·56 |
| Phosphoric acid | 0·14 |
| Sulphuric acid | trace |
| Bisulphide of iron | 0·08 |
| Water | 1·00 |
| Organic matter | 0·33 |
| Insoluble residue | 35·73 |
| Total | <u>99·34</u> |

INSOLUBLE RESIDUE.

| | |
|----------------------------|--------------|
| Silica | 24·98 |
| Alumina | 9·75 |
| Peroxide of iron | 0·53 |
| Magnesia | 0·20 |
| Potash | 1·00 |
| Total | <u>36·46</u> |

The metallic iron in this ore is equivalent to 23·22 per cent. ; a trace of lead being detected in 910 grains of the ore.

Another clay ironstone of the Ystalyfera district, known as the "Cheese Mine," published in the "Returns of Cast-Iron Experiments" previously referred to, is thus described: "The sample from which an average was selected for analysis, consisted of a nodule of clay ironstone, dark grey in colour, and intersected by numerous veins of calcareous iron spar, in which a few crystals of quartz were discovered."

RESULTS TABULATED.

| | |
|--------------------------------|---------------|
| Peroxide of iron | 42·72 |
| Oxide of manganese | 0·46 |
| Lime | 4·66 |
| Magnesia | 5·73 |
| Carbonic acid | 35·70 |
| Phosphoric acid | 0·40 |
| Bisulphide of iron } | traces |
| Silica, as quartz } | |
| Water hygroscopic | 0·26 |
| Water in combination | 1·54 |
| Organic matter | 0·30 |
| Clay ignited | 8·23 |
| Total | <u>100·00</u> |

The metallic iron contained in the above was equivalent to 33·45 per cent.

The annexed summary exhibits, at a glance, the amount of metallic iron contained in those measures of the South Wales coal-field contained in the foregoing analyses, and others :—

| Ironstones. | Analyst. | Metallic Iron. |
|---|------------------|----------------|
| <i>Monmouthshire—</i> | | |
| Spotted Veins, Blaenavon | A. Dick . . . | 35·48 |
| Three-quarter Balls, „ | „ . . . | 28·55 |
| Black Pin, „ | „ . . . | 32·44 |
| Spotted Vein Balls, Pontypool | E. Riley . . . | 34·96 |
| Meadow Vein, „ | A. Dick . . . | 26·01 |
| Three Cakes, „ | „ . . . | 20·95 |
| Black Pin, „ | E. Riley . . . | 21·49 |
| Black Band, „ | A. Dick . . . | 24·90 |
| „ Abercarne | W. Ratcliffe . . | 36·49 |
| Red Vein, Cwm Celyn | Dr. Noad . . . | 35·62 |
| Black Vein, „ | „ . . . | 38·75 |
| “ Jack ” in Red Vein, Cwm Celyn | „ . . . | 24·65 |
| Grey Vein, „ | „ . . . | 34·00 |
| Black Pin, „ | „ . . . | 34·60 |
| Red Pin, „ | „ . . . | 28·00 |
| Yellow Pin, „ | „ . . . | 23·30 |
| Top Soap Vein, „ | „ . . . | 28·75 |
| Bottom Soap Vein, „ | „ . . . | 37·30 |
| <i>Glamorganshire—</i> | | |
| Rosser Vein, Dowlais | E. Riley . . . | 32·18 |
| Spotted Vein, „ | „ . . . | 53·60* |
| Welsh Little Vein, „ | „ . . . | 30·43 |
| Welsh Lumpy, „ | „ . . . | 34·72 |
| Gŵr Hyd Mine, „ | „ . . . | 30·33 |
| Black Band, „ | „ . . . | 37·80 |
| Sulphury Mine, Cwm Avon | A. Dick . . . | 31·63 |
| White Pins, Ystalyfera | „ . . . | 23·22 |
| Cheese Mine, „ | F. A. Abel . . . | 33·45 |
| Black Band Lower, Llynvi† | „ . . . | 36·08 |
| Black Band Lower, „ | „ . . . | 36·80 |
| Black Band Upper, „ | „ . . . | 31·36 |
| <i>Pembrokeshire—</i> | | |
| Catshole, Saundersfoot | W. Ratcliffe . . | 26·39 |
| Kilvelgy, „ | „ . . . | 29·15 |

Production of Ironstone.—There does not appear to exist any reliable information before the year 1857. Occasional returns for a few districts are met with, but they fail to represent anything like the yield of the ironstone measures of South Wales. For

* In calcined stone.

† Used extensively for making iron in the Llynvi and Maesteg districts.

1857, however, there appears a return amounting to 1,013,941 tons of argillaceous ironstone, and a further quantity of 24,300 tons of brown hematite, also raised in the South Wales area from the carboniferous limestone and Permian series, to which attention will be called further on. The production of 1857 appears in the annexed details:—

| COUNTY. | DISTRICT. | QUANTITY. Tons. | QUANTITY. Tons. |
|-------------------|-------------------------------------|--------------------|--------------------|
| <i>Monmouth,</i> | <i>Abersychan</i> | 43,098 | |
| " | <i>Blaenavon</i> | 80,111 | |
| " | <i>Blaina</i> | | |
| " | <i>Coalbrook Vale</i> } | 73,207 | |
| " | <i>Cwm Celyn</i> } | | |
| " | <i>Ebbw Vale</i> | 37,567 | |
| " | <i>Pontypool</i> | 41,200 | |
| " | <i>Sirhowey</i> | 65,886 | |
| " | <i>Tredegar</i> | 86,182 | |
| " | <i>Varteg and Golynos</i> | 56,133 | |
| " | <i>Varteg Hill</i> | 60 | |
| " | <i>Victoria</i> | 15,852 | |
| | Total of Monmouth | | 499,296 |
| <i>Brecknock,</i> | <i>Beaufort</i> | 74,600 | |
| " | <i>Clydach</i> | 34,000 | |
| | Total of Brecknock | | 108,600 |
| <i>Glamorgan,</i> | <i>Aberamman</i> | 32,812 | |
| " | <i>Dowlais</i> | 145,036 | |
| " | <i>Gadly's</i> | 17,468 | |
| " | <i>Llynvi</i> | 49,481 | |
| " | <i>Maesteg</i> | 65,000 | |
| " | <i>Penydarren</i> | 80,617 | |
| " | <i>Tondu</i> | 15,631 | |
| | Total of Glamorgan | | 406,045 |
| | Total of South Wales | | <u>1,013,941</u> |

Again, for the year 1858, the production was 752,231 tons, of which 24,635 tons were brown hematite, raised at Llantrissant, Mwyndy and Wenvoe. Regarding the value of these and other iron ores employed in the ironworks on the eastern edge of the coal basin in Monmouthshire at that time, the following were the prices of the several varieties delivered at Newport, per ton:—

| COUNTY. | IRON ORE. | s. | d. |
|-----------------------|--|----|----|
| <i>Devonshire,</i> | <i>Brixham</i> | 13 | 0 |
| " | <i>Prawle</i> | 13 | 0 |
| <i>Somersetshire,</i> | <i>Honeyhead</i> | 10 | 0 |
| " | <i>Ashton Vale</i> | 10 | 0 |
| <i>South Wales,</i> | <i>Argillaceous</i> | 11 | 0 |
| " | <i>Llantrissant (Brown Hematite)</i> | 15 | 0 |

The charge of conveyance from Newport to the ironworks varying from 2s. 3d. to 2s. 6d. per ton. It need scarcely be said that the ironstone obtained annually in South Wales is totally inadequate to the requirements of the blast furnaces; on the other hand, the abundance of fuel enables the ironmaster to increase his supplies by importing rich and valuable ores from the hematite districts of Cumberland, Lancashire, the Midland and South-Western districts of England, bearing a high rate of carriage, and he is further in a position to supply his wants by the favourable geographical situation of the district, which enables him to import ores from Spain and other foreign countries.

Since 1859 the production of clay ironstone in South Wales has been as follows:—There is every reason to believe, however, that these figures fall short of the actual quantities raised; this conclusion is arrived at by a comparison of the annual yield of the blast furnaces, for which reliable data exist in the quantities of the ores employed and their yield of metallic iron:—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1859 | 649,758 | 1870 | 560,005 |
| 1860 | 630,705 | 1871 | 969,714 |
| 1861 | 545,705 | 1872 | 1,247,594 |
| 1862 | 472,053 | 1873 | 943,926 |
| 1863 | 420,017 | 1874 | 661,616 |
| 1864 | 468,355 | 1875 | *495,840 |
| 1865 | 387,742 | 1876 | 476,285 |
| 1866 | 368,692 | 1877 | 367,316 |
| 1867 | 501,186 | 1878 | 318,399 |
| 1868 | 712,680 | 1879 | 299,000 |
| 1869 | 715,001 | 1880 | 278,361 |

The value of these ores in 1872 averaged 12s. per ton; while during the year 1878 the price did not exceed 10s. per ton. The production of ironstone in South Wales in the year 1880 amounted to 278,361 tons, of the value of £139,180, or 10s. per ton.

Iron Ore Deposits of the Carboniferous Limestone.—At Whitchurch, near Cardiff, in Glamorganshire, and at Penttyrch, at the mouth of the Taff Valley, deposits of brown hematite occur at the base of the carboniferous limestone, in nearly vertical

* In the above return till 1875 are included the hematite ores raised in Wales, after 1875 the quantities above include clay iron ores only.

fissures in the limestone, with an underlay of from 3 to 7 degrees south. The ore wrought at Pentyrch has been extensively employed in the works of the same name, in the manufacture of sheet iron and tin plates, and has long enjoyed the reputation of being amongst the best brands in the kingdom.

Again, in the lower bed of the Permian series, brown hematite ore exists. These deposits occur locally in hollows or basins; these basins at Mwyndy, near Llantrissant, assume wedge-like shapes at the outcrop, the ore occurring in hollows in the upturned edges of the underlying rocks. Similar ore is also wrought at the Bute Mine, near the same place. Another deposit exists west of Llantrissant, at Quay-Coch, two miles north of Porth Cawl, where it lies over the carboniferous limestone, having a thickness of five feet.

Of the hematite ore raised in Glamorganshire the following gives the production in each of the years named. Formerly hematite was wrought to a limited extent at Hendy and Wenvoe, and recently at Llwynsaer by the Mwyndy Iron Ore Company.

The ore raised at Llwynsaer in 1880 amounted to 12,315 tons, of the value of £6,773.

| Year. | Mwyndy. | Bute. | Garth. | Total. |
|-------|---------|--------|--------|---------|
| | Tons. | Tons. | Tons. | Tons. |
| 1858 | 12,500 | ... | ... | 12,500 |
| 1860 | 29,217 | ... | ... | 29,217 |
| 1862 | 27,260 | 16,633 | ... | 43,893 |
| 1864 | 50,401 | 13,168 | ... | 63,569 |
| 1866 | 41,387 | 26,000 | ... | 67,387 |
| 1868 | 60,660 | 22,875 | ... | 83,535 |
| 1870 | 66,191 | 22,530 | ... | 88,720 |
| 1871 | 58,723 | 24,601 | ... | 83,324 |
| 1872 | 49,661 | 23,105 | ... | 72,766 |
| 1873 | 52,816 | 339 | ... | 53,155 |
| 1874 | 68,787 | 36,558 | 15,545 | 120,890 |
| 1875 | 67,697 | 16,057 | 16,536 | 100,290 |
| 1876 | 61,618 | 8,525 | 13,421 | *83,970 |
| 1877 | 49,084 | 7,581 | 9,861 | †77,320 |
| 1878 | 30,451 | 8,375 | 7,828 | ‡56,639 |
| 1879 | 20,986 | 985 | 6,695 | §53,811 |
| 1880 | 43,095 | 191 | 9,966 | 65,567 |

* Including 405 tons raised at Rudry.

† Including 10,794 tons raised at Llwynsaer.

‡ Including 9,894 tons raised at Llwynsaer and Treacastle.

§ Including 20,986 raised at Treacastle.

|| Including 12,315 tons raised at Llwynsaer.

The value of these hematite ores for some years past shows little variation, the average price being from 12s. to 14s. per ton.

The mines raising hematite ore in South Wales, their situation, proprietors, and chief agents are as follows during the year 1880:—

| No. | Name of Mine. | Situation. | Name of Proprietor or Company. | Name of Manager or Agent. |
|-----|-----------------------------|------------------|--------------------------------|---------------------------|
| 1 | Bute Hematite . | Llantrissant . . | Dowlais Iron Co. | John Powell. |
| 2 | Llwynsauer . . | " | Mwyndy Iron Ore Co., Lim. . | William Vivian. |
| 3 | { Mwyndy and Trecastle } | " | " " " | David Evans. |
| 4 | Melyn Griffith . | Cardiff | T. W. Booker & Co., Lim. . | E. D. Howell. |
| 5 | Garth | " | | |

Analyses of these Iron Ores.—The ore raised at Mwyndy, near Llantrissant, is thus described by Mr. W. Ratcliffe: "Compact hematite; easily scratched by a file; lustre, earthy; colour, deep red yellow; streak, brown red; fracture, uneven, showing numerous cavities lined with crystals of quartz; the ore contains minute particles of quartz, visibly diffused through it. Some specimens selected from large solid masses of the ore are scarcely scratched by a file; colour, bright purple blue. Particles of quartz are diffused through these, and are only plainly visible by the aid of the microscope. The samples analysed were composed of a mixture of these varieties."

RESULTS TABULATED.

| | |
|-------------------------------|----------------------|
| Sesquioxide of iron | 70·572 |
| Oxide of manganese | 0·522 |
| Silica | 18·362 |
| Alumina | 1·572 |
| Lime | 3·562 |
| Magnesia | 1·311 |
| Potash | 0·317 |
| Sulphuric acid | 0·451 |
| Phosphoric acid | 0·132 |
| Carbonic acid | 1·716 |
| Water | 0·660 |
| Total | <u>99·177</u> |

The total amount of metallic iron contained in this ore is equivalent to 48·984 per cent.; it further appears that a trace of cobalt was detected in 300 grains of the ore.

The calcareous hematite of Whitchurch, also examined by

Mr. W. Ratcliffe, gives the following results. The ore is thus described:—"Compact; soft; lustre, greasy to dull; colour, dark red on outside; on the fracture, blackish red; streak, bright red, soils the fingers, and makes a red streak on paper; structure, oolitic and sometimes pisolitic."

RESULTS TABULATED.

| | |
|-------------------------------------|----------------|
| Sesquioxide of iron | 66·554 |
| Protoxide of iron | 1·131 |
| Oxide of manganese | 1·127 |
| Alumina | 1·753 |
| Lime | 8·547 |
| Magnesia | 1·116 |
| Silica | 0·312 |
| Potash | 0·190 |
| Soda | 0·068 |
| Carbonic acid | 5·733 |
| Sulphuric acid | 1·309 |
| Phosphoric acid | 1·017 |
| Organic matter | 0·376 |
| Water (total) | 2·118 |
| Ignited insoluble residue | 10·356 |
| Total | <u>101·707</u> |

IGNITED INSOLUBLE RESIDUE.

| | |
|--|---------------|
| Silica | 8·589 |
| Alumina (with a little iron) | 1·042 |
| Lime | 0·850 |
| Magnesia | 0·272 |
| Potash | 0·235 |
| Soda | 0·076 |
| Total | <u>11·064</u> |

The total amount of metallic iron contained in this ore is equivalent to 47·468 per cent. A note appended to the analysis states,* that "No metal precipitable by sulphuretted hydrogen from the hydrochloric acid solution of 300 grains of ore, was detected.

The Mwyndy Company previously referred to possesses an estate at Treacastle containing some valuable deposit of iron ore; the mines are situated near the Llantrissant station and on the Cowbridge line, three miles distant from Mwyndy. Of late these deposits have not been worked except in a limited manner. The following analyses of two samples of this hematite, by Mr.

* "Iron Ores of Great Britain," Part III., p. 217.

John Pattinson, of Newcastle-upon-Tyne, show the subjoined results:—

| Constituents. | Treacastle. No. 1. | Treacastle. No. 2. |
|------------------------------|-----------------------|-----------------------|
| Peroxide of iron | 87·43 | 74·71 |
| Protoxide of manganese . . . | 0·24 | 0·19 |
| Alumina | 0·24 | 1·90 |
| Lime | 0·28 | 5·56 |
| Magnesia | 0·27 | 0·94 |
| Oxide of copper | trace | trace |
| Carbonic acid | ... | 4·90 |
| Silica | 1·97 | 3·86 |
| Sulphur | 0·02 | 0·02 |
| Phosphoric acid | 0·01 | 0·01 |
| Combined water | 9·29 | 7·64 |
| Moisture | 0·21 | 0·24 |
| | 99·96 | 99·97 |

The high character of these ores appears in the fact that the first gives 61·20 and the second sample 52·30 of metallic iron.

Pig Iron Manufacture.—On the northern and eastern out-crop of the South Wales mineral basin, in the shires of Monmouth and Brecknock, are established some of the oldest and most extensive iron works in the kingdom. About the year 1755 it appears that a Mr. Anthony Bacon acquired an extensive mineral property in the neighbourhood of Merthyr, for a term of 99 years, at the moderate rental of £200 per annum, and it was upon this same property in later years that many of the present iron works of the above named districts were established.

Previously, in the year 1565, it is known that a Mr. Capel Hanbury erected a charcoal blast furnace at Pontypool, which place is regarded as one of the earliest seats of the iron trade; and there is reason to believe that the Romans worked iron ore in those hills then covered with wood, as they undoubtedly did in Dean Forest, ancient heaps of slag being occasionally struck upon. In consequence of the destruction of timber for fuel being carried to a serious extent in the reign of Elizabeth, Acts were passed prohibiting the erection of iron works except in districts specified; so that in the year 1740 the aggregate yield of charcoal pig iron amounted to but 17,350 tons, the yield of 59 furnaces distributed over the kingdom as follows:—

| County. | No. of Furnaces. | Charcoal Pig Iron. Tons. |
|--------------------------|---------------------|------------------------------------|
| <i>South Wales—</i> | | |
| Brecon | 2 | 600 |
| Caermarthenshire | 1 | 100 |
| Glamorganshire | 2 | 400 |
| Monmouthshire | 2 | 900 |
| <i>North Wales—</i> | | |
| Denbighshire | 2 | 550 |
| <i>England—</i> | | |
| Cheshire | 3 | 1,700 |
| Derbyshire | 4 | 800 |
| Gloucestershire | 6 | 2,850 |
| Hampshire | 1 | 200 |
| Herefordshire | 3 | 1,350 |
| Kent | 4 | 400 |
| Nottinghamshire | 1 | 200 |
| Shropshire | 6 | 2,100 |
| Staffordshire | 2 | 1,000 |
| Sussex | 10 | 1,400 |
| Warwickshire | 2 | 700 |
| Worcestershire | 2 | 700 |
| Yorkshire | 6 | 1,400 |
| Total | 59 | 17,350 |

Thus of the make of charcoal iron in the year 1740 South Wales with its seven furnaces produced 2,000 tons. Advancing to the year 1788* there appear to have been but 24 furnaces in England and Wales making charcoal pig iron amounting to 13,100 tons, and 53 furnaces making 48,200 tons of coke pig iron, the former giving an average of 545 tons per furnace, compared with 294 tons per furnace in the year 1740.

Of the production of 1788, seven furnaces were in South Wales, producing 4,300 tons of charcoal pig, and eight furnaces making 8,200 tons of coke pig iron, giving a total of 12,500 tons of pig iron, the make of fifteen furnaces in South Wales, amounting to nearly one-fourth of the total production of the kingdom at this period.

As this period marks a new era in the history of pig iron manufacture, and the more general use of coke as a reducing agent in the blast furnace, it will be a fitting place to record the quantities of charcoal, and coke pig iron produced in Great Britain, viz., for the year 1788, which were as follows :—

* "History of the Iron Trade," by H. Scrivener, 1854, p. 87.

CHARCOAL PIG IRON.

| | No. of Furnaces. | Make of each Furnace. | Total. |
|------------------------|---------------------|--------------------------|--------|
| | | Tons. | Tons. |
| <i>South Wales—</i> | | | |
| Caermarthenshire . . . | 1 | 400 | 400 |
| Glamorganshire . . . | 3 | 600 | 1,800 |
| Monmouthshire . . . | 3 | 700 | 2,100 |
| <i>England—</i> | | | |
| Cumberland . . . | 1 | 300 | 300 |
| Derbyshire . . . | 1 | 300 | 300 |
| Gloucestershire . . . | 4 | 650 | 2,600 |
| Lancashire . . . | 3 | 700 | 2,100 |
| Shropshire . . . | 3 | 600 | 1,800 |
| Sussex . . . | 2 | 150 | 300 |
| Westmoreland . . . | 1 | 400 | 400 |
| Yorkshire . . . | 1 | 600 | 600 |
| <i>North Wales—</i> | | | |
| Merionethshire . . . | 1 | 400 | 400 |
| Total . . . | 24 | | 13,100 |

In the same year the make of coke pig iron in England and Wales was as follows :—

COKE PIG IRON.

| | No. of Furnaces. | Make of each Furnace. | Total. |
|----------------------|---------------------|--------------------------|--------|
| | | Tons. | Tons. |
| <i>South Wales</i> | | | |
| Brecknockshire . . . | 2 | 800 | 1,600 |
| Glamorganshire . . . | 6 | 1,100 | 6,600 |
| <i>England—</i> | | | |
| Cheshire . . . | 1 | 600 | 600 |
| Cumberland . . . | 1 | 700 | 700 |
| Derbyshire . . . | 7 | 600 | 4,200 |
| Shropshire . . . | 21 | 1,100 | 23,100 |
| Staffordshire . . . | 6 | 750 | 4,500 |
| " . . . | 3 | 800 | 2,400 |
| Yorkshire . . . | 6 | 750 | 4,500 |
| Total . . . | 53 | | 48,200 |

Scotland produced in the year 1788 from two furnaces in Argyshire, situated at Goatfield and Bunawe, 1,400 tons of charcoal pig iron and 5,600 tons of coke pig iron, from four furnaces erected at the Carron Works in Stirlingshire, and two

furnaces erected at Wilsonstown or Cleugh, in Lanarkshire. Summarising the above returns for 1788 the result is as shown:—

| Districts. | | No. of Furnaces. | Pig Iron. |
|---------------------|-------------------|---------------------|----------------|
| South Wales | Charcoal furnace. | 7 | Tons. 4,300 |
| England | „ . . | 16 | 8,400 |
| North Wales | „ . . | 1 | 400 |
| Scotland | „ . . | 2 | 1,400 |
| | Total . . | 26 | 14,500 |
| South Wales | Coke Pig . . | 8 | 8,200 |
| England | „ . . | 45 | 40,000 |
| Scotland | „ . . | 6 | 5,600 |
| | Total . . | 59 | 53,800 |

Presenting a total for Great Britain of 85 furnaces and 68,800 tons of pig iron, the average yield of the English furnaces being 796 tons, compared with 875 tons, the average yield of the Scotch furnaces. The three charcoal furnaces in operation in Monmouthshire in 1788 were situated at Pontypool, Tintern Abbey, and Monmouth. Passing on to the date of the erection of coke furnaces it appears that the first furnace using coke was erected at the Sirhowey works, by the Messrs. Atkinson and Co., in 1788, and in the year 1796 produced 1,980 tons of coke pig iron. The Blaenavon works followed in the same year with three furnaces, and in the year 1796 made 4,311 tons of coke pig iron; while in the same year the works at Blaendare, near Pontypool, and the Ebbw Vale Works put their first furnaces in blast; the former in the year 1796 making 1,500 tons, and the latter 1,660 tons of coke pig iron. Other works succeeded with rapidity; those at Nantyglo were founded in 1795, Varteg in 1803, and the works at Tredegar in 1805. In Brecknockshire the Beaufort Works were laid down by the Messrs. Kendall and Evans, in the year 1780, the furnace producing in the year 1796 some 1,660 tons of coke pig iron.

Towards the close of the past century much anxiety was shown by the coal and iron masters of the kingdom at Mr. Pitt's projects to increase the revenue—the first in 1796, by a tax on coal at the pit's mouth, and the second in 1797, on pig iron of 20 shillings

per ton; considerable opposition was shown to both those measures. A committee of the House of Commons was appointed, presided over by William Manning, M.P., and the whole subject very fully considered, the result being the abandonment of both measures. The inquiry was not however barren in results, as it brought out some very important and interesting facts upon the condition of the iron works in Great Britain at this time. These were embodied in a statement prepared by Dr. H. G. McNab,* of Severn House, Shropshire, and addressed to the chairman. In this statement a complete list of all the furnaces in Great Britain appears, with the return given by the Excise of the quantity of pig iron made in the year 1796; the quantities supposed and calculated upon, by three gentlemen whose initials alone appear, and a third statement of the quantities really made. The works in operation at this period in Monmouthshire and Brecknockshire were those named in the following table:—

| Names of Furnaces. | No. of Furnaces. | Excise Return. | Supposed Quantities. | Exact Return. |
|------------------------|---------------------|-------------------|-------------------------|------------------|
| | | Tons. | Tons. | Tons. |
| <i>Monmouthshire</i> | | | | |
| Blaendare . . . | 1 | 1,404 | 1,404 | 1,500 |
| Blaenavon . . . | 3 | 5,460 | 5,460 | 4,318 |
| Ebbw Vale . . . | 1 | 1,560 | 1,560 | 397 |
| Sirhowey . . . | 1 | 1,820 | 1,820 | 1,930 |
| Total . . . | 6 | 10,244 | 10,244 | 8,145 |
| <i>Brecknockshire—</i> | | | | |
| Beaufort . . . | 1 | 1,560 | 1,560 | 1,660 |
| Clydach . . . | 1 | 1,820 | 1,820 | 1,825 |
| Hirwain . . . | 1 | 1,400 | 1,400 | 1,050 |
| Total . . . | 3 | 4,780 | 4,780 | 4,335 |

The three sources of information are given for comparison; the exact returns however give a total production in the two districts of 12,480 tons, the make of nine furnaces, showing an average make per furnace of 1,387 tons.

This return for the year 1796 possesses so much interest as containing the detailed list of iron works existing in the kingdom, and for purposes of comparison will be so frequently referred to in subsequent pages, that the annexed table has been prepared from

* McNab on the "Coal Trade," 1801.

the original of Dr. Macnab, intending to show the number of furnaces and the make of each district in the kingdom; these were as follows :—

| Districts. | No. of Furnaces. | Excise Return. | Supposed Quantities. | Exact Return. |
|--------------------------------|---------------------|-------------------|-------------------------|------------------|
| | | Tons. | Tons. | Tons. |
| Cumberland | 2 | 3,744 | 1,600 | 565 |
| Derbyshire | 12 | 10,200 | 10,200 | 9,656 |
| Gloucestershire | 2 | 380 | 380 | 380 |
| Herefordshire | 4 | 2,070 | 2,070 | 1,749 |
| Lancashire | 3 | 2,180 | 2,180 | 2,249 |
| Mid Wales | 1 | 200 | 200 | 150 |
| Shropshire | 23 | 68,129 | 43,360 | 32,969 |
| Staffordshire, North | 2 | 4,700 | 2,200 | 1,959 |
| " South | 14 | 15,820 | 15,256 | 13,210 |
| Sussex | 1 | 172 | 173 | 173 |
| South Wales | 24 | 38,508 | 39,808 | 34,101 |
| Wales, North | 5 | 6,230 | 1,560 | 1,144 |
| " West | 1 | 1,056 | 1,056 | 290 |
| Yorkshire, West Riding | 13 | 13,922 | 13,922 | 10,398 |
| Scotland | 15 | ... | 17,040 | 15,186 |
| " charcoal | 2 | ... | 1,600 | 900 |
| Total | 124 | 167,311 | 152,605 | 125,079 |

Towards the end of the year 1800 the total number of furnaces was increased by 40, of which 21 were in blast and 19 in course of erection in Great Britain, distributed as follows :—

| Districts. | In Blast. | Building. |
|--------------------------------|-----------|-----------|
| | Nos. | Nos. |
| Durham | 0 | 1 |
| Gloucestershire | 1 | 0 |
| Shropshire | 5 | 2 |
| Staffordshire, North | 2 | 1 |
| " South | 7 | 11 |
| South Wales | 5 | 4 |
| Scotland | 1 | 0 |
| Total | 21 | 19 |

Beginning with the present century, a reliable source of information is at hand; one return in 1806, prepared by an iron-master conversant with the iron industries of the kingdom, shows the production of the Brecknockshire furnaces as 7,998 tons, and those of Monmouthshire as 22,950 tons, giving a total of 30,948 tons for both counties. From the return referred to, the annexed statement has been prepared, showing the works and furnaces in operation and details of production :—

| Districts. | FURNACES. | | Pig Iron Made. |
|-------------------------|-----------|-----------|-------------------|
| | Built. | In Blast. | |
| <i>Brecknockshire—</i> | | | Tons. |
| Beaufort | 2 | 2 | 4,696 |
| Clydach | 2 | 1 | 2,802 |
| Hirwain | 1 | 1 | 500 |
| Total | 5 | 4 | 7,998 |
| <i>Monmouthshire—</i> | | | |
| Blaendare | 1 | 0 | ... |
| Blaenavon | 4 | 3 | 7,846 |
| Bishop's Wood | 1 | 1 | 653 |
| Ebbw Vale | 2 | 1 | 3,664 |
| Nantyglo | 2 | 0 | ... |
| Pontypool | 1 | 1 | 600 |
| Sirhowey | 2 | 2 | 3,700 |
| Tintern Abbey | 1 | 1 | 987 |
| Tredegar | 2 | 2 | 4,500 |
| Varteg | 1 | 1 | 1,000 |
| Total | 17 | 12 | 22,950 |

In the same year the total production of the 161 furnaces in Great Britain amounted to 248,851 tons, being an average make per furnace of 1,515 tons. Advancing to the year 1811 there appears to have been 24 furnaces in blast in these districts, giving an average yield per furnace of 2,000 tons, or a total production of 48,000 tons of pig iron. A paper in the *Edinburgh Philosophical Magazine** affords information of the production of Great Britain in the year 1827, when 284 furnaces were in operation, yielding 690,000 tons of pig iron. The general production appears to have been as follows:—

| Districts. | Furnaces. | Tons. |
|-------------------------|-----------|---------|
| Staffordshire | 95 | 216,000 |
| Shropshire | 31 | 78,000 |
| South Wales | 90 | 272,000 |
| North Wales | 12 | 24,000 |
| Yorkshire | 24 | 43,000 |
| Derbyshire | 14 | 20,500 |
| Scotland | 18 | 36,500 |
| Total | 284 | 690,000 |

* "The Iron Trade of Great Britain," 1828, p. 115.

It is here shown that the yield of the South Wales furnaces gave upwards of an average make of 3,000 tons, compared with 2,000 tons in 1811, and 1,515 tons in 1806.

The Government instituted an inquiry in the year 1831, which was intrusted to Mr. F. Finch, formerly member for Walsall. This inquiry embraced all the iron producing districts of the kingdom, for the years 1823 and 1830.

From this statement it is gathered, that the total yield of the Brecknockshire and Monmouthshire furnaces in the above named years, were 102,260 tons, and 156,277 tons; the number of furnaces in operation being respectively 35 and 68, in each of the same years.

| Districts. | 1823. | | 1830. | |
|------------------------|-----------|-----------|-----------|-----------|
| | Furnaces. | Pig Iron. | Furnaces. | Pig Iron. |
| | No. | Tons. | No. | Tons. |
| <i>Brecknockshire—</i> | | | | |
| Beaufort | 3 | 5,243 | 4 | 7,276 |
| Clydach | 2 | 5,200 | 9 | 10,190 |
| Hirwain | 2 | 4,160 | 4 | 9,360 |
| Yniscedwyn. . . . | 1 | 1,498 | 2 | 2,111 |
| Total | 8 | 16,101 | 19 | 28,937 |
| <i>Monmouthshire—</i> | | | | |
| Abersychan | ... | ... | 6 | 10,640 |
| Blaenavon | 5 | 16,882 | 5 | 13,843 |
| Blaina | ... | ... | 3 | 4,905 |
| Coalbrook Vale . . . | 1 | 2,704 | 2 | 2,780 |
| Ebbw Vale & Sirhowey | 6 | 20,425 | 6 | 26,020 |
| Pentwyn | ... | ... | 3 | 5,391 |
| Rhymney | ... | ... | 1 | 220 |
| Rhymney and Bute . | 3 | 5,500 | 6 | 7,608 |
| Tredegar | 5 | 16,385 | 5 | 18,514 |
| Varteg | 2 | 6,513 | 5 | 13,536 |
| Nantyglo | 5 | 17,750 | 7 | 23,883 |
| Total | 27 | 86,159 | 49 | 127,340 |

Comparing the totals there is shown an increase of 33 furnaces and 54,017 tons of pig iron, equivalent to 50 per cent. The result arrived at by Mr. Finch shows that in 1823 the 266 furnaces in operation in Great Britain produced 455,166 tons, compared with 372 furnaces and 748,417 tons in the year 1830.

It thus appears that between the years 1823 and 1830 the increase in production was twofold, while the average yield of

each furnace increased from 1,786 tons in 1823 to 1,823 tons in the year 1830. About this period some interesting returns are at hand showing the make of pig iron in some of the more important works in these districts, which compare favorably with earlier returns of the same works in previous years. These are as follows :—

MONMOUTHSHIRE.

| Year. | Blaenavon. | Tredegar. | Nantyglo. | Blaina. | Ebbw Vale. |
|-------|------------|-----------|-----------|---------|------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1829 | 9,135 | 13,379 | 17,436 | 5,137 | 17,082 |
| 1830 | 9,401 | 12,335 | 17,536 | 4,292 | 18,258 |
| 1831 | 9,714 | 13,339 | 17,955 | 2,894 | 19,077 |
| 1832 | 9,066 | 13,372 | 21,333 | 8,058 | 18,347 |
| 1833 | 8,709 | 12,340 | 21,023 | 5,062 | 19,905 |
| 1834 | 8,391 | 12,920 | 22,663 | 6,074 | 20,240 |
| 1835 | 9,036 | 13,917 | 24,997 | 8,581 | 24,994 |
| 1836 | 7,596 | 12,133 | 25,407 | 9,020 | 22,957 |
| 1837 | 7,512 | 12,661 | 23,972 | 6,380 | 20,035 |
| 1838 | 8,085 | 15,538 | 25,241 | 7,458 | 23,320 |

These quantities refer solely to the works named. The Beaufort and Clydach works of Brecknockshire in each of the same years produced pig iron in the following quantities :—

BRECKNOCKSHIRE.

| Year. | Beaufort. | Clydach. |
|-----------|-----------|----------|
| | Tons. | Tons. |
| 1829 | 7,102 | 7,431 |
| 1830 | 6,005 | 7,573 |
| 1831 | 5,153 | 7,031 |
| 1832 | 6,882 | 6,542 |
| 1833 | 7,522 | 7,384 |
| 1834 | 9,808 | 6,262 |
| 1835 | 12,979 | 7,562 |
| 1836 | 14,567 | 7,738 |
| 1837 | 11,162 | 7,087 |
| 1838 | 10,917 | 9,282 |
| Total . . | 92,097 | 73,892 |

In the period between 1830 and 1840 the iron industries of the county received a great impetus from the expansion of our railway system; all possible skill was brought to bear on the

improvement of the furnace, the quantity and quality of the iron. The old charcoal furnaces of small dimensions gave way to others of larger capacity, coke being employed; in height the charcoal furnaces varied from 12 to 18 feet, and even 28 feet where good water power existed, those of the coke furnaces being 40 and 50 feet, and even more in height, the width of the boshes varying from 10 to 15 feet. The production of the Monmouthshire and Brecknockshire furnaces till the year 1857 are included in the production of South Wales; after 1857, the number of furnaces and production of each district is separately distinguished. Before giving this summary the annexed statement, prepared from reliable sources, will show the total production of the several works in both Monmouthshire and Brecknockshire between the years 1829 and 1838 inclusive:—

| MONMOUTHSHIRE. | |
|--------------------------|--------------------|
| WORKS. | PIG IRON. Tons. |
| Blaenavon | 86,645 |
| Blaina | 62,956 |
| Coalbrook Vale | 29,889 |
| Bute | 72,040 |
| Ebbw Vale | 204,215 |
| Nantyglo | 217,563 |
| Pontypool | 48,835 |
| Tredegear | 131,934 |
| Varteg | 113,941 |

| BRECKNOCKSHIRE. | |
|--------------------|--------|
| Beaufort | 92,088 |
| Clydach | 73,892 |

Mr. Francis Foster, writing about the year 1830, in his observations on the South Wales Coal Basin,* remarks "that the quantity of iron annually made in South Wales is calculated at 270,000 tons, three-quarters of which, it would appear, was converted into bars, and one-quarter into pigs and castings. The average quantity of coal required included that used by engines, workmen, &c., being about five and a half tons for each ton of pig iron made."

From the year 1857 the following table exhibits at a glance the number of furnaces built, in blast, and make of iron in each district:—

* Pamphlet, "South Wales Coal Basin," June, 1830.

| MONMOUTHSHIRE. | | | | BRECKNOCKSHIRE. | | | |
|----------------|-----------|-----------|-----------|-----------------|-----------|----------------|--|
| Year. | FURNACES. | | Pig Iron. | FURNACES. | | Pig Iron Made. | |
| | Built. | In Blast. | | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Nos. | Nos. | Tons. | |
| 1857 | 68 | 54 | 399,649 | 16 | 14 | 70,779 | |
| 1859 | 59 | 42 | 327,300 | 19 | 14 | 59,600 | |
| 1861 | 74 | 54 | 338,439 | 17 | 10 | 43,300 | |
| 1863 | 67 | 46 | 349,387 | 17 | 8 | 35,700 | |
| 1865 | 68 | 45 | 367,656 | 17 | 10 | 49,750 | |
| 1867 | 71 | 50 | 418,235 | 15 | 5 | 29,443 | |
| 1869 | 59 | 44 | 472,450 | 17 | 6 | 39,201 | |
| 1870 | 59 | 45 | 472,450 | 17 | 6 | 32,000 | |
| 1871 | 62 | 47 | 470,982 | 17 | 4 | 30,086 | |
| 1872 | 63 | 49 | 465,603 | 17 | 6 | 28,504 | |
| 1873 | 62 | 42 | 360,583 | ... | ... | ... | |
| 1874 | 62 | 41 | 360,480 | ... | ... | ... | |
| 1875 | 62 | 37 | 262,253 | ... | ... | ... | |
| 1876 | 62 | 35 | 413,946 | ... | ... | ... | |
| 1877 | 61 | 30 | 368,480 | ... | ... | ... | |
| 1878 | 57 | 29 | 373,744 | ... | ... | ... | |
| 1879 | 57 | 27 | 337,684 | ... | ... | ... | |
| 1880 | 56 | 35 | 448,823 | ... | ... | ... | |

Brecknockshire has of late years disappeared from the published return as an iron producing district, and many of the furnaces have been dismantled.

Some interesting facts may be gathered from the above, showing the increased capacity and production of the furnaces during the past twenty years; thus in Monmouthshire in 1857 the average yield per furnace did not exceed 7,400 tons per annum, while in the year 1878 an average is shown of nearly 13,000 tons per furnace.

The success of the Blaenavon Works in the early part of the present century gave a great impetus to the iron trade in the Monmouthshire Hills, and a range of works sprung up to the westward, almost in a line near the heads of valleys that stretch towards Merthyr. Before giving the annexed statement showing the number of furnaces built, in blast, the respective firms, and the producing power of the works in the year 1880, the following dates, showing the establishment of some of the Monmouthshire works, will indicate the growth of the iron trade. The Beaufort, Ebbw Vale, Clydach, and Varteg works were in operation in 1803, Tredegar in 1805, Blaina and Coalbrook Vale before 1823, Abersychan in 1827, and Victoria in 1838.

MONMOUTHSHIRE.

| No. | Name of Works. | Owners. | FURNACES. | |
|--------------------------|----------------|--|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Abersychan . | Ebbw Vale Steel, Iron, and Coal Co., Limited . . . | 6 | 4 |
| 2 | Pontypool . . | | 4 | 2 |
| 3 | Sirhowey . . | | 4 | 4 |
| 4 | Ebbw Vale . . | | 4 | 4 |
| 5 | Victoria . . | | 2 | 2 |
| 6 | Blaenavon . . | Blaenavon Iron and Steel Co., Limited . . . | 9 | 5 |
| 7 | Cwmbrân . . | | 2 | 2 |
| 8 | Nantyglo . . | Nantyglo and Blaina Iron Works Co., Limited . . | 3 | 0 |
| 9 | Blaina . . . | | 3 | 0 |
| 10 | Coalbrook Vale | | 1 | 0 |
| 11 | Rhymney . . | Rhymney Iron Co., Limited. | 9 | 6 |
| 12 | Tredegar . . | Tredegar Iron Co., Limited . | 9 | 6 |
| Total of Monmouthshire . | | | 56 | 35 |

Glamorganshire.—In considering the production of pig iron manufacture in Glamorganshire, it will be convenient to consider the early history and progress of those works in which the reduction of the ores of iron is effected by coal of a bituminous character, and subsequently of those districts in which anthracite is exclusively employed.

As early as the 15th century evidence exists of the ores of iron being smelted in Glamorganshire, the furnaces being erected on the mountain tops, exposed to the wind, charcoal being alone used ; at a later period the furnaces were erected on sites in the valleys where water power could be advantageously employed. The great consumption of charcoal necessary for iron smelting led to great scarcity of this necessary material ; so much so that in the year 1740 the manufacture of iron was nearly extinct in South Wales, there being in that year but seven charcoal furnaces in operation, producing 2,000 tons of pig iron ; of these two were in Glamorganshire and one in Caermarthenshire, making 500 tons, the others in Monmouthshire and Brecknockshire, four in number, making 1,500 tons. The total make of the 59 furnaces at that period amounting to 17,850 tons.

The Dowlais Iron Works, situated near Merthyr, were established by Messrs. Lewis and Guest about the year 1757 ; about 1776 Mr. A. Bacon erected a smelting furnace at Cyfarthfa, and

a forge for the manufacture of bar iron. In 1784 the Penydarren works were laid out by Messrs. J. Homfray and Co., and were a source of great profit. A few years later Mr. Homfray was the projector of a canal to Cardiff, which however was constructed under the direction of Mr. Richard Crawshay, who, on the demise of Mr. A. Bacon, toward the end of the century, became sole proprietor of the Cyfarthfa works, which he rapidly extended; other works succeeded, and in 1790 the Plymouth works were established.

The production of charcoal iron in 1788 from three furnaces in Glamorganshire and five in Caermarthenshire amounted to 2,200 tons, the make of coke pig iron in the same year in Glamorganshire being 6,600 tons, the yield of six furnaces.

Advancing to the year 1796, when Dr. Macnab's return appeared, the works showing the number of furnaces and make of pig iron in Glamorganshire were as follows :—

GLAMORGANSHIRE.

| Works. | No. of Furnaces. | Excise Returns. | Supposed Quantities. | Exact Returns. |
|---------------------|---------------------|--------------------|-------------------------|-------------------|
| | | Tons. | Tons. | Tons. |
| Caerphilly | 1 | 600 | 600 | 695 |
| Cyfarthfa | 3 | 6,000 | 6,000 | 7,204 |
| Dowlais | 3 | 4,100 | 5,400 | 2,800 |
| Ennisgedyr | 1 | 1,352 | 1,352 | 800 |
| Llanelli | 1 | 1,664 | 1,664 | 1,560 |
| Neath Abbey | 2 | 3,120 | 3,120 | 1,759 |
| Penydarren | 2 | 4,000 | 4,000 | 4,100 |
| Plymouth | 1 | 2,000 | 2,000 | 2,200 |
| Melincourt | 1 | 648 | 648 | 503 |
| Total | 15 | 23,484 | 24,784 | 21,621 |

The total yield of the 124 furnaces in blast in Great Britain the same year being 125,079 tons, giving an average make of 1,008 tons per furnace, compared with 796 tons per furnace in the year 1788.

In the interval before the next returns appear in 1806 the iron works of the Aberdare Company were established, adding to the works already existing. From the returns for that year the following abstract has been prepared, showing the number of blast furnaces built, in operation, and the make of pig iron in Glamorganshire, when of the 25 furnaces built, 21 were in blast, and produced 40,009 tons of pig iron, giving an average make of 1,905 tons per furnace :—

| Works. | FURNACES. | | Pig Iron Made. |
|-----------------------|-----------|-----------|----------------|
| | Built. | In Blast. | |
| | No. | No. | Tons. |
| Aberdare | 2 | 2 | 3,586 |
| Abernant | 2 | 1 | 4,376 |
| Caerphilly | 1 | 1 | 1,000 |
| Cyfarthfa | 4 | 4 | 9,000 |
| Dowlais | 3 | 3 | 6,000 |
| Ennisgedyr | 1 | 1 | 1,000 |
| Llanelly | 2 | 2 | 2,267 |
| Melincourt | 1 | 1 | 1,000 |
| Neath Abbey | 2 | 0 | ... |
| Penydarren | 3 | 3 | 6,780 |
| Plymouth | 3 | 3 | 5,000 |
| Penrton | 1 | 0 | ... |
| Total | 25 | 21 | 40,009 |

It is a notable fact that at this period the only other districts in the kingdom exceeding the production of Glamorganshire were those of Staffordshire with 32 furnaces, yielding 50,002 tons, and Shropshire with 30 furnaces yielding 54,996 tons.

Mr. David Mushet, who made a special inquiry bearing on the production of pig iron in Great Britain, writes :—" In a survey I made of the iron works in 1820, my computation of the annual quantity of pig iron manufactured " was as follows, of which South Wales produced 150,000 tons :—

| DISTRICTS. | QUANTITIES. |
|--|----------------|
| | Tons. |
| South Wales, &c. | 150,000 |
| Staffordshire and Shropshire | 180,000 |
| Yorkshire and Derbyshire | 50,000 |
| Scotland and other places | 20,000 |
| Total | <u>400,000</u> |

Mr. Frederick Finch, in his return prepared for the Government, of the make of pig iron for the years 1823 and 1830, gives the total production of the furnaces of South Wales in each of those years as follows :—

| Year. | Furnaces. | Pig Iron. |
|-------|-----------|-----------|
| | Nos. | Tons. |
| 1823 | 72 | 182,325 |
| 1830 | 113 | 277,643 |

These figures show an increase in seven years of 41 furnaces and 95,318 tons, equivalent to 28 per cent. The average yield per furnace in 1823 was 2,532 tons, compared with 2,333 tons in 1830.

The Glamorganshire works produced pig iron in the following quantities in each of the same years according to Mr. Finch's statement:—

| Name of Works. | 1823. | | 1830. | |
|-----------------------|------------------|-----------|------------------|-----------|
| | No. of Furnaces. | Pig Iron. | No. of Furnaces. | Pig Iron. |
| | | Tons. | | Tons. |
| Aberdare | 3 | 2,838 | 3 | 6,285 |
| Abernant | 3 | 2,838 | 3 | 6,285 |
| Cyfarthfa | 8 | 24,200 | 9 | 29,000 |
| Dowlais | 8 | 22,287 | 12 | 32,611 |
| Gadly's | ... | ... | 1 | ... |
| Maesteg | ... | ... | 1 | 2,430 |
| Pentyrch | 1 | 1,235 | 1 | 2,412 |
| Plymouth | 3 | 6,387 | 5 | 18,582 |
| Penydarren | 5 | 15,547 | 5 | 17,015 |
| Cwm Avon | 1 | 1,560 | 1 | 1,950 |
| Neath Abbey | ... | ... | 2 | 2,374 |
| Race | 3 | 3,173 | 3 | 2,421 |
| Total | 35 | 80,065 | 46 | 121,365 |

Comparing the aggregate returns an increase is shown of 11 furnaces, and 41,300 tons, equivalent to 50 per cent.

About the year 1839 an interesting pamphlet appeared "On the State and Prospects of the Iron Trade in Scotland and South Wales."* The writer, in referring to the iron works of South Wales, gives some interesting facts and figures, showing the extent and capacity for production of pig iron of the works in Glamorganshire from which the following details are drawn.

The Aberdare Company's works in 1839 consisted of six furnaces in blast, two blown with hot air, and four with cold air, and producing from 350 to 400 tons of cast iron per week.

The Cyfarthfa Iron Works, belonging to Messrs. Crawshay and Sons, and the Hirwain Works of the same firm, situated about six miles from Merthyr, possess 14 blast furnaces, all blown with cold air, the 12 in operation producing weekly from 850 to 900 tons, the greater part of which is converted into malleable iron, of which they produce from 600 to 650 tons per week.

* By John Johnson, Esq., Iron Merchant, of Liverpool.

The Dowlais Works of Sir John Guest, Lewis and Co., had at this period 15 furnaces in full operation, and 4 others in course of erection; those in blast averaging 90 tons per week, giving a total weekly production of 1,350 tons.

The Plymouth Iron Works of Messrs. Richard and Anthony Hill consisted of 7 furnaces, all blown with cold air and making 700 tons of iron per week, 600 tons being converted into bar.

The Penydarren Iron Company have seven furnaces, six of which were in blast, making an average of from 400 to 500 tons of cast iron weekly, nearly the whole being converted into malleable iron.

The Pentyrch Iron Works of T. W. Booker, Esq., near Cardiff, have two blast furnaces blown with cold air, and yielding an average of 150 tons weekly of pig iron.

The returns from 1829 to 1839 of pig iron production, will show the magnitude of the iron works of Glamorganshire at this period; they are as follows:—

| Year. | Aberdare. | Cyfarthfa. | Dowlais. | Plymouth. | Penydarren. |
|-------|-----------|------------|----------|-----------|-------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1829 | 8,644 | 24,768 | 23,352 | 13,534 | 10,085 |
| 1830 | 6,765 | 19,892 | 27,647 | 12,177 | 11,744 |
| 1831 | 6,903 | 15,465 | 22,075 | 10,198 | 11,819 |
| 1832 | 5,997 | 22,668 | 29,395 | 9,200 | 10,582 |
| 1833 | 6,964 | 37,380 | 35,072 | 12,093 | 12,150 |
| 1834 | 8,497 | 34,952 | 33,477 | 12,073 | 12,752 |
| 1835 | 9,261 | 35,090 | 39,145 | 12,631 | 12,834 |
| 1836 | 9,981 | 34,654 | 39,286 | 13,573 | 12,537 |
| 1837 | 9,830 | 33,580 | 38,914 | 15,353 | 12,834 |
| 1838 | 12,247 | 36,986 | 39,361 | 16,143 | 12,707 |
| 1839 | 11,307 | 37,009 | 40,495 | 15,762 | 15,540 |
| Total | 96,396 | 332,444 | 368,219 | 142,737 | 135,584 |

Much light is thrown upon the progress of the South Wales iron industries in the following returns:—

| Year. | FURNACES. | | Pig Iron Made. |
|-------|-----------|-----------|----------------|
| | Built. | In Blast. | |
| | Nos. | Nos. | Tons. |
| 1839 | 101 | 99 | 388,100 |
| 1840 | 163 | 132 | 505,000 |
| 1848 | 196 | 151 | 706,680 |
| 1852 | 162 | 135 | 635,000 |

Resuming with the year 1854, it appears that there were 154 furnaces built in South Wales, including Monmouthshire; of these 100 were in blast, making 750,000 tons of pig iron; the total production of the furnaces of Great Britain in the same year, when 555 were in blast, being 3,069,838 tons.

In the year 1857 and since, the production of the Glamorgan-shire furnaces is separately distinguished, and appears in the following table, with the average make per furnace:—

GLAMORGANSHIRE.

| Year. | FURNACES. | | Pig Iron Made. | Average Make per Furnace. |
|-------|-----------|-----------|----------------|---------------------------|
| | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Tons. |
| 1857 | 87 | 76 | 436,859 | 5,748 |
| 1858 | 89 | 78 | 451,043 | 5,795 |
| 1859 | 89 | 73 | 539,470 | 7,390 |
| 1860 | 89 | 64 | 517,525 | 8,087 |
| 1861 | 82 | 59 | 453,821 | 7,692 |
| 1862 | 82 | 61 | 441,869 | 7,244 |
| 1863 | 82 | 60 | 439,722 | 7,349 |
| 1864 | 82 | 64 | 461,822 | 7,216 |
| 1865 | 81 | 64 | 408,416 | 6,384 |
| 1866 | 83 | 63 | 455,000 | 7,222 |
| 1867 | 76 | 49 | 403,050 | 6,226 |
| 1868 | 75 | 48 | 399,291 | 8,318 |
| 1869 | 79 | 53 | 348,475 | 6,575 |
| 1870 | 75 | 74 | 478,243 | 6,382 |
| 1871 | 72 | 53 | 510,087 | 9,064 |
| 1872 | 71 | 51 | 462,041 | 9,060 |
| 1873 | 78 | 51 | 424,384 | 8,321 |
| 1874 | 78 | 40 | 330,484 | 8,257 |
| 1875 | 78 | 35 | 249,667 | 7,133 |
| 1876 | 59 | 28 | 321,754 | 11,491 |
| 1877 | 76 | 26 | 342,478 | 13,172 |
| 1878 | 75 | 24 | *367,392 | 15,308 |
| 1879 | 75 | 23 | *332,174 | 14,442 |
| 1880 | 74 | 30 | *440,915 | 14,697 |

The falling off in the average yield per furnace in 1880, being due to the additional furnaces being in operation for a part of the year only.

The works, owners, and number of furnaces built and in operation in the year 1880 were as follows:—

* This quantity includes the production of anthracite pig iron.

GLAMORGANSHIRE.

| No. | Name of Works. | Owners. | FURNACES. | |
|-----------------------------------|---|--|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Brynamman | Amman Iron Co. | Nos. 3 | Nos. 1½ |
| 2 | Llwydcoed | The Aberdare and Plymouth Co., Limited | 5 | 0 |
| 3 | Abernant and Taffvale | | 2 | 2 |
| 4 | Briton Ferry | Townshend, Wood & Co. | 2 | 2 |
| 5 | Cwm Avon, Port Talbot | Governor and Co. of Copper Miners in England | 2 | 2 |
| 6 | Cyfarthfa, Merthyr* | Crawshaw Brothers | 10 | 6 |
| 7 | Ynisfach | | 17 | 13 |
| 8 | Dowlais† | Dowlais Iron Co. | 6 | 1½ |
| 9 | Llynvi, Maesteg | Llynvi, Tondy, and Ogmore Coal and Iron Co., Limited | 4 | 0 |
| 10 | Gadlys, Aberdare | Waynes Merthyr Steam Coal and Iron Works, Limited | 3 | 1 |
| 11 | Melin Griffith and Penttyrch | Thos W. Booker & Co., Limited | 10 | 0 |
| 12 | Plymouth, Merthyr | The Aberdare and Plymouth Co., Limited | 7 | 0 |
| 13 | Penydarren | Forest Iron and Steel Co., Lim. | 3 | 2 |
| 14 | { Forest Iron and Steel, Pontypridd | | 2 | 1 |
| 15 | Tondy, Bridgend | Llynvi, Tondy, and Ogmore Coal and Iron Co., Limited | 74 | 30 |
| Total of Glamorganshire | | | | |

The following account of the Cyfarthfa Iron Works, from "Wilkin's History of Merthyr," written a quarter of a century since, will possess much interest, inasmuch as the works have been recently restarted, after an interval of five years' inactivity:—"Cyfarthfa Works now employ 4,000 to 5,000 men, who at a rough average, may be said to support 20,000 souls. There are eleven furnaces, seven mine pits, eight coal pits, and the yield of coal is 1,000 tons per foot thick per acre. The steam and water power used is equal to more than 4,000 horses, and the works in full force can produce 1,300 tons of pig iron, 1,000 to 1,100 tons of finished bars and railway iron weekly. Such is the result of a minute investigation of these magnificent works, so admired for their order and completeness. Seen by night by the traveller entering Merthyr from the Breconshire valley the picture is grand in the extreme. The border of the scene cast into deeper darkness by the brilliancy of the glare in turn adds to the fiery glow by its gloom. Forked tongues of flame leap up defiantly,

* Operations resumed in December, 1879, the works having been standing for several years. In the beginning of 1881 the manufacture of Bessemer pig iron was commenced.

† One furnace building.

and the very smoke is forced upwards, as it were, tinged with a ruddy glow. Here and there the molten iron sends forth an intense heat; myriads of fiery stars rush into the open air, and the clang and roar, the whirl of monster wheels, and shrill escape of steam, combine to form one of the grandest pictures of the terrible it is possible to conceive. Entering the works the force of the picture is enhanced. Standing by the rolls on each side are hardy, muscular men, wiry and active, whose duty seems to consist in pushing long red hot iron rails now through one roller and then through another, until they become of the required form and size. The dexterity with which the rails are handled is most startling. One moment's hesitation and nervousness would be followed by an accident, but there is no hesitation or nervousness there. Ribbon in a Coventry factory, calico on a Manchester loom, cloth in a Gloucestershire mill, wind not through with more care, nor are they handled with greater freedom and *sang froid*, though the rail is 600 pounds weight and of an intense white heat; watching this process for a minute, we see one of the men suddenly seize hold of the 600 pound rail with a pincers, pull it vigorously towards him and then, by the aid of a roller, run away with it as though it were a plaything, to a place where a saw, worked by machinery, cuts it to the required measurement, scattering with a hideous noise a thousand fiery sparks around. Then two men rush to each end and fashion them off smoothly, and the tortured iron is drawn out to cool. Every moment this process is carried on. There is no hesitation. Every man takes up his task like an automaton, little speaking is heard, but the toil and wear of the human machinery in this hard labour must be most excessive."

Anthracite Pig Iron.—The reduction of the ores of iron, by the agency of anthracite in the blast furnace, is of comparatively recent date, and the industry in Great Britain is confined exclusively to the western district of the South Wales Coal Field.

The successful application of anthracite as a reducing agent dates from the year 1836, and its use is intimately associated with the names of Mr. James Palmer Budd, of the Ystalyfera Iron Works, and of Mr. George Crane, of the Yniscedwyn Iron Works. The anthracite furnaces of South Wales are of small volume and height compared with the furnaces of other districts; their average height may be taken as from 36 to

40 feet; of late years, however, there is a tendency to increase not only the height but the capacity of those furnaces in which anthracite is employed. Anthracite in high furnaces is found attended with considerable difficulties, mainly due to its decrepitation tending to impede the smelting operation; this difficulty is overcome by increasing the density of the blast; the pressure employed varies from 4 to 6 lbs. to the square inch, while the heated air of the blast ranges from 320° to 500° C. Mr. Crane, in his early operations at Yniscedwyn in 1837, produced by the aid of anthracite in a furnace of the above named works 36 tons per week. In the following year it appears the industry was carried to the far west by a Mr. David Thomas from South Wales, who erected a furnace in the United States of America, at Maunch Chunk, in the Lehigh Valley, State of Pennsylvania.

Resuming with the anthracite districts of South Wales, the production in 1839, the first on record, it appears that of the 26 furnaces built, 23 were more or less actively employed, making of anthracite pig iron 65,780 tons, giving an average make per furnace of 2,860 tons, while in the same year the powers of production were being increased by the erection of eleven new furnaces. The make of pig iron in Great Britain in 1839 is shown in the annexed table:—

| Districts. | FURNACES. | | Pig Iron Made. |
|-------------------------------------|-----------|-----------|----------------|
| | Built. | In Blast. | |
| | | | Tons. |
| Derbyshire | 16 | 14 | 34,372 |
| Durham and Northumberland | 5 | 5 | 13,000 |
| Gloucestershire | 8 | 5 | 18,200 |
| Lancashire (charcoal) | 2 | 2 | 800 |
| Shropshire | 34 | 29 | 80,940 |
| Staffordshire, North | 10 | 3 | 18,200 |
| Staffordshire, South | 226 | 120 | 346,213 |
| Wales, North | 20 | 13 | 33,800 |
| Wales, South | 101 | 99 | 388,100 |
| Wales (Anthracite) | 26 | 23 | 65,780 |
| Yorkshire | 29 | 24 | 52,416 |
| Scotland (coke iron) | 60 | 54 | 196,560 |
| Scotland (charcoal) | 2 | 2 | 400 |
| Total | 539 | 393 | 1,248,781 |

Advancing to the year 1848, there appears to have been eight

works engaged in this manufacture, with 31 furnaces built, 14 of which were in blast, producing, as has been ascertained from reliable sources, between 60,000 and 65,000 tons of pig iron. The average make per furnace at this period may be taken as about 4,000 tons per annum. In the subjoined list appears a complete account of the works in South Wales in 1848, in which anthracite was employed as a reducing agent, together with the number of furnaces built, in blast, and the owners.

| Name of Works. | Owners. | FURNACES. | |
|--------------------------|-------------------------|-----------|-----------|
| | | Built. | In Blast. |
| <i>Brecknockshire—</i> | | | |
| Ynisedwyn. . . | Ynisedwyn Iron Co. . | 7 | 3 |
| <i>Caermarthenshire—</i> | | | |
| Gwendraeth . . . | T. Watney & Co. . . | 3 | 2 |
| Trimsaren . . . | E. H. Thomas . . . | 2 | 0 |
| Bryn Amman . . . | L. Llewellyn & Co. . . | 2 | 2 |
| <i>Glamorganshire—</i> | | | |
| Banwen . . . | Joint Stock Co. . . | 2 | 0 |
| Onllwyn . . . | John Williams . . . | 2 | 2 |
| Venalt . . . | Aberdare Iron Co. . . | 2 | 0 |
| Ystalyfera . . . | Ystalyfera Iron Co. . . | 11 | 5 |
| Total . . . | . . . | 31 | 14 |

For a few years the production was well maintained, until 1857, since which it has gradually diminished, so much so that in the year 1880 the only furnaces producing anthracite pig iron were those of Ystalyfera, with eleven still standing as in 1848, of which four only were in blast, the estimated production not exceeding 14,000 or 15,000 tons of pig iron.

It has been observed that some varieties of anthracite decrepitate in a surprising degree when heated. Dr. Percy refers to specimens which he received from Neath, which, on the application of sudden heat, were reduced to absolute dust; and it is further remarked that the great difficulty experienced in the use of anthracite arises from the running together of the slag and the decrepitated particles of anthracite into an infusible mass, and gobbing up the furnace.

Following the production of anthracite pig iron in South Wales, the annexed table shows the number of furnaces built, and in blast, in each year since 1855, with the make of pig iron, and side by side the average yield per furnace.

ANTHRACITE PIG IRON.

| Year. | FURNACES. | | South Wales. | Average make per Furnace. |
|-------|-----------|-----------|--------------|---------------------------|
| | Built. | In Blast. | Pig Iron. | |
| | | | Tons. | Tons. |
| 1854 | 34 | 21 | ... | ... |
| 1855 | 34 | 19 | 52,755 | 2,776 |
| 1856 | 36 | 21 | 62,400 | 2,971 |
| 1857 | 36 | 20 | 63,440 | 3,172 |
| 1858 | 36 | 16 | 50,774 | 3,173 |
| 1859 | 36 | 18 | 58,920 | 2,162 |
| 1860 | 35 | 16 | 52,260 | 3,266 |
| 1861 | 31 | 14 | 50,740 | 3,643 |
| 1862 | 32 | 9 | 30,375 | 3,374 |
| 1863 | 31 | 9 | 22,944 | 2,549 |
| 1864 | 29 | 9 | 26,595 | 2,955 |
| 1865 | 29 | 9 | 29,213 | 3,246 |
| 1866 | 24 | 11 | 34,516 | 3,138 |
| 1867 | 25 | 11 | 35,506 | 3,228 |
| 1868 | 23 | 11 | 38,143 | 3,468 |
| 1869 | 23 | 9 | 27,909 | 3,101 |
| 1870 | 23 | 9 | 28,500 | 3,166 |
| 1871 | 19 | 8 | 34,761 | 4,345 |
| 1872 | 13 | 8 | 25,678 | 3,209 |
| 1873 | 13 | 8 | 32,822 | 4,103 |
| 1874 | 13 | 7 | 23,760 | 3,394 |
| 1875 | 13 | 7 | 29,889 | 4,270 |
| 1876 | 13 | 6 | 20,421 | 3,403 |
| 1877 | 13 | 4 | * | ... |
| 1878 | 11 | 4 | * | ... |
| 1879 | 11 | 4 | * | ... |
| 1880 | 11 | 4 | * | ... |

As previously remarked, the height and capacity of the anthracite furnaces have increased in late years; this is best shown in the average yield per furnace, taking the year 1855, when 19 furnaces produced 52,755 tons, the average yield was 2,776 tons, compared with 4,270 tons per furnace in 1875, when the make of 7 furnaces was 29,889 tons. The only works since 1876 engaged in South Wales in the production of anthracite pig iron, are those of the Ystalyfera Iron Company, the Yniscedwyn Company having discontinued the manufacture in the above named year.

Having generally traced the production of pig iron in the South Wales area, distinguishing that made in the bituminous and anthracite districts, as well as in each county, in the coal-fields in which the iron industries are located, it only remains

* Estimated production between 14,000 and 15,000 tons.

to summarise the returns of each district and arrive at the total yield of the furnaces in South Wales. To this table is appended, the total number of furnaces, built and in blast, in each of the same years; the result being as follows:—

| Year. | BITUMINOUS DISTRICT. | | | ANTHRACITE DISTRICT. | TOTAL, SOUTH WALES. | | |
|-------|----------------------|-----------------|-----------------|-----------------------|---------------------|-----------|-----------|
| | Monmouthshire. | Brecknockshire. | Glamorganshire. | Glamorgan, Brecknock. | FURNACES. | | Pig Iron. |
| | | | | | Built. | In Blast. | |
| | Tons. | Tons. | Tons. | Tons. | No. | No. | Tons. |
| 1854 | ... | ... | ... | ... | ... | 121 | 750,000 |
| 1855 | * | * | 787,315 | 52,755 | ... | 148 | 840,070 |
| 1856 | * | * | 814,750 | 62,400 | 199 | 162 | 877,150 |
| 1857 | 399,649 | 70,779 | 436,859 | 63,440 | 207 | 164 | 970,727 |
| 1858 | 315,124 | 69,537 | 451,043 | 50,774 | 199 | 147 | 886,478 |
| 1859 | 327,300 | 59,600 | 539,470 | 58,920 | 213 | 147 | 985,290 |
| 1860 | 349,670 | 49,570 | 517,525 | 52,260 | 214 | 139 | 969,025 |
| 1861 | 338,439 | 43,300 | 453,821 | 50,740 | 200 | 137 | 886,300 |
| 1862 | 382,065 | 39,000 | 441,869 | 30,375 | 197 | 125 | 893,309 |
| 1863 | 349,387 | 35,700 | 439,722 | 22,944 | 197 | 123 | 847,753 |
| 1864 | 415,174 | 34,260 | 461,822 | 26,595 | 197 | 133 | 937,621 |
| 1865 | 357,656 | 49,750 | 408,416 | 29,213 | 195 | 128 | 845,035 |
| 1866 | 410,000 | 27,750 | 455,000 | 34,516 | 193 | 132 | 927,454 |
| 1867 | 418,235 | 29,443 | 403,050 | 35,506 | 185 | 115 | 886,234 |
| 1868 | 427,821 | 29,000 | 399,291 | 38,143 | 184 | 108 | 894,255 |
| 1869 | 392,387 | 32,201 | 348,475 | 27,909 | 178 | 112 | 800,972 |
| 1870 | 440,450 | 32,000 | 478,243 | 28,500 | 174 | 114 | 979,193 |
| 1871 | 470,982 | 30,086 | 510,087 | 34,761 | 167 | 112 | 1,045,916 |
| 1872 | 481,342 | 28,504 | 465,603 | 25,678 | 154 | 114 | 1,002,643 |
| 1873 | 360,583 | nil | 424,384 | 32,822 | 148 | 101 | 817,789 |
| 1874 | 360,480 | nil | 330,484 | 23,760 | 139 | 88 | 714,724 |
| 1875 | 362,253 | nil | 249,667 | 29,889 | 153 | 79 | 541,819 |
| 1876 | 413,946 | nil | 321,754 | 20,421 | 134 | 69 | 756,121 |
| 1877 | 368,480 | nil | +342,478 | ... | 150 | 60 | 710,958 |
| 1878 | 373,744 | nil | +367,392 | ... | 145 | 57 | 741,136 |
| 1879 | 337,684 | nil | +332,174 | ... | 145 | 54 | 669,858 |
| 1880 | 448,823 | nil | +440,915 | ... | 141 | 69 | 889,738 |

The returns for the years 1871 and 1872 show a great increase, due, as it may be remembered, to the prosperity reigning in those years; the causes of decline would in themselves present an interesting chapter; however, happily a new state of things now prevails, and a return of prosperity to the iron and other industries of the kingdom is, it is to be hoped, now set in.

Monmouthshire Mills and Forges, and Bessemer Steel Works.

—These important works have existed from an early period in the

* Production included in the Glamorganshire returns in 1855 and 1856.

† Production of anthracite pig iron included in this quantity.

Monmouthshire extension of the South Wales coal-field. The earliest forges in operation employed charcoal and were established in the neighbourhood of Pontypool as far back as the 16th century: at a later period numerous works were established on the banks of the Ebbw river, Tredegar Park, and Machen. In the early part of the present century there existed eleven such works in Monmouthshire in which charcoal was exclusively employed, of which the following is a list:*

| FORGES. | PROPRIETORS. |
|-------------------------|----------------------------|
| Abercarne | Benjamin Hall & Co. |
| Bassoleg | Harfords & Co. |
| Caerleon | T. Buller & Co. |
| Gellywasted | Harfords & Co. |
| Machen | " |
| Monmouth | Assignees of David Tanner. |
| Llanvillio | " |
| Newport | Sir Robert Salisbury & Co. |
| Pontypool | Capel Leigh & Co. |
| Tintern Abbey | Thomson & Co. |
| Trostre | Harvey & Co. |

Of these works those at Abercarne and Tintern Abbey possessed furnaces, and wire-works, in addition to the forges. Not again until the year 1860, when the first published list appeared in the "Mineral Statistics of the United Kingdom," is any reliable information available; in that year, however, there were 16 works, of which 13 were in Monmouthshire and 3 in Brecknockshire, with a total of 345 puddling furnaces, and 40 rolling mills. Since 1860 the powers of production of many of these works have been greatly increased, while a few have been standing and others dismantled. The works and their resources stood as follows in each of the years named:—

| Year. | No. of Works. | Puddling Furnaces. | Rolling Mills. |
|-------|---------------|--------------------|----------------|
| 1865 | 16 | 570 | 60 |
| 1870 | 12 | 577 | 49 |
| 1875 | 13 | 597 | 54 |
| 1880 | 13 | 209 | 41 |

The annexed list gives the several works in Monmouthshire and Brecknockshire, with the numbers of puddling furnaces and rolling mills in operation in the year 1880:—

* See "General View of the Agriculture of the County of Monmouth," by Charles Hassall, 1812.

| No. | Works. | Name of Firms. | Puddling Furnaces. | Rolling Mills. |
|---------------------------|--------------|--|-----------------------|-------------------|
| <i>Monmouthshire—</i> | | | | |
| 1 | Abersychan . | Ebbw Vale Iron Co. . . . | ... | ... |
| 2 | Victoria . . | " | ... | ... |
| 3 | Ebbw Vale . | " | 64 | 17 |
| 4 | Pontypool . | " | 20 | 4 |
| 5 | Blaina . . | { Nantyglo and Blaina Iron Works Co., Limited } | ... | ... |
| 6 | Nantyglo . | " | ... | ... |
| 7 | Blaenavon . | { Blaenavon Iron and Steel Co., Limited . . . } | ... | ... |
| 8 | Pontnewynydd | W. T. Henley | ... | ... |
| 9 | Rhymney . | Rhymney Iron Co., Limited | 18 | 7 |
| 10 | Tredegar . . | { Tredegar Iron and Coal Co., Limited . . . } | 72 | 5 |
| 11 | Oakfields . | James C. Hill & Co., Lim. . | 12 | 4 |
| 12 | Cwmbran . | Patent Nut and Bolt Co. . | 23 | 4 |
| Total Monmouthshire . . . | | | 209 | 41 |
| <i>Brecknockshire—</i> | | | | |
| 1 | Coedcae . | The Welsh Iron Works Co. . | ... | ... |

The only works in Monmouthshire where steel is produced by the system associated with the name of Sir Henry Bessemer are those of the Ebbw Vale Company; these works were established in the year 1866, and at the present time possess six convertors, four of which have a capacity of eight tons and two a capacity of ten tons each; six cupolas being employed for supplying molten metal to the convertors. When actively employed these works can produce 1,000 tons of steel ingots per week, while one of the rail mills have been known in a single week to turn out 800 tons of finished rails. It was at these works that "speigelsisen" was first manufactured in this country, due to the energy and activity of Messrs. Richards and Parry, the engineer and chemist to these extensive works.

Coal used in Mills and Forges.—In these and the Tin Plate Works in Monmouthshire and Brecknock in the year 1873, the total consumption of coal may be set down as not less than 600,000 tons, but it will be remembered that during a period of three months the tin plate works were affected by a strike, which had the effect of diminishing the consumption of fuel by at least 100,000 tons; while in the year 1880 it probably did not exceed 460,000 tons. The average consumption of coal in the puddling

furnaces of this district may be set down as varying from 1,000 to 1,100 tons per annum.

Glamorganshire Mills and Forges. Bessemer Steel Works.

—Here, as in Monmouthshire, mills and forges were in active operation cotemporary with the great iron works which have long flourished. In the year 1860 there were 16 of these malleable works in operation, with 628 puddling furnaces and 69 rolling mills; the resources since that period have been greatly augmented. The extent to which the works in Great Britain have extended from 1860 to 1875 is considerable, in the first named year, 208 works were in operation, increased to 314 in 1875, the number of puddling furnaces increasing from 3,462 to 7,575, and the rolling mills from 432 to 909 in each of the same years.

Of the iron works established since 1860 many have been closed for the past four or five years, and some have been entirely dismantled. The depreciation in the finished iron trade referable to Glamorganshire, may be gathered from the fact, that in 1870 there were 568 puddling furnaces in operation, compared with 340 in the year 1877, and 308 in the year 1880. The Dowlais Iron Works are the most extensive, with 150 puddling furnaces and 15 rolling mills; of these 65 furnaces and 15 mills were in operation in the year 1880. The Dowlais Company also possess important Bessemer steel works, the first introduced into this country. These were started in June, 1865; they at the present time consist of six converters, two with a capacity of five tons, two of six tons, and two of seven and-a-half tons, or a total capacity of 37 tons, together with the usual blowing and hydraulic machinery. The Dowlais works in activity are capable of producing 1,500 tons of steel per week, consisting chiefly of railway bars and fastenings. In addition to which there are six furnaces constructed on the Siemens Martin system; the steel made by this process is employed for all purposes in which soft steel is ordinarily applied. In England it is used for casting screw propellers, and for various other high class steel castings.

At the celebrated French works at Creusot, steel containing 10 per cent. of carbon is manufactured by this process, and is used for piston rods, and other parts of steam engines, boiler plates, and more recently for shipbuilding.

Another important establishment to refer to, is the Landore Siemens Steel Company Works, situated at Landore, near Swansea :

the works consist of:—Two blast furnaces with Cowper's patent stoves, turning out when fully occupied 600 tons of pig iron per week; 24 Siemens' regenerative steel melting furnaces, making on an average 65 tons of steel per week; eight steam hammers of eight tons each, one four tons, and one two tons for making blooms for rails, tyres, &c., and for forgings; two rail mills complete with saws, straightening and other machines capable of making 1,800 tons of finished rails per week; beyond these are a tyre mill complete, bar mill for steel bars of all kinds, wire mill for rolling wire rods; 93 Siemens gas heating furnaces, for heating ingots and blooms for hammer and mills, with producers for making the necessary gas; 100 coke ovens for supplying coke to blast furnaces; brick-works for making the necessary bricks for the melting and other furnaces. The company also employ 64 steam engines of all sizes, besides five locomotives, foundries for casting both in steel and iron, and fitting shops. The coal properties of the company comprise all varieties of coal, coking coals, and anthracite, ensuring an unlimited supply of fuel; and in the steel works, when actively engaged, upwards of 2,000 men are employed.

Coal used in Mills and Forges (Glamorganshire).—In the years 1872 and 1873, when it was first attempted to gather information on this subject, it was ascertained that not less than from 750,000 to 800,000 tons were employed, including that used in tin plate manufacture, and even this last quantity is believed to fall short of that actually consumed; it is, however, stated on reliable authority that the average consumption of coal in the mills and forges of Glamorganshire is about from 1,200 tons to 1,800 tons per annum in the manufacture of 500 tons of bars or rails, it being also generally regarded that from five to five and-a-half tons of coal are required to bring each ton of bars or rails into their finished state.

The works of Glamorganshire, showing the number of puddling furnaces and rolling mills, were as follows in the years given:—

| Year. | No. of Works. | Puddling Furnaces. | Rolling Mills. |
|-------|---------------|--------------------|----------------|
| 1870 | 17 | 568 | 90 |
| 1875 | 18 | 526 | 85 |
| 1880 | 18 | 308 | 72 |

The list of the works in the last-named year, with the numbers

of puddling furnaces and rolling mills in operation, appear in the annexed table:—

GLAMORGANSHIRE.

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No of Puddling Furnaces. | No. of Rolling Mills. |
|---------------------------|--|--|----------------------------------|--------------------------|-----------------------|
| 1 | Brynamman . . . | Amman Iron Co. | Llanelli . . . | 10 | 2 |
| 2 | Margam, Talbach . . | Robt. B. Byass & Co. . . . | Aberavon . . . | .. | .. |
| 3 | Clydach | Byrnmawr Coal and Iron Co., Limited | Abergavenny . . | .. | .. |
| 4 | Gadlys | Waynes Merthyr Steam Coal and Iron Works Co., Llm. | Aberdare . . . | .. | .. |
| 5 | Llynvi | Llynvi, Tondy and Ogmores Coal and Iron Co. . . . | Bridgend . . . | 33 | 4 |
| 6 | { Abernant, Taff Vale and Lewydcoed } | Aberdare Iron Co. | Aberdare . . . | .. | .. |
| 7 | Aberaman | Powell Duffryn Steam Coal Co. | " | .. | .. |
| 8 | { Mellin Griffith and Pentyrch . . . } | Thos. W. Booker & Co. . . . | Cardiff | 7" | 14 |
| 9 | Penydarren | { The Aberdare and Plymouth Co., Limited } | " | .. | .. |
| 10 | Briton Ferry | Townsend, Wood & Co. . . . | Briton Ferry . . | 43 | 4 |
| 11 | Cyfarthfa | Robt. Crawshaw | Merthyr Tydfil . | 61 | 5 |
| 12 | Dowlais | Dowlais Iron Co. | " | 65 | 15 |
| 13 | Plymouth | { The Aberdare and Plymouth Co., Limited } | " | .. | .. |
| 14 | Cwm Avon, Talbach . | Governor and Company of Copper Miners Successors | Port Talbot . . | .. | .. |
| 15 | Ystalyfera | Ystalyfera Iron Co. | Swansea | 42 | 16 |
| 16 | Pontardawe | W. Gilbertson & Co. | " | 12 | 6 |
| 17 | Tondy, Bridgend . . . | Llynvi, Tondy and Ogmores Coal and Iron Co. . . . | Tondy | 23 | 3 |
| 18 | College | Thomas Protheroe Gwillelm and Thomas Williams . . | Llandaff | 12 | 3 |
| Total of County | | | | 308 | 72 |

Coal used in Pig Iron Manufacture (Monmouthshire).—In all the early returns bearing on the use of coal, the returns of Monmouthshire are included in those of South Wales. In the year 1828, however, it was ascertained that five and-a-half tons of coal was used in each ton of pig iron manufactured. The results attained by the Royal Coal Commission show that in the year 1869 the average quantity employed did not exceed three tons, which included the necessary fuel for raising steam, engine fires blowing the blast, &c. About the year 1873 a select committee of the House of Commons was appointed to inquire into the high price of coal. It was at this juncture that the Mining Record Office, at the direction of the committee, made a special inquiry with a view of ascertaining the actual quantity of coal used in the iron manufactures of the kingdom, and the result was most satisfactory, inasmuch as it showed that considerable economy in the use of coal in the blast furnace had been secured.

In the Monmouthshire furnaces in 1873 it was subsequently

* Four double and three single furnaces.

ascertained that 48 cwts. of coal was the average quantity used in the manufacture of each ton of pig iron; in the Glamorganshire furnaces 49 cwts. was the average; while in the anthracite furnaces it amounted to 50 cwt.; and taking all the iron works in the kingdom it did not exceed 51 cwts.; while in Scotland, where raw coal was exclusively employed, the average reached 55 cwts. of coal to each ton of pig iron made.

As the consumption of fuel in the manufacture of pig iron will form the subject of inquiry in a future page it will be only necessary here, as in other districts, to record carefully the actual quantities employed, as they appear in the official returns, noting the average consumption of fuel to each ton of pig iron made, at the same time observing that in all cases where coke has been employed its equivalent in coal has been computed; thus, in the following years, the annexed figures show the quantities of pig iron made of coal used and the average quantity of coal to each ton of pig iron made, which includes all purposes in which heat is required, also the economy secured by the utilisation of the waste gases, which of late years have been considerable:—

MONMOUTHSHIRE (BITUMINOUS).

| Year. | FURNACES. | | Pig Iron Made. | Coal Used. | Coal, per ton. |
|-------|-----------|-----------|----------------|------------|----------------|
| | Built. | In Blast. | | | |
| | | | Tons. | Tons. | Cwts. |
| 1872 | 63 | 49 | 465,603 | 1,117,626 | 48 |
| 1873 | 62 | 42 | 360,583 | 867,640 | 48 |
| 1874 | 62 | 41 | 360,480 | 901,200 | 50 |
| 1875 | 62 | 37 | 262,253 | 577,272 | 44 |
| 1876 | 62 | 35 | 413,946 | 879,732 | 43 |
| 1877 | 62 | 30 | 368,480 | 832,723 | 45 |
| 1878 | 57 | 29 | 373,744 | 879,721 | 47 |
| 1879 | 57 | 27 | 337,684 | 769,894 | 45½ |
| 1880 | 56 | 35 | 448,823 | 1,045,449 | 46 |

Coal used in Manufacture (Glamorganshire).—In the furnaces of Glamorganshire, in the bituminous coal districts, it has been ascertained that about the year 1830 four tons of coal were consumed in the manufacture of each ton of iron. In South Staffordshire in the same year the average varied from six to six-and-a-half tons, while in Scotland where raw coal was chiefly employed, the quantity varied from seven-and-a-half to eight tons. A very different state of things now exists, increased economy

being secured, by the many improvements introduced into the smelting operations of the blast furnace since that date, all of which will be generally referred to.

With the year 1872 fairly reliable information is at hand, showing the consumption of fuel, and in the following summary will be seen the proportion of fuel consumed to each ton of pig iron made in the furnaces of Glamorganshire in which bituminous coal was exclusively used :—

GLAMORGANSHIRE (BITUMINOUS).

| Year. | FURNACES. | | Pig Iron Made. | Coal Used. | Coal per ton. |
|-------|-----------|-----------|----------------|------------|---------------|
| | Built. | In Blast. | | | |
| | | | Tons. | Tons. | Cwts. |
| 1872 | 71 | 51 | 462,041 | 1,172,453 | 50 |
| 1873 | 78 | 51 | 424,384 | 1,047,245 | 49½ |
| 1874 | 78 | 40 | 330,484 | 668,769 | 40 |
| 1875 | 78 | 35 | 249,667 | 531,036 | 42½ |
| 1876 | 59 | 28 | 321,754 | 660,558 | 41 |
| 1877 | 76 | 26 | 342,478 | 739,274 | 43 |
| 1878 | 75 | 24 | 367,392 | 755,126 | 41 |
| 1879 | 75 | 23 | 332,174 | 684,249 | 41½ |
| 1880 | 74 | 30 | 440,915 | 922,155 | 41½ |

Some little variation appears in the last column in the average quantities of coal used to each ton of iron made; however the figures as a whole show economy.

In Brecknockshire in the year 1872, the last year in which it appears as an iron producing district, the 28,504 tons of pig iron made in the Beaufort furnaces, with the expenditure of 88,519 tons of coal, gives an average of 62 cwts. of coal to each ton of pig iron made.

Coal used in Manufacture (Anthracite Furnaces).—Attention has been already called to the use of anthracite as a reducing agent in the smelting of the ores of iron in the blast furnace, and accomplished at the Ynisedwyn Iron Works by Mr. George Crane, in the year 1836, and by Mr. J. Palmer Budd, of the Ystalyfera Iron Works in the same year. Anthracite possesses many characteristics, and these are clearly described by Dr. Percy, in his recent Metallurgical volume on Fuel:—"It is very compact, deep black, both when massive and in powder; bright, occasionally somewhat bronzelike, or sub-metallic in lustre, brittle, uneven, or conchoidal in fracture; it does not soil the fingers; it burns with a feebly luminous flame, and is much less

easily combustible than other kinds of coal, and when heated does not in the least sinter; some varieties decrepitate considerably, even when gradually heated." When converted into coke, the small is selected and in admixture with caking coals, pitch or coal tar, in varying proportions, is heated at a high temperature.

Anthracite, owing to its density and purity, yields pig iron of good quality, and in order to overcome its decrepitation in the furnace, and secure satisfactory results, hot blast of a high pressure must be employed. The average quantity of anthracite used in the manufacture of pig iron is variously stated; some twenty-five years since it exceeded 50 cwts.; but in recent years, as far as can be ascertained, it has varied from 48 cwts. to 50 cwts. In one instance at the Ynisedwyn works, it appears on the authority of Mr. S. Kenyon Rogers, that his uncle, Mr. Blackwell, at the above-named works, made pig iron with a consumption of 18 cwts. 2 qrs. and 9 lbs. of anthracite per ton. In the anthracite furnaces of South Wales a pressure of blast of from 4 to 6 lbs. is used; while in the anthracite furnaces of Pennsylvania, in the United States, of larger capacity, the pressure varies from $6\frac{1}{2}$ to $7\frac{1}{2}$ lbs. pressure on the square inch.

In all the computations where fuel is used in the manufacture of pig iron, it will be understood that the quantity for heating the blast, &c., is included; in the case, however, above referred to, of Mr. Blackwell's experiment, in addition to the 18 cwts. 2 qrs. and 9 lbs. employed in the blast furnace, a further amount of 8 cwts. 3 qrs. and 11 lbs., was used for the heating of the boilers in raising steam, making the total quantity of anthracite used 27 cwts. 1 qr. 20 lbs. to each ton of pig iron made. The pig iron thus manufactured, it should be stated, was particularly suitable for conversion into steel, on account of the freedom of the anthracite from sulphur. An average sample of anthracite employed in smelting, contains of sulphur 0.70 per cent., of ash 9.14 per cent.; the ash consisting of silicate of alumina, a small quantity of lime, and a trace of peroxide of iron. Sulphur is always present in coal, in combination with iron pyrites, or bisulphide of iron, from which no coal is entirely free, and is either disseminated through the mass, so as to be invisible, or occurring in laminæ of a brass yellow colour, and sometimes in layers or nodules of considerable size.

Previous to the introduction of apparatus at the mouth of the blast furnace, for the collection and utilisation of the waste gases, it has been estimated that fully two-thirds of the total quantity of heat produced in the blast furnace escaped and was lost. The problem was solved at the Ystalyfera Iron Works by Mr. Budd, and considerable economy has been the result. It would appear that the first idea for utilising the heat of the gases and vapours escaping from the funnel head, was to conduct this hot air through the hot air stove, and use it instead of coal for heating the air which was to be blown into the furnace. In carrying out this arrangement Mr. Budd states that he constructed his stoves for heating the blast in such a manner that a portion of the hot gaseous escape from the top of the furnace was drawn through them and thus economised; previous to the introduction of this arrangement the three stoves required to heat the blast at the Ystalyfera furnaces consumed 35 tons of coal a-week, and required the attendance of two men.

These gases, it should be stated, entered the stove at a temperature of 1800° Fahr., and left it at about 800° Fahr., while the temperature required for the blast did not exceed 600°; thus it will be seen that the heated gases above, without any access of air, supplied more than the heat required, the gases, it must be remembered, escaping at such a temperature that if air was admitted to them they would at once burst into combustion, and thus form another source of heat which has been utilised in many of the iron works of the kingdom in raising steam, and experience shows that the higher the temperature of the blast employed in the furnace the less fuel will be required, while in every case the waste gases from the blast furnaces would be found sufficient to heat the blast, and produce all the steam required for the blast furnaces, and that in addition they might be used to calcine the mine.*

Taking the actual returns of pig iron made in the anthracite furnaces in the year 1872, when eight furnaces produced 25,678 tons, consuming 72,392 tons of anthracite, an average consumption of 56 cwts. appears to each ton of iron made: this appears excessive; however it doubtless includes all fuel used.

In the annexed table is given the number of furnaces built and

* A term commonly used in South Wales for ore.

in blast, the pig iron made, coal used, and the average quantity per ton, in the anthracite furnaces :—

GLAMORGANSHIRE (ANTHRACITE).

| Year. | FURNACES. | | Pig Iron Made. | Coal Used. | Average of Coal per Ton. |
|-------|-----------|-----------|----------------|------------|--------------------------|
| | Built. | In Blast. | | | |
| | No. | No. | Tons. | Tons. | Cwts. |
| 1872 | 13 | 8 | 25,678 | 72,392 | 56 |
| 1873 | 13 | 8 | 32,822 | 81,837 | 50 |
| 1874 | 13 | 7 | 23,760 | 57,240 | 49 |
| 1875 | 13 | 7 | 29,889 | 61,169 | 41 |
| 1876 | 13 | 6 | 20,421 | 52,997 | 51 |
| 1877 | 13 | 4 | * | ... | ... |
| 1878 | 13 | 4 | * | ... | ... |
| 1879 | 13 | 4 | * | ... | ... |
| 1880 | 11 | 4 | * | ... | ... |

The average consumption of coal used as stated above in the year 1875 as 41 cwts. is clearly far below the quantity employed, however, it appears, that if the average be taken at 50 cwt. it will be very near the exact quantity.

Coal used in Pig Iron Manufacture in South Wales.—The production of pig iron and of coal used, in each division of the South Wales mineral field, has been considered; namely, the bituminous districts of Monmouthshire and Brecknockshire, Glamorganshire, and the district in which anthracite is exclusively employed. The next step will be to follow the production of pig iron and of coal used in South Wales as one district, and trace the progress of the economy in the use of fuel. It has been previously stated that about the year 1890 four tons of coal was the average quantity employed in producing each ton of pig iron in South Wales. Since the year 1872, when special attention was devoted to this important subject, by the Mining Record Office, much additional light has been thrown upon it.

In the annexed summary is shown the number of furnaces built and in blast, and the proportion of coal to iron used in the South Wales furnaces. In the year 1873 the total number of blast furnaces in Great Britain numbered 683 in blast, the number built being 892, the make of pig iron was 6,566,457 tons, the coal used 16,718,532 tons; taking these figures the average con-

* The estimated production in each of those years did not exceed from 14,000 to 15,000 tons.

sumption of coal appears to have been 51 cwts. to each ton of pig iron made, comparing favourably with the year 1869, when the average amounted to 60 cwts. :—

SOUTH WALES (INCLUDING MONMOUTHSHIRE).

| Year. | FURNACES. | | Pig Iron Made. | Coal Used. | Average Coal per Ton. |
|-------|-----------|-----------|----------------|------------|-----------------------|
| | Built. | In Blast. | | | |
| | No. | No. | Tons. | Tons. | Cwts. |
| 1872 | 154 | 114 | 1,002,643 | 2,450,990 | 49 |
| 1873 | 148 | 101 | 817,789 | 1,996,722 | 48½ |
| 1874 | 139 | 88 | 714,724 | 1,627,209 | 45½ |
| 1875 | 153 | 79 | 541,819 | 1,169,477 | 43½ |
| 1876 | 134 | 69 | 756,121 | 1,593,487 | 42 |
| 1877 | 150 | 60 | 710,958 | 1,571,997 | 44 |
| 1878 | 145 | 57 | 741,136 | 1,634,847 | 44 |
| 1879 | 145 | 54 | 669,858 | 1,454,143 | 43½ |
| 1880 | 140 | 68 | 889,738 | 1,967,604 | 43½ |

The utilisation of the waste gases, introduced by Mr. Budd, of the Ystalyfera Iron Works, Swansea, some years after the application of the hot blast by Mr. Neilson, has been a fruitful source of economy, from four tons of coal to each ton of iron made in 1830, to 51 cwts. in the year 1872. Various arrangements have been successfully applied towards this end, all of which will be found fully described in the works of the great authorities on metallurgy, the matter being generally referred to here as a cause for the diminution in the consumption of fuel in iron making. On the continent of Europe, where fuel was more expensive, the utilisation of the waste gases was introduced at an earlier period than in this country; however, at present the system is, with few exceptions, universally adopted in all our iron-producing districts.

Iron Ore used in the Manufacture of Pig Iron.—The total quantity of ironstone of all varieties used in the make of pig iron in the blast furnaces of Monmouthshire in the year 1873 was 792,094 tons. The ironstone or “mine” of the district when smelted alone yields from 32 to 33 per cent. of metallic iron, and in this proportion would require for each ton of pig iron made, from 60 to 62 cwts. The admixture of other ores obtained from Lancashire and Cumberland, as well as ores imported from Spain, all rich in metallic iron and extensively employed in the district, reduce the bulk of ore required to an average of about 44 cwts. of raw stone to each ton of pig iron made. The iron

ore smelted in this district in 1873 may be approximately stated as follows :—

| DISTRICTS. | TONS. |
|-------------------------|----------------|
| Native mine | 502,734 |
| Foreign ores | 140,000 |
| Somersetshire | 29,360 |
| Forest of Dean | 120,000 |
| Northamptonshire | |
| Cornwall | |
| Lancashire | |
| Ireland | |
| Total | <u>792,094</u> |

The metallic iron contained in the foreign ores vary from 50 to 60 per cent., the hæmatite ore of the Forest of Dean from 62 to 63 per cent., the Northamptonshire ore 40 per cent., the Cornish ores from 50 to 60 per cent., the rich red ores of Lancashire and Cumberland from 60 to 64 per cent., and the aluminous ores from the North of Ireland, from 35 to 40 per cent. In subsequent years since 1872 ores of all kinds in the following quantities have been smelted in the furnaces of Monmouthshire :—

| Year. | Pig Iron. | Iron Ore. |
|-------|-----------|-----------|
| | Tons. | Tons. |
| 1873 | 360,583 | 792,094 |
| 1874 | 360,480 | 760,600 |
| 1875 | 262,253 | 536,367 |
| 1876 | 413,946 | 828,865 |
| 1877 | 368,480 | 719,869 |
| 1878 | 373,744 | 749,588 |
| 1879 | 337,684 | 644,248 |
| 1880 | 448,823 | 811,743 |

The argillaceous ores of the coal measures, or native mine, when calcined, lose from 27 to 30 per cent., an amount that is made up of the water and carbonic acid that is driven off, diminished by the oxygen taken up in the conversion of the protoxides of iron and manganese into magnetic oxides. As far as can be ascertained in the years 1878 and 1879 the iron ore reduced in the Monmouthshire furnaces, was derived from the following districts. The total production of iron ore in 1880, in South Wales, amounted to 848,927, of which 278,361 tons were argillaceous, and 65,566 tons hematitic :—

| Districts. | 1878. | 1879. |
|-------------------------------------|---------|---------|
| | Tons. | Tons. |
| Native mine | 276,974 | 253,789 |
| Foreign ores | 326,614 | 308,299 |
| Somersetshire | 40,000 | 21,736 |
| Forest of Dean | 106,000 | 20,000 |
| Northamptonshire | | |
| Cornwall, Ireland, &c. | | |
| Lancashire and Cumberland | ... | 40,424 |
| Total | 749,588 | 644,248 |

In the Glamorganshire furnaces in the year 1873 the quantity of iron ore smelted amounted to 854,171 tons, producing 424,384 tons of pig iron; and as far as can be ascertained this quantity was obtained from the following sources:—

| | |
|---|----------------|
| | TONS. |
| Argillaceous ores (Native mine) | 248,777 |
| Foreign ores (ascertained) | 155,082 |
| Various (British and foreign) | 450,312 |
| Total | <u>854,171</u> |

In the metallurgical works of this district in late years the main bulk of the ores smelted consist of foreign ores; in one establishment from 30 to 34 cwts. of these rich ores yield one ton of pig iron, in other works the quantity varies according to the admixture of ores employed, ranging from 38 to 40, 44 and 47 cwts. to each ton of pig iron made, a careful examination of the quantity showing that the average consumption of ore to one ton of crude metal may be taken as 40 cwts. 1 qr. As far as can be ascertained the following quantities represent the total tons of all kinds of ore used in each of the years since 1873 in the Glamorganshire furnaces, the pig iron made being also given:—

| Year. | Pig Iron. | Iron Ore. |
|-------|-----------|-----------|
| | Tons. | Tons. |
| 1873 | 424,384 | 854,171 |
| 1874 | 330,484 | 638,359 |
| 1875 | 249,667 | 479,612 |
| 1876 | 321,754 | 640,768 |
| 1877 | 342,478 | 667,619 |
| 1878 | 367,392 | 699,769 |
| 1879 | 332,174 | 643,398 |
| 1880 | 440,915 | 787,279 |

In the Anthracite district in the year 1873 the total quantity of ironstone of all kinds employed in the manufacture of 32,822 tons of pig iron, was 77,000 tons; the great bulk of this ore was obtained from foreign countries, the ironstone of the district did not exceed 20,000 tons of the quantity; the Spanish ores as previously stated yielding from 50 to 60 per cent. of metallic iron.

Taking all the facts obtainable the average quantity of ore of all kinds used in this district in obtaining one ton of pig iron may be set down as 48 or 49 cwt., and it may be observed that under the most favourable circumstances it rarely happens that the whole of the metal contained in the ore is obtained, a portion remaining in the cinder. In each of the years since 1873 the annexed quantities show generally the proportion of iron ore to the pig iron obtained in the anthracite furnaces :—

| Year. | Pig Iron. | Iron Ore. |
|-------|-----------|-----------|
| | Tons. | Tons. |
| 1873 | 32,822 | 77,000 |
| 1874 | 23,760 | 53,487 |
| 1875 | 29,889 | 61,780 |
| 1876 | 20,421 | 56,263 |

The annual production of anthracite pig iron since 1876 has not exceeded 15,000 tons, the iron ore employed amounting to about 40,000 tons.

Having generally considered the quantites of iron ore and ironstone of all kinds employed in the blast furnaces of South Wales, it only remains to summarise results and tabulate the quantities in the aggregate; thus in each of the years since 1872 the annexed table shows the make of pig iron in South Wales and the total quantities of iron ore employed :—

SOUTH WALES (INCLUDING MONMOUTHSHIRE).

| Year. | Pig Iron. | Iron Ore. |
|-------|-----------|-----------|
| | Tons. | Tons. |
| 1873 | 817,789 | 1,723,265 |
| 1874 | 714,724 | 1,452,446 |
| 1875 | 541,819 | 1,077,759 |
| 1876 | 756,121 | 1,525,896 |
| 1877 | 725,958 | 1,427,488 |
| 1878 | 756,136 | 1,529,357 |
| 1879 | 669,858 | 1,287,646 |
| 1880 | 889,738 | 1,599,022 |

An examination of the above figures shows that since the first-named year the foreign ores have been more extensively employed in the furnaces of South Wales; this is apparent in the increased quantities imported in each of the years 1878 and 1879. It is also a matter of fact that during the same years the argillaceous ores of the district have been somewhat less employed. This will be better understood when the figures are reduced to an average, from which it appears that 42 cwts. were required to make a ton of pig iron in the year 1873; $40\frac{1}{2}$ cwts. in 1878; $38\frac{1}{2}$ cwts. in 1879, and but $36\frac{1}{2}$ cwts. in the year 1880.

CHAPTER XVI.

GLOUCESTERSHIRE IRON INDUSTRIES.

Iron Ore of the Carboniferous Limestone—Description of Deposits—Mines in Operation in 1880—Analyses and Production of Brown Iron Ore—Output of the more important Mines—Distribution of the Forest of Dean Ore—Pig Iron Manufacture—Early History—Production and Yield of Furnaces—Malleable Iron Works, early history—Quantities of Coal and Iron Ore used in Pig Iron Manufacture.

Iron Ore Deposits.—The valuable ores of iron occurring in the carboniferous or mountain limestone, in the Forest of Dean, appear to have been worked about the year 1650, and again, though on a limited scale, in the beginning of the present century; this latter fact we glean from the "Survey of Gloucestershire," by Mr. Thomas Rudge, who states that in the year 1806 the greater part of the ore employed in the blast furnaces, was obtained from Lancashire, and that the ironmasters found it more profitable to import this ore, notwithstanding the high rate of carriage then charged, rather than employ the ores of the district. As the rich character of the Forest hematite became better known the deposits were more fully developed. The year of greatest production was 1871, when the output of the iron mines in the Forest reached 170,611 tons, of the value of £127,957.

In the millstone grit formation the ore is worked but very locally, the principal masses being found in the mountain limestone, where it exists in irregular chambers or "churns," some of which are of considerable extent, yielding many thousands of tons, and having the additional advantage of being worked economically, from the circumstance that no timbering or other supports for the roof is required. The ore is in good request in the ironworks of South Wales and other districts; the quantities, however, sent out of the Forest of Dean have decreased considerably of late years.

Most of the coal-fields of Great Britain possess in a greater or less degree productive measures of ironstone; in the years 1879 and 1880 upwards of one-third of the ironstone raised in the United Kingdom was derived from the argillaceous ores of the coal measures. South Wales, Staffordshire, Derbyshire, Yorkshire and Shropshire, North Wales, and Scotland, are amongst our coal-fields most abundantly supplied with these ores, while, on the other hand, in the coal-fields of Durham and Northumberland, Lancashire and the Forest of Dean, these argillaceous ores of iron are of rare occurrence; their absence, however, in Gloucestershire is amply compensated for by the almost unlimited deposits of brown hematite, occurring in the carboniferous limestone—a rock of a tough crystalline character, bluish-grey in colour, and emitting when fractured a sulphurous odour, due to the presence and decomposition of iron pyrites. This limestone is of considerable value commercially, being used as a flux, and employed as a road metal.

The principal deposits of brown hematite in the Forest of Dean occur in the carboniferous or mountain limestone in extensive hollows, or chambers, caverns, or churns. The mines are situated for the most part on the outcrop or basset of the mineral basin, and many of them are worked to a considerable depth. At the Buckshrafft Mine, one of the earliest wrought mines in the Forest on the eastern side, the hematite is worked at a depth of 250 yards below the level of the outcrop. Various opinions have been recorded as to the extension of these valuable deposits of brown hematite in depth. The Forest of Dean was examined and reported upon some years since, in 1835, by Thomas Sopwith, Esq., F.R.S., one of the Commissioners on behalf of Her Majesty's Commissioners of Woods and Forests; the results of this survey were at a later period delineated in a most interesting and instructive model of the Forest of Dean, now deposited in the Museum of Practical Geology, in Jermyn-street. Again, in the year 1855 the officers of the Geological Survey surveyed the Forest, acting under the direction of the late Sir Henry de la Beche.

Generally it may be regarded that the greatest depth of the coal measures in the Forest mineral basin does not exceed 500 yards from the high water level of the River Severn, while the iron ore deposits, if they occur, are not more than 100 yards

below the coal measures; doubtless, with the winning of the brown hematite at this great depth, considerable difficulties will be experienced in the matter of drainage, from the accumulation of water which would be met with in sinking to the deep of the mineral basin through the coal measures. It is stated that in the Shakemantle Pit, in the Buckshraff Mine, at the depth of 120 yards, the quantity of water encountered does not exceed 2,000 gallons per minute in the worst season of the year. This pit is considerably below the level of the River Severn, draining, probably, the whole of the waters from the outcrop, a distance of nearly three miles north and south. The cylinder of the pumping-engine employed at the above-named pit by Messrs. Crawshay has a diameter of 60 inches, and successfully keeps the mine free of water.

The dip of the strata of the mineral basin near the outcrop on the eastern side of the Forest is about 45 degrees, decreasing gradually towards the centre of the basin, till it reaches the Light Moor Colliery, where it diminishes to 4 degrees, rising again towards the westward, where the strata have the same inclination as on the eastern outcrop.

The question of the occurrence in depth of the brown iron ore is an all-important one; it does not appear improbable, that it will be found deep, and so far as the subterranean operations of the district have been carried, no diminution is apparent either in the quantity or character of the ore wrought. The question has received much attention, and will probably be determined at no distant period, inasmuch as on the eastern side of the Forest, immediately adjoining the Cinderford property of Messrs. Crawshay & Co., are a series of "gales," or royalties, of iron mines known as the Polar Star, Duke of Gloucester, Emperor Napoleon, Berkeley Castle, and Elephant, comprising an area of upwards of 2,000 acres, or 3 square miles, and situated some 6 miles north of Lydney, $4\frac{1}{2}$ miles east of Coleford, and $2\frac{1}{2}$ miles west of Newnham, and favourably situated in regard to railway communication, being intersected by two lines.

Within the above-named area it has been recommended that shafts be sunk in suitable positions by the aid of Messrs. Kind's and Chaudron's pit sinking machinery, iron tubbing being employed to deal more effectually with the influx of water expected to be encountered in these operations. An important

and extensive work of this kind must of necessity be attended with considerable outlay of capital, and calls for the employment not only of large resources, but of great engineering experience and sound judgment in its accomplishment. It is well deserving the attention of the ironmasters connected with these industries, in view of securing future supplies to supplement the diminishing resources of the blackband ironstone, to aid in the solution of the problem, namely, the discovery of the rich brown hematite deposits, supposed to extend to the centre of the mineral basin in the Forest of Dean.

Before passing on to the analyses of the ores, a list of the iron mines in the Forest of Dean, their situation, and the firms working the same, may be found convenient for reference; they were as follows in the year 1880:—

| No. | Name of Mine. | Situation. | Name of Proprietor or Company. |
|-----|---|---|--|
| 1 | Buckahraft . . . | Cinderford . . . | Hy. Crawahay and Son. |
| 2 | Coleford . . . | Coleford . . . | Coleford Iron Co. |
| 3 | Easter . . . | " . . . | Easter Hematite Iron Ore Co., Limited. |
| 4 | Forget-me-not . . . | Bream . . . | J. W. Blanch and Wood. |
| 5 | Oakwood Mill Upper . . . | Noxon . . . | Forest Hematite Iron Ore Co., Limited. |
| 6 | New China Level . . . | | |
| 7 | New China Engine . . . | | |
| 8 | Oakwood Deep Level . . . | Bream . . . | William James. |
| 9 | New Dun Pit . . . | Coleford . . . | Coleford Iron Co. |
| 10 | Lydbrook . . . | Lydney . . . | Thomas Smith. |
| 11 | Noxen Park . . . | Bream . . . | Great Western Iron Co., Lim. |
| 12 | Old Bow and Tufthorn . . . | Clearwell Meend . . . | G. Atkinson. |
| 13 | Old Ham Pit . . . | " . . . | William Henry Fryer. |
| 14 | Old Sling Pit . . . | " . . . | " . . . |
| 15 | Old Park . . . | Bream . . . | Blanch and Wood. |
| 16 | Park Hill . . . | Lydney . . . | H. Crawahay and Son. |
| 17 | Perseverance . . . | Newnham . . . | " . . . |
| 18 | Shraves . . . | Bream . . . | Thomas Hewlett. |
| 19 | { St. Annals Oak Pit, } Shraves . . . | " . . . | J. Hewlett. |
| 20 | Westbury Brook . . . | { Mitcheldean . . . Coleford . . . Staunton . . . | Dowlais Iron Co. William James. Highmeadow Iron Mining Co., Limited. |
| 21 | Dean's Meend . . . | | |
| 22 | Slope Pit . . . | | |
| 23 | Staunton . . . | | |
| 24 | Scar Pit . . . | Bream . . . | William James. |
| 25 | Lufton Frog Pit . . . | " . . . | " . . . |
| 26 | Kingmoor . . . | Noxon . . . | Great Western Iron Co., Lim. |
| 27 | Yew Tree Shraves . . . | Bream . . . | John Shingles. |
| 28 | Tufton . . . | Coleford . . . | Great Western Iron Co., Lim. |
| 29 | Lambe Quay . . . | Clearwell Meend . . . | W. H. Fryer. |
| 30 | Lower Oakwood Mill . . . | Bream . . . | William James. |
| 31 | Lydney Park . . . | " . . . | Lydney and Wigpool Iron Ore Co. |
| 32 | Saint Annals . . . | Cinderford . . . | H. Crawahay and Sons. |
| 33 | { Wigpool Belt and } Injunction Belt . . . | Mitcheldean Meend . . . | { Lydney and Wigpool Iron Ore Co., Limited. |

Analyses of the Forest of Dean Brown Iron Ore or Limonite.—

The hematite of this district, as far as it has been worked, has been thoroughly examined, and numerous analyses are at hand to show the composition of the several varieties. The varieties may be classified as follows: first, a very compact close-grained black ore, of high per centage, locally termed "Brush Ore," sometimes met with in large lumps weighing from two to three tons, but more generally in small masses mixed with the other ores;—secondly, a cellular or spongy variety, often tough, also black and very rich, and occasionally occurring in large quantities; and thirdly, a broken, earthy-looking ore, assuming, on exposure in heaps to the air, a deep red colour, not very rich in itself but extensively used in admixture with the two previous varieties, and it appears to form nearly two-thirds of the bulk of the ore raised in the district.

In the smelting of the ores of this locality considerable facilities are afforded by the abundance of good and cheap fuel from the Forest collieries, and when fluxing material is required, from the limestone of the neighbouring hills. On the principal floor of the Museum of Practical Geology will be found in the wall cases numbered 48 and 49 a large collection of the ores of iron wrought in Dean Forest, described as Brown Iron Ore, one variety distinguished as very compact "Sandstone Ore"; a second from the Mountain Limestone, locally called "Grey Ore"; a third, provincially called "Smith Ore"; and a fourth of a cellular or tubiporous variety, raised at the Easter Mine, near Coleford.*

An examination of two varieties of ore by Mr. Charles Greenham, of the Park End Ironworks, made some years since, the samples submitted to analyses being described as follows: "first, the "Brush Ore," the sample was composed mainly of fragments of the purple-brown hydrated peroxide of iron, having the peculiar stalactitic structure which characterises this ore. A smaller quantity of the brown pulverulent variety was intermixed with the former, and therefore included in the "sample analyses." Another variety, the "Grey Vein," is thus referred to: this ore appears to have been derived from the brush ore by the partial filling up of the cavities, with a crystallised carbonate of lime and magnesia." The following shows the constituents of each of the varieties:—

* "Catalogue, Mineral Collection, Museum of Practical Geology," 1864, p. 5.

| Constituents. | Brush Ore. | Grey Vein. |
|----------------------------|------------|------------|
| Peroxide of iron | 90·70 | 41·86 |
| Protoxide of iron | traces. | traces. |
| Oxide of manganese | | |
| Carbonate of lime | | |
| Phosphoric acid | 0·07 | 0·13 |
| Water | 8·87 | 4·65 |
| Sand and clay | 0·60 | 1·32 |
| Carbonate of magnesia . . | ... | 21·50 |
| Total | 100·24 | 99·86 |

Of these ores the "Brush Ore" yielded of metallic iron 68·50 per cent., and the "Grey Vein" 29·30 per cent. It is further observable that neither of the above samples contains any appreciable amount of sulphur.

The Forest of Dean ores have also been examined in Dr. Percy's laboratory of the Royal School of Mines by Mr. A. Dick, whose results are shown in the annexed statement; the ores examined being those known as the "Brush Ore" and the "Smith Ore," the latter being a more earthy variety derived from the carboniferous rocks :—

| Constituents. | Brush Ore. | Smith Ore. |
|----------------------------|------------|------------|
| Peroxide of iron | 90·05 | 89·76 |
| Protoxide of manganese . . | 0·08 | 0·04 |
| Lime | 0·06 | 0·49 |
| Alumina | ... | 0·63 |
| Magnesia | 0·20 | 0·40 |
| Phosphoric acid | 0·09 | 0·13 |
| Water | 9·22 | 7·05 |
| Insoluble residue | 1·07 | 2·57 |
| Total | 100·77 | 101·07 |

The "Brush Ore," in the foregoing analysis, was found to contain 68·04 per cent. of metallic iron, while that of the Smith Ore was equivalent to 62·86 per cent. These hematites compare favourably with those of Llantrissant, siliceous in character, yielding an average of 41·34 per cent. of metallic iron.

In the north-western district of the Forest there are two descriptions of ore worked, known locally as "Brandy Brush" and "Grey Ore," the former distinguished for containing a high per centage of silica, and the latter of carbonate of lime and silica.

The "Brandy Brush" ore also appears in a few other localities, while the Grey Ore chiefly appears on the western side of the mineral basin near Coleford. The following gives the composition of each variety of these ores; the examination was made in the laboratory of the Royal School of Mines:—

| Constituents. | Brandy Brush. | Grey Ore. |
|------------------------------------|---------------|-----------|
| Sesquioxide of iron | 32·76 | 48·98 |
| Protoxide of iron | ... | 0·24 |
| Protoxide of manganese | trace. | 0·16 |
| Alumina | 0·05 | 0·12 |
| Lime | 0·25 | 14·07 |
| Magnesia | 0·25 | 10·21 |
| Potash | ... | ... |
| Silica | 0·07 | ... |
| Carbonic acid | ... | 20·75 |
| Phosphoric acid | 0·09 | 0·06 |
| Sulphuric acid | trace. | trace. |
| Water hygroscopic | 3·55 | 5·18 |
| Organic matter | ... | ... |
| Ignited insoluble matter | 63·38 | 0·86 |
| Total | 100·40 | 100·63 |
| IGNITED INSOLUBLE RESIDUE. | | |
| Silica | 63·45 | 0·79 |
| Alumina | traces. | 0·05 |
| Sesquioxide of iron | traces. | 0·01 |
| Total | 63·45 | 0·85 |

The metallic iron contained in these ores are equivalent respectively to 22·98 and 34·46 per cent.

The ores raised on the eastern side of the Forest, at the well-known mines of Buckshraff, Findall, and Westbury Brook, appear to be more easily dealt with in the blast furnace than the ores obtained on the north-western side; this is due to the fact that the great bulk of the ore is found in a pulverised condition, and freed from the presence of silica and other injurious elements, while the deposits referred to on the western side occur in a hard compact condition, requiring much blasting in the operation of mining, and containing a high per centage of silica and carbonate of lime.

On the eastern side of the Forest, adjoining the property of

Messrs. Crawshay, at Cinderford, explorations recently made have attracted some attention. The royalties referred to are those "Gales" or "Setts" previously referred to and known as the Polar Star, Duke of Gloucester, Emperor Napoleon, Berkeley Castle, and Elephant Iron Mines. The annexed analysis of the hematite ore raised in the above gales compares favourably with the best quality of similar ores, not only in the Forest but in other parts of the kingdom:—

RESULTS TABULATED.

| | |
|-------------------------------|---------------|
| Peroxide of iron | 82·64 |
| Silica and lime | 5·07 |
| Alumina | 1·09 |
| Phosphoric acid | 1·05 |
| Sulphur | 0·06 |
| Loss in calcination | 10·68 |
| Total | <u>100·59</u> |

The amount of metallic iron contained in the above peroxide is equivalent to 57·85 per cent., while in the calcined ore the metal is concentrated to the extent of 64·77 per cent. The analysis above noted was made in Dr. Percy's laboratory of the Royal School of Mines.

Production of Brown Iron Ore.—The ore raised from the mines of the Forest of Dean is a stalactitic brown hematite, locally known as "Brush Ore;" the more earthy varieties being distinguished as "Smith Ore." The earliest return accessible is for the year 1854, when the production amounted to 85,506 tons, the output of the following iron mines then in operation:—

| NAME OF MINE. | WHERE SITUATED. |
|------------------------------------|------------------------------|
| Buckshraft | Cinderford. |
| Dean Pit | Clearwell Meend. |
| New China Level | Noxon Park. |
| Old Park | Oakwood near Bream. |
| Old Sling Pit | Lydney Old Park. |
| Perseverance and Findall | Soudley. |
| Westbury Brook | Edge Hill, near Mitcheldean. |

The returns, since 1854, of the Forest of Dean iron mines are as follows, and side by side appears the distribution in each of the same years, with the quantities used in the iron works:—

| Year. | DISTRIBUTION OF THE ORE. | | | Used in Iron-works. | Total of Dean Forest. |
|-------|--------------------------|----------------|----------|---------------------|-----------------------|
| | South Wales. | Staffordshire. | Bristol. | | |
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1855 | 20,810 | 31,042 | ... | 40,756 | 92,608 |
| 1856 | 39,450 | 12,000 | ... | 57,818 | 109,268 |
| 1857 | 49,049 | 21,773 | ... | 56,732 | 127,554 |
| 1858 | 34,652 | 16,288 | ... | 56,712 | 107,652 |
| 1859 | 22,587 | 18,524 | 1,726 | 63,455 | 106,292 |
| 1860 | 10,572 | 11,131 | 767 | 67,996 | 90,466 |
| 1861 | 34,024 | 483 | 3,444 | 62,468 | 100,419 |

The total of Dean Forest for the year 1861 includes 1,004 tons carried from the western side of the Forest to the Bullo Pill Junction in that year.

Other deposits of hematite in Gloucestershire, occurring at Frampton Cotterell, near Bristol, were opened out about the year 1861; these deposits occur in the Pennant Grit, an arenaceous rock interposing between the upper and lower coal measures, and have produced ore in the following quantities. The works have been abandoned since the year 1875 :—

FRAMPTON COTTERELL MINES.

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1862 | 5,107 | 1869 | 6,773 |
| 1863 | 6,000 | 1870 | 15,249 |
| 1864 | 11,000 | 1871 | 8,487 |
| 1865 | 8,000 | 1872 | 9,201 |
| 1866 | 6,000 | 1873 | 13,682 |
| 1867 | 6,100 | 1874 | 14,842 |
| 1868 | 6,566 | 1875 | 8,845 |

The other places yielding brown hematite in Gloucestershire occur at Iron Acton, Saint Pierre, Hopewell, Noxon Park, High Meadow, and Lydney Park. The three latter on the estate of the Countess of Dunraven, have from time to time produced ore in some quantity. Iron ore is also known to occur at Cotswold, Eldon Redding, Hoxenwall, Midsummer Norton, Pensford, and Temple Cloud, where pits have been sunk, and the ore occasionally worked. The returns of Noxon Park, High Meadow, and Lydney Park Mines, are as follows in the years given :—

| Year. | Noxon Park. | High Meadow. | Lydney Park. |
|-------|-------------|--------------|--------------|
| | Tons. | Tons. | Tons. |
| 1865 | 22,000 | ... | ... |
| 1866 | 19,126 | ... | ... |
| 1867 | 16,480 | ... | ... |
| 1868 | 25,093 | ... | ... |
| 1870 | 30,000 | ... | ... |
| 1871 | 28,500 | ... | ... |
| 1872 | 10,000 | 1,668 | 15,695 |
| 1873 | 10,000 | 2,703 | 12,000 |
| 1874 | ... | 4,309 | 5,950 |
| 1875 | ... | 3,500 | 3,105 |
| 1876 | 6,626 | 6,755 | 1,186 |
| 1877 | 4,927 | 3,944 | ... |
| 1878 | ... | 561 | ... |
| 1879 | ... | 299 | ... |
| 1880 | 7,028 | 1,555 | ... |

Following the returns of Dean Forest since the year 1861, up to which time they have been given, it will be convenient to continue the returns published since the year 1862, which enables a comparison to be made of the produce of Dean Forest, and the total ore raised in Gloucestershire, together with the respective values in each year. It will be understood that the total of Gloucestershire includes in each year the produce of the outlying deposits previously referred to. The quantities and values of the ores are as follows :—

| Year. | DEAN FOREST. | | TOTAL OF GLOUCESTERSHIRE. | |
|-------|--------------|---------|---------------------------|---------|
| | Quantities. | Value. | Quantities. | Value. |
| | Tons. | £ | Tons. | £ |
| 1862 | 158,908 | 71,508 | 164,015 | 73,806 |
| 1863 | 121,397 | 54,627 | 127,497 | 57,372 |
| 1864 | 130,482 | 58,723 | 141,843 | 63,830 |
| 1865 | 142,807 | 64,526 | 152,710 | 68,983 |
| 1866 | 156,079 | 70,236 | 162,129 | 72,982 |
| 1867 | 156,069 | 70,231 | 156,169 | 70,271 |
| 1868 | 160,722 | 72,324 | 167,288 | 75,333 |
| 1869 | 134,595 | 60,567 | 172,023 | 77,460 |
| 1870 | 138,254 | 62,214 | 183,503 | 82,576 |
| 1871 | 170,611 | 127,957 | 207,598 | 155,060 |
| 1872 | 162,888 | 122,166 | 199,453 | 149,585 |
| 1873 | 163,660 | 98,196 | 199,342 | 125,447 |
| 1874 | 110,203 | 82,653 | 171,428 | 148,910 |
| 1875 | 92,825 | 62,500 | 111,825 | 71,760 |
| 1876 | 98,133 | 66,285 | 114,728 | 77,394 |
| 1877 | 80,555 | 55,219 | 92,974 | 63,261 |
| 1878 | 69,034 | 41,440 | 74,761 | 44,877 |
| 1879 | 52,061 | 31,237 | 58,552 | 35,091 |
| 1880 | 83,198 | 49,918 | 92,159 | 55,174 |

The value of the ore delivered into trucks at the mines in 1862 did not exceed 9s. per ton, increasing to 14s. per ton in 1873; as a general average some varieties did not bring more than 10s. per ton; in the year 1876 the average was 13s. 6d., and in 1880 about 12s. per ton.

The detailed production of the mines in the last-named year was as follows:—

GLoucestershire IRON MINES, FOREST OF DEAN.

| No. | Names of Mines. | Quantities. | Value. |
|-----|---|-------------|------------|
| | | Tons. | £ s. d. |
| 1 | Buckahraft (Cinderford) | 17,641 | 49,918 6 0 |
| 2 | China Engine (Noxon) | 510 | |
| 3 | Coleford (Coleford) | 84 | |
| 4 | Deans Meend (Mitcheldean) | 3,685 | |
| 5 | Easter (Coleford) | 8,994 | |
| 6 | Forget-me-not (Bream) | 200 | |
| 7 | Lambsquay (Clearwell Meend) | 167 | |
| 8 | Lydbrook | 6 | |
| 9 | New China Level (Noxon) | 4,372 | |
| 10 | New Dun Pit | 213 | |
| 11 | Oak Pit | 131 | |
| 12 | Old Ham Pit (Clearwell Meend) | 1,071 | |
| 13 | Old Row Pit | 16 | |
| 14 | Oakwood Mile (Noxon) | 3,233 | |
| 15 | Old Sling Pit (Clearwell Meend) | 9,986 | |
| 16 | Old Park (Bream) | 1,008 | |
| 17 | Parkhill (Lydney) | 596 | |
| 18 | Perseverance (Newnham) | 1,537 | |
| 19 | Saint Annals (Bream) | 4,621 | |
| 20 | Shraves | 592 | |
| 21 | Slope Pit | 983 | |
| 22 | Westbury Brook (Mitcheldean) | 12,413 | |
| 23 | Wigpool Belt | 10,750 | |
| 24 | Yew Tree (Bream) | 389 | |
| | Total of Forest of Dean Ore | 83,198 | 49,918 6 0 |
| 25 | Highmeadow (Coleford) | 378 | 106 16 0 |
| 26 | Ringwell and Gattell | 1,555 | 933 0 0 |
| 27 | Noxon Park (Bream) | 7,028 | 4,216 6 0 |
| | Total of Gloucestershire | 92,159 | 55,174 8 0 |

Before considering the distribution of the Forest of Dean hematite, it will interest those familiar with the district and connected with its mining operations to have for convenient reference reliable data, showing the produce of some of the more important mines in the Forest. With this object in view, the following abstracts have been prepared, showing the annual produce of the

mines named, and giving the returns as far back as possible. The first group to which attention is directed includes those mines in the neighbourhood of Cinderford, on the eastern side of the Forest, from which mines the blast furnaces of the district have received their supplies of hematite ; they are as follows :—

| Year. | Buckshraff. | Findall, &c. | Westbury Brook. |
|-------|-------------|--------------|-----------------|
| | Tons. | Tons. | Tons. |
| 1863 | 44,219 | 9,678 | 13,659 |
| 1864 | 39,770 | 9,416 | 20,501 |
| 1865 | 46,127 | 13,947 | 33,822 |
| 1866 | 48,735 | 10,738 | 35,495 |
| 1867 | 48,659 | 15,079 | 21,810 |
| 1868 | 47,649 | 14,983 | 28,080 |
| 1869 | 42,096 | 11,443 | 25,825 |
| 1870 | 38,639 | 8,471 | 26,352 |
| 1871 | 37,694 | 8,117 | 16,005 |
| 1872 | 34,409 | 3,939 | 14,693 |
| 1873 | 30,706 | 4,472 | 14,112 |
| 1874 | 15,531 | 9,239 | 25,200 |
| 1875 | 21,008 | ...* | 12,518 |
| 1876 | 21,139 | 8,245 | 23,798 |
| 1877 | 17,783 | 9,020 | 10,976 |
| 1878 | 27,212 | 3,077 | 17,781 |
| 1879 | 19,041 | ... | 8,730 |
| 1880 | 17,641 | ... | 12,413 |

Turning to the western side of the Forest, in the district of Clearwell Meend, the mines have produced hematite in the following quantities :—

| Year. | Clearwell. | Old Bow Pit. | Easter. |
|-------|------------|--------------|---------|
| | Tons. | Tons. | Tons. |
| 1863 | 1,309 | ... | 11,398 |
| 1864 | 4,693 | ... | 9,495 |
| 1865 | ... | ... | 4,548 |
| 1866 | 306 | ... | 5,728 |
| 1867 | 1,254 | ... | 10,435 |
| 1868 | 2,151 | 2,981 | 10,409 |
| 1869 | 4,925 | 4,317 | 11,013 |
| 1870 | 1,765 | 6,691 | 9,968 |
| 1871 | 4,861 | 5,181 | 17,619 |
| 1872 | 3,858 | 7,131 | 14,726 |
| 1873 | 5,331 | 5,230 | 13,675 |
| 1874 | 3,255 | 3,234 | 7,077 |
| 1875 | 2,330 | 257 | 6,974 |
| 1876 | 2,331 | 682 | 7,633 |
| 1877 | 340 | 631 | 3,345 |
| 1878 | 602 | 184 | 1,859 |
| 1879 | ... | ... | 1,559 |
| 1880 | ... | 16 | 8,994 |

* No return.

A falling off appears in the output of the above mines, due to the depressed condition of the iron industries of late years.

The following mines in the neighbourhood of Lydney and Coleford gave tonnages as follows in each of the years named :—

| Year. | LYDNEY. | | | COLEFORD. |
|-------|----------|------------|----------|--------------|
| | Oakwood. | Old Sling. | Shraves. | Crow's Nest. |
| | Tons. | Tons. | Tons. | Tons. |
| 1863 | 4,227 | 16,904 | 380 | 300 |
| 1864 | 5,145 | 15,940 | 1,095 | 4,868 |
| 1865 | 6,484 | 12,380 | 553 | ... |
| 1866 | 8,742 | 8,519 | 819 | 158 |
| 1867 | 10,251 | 11,585 | 866 | 5,342 |
| 1868 | 2,981 | 9,952 | 431 | 1,109 |
| 1869 | 3,018 | 4,671 | 175 | 4,790 |
| 1870 | 6,804 | 6,887 | 766 | 5,390 |
| 1871 | 6,858 | 6,285 | 823 | 5,782 |
| 1872 | 8,750 | 7,233 | 2,295 | 4,404 |
| 1873 | 9,960 | 4,988 | 2,704 | 5,230 |
| 1874 | 5,445 | 5,916 | 2,341 | 870 |
| 1875 | 2,121 | 6,455 | 863 | ... |
| 1876 | 765 | 5,543 | 505 | ... |
| 1877 | 408 | 3,603 | 689 | ... |
| 1878 | 4,334 | 3,479 | 102 | ... |
| 1879 | 3,501 | 881 | 57 | ... |
| 1880 | 3,233 | 9,986 | 592 | ... |

The Deen's Meend Mine of the Dowlais Iron Company, situated near Mitcheldean, and the Wigpool and Saint Annal's Mines, the last-named situated near Cinderford, produced the following quantities in each of the years named :—

| Year. | Wigpool. | Deen's Meend. | Saint Annal's. |
|-------|----------|---------------|----------------|
| | Tons. | Tons. | Tons. |
| 1863 | ... | 13,180 | ... |
| 1864 | ... | 14,768 | ... |
| 1866 | 402 | 12,233 | ... |
| 1867 | 124 | 8,421 | ... |
| 1868 | 122 | 9,813 | ... |
| 1869 | ... | 8,622 | ... |
| 1870 | 6,815 | 6,231 | ... |
| 1871 | 19,792 | 5,336 | 3,214 |
| 1872 | 11,729 | 3,256 | 9,811 |
| 1873 | 22,106 | 3,491 | 10,874 |
| 1874 | ... | 3,555 | 9,620 |
| 1875 | 6,844 | 2,580 | 11,112 |
| 1876 | 4,378 | 2,686 | 3,806 |
| 1877 | 10,535 | 2,490 | ... |
| 1878 | 2,665 | 2,810 | ... |
| 1879 | 2,848 | 2,585 | ... |
| 1880 | 10,750 | 3,685 | 4,621 |

Distribution of the Forest of Dean Ore.—The early returns showing the distribution of the ore to the year 1861, being intimately associated with the production, have already appeared. It will now be desirable to follow the inquiry, and note for subsequent years the quantities sent into other iron-making districts, notably South Wales, Staffordshire, and Somersetshire, distinguishing the quantities retained in the Forest for consumption in the ironworks :—

| Year. | South Wales. | Stafford- shire. | Bullo Pill Junction. | Bristol. | Used in Forest. | Total. |
|-------|-----------------|---------------------|-------------------------|----------|--------------------|---------|
| | Tons. | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1862 | 49,718 | 978 | 8,617 | ... | 99,595 | 158,908 |
| 1863 | 45,946 | 665 | 13,450 | ... | 61,336 | 121,397 |
| 1864 | 51,210 | 32 | 14,741 | 335 | 64,164 | 130,482 |
| 1865 | 43,152 | ... | 9,170 | 3,354 | 87,131 | 142,807 |
| 1866 | 57,904 | ... | 6,000 | 2,074 | 90,101 | 156,079 |
| 1867 | 53,114 | ... | ... | 1,644 | 101,311 | 156,069 |
| 1868 | 50,068 | 251 | ... | ... | 110,403 | 160,722 |
| 1869 | 29,794 | ... | ... | ... | 104,801 | 134,595 |

Of the ore raised in the Forest of Dean, the respective quantities sent from the eastern and western sides appear as follows for each of the years given :—

| Year. | Eastern Side. | Western Side. | Total. |
|-------|---------------|---------------|---------|
| | Tons. | Tons. | Tons. |
| 1856 | 55,450 | 53,818 | 109,268 |
| 1857 | 56,475 | 71,079 | 127,554 |
| 1858 | 71,098 | 36,554 | 107,652 |
| 1859 | 62,557 | 43,735 | 106,292 |
| 1860 | 46,661 | 43,805 | 90,466 |
| 1861 | 64,758 | 35,661 | 100,419 |
| 1862 | 98,431 | 60,477 | 158,908 |
| 1863 | 94,601 | 26,796 | 121,397 |
| 1864 | 95,858 | 34,624 | 130,482 |
| 1865 | 108,985 | 33,822 | 142,807 |
| 1866 | 109,503 | 46,576 | 156,079 |
| 1867 | 123,838 | 32,231 | 156,069 |
| 1868 | 50,649 | 110,073 | 160,722 |
| 1869 | 34,407 | 100,188 | 134,595 |

In the above returns, the ore consumed in the iron furnaces for the years 1868 and 1869 is included in the western side, while in previous years it is included in the eastern side of the Forest.

Since the year 1869 the Severn and Wye Railway have forwarded ore in the following quantities :—

| Forwarded. | 1870. | 1872. | 1873. | 1874. | 1875. |
|----------------------------|--------|--------|--------|--------|--------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| By Water to Wales . . | 21,277 | 35,540 | 12,632 | 2,233 | ... |
| By Rail to Wales . . . | 15,734 | 12,154 | ... | | 12,864 |
| By Rail to Bullo Pill . . | 14,291 | 12,057 | 43,252 | | 1,445 |
| By Rail to Staffordshire . | 12 | 3,855 | ... | 26,437 | 250 |
| By Water to Bristol . . | 148 | 446 | 150 | | ... |
| By Water to Gloucester . | ... | 3,389 | 728 | | ... |
| Total . . | 51,462 | 67,441 | 56,762 | 28,670 | 14,559 |

In the year 1876, and since, the distribution of ore appears in the following quantities by the Great Western Railway :—

| YEAR. | GREAT WESTERN. Tons. |
|----------------|-------------------------|
| 1876 | 73,286 |
| 1877 | 73,236 |
| 1878 | 56,111 |
| 1879 | 37,586 |
| 1880 | 45,014 |

In the year 1876 the Severn and Wye Railway carried out of the district 8,005 tons.

Fig Iron Manufacture.—The Forest of Dean has for many centuries been associated with the iron manufactures of Great Britain, in many localities in the Forest, near the sites selected by the Romans for the erection of their altars dedicated to Mars, the god of battle, numerous remains of scorix or slags have been found, and containing so large an amount of metallic iron, that for many generations it has been found profitable to re-smelt them. In other districts in this country similar remains have been discovered—as, for example, at Bierley, near Bradford, in the West Riding of Yorkshire, and again on the Brendon Hills, in Somersetshire. It is stated that during a period of three centuries about 20 small charcoal furnaces existed in the Forest of Dean, engaged in the re-smelting of these rich slags, said to contain from 30 to 40 per cent. of metallic iron. It is no less remarkable that it was on the hills that these Roman slags were invariably discovered, leading to the inference that bellows were not then employed, but that the furnaces were so constructed as

to utilise the wind by suitable channels, through which it was conducted, always taking advantage of the natural currents. These furnaces, or air bloomeries, were hollows dug out at the top of a hill, with covered channels leading to the hillside in the direction of the prevailing wind, which would blow through them into the fire, the latter being kept up with wood or charcoal, the iron ore being introduced into the burning mass. The early process thus referred to was of a very primitive character, and was attended with very great loss of metallic iron remaining in the rejected slags. Similar air furnaces, it is stated, were employed in Derbyshire in the 17th century for the reduction of the ores of lead. As soon as bellows were introduced, about the 8th⁷ century, a new impulse was given to the iron industries generally; instead of hollows these so-called bloomeries were built up walls, which were gradually heightened till they attained an elevation of from 5 to 6 feet, the diameter also augmenting to 3 and 4 feet, thus becoming wolf furnaces, and furnaces of this description were employed in America and Hungary until less than 100 years ago, and are now in use at the present time in the East, in India and Turkey. Originally these furnaces were rectangular in form, but after the 16th century they became elliptical, and eventually in the last century circular in section. They were not, however, in such a condition as to produce a fusible cast iron, as they could only deliver lumps, "wolves," or pigs of half malleable wrought iron. Previous to the introduction of bellows, as already stated about the 8th century, we find the valleys selected for the sites of blast furnaces or bloomeries, where water power was obtainable, and could be made available as a motive power in impelling the blast; with this change the manufacture was carried on under more favourable circumstances.

In the Forest of Dean, about the beginning of the 16th century, charcoal blast furnaces, it appears, were introduced from the iron districts of the Rhine; these furnaces were 6 feet wide at the boshes and 15 feet high, and we have the authority of Mr. David Mushet, who found the remains of two such furnaces, having probably been built during the reign of Edward VI., and about the year 1550. Again, in the reign of Elizabeth, it is known that the art of iron casting had in this country attained a certain degree of perfection, as cast-iron ordnance were then largely exported to the Continent, and the annual production of charcoal

pig iron at this period was estimated at not less than 180,000 tons per annum. The great drain on our forests at a subsequent period to furnish the fuel—charcoal—for the reduction of the ores of iron in the blast furnace, nearly brought the iron industries of England and Wales to a standstill; indeed, not less than three-fourths of the blast furnaces then erected were inactive. As a matter of history, it may be here stated that Oliver Cromwell was an ironmaster in the Forest of Dean about the middle of the seventeenth century.

Not until the year 1740 have we any information to refer to, showing the production of pig iron in the Forest of Dean, although ample evidence exists of the industry being carried on at a very much earlier period. Dealing, however, with the statistical facts available for the year 1740, we find in Gloucestershire, presumably in the Forest of Dean, four furnaces producing 800 tons of charcoal pig iron, being an average make of 200 tons per furnace. At this period the production of charcoal pig iron in Great Britain amounted to 17,350 tons, the make of 59 furnaces. Charcoal continued to be used in the Forest of Dean furnaces, for in the year 1788 we find four furnaces in operation, producing 2,600 tons, giving an average yield of 650 tons per furnace. In this last-named year 24 furnaces using charcoal were in operation in England and Wales, making 18,100 tons of iron, and 53 furnaces using coke making 48,200 tons of iron, or a total make in 1788 of 61,300 tons of pig iron, to which should be added the production of Scotland, amounting to 5,600 tons of coke pig, and 1,400 tons of charcoal pig iron; the Scotch furnaces being those of the Carron Company, and other works situated at Wilsonstown and Cleugh. The total iron made in Great Britain at this time, 1788, being 68,300 tons.*

Advancing to the year 1796, the only furnaces in operation were situated at Flaxley, and produced in that year 380 tons of pig iron; the number of blast furnaces in England and Wales being 104, and the production of pig iron 167,321 tons, while in Scotland the same year 17 furnaces produced 16,086 tons, giving the total yield of the furnaces of Great Britain as 183,407 tons.

At the end of the last and beginning of the present century it is quite certain the iron industries of Great Britain were far from

* For details, see Appendix II., p. 831.

being in a prosperous condition ; indeed, it is stated by some writers that at the period referred to, the iron trade of the Forest of Dean was nearly at a standstill. Other periods of depression ensued, while in later years more prosperous times succeeded, and when about the year 1826 the works and furnaces at Parkend commenced operations, a new era was inaugurated. The Parkend works were projected and carried out by Mr. Moses Teague, who at a later period established the works at Cinderford. The above-named gentleman has the distinction of being the chief agent in promoting the successful development of the iron industries of Dean Forest. Considerable obscurity surrounds the progress of iron manufacture in the Forest between the years 1796 and 1839. In the last-named year the furnaces in operation were those of the Parkend and Cinderford companies, the former having three, and the last-named, two blast furnaces at work, producing 18,000 tons of pig iron, giving an average yield of 3,600 tons per furnace. The return here referred to was prepared by Mr. David Mushet, who made in the same year a survey of the iron industries of the United Kingdom, ascertaining the number of furnaces in operation as 396, and the production of pig iron 1,248,781 tons.*

Again, in the year 1840 the four furnaces in operation in the Forest produced 15,500 tons. From the investigation made in the same year by Mr. William Jessop, of the Butterley Iron-works, who pursued his inquiries to all the iron-making districts of Great Britain, it was ascertained that of the 490 furnaces built 402 were in blast, making 1,896,400 tons of pig iron, and consuming 4,877,000 tons of coal in its manufacture.

Advancing to the year 1851, the total production of pig iron in the five furnaces working amounted to 30,000 tons. At this period the Darkhill and Oakwood Vale furnaces were in course of erection ; the former by Messrs. Mushet, the latter by the Ebbw Vale Iron Company ; and in the year 1855 the works at Soudley were erected by Mr. B. Gibbons, junr. In subsequent years the furnaces built and in operation, with the production of pig iron and average make per furnace, appear as follows, the production increasing from 21,990 tons in 1854 to 34,927 tons in 1863, and the average make per furnace from 4,395 tons to 5,821 tons :—

* For details, see Appendix II., p. 835.

| Year. | FURNACES. | | Pig Iron Made. | Make per Furnace. |
|-------|-----------|-----------|-----------------|-------------------|
| | Built. | In Blast. | | |
| 1854 | 7 | 5 | Tons. 21,990 | Tons. 4,395 |
| 1855 | 7 | 4 | 19,500 | 4,975 |
| 1856 | 10 | 5 | 24,132 | 4,826 |
| 1857 | 10 | 5 | 23,882 | 4,776 |
| 1858 | 10 | 4 | 23,580 | 5,895 |
| 1859 | 10 | 6 | 31,750 | 5,292 |
| 1860 | 9 | 4 | 26,458 | 6,614 |
| 1861 | 9 | 3 | 23,163 | 7,721 |
| 1863 | 9 | 6 | 34,927 | 5,821 |

Since the year 1863, and until 1871, the production of the Forest of Dean furnaces are included with the furnaces of Wiltshire and Somersetshire, and appear in the following table :—

| Year. | FOREST OF DEAN. | | WILTSHIRE. | | SOMERSETSHIRE. | | Pig IRON. |
|-------|-----------------|-----------|------------|-----------|----------------|-----------|-----------------|
| | FURNACES. | | FURNACES. | | FURNACES. | | Total. |
| | Built. | In Blast. | Built. | In Blast. | Built. | In Blast. | |
| 1864 | 9 | 6 | 3 | 3 | 2 | 1 | Tons. 65,312 |
| 1865 | 9 | 6 | 3 | 3 | 2 | 1 | 65,471 |
| 1866 | 10 | 6 | 3 | 3 | 2 | 1 | 59,817 |
| 1867 | 10 | 6 | 4 | 3 | 2 | 1 | 71,186 |
| 1868 | 10 | 6 | 4 | 3 | 2 | 1 | 75,847 |
| 1869 | 10 | 6 | 4 | 3 | 2 | 1 | 81,306 |
| 1870 | 10 | 7 | 5 | 4 | 2 | 1 | 93,601 |
| 1871 | 9 | 7 | 7 | 5 | 2 | 1 | 99,997 |

In the year 1872, and following years, the production of the Forest of Dean furnaces is separately distinguished, and appears in the annexed table ; side by side the average yield of each furnace is given :—

| Year. | FURNACES. | | Pig Iron. | Average per Furnace. |
|-------|-----------|-----------|-----------------|----------------------|
| | Built. | In Blast. | | |
| 1872 | 10 | 6 | Tons. 46,226 | Tons. 7,704 |
| 1873 | 10 | 6 | 44,049 | 7,341 |
| 1874 | 10 | 6 | 43,139 | 7,186 |
| 1875 | 10 | 6 | 27,088 | 4,514 |
| 1876 | 10 | 5 | 28,108 | 5,621 |
| 1877 | 9 | 4 | 25,602 | 6,400 |

In the years 1878, 1879, and 1880, the yield of the Forest of Dean furnaces did not exceed 15,000 or 16,000 tons; those in operation being the Cinderford Works, of Messrs. Henry Crawshay & Co., the production of which is included in the returns of Wiltshire and Somersetshire.

The Ebbw Vale Company's Works at Oakwood, it may be noted, were a few years since closed, and the furnaces dismantled. The works in Gloucestershire in 1880, with the names of the companies and number of furnaces built and in blast, were as follows :—

| No. | Names of Works. | Owners. | FURNACES. | |
|------------------------------------|--------------------------|----------------------------------|-----------|-----------|
| | | | Built. | In Blast. |
| 1 | Cinderford | Henry Crawshay and Co. | 4 | 2 |
| 2 | Park End, Lydney | Forest of Dean Iron Co., Limited | 3 | 0 |
| 3 | Great Western, Soudley. | Great Western Iron Co., Limited | 2 | 0 |
| Total of Gloucestershire | | | 9 | 2 |

Malleable Ironworks, Mills, and Forges.—The early history of the Malleable iron trade is more or less historically identified with the early records of the Forest of Dean. According to Scrivenor, in his "History of the Iron Trade," it appears probable that shortly after the Emperor Adrian visited this country (A.D. 120), accompanied by the sixth legion of Roman soldiers, a great military forge—Fabrica—was by his direction established at Bath, for the purpose of manufacturing war implements for the various troops in Britain, and for some bodies of Roman soldiers on the Continent. This branch of manufacture was of considerable importance at that time, and the regulations for the management of the Fabrica, or College of Armourers, were most systematic and complete. The iron used for the manufacture of the military weapons at this establishment is supposed to have been obtained from the Forest of Dean and the hills of Monmouthshire, where the ore was dug up and smelted, the iron taken across the Severn at Lydney, landed at Aust, and taken to Bath by a military way almost parallel with the Upper Bristol Road. Again, we have it on the authority of the Domesday Book that bolts and bars of iron required by King Edward's shipbuilders were obtained from the city of Gloucester, which from its close proximity to the Forest

of Dean reasonably induces to the inference that they were produced there.

Slags and cinders occur in various places in the Forest of Dean and in the Brendon Hills, in which pottery and Roman coins have been discovered, tending to establish the fact of the existence at an early period of ironworks and foundries, in which charcoal had alone been employed. It also appears that at an early period the monks of Flaxley, located in the Forest of Dean, established forges in various places where wood, iron ore, and water were abundant, power being secured for the primitive mechanical appliances then in use, by the flowing streams in the sites selected.

From an original document in the possession of Samuel Timmins, Esq., of Birmingham, and supposed to have been prepared about the middle of the last century, 1750, we learn that about that period there were five works in operation in Gloucestershire, producing 1,120 tons of bar iron per annum. The works were as follows, with the individual production of each :—

| NAME OF WORKS. | MAKE OF BAR IRON. Tons. |
|----------------------------------|----------------------------|
| Lidney | 350 |
| Lidbrook, Three Forges | 350 |
| Upleaden | 120 |
| Tortworth | 150 |
| Flaxley | 150 |
| Total | <u>1,120</u> |

More recently, in the beginning of the present century, about the year 1805, the principal works existing were situated at Froombridge, in the parish of Frampton, where iron and brass wire was made, and at Framilode, in the parish of Eastington, a manufactory of tin-plate was in operation. Again, at Flaxley and at Lydney works of an extensive character are known to have been in existence, both for the reduction of the ores of the district and the manufacture of malleable iron, the first-named of the above works having then, as now, the reputation of making iron of a character known as "red short," especially celebrated and in great request for the manufacture of tin-plate. The works at present and for many years in operation in the Forest of Dean are those at Park End, formerly belonging to the Forest of Dean Iron Company, and now to Messrs. Crawshaw and Sons, consist-

ing of three puddling furnaces and two rolling mills, and the works of the Great Western Iron Company, Limited, situated at Soudley, with one rolling mill.

Coal and Iron Ore used in Manufacture.—Mr. William Jessop, of the Butterley Ironworks, a gentleman previously referred to as being intimately acquainted with the iron industries of Great Britain, ascertained that in the year 1840, in Dean Forest, the quantity of coal consumed in the manufacture of each ton of pig iron was 67 cwts. The Royal Coal Commission, in the year 1869, after a careful inquiry, found that the consumption did not exceed 66 cwts.

Since the year 1872 the exact proportions have been ascertained and appear as follows, of pig iron made and of coal and ore used in its manufacture :—

| Year. | Pig Iron. | Coal Used. | Iron Ore. |
|-------|-----------|------------|-----------|
| | Tons. | Tons. | Tons. |
| 1872 | 46,226 | 125,461 | 119,485 |
| 1873 | 44,049 | 134,019 | 94,019 |
| 1874 | 43,139 | 137,413 | 92,150 |
| 1875 | 27,088 | 87,051 | 75,975 |
| 1876 | 28,108 | 89,318 | 79,541 |
| 1877 | 25,602 | 77,196 | 68,520 |

The quantities of hematite above referred to are exclusively the produce of the Forest mines ; other ores are employed, also a small proportion of mill cinder ; of these latter the quantities are not considerable. Taking the ores throughout, [including the mill cinder used, the average employed varies from 55 to 60 cwts. to each ton of pig iron made. In the preparation of these ores before smelting it is usual to subject them to the process of roasting or calcination, by which the metal is concentrated into a smaller weight by the removal of water, carbonic acid, &c.

In the higher class of hematite ore raised from the Forest of Dean mines, the iron is concentrated by calcination to the extent of from 10 to 12 per cent., the fragments being rendered more porous and susceptible of change in the subsequent operations of smelting in the blast furnace.

Taking the consumption of coal in pig iron manufacture in the Forest of Dean, the average may be generally regarded as slightly in excess of 61 cwts. of coal to each ton of pig iron made ; the

ores of all kinds, as already stated, varying from 55 cwts. to 60 cwts. to each ton of pig iron made. For a few years the details in the annexed table show the quantities of ore conveyed to the several ironworks for reduction since 1856 :—

| Year. | Cinderford. | Parkend. | Soudley. | Total. |
|-------|-------------|----------|----------|---------|
| | Tons. | Tons. | Tons. | Tons. |
| 1856 | 28,000 | 29,818 | ... | 57,818 |
| 1857 | 29,000 | 27,732 | ... | 56,732 |
| 1858 | 40,000 | 16,712 | ... | 56,712 |
| 1859 | 44,000 | 17,655 | 1,800 | 63,455 |
| 1860 | 43,700 | 16,796 | 7,500 | 67,996 |
| 1861 | 42,300 | 19,640 | 528 | 62,468 |
| 1862 | 64,625 | 17,100 | 17,870 | 99,595 |
| 1865 | ... | ... | ... | 87,131 |
| 1867 | 61,311 | 30,000 | 10,000 | 101,311 |
| 1869 | 54,793 | 38,508 | 11,500 | 104,801 |
| 1871 | 60,000 | 52,725 | 20,600 | 133,325 |
| 1872 | 51,748 | 44,137 | 23,600 | 119,485 |
| 1873 | ... | ... | ... | 74,019 |
| 1874 | ... | ... | ... | 92,150 |
| 1875 | ... | ... | ... | 75,975 |
| 1876 | ... | ... | ... | 79,541 |
| 1877 | ... | ... | ... | 68,520 |
| 1878 | ... | ... | ... | 41,312 |
| 1879 | ... | ... | ... | 47,000 |
| 1880 | ... | ... | ... | • |

From the above table it will be seen that from 1867 to 1872 was a period of great activity, since which latter year a great falling off is shown.

* Not ascertained.

CHAPTER XVII.

SOMERSETSHIRE IRON INDUSTRIES.

Description of the Spathose Iron Ore Deposits of the Brendon and Eisen Hills—
Early explorations at Gupworthy Mine—Analyses and Production of Iron Ore
—Pig Iron Manufacture—Mills and Forges.

Iron Ore Deposits of the Brendon Hills.—The district known as the Brendon Hills extends nearly east and west at about six miles south of that part of the coast in the Bristol Channel lying between Watchet and Minehead, and terminates in a deep valley near Eisen Hill, where deposits of iron ore also occur. The Brendon Hills rise boldly on the north side, but on the south side the decline is easier, and they merge into numerous small valleys and gentle elevations; the highest ground in this range of hills is about 1800 feet above the level of the sea. The variety of iron ore occurring in the Brendon and Eisen Hills is that known as Spathic, or carbonate of iron, and brown iron ore; it is also known as Siderite, and forms an important ore and source of metal.

These spathic ores are rich in manganese and valuable for conversion into spiegeleisen; the only other deposits of this kind known to exist in this country are those of Weardale in Durham, where the ore is associated with ores of lead and zinc, at Exmoor in North Devon, the Exmouth and Frank Mills mines near Exeter, the Duchy and Peru, and Perran mines in Cornwall.

The ferruginous deposits of the Brendon Hills occur in the upper division of the middle Devonian rocks, known as Morte slates, composed of clay slate. At the surface the clay slate is of a greyish colour, but in depth it invariably acquires a blue or greenish colour. At a distance of two miles north of the most elevated part of the hills at Treborough, lower beds of this slate (Ilfracombe type) associated with limestone are extensively

quarried, and yield a good roofing material. The ore wrought in the Brendon Hills may be generally referred to the following varieties: first, a "white ore," a spathose ore, generally crystalline in character; secondly, a red ore consisting of decomposed spathose; and thirdly, other varieties known as "black ore," "brown ore," and "potty ore," composed of dark brown ores, more or less cellular.

The above varieties occur in the form of pockets, which sometimes exist in close proximity to each other, admitting of their being worked from one mine. The term "lode," it should be observed, in this district is applied to any metalliferous part of a vein, while the unproductive parts of the lode are said to be "dead;" again, when the sudden enlargement of a lode or pocket takes place, it is designated a bunch of ore.

Numerous indications of old workings in the Brendon Hills point to the fact of there having been extensive explorations in ancient times; it is, however, within the last twenty-five years that they have been opened up on a large scale, growing from insignificant workings to important mines. The iron deposits of the Brendon Hills are the property of the Ebbw Vale Company, the ore raised from the mines being sent to the works of the Company in Monmouthshire.

The most ancient workings appear at the eastern end of the Brendon Hills, known as the Colton Pits, and were wrought horizontally of a zig-zag form; further to the east these old workings are again met with, clearly showing that the ancient miners selected localities in which the ore existed most abundantly; further to the west the Roman and Carew mines occur; these have of late years been further explored and worked on a limited scale. Taking a westerly direction, is the Raleigh Cross Mine, situated and adjoining the Carnarvon Mine, with which it is connected by a heading; the first drift sunk on the lode at the Carnarvon Mine did not reveal a favourable condition; later, in the year 1866, a new drift was commenced, and the more productive part of the lode was opened. Other workings appear to the west at the Burrow Mine, near Wiveliscombe; the ore here wrought is at times hard and red, and occasionally possesses a rich blue colour. The next workings are those at Florry Mine, where the ancient workings were found to have a depth of 30 feet, below which the lode appears to yield a hard red ore; again, in the Bearland Wood

Mine to the west, are found some extensive explorations, the lode yielding large quantities of a soft red ore.

The Gupworthy Mine was the first opened in the Brendon Hills of which there is any account, and it appears to be the locality from which the first undecomposed spathose ore was obtained. Mr. Morgan Morgans, in an interesting paper on the Brendon Hills spathose iron ores and mines, read before the South Wales Institute of Mining Engineers, in 1868, gives the following account of the history of the discovery which led to the development in the Brendon Hills:—"Many years ago a Mr. Tibbets, of Cornwall, being convinced from the nature of the ground, old surface workings, and small mineral specimens found in the latter, that a copper lode existed below, began exploration by driving an adit at Gupworthy. This adit intersected the iron lode, which at this point (20 fathoms deep) was very excellent, compact, and undecomposed spathose.

"Some years later the deposits of the Brendon Hills attracted the attention of the late Mr. Ebenezer Rogers, of Abercarne, who was struck with the similarity of the continental ores and those raised at Gupworthy, a collection of which had been previously made and exhibited in the Great Exhibition of the year 1851 from this and other districts. He subsequently more fully explored the deposits, ascertaining their extent and importance, and eventually transferred his interest to the Ebbw Vale Iron Company, who set to work vigorously and developed the deposits, a considerable portion of the lode of which had a thickness of 20 feet. Further to the west explorations were made at Kennesome Hill and Goose-Moor Mines in the Brendon Hills, beyond which ore has not hitherto been wrought to any extent, until Eisen Hill is reached, where, as previously stated, valuable pockets of ore occur."

Analyses of the Spathose Iron Ore of the Brendon Hills:—
This ore, especially rich in manganese, has attracted considerable attention of late years, the pig iron made therefrom being of excellent quality, and suitable for conversion into Bessemer steel. The ore has been examined by Mr. John Spiller, and is found occasionally streaked with red hematite. At the outcrop of the veins the spathose ore is invariably found to be converted to a considerable depth into brown hematite by the influence of air and water. The following shows the composition of the ore:—

RESULTS TABULATED.

| | |
|----------------------------------|---------------|
| Protoxide of iron | 43·84 |
| Protoxide of manganese | 12·64 |
| Peroxide of iron | 0·81 |
| Lime | 0·28 |
| Magnesia | 3·63 |
| Carbonic acid | 38·86 |
| Total | <u>100·06</u> |

The equivalent of metallic iron determined by the above analysis is 34·65 per cent., and of manganese 9·73 per cent.; the spathose ore of Weardale giving 38·56 per cent. of metallic iron, and 1·86 per cent. of manganese.

The ore by calcination exhibits the following constituents, the loss in weight by the process being equivalent to 34·29 per cent.:—

RESULTS TABULATED.

| | |
|------------------------------------|---------------|
| Magnetic oxide of iron | 47·87 |
| Sesquioxide of manganese | 14·06 |
| Lime | 0·28 |
| Magnesia | 3·63 |
| Insoluble residue | 0·08 |
| Loss by calcination | 34·40 |
| Total | <u>100·32</u> |

The metallic iron contained in the calcined ore is equivalent to 34·16 per cent. The following analyses, composed of a burthen of Brendon Hills ore and Welsh Mine, is given by Dr. Percy in his "Metallurgy of Iron and Steel," the yield of metallic iron representing 32·18 per cent. The details of analysis are as follows:—

RESULTS TABULATED.

| | |
|----------------------------------|--------------|
| Protoxide of iron | 41·03 |
| Peroxide of iron | 0·41 |
| Protoxide of manganese | 0·55 |
| Alumina | 5·79 |
| Lime | 3·00 |
| Magnesia | 3·36 |
| Potash | 0·86 |
| Silica | 13·35 |
| Carbonic acid | 28·49 |
| Phosphoric acid | 0·70 |
| Water | 1·93 |
| Organic matter | 0·07 |
| Total | <u>99·54</u> |

The calcined ore of the Brendon Hills is concentrated to the extent of 51 per cent. in the raw state, it varies between 34 and 35 per cent. Thus, to make a ton of pig iron, 2·89 tons of raw ore would be required, while in the calcined state 1·96 tons would be the quantity required. Mr. John Spiller, who has carefully examined these ores, in Dr. Percy's laboratory, gives the following elementary analysis of the ore after calcination, including the insoluble residue :—

RESULTS TABULATED.

| | | | |
|---------------|----------|----------------------|---------|
| Metallic iron | 50·9971 | combined with oxygen | 21·8559 |
| „ manganese | 14·9130 | „ | 6·4840 |
| „ calcium | 0·3044 | „ | 0·1222 |
| „ magnesium | 3·3150 | „ | 2·2100 |
| „ silica | 0·0509 | „ | 0·0549 |
| „ aluminium | 0·0079 | „ | 0·0069 |
| Oxygen | 30·7739 | „ | 30·7339 |
| Total | 100·3622 | | |

The ore thus calcined is sufficiently rich in manganese to yield a spiegeleisen containing 20 per cent. of that metal.

Production of Iron Ore in Somersetshire.—The spathic ores of the Brendon Hills are worked extensively, as they have been for some years by the Ebbw Vale Iron Company. The ore raised from the mines is conveyed by railway to the coast, shipped to Newport in Monmouthshire, and forwarded from that port to the works of the Company for reduction. The ore was originally obtained from the Carnarvon and Raleigh Cross Mines and shipped from the district; but about the year 1864 a line of railway was constructed over the hills, from the top of the Brendon Hills to Gupworthy, giving increased facilities for sending the ore out of the district. Iron ore has also been raised from time to time at Yatton, Winford, and in the Mendip Hills, being distributed by the Bristol and Exeter Railway for shipment to Bristol, Highbridge, and Bridgewater. The following statement shows the production of the Somersetshire mines from 1855 to 1858 inclusive :—

| Year. | Brendon Hills. | Yatton. | Winford. | Bristol. |
|-------|----------------|---------|----------|----------|
| | Tons. | Tons. | Tons. | Tons. |
| 1855 | 4,940 | ... | ... | ... |
| 1856 | 7,620 | 5,000 | 1,500 | 500 |
| 1857 | 9,642 | 6,000 | 1,200 | 7,500 |
| 1858 | 19,018 | 767 | ... | 1,200 |

The ore raised at Yatton, Winford, the Crescent at Bristol, and Ashton Hill Mines, is brown hematite, that at Ashton Vale, clay ironstone from the coal measures.

In the year 1858, quantities in addition to the above were produced, namely, at Honeymead, 2,000 tons; Ashton Vale, 2,616 tons; and Ashton Hill, 2,000 tons. The total production of all varieties of ore in each of the above years was 4,940 tons in 1855, increased in 1856 to 14,620 tons, in 1857 to 25,342 tons, and 26,041 tons in 1858, the value at the place of production in the last-named year being about 10s. per ton.

In subsequent years the mines of Somersetshire produced ore in the following quantities :—

| Year. | Brendon and Eisen. | Yatton. | Ashton Vale. | Ashton Hill. | Bristol. |
|-------|--------------------|---------|--------------|--------------|----------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1859 | 23,183 | 1,580 | 2,000 | 750 | 1,507 |
| 1860 | 18,072 | 569 | 3,960 | ... | 1,500 |
| 1861 | 23,787 | 175 | 7,300 | ... | 1,500 |
| 1862 | 29,321 | ... | 342 | ... | 1,750 |
| 1864 | 36,385 | 74 | 12,965 | * | 3,500 |
| 1865 | 27,541 | ... | 6,348 | 620 | 3,475 |
| 1866 | 29,468 | ... | 2,720 | 635 | 2,500 |
| 1867 | 32,525 | ... | 2,350 | ... | 2,000 |
| 1868 | 27,925 | ... | 2,760 | ... | 1,765 |
| 1869 | 23,458 | ... | 1,646 | 626 | 1,500 |
| 1870 | 14,603 | ... | 2,110 | 2,051 | 975 |
| 1871 | 27,556 | ... | 1,673 | 2,654 | 1,000 |
| 1872 | 27,913 | ... | ... | 2,000 | 1,000 |
| 1873 | 28,982 | ... | 620 | 15,800 | 1,012 |
| 1874 | 38,316 | ... | 952 | ... | 500 |
| 1875 | 41,793 | 1,674† | 1,015 | ... | 550 |
| 1876 | 41,351 | 2,761† | ... | ... | ... |
| 1877 | 46,895 | 5,033‡ | ... | ... | ... |
| 1878 | 40,115 | ... | ... | ... | ... |
| 1879 | 14,100 | ... | ... | ... | ... |
| 1880 | 27,668 | ... | ... | ... | ... |

The aggregate returns of production of iron ore in Somersetshire as detailed in the above abstract, a few occasional parcels being omitted, appear in the following total, with the value in each year at the place of production, the years of greatest production being 1873 and 1877, increasing from 46,532 tons in the former to 51,927 tons in the last-named year :—

* Included in Ashton Vale return.

† Winford Mines (a variety of ore known as paint ore).

‡ Including Winford and Exford Mines.

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1857 | 25,342 | 12,671 | 1869 | 27,230 | 7,980 |
| 1858 | 26,041 | 13,020 | 1870 | 19,739 | 6,908 |
| 1859 | 29,083 | 14,501 | 1871 | 32,883 | 32,883 |
| 1860 | 24,101 | 12,450 | 1872 | 30,913 | 30,163 |
| 1861 | 32,763 | 16,381 | 1873 | 46,532 | 42,149 |
| 1862 | 31,443 | 15,182 | 1874 | 41,342 | 30,588 |
| 1863 | 34,709 | 17,354 | 1875 | 45,166 | 33,186 |
| 1864 | 54,925 | 26,868 | 1876 | 44,299 | 31,110 |
| 1865 | 37,984 | 18,992 | 1877 | 51,927 | 36,348 |
| 1866 | 35,323 | 17,661 | 1878 | 43,115 | 30,180 |
| 1867 | 36,875 | 17,952 | 1879 | 14,100 | 10,147 |
| 1868 | 32,450 | 12,168 | 1880 | 29,318 | 23,127 |

The average value of the ores from 1858 to 1867 appears to be about 10*s.* per ton; during the years 1871 and 1872 a period of commercial prosperity reigned, not only in the iron and coal, but in other industries, and at this period the value of the ore was greatly augmented, averaging 20*s.* per ton. Since that date a gradual diminution in value is apparent; thus, in the year 1874, the average price per ton was nearly 15*s.*, receding in the year 1876 to 14*s.*, since which the same price may be said to have ruled.

The mines producing iron ore in Somersetshire in 1880 are given in the annexed table, with the respective quantities and value:—

| No. | District or Mine. | Character of Ore. | Quantities. | Value. |
|-----|--------------------------------|-------------------|-------------|----------|
| | | | Tons. | £ s. |
| 1 | Brendon Hills | Spathose . . | 27,668 | 22,134 8 |
| 2 | Dolberrow (Lyncombe) . | | 450 | 270 0 |
| 3 | Harptree, E. & W. (Mendips) | Brown Hematite | 100 | 60 0 |
| 4 | Michael Hobbs (Winford) . | „ | 925 | 555 0 |
| 5 | Tallards (Winford) . . . | „ | 125 | 78 0 |
| 6 | Tarn (Winford) | „ | 50 | 30 0 |
| | Total of Somersetshire | | 29,318 | 23,127 8 |

Pig Iron Manufacture.—About the year 1857 works were erected at Pennywell Road, near Bristol, by Messrs. Langford & Co., commencing the make of pig iron; the quantity made did not exceed 300 tons, the furnace being in blast but a few months; in the year 1858 the make of the furnace increased to nearly 5,000 tons. In the following year the works at Ashton Vale were

projected by Messrs. Knight & Co., and in 1860 produced 1,960 tons of pig iron. The Pennywell Road Works were for many years standing, and finally abandoned about the year 1865. The returns of production of the Ashton Vale Works in subsequent years until 1871 are included in the Gloucestershire returns, and until 1876 in the Wiltshire returns, since which the works have been standing. The malleable iron works, mills, and forges are represented in Somersetshire, by the establishment at Ashton Vale,* conducted by Mr. Joseph Tinn, and possessing 10 puddling furnaces and 3 rolling mills.

* Standing in 1880.

CHAPTER XVIII.

WILTSHIRE, DORSETSHIRE, OXFORDSHIRE, BUCKINGHAMSHIRE, HAMPSHIRE, AND THE ISLE OF WIGHT IRON INDUSTRIES.

Iron Ore Deposits of the Lower Greensand, Coral Rag, and Marlstone rocks of these Counties—Analyses and Production of Ore—Pig Iron Manufacture in Wiltshire, at Westbury and Seend—Production of Pig Iron in Wiltshire (including Gloucestershire and Somersetshire)—Charcoal Pig Iron Manufacture in Hampshire—Coal and Iron Ore used in Manufacture.

Wiltshire and Dorsetshire Iron Ore Deposits.—The form of iron ore known as brown hematite, existing abundantly in this country in the Lias, Oolitic, and Lower Greensand formations, has in recent years given rise to the important iron-producing districts of Middlesborough, Lincoln, Northampton, and Wiltshire. These extensive deposits extend almost continuously from the northern parts of Wiltshire, in the south of England, to the East Riding of Yorkshire, passing through the counties of Oxford, Buckingham, Northampton, and Lincoln. The ores are for the most part of an impure and sandy character, inexpensively wrought and largely employed in admixture with other ores in South Wales, Derbyshire, and Staffordshire.

In Wiltshire the principal deposits of ore occur at Westbury, Seend, and Heywood. At Westbury and at Heywood, in the coral rag, a division of the Middle Oolite; at Seend in the Lower Greensand. The coral rag consists of beds of fossiliferous limestone, containing corals and shells generally in a fragmentary state; the thickness of the deposit at Westbury, where the iron furnaces are erected, is about 15 feet, and it has been traced from the junction of the Salisbury branch of the Great Western Railway to Warminster, which is below the Westbury station, up through Steeple Ashton in Oxfordshire, by Rowde, north of Devizes, and to Kemby, the high ground south of Chippenham.

At Seend, the deposits of iron ore, as previously stated, occur

in the Lower Greensand formation, and are very similar in character to the ores raised in the north of France, in the neighbourhood of Marquise, which are smelted at the ironworks at Outreau, on the river Lianne, near Boulogne. The deposits at Seend are said to occupy an area of 150 acres and upwards, containing an enormous mass of ore, and easily wrought with a pick and shovel; the overburden in some places not exceeding 1 or 2 feet, which is easily removed, enabling the ore to be wrought inexpensively. Operations have been suspended at these mines since 1874, when Messrs. Malcolm and Co. had two furnaces in blast, after which it passed to the Ducal Iron Company. Some years since the Seend ore was in request in South Staffordshire, and at that time bore a carriage of 7*s.* per ton.

Iron ore of a similar character to that occurring at Westbury in Wiltshire is found in Dorsetshire, at Abbotsbury.* The deposit is described as being "in the upper part of the coral rag, containing oolitic grains of oxide of iron imbedded in a calcareous base and forming an iron ore," of which the following is an analysis by G. D. Livering, Esq., of St. John's College, Cambridge. A portion was taken at random, pounded up, and a part of the powder analysed, so as to give as near the average as possible:—

| | |
|-------------------------------|--------------|
| Sesquioxide of iron | 43·97 |
| Silica | 42·60 |
| Magnesia | 1·40 |
| Lime | trace |
| Common salt | |
| Water | 11·88 |
| Total | <u>99·85</u> |

This is equivalent to about 34 or 35 per cent. of iron in the roasted state. At Redlake, a little beyond the village, the ore is of a deep rusty red colour, forming incoherent and heavy masses. About half a mile to the west, on the road to Gorwell, there are bands containing a larger proportion of metallic iron. In the former place it exists to a considerable extent, but in the latter it is less abundant.

Other parts of the coral rag in the neighbourhood of Weymouth are more or less ferruginous, as may be seen in the rusty-looking

* Damons' "Handbook of the Geology of Weymouth and the Island of Portland," 1860, p. 48.

cliff near Sandsfoot Castle, but nowhere is it so rich in iron as at Abbotsbury. At some period these beds may probably be turned to account, either by the erection of furnaces on the spot, or by the conveyance of the raw materials to existing furnaces elsewhere.

Production of Ironstone.—Attention was first directed to these deposits about the year 1855; in 1856 Wiltshire produced 15,000 tons of brown hematite, 5,000 tons being raised at Westbury, and 10,000 tons at Seend, and in the following year this was increased to 15,500 tons.

The following table gives the returns of production since the year 1858, the ore raised at Westbury being smelted at the iron-works of the Westbury Iron Company; the ore at Seend being also smelted on the spot:—

| Year. | Westbury. | Seend. | Heywood. | Total. |
|-------|-----------|--------|----------|---------|
| | Tons. | Tons. | Tons. | Tons. |
| 1858 | 5,719 | 4,103 | ... | 9,822 |
| 1859 | 16,947 | 1,381 | 10,665 | 28,993 |
| 1860 | 40,112 | 32,000 | 4,088 | 76,200 |
| 1861 | 37,529 | 15,000 | 3,250 | 55,779 |
| 1862 | 47,900 | ... | ... | 47,900 |
| 1863 | 72,612 | ... | ... | 72,612 |
| 1864 | 79,918 | ... | ... | 79,918 |
| 1865 | 77,291 | ... | ... | 77,291 |
| 1866 | 75,645 | ... | ... | 75,645 |
| 1867 | 82,586 | ... | ... | 82,586 |
| 1868 | 75,084 | ... | ... | 75,084 |
| 1869 | 104,795 | ... | ... | 104,795 |
| 1870 | 101,423 | ... | ... | 101,423 |
| 1871 | 109,151 | 50,743 | ... | 159,894 |
| 1872 | 95,117 | 1,000 | ... | 96,117 |
| 1873 | 105,929 | 34,200 | ... | 140,139 |
| 1874 | 86,120 | 500 | ... | 86,620 |
| 1875 | 87,152 | ... | ... | 87,152 |
| 1876 | 83,957 | ... | ... | 83,957 |
| 1877 | 79,176 | ... | ... | 79,176 |
| 1878 | 84,756 | ... | ... | 84,756 |
| 1879 | 47,623 | ... | ... | 47,623 |
| 1880 | 67,500 | ... | ... | 67,500 |

The average value of the Westbury ore may be taken at about 4s. per ton, the ore raised at Westbury being smelted at the iron-works of the same name. A glance at the above table will show that Westbury has been the only locality in Wiltshire in which iron ore has been raised since the year 1874.

Analysis of the ore.—The ore raised and smelted at the

Westbury Ironworks is of two varieties, known locally as "brown" and "green" iron ore; the general appearance of the ore is of a dark ochreous character, which, when freshly broken, yields a greenish tinge. The following will show the constituents of each variety, the first-named yielding 41·99 per cent. and the latter 38 per cent. of metallic iron :—

| Constituents. | Brown Ore. | Green Ore. |
|-----------------------------|------------|------------|
| Metallic iron | 41·99 | ... |
| Oxygen | 17·94 | ... |
| Silica | 18·99 | 14·720 |
| Alumina | 2·79 | 5·462 |
| Carbonate of lime | 3·29 | 1·327 |
| Magnesia | 0·54 | trace |
| Combined water | 13·70 | ... |
| Protoxide of iron | ... | 47·250 |
| Peroxide of iron | ... | 1·325 |
| Carbonic acid | ... | 29·237 |
| Sulphuric acid | ... | 0·105 |
| Phosphoric acid | ... | trace |
| Organic matter | ... | 0·365 |
| Loss | 0·73 | 0·209 |
| | 99·97 | 100·000 |

The ore worked at Seend, near Devizes, and, as previously stated occurring in the Lower Greensand, has been examined by Mr. Edward Riley, F.C.S., who has determined its composition as follows; side by side appears for comparison an analysis of the iron ore raised from the Northampton sands of the Great Oolite, near Wellingborough, examined by Mr. John Spiller, formerly of the Royal School of Mines :—

| Constituents. | Seend Ore. | Wellingborough Ore. |
|-----------------------------|------------|---------------------|
| Peroxide of iron | 64·61 | 52·86 |
| Alumina | 3·85 | 7·39 |
| Protoxide of iron | ... | 0·51 |
| Lime | 0·64 | 7·46 |
| Magnesia | 0·20 | 0·68 |
| Phosphoric acid | 0·64 | 1·26 |
| Carbonic acid | ... | 4·92 |
| Silica | 18·02 | 13·16 |
| Sulphur | ... | 0·03 |
| Water | 11·85 | 11·37 |
| | 99·81 | 99·64 |

The amount of metallic iron contained in the Seend ore is equivalent to 45·22 per cent., that contained in the Wellingborough ore amounting to 37 per cent.

Oxfordshire Iron Ore Deposits.—The “Marlstone,” or Middle Lias is the chief repository of the ferruginous ores in this county. The principal localities in which the ore has been wrought, being Fawler, Charlbury, Aynho, Steeple Ashton, Adderbury, and in the neighbourhood of Banbury and Woodstock. As far back as the year 1860 Professor Hull read an interesting paper on the Blenheim iron ore before the meeting of the British Association, in which he remarked “the existence of highly ferruginous beds in the direction of Banbury and Deddington, which had been known for some years, and had to a small extent been quarried and smelted; these are of two varieties, a siliceous ore occurring at the top of the sands which form the lower zone of the Great Oolite, and a calcareous ore forming the upper rock bed of the Marlstone or Middle Lias.” During the progress of the geological survey in the neighbourhood of Woodstock, the existence of this latter ore was ascertained in several places, but in particular along the valley of the Cherwell, west of Charlbury; Mr. Hull subsequently gives the following details concerning its nature and stratigraphical position. The Blenheim ore is identical in geological position, and almost in its nature, with the Cleveland ore of Yorkshire. It forms the rock bed at the top of the Marlstone, which, in Gloucestershire and elsewhere produces the tabulated promontories, which jut out from the flanks of the Oolite escarpment. At Fawler it rests upon soft sands, composing the lower division of the Marlstone, and is surmounted by the clay of the Upper Lias. It varies in thickness from 10 to 15 feet of a nearly uniform composition throughout, except where there occurs bands of fossils, with an excess of carbonate of lime. The shells are marlstone species, as “*Rhynchonella tetrahedra*,” “*Terebratula punctata*,” &c. At the outcrop the rock presents a rich ferruginous aspect, but when reached at positions where it has been protected from atmospheric influences its colour is deep olive green, and the gradual change may be observed in blocks newly split. In its latter state it appears to be oolitic under the magnifying glass. The character of the iron before oxidation is probably that of carbonate and silicate of iron, the latter imparting the green tinge; when exposed it passes into a hydrated peroxide or

iron. The following gives the order of occurrence of the strata near Fawler, where the Marlstone rock bed gives a thickness of 8 feet :—

Great Oolite, White Shelly Oolite.

Inferior Oolite, Coarse Rubbly Oolite (6 feet thick).

Upper Lias, Grey shales and clay (5 feet thick).

Marlstone Rock Bed, Iron ore (8 feet thick).

Marlstone Sands, Fine sands with balls of concretionary iron ore (15 feet).

The outcrop of the rock may be traced along the valley of the Cherwell at Fawler, on the estate of the Duke of Marlborough. The Marlstone rock bed as seen in the cuttings of the railway between Fawler and Charlbury exhibits in section a thickness of nearly 10 feet.

Recently a considerable tract extending over 500 acres is said to have been acquired by the Ducal Coal and Iron Company, in the neighbourhood of Charlbury, to work the iron ore deposits known as the "Fawler Mines;" it has been contemplated to erect blast furnaces to smelt these ores in admixture with other ores known to exist in the Mendips in Somersetshire, the ore being described as a siliceous hematite containing from 42 to 47 per cent. of metallic iron, and from 20 to 25 per cent. of silica. Already the ores raised from the Fawler and Mendip deposits have been smelted in South Staffordshire at the Hange furnaces of Messrs. Round Brothers at Tipton, in the proportion of three tons of Fawler ore to one ton of Mendip ore, the pig iron produced being of good quality.

The ironstone at Adderbury lies beneath the soil at depths varying from 6 to 8 inches to depths of as many feet. The beds of stone themselves varying from 2 to 10, and in some localities to 12 feet in thickness, and is in some places so compact that the pick which is ordinarily employed is laid aside and blasting resorted to, the deposits assuming the character of a solid rock. The cost of production is moderate, the stone being loaded into trucks at the mine at from 3*s.* 6*d.* to 4*s.* 6*d.* per ton of 2,400 lbs.; the ore is said to be comparatively free from impurities, and is chiefly sent into South Staffordshire, where it is used as a mixture in making forge iron of the best quality. These ores were first wrought about the year 1859; the details of production appear as follows :—

| Year. | Fawler. | Adderbury. | Total. |
|-------|---------|------------|---------|
| | Tons. | Tons. | Tons. |
| 1859 | 2,000 | 3,410 | 6,030* |
| 1860 | 4,583 | 1,250 | 5,833 |
| 1861 | 5,600 | ... | 5,600 |
| 1862 | 2,244 | ... | 2,244 |
| 1863 | 4,803 | ... | 4,803 |
| 1864 | 6,666 | ... | 6,666 |
| 1865 | 2,557 | ... | 2,557 |
| 1866 | 1,552 | ... | 1,552 |
| 1869 | ... | 10,167 | 10,167 |
| 1870 | ... | 38,442 | 38,803† |
| 1871 | ... | 26,230 | 28,330‡ |
| 1872 | ... | 56,536 | 63,536§ |
| 1873 | ... | 49,962 | 49,962 |
| 1874 | ... | 38,608 | 38,608 |
| 1875 | ... | 34,568 | 34,568 |
| 1876 | ... | 26,140 | 26,140 |
| 1877 | ... | 14,661 | 14,661 |
| 1878 | ... | 6,240 | 6,240 |
| 1879 | ... | 1,233 | 1,233 |
| 1880 | ... | 8,360 | 8,360 |

At Steeple Ashton the ore deposits also occur in the Marlstone, an upper bed having a thickness of 14 feet and a lower bed of 12 feet thick, reached by a shaft some 30 yards from the surface, said to be in the Oxford clay. The mines are situated about 6 miles north-east of Woodstock, but of late years the deposits have not been wrought.

Analyses of the Ores.—The Fawler ore very much resembles the yellowish-brown variety raised in Northamptonshire from the Marlstone between the Upper and Lower Lias. In the following analysis from a sample consisting of several specimens the results below appear, and side by side an analysis of the Northampton variety, yielding 39·34 per cent. of metallic iron compared with 31·94 per cent. the yield of the Fawler ore, which, by calcination, is increased to 41 per cent. The last-named analysis is by Mr. Charles Tookey, and was made in Dr. Percy's laboratory, who remarks, as regards the Fawler ore, that "the phosphoric acid is only present in a small quantity as compared with specimens of the Northamptonshire ores which have been examined in this

* Including 620 tons raised at Steeple Ashton.

† Including 361 tons raised at King's Sutton.

‡ Including 2,100 tons raised at King's Sutton.

§ Including 7,000 tons raised at King's Sutton.

laboratory ; the absence of this ingredient is an important consideration to the iron smelter" :—

| Constituents. | Fawler. | Northampton. |
|------------------------------|---------|--------------|
| Sesquioxide of iron . . . | 44·67 | 56·20 |
| Protoxide of iron . . . | 0·86 | trace |
| Protoxide of manganese . . . | 0·44 | 0·20 |
| Alumina . . . | 7·85 | 2·43 |
| Carbonate of lime . . . | 9·29 | 0·49 |
| Carbonate of magnesia . . . | 0·66 | 0·17 |
| Silica . . . | 0·48 | ... |
| Carbonic acid . . . | 6·11 | ... |
| Bisulphide of iron . . . | trace | ... |
| Water hygroscopic . . . | 16·31 | { 1·16 |
| Water combined . . . | | { 9·74 |
| Phosphoric acid . . . | 0·55 | 0·84 |
| Insoluble residue . . . | 13·10 | 29·07 |
| | 100·32 | 100·30 |

The insoluble residue of the Fawler ore consisted of silica and alumina, with a trace of lime ; that of the Northampton ore from the neighbourhood of Heyford, near Weedon, containing in the residue quartz, soluble silica, and a little mica. Other analyses of ore from the neighbourhood of Fawler, on the Duke of Marlborough estate, examined and reported upon by Dr. Percy, gives the following percentage of metallic iron :—*

| Samples. | Metallic Iron. | Samples. | Metallic Iron. |
|----------|----------------|----------|----------------|
| No. 1 | 38·65 | No. 6 | 36·94 |
| „ 2 | 35·46 | „ 7 | 31·40 |
| „ 3 | 37·14 | „ 8 | 22·86 |
| „ 4 | 34·42 | „ 9 | 13·06 |
| „ 5 | 32·52 | | |

It is remarked of the two last samples that they contained fossils and a sensible (visible) amount of carbonate of lime.

The Fawler ore already referred to in connection with the Ducal Coal and Iron Company, and operated upon by Messrs. Round, Brothers, gave the following results on analysis by Mr. E. W. T. Jones, public analyst for the county of Stafford. The sample was taken from the heap and examined in the dry state. The sample for the second analysis was obtained from the heading of the underground workings :—

* "Geology of the Country around Woodstock," by Professor Hull, F.R.S., p. 11.

RESULTS TABULATED.

| Constituents. | First. | Second. |
|---------------------------|--------|---------|
| Protoxide of iron | 0·58 | 1·04 |
| Peroxide of iron | 36·50 | 46·93 |
| Manganous oxide | 0·66 | 0·51 |
| Alumina | 7·53 | 7·86 |
| Silica | 10·49 | 10·55 |
| Lime | 19·26 | 11·79 |
| Magnesia | 1·29 | 1·12 |
| Phosphoric acid | 0·71 | 0·66 |
| Sulphuric acid | 0·05 | trace |
| Carbonic acid | 14·00 | 8·55 |
| Pyrites | trace | ... |
| Combined water | 9·60 | 10·15 |
| Loss, &c. | ... | 0·84 |
| | 100·67 | 100·00 |
| Metallic iron | 26·00 | 33·66 |
| | *0·31 | *0·29 |

The ironstone raised at Adderbury is calcareous in character, the best varieties yielding between 36 and 37 per cent. of metallic iron, while the average throughout may be taken as between 28 and 32 per cent.; the amount of lime varies from 15·50 to 51·00 per cent., and on this account the stone is advantageously used with other ores, producing a very fair quality of pig iron. The constituents of the several varieties appear in the annexed analyses:—

RESULTS TABULATED.†

| Constituents. | 1. | 2. | 3. |
|---|--------|--------|--------|
| Sesquioxide of iron | 49·50 | 53·00 | 29·50 |
| Alumina | 12·50 | 9·50 | 7·80 |
| Carbonate of lime | 19·50 | 15·50 | 51·00 |
| Water of hydration, carbonic acid | 9·22 | 13·51 | 7·91 |
| Silica | 9·28 | 8·49 | 3·79 |
| Phosphoric acid | trace | trace | trace |
| Magnesia | trace | trace | trace |
| Manganese | trace | trace | trace |
| | 100·00 | 100·00 | 100·00 |
| Metallic iron (average 31½) . | 35% | 37½% | 22% |
| Average | 36½% | | ... |

* Phosphorus.

† Favoured by S. J. Bates, Esq., Birmingham.

Buckinghamshire Iron Ore Deposits.—In the beds of the Lower Greensand in the neighbourhood of Leighton Buzzard, and at Linslade ironstone occurs; in the last-named locality it appears in nodules disseminated through a thickness of about 50 or 60 feet of brown sand. In no instance in the above localities does the ironstone appear in a continuous bed, the nodules are large and massive, of a brown ochreous character, often hollow and found to contain loose white sand. In the year 1857 the pits produced 2,500 tons of ironstone, since which period all operations have been suspended.

Hampshire and Isle of Wight Iron Ore Deposits.—Near the south-western extremity of the Hampshire coast, in the Bagshot beds, occurring near Christchurch, at Hengistbury Head, iron ore was formerly obtained in considerable quantity by the Hengistbury Mining Company. The Bagshot beds occur in the following order:—uppermost, a superficial flint gravel, succeeded by greenish clayey sands, containing four courses of nodular ironstone, the lowest division consisting of dark carbonaceous clay. The ironstone was wrought by cutting back the face of the cliff, the nodules thus obtained varying in size from 5 to 8 feet in length. On the south and east side of the headland, numbers of these massive nodules repose on the beach, mingled with the sands and gravels detached from the cliff, and forming to some extent a natural breakwater against the inroads of the sea, by which the base of the cliff is washed at high water.

In the Isle of Wight, on the shore, at the foot of the cliffs between Yarmouth and Hempstead Ledge, on the north-western coast, argillaceous ore was formerly collected in some quantities and conveyed to the iron works in South Wales. In the table following appear the quantities of ore raised in each locality since the year 1856:—

| Year. | Hengistbury Head. | Isle of Wight. | Total. |
|-------|-------------------|----------------|--------|
| | Tons. | Tons. | Tons. |
| 1856 | 13,000 | ... | 13,000 |
| 1857 | 7,000 | ... | 7,000 |
| 1858 | 6,000 | 934 | 6,934 |
| 1859 | 6,000 | 1,803 | 7,803 |
| 1860 | 5,000 | 1,119 | 6,119 |
| 1861 | 3,500 | 507 | 4,007 |
| 1862 | 2,800 | 676 | 3,476 |
| 1863 | 1,400 | ... | 1,400 |
| 1864 | 4,400 | 700 | 5,100 |
| 1865 | 3,000 | 525 | 3,525 |

Since the year 1865 there appears to have been a cessation of mining operations in these districts, the cost of carriage of the ore not enabling the mines to compete with districts more favourably situated, from which a class of ore was obtained giving a higher percentage of metallic iron and at a less cost.

Pig Iron Manufacture.—This industry was commenced in Wiltshire by the Messrs. Greenwood & Co., in the year 1857, when the iron works at Westbury, conveniently situated near the railway station, were projected and put in operation by the above-named firm. In the year 1858 the first furnace was put in blast. The yield for the year 1858 is not separately stated, being included in the production of the Pennywell Road furnaces of the Messrs. Langford & Co. of the adjoining county of Somerset, amounting to 2,040 tons of pig iron. It may therefore be assumed that the production of the Westbury furnace exceeded 1,000 tons, there being at this period but one furnace in blast in each county. In the year 1859 the Messrs. Sarl & Co. commenced the erection of two blast furnaces at Seend, and in the following year they were put in blast. At this period the joint production of the works at Westbury and Seend amounted to 21,785 tons, the make of four furnaces giving an average make of 5,469 tons per furnace. In the year 1861 the Seend Works were out of blast, while those of the Westbury Company were but partially employed, there being but one furnace in blast for a period of eight months; at this time and in subsequent years the production of the Wiltshire furnaces is included with those of Somersetshire. The "Mining Journal" gives the following account of the Seend Works at this period:—

"The Seend Iron Works are situated close to the Seend Station, Great Western Railway, being connected thereto by a siding which connects the pig bank of the furnaces with the main line, and the works are built at the foot of a hill which covers the little rural village of Seend. There are three blast furnaces capable of making 300 tons of pig iron per week. The mine is lifted to the top of the furnace by an ordinary but well-constructed hydraulic apparatus, warm water being supplied for the gravitating purposes of the machine from the exhausted condensing water of the blast engine, without heating cost, which precludes the possibility of hindrance from freezing during the winter months. The furnaces are substantially built, and hot blast is used. The

blast engine is 120 horse-power, substantially erected, working with beam and fly-wheel, and slide valves, with an eccentric cam, being a condenser working the steam at a pressure of 14 lbs., three boilers of the ordinary size being used to generate the steam. The make of iron in these works at the time the above was written was about 250 tons per week, and the quality of the No. 1 iron was very fine, breaking strong, and exhibiting a large crystalline fracture."

The above account by a South Staffordshire ironmaster further states that the furnaces were projected and erected under the superintendence of Mr. Fred. Vernon Smith, the then manager.

In giving the yield of the furnaces of Wilts and Somerset, it only remains to add that the Westbury Company put up a third furnace in the year 1862, and a fourth in the year 1865. The works at Seend appear to have been in abeyance for some years after 1861; later a change of ownership took place, and in the year 1870 the works came into the hands of the Messrs. W. and S. S. Malcolm & Co. renewing the manufacture of pig iron with one furnace in blast, the number being subsequently increased to two. Again in the year 1874 a change of ownership takes place, the Ducal Iron and Coal Company appearing as owners, but who never appear to have put any furnaces in blast.

In the following *resumé* the number of furnaces appear in each district, with the total yield of pig iron in the three counties named :—

| Year. | WILTSHIRE. | | GLOUCESTER. | | SOMERSET. | | Total Pig Iron. |
|-------|------------|-----------|-------------|-----------|-----------|-----------|--------------------|
| | Built. | In Blast. | Built. | In Blast. | Built. | In Blast. | |
| | Nos. | Nos. | Nos. | Nos. | Nos. | Nos. | Tons. |
| 1861 | 4 | 2 | 9 | 3 | 2 | 1 | 40,493 |
| 1862 | 5 | 2 | 9 | 5 | 2 | 0 | 51,968 |
| 1863 | 5 | 3 | 9 | 6 | 2 | 1 | 64,001 |
| 1864 | 5 | 3 | 9 | 6 | 2 | 1 | 65,312 |
| 1865 | 3 | 3 | 9 | 6 | 2 | 1 | 65,471 |
| 1866 | 3 | 3 | 10 | 6 | 2 | 1 | 59,817 |
| 1867 | 4 | 3 | 10 | 6 | 2 | 1 | 71,186 |
| 1868 | 4 | 3 | 10 | 6 | 2 | 1 | 75,847 |
| 1869 | 4 | 3 | 10 | 6 | 2 | 1 | 81,306 |
| 1870 | 5 | 4 | 10 | 7 | 2 | 1 | 93,601 |
| 1871 | 7 | 5 | 9 | 7 | 2 | 1 | 99,997 |

In the last-named year the average make per furnace gives 7,692 tons, compared with 5,469 tons in the year 1860. Since

the year 1872, when the consumption of coal became one of considerable interest in the question of the manufacture of iron, returns of the quantities of coal used in pig iron manufacture has been published in the "Mineral Statistics." Following the production of pig iron in Wiltshire, the annexed figures may be generally regarded as a close approximation to the make of the furnaces in each year since that date :—

| Year. | FURNACES. | | Pig Iron. |
|-------|-----------|-----------|-----------|
| | Built. | In Blast. | |
| | Nos. | Nos. | Tons. |
| 1872 | 7 | 5 | 44,255 |
| 1873 | 7 | 5 | 42,844 |
| 1874 | 7 | 3 | 26,605 |
| 1875 | 7 | 2 | 26,388 |
| 1876 | 7 | 2 | 25,718 |
| 1877 | 7 | 2 | 24,988 |
| 1878 | 7 | 2 | 26,751 |
| 1879 | 7 | 2 | 25,000 |
| 1880 | 4 | 1½ | 22,350 |

An examination of the table above shows the increased production of the furnaces; thus, in the year 1872, the average yield was 8,851 tons per annum, compared with 13,194 tons in the year 1875, and 13,875 tons in the year 1878.

The iron ore raised in Wiltshire is smelted in the ironworks of the district, railway communication with moderate freights giving ample means for bringing the necessary materials, coal, and limestone to the works.

The subjoined abstract gives approximately the make of pig iron, and of coal and ore employed in the Wiltshire works since the year 1872 :—

| Year. | Pig Iron. | Coal Used. | Iron Ore Used. |
|-------|-----------|------------|----------------|
| | Tons. | Tons. | Tons. |
| 1872 | 44,255 | 127,255 | ... |
| 1873 | 42,844 | 119,793 | 140,139 |
| 1874 | 26,605 | 74,238 | 86,126 |
| 1875 | 26,388 | 79,575 | 87,152 |
| 1876 | 25,718 | 60,652 | 84,162 |
| 1877 | 24,988 | 61,361 | 82,966 |
| 1878 | 26,751 | 59,771 | 84,756 |
| 1879 | 25,000 | 58,000 | 83,000 |
| 1880 | 22,350 | 50,500 | 67,500 |

In the above table ample data is afforded to determine the proportion of materials employed, which may be assumed to vary from 64 to 65 cwts. of ore to each ton of pig iron made, the average yield of the ore from analysis giving 38 to 41 per cent. of metallic iron. This proportion is fully sustained in each successive year, while in the year 1878 a more favourable condition appears, the average of ore not exceeding 63 cwts. to each ton of pig iron made. The quantity of coal employed in like manner in the production of each ton of pig iron points to economy; for example, taking the figures for the year 1872, an average of $57\frac{1}{2}$ cwts. of coal appears for each ton of pig iron made; advancing to the year 1880, the average appearing in the above returns does not exceed 45 cwts. The Westbury Iron Company in addition to their resources of ore in Wiltshire, possess their own colliery at Nettlebridge in the adjoining county of Somerset, where the coal is coked and conveyed to the works at Westbury, and subsequently employed in the smelting of the ores.

Hampshire Charcoal Pig Iron.—About the year 1868 the Messrs. Harrison, Ainslie, & Co., erected a small furnace at Warsash, near Titchfield in the above-named shire for the manufacture of pig iron with charcoal; this furnace was put in blast in the year 1869, and has since continued, with occasional intervals, to make charcoal pig iron according to the supply of charcoal obtainable from time to time in the immediate neighbourhood and in the south of England. The same firm possess other furnaces of a similar construction at Bonawe in Argyleshire, at Newland, near Ulverstone, and Backbarrow, near Haverthwaite, both in Lancashire, and a fifth at Duddon in Cumberland.

A noticeable feature connected with the Warsash furnace is that suitable mechanical arrangements were at an early period successfully introduced, by which the gases escaping from the top of the furnace were utilised as a source of power and made available for raising steam. The ore smelted at these works is brought from Lancashire, a rich red hematite containing from 64 to 66 per cent. of metallic iron; the iron here made enjoys a high reputation, always secures a ready market, and from its superior quality and strength, as well as toughness, compares favourably with the best charcoal irons of Sweden, Norway, and Russia. The quantity annually produced of charcoal pig iron is not considerable in these works, nor is it separately distinguished, being

included with the returns of the other furnaces of the same firm in Lancashire previously referred to.

There is no exact information available showing the quantity of charcoal necessary for the production of one ton of charcoal pig iron ; from inquiries, however, made on the subject of gentlemen conversant with the manufacture, it may be generally stated that the quantity varies from about 46 to 50 cwts. to each ton of iron made.

CHAPTER XIX.

DEVONSHIRE IRON INDUSTRIES.

Iron Ore Deposits—Early account of Magnetic Ores wrought at Haytor—Deposits at Hennock, Buckfastleigh, North Molton, Smallacombe, Torbay (Paint ore) and Exmoor—Analyses, Production and Distribution of Ores.

Iron Ore Deposits.—Ferruginous deposits are more or less abundantly diffused through the formations of every geological age, the richest varieties being found in the older rocks. In this country the most important deposits of red hematite are found in the hollows of the carboniferous limestone in Lancashire, Cumberland and other places, yielding from 60 to 66 per cent. of metallic iron. The other principal sources of supply being the argillaceous carbonates obtained from the ironstone measures of our coal-fields, which with the varieties obtained from the Liassic and Oolitic strata, furnishes by far the greatest proportion of the ironstone smelted in the blast furnaces of Great Britain.

Spathic ores occur in a few localities in this country, which have been already named, and in a few districts in Cornwall and Devonshire; this latter county, though possessing deposits of iron ore of a good quality, does not produce ore in any considerable quantity compared with other districts; still it commends itself to the attention of the ironmaster, occasioning demand when the iron trade is active.

At an early period iron ore (magnetic oxide,) was wrought at Haytor, near Ilstington. Nearly half a century since, Mr. J. T. Kingston, of Ilstington, Devon, published a very interesting account of this deposit in the "Philosophical Magazine." At that time the lode, as far as explored, exhibited much regularity, and is thus described: "The lode occurs in the clay schist, and the direction of its strata is nearly north-west and south-east, underlying to the north-east at an angle of 22° or 23° only for the first few feet from the surface, but below this the

dip is very regular at an angle of 45° , the lode having a width of 28 feet, of which 16 feet was iron ore." From some experiments made, it appears this ore when smelted yielded iron of a tough and superior description, and was at that time used in admixture with the argillaceous ironstone of the coal measures of South Wales. The Haytor ore at the period referred to was favourably regarded for the manufacture of steel; the average yield of the ore being about 50 per cent. of metallic iron, as determined at that period.

Recent analyses of magnetic oxide of iron made in Dr. Percy's laboratory by Mr. Edward Riley, show the following constituents; the ore is presumably that raised at Haytor, the precise locality of the sample examined not being stated. It is thus described: "Magnetic oxide of iron, Dartmoor, Devonshire. It was compact, black, sub-metallic in lustre, uneven and granular on fracture, and gave a black streak. There was disseminated through the ore a pale green mineral, which remained in the insoluble residue obtained by digestion with hydrochloric acid. Traces of bismuth, tin, and copper were detected in a solution of 900 grains of the ore":—

RESULTS TABULATED.

| | |
|-------------------------------------|---------------|
| Sesquioxide of iron | 62.20 |
| Protoxide of iron | 16.20 |
| Protoxide of manganese | 0.14 |
| Alumina | 2.28 |
| Lime | 2.34 |
| Magnesia | 0.37 |
| Silica | 0.24 |
| Phosphoric acid | 0.10 |
| Bisulphide of iron | 0.07 |
| Water { hygroscopic | 0.28 |
| { combined | 0.34 |
| Ignited insoluble residue | 16.26 |
| Total | <u>100.82</u> |

IGNITED INSOLUBLE RESIDUE.

| | |
|-----------------------------|--------------|
| Silica | 9.42 |
| Alumina | 1.53 |
| Protoxide of iron | 1.12 |
| Lime | 3.18 |
| Magnesia | 1.45 |
| Potash and Soda | 0.10 |
| Total | <u>16.80</u> |
| Metallic iron | <u>57.01</u> |

Haytor has produced iron ore in the quantities given in each of the years named :—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1858 | 3,000 | 1,420 | 1872 | 3,000 | 1,800 |
| 1859 | 1,293 | 612 | 1873 | 600 | 450 |
| 1861 | 68 | 27 | 1874 | 1,669 | 1,500 |
| 1862 | 1,356 | 542 | 1875 | 530 | 159 |
| 1865 | 2,176 | 730 | 1876 | 1,781 | 891 |
| 1866 | 60 | 20 | 1877 | 2,611 | 1,305 |
| 1868 | 1,127 | 338 | 1878 | 724 | 362 |
| 1869 | 505 | 151 | 1879 | 150 | 75 |
| 1871 | 200 | 150 | 1880 | 3,395 | 2,121 |

At Smallacombe, near Ilstington, in the clay slate or killas, which is traversed by masses of greenstone (dolerite,) highly ferruginous and much decomposed near the surface, ores of iron of two varieties occur—the one brown hematite or limonite, the other magnetite; they are thus described * as they occur at Smallacombe : “ The limonite occurs in nodules forming irregular beds in a thick mass of variegated sands and clays, the innumerable layers of which slope gently a few degrees only from the horizontal to the south-east. The magnetite forms three or four beds of variable thickness, occurring in a thick mass of greenstone, which cuts the killas under and west of the beds of limonite. The general dip of the greenstone and its enclosed beds seems to be about 90° from the horizontal and their ‘strike’ nearly north. The brown iron ore beds have a strike considerably west of north, so that the two series of deposits come together near the north of the estate. The upper part of the greenstone, with its enclosed magnetite, is much decomposed, in fact it is worked for umber; and at a few fathoms below the surface large quantities of garnet rock and crystallised garnets, together with tolerably pure hornblende, have been met with.”

At Smallacombe the beds of hematite are wrought in open quarry workings, from which an adit has been driven obliquely through them, westward and northward, for a distance of 90 fathoms, with the object of reaching the beds of magnetite at a greater depth under the hill.

* “ Note on the Iron Deposit at Smallacombe, in Devonshire,” by J. H. Collins, F.G.S., *Miners Association Reports*, 1872—73 p. 71.

An examination of the iron ore raised at Smallacombe, made by Mr. Child of the Dowlais Ironworks, shows the following constituents. The equivalent of metallic iron contained in the ore amounted to 50·44 per cent. :—

RESULTS TABULATED.

| | |
|-------------------------------|---------------|
| Sesquioxide of iron | 41·96 |
| Oxygen | 17·98 |
| Iron as carbonate | 8·48 |
| Carbonic acid | 9·09 |
| Alumina | 1·20 |
| Lime | 1·70 |
| Silica | 10·15 |
| Phosphoric acid | nil. |
| Sulphur | trace |
| Magnesia | trace |
| Moisture | 4·83 |
| Combined Water | 5·49 |
| Total | <u>100·88</u> |

The following are the quantities of iron ore raised and sold from the Smallacombe deposits ; ore was raised in years other than those given, but the quantities are not separately distinguished :—

| Year. | Tons. | Year. | Tons. |
|-------|-------|-------|-------|
| 1865 | 2,176 | 1871 | 352 |
| 1866 | 1,870 | 1872 | 1,775 |
| 1868 | 73 | 1873 | 1,272 |
| 1869 | 507 | 1874 | 2,069 |

Hennock is another locality, near Bovey Tracey and north of Ilsington, where lodes of iron of a micaceous variety occur, varying from 1 to 12 feet in width, bearing east and west, and occurring in a close-grained porphyritic granite, the ore being associated with quartz, schorl, clay and hornblende ; a brown iron ore also occurs at Bishopsteignton, in the limestone in irregular masses.

The Hennock deposit has been worked, at intervals, over a distance of nearly 2 miles, and to the depth of from 20 to 30 feet, and is said to have gone down very rich, the ore being of a micaceous character, yielding 55 per cent. of metallic iron ; the lode nearly vertical, and about 4 feet wide, being worked by two adits driven on the lode from the bottom of the hill. At

Hennock Mine in 1872 there appear to have been raised and sold 181 tons.

The ore and its value raised at Hennock in each year since 1873 is as follows :—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1873 | 3,000 | 2,250 | 1876 | 5,712 | 2,856 |
| 1874 | 4,386 | 3,125 | 1877 | 3,611 | 1,805 |
| 1875 | 1,215 | 911 | 1878 | 2,769 | 1,384 |

The ore is delivered in trucks on the Devon and Somerset Railway, at the Company's siding, at 10s. per ton, and delivered in South Wales at 18s. per ton.

At the South Devon Mine, near Buckfastleigh, occur lodes of brown hematite, coursing east and west, and yielding ore of good quality, the lodes being embedded in killas and limestone. The ore raised in 1872 and 1873 amounted to 380 tons and 476 tons respectively, and in 1874 to 255 tons, the value per ton being 15s., and the yield of metallic iron 55·0 per cent. Several lodes of iron ore have been, from time to time, worked near Brent, in Devon.

At the Florence Mine, North Molton, lodes of hematite are worked by the Florence Mining Company. The lodes dip at an angle of 62°, and vary from 4 feet to 13 feet in thickness, the levels being opened on two separate lodes. Spathose ore also occurs at this mine, but it is not wrought, as purchasers require it calcined. The ore is said to contain from 50 to 55 per cent. of metallic iron, from 10 to 15 per cent. of silica, and free from phosphoric acid and sulphur.

Spathose iron ore has been met with in the Frank Mills Lead Mine, the lead lode passing into white iron ore in depth. A considerable quantity of this spathose ore was raised, and a few small parcels were sold, but recently a large pile of iron ore was to be seen amongst the waste heaps of the mine. Of this pile of spathose ore, a few samples have been taken from time to time, but the cost of transfer from the mine to the shipping port at Teignmouth, prevents its being purchased for use. An analysis of this ore by Dr. Noad, F.R.S., gives the following results :—

RESULTS TABULATED.

| | |
|-----------------------------------|--------------|
| Carbonate of iron | 68.53 |
| Carbonate of manganese | 14.40 |
| Carbonate of lime | 6.48 |
| Carbonate of magnesia | 7.40 |
| Sulphide of lead 1.80 = | sulphur 0.23 |
| Silica | 1.20 |
| Total | 99.81 |
| Iron in raw ore | 38.26 |
| Iron in roasted ore | 54.70 |

Dr. Noad appends a note to the above in which he says, "As nearly the whole of the small quantity of sulphur which this ore contains will be expelled by roasting, and as it is perfectly free from phosphorus, he considers it to be very valuable for making the higher qualities of iron, especially for steel.

The ore obtained from Frank Mills since 1872 was in the following quantities and values:—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1872 | 20 | 13 | 1877 | 12 | 9 |
| 1874 | 70 | 105 | 1879 | 30 | 15 |
| 1875 | 100 | 55 | 1880 | 190 | 95 |

In the neighbouring lead mines, Exmouth and South Exmouth, in Christow, near Exeter, the same change of the lode into spat-hose iron ore took place. At the latter mine, a few years since, preparations for working the iron ore were made, but after raising some fine samples from the mine the adventure was abandoned.

Brown hematite iron ore is also wrought in Torbay, on the south coast of Devon, within one mile of Brixham, and between Torquay and Brixham. The ore occurs in the Devonian limestone, which is tilted at a considerable angle, and broken asunder near the surface. In the fissures formed by the rupture of the rock, repose deposits of iron ore, a large proportion being a hard brown and massive hematite, including some kidney ore and soft oxide of iron.

The fissures containing the ore has been said to have a direction east and west, but from the fractured state of the rock, it is not easy to determine this. It is said to extend to a distance of 800 yards from the sea coast, where the deposit at the top of the

cliff shows an irregular width of nearly 80 yards, and somewhat less below. Five pits have been sunk nearly to the sea level, and have yielded ore of good quality. There are several workings at Brixham, but they have been in abeyance for some time owing to the depressed condition of the iron trade. The hematite deposits known as the Brixham Mines, including workings at Sharkham Point, Five Acres and Charter, have been worked by Messrs. W. Brown and Sons. Brown hematite has also been wrought at the Upton Mine, near Brixham, by the Upton Company.

The hematite raised at Brixham, of two varieties, submitted to Dr. Odling, F.R.S., for examination, gives the following results, the first yielding 66·57 per cent., and the second, 48·70 per cent. of metallic iron.

RESULTS TABULATED.

| Constituents. | First. | Second. |
|--------------------------|--------|---------|
| Peroxide of iron | 95·10 | 69·58 |
| Siliceous matter | 4·15 | 14·38 |
| Sulphur | ·12 | ·15 |
| Phosphorus | trace. | ·10 |
| Water | ·14 | 14·39 |
| Organic matter | ·49 | 1·40 |
| Total | 100·00 | 100·00 |

Other analyses of the Brixham hematite give the following results. One by Dr. Noad, F.R.S., includes an examination of the soft ore, and a second of the ore in lumps, the first being in fine (moist) powder, which was carefully dried:—

RESULTS TABULATED.

| Constituents. | Ore in Powder. | Ore in Lumps. |
|--------------------------|----------------|---------------|
| Peroxide of iron | 63·42 | 90·00 |
| Oxide of manganese . . . | 0·24 | 0·30 |
| Lime | 0·60 | 0·42 |
| Phosphoric acid | 0·28 | 0·38 |
| Insoluble sand | 35·20 | 8·60 |
| Total | 99·74 | 99·70 |

The yield of metallic iron in the soft ore was equivalent to 44·56 per cent., and of the ore in lumps, 68 per cent. Dr. Noad adds, in reference to these analyses, that the first is siliceous in character and not particularly rich in iron; while the second

analysis, of ore in lumps, constitutes by far the largest bulk of the sample, to the extent of seven-eighths is rich and valuable, being materially enhanced by the absence of sulphur and the small percentage of phosphoric acid.

Of the iron ore raised at the mines at Brixham, one kind—a brilliant hematite of a soft variety—is prepared and ground in a mill with linseed oil into paint, which is largely employed in coating ironwork, as a preservative against corrosion, and is commercially known as “Torbay paint.” The ore used in this preparation has the following constituents :—

RESULTS TABULATED.

| | |
|-------------------------------------|---------------|
| Sesquioxide of iron | 89.34 |
| Protoxide of manganese | 0.33 |
| Alumina | 0.33 |
| Lime | 0.33 |
| Magnesia | 0.20 |
| Phosphoric acid | 0.13 |
| Sulphuric acid | trace |
| Bisulphide of iron | trace |
| Water combined | 8.83 |
| Ignited insoluble residue | 1.70 |
| Total | <u>101.19</u> |

These paints are used extensively and advantageously for preserving iron from the corroding influence of impure water, and gaseous exhalations, and are employed by water, gas and railway companies, and in several departments of the Government works.

Other analyses of these paint ores made by different chemists for the original proprietor (Mr. Wolston), who developed the deposits, are as follows :—

RESULTS TABULATED.

| Constituents. | Johnson and Cook. | Herapath. | Prince. | Prince. |
|------------------------------|-------------------|-----------|---------|---------|
| Peroxide of iron | 58.0 | 46.7 | 87.0 | 66.5 |
| Silica | 9.3 | 21.0 | 7.0 | 4.0 |
| Alumina | 12.3 | 12.0 | 2.5 | 2.0 |
| Water | 20.0 | ... | ... | ... |
| Lime | ... | 2.0 | 1.0 | .5 |
| Oxygen | ... | 18.3 | ... | 27.0 |
| Oxide of manganese | ... | trace | 2.5 | ... |
| Total | 99.6 | 100.0 | 100.0 | 100.0 |

The production of brown hematite from the mines in the districts here referred to, is as follows, the interruptions in the returns, showing that the mines were in some years either inactive or their output included in the returns of other mines.

The value of the ore F.O.B. in the year 1875 was 15*s.* per ton.

PRODUCE OF THE BRIKHAM MINES.

| Year. | Tons. | Year. | Tons. |
|-------|--------|-------|--------|
| 1856 | 3,700 | 1866 | 20,005 |
| 1857 | 2,000 | 1867 | 8,762 |
| 1858 | 1,400 | 1868 | 10,976 |
| 1859 | 2,220 | 1869 | 6,092 |
| 1860 | 2,400 | 1870 | 6,100 |
| 1861 | 5,227 | 1871 | 8,772 |
| 1862 | 3,550 | 1872 | 1,593 |
| 1863 | 7,014 | 1874 | 3,466 |
| 1864 | 9,768 | 1875 | 907 |
| 1865 | 16,710 | 1876 | 1,603 |

These mines in the year 1880 appear to have produced some 362 tons of soft ore, of the value of £279.

In North Devon and West Somerset, in that hilly tract of country extending from Ilfracombe to near Bridgewater, considerable explorations have been made in the iron ore deposits, which may be said to extend some thirty miles in length by about five miles in width. Within this area at intervals various iron mines have from time to time been opened. Prof. W. W. Smyth, F.R.S., in a paper * on the iron ores of the district here referred to, thus describes the area: "If from Linton, where the lower beds of the range may be examined, the observer travels southward, he will pass over a constantly ascending series of strata, and about Simon's Bath, on Exmoor, will reach the line of irregular lenticular deposits of limestone, which trending from Coombe Martin by Challacombe, through the midst of Exmoor, to Catborough and Treborough, furnishes an indication of the general strike of the district and a supposed parallel to the more massive limestones of Plymouth."

The ores of iron in Exmoor occur both in regular strata and veins, and it is evident from various circumstances that they were

* "Iron Ore of Exmoor," Geological Society's Journal, 1858, p. 105.

known and worked at an early period. The ores occurring in strata have been found on the flank of Hangman's Hill, near Coombe Martin, in the Valley of the Exe, north-east of Simon's Bath, and in the North Forest, Exmoor, in nodules, generally of small size, and often tilted with the shales in which they occur at such considerable angles, as to render their working difficult. An uncommon variety of chocolate or claret-coloured ore, with an unusually high percentage of iron, is seen in the North Forest of Exmoor. The lodes or iron-bearing veins of this district appear to have a direction running east 10° south, inclining at an angle of from 45° to 65° southwards.

The ore of some of the veins has been examined by Mr. Edward Riley: the first, from the Roman Lode, Cornham Farm, exhibiting small crystals of specular iron, but with a structure through the mass resembling sparry iron (carbonate). The second analysis refers to ore occurring in Roger's Lode, some mile distant, and south of Simon's Bath in the Deer Park, consisting of brown or hydrous peroxide of iron, in a state of great purity, as evidenced by the millions of little prismatic crystals of "Gæthite" lining the interior of numerous cavernous hollows, which are interspersed amidst a mass, bearing evidently the general rhombo-hedral structure of sparry iron:—

RESULTS TABULATED.

| Constituents | First. | Second. |
|-------------------------------------|--------|---------|
| Peroxide of iron | 98·41 | 71·34 |
| Peroxide of manganese | ... | 16·79 |
| Oxide of manganese | 0·29 | ... |
| Silica | 1·01 | 1·49 |
| Magnesia | 0·16 | 0·22 |
| Phosphoric acid | 0·12 | 0·33 |
| Alumina | ... | 1·10 |
| Lime | ... | 0·13 |
| Moisture | 0·13 | 0·79 |
| Combined water | ... | 7·98 |
| Oxide of copper | 0·04 | 0·05 |
| Oxides of nickel and cobalt | ... | 0·19 |
| Total | 100·16 | 100·41 |

The workings in Roger's Lode above referred to, prove it to consist in a width averaging probably 9 feet, of a loosely

agglomerated "Goethite," with much the same character throughout, occasionally intermingled with bands of quartz and fragments of the adjoining slate rock. At Hangley Cleave, on the extreme south of the Moor, a lode of from 15 to 20 feet wide occurs, of botryoidal and cavernous brown ore, intermingled with quartz and slate, and is succeeded, at the depth of a few fathoms only, first by single nuclei and further by masses of a pale coloured and sparry ore.

Ore in some quantity has been raised on the Moor and conveyed to South Wales, but the cost of carriage has operated unfavourably against the development of the deposits on Exmoor.

In North Devon, near Barnstaple, some promising lodes of iron ore were opened out a few years since, at Spreecombe and Bratton Fleming, manganese being also found in the last-named mine. The lodes at Bratton Fleming are situated on the road to Bratton, close to the village, parallel to each other, and three in number. These lodes are also seen in Haxon Lane, some distance north, where they consist of hematite of good quality. At Haxon Lane, already alluded to, these lodes have been laid open by pits; the north-east is about 2 feet wide, the middle lode 4 feet, and the south-west $4\frac{1}{2}$ feet wide. In a field at Haxon, a lode known as "Clegg's Lode," and another as "Shaft Lode," has been proved; the former is found running in a direction north and south, and forms a junction with the latter, which bears north-west and south-east. The lodes are said to produce ore of good quality. The width of Clegg's Lode is about 1 foot, and that of Shaft Lode 4 feet. Again, at Brent, in South Devon, magnetic iron ore occurs near the river Avon, or Aunn, in shallow deposits on a mass of greenstone. Other deposits in lodes appear on Brent Hill, but the explorations here have been carried out on a very limited scale.

The earliest returns bearing on the production of iron ore in Devonshire appear to refer to the end of the last century, when between the years 1796 and 1802 iron ore amounting to 9,293 tons was shipped from the lodes at Coombe Martin to the iron-works at Llanelly, in South Wales.

Production of Iron Mines.—Since the year 1855 the production of the Devonshire iron mines has been as follows; the output of the mines of the adjoining county of Somerset is given side by side:—

| Year. | Devonshire. | Somersetshire. |
|-------|-------------|----------------|
| | Tons. | Tons. |
| 1855 | 1,500 | 4,840 |
| 1856 | 4,100 | 14,620 |
| 1857 | 2,000 | 25,842 |
| 1858 | 4,754 | 26,041 |
| 1859 | 3,598 | 29,083 |
| 1860 | 3,836 | 24,101 |
| 1861 | 5,399 | 32,763 |
| 1862 | 3,550 | 31,413 |
| 1863 | 7,014 | 34,709 |
| 1864 | 11,068 | 54,925 |
| 1865 | 37,814 | 37,984 |
| 1866 | 40,671 | 35,323 |
| 1867 | 10,212 | 36,874 |
| 1868 | 11,178 | 32,450 |
| 1869 | 7,104 | 27,230 |
| 1870 | 10,103 | 19,739 |
| 1871 | 14,124 | 32,883 |
| 1872 | 29,361 | 30,913 |
| 1873 | 31,455 | 46,532 |
| 1874 | 21,313 | 41,432 |
| 1875 | 10,594 | 45,168 |
| 1876 | 9,936 | 44,299 |
| 1877 | 6,434 | 51,928 |
| 1878 | 4,493 | 43,115 |
| 1879 | 592 | 14,100 |
| 1880 | 12,652 | 29,318 |

The value of the Devonshire iron ores about the years 1874 and 1875 was 15s. per ton, since that date it has been declining, till in 1879 it was but 10s. per ton.

The latest returns show not only increased production but better prices, the latter exceeding 15s. per ton. The mines selling ore in 1880, were as follows :—

| No. | District or Mine. | Character of Ore. | Quantities. | | Value. | |
|---------------------------|-------------------|--------------------|-------------|-------|--------|----|
| | | | Tons. | Cwts. | £ | s. |
| 1 | Bampfylde . . | Brown Hematite . . | 1,309 | 4 | 785 | 8 |
| 2 | Frank Mills . . | " " . . | 190 | 0 | 95 | 0 |
| 3 | Haytor . . . | Magnetic Oxide . . | 3,395 | 0 | 2,037 | 0 |
| 4 | Kelley . . . | Brown Hematite . . | 22 | 0 | 66 | 0 |
| 5 | Molland . . . | " " . . | 1,681 | 11 | 1,008 | 12 |
| 6 | New Florence . . | Red Hematite . . | 5,593 | 0 | 5,593 | 0 |
| 7 | Brixham . . . | " " . . | 362 | 0 | 279 | 0 |
| 8 | " . . . | " " . . | 100 | 0 | 75 | 0 |
| Total of Devonshire . . . | | | 12,652 | 15 | 9,939 | 0 |

Distribution of Devonshire Iron Ore.—It appears furnaces were erected some years ago by the Messrs. Sarl and Sons at Bovey Tracey for the reduction of the iron ores of that district; the furnaces, however, were never blown in, and the works have long since been abandoned and dismantled. The ore is exported to South Wales, and some quantities, though inconsiderable, are conveyed to the North of England. In the annexed table will be found the quantities shipped from the respective ports of Devon, together with the quantities carried by the South Devon Railway in each of the following years:—

| Year. | Brixham. | Teignmouth. | Dartmouth. | South Devon Railway. |
|-------|----------|-------------|------------|----------------------|
| | Tons. | Tons. | Tons. | Tons. |
| 1865 | 33,814 | 1,422 | ... | ... |
| 1866 | 18,867 | 1,742 | 1,000 | ... |
| 1867 | 8,829 | 590 | 250 | ... |
| 1868 | 3,563 | 345 | ... | ... |
| 1870 | 5,000 | 145 | ... | ... |
| 1871 | 11,000 | ... | 672 | ... |
| 1872 | 15,305 | 301 | 364 | ... |
| 1873 | 2,263 | 703 | ... | 824 |
| 1874 | 2,166 | 230 | ... | 5,678 |
| 1875 | 1,906 | 90 | ... | ... |
| 1876 | 1,603 | 290 | ... | 2,566 |
| 1877 | ... | 255 | ... | 1,725 |
| 1878 | ... | ... | ... | 811 |
| 1879 | ... | ... | ... | 202 |
| 1880 | ... | ... | ... | 3,277 |

The railway returns for the year 1874 give the respective quantities carried from the several stations of the South Devon Railway:—

RAILWAY DISTRIBUTION.

| STATIONS. | TONS. |
|------------------------------|--------------|
| From Shaugh Siding | 905 |
| Kingsbridge Road | 320 |
| Newton | 857 |
| Bovey | 3,535 |
| Buckfastleigh | 151 |
| Total | <u>5,768</u> |

In the following table will be found the names of the principal localities in Devonshire above referred to, with the situation

of the mines and the amount of metallic iron contained in the ore :—

| Mines or District. | Situation. | Character of Ore. | Iron per Cent. |
|--------------------|---------------------|----------------------|----------------|
| Haytor . . . | Ilminster . . . | Magnetic . . . | 57·01 |
| Hennock . . . | " . . . | Micaceous . . . | 55·00 |
| Florence . . . | North Molton . . . | Spathose . . . | 55·00 |
| Frank Mills . . . | Christow . . . | " . . . | 38·26 |
| Smallacombe . . . | Ilminster . . . | Brown Hematite . . . | 50·44 |
| Torbay . . . | Brixham . . . | " . . . | 66·57 |
| " . . . | " . . . | " . . . | 48·70 |
| " . . . | " . . . | " . . . | 44·56 |
| " . . . | " . . . | " . . . | 63·00 |
| Brixham . . . | " . . . | Red Hematite . . . | 62·50 |
| South Devon . . . | Buckfastleigh . . . | Micaceous . . . | 55·00 |

CHAPTER XX.

CORNWALL IRON INDUSTRIES.

Early references to Iron Ore Deposits—Borlase and Pryce—Restormel Iron Mine, account of—Analyses of Restormel and other Iron Ores raised in Cornwall—The Perran Iron lode—Production and Distribution of Iron Ore—Mines and Localities producing Ore—Distribution of Iron Ore.

Iron Ore Deposits.—This most western county of England has ever been famous for the great richness and variety of her mineral treasures. The ores of tin were wrought at a very early period, and in Cornwall and the adjoining county of Devon this important ore occurs disseminated through its rocks. Copper ore is also abundant, and but few minerals known to the miner are absent. The ores of iron are widely diffused, occurring principally in the form of lodes, and traversing large tracts of country. These deposits, though long known, have been but partially developed.

Borlase, writing about the year 1758, mentions the fact of iron ore being known to exist in many parts of the county, though not at that time worked. Later, in the year 1788, it appears from Pryce that these lodes of iron still remained unwrought.

The iron ore deposits of Cornwall, as above stated, occur principally in lodes; many of these are known to extend for several miles in a direct course. Generally these lodes have a direction a few degrees west of north, underlying about one foot in a fathom, and containing hematite of the red or brown variety, many of these lodes being in fact the cross courses of the respective districts in which they occur.

One of the most important deposits of iron ore in Cornwall is situated near Lostwithiel, in the Manor of Restormel, held under lease from the Duchy of Cornwall, at a royalty of 6*d.* per ton, and a minimum rent of £40 per annum. The sett is nearly a mile and three-quarters in extent from north to south, and is

traversed throughout nearly its entire length by a large and productive lode of hematite ore. The deposit was originally opened out by a Mr. Adam Thompson, and the property was subsequently acquired by the Messrs. John Taylor and Sons, and worked under the name of the Royal Restormel Iron Mine. Clay slate or killas is the rock of the district, dipping to the east; the lode has a direction north and south, dipping one foot in six, and consisting chiefly of iron ore, quartz, and floocan.

The mine has been extensively worked by means of day levels, while the ore wrought is brought out of the mine by the deep adit, over tramways drawn by horses, to the quays at Lostwithiel, where the ore is shipped in barges and carried to the port of Fowey, whence it is trans-shipped to the ironworks of South Wales and elsewhere. A notable feature in the mine is the new winning below the deep adit, recently opened out, and exposing a run of ore ground, estimated to yield 200,000 tons of ore. Here the plan for draining, working the mine, and dressing the ore, is efficient in all respects for working to a depth of 24 fathoms, and even more, below the adit. The engines are placed underground at the adit; one, a pumping engine, 24-inch diameter cylinder; a hauling engine, the cylinder 12 inches diameter; a double skip road has been made, and a 14-inch plunger fixed; a brick stack being carried up through a shaft to the top of the hill to meet the requirements of the engine and boiler houses constructed under ground at the adit.

The drainage of the mine is economically effected—indeed, there is very little water to get rid of; while the plan of working by a series of cross cuts from the main levels which are driven parallel to, and within a short distance of the lode, enables the rapid extension of the main works without interfering with the extraction of the ore. In the southern part of the sett there is a lode worked open-cast, but here little has hitherto been done.

The quality of the ore obtained from Restormel is now in some request for the manufacture of Bessemer pig. It consists principally of a crystallised brown hematite, or Goethite, occurring in fibrous and mammilated aggregations, and also in long prismatic crystals. In the upper levels crystals of carbonate of iron altered to brown hematite are met with, while the presence of manganese in these ores render them of value, and well adapted to the manufacture of steel and iron. The percentage of metallic iron

averages from 40 to 42 and 45. Recent analyses, however, of samples taken from the 12-fathom level give higher results.

The following are the results of five samples of ore made by Mr. John Pattinson, of Newcastle-upon-Tyne, for the present proprietors, the Restormel Iron Mining Company, Limited :—*

| Constituents. | No. 1. | No. 2. | No. 3. | No. 4. | No. 5. |
|-----------------------|--------|--------|--------|--------|--------|
| Peroxide of iron . . | 78·57 | 56·43 | 77·14 | 75·43 | 45·57 |
| „ of manganese . . | 4·71 | 22·60 | 3·15 | ·38 | 32·57 |
| Protoxide of „ . . | ... | 3·46 | ... | ... | 4·28 |
| Oxide of Cobalt „ . . | ... | ·13 | ... | ... | ·21 |
| Alumina | 1·00 | 3·42 | ·90 | 1·00 | 1·60 |
| Lime | trace | ·36 | trace | trace | trace |
| Baryta | ·35 | 2·58 | ·10 | trace | 3·77 |
| Magnesia | ·12 | ·12 | ·12 | ·19 | ·38 |
| Silica | 6·00 | 2·83 | 9·93 | 13·97 | 4·13 |
| Sulphur | trace | trace | trace | trace | trace |
| Phosphoric acid . . | ·06 | ·33 | ·16 | ·19 | ·40 |
| Combined water . . | 8·61 | 7·14 | 7·65 | 8·37 | 6·46 |
| Moisture | ·39 | ·48 | ·75 | ·26 | ·50 |
| | 99·81 | 99·88 | 99·90 | 99·79 | 99·87 |
| Metallic iron . . . | 55·00 | 39·50 | 54·00 | 52·80 | 31·90 |
| Metallic manganese . | 2·97 | 16·95 | 1·99 | ·24 | 23·87 |

It is remarked that the amount of silica in these samples is less than in others previously examined from higher levels, and that the ore contains manganese in important quantities. The bulk of the ore may not perhaps show such results as the above samples, but they nevertheless indicate the probability of the deeper workings yielding a more valuable ore than was obtained from the shallower levels.

The ore has also been examined by Mr. E. Riley, F.C.S., with the following results :—

TABULATED.

| | |
|--------------------------------|-------|
| Moisture at 212° Fahr. | 0·85 |
| Metallic iron | 46·42 |
| Metallic manganese | 3·98 |
| Siliceous matter | 18·21 |

Another sample of ore dried at 212° Fahr., giving 51·76 of metallic iron.

* Favoured by the Messrs. John Taylor and Sons, who also furnished the foregoing particulars of the Restormel Mine.

The returns of production of the Restormel Mine of brown hematite since the year 1855 are as follows :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1855 | 20,807 | 1867 | 1,005 |
| 1856 | 8,229 | 1868 | 608 |
| 1857 | 7,077 | 1869 | 1,089 |
| 1858 | 12,956 | 1871 | 3,964 |
| 1859 | 6,915 | 1872 | 7,521 |
| 1860 | 2,980 | 1873 | 4,609 |
| 1861 | 5,519 | 1874 | 1,087 |
| 1862 | 2,611 | 1875 | 3,510 |
| 1863 | 2,294 | 1876 | 4,120 |
| 1864 | 8,357 | 1877 | 1,056 |
| 1865 | 6,170 | 1878 | 344 |
| 1866 | 4,190 | 1880 | 1,724 |

The brown hematite hitherto worked in Cornwall occurs chiefly in a series of great fissures, which cross the centre of the county on a line nearly coincident with the magnetic meridian, from a point a few miles east of Saint Austell on the south, to the estuary of the Camel at Padstow on the north. On the line referred to, proceeding from south to north, hematite has been worked at the Ruby, Knightor, Treverbryn, Coldbruggen, Withiel, and Pawton Mines, and similar ore has been seen at Resugga, Rosevear Moor, Bilberry, Tresible, and other places. Of the mines referred to, the Ruby on the south, and Pawton on the north, have been hitherto the most extensively wrought, and have proved the most productive.

The Pawton Mine is situated about five miles from Padstow, and three from Wadebridge. The lode bears about 18° west of true north, and underlies to the east about 1 foot in a fathom. It occupies a distinct fissure in the killas; varies from about 1 to 30 feet in width, and averages from 6 to 8 feet. As is usually the case, smaller parallel lodes have been observed on either side of the main lode, but these have not been worked upon. The "Killas" * country is brownish-red, rather soft, and readily decomposes when exposed to the air; it dips gently to the north, so that the lode cuts through it nearly at right angles to its general cleavage, which sometimes coincides with its bedding. The mine so far has been but partially developed. The workings

* "Killas," or clay slate.

extend over a length of about 150 fathoms in all, but north of the engine shaft these are mostly inaccessible. In the upper part of the mine the ore is partially red hematite, but most of it is found to occur as brown hematite. In the stopes below the 22-fathom level, the ore consists occasionally of red hematite, intermixed with spathose carbonate. At all depths much of the ore has been of botryoidal form, and generally very free from silica, sulphur, and phosphorus. The workings have been carried down 33 fathoms. A cross course, about two feet wide, bearing nearly east and west, traverses the lode, and heaves it nearly two fathoms to the left, which is also towards the greater angle. Near the cross course the lode is more siliceous than elsewhere, but this adverse influence only extends to a few fathoms north and south of the intersection. The cross course itself consists chiefly of quartz, but near the lode contains some iron ore also.

The ore raised from the Pawton Mine, examined by Mr. J. H. Collins, F.G.S.,* exhibits the annexed results.

The first analysis consists of portions of ore taken from different parts of the lode, from which a fair average sample was selected :—

RESULTS TABULATED.

| | |
|--------------------------------------|---------------|
| Peroxide of iron | 93·00 |
| Carbonic acid and moisture | 2·50 |
| Silica, chiefly (quartz) | 3·60 |
| Sulphur | trace |
| Phosphorus | trace |
| Alumina and lime | 1·10 |
| Total | <u>100·20</u> |

Another sample, selected from ore obtained from the stopes below the 22-fathom level, shows the following results :—

RESULTS TABULATED.

| | |
|-----------------------------|-------------|
| Peroxide of iron | 65·0 |
| Carbonate of iron | 26·1 |
| Silica | 4·4 |
| Sulphur | 0·2 |
| Phosphorus | trace |
| Alumina | 1·8 |
| Manganese | 1·0 |
| Moisture | 1·2 |
| Total | <u>99·7</u> |

* Mr. Collins has most liberally placed at the author's disposal the foregoing facts, describing the Pawton and other mines.

It is remarked that the walls of the lode are tolerably regular, that they are not coated with either siliceous matter or "capel," the ore being frequently free from silica, even where it is in contact with the killas. In many parts small "horses" * of killas are enclosed in the ore, which nearly resemble the killas of the adjoining country, as might be supposed.

At Knightor, Treverbyn, and Resugga, the boundary line of which extends some 500 fathoms south, where it gains the Ruby Mine, some important hematite deposits have been proved, extending through the above-named mine sett, consisting of a main lode, and another to the east. These lodes produced ore in some quantities previous to the year 1873, since which date very little appears to have been done, although the ore there raised was of good quality.

The hematite iron ore raised at Knightor and Treverbyn, examined by Mr. Edmund G. Tosh, F.C.S., who remarks that these hematites are quite equal in purity and richness to the best of the district, the first sample being an aggregation of small "kidney ore," in every respect excellent, gives the following results :—

| Constituents. | East Lode. | West Lode. | New Lode. |
|-------------------------------|------------|------------|-----------|
| Ferrie oxide | 94·62 | 83·29 | 84·85 |
| Manganous oxide | 0·11 | 0·08 | trace |
| Alumina | 0·27 | 0·55 | 0·50 |
| Lime | 0·09 | 0·14 | 0·09 |
| Magnesia | 0·03 | 0·08 | 0·02 |
| Phosphoric acid | 0·018 | 0·025 | 0·021 |
| Sulphur | trace | 0·020 | trace |
| Siliceous matter | 3·39 | 14·46 | 11·79 |
| Water and carbonic acid . . . | 0·69 | 1·19 | 2·34 |
| | 99·218 | 99·835 | 99·611 |
| INSOLUBLE RESIDUE. | | | |
| Silica | 3·39 | 13·86 | 11·08 |
| Alumina | ... | 0·47 | 0·49 |
| | 3·39 | 14·33 | 11·57 |
| Metallic iron | 66·23 | 58·30 | 59·40 |

* A "Horse" in a lode, is a mass of rock in the middle of the vein of ore.

Other analyses of the Knightor and Treverbyn hematite, made by Mr. W. Crosby, of Middlesborough, and Mr. J. H. Collins, of Truro, give the following results; both are described as hematite ore, fair average samples being selected from several points in the above mines; the first containing 58·01, and the second 51·20 per cent. of metallic iron :—

RESULTS TABULATED.

| Constituents. | W. Crosby. | J. H. Collins. |
|--------------------------------------|------------|----------------|
| Peroxide of iron | 82·87 | 73·2 |
| Silica | 8·30 | 14·4 |
| Alumina | 4·30 | 4·9 |
| Lime | 1·24 | 1·6 |
| Oxide of manganese | 0·16 | 0·3 |
| Magnesia | 0·75 | 0·9 |
| Sulphur | trace | trace |
| Phosphoric acid | 0·03 | 0·4 |
| Moisture and carbonic acid | 2·06 | 3·4 |
| | 99·71 | 99·1 |

In the following table is given the production of Pawton in Lanivet and other mines above referred to since the year 1860:—

| PAWTON. | | KNIGHTOR AND RUBY. | | LADOCK.* | |
|---------|--------|--------------------|-------|----------|-------|
| Year. | Tons. | Year. | Tons. | Year. | Tons. |
| 1861 | 14,400 | 1862 | 2,000 | 1860 | 1,254 |
| 1862 | 9,876 | 1863 | 2,000 | 1862 | 762 |
| 1863 | 7,618 | 1864 | 7,925 | 1863 | 2,413 |
| 1864 | 7,848 | 1865 | 6,545 | 1864 | 1,177 |
| 1865 | 9,626 | 1866 | 7,951 | 1865 | 121 |
| 1873 | 1,000 | 1867 | 1,772 | 1872 | 844 |
| 1874 | 4,372 | 1868 | 5,937 | 1873 | 512 |
| 1876 | 4,625 | 1870 | 5,406 | 1874 | 250 |
| 1878 | 617 | 1871 | 9,154 | 1875 | 200 |
| 1880 | 810 | 1872 | 3,901 | | |

The Perran great iron lode is another, and the most, important deposit in Cornwall. Nearly fifty years ago it was referred to, in the "Geological Transactions," by Mr. Henwood, who says: "At the eastern extremity of Ligger Bay is a large vein bearing

* The lode at Ladock yields an ore of good quality of hard brown hematite from 10 to 12 feet wide, embedded in a very supporting light brown killas.

south-east, north-west, and dipping south 50° . It contains hematite, specular, and earthy-brown iron ore, quartz, and slate; has many cavities lined with crystals of quartz, and is traversed by many small quartz veins." * Sir Henry de la Beche wrote in 1839: "There can be little doubt that a large supply of good hematite iron ore could be readily obtained from the district" (of Cornwall and Devon) "if the necessary demand existed." †

Many of the iron lodes of Cornwall are known to extend for several miles in a direct line, and the depth to which the ore holds down is quite unknown. In many respects, however, the Perran lode differs from most of the others, especially in direction, size, underlie, and in the nature of its contents. The Cornish iron lodes have usually a direction a few degrees west of north; average perhaps 3 to 4 feet wide; underlie, about 1 foot in a fathom, and contain either red or brown hematite. On the other hand the Perran lode bears about 85° north of west; averages perhaps 30 feet in width for a course of several miles; underlies from 3 to 4 feet in a fathom, and contains in depth large quantities of carbonate of iron, or spathose iron ore.

The lode is seen on the northern coast of Cornwall at Perran Bay, where it attains a width of nearly 100 feet, consisting of two great branches, divided by a horse of killas or clay slate. The most productive part hitherto explored is that extending to Mount and Trebisken, a distance of some four miles from the coast. It has been traced to the neighbourhood of Grampond, but this latter portion of the lode has not been worked. The first workings were commenced by Mr. Samuel Hockaday, the ore being quarried near the cliff at the outcrop, drawn up over an incline and carted to Newquay, a distance of about six miles, where it was shipped to the ironworks of South Wales. Mr. Hockaday, above referred to, also opened the Mount Mine, about a mile and a-half inland on the same lode. From him it passed to the Saint Columb Bank, and when that failed, to the Agra and Mastermans' Bank. Very considerable workings were made on the lode at the Great Retallack and Duchy Peru mines, which is now worked for zinc. From the extent of the excavations it is probable that not much less than 100,000 tons of iron ore have been removed from this part of the lode.

* "Transactions of the Royal Geological Society of Cornwall," vol. v.

† "Geological Report on Cornwall, Devon, and West Somerset," p. 618.

Previous to the year 1865 a contract was entered into between the manager of the Dowlais Iron Company, and Mr. Carter, of Saint Columb, for the supply of 40,000 tons of the ore. The contract was fulfilled, but the difficulties of transport prevented a renewal of the contract, which was much to be regretted, as the ore gave satisfactory results in reduction to the metallic state. About the year 1874 this lode was vigorously worked by the Cornish Consolidated Iron Mines Corporation; the principal workings are at Gravel Hill, the Mount Mine; still farther east the great excavations at Treamble are situated; a branch of the Newquay Railway leading to the quarries. The Great Retallack Mine adjoins to the north and east; here, in working the iron lode, some 60 or 70 tons of silver lead ore were obtained, the ore containing from 15 to 30 ozs. of silver per ton.

At Great Retallack the lode is found to be several fathoms wide; at one point the workings are down a depth of 40 fathoms, where it was found to be rich for iron, with a little blende for the first 25 fathoms, but at a greater depth the blende increased, and for several months upwards of 500 tons per month were raised and sold at a very low price. The next workings on the lode to the east of Great Retallack are those of the Duchy Peru Mine and Deer Park, where extensive excavations mark the position of the Great Perran iron lode. At the Duchy Peru Mine the old workings on the lead and copper lodes were carried to a depth of 50 fathoms on the iron lode, where white spathose iron ore was met with; here the celebrated Peru lode comes in contact with the great iron lode.

Cellular brown hematite also occurs, and has been raised in some quantity on the western boundary of the Duchy sett. The ore here contains several ounces of silver to the ton, but not sufficient to pay for extraction. Much of the ore contains large "Vugs."* Many of these contain a loosely-fitting kernel of white carbonate of iron. The space between the kernel and the enclosed shell is often filled with water, which is quite clear and tasteless.

The "Killas" country about the great lode at the Duchy Peru Mine seems to be much disturbed; south of the lode it is hard,

* "Vug" or "Vugh." In mining, a cavity, a hollow in the rock or lode.

and appears to dip towards it, but next the lode it is soft, and dips with it; and it is stated that the great bunches of ore in the Perran lode appear to occur where it is crossed by the numerous north and south lead lodes of the district.

Recent analyses of the spathose ores raised at the Duchy Peru and Mount Mines, give the following results. The two first analyses are, from fair average samples, of several thousand tons, while that of Mount Mine was from a stone taken promiscuously from a heap, and weighing about 14 lbs. The three analyses were made by Mr. J. H. Collins, of Truro :—

RESULTS TABULATED.

| Constituents. | 1. | 2. |
|---------------------------------------|--------|--------|
| Protoxide of iron | 48·00 | 46·27 |
| Protoxide of manganese | 6·80 | 5·97 |
| Lime | ·63 | 1·37 |
| Magnesia | 2·32 | 1·88 |
| Sulphur | ·43 | ·28 |
| Phosphoric acid | ·10 | trace |
| Insoluble | 3·60 | 3·40 |
| Moisture, alumina, and loss | 1·52 | 4·25 |
| Carbonic acid | 36·60 | 36·58 |
| | 100·00 | 100·00 |

The spathose ore raised at Mount Mine gave the following results on examination :—

RESULTS TABULATED.

| | |
|----------------------------------|--------|
| Carbonate of iron | 79·00 |
| Carbonate of manganese | 9·10 |
| Carbonate of lime | 4·90 |
| Carbonate of magnesia | 5·20 |
| Sulphur | 0·20 |
| Phosphorus | trace |
| Silica moisture } | 2·00 |
| Alumina and loss } | |
| Total | 100·40 |

Beyond Deer Park the outcrop of the lode is seen on Penhallow Moor, where trials only have been made.

Of the iron ore raised from the several workings on the Perran lode the annexed analyses fairly show their composition; the first two from Gravel Hill, by Mr. J. H. Collins; the third and fourth by Mr. John Mitchell, locality not stated :—

| Constituents. | Gravel Hill. | Gravel Hill. | Perran Ore. | Perran Ore. |
|---------------------------|--------------|--------------|-------------|-------------|
| Peroxide of iron . . . | 68·30 | 70·82 | 91·428 | ... |
| Protoxide of iron . . . | ... | ... | trace | 48·625 |
| Oxide of manganese . . . | ·11 | ·98 | ·174 | trace |
| Lime | ... | ... | ·110 | trace |
| Magnesia | ... | ... | ·129 | ... |
| Potash | ... | ... | ·076 | ... |
| Soda | ... | ... | ·054 | ... |
| Silica | 11·41 | 11·40 | 1·140 | 13·750 |
| Alumina | 1·34 | 2·07 | ... | 6·250 |
| Carbonic acid | ... | ... | ... | 29·362 |
| Phosphoric acid | 1·21 | 1·84 | ·072 | ... |
| Sulphuric acid | ... | 1·12 | ·013 | 1·255 |
| Water and loss | 15·32 | 11·40 | 6·804 | ·758 |
| | 97·69 | 99·63 | 100·000 | 100·000 |

The equivalent of metallic iron in the Gravel Hill ore amounts to 53 per cent., and of the brown and spathose ore of Perran 64 and 98 per cent. respectively, while as regards the last ore it was found to contain 8 ozs. 3 dwts. and 8 grains of silver per ton.

The ore raised at Treamble Mine, of three varieties of fair average samples, show the annexed constituents. The first analysis is by Dr. Noad, the second by Mr. Collins, and the third by the Wigan Coal and Iron Company:—

| Constituents. | Brown Hematite. | Kidney Ore. | White Spathose. |
|---------------------------------|-----------------|-------------|-----------------|
| Silica | 4·20 | 10·00 | 1·74 |
| Peroxide of iron | 69·10 | 78·10 | ... |
| Peroxide of manganese | 14·00 | trace | 8·13 |
| Protoxide of iron | ... | ... | 51·61 |
| Lime | ·80 | trace | 1·51 |
| Magnesia | ... | ... | ·36 |
| Alumina | ... | trace | ... |
| Sulphuric acid | ·24 | ... | ·15 |
| Phosphoric acid | ... | 1·44 | trace |
| Carbonic acid | ... | ... | 35·55 |
| Water | 11·60 | 10·00 | ... |
| | 99·94 | 99·54 | 99·05 |
| Metallic iron | 66·23 | ... | ... |

The production of the several mines on the Perran lode above referred to are given as follows, and this important deposit can furnish considerable quantities of ore to the ironmaster whenever circumstances may arise causing increased demand:—

| DUCHEY PERU. | | TREBISKEN AND MOUNT. | | TREMBLE. | |
|--------------|-------|----------------------|-------|------------------|--------|
| Year. | Tons. | Year. | Tons. | Year. | Tons. |
| 1858 | 2,762 | 1859 | 4,338 | 1859 | 2,391 |
| 1859 | 1,995 | 1860 | 2,641 | 1860 | 1,312 |
| 1860 | 4,895 | 1861 | 1,860 | 1864 | 222 |
| 1862 | 169 | 1864 | 2,876 | 1873 | 426 |
| 1863 | 3,950 | 1865 | 6,193 | 1874 | 9,438 |
| 1864 | 2,366 | 1866 | 1,234 | 1875 | 958 |
| 1865 | 3,539 | 1871 | 2,785 | 1876 | 426 |
| 1866 | 150 | 1872 | 8,293 | 1880 | 2,728* |
| 1872 | 50 | 1873 | 4,706 | GREAT RETALLACK. | |
| 1873 | 528 | 1874 | 2,545 | | |
| 1874 | 2,566 | 1875 | 374 | Year. | Tons. |
| 1875 | 412 | 1876 | 517 | 1858 | 4,017 |
| 1876 | 1,121 | 1877 | 283 | 1859 | 6,609 |
| 1878 | 17 | 1880 | 379 | | |
| 1880 | 3,238 | | | | |

At Gravel Hill 2,505 tons of iron ore were raised in the year 1874, and 494 tons in 1875. Again, in 1876 about the same quantity, increased in 1880 to 2,652 tons.

West of Bodmin, and distant some three miles at Boscarne, occurs a lode partly wrought; this lode has a run of some 750 fathoms, worked to a depth of 20 fathoms, with an average width of 1 fathom. Other lodes, known as the Nantallon lodes, occur south of Boscarne; these are three in number, running with little variation north and south, with a slight underlie. Two of the lodes have a range of nearly 1,750 fathoms, while the third has a range of 2,200 fathoms. The average depth to which these lodes have been worked does not exceed 20 fathoms, while in width one is 3 feet, and the remaining two are each 6 feet or 1 fathom in width. The ore wrought at Nantallon is of the variety known as "fibrous kidney ore," the iron existing in the form of hydrated peroxide.

At Tregorne, to the west of Mulberry Hill, hematite, of an irregular structure and associated with quartz, has been wrought, occurring as anhydrous peroxide, the lode having a range of some 500 fathoms, 30 fathoms in depth, and with an average width of 3 feet. Other lodes occur to the west and south of Bodmin; at Tremoor two lodes, extending some 2,000 yards, 15 fathoms deep, and with an average width of 3 feet; again, at Withiel, Retire,

* Perran Mines, including Treample and others.

Coldvreath, and Trerank. The Coldvreath lodes have formerly been worked to some extent, their direction extending 800 fathoms north and south, 16 fathoms in depth, and having an average width exceeding 1 fathom. The ore raised at Coldvreath is known as compact hematite, a small portion being distinguished as "kidney ore."

Many other localities in Cornwall are known to yield iron ore of good quality; in the district of Constantine, to the east of Falmouth, a lode of iron ore, wrought in recent years, varying from 6 feet to 6 inches in width, has produced ore in notable quantity. In the district of Saint Columb lodes occur, one worked at the Ruthers Mine. Again, we have those of Indian Queens and Trelivier, near Saint Austell; the former was opened out about the year 1866, and continued in operation nearly ten years.

The ores raised in the neighbourhood of Saint Austell, near Grampound, at the Kernick and Bodennick mines, is a brown hematite, the thickness of the lode at the former varying from 27 to 31 feet, and the latter having an average of 13 feet 6 inches; these have been partially wrought. The ores, examined by Dr. Noad and Dr. Perkins, are described as compact brown hematite, intermixed with spar at the outcrop, but comparatively free from it about 14 feet below; they contain by analysis from 76 to 80 per cent. of peroxide of iron, some oxide of manganese, no sulphur, and a small admixture of phosphoric acid. The following are the results:—

| Constituents. | Dr. Noad. | Dr. Noad. | Dr. Perkins. |
|---------------------------|-----------|-----------|--------------|
| Peroxide of iron | 76·00 | 79·56 | 80·20 |
| Oxide of manganese . . . | 3·20 | 1·20 | 2·01 |
| Lime | 1·00 | 1·20 | ·14* |
| Magnesia | ... | ·53 | ... |
| Sulphur | ... | ... | ... |
| Phosphoric acid | ·30 | ·28 | ·09 |
| Silicate of alumina . . . | 10·00 | 7·20 | 15·50† |
| Water | 9·50 | 10·00 | 2·06 |
| | 100·00 | 99·97 | 100·00 |

The equivalent of metallic iron contained in the peroxide being respectively 53·2 per cent., 55·6 per cent., and 56·17 per cent.

* Lime and alumina.

† Silica.

At South Terras, near Grampound Road, a magnetic ore of iron is wrought, giving on examination the following results :—

RESULTS TABULATED.

| | |
|--------------------------------------|---------------|
| Magnetic oxide of iron | 84·24 |
| Peroxide of iron | 3·84 |
| Magnesia | trace |
| Lime | trace |
| Phosphoric acid | trace |
| Sulphur and sulphuric acid | trace |
| Lead | faint trace |
| Oxide of magnesia | 1·06 |
| Alumina | 1·35 |
| Silica of gangue | 7·51 |
| Water | 2·00 |
| Total | <u>100·00</u> |

Production of Iron Ore.—The produce of a few of the more important iron mines has already been given; in the table below appears the total output of the mines of Cornwall in each year since 1855 :—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1855 | 24,057 | 1867 | 6,426 |
| 1856 | 22,650 | 1868 | 8,310 |
| 1857 | 19,359 | 1869 | 4,619 |
| 1858 | 55,150 | 1870 | 11,214 |
| 1859 | 35,213 | 1871 | 21,947 |
| 1860 | 23,953 | 1872 | 48,199 |
| 1861 | 26,262 | 1873 | 31,455 |
| 1862 | 24,626 | 1874 | 45,055 |
| 1863 | 18,975 | 1875 | 11,403 |
| 1864 | 34,210 | 1876 | 18,390 |
| 1865 | 36,112 | 1877 | 4,963 |
| 1866 | 18,683 | 1878 | 1,308 |

In the year 1874, when the Cornish ores were in good demand, the following will show the value per ton :—Gravel Hill, Tremble, and the Duchy Peru, 15s. 6d.; Pawton, 16s.; Ladock, 17s.; Coldvreath ore, 17s. 6d.; and Blackhay, 16s. per ton. In the year 1879 the last-named mine was the only one in Cornwall working; it produced but 400 tons, of the value of £240, giving an average value of 12s. per ton. In 1880 greater activity appears, the total output amounting to 15,865 tons, of the value of

£9,845, giving an average of 12s. per ton. The produce and value of the iron ores raised were as follows in the year 1880 :—

| No. | District or Mine. | Character of Ore. | Quantities. | | Value. | |
|-----------------------|-------------------|-------------------|-------------|-------|--------|----|
| | | | Tons. | Cwts. | £ | s. |
| 1 | Blackhay . . | Brown Hematite . | 950 | 0 | 570 | 0 |
| 2 | Duchy Peru . . | " " | 3,238 | 0 | 1,942 | 16 |
| 3 | Gravel Hill . . | " " | 2,652 | 0 | 1,856 | 8 |
| 4 | Lanivet . . | " " | 810 | 0 | 486 | 0 |
| 5 | Restormel . . | " " | 1,724 | 17 | 1,120 | 12 |
| 6 | Ruthers . . | Red Hematite . | 134 | 10 | 94 | 2 |
| 7 | Mount . . | Spathose . | 269 | 16 | 134 | 18 |
| 8 | Mount . . | Brown Hematite . | 110 | 0 | 55 | 0 |
| 9 | South Terras . . | " " | 3,000 | 0 | 1,800 | 0 |
| 10 | Retew . . | " " | 248 | 0 | 148 | 16 |
| 11 | Perran Mines . . | " " | 2,728 | 0 | 1,636 | 16 |
| Total of Cornwall . . | | | 15,865 | 3 | 9,845 | 8 |

The principal iron mines in Cornwall, their situation, with the character of the ore raised, appear in the following table :—

| Iron Mines. | Localities. | Character of Ore. |
|----------------------------|-----------------|------------------------|
| Blackhay | Withiel . . | Brown Hematite. |
| Colbiggen | Roche . . | " " |
| Coldvreath | St. Austell . . | " " |
| Constantine | Constantine . . | " " |
| Dear Park | Perran . . | " " |
| Duchy Peru | " . . | Spathose and Hematite. |
| Gravel Hill | " . . | " " |
| Granville East Wheal . . | Camborne . . | " " |
| Knightor and Treverbyn . . | St. Austell . . | Brown Hematite. |
| Ladock | Ladock . . | " " |
| Lanivet | Lanivet . . | " " |
| Mount and Trebiskin . . | Perran . . | Spathose and Hematite. |
| Old Treburgett | St. Teath . . | " " |
| Mills, New | Ladock . . | Brown Hematite. |
| Pawton | St. Breocks . . | " " |
| Restinnis | St. Blazey . . | " " |
| Restormel | Lostwithiel . . | " " |
| Ruby and Tregurthy . . | St. Austell . . | " " |
| St. Stephens | " . . | " " |
| South Terras | Grampound . . | " " |
| Treamble | Perran . . | Spathose and Hematite. |
| Trebarvah | " . . | Brown Hematite. |
| Tretoil | Bodmin . . | " " |

Distribution of Ore.—The iron ores of Cornwall, in times of commercial activity, are in good demand for the economical

production of iron, either when used alone or in admixture with poorer ores. These ores find a market in Mid-England and the Northern iron-making districts. The principal shipping ports on the north coast are Padstow, New Quay, Saint Agnes; and on the south coast, Truro, Fowey, and Charlestown. As far as returns are obtainable the table below gives the quantities shipped in each year since 1859 from the ports named :—

| PADSTOW. | | NEW QUAY. | |
|----------|-------|--------------|-------|
| Year. | Tons. | Year. | Tons. |
| 1859 | 8,806 | 1865 | 4,000 |
| 1861 | 8,209 | 1866 | 1,602 |
| 1864 | 7,618 | 1868 | 2,164 |
| 1865 | 9,626 | 1879 | 100 |
| 1866 | 4,350 | 1880 | 5,860 |
| 1867 | 468 | ST. AGNES. | |
| 1868 | 1,256 | | |
| 1869 | 1,200 | ST. AGNES. | |
| 1870 | 933 | | |
| 1871 | 2,132 | Year. | Tons. |
| 1872 | 6,132 | 1865 | 4,400 |
| 1873 | 6,486 | 1866 | 1,974 |
| 1874 | 6,406 | 1871 | 526 |
| 1875 | 2,089 | 1872 | 2,234 |
| 1876 | 4,605 | 1873 | 2,027 |
| 1877 | 443 | 1874 | 118 |
| 1878 | 617 | 1875 | 196 |
| 1879 | 75 | CHARLESTOWN. | |
| 1880 | 810 | | |
| TRURO. | | CHARLESTOWN. | |
| Year. | Tons. | Year. | Tons. |
| 1865 | 1,700 | 1876 | 1,779 |
| 1866 | 2,637 | 1877 | 662 |
| 1871 | 3,500 | 1878 | 225 |
| 1872 | 7,200 | 1879 | 152 |

The Cornwall and South Devon Railway has also distributed some of the Cornish iron ore as follows in each of the years given :—

| Year. | Tons. | Year. | Tons. |
|-------|-------|-------|-------|
| 1876 | 2,566 | 1878 | 811 |
| 1877 | 1,725 | 1879 | 202 |

And in the year 1880 some 3,277 tons. The quantities given are comparatively unimportant, but they serve generally to show the depressed condition of the iron industries of Cornwall at the present time. On the other hand, Cornwall, whenever the demand may arise, may probably supplement the resources of our iron-making districts by the development of her ferruginous deposits, and expand an important industry in the interest of that western county.

CHAPTER XXI.

IRON INDUSTRIES OF SCOTLAND.

Iron Ores of the Coal Measures—Clay Bands and Black Bands—Discovery of Black Band Iron Ore by Mushet, in 1801—Analyses and Production of Clay and Black Band and other Iron Ores—Population employed in Iron Mining—Pig Iron Manufacture—Early History, 1750—Charcoal Iron—Carron Works—Smeaton's blowing machinery—Account of Devon Iron Works, 1782—Hot Blast, invention by Neilson, 1829—Extension of Iron Works and their resources—Production of Pig Iron—Works in 1880—Distribution and average prices of Pig Iron—Exports and Home Consumption—Malleable Iron Works—Account of Dalziel Steel Works—Production of Malleable Iron and prices—Coal and Iron Ore used in Pig Iron Manufacture—Iron Shipbuilding.

Ironstone of the Coal-fields and Analyses.—The principal ironstone measures have been already referred to in the several sections given in the coal-fields of Scotland. A brief notice of the black band ironstone, which has so largely contributed to the development of the iron industries of Scotland, will here be interesting. It was originally discovered by Mr. Robert Mushet in the year 1801, at Airdrie, near Glasgow, in Lanarkshire, but it does not appear to have come into general use till about the year 1830. The Possil black bands were discovered in the year 1838, and have an average thickness of 9 inches. Subsequently in the year 1840, black band ironstones were discovered in Ayrshire, giving rise to the important ironworks of Blair and Glengarnock; and some years later it was found extending from Dalry, in Ayrshire to Banton, in Stirlingshire, and more recently at Lugar and Dalmellington, in Ayrshire; at Forth, Lochgelly and Lumphinans, in Fifeshire; at Borrowstoness and Almond in Stirlingshire, and in other places.

A very important seam of ironstone was discovered a year or two since, 24 inches thick, on the lands of the Carron Iron Company, near Eastgrange, Culross; the same seam was long known and worked to the east of the locality above referred to, and a search was instituted for its discovery. Boring operations were carried on for several months, and at a depth of 140 fathoms the

efforts of the borers were rewarded by cutting this valuable seam. It is related that some years previously similar operations were conducted by the Shotts Iron Company on the same estate, the borings being carried to a depth of 100 fathoms, but not meeting with the seam the company relinquished the lease.

Brown Iron Ore.—Ores of iron occur and are worked in some few localities in various parts of Scotland, but to a very limited extent, due in most cases to the remote districts, the want of cheap carriage to the ironworks, and the necessary fuel for their reduction. In Ayrshire, hitherto, hematite has been worked at Muirkirk and at Whytock; in Haddingtonshire at Garleton, and in Shetland at Sandlodge; also in the northern counties of Aberdeen and Moray, and in Kirkcudbrightshire at Auchencairn. The great bulk of the hematite employed in the blast furnaces of Scotland is imported from the west coast of Lancashire and Cumberland, from Spain and other foreign countries.

The iron ores most generally employed in the furnaces of Scotland are black bands and clay bands, and a certain admixture of brown iron ores previously referred to. Black band ironstone may be described as a compact, dull, earthy mineral, with frequently a schistose or ribbon structure, varying in colour from deep brown to black. Some varieties contain little but carbonate of iron and carbonaceous or bituminous matter, silica, alumina, lime and manganese entering into their constituents in a very minute proportion. The carbonaceous matter contained in these black bands is generally sufficient to effect their calcination without the aid of additional fuel. They are very valuable ores, easily and cheaply calcined in heaps in the open air, the residue yielding from 50 to 70 per cent. of metallic iron.

Mushet's black band is thus constituted, as determined by the analysis of Dr. Colquhoun, who devoted considerable attention to the iron ores of Scotland:—

RESULTS TABULATED.

| | |
|-----------------------------|---------------|
| Carbonic acid | 35·17 |
| Protoxide of iron | 53·03 |
| Lime | 3·33 |
| Magnesia | 1·77 |
| Silica | 1·40 |
| Alumina | 0·63 |
| Peroxide of iron | 0·23 |
| Bituminous matter | 3·03 |
| Water | 1·41 |
| Total | <u>100·00</u> |

The amount of metallic iron being equivalent to 40 per cent.

The wide variation in the produce of various measures of black band ironstones appear in the annexed table of analyses :—

TABULATED RESULTS OF SCOTCH BLACK BAND IRONSTONES.

| Constituents. | 1. | 2. | 3. | 4. | 5. | 6. |
|---|--------|--------|--------|--------|--------|--------|
| Carbonic acid | 32·71 | 32·61 | 22·87 | 33·08 | 30·74 | 30·95 |
| Protoxide of iron | 47·31 | 42·02 | 32·14 | 41·65 | 44·19 | 45·78 |
| Lime | 1·79 | 3·65 | 2·82 | 5·78 | 2·22 | 1·79 |
| Magnesia | 1·73 | 3·54 | 1·08 | 3·62 | 0·91 | 1·30 |
| Silica | 1·20 | 4·40 | 12·40 | 0·52 | 2·12 | 1·60 |
| Alumina | 0·80 | 2·64 | 7·06 | 0·96 | 0·92 | 1·28 |
| Protoxide of manganese | 1·67 | 0·82 | 1·05 | .. | 1·93 | 1·12 |
| Bituminous matter | 10·40 | 9·12 | 18·60 | 11·16 | 15·52 | 7·85 |
| Phosphoric acid | 0·59 | 0·46 | 0·82 | 0·84 | 0·43 | 0·55 |
| Sulphur | .. | .. | 0·22 | 0·25 | 0·22 | 3·28 |
| Iron combined with sulphur | .. | .. | 0·19 | 0·22 | 0·19 | 2·87 |
| Water | 1·80 | 0·74 | 0·75 | 2·04 | 0·61 | 1·63 |
| Total | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 |
| Metallic iron | 36·80 | 32·68 | 25·19 | 32·62 | 34·56 | 38·47 |
| Yield of calcined ore | .. | .. | 61·28 | 58·20 | 56·41 | 60·85 |
| Metallic iron in calcined ore | .. | .. | 41·10 | 56·04 | 61·27 | 63·22 |
| Silica in calcined ore | .. | .. | 20·24 | 0·90 | 3·76 | 2·63 |

Analyses 3 to 6 were made by Mr. John Saint Day, C.E., who in a paper read at the Glasgow meeting of the British Association in the year 1876, entered very fully into the iron and steel industries of Scotland. Other analyses from Mr. Day's paper, may be summarized as follows, showing the amount of metallic iron contained in various black band ironstones, and other results :—

BLACK BAND IRONSTONES.

| | 1. | 2. | 3. | Slaty Band. | |
|----------------------------------|-------|-------|-------|-------------|-------|
| Yield of metallic iron | 36·36 | 32·68 | 36·80 | 31·54 | 31·51 |
| Yield of calcined ore | 63·60 | 62·26 | 60·48 | 59·64 | 52·85 |
| Metallic iron in ore | 57·16 | 52·50 | 60·85 | 52·88 | 59·61 |
| Silica in ore | 5·41 | 7·06 | 1·98 | 11·94 | 3·60 |

Taking the average yield of metallic iron, the black band ironstones of Scotland do not exceed 35 per cent. These ores, when calcined, yield from 50 to 70 per cent. of metallic iron, the average may be taken as 60 per cent.; those of other districts vary considerably. The next most important measures of black

band in Great Britain are those obtained in the North Staffordshire coal-field; reduced in the furnace without admixture with other ores. Like the Scotch black bands, they make a very good quality of iron, are extensively raised and calcined, and in this state sent into the South Staffordshire districts, for the most part wanting in black band ores.

The argillaceous or clay band ironstones, like the black bands, vary considerably. Numerous analyses are available showing the composition of these ores, the series, however, made by Mr. Day, in his paper previously referred to, are so complete, that they have been selected for illustration: *—

TABULATED RESULTS OF SCOTCH CLAY BAND IRONSTONES.

| Constituents. | 1. | 2. | 3. | 4. | 5. | 6. | 7. |
|---------------------------------|--------|--------|--------|--------|--------|--------|--------|
| Protoxide of iron | 47·91 | 39·80 | 34·98 | 37·23 | 32·20 | 24·90 | 37·54 |
| Protoxide of manganese | trace | 1·52 | 0·82 | 1·96 | 1·64 | 1·22 | 3·60 |
| Lime | 0·97 | 1·79 | 1·66 | 5·17 | 5·74 | 16·55 | 6·50 |
| Magnesia | 0·61 | 3·96 | 2·08 | 4·17 | 4·08 | 7·54 | 0·43 |
| Carbonic acid | 30·22 | 30·31 | 25·46 | 32·21 | 29·30 | 35·61 | 28·94 |
| Phosphoric acid | 0·49 | 0·64 | 0·50 | 0·45 | 0·60 | 1·76 | 1·92 |
| Sulphur | trace | 0·08 | 0·11 | 0·28 | 0·51 | 0·31 | 0·27 |
| Iron combined with sulphur . . | .. | 0·07 | 0·10 | 0·25 | 0·45 | 0·27 | 0·24 |
| Alumina | 7·10 | 7·93 | 11·66 | 5·12 | 6·55 | 3·27 | 6·23 |
| Silica | 10·12 | 11·80 | 17·80 | 10·44 | 14·60 | 6·80 | 11·30 |
| Bituminous matter | 2·32 | 1·55 | 4·17 | 1·75 | 2·84 | 0·73 | 2·03 |
| Water | 0·56 | 0·75 | 0·66 | 0·97 | 1·19 | 0·52 | 1·10 |
| Total | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 |
| Metallic iron | 36·80 | 30·87 | 27·30 | 29·21 | 25·49 | 19·63 | 29·41 |
| Yield of calcined ore | 72·16 | 70·39 | 72·28 | 67·80 | 68·53 | 64·77 | 70·94 |
| Metallic iron in ore | 51·00 | 43·84 | 37·77 | 43·05 | 37·19 | 30·38 | 41·50 |
| Silica in ore | 14·03 | 16·77 | 24·62 | 15·40 | 21·30 | 10·50 | 15·77 |

The average yield of metallic iron from the argillaceous ores of Scotland may be regarded as about 30 per cent., and when calcined about 70 per cent., compared with the black bands which, as already stated, give an average of 35 per cent. of metallic iron in the raw state and 60 per cent. when calcined.

The hematite obtained at Auchencairn, in Kirkcudbrightshire, is very similar in character to the kidney ore of Whitehaven, in Cumberland, and like another variety known as "small kidney ore," obtained in the same locality, yields a high percentage of metallic iron. Analyses of the two varieties by Mr. Robert Mushet, are as follows:—

* "Iron," 30th September, 1876.

| Constituents. | Large Kidney Ore. | Small Kidney Ore. |
|----------------------------|----------------------|----------------------|
| Peroxide of iron | 88.00 | 98.43 |
| Silica | 11.53 | 1.57 |
| Alumina | 0.47 | trace |
| Total | 100.00 | 100.00 |

The small kidney ore may be regarded as a pure peroxide of iron, yielding 68.91 per cent. of metallic iron; the large kidney ore giving 61.60 per cent.

In one locality at Auchencairn the hematite exhibits two varieties of ore, known as "Black Metal Kidney Ore" and "Red Ore," the former a compact oxide of iron, yielding 55.63 per cent. of metallic iron, the red ore ranging from 44 to 63 per cent., and a mixture of the two varieties giving 51.79 per cent. of metallic iron. The annexed analyses show the composition of both varieties:—

| Constituents. | Black Metal. | Black Metal and Red Ore. |
|----------------------------|--------------|-----------------------------|
| Peroxide of iron | 79.46 | 73.98 |
| Silica | 14.07 | 17.45 |
| Alumina | 1.36 | 1.04 |
| Moisture | 5.11 | 4.31 |
| Magnesia | ... | 3.22 |
| Total | 100.00 | 100.00 |

A detailed analysis of the variety known as "Red Ore" of Auchencairn gives the following tabulated results:—

ANALYSIS OF "RED ORE."

| | |
|------------------------------|---------------|
| Peroxide of iron | 63.00 |
| Oxide of manganese | 0.72 |
| Lime | 1.74 |
| Magnesia | 1.33 |
| Carbonic acid | 2.42 |
| Phosphoric acid | trace |
| Alumina | 4.09 |
| Silica | 23.20 |
| Water | 3.50 |
| Total | <u>100.00</u> |

The equivalent of metallic iron in the above peroxide amounts to 44·10 per cent.

The hematite occurring at Sandlodge, in Shetland, contains upwards of 70 per cent. of metallic iron and a small percentage of copper. Another variety, known as "Gossan," rich in iron, containing 60 per cent., in addition to 3 per cent. of copper; this last variety is extensively used for purifying gas.

Production of Ironstone in Scotland.—The earliest information on this subject begins with the year 1855, when the Keeper of Mining Records for the first time ascertained that the production of all kinds of ironstone, clay band, black band and hematite raised in Scotland amounted to 2,400,000 tons, the production of Great Britain in the same year amounting to 9,953,741 tons; it thus appears that in the year referred to, Scotland produced nearly 25 per cent. of all the ironstone and ore raised in the kingdom. Since the year 1855 the ironstone production of Scotland appears as follows, so far as returns have been received :—

| Year. | Tons. | Year. | Tons. |
|-------|-----------|-------|-----------|
| 1855 | 2,400,000 | 1868 | 1,250,000 |
| 1856 | 2,201,250 | 1869 | 1,950,000 |
| 1857 | 2,500,000 | 1870 | 1,980,000 |
| 1858 | 2,312,000 | 1871 | 1,975,000 |
| 1859 | 2,225,000 | 1872 | 1,978,000 |
| 1860 | 2,150,000 | 1873 | 1,986,000 |
| 1861 | 1,975,000 | 1874 | 2,119,771 |
| 1862 | 1,500,000 | 1875 | 2,452,235 |
| 1863 | 1,500,000 | 1876 | 2,552,553 |
| 1864 | 1,950,000 | 1877 | 2,621,852 |
| 1865 | 1,470,000 | 1878 | 2,443,923 |
| 1866 | 1,587,000 | 1879 | 2,458,407 |
| 1867 | 1,264,800 | 1880 | 2,659,317 |

The reports of H.M. Inspectors acting under "The Coal Mines Regulation Act," show that in the year 1874 the production of ironstone in Scotland was 2,119,771 tons, compared with 2,659,317 tons in the year 1880; of this quantity 1,435,647 tons were black band, and 1,223,670 tons clay band. The annexed statement gives the production of each shire in the eastern district of Scotland in the same years as follows; the western district giving 1,418,698 tons and 1,887,274 tons respectively :—

| Counties. | 1874. | 1880. |
|---|------------------|------------------|
| <i>Eastern Scotland—</i> | <i>Tons.</i> | <i>Tons.</i> |
| Clackmannan, Perth, Kinross and Sutherland. } | 7,890 | ... |
| Edinburgh | 39,661 | 101,619 |
| Fife | 59,272 | 652 |
| Haddington | 8,601 | 458 |
| Lanark, part of | 342,224 | 510,342 |
| Linlithgow | 238,605 | 148,423 |
| Stirling, part of | 4,820 | 10,549 |
| Total | 701,073 | 772,043 |
| <i>Western Scotland</i> | <i>1,418,698</i> | <i>1,887,274</i> |
| Total of Scotland | 2,119,771 | 2,659,317 |

In the year 1874 the total production of all kinds of iron ore in the United Kingdom amounted to 14,844,936 tons; the estimated value at the place of production being £7,313,146; ten years previously, in the year 1864, the iron ore raised in the United Kingdom amounted to 10,064,890 tons, of the value of £3,867,144, while in the year 1880 the production reached 18,026,049 tons, of the value of £6,585,806.

Since the year 1875 the Inspectors' annual reports give the aggregate production in each of the iron ore producing districts of Scotland. The annexed table shows the yield of each district in Scotland, since the year 1875, of all varieties of ironstone and hematite :—

| Counties. | 1875. | 1876. | 1877. | 1878. | 1879. | 1880. |
|--------------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| | <i>Tons.</i> | <i>Tons.</i> | <i>Tons.</i> | <i>Tons.</i> | <i>Tons.</i> | <i>Tons.</i> |
| Ayrshire | 853,868 | 860,648 | 856,129 | 930,121 | 947,636 | 1,008,253 |
| Dumbartonshire | 231,885 | 249,637 | 284,875 | 257,515 | 287,810 | 290,560 |
| Edinburghshire | 49,469 | 61,262 | 75,779 | 57,565 | 92,891 | 101,619 |
| Fife | 36,833 | 14,274 | 13,113 | 19,463 | 9,827 | 652 |
| Haddingtonshire | 9,899 | 6,224 | 4,340 | 2,101 | 550 | 458 |
| Kinrosshire and Perthshire | 14,264 | 41,100 | 31,274 | 21,559 | .. | .. |
| Lanarkshire | 747,406 | 779,263 | 803,382 | 635,272 | 681,231 | 757,291 |
| Renfrewshire | 170,106 | 185,678 | 180,596 | 173,529 | 174,118 | 223,831 |
| Stirlingshire | 143,165 | 162,781 | 172,573 | 169,104 | 108,766 | 128,230 |
| Linlithgowshire | 188,772 | 186,460 | 194,322 | 170,126 | 155,086 | 148,423 |
| Sundries, hematite | 8,568 | 5,226 | 5,469 | 7,568 | 492 | 5,166 |
| Total | 2,454,235 | 2,552,553 | 2,621,852 | 2,443,923 | 2,458,407 | 2,664,483 |

In the three years ending 1880 the separate varieties of ore

raised from the coal and ironstone measures and the hematite deposits of Scotland are separately distinguished, and are as follows :—

| Year. | Clay Band. | Black Band. | Hematite. |
|-------|------------|-------------|-----------|
| | Tons. | Tons. | Tons. |
| 1878 | 1,123,772 | 1,312,583 | 7,568 |
| 1879 | 1,135,247 | 1,322,668 | 492 |
| 1880 | 1,223,670 | 1,435,647 | 5,166 |

Population employed in Ironstone Mines.—But little information exists on this subject before the year 1873; in that and succeeding years the reports of H.M. Inspectors of Mines give the following as the numbers employed under ground and above ground in the eastern and western Inspection districts of Scotland :—

| Year. | EASTERN DISTRICT. | | WESTERN DISTRICT. | | Total Persons Employed. | Ironstone Returned. |
|-------|-------------------|--------|-------------------|--------|-------------------------|---------------------|
| | Above. | Below. | Above. | Below. | | |
| | Nos. | Nos. | Nos. | Nos. | Nos. | Tons. |
| 1873 | 640 | 3,311 | 1,673 | 8,029 | 13,653 | 1,986,000 |
| 1874 | 827 | 4,066 | 1,757 | 7,898 | 14,548 | 2,119,771 |
| 1875 | 788 | 3,885 | 1,641 | 7,313 | 13,627 | 2,452,235 |
| 1876 | 871 | 3,776 | 1,734 | 7,364 | 13,745 | 2,552,553 |
| 1877 | 826 | 3,826 | 1,631 | 7,002 | 13,285 | 2,621,852 |
| 1878 | 702 | 3,123 | 1,530 | 7,179 | 12,534 | 2,443,923 |
| 1879 | 648 | 2,928 | 1,371 | 6,704 | 11,651 | 2,458,407 |
| 1880 | 652 | 2,924 | 1,582 | 7,133 | 12,291 | 2,659,317 |

These returns show a high state of efficiency, the average work of the miner increasing from 145 tons in 1873 to 185 tons in 1876, and 215 tons in 1880, showing an increase of 48 per cent. in the above period.

Fig Iron Manufacture.—The earliest information bearing on iron smelting in Scotland dates about the year 1750, in which year the first furnace was erected at Bunawe, in Argyleshire, by a Mr. Ford. In this furnace the blast was impelled by water power obtained from the river Awe, the ore employed being hematite brought from Ulverston, in Lancashire, while for fuel charcoal alone was used, with the aid of cold blast. The iron thus manufactured enjoyed then, as now, a high reputation, and for purposes

of conversion into crucible steel is quite as reliable as the best Swedish or Russian brands.

The Bunawe furnace, now known as the Lorne, is still occasionally in operation, the proprietors being Messrs. Harrison, Ainslie & Co., who continue to make charcoal pig iron, according to the supply of charcoal obtainable. Previous to the year 1788 there appears to have been a similar furnace erected at Goatfield, also in Argyleshire, and it is recorded that the yield of the Bunawe and Goatfield furnaces in 1788 amounted to 1,400 tons, or 700 tons each furnace. The charcoal iron manufacture in Scotland followed precisely the same conditions as those prevailing in other parts of the kingdom; with the exhaustion of the woods, the use of coal was gradually introduced.

The Carron Ironworks, situated on the bank of the Carron river, about two miles from Falkirk, were projected and the first furnace put in blast in the year 1760. The site of Carron was selected on account of the abundant water supply, and the immense deposits of coal, ironstone and limestone in the immediate neighbourhood of the village. The name of Dr. John Roebuck is intimately associated with the Carron Works; he was the principal proprietor of the works, and a man of considerable scientific attainments, devoting his energy most thoroughly towards the development of the iron industries of Scotland. The Carron Works were erected by the eminent engineer John Smeaton; it was at these works that the powerful blowing machinery invented by the same engineer was first introduced; the blowing machinery referred to consisted of 4 cylinders, 4 feet 6 inches in diameter, exactly fitted with pistons, and so contrived that the strokes of the pistons being made alternately produced an almost uninterrupted blast. The pumps were worked alternately by means of a powerful water wheel, which had 4 cranks upon the axis, each of which moved the piston of a cylinder, through its stroke of 4 feet 6 inches.

The great advantages secured by Smeaton's invention enabled the ironmaster to consume the hard dense coke in the furnace which the ordinary bellows previously in use was unable to effect; an increased yield of the furnace was the result: previously it had been from 10 to 12 tons per week, now it rose to 40 tons in the same period, and on the average 1,500 tons of pig iron were made per annum. It was in the immediate neighbourhood of

Carron that James Watt, in association with Dr. Roebuck, erected his first steam engine, the patent for which was secured in the year 1769. In that year too the first carronade, the invention of General Melville, was cast at Carron Foundry, from which indeed the new form of cannon derived its name; and the manufacture of carronades was long the speciality of these ironworks, and it was in a great measure owing to the great extent of this branch of industry during the wars that the proprietors of the works made their large profits.

Succeeding the Carron Works the next important seat of iron manufacture sprang up in Scotland, at Wilsonstown or Cleugh, in the upper ward of Lanarkshire, and near the boundary of Midlothian. It was here, about the year 1774, that the brothers Wilson—merchants engaged in the Swedish iron trade—commenced to develop the coal deposits of the district, and soon afterwards established a foundry. This was succeeded about the years 1780—1781 by the Messrs. Wilson erecting a blast furnace, put in operation in 1781, subsequently the works were greatly extended, and in the year 1787 a second furnace was blown in.

In Mr. William Aiton's "General View of the Agriculture of the County of Ayr,"* some interesting facts are gleaned bearing on the iron industries of Scotland, from which it appears that the manufacture of iron was carried on for some time, by Lord Cathcart and others at Muirkirk in the early part of the previous century. It was made from the ore dug there, and sent to Bunawe, in the county of Argyle, to be reduced into pig iron, which was afterwards brought to the works at Muirkirk, near Glasgow, where it was made into bar iron, in the last operation charred peat being used. These operations were found, however, to be too expensive, and the work was abandoned.

It is further stated by Aiton that in the year 1787 some gentlemen in Glasgow entered into a co-partnery and erected some very extensive ironworks in that parish, which were still carried on in Aiton's time by another company. The works at that time consisted of three blast furnaces for making pig iron, with a foundry and other accessory works, the number of hands employed in the above works at that time being from 800 to 400; while the

* Published in the year 1811.

mineral-field of the Muirkirk Company, at the time referred to, exceeded 2,000 acres of coal and ironstone.

In the year 1788, the Wilsonstown or Cleugh furnaces, two in number, produced 1,600 tons of coke pig iron, and the four furnaces at the Carron Works, 4,000 tons, amounting to 5,600 tons of coke pig iron in Scotland in 1788. The total production of charcoal pig iron in Great Britain the same year was 14,500 tons, and of coke pig iron, 53,800 tons, or a total make of pig iron of 68,300 tons.* Scotland at this time produced 10 per cent. of the above quantity, the average yield of her blast furnaces being 875 tons, compared with 796 tons, the yield of the furnaces of England and Wales.

The Muirkirk Works and those at Omoa, in Lanarkshire, commenced operations in the year 1788; the last named was dismantled a few years since. The former still exists. The Clyde Ironworks, near Glasgow, projected about the same year by Messrs. Edington and Co., commenced operations a few years later.

These latter works have been rendered famous by being associated with two names celebrated in the history of the metallurgical industries of Great Britain. The one, Mr. David Mushet, the other, Mr. James Beaumont Neilson. The first named entered these works as accountant in the year 1792, when he was nineteen years of age and remained till the year 1800. In the following year, while engaged in the projection of the Calder Ironworks in association with Mr. William Dixon, senior, of Govan, Mushet made the discovery of the black band ironstone, which in subsequent years exercised such an important influence in the prosperity of Scotland in her iron and other industries.

The last return quoted was for the year 1788; not again until the year 1796, when Dr. McNab's return, prepared for a Committee of the House of Commons, appears, does any reliable information throw light on the progress of this industry. The following details from Dr. McNab's return show the respective works in operation in Scotland, with the number of furnaces and the make of pig iron: side by side is given the average yield per furnace. Of the 16,086 tons of pig iron it will be observed that 900 tons was charcoal pig, the yield of the Bunawe and Goatfield furnaces.

* For details of this return, see Appendix II., p. 830.

| No. | Name of Works. | No. of Furnaces. | Make of Pig Iron. | Average per Furnace. |
|-----|-----------------------------|---------------------|----------------------|-------------------------|
| | | | Tons. | Tons. |
| 1 | Carron | 4 | 5,616 | 1,404 |
| 2 | Wilsonstown or Cleugh . . . | 2 | 2,080 | 1,040 |
| 3 | Muirkirk | 2 | 2,878 | 1,489 |
| 4 | Clyde | 3 | 2,216 | 738 |
| 5 | Omoa | 2 | 1,198 | 599 |
| 6 | Devon | 2 | 1,198 | 599 |
| 7 | Goatfield (charcoal) . . . | 1 | 300 | 300 |
| 8 | Bunawe „ | 1 | 600 | 600 |
| | Total | 17 | 16,086 | |

In the same year the total number of furnaces in operation in Great Britain,* was 124, producing 125,079 tons of pig iron, showing an average yield per furnace of upwards of 1,000 tons.

Towards the close of the past century, about the year 1782, the Devon Ironworks, in Clackmannanshire, were erected, singular alike in situation and construction. Sir John Sinclair, who describes them, says: † “They merit the attention of the curious in mechanics and architecture. A steep bank rises more than 90 feet from the level of the river, and is composed of a rock, or very thick stratum of limestone, very dry and uniform in its texture, and almost free from cracks and fissures. Instead of the usual method of building with stone and lime, the several parts of the works have been formed in this bank by excavations made in the rock. Two furnaces, which are each 40 feet high and 14 feet in diameter, and also the spacious arches which give access to the workmen at the bottom of the furnace, to draw off the liquid metal and slag, are cut out of the rock. The roof which covers the casting house, a room 70 feet long, 50 feet wide, and 23 feet high, is supported by the sides of the quarry, and the solid pillars of the rock that were left for the purpose in making the excavation. In like manner is formed the engine house and its apparatus, which is intended to supply the two furnaces with wind, by throwing at each vibration of the engine a sufficient quantity of air out of a large cylinder into a long gallery or close mine formed in the rock. This magazine of wind will contain 10,000 cubic feet of air, much condensed by the power of the engine, as the gallery is very closely shut up and made air-tight,

* For details see Appendix II., p. 831.

† “Statistical Account of Scotland,” 1792.

having only two apertures, one to receive the supply of air from the air-pump and the other to admit a pipe that conducts the condensed air to blow the two furnaces." These works continued in operation for many years, but were stopped about the year 1858, and soon after dismantled.

Resuming inquiries with the present century it appears, as previously stated, that the Calder Ironworks commenced operations in the year 1801. These works take a prominent position in the history of the iron trades of Scotland, from the circumstance that it was here that the black band ironstone discovered by Mushet was first used as an ore of iron. The Shotts Ironworks were projected in the year 1802, under the able management of Mr. John Baird, of the Canal Basin Foundry, Glasgow, who continued to be the managing partner of the concern for upwards of 40 years. At these works in recent years Bessemer pig iron has been produced from hematite ore and with the use of raw coal.

Continuing the returns of production, the year 1806 comes next in order, when the following works and furnaces produced iron in the quantities given, to which is added the average yield per furnace :—

| County. | Name of Works. | FURNACES. | | Pig Iron Made. | Average per Furnace. |
|-------------------|---------------------|-----------|-----------|----------------|----------------------|
| | | Built. | In Blast. | | |
| | | Nos. | Nos. | Tons. | Tons. |
| Stirlingshire . . | Carron | 5 | 5 | 7,380 | 1,476 |
| Lanarkshire . . | Calder | 2 | 1 | 1,077 | 1,077 |
| " | Clyde | 3 | 2 | 2,687 | 1,343 |
| " | Glenbuck | 1 | 1 | 790 | 790 |
| " | Omoa | 3 | 2 | 1,852 | 926 |
| " | Shotts | 1 | 1 | 2,034 | 2,034 |
| " | Wilsonstown | 2 | 1 | 1,381 | 1,381 |
| Fifeshire | Markinch | 2 | 0 | ... | ... |
| Ayrshire | Muirkirk | 3 | 2 | 3,043 | 1,521 |
| Clackmannan . . | Devon | 2 | 2 | 2,596 | 1,298 |
| Argyle | Goatfield | 2 | 0 | ... | ... |
| " | Bunawe | 1 | 0 | ... | ... |
| Total | | 27 | 17 | 22,840 | |

Comparing the above returns with those of the year 1796, it will be seen that considerable advance had been made in the yield of pig iron, to the extent of upwards of 40 per cent. The

average make per furnace being 1,270 tons, compared with 946 tons in the year 1796, equal to an increase of 12 per cent.

The make of pig iron in Great Britain in 1806, when of the 216 furnaces built 161 were in blast, was 248,851 tons.

During the first quarter of the present century there is but little to record, either in the way of greatly increased production of pig iron in Scotland or in the extension of the then existing ironworks; not until the year 1825 does it appear any new works were established.

The Monkland Iron Company led the way, about this period putting their first furnace in blast, adding a second to their works about the year 1828 or 1829. The works at Gartsherrie followed about the year 1830, when the first furnace was blown in; these works, situated at Coatbridge, near Glasgow, and projected by the Messrs. Baird and Company, are the most extensive at the present time in Lanarkshire, possessing 16 blast furnaces; the only other iron company in Scotland possessing greater resources of production is that of the Eglinton Company in Ayrshire, with 21 furnaces.

As previously stated the production of pig iron in Scotland in the year 1806 was 22,840 tons; advancing to the year 1823, it appears the production did not exceed 24,500 tons, the yield of 22 furnaces, of which the following is an account, showing the works, furnaces blowing, firms engaged in manufacture, and yield of individual works:—

| County. | Name of Works. | Name of Firm. | No. of Furnaces. | Pig Iron Made. |
|--------------|----------------|-----------------------|---------------------|-------------------|
| | | | | Tons. |
| Stirling . . | Carron . . | Carron Iron Co. . . | 5 | 7,000 |
| Lanark . . | Calder . . | William Dixon . . | 3 | 4,000 |
| „ . . | Clyde . . | Dunlop & Co. . . | 3 | 2,500 |
| „ . . | Omoa . . | Dalrymple & Co. . . | 2 | 2,500 |
| „ . . | Shotts . . | Shotts Iron Co. . . | 1 | 2,000 |
| Ayr . . | Muirkirk . . | Muirkirk Iron Co. . . | 3 | 3,500 |
| Clackmannan | Devon . . | Devon Iron Co. . . | 3 | 3,000 |
| Total . . | | | 20 | 24,500 |

We now advance to the period when the successful experiments of Mr. James Beaumont Neilson resulted in the application of the hot blast, inaugurating a new era in the history of the iron trade and leading to greatly increased production. Neilson, to

whom we are indebted for this important invention, was educated as an engineer, and in the year 1817, at the age of 25 years, was appointed foreman to the Glasgow Gas Light Company; the great experience acquired by him in this capacity led to his being consulted by ironmasters, which gave him opportunities of gaining a great insight into the operations connected with blast furnace management. At an early period he was consulted by Mr. Dixon of the Wilsonstown Works and by the Muirkirk Iron Company, but it was at the Clyde Ironworks that his experiments were successfully carried out, the then proprietor being Mr. Colin Dunlop; eventually Neilson secured his invention by patent in the year 1828, which is entitled "Improved application of Air to produce Heat in Fires, Forges, and Furnaces." The discovery of the superior power of a hot over a cold blast in fusing refractory lumps of cast-iron was accidentally observed by Neilson while in the service, as previously stated, of the Glasgow Gas Light Company. No particular description of apparatus was given by the inventor by which the air was to be heated and conveyed to the furnace, but it was merely stated that the air may be heated in a chamber or closed vessel, having a fire under it, or in a vessel connected in any convenient manner with the forge or furnace. Dr. Percy,* referring to this important invention, says: "The advantages, however, of the hot blast with respect to the economy of fuel were so soon recognised by the Scotch ironmasters, that in the year 1835 it was in operation at every ironworks in Scotland except one, and there it was in process of introduction."

Another important invention, perfected about the year 1830, by Mr. Condie, manager of the Wilsonstown Ironworks, was the Water-Tuyere, now so generally employed, and which owes its great utility to the spirally disposed malleable iron tube contained within a mass of cast-iron. It was at the same works in the year 1808, that the Water-Tuyere was brought into use to supersede the dry-tuyere, but it was not till the year 1830, as already stated, that Mr. Condie devised and perfected the present arrangement. It was also at the Wilsonstown works that the possibility of using raw coal in the blast furnace was first solved, dating an eventful period in the history of pig iron manufacture.

The next return of pig iron production is for the year 1830, when Scotland had 24 furnaces in operation out of 27 then built,

* "Metallurgy," Iron and Steel, p. 395.

the yield of pig iron amounting to 37,500 tons. The details of which will be seen in the following abstract, giving also the average make per furnace :—

| County. | Name of Works. | No. of Furnaces. | Pig Iron Made. | Average per Furnace. |
|---------------|------------------|---------------------|-------------------|-------------------------|
| | | | Tons. | Tons. |
| Stirling . . | Carron . . . | 5 | 7,000 | 1,400 |
| Lanark . . | Calder . . . | 4 | 9,000 | 2,250 |
| " . . | Clyde . . . | 4 | 8,000 | 2,000 |
| " . . | Monkland . . . | 2 | 2,000 | 1,000 |
| " . . | Shotts . . . | 1 | 2,000 | 2,000 |
| " . . | Wilsonstown* . . | 2 | 2,000 | 1,000 |
| Ayr . . | Muirkirk . . . | 3 | 4,000 | 1,333 |
| Clackmannan . | Devon . . . | 3 | 3,500 | 1,166 |
| | Total . . | 24 | 37,500 | |

Comparing the production of Scotland in the year 1830 with that of the year 1823, it will be seen that the increase is 53 per cent.; the average yield of the furnaces increasing from 1,225 tons in the year 1823 to 1,480 tons in the year 1830.

It may be interesting, while considering the state of the iron industries of Scotland in the years 1823 and 1830, to note the production of the iron works in the other districts of England and Wales; to enable comparison to be made, the returns of Great Britain are appended in the annexed abstract :—

| Counties. | 1823. | | 1830. | |
|--|-----------|----------------|-----------|----------------|
| | Furnaces. | Pig Iron Made. | Furnaces. | Pig Iron Made. |
| | Nos. | Tons. | Nos. | Tons. |
| Durham and Northum- berland . . . } | 2 | 2,379 | 4 | 5,327 |
| Yorkshire . . . | 26 | 27,311 | 27 | 28,926 |
| Derbyshire . . . | 15 | 14,038 | 18 | 17,999 |
| Shropshire . . . | 38 | 57,923 | 48 | 73,418 |
| Staffordshire . . . | 84 | 133,590 | 123 | 211,604 |
| South Wales . . . | 72 | 182,325 | 113 | 277,643 |
| North Wales . . . | 7 | 13,100 | 12 | 25,000 |
| Scotland . . . | 22 | 24,500 | 27 | 37,500 |
| Total . . . | 266 | 455,166 | 372 | 677,417 |

The above totals show an increase in the production of the furnaces in the seven years between 1823 and 1830 of 48 per cent.

* These works ceased operations in the year 1842.

The hot blast is so important, contributing as it did to the ironmaster's powers of increasing the blast furnace yield, that a few facts connected with its early history will possess some interest to the general reader.

Previous to the introduction of Neilson's invention, coke was largely employed in the blast furnace, now the hot blast enabled the ironmaster to employ raw coal; the saving thereby effected amounted to no less than 5 tons to each ton of pig iron made, and these advantages, taken in connection with Mushet's discovery of the black band ironstone, a furnace working hot blast and making 60 tons of iron per week, had its production raised to from 80 and 90 tons; and it is recorded that at the Calder and Wilsonstown Ironworks Neilson's invention was early put to the test, and such material aid was rendered by Mr. William Dixon, and his manager, Mr. Condie, in working and developing the merits of the invention, that the proprietors of the patent rights granted the use of the patent for several of the Calder furnaces without exacting the usual royalty charges.

From this period forward each year witnessed an increase to the resources of existing works, and the accession of many new ones; thus in the year 1833 the works at Dundyvan were projected by Mr. John Wilson, followed in the year 1836 by the Coltness Company, and the Summerlee Works in the year 1837 by Messrs. Wilsons and Co., the Carnbroe Works, in Lanarkshire, by Messrs. Allison and Co. in the year 1838, and the Langloan Works, also in Lanarkshire, near Coatbridge, by the Messrs. Addie and Co., in the year 1841. The other works projected about this period were those of Castle Hill, near Wishaw, by the Shotts Iron Company, and Govan, near Glasgow, by Mr. William Dixon, Glengarnock, in Ayrshire, near Kilbirnie, now owned by William Dixon, Limited. These works were originally intended to consist of eight blast furnaces, but up to the present time five only have been erected; of these, two have been raised considerably in height, and provision made for taking off the gas. This establishment also possesses extensive malleable iron works, capable of producing 400 tons per week of plates, bars, and rods. Advancing to the year 1843, a period of great depression in the iron industries of Great Britain, we find the following statement, showing the weekly make of the ironworks of Scotland, together with the number of furnaces built and in blast in that year:—

| County. | Name of Works. | Name of Firm. | FURNACES. | | Weekly Make. |
|------------------|-----------------|-------------------------|-----------|-----------|--------------|
| | | | Built. | In Blast. | |
| | | | Nos. | Nos. | Tons. |
| Stirling | Carron . . | Carron Iron Co. . . | 5 | 3 | 200 |
| Lanark | Calder . . | William Dixon . . | 8 | 6 | 600 |
| " | Olyde . . | C. Dunlop & Co. . . | 6 | 3 | 250 |
| " | Coltness . . | Coltness Iron Co. . . | 4 | 3 | 240 |
| " | Dundyvan . . | John Wilson . . | 9 | 7 | 750 |
| " | Castle Hill . . | Shotts Iron Co. . . | 2 | 0 | ... |
| " | Carnbroe . . | Allison & Co. . . | 6 | 4 | 500 |
| " | Gartsherrie . . | William Baird & Co. . . | 16 | 11 | 1,200 |
| " | Govan . . | Messrs. Dixon . . | 5 | 5 | 500 |
| " | Langloan . . | Addie & Co. . . | 3 | 3 | 400 |
| " | Monkland . . | Monkland Iron Co. . . | 5 | 5 | 500 |
| " | Summerlee . . | Wilsons & Co. . . | 6 | 3 | 270 |
| " | Shotts . . | Shotts Iron Co. . . | 4 | 2 | 160 |
| " | Wilsonstown . . | | 2 | 0 | ... |
| " | Omoa . . | R. Stewart . . | 2 | 1 | 80 |
| Ayr | Glengarnock . . | Allison & Co. . . | 3 | 3 | 300 |
| " | Muirkirk . . | Muirkirk Iron Co. . . | 4 | 2 | 180 |
| " | Blair . . | Blair Iron Co. . . | 3 | 0 | ... |
| " | Cessnock . . | Cessnock Iron Co. . . | 2 | 0 | ... |
| " | Henschell . . | Henschell Iron Co. . . | 2 | 0 | ... |
| " | Garscube . . | Galloway & Co. . . | 2 | 0 | ... |
| Clackman- nan | Devon . . | Devon Iron Co. . . | 4 | 1 | 90 |
| Total . . | | | 103 | 62 | 6,220 |

In computing the annual production of pig iron in Scotland from the above weekly make, and taking 50 weeks for the year, we have an annual yield of 311,000 tons. Comparing this quantity with the make in the year 1839, when of the 60 furnaces then erected in Scotland, 54 were in blast, yielding 196,566 tons of pig iron, the returns exhibit an increase between the years 1839 and 1848 of no less than 114,440 tons, equal to nearly 60 per cent.

As previously stated, the iron industries of the kingdom were passing through a period of great depression, which continued from about the year 1840 until the year 1844, when the extension of the railway system gave rise to a great demand for all kinds of iron, and brought about more prosperous times for the iron trade. About the period referred to the quotations for iron were very low and to the ironmaster comparatively unremunerative. It was about this period that the patent of Neilson of the hot blast expired, and this circumstance led to the foundation of many new

and extensive ironworks in Scotland, and to the extension of existing works. Among these may be mentioned those of Messrs. Merry and Cunninghame, of Ardeer and Glengarnock, the works at Eglinton, Lugar, and Portland, of the Eglinton Iron Company, and the works of the Dalmellington Company, all in Ayrshire. In Lanarkshire, the works of Mr. William Dixon, at Govan, and of the Shotts Iron Company, at Castlehill, were extended; while in Linlithgow, the works at Kinneil were founded by Mr. J. Wilson.

In the year 1843 the production of pig iron in Great Britain amounted to 1,215,950 tons; in 1848 it rose to 1,998,568 tons, the yield of the Scotch furnaces during the same period increasing from 311,000 tons in the year 1843, to 534,000 tons, an estimated return in the year 1848. The following is a list of the works and furnaces built and in operation in Scotland in the year 1848, together with the production of pig iron:—

| County. | Name of Works. | FURNACES. | | Pig Iron Made. |
|----------------|---------------------|-----------|-----------|----------------|
| | | Built. | In Blast. | |
| | | Nos. | Nos. | Tons. |
| Stirling . . | Carron | 4 | 3 | 18,000 |
| Lanark . . . | Calder | 8 | 3 | 18,000 |
| " | Carnbroe | 6 | 3 | 18,000 |
| " | Clyde | 7 | 5 | 30,000 |
| " | Coltness | 6 | 4 | 24,000 |
| " | Castlehill | 3 | 2 | 12,000 |
| " | Dundyvan | 9 | 8 | 48,000 |
| " | Gartsherrie | 16 | 16 | 96,000 |
| " | Govan | 6 | 4 | 24,000 |
| " | Langloan | 6 | 5 | 30,000 |
| " | Monkland | 9 | 9 | 54,000 |
| " | Omoa | 4 | 4 | 24,000 |
| " | Shotts | 4 | 3 | 18,000 |
| " | Summerlee | 6 | 5 | 30,000 |
| Ayr | Blair | 5 | 0 | ... |
| " | Garscube | 2 | 0 | ... |
| " | Glengarnock | 7 | 6 | 36,000 |
| " | Muirkirk | 4 | 0 | ... |
| " | Eglinton | 3 | 0 | ... |
| " | Lugar | 4 | 0 | ... |
| Clackmannan . | Devon | 1 | 1 | 6,000 |
| Fife | Forth | 6 | 4 | 24,000 |
| Linlithgow . . | Kinneil | 4 | 4 | 24,000 |
| | Total | 130 | 89 | 534,000 |

From the above return it appears that the production of Scotland is set down at 584,000 tons ; in another return for the same year, the yield is stated to have been 539,962 tons.* The sub-joined table shows the production in Great Britain in the same year :—

| Districts. | FURNACES. | | | Pig Iron Made. |
|--------------------------|------------|------------|------------|------------------|
| | In. | Out. | Total. | |
| | Nos. | Nos. | Nos. | Tons. |
| Northumberland . . . | 24 | 12 | 36 | 99,840 |
| Yorkshire | 23 | 5 | 28 | 66,560 |
| Derbyshire | 20 | 10 | 30 | 95,160 |
| Shropshire | 28 | 6 | 34 | 88,400 |
| Staffordshire, North . . | 16 | 3 | 19 | 65,520 |
| Staffordshire, South . . | 77 | 62 | 139 | 320,320 |
| Wales, North | 5 | 6 | 11 | 16,120 |
| Wales, South | 151 | 45 | 196 | 706,680 |
| Scotland | 89 | 41 | 130 | 539,968 |
| Total | 433 | 190 | 623 | 1,998,568 |

From the year 1848, to which the above return refers, great activity set in, not only in Scotland but in many iron districts of England and Wales. In Fifeshire works were founded at Lochgelly and Lumphinnans, the last-named by Messrs. A. Christie and Co., and in Linlithgowshire, the Bridgeness and Almond Works, by Mr. Henry Cadell and Messrs. Russell and Sons.

The other works in Lanarkshire erected in recent years are those at Calder Bank and Chapel Hill, near Airdrie, the property of the Monkland Iron and Coal Company, Limited, consisting of nine blast furnaces ; the Quarter Works, near Hamilton, with five furnaces, belonging to Messrs. Colin Dunlop and Co. ; and the Wishaw Works of the Glasgow Iron Company, with three furnaces.

Following the production of pig iron in Scotland since the year 1850, the most complete information is available, showing the number of furnaces built and in blast, together with the production of pig iron ; side by side is given, for comparison, the production of the North Riding of Yorkshire, or Cleveland district, and that of Lancashire in each of the same years :—

* " Report on the State of the Population in the Mining Districts," 1848, p. 27.

| Year. | SCOTLAND. | | | CLEVELAND. | LANCASHIRE. |
|-------|-----------|-----------|-----------|------------|-------------|
| | FURNACES. | | Pig Iron. | Pig Iron. | Pig Iron. |
| | Built. | In Blast. | | | |
| | Nos. | Nos. | Tons. | Tons. | Tons. |
| 1850 | ... | 105 | 595,000 | ... | ... |
| 1852 | ... | 113 | 775,000 | ... | ... |
| 1854 | 156 | 118 | 770,000 | ... | ... |
| 1856 | 141 | 127 | 832,000 | 179,400 | ... |
| 1858 | 177 | 132 | 945,000 | 189,320 | 2,840 |
| 1860 | 175 | 131 | 1,000,000 | 248,665 | 81,250 |
| 1862 | 171 | 125 | 1,080,000 | 283,398 | 138,563 |
| 1863 | 169 | 134 | 1,160,000 | 315,197 | 164,110 |
| 1864 | 170 | 131 | 1,160,000 | 409,106 | 195,460 |
| 1865 | 180 | 141 | 1,163,478 | 486,421 | 204,925 |
| 1866 | 165 | 99 | 994,000 | 546,091 | 268,680 |
| 1867 | 167 | 112 | 1,031,000 | 640,892 | 318,801 |
| 1868 | 147 | 103 | 1,068,000 | 699,494 | 325,367 |
| 1869 | 165 | 132 | 1,150,000 | 766,410 | 436,662 |
| 1870 | 156 | 123 | 1,206,000 | 916,970 | 422,728 |
| 1871 | 155 | 127 | 1,169,000 | 1,029,885 | 520,359 |
| 1872 | 154 | 130 | 1,090,000 | 1,122,114 | 524,041 |
| 1873 | 156 | 126 | 993,000 | 1,156,431 | 529,271 |
| 1874 | 157 | 121 | 806,000 | 1,158,471 | 488,672 |
| 1875 | 159 | 116 | 1,050,000 | 1,240,243 | 558,780 |
| 1876 | 157 | 116 | 1,103,000 | 1,261,013 | 552,984 |
| 1877 | 152 | 109 | 982,000 | 1,374,582 | 624,189 |
| 1878 | 152 | 94 | 902,000 | 1,358,442 | 616,256 |
| 1879 | 157 | 96½ | 932,000 | 1,210,091 | 631,343 |
| 1880 | 149 | 112 | 1,049,000 | 1,666,156 | 738,023 |

In the year 1854, of the 770,000 tons of pig iron produced in Scotland, Ayrshire contributed 249,600 tons; the Lanarkshire furnaces, 468,000 tons, and the remaining districts, 52,400 tons. In later years, the iron-making districts contributed in the following proportion:—

| Districts. | MAKE OF PIG IRON. | | | | |
|---------------------------|-------------------|-----------|---------|---------|-----------|
| | 1874. | 1876. | 1878. | 1879. | 1880. |
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| Lancashire | 501,000 | 680,076 | 604,280 | 625,634 | 670,085 |
| Ayrshire | 210,000 | 360,924 | 256,377 | 276,552 | 345,729 |
| Fifehire | 14,000 | .. | .. | .. | .. |
| Linlithgowshire | 35,000 | 62,000 | 41,343 | 29,814 | 33,186 |
| Stirlingshire | 16,000 | .. | .. | .. | .. |
| Total | 806,000 | 1,103,000 | 902,000 | 932,000 | 1,049,000 |

The average annual yield of the Scotch blast furnaces in the

year 1850, was 5,700 tons, increased in the year 1860 to 7,630 tons, 9,800 tons in the year 1870, and 9,866 tons in 1880.

The annexed is a complete list of the works, owners, furnaces built and in blast in Scotland in the year 1880:—

| No. | Name of Works. | Owners. | FURNACES. | |
|-----|---|-----------------------------------|-----------|-----------|
| | | | Built. | In Blast. |
| | <i>Ayrshire—</i> | | Nos. | Nos. |
| 1 | Ardeer, Stevenston . . . | Merry and Cunninghame, Lim. . . | 5 | 3 |
| 2 | Glengarnock, Kilbirnie . . | " " " " " " . . . | 9 | 6 |
| 3 | Eglinton, Glasgow . . . | Eglinton Iron Co. | 7 | 5½ |
| 4 | Lugar, " " " " . . . | " " " " " " . . . | 5 | 4 |
| 5 | Muirkirk, " " " " . . . | " " " " " " . . . | 3 | 3 |
| 6 | Portland, " " " " . . . | " " " " " " . . . | 6 | 4 |
| 7 | Dalmellington, Glasgow . . | Dalmellington Iron Co. . . . | 8 | 7 |
| | Total of Ayrshire | | 43 | 32½ |
| | <i>Lanarkshire—</i> | | | |
| 1 | Calder | William Dixon, Limited . . . | 6 | 4 |
| 2 | Govan, Glasgow | " " " " " " . . . | 5 | 5 |
| 3 | Carnbroe, Coatbridge . . . | Merry and Cunninghame, Lim. . | 6 | 3 |
| 4 | Castlehill | Shotts Iron Co. | 3 | 3 |
| 5 | Shotts | " " " " " " . . . | 5 | 5 |
| 6 | Clyde | James Dunlop & Co. | 5 | 5 |
| 7 | Quarter, Hamilton | Colin Dunlop & Co. | 5 | 5 |
| 8 | Coltness | Coltness Iron Co. | 12 | 10 |
| 9 | Gartsherrie, Coatbridge . . | William Baird & Co. | 14 | 12 |
| 10 | Langloan, " " " " . . . | Robert Addie & Sons | 7 | 7 |
| 11 | Calder Bank, Airdrie . . . | Monkland Iron and Coal Co., Lim. | 6 | 5 |
| 12 | Chapelhill, " " " " . . . | " " " " " " . . . | 3 | 3 |
| 13 | Summerlee " " " " . . . | Summerlee Iron Co. " " . . . | 8 | 6 |
| 14 | Wiahaw | Glasgow Iron Co. | 3 | 3 |
| | Total of Lanarkshire . . . | | 88 | 76 |
| | <i>Fifeshire—</i> | | | |
| 1 | Lochgelly | Lochgelly Iron and Coal Co., Lim. | 4 | 0 |
| 2 | Lumphinnans, Lochgelly . . | A. Christie & Co. | 2 | 0 |
| | Total of Fifeshire | | 6 | 0 |
| | <i>Linlithgowshire—</i> | | | |
| 1 | Kinniel, Boness | George Wilson & Co. | 2 | 1 |
| 2 | Bridgeness, " " " " . . . | Henry Cadell | 2 | 0 |
| 3 | Almond, Causewayend . . . | James Russell & Sons | 3 | 1 |
| | Total of Linlithgowshire . . | | 7 | 2 |
| | <i>Stirlingshire—</i> | | | |
| 1 | Carron, Falkirk | Carron Iron Co. | 4 | 2 |
| | <i>Argyleshire—</i> | | | |
| 1 | Lorn | Harrison, Ainslie, & Co., . . . | 1 | 0 |
| | Total of Fifeshire, Linlithgowshire, Stirlingshire, and Argyleshire | | 18 | 4 |
| | Total of Scotland | | 149 | 112½ |

Distribution of Scotch Pig Iron and Prices.—The ironworks of Scotland are most favourably situated for the distribution of the products of her iron furnaces, possessing at easy distances two coasts, with numerous shipping ports and ample railway and canal communication; they are also close to the rivers Clyde and Forth, both navigable for the greater part of their course. The exports of pig iron in 1830, when the total production of Scotland did not exceed 37,500 tons, varied from 8,000 to 9,000 tons. In 1845, out of a production of 500,000 tons, the exports were only 56,761 tons, about one-tenth and less in proportion than in the year 1830. Between the years 1840 and 1845, a great impetus was given to the iron trade by the extension of the railway system of the United Kingdom, the home consumption absorbing the additional production. The increased number of works and more active competition existing at this period, coupled with a now more restricted home market, led to a first fall in prices, which set in about the year 1841, and continued till the year 1853. In the following table appears the average prices of pig iron in Scotland from 1830 to 1862; the prices since that date are given on page 747:—

| Year. | Average Price. | | | Year. | Average Price. | | |
|-------|----------------|----|----|-------|----------------|----|----|
| | £ | s. | d. | | £ | s. | d. |
| 1830 | 5 | 0 | 0 | 1848 | 2 | 4 | 5 |
| 1831 | 4 | 10 | 0 | 1849 | 2 | 6 | 1 |
| 1832 | 4 | 10 | 0 | 1850 | 2 | 4 | 5 |
| 1833 | 4 | 0 | 0 | 1851 | 2 | 0 | 3 |
| 1834 | 4 | 5 | 0 | 1852 | 2 | 5 | 4 |
| 1835 | 4 | 10 | 0 | 1853 | 3 | 1 | 6 |
| 1836 | 6 | 15 | 0 | 1854 | 3 | 19 | 9 |
| 1837 | 4 | 10 | 0 | 1855 | 3 | 10 | 9 |
| 1838 | 4 | 0 | 0 | 1856 | 3 | 12 | 6 |
| 1839 | 4 | 10 | 0 | 1857 | 3 | 9 | 2 |
| 1840 | 3 | 15 | 0 | 1858 | 2 | 14 | 5 |
| 1841 | 3 | 0 | 0 | 1859 | 2 | 11 | 11 |
| 1842 | 2 | 10 | 0 | 1860 | 2 | 13 | 9 |
| 1843 | 2 | 16 | 0 | 1861 | 2 | 9 | 3 |
| 1844 | 2 | 14 | 9 | 1862 | 2 | 13 | 0 |

Previously, in the year 1810, the average price of Scotch pig iron per ton was £9 5s.; in 1815 it receded to £7 15s. per ton, and in 1820 to £7, rising again in 1825 to £11 per ton.

Since the year 1845 the distribution of Scotch pig iron to foreign countries and coastwise to other ports in the United Kingdom has gone on increasing. In the following table appear

the quantities under each of the above heads, also the stocks of pig iron in warehouses at the end of each year :—

| Year. | EXPORTED. | | Total. | Stocks. |
|-------|-----------|------------|---------|---------|
| | Foreign. | Coastwise. | | |
| | Tons. | Tons. | Tons. | Tons. |
| 1845 | 56,671 | ... | ... | 240,000 |
| 1846 | 119,107 | 192,893 | 312,000 | 144,000 |
| 1847 | 143,460 | 227,005 | 370,465 | 89,000 |
| 1848 | 162,114 | 227,870 | 389,984 | 90,000 |
| 1849 | 153,200 | 221,943 | 375,143 | 196,000 |
| 1850 | 134,710 | 189,490 | 324,200 | 200,000 |
| 1851 | 192,610 | 260,090 | 452,700 | 300,000 |
| 1852 | 224,370 | 210,530 | 434,900 | 360,000 |
| 1853 | 318,020 | 316,980 | 635,000 | 450,000 |
| 1854 | 283,903 | 301,097 | 585,000 | 216,000 |
| 1855 | 243,108 | 295,000 | 538,108 | 132,000 |
| 1856 | 258,589 | 245,000 | 503,589 | 130,000 |
| 1857 | 294,232 | 233,768 | 528,000 | 90,000 |
| 1858 | 274,000 | 280,000 | 554,000 | 196,000 |
| 1859 | 254,245 | 312,755 | 567,000 | 350,000 |
| 1860 | 255,628 | 321,372 | 577,000 | 390,000 |

In the year 1845—46 a new era opened out for the products of the Scotch blast furnaces, the markets of France, Germany and the United States contributing to the greatly increased exports apparent in those years. In 1848, in Scotland as elsewhere, industrial and commercial affairs were more or less affected by the disturbed state of affairs prevailing in Europe.

Following the course of events at this period a more encouraging state of trade appears in the years 1852—53, when prices ruled higher, the demand at home and abroad increasing. This condition was however of short duration, inasmuch as the crisis then taking place in America and the condition of affairs in Europe materially checked the prosperity which had set in about this time in the iron and other industries of the country.

It would give an inadequate idea of the condition of the Scotch iron trade at this eventful period, did we omit the statistics bearing on the local consumption of pig iron in Scotland; we therefore give the following table, distinguishing the quantity of pig iron employed in the foundry, from that used in the malleable ironworks for conversion into the various forms of iron applicable to the construction of iron vessels, bridges, and machinery, be-

tween the years 1846 and 1860, increasing from 280,000 tons in the first to 355,000 tons in the last-named year :—

| Year. | Foundries. | Malleable Iron Works. | Total Home Consumption. |
|-------|------------|-----------------------|-------------------------|
| | Tons. | Tons. | Tons. |
| 1846 | 200,000 | 80,000 | 280,000 |
| 1849 | ... | ... | 221,000 |
| 1850 | ... | ... | 225,000 |
| 1851 | ... | ... | 250,000 |
| 1852 | ... | ... | 250,000 |
| 1853 | 125,000 | 180,000 | 305,000 |
| 1854 | 116,000 | 170,000 | 286,000 |
| 1855 | 125,000 | 175,000 | 300,000 |
| 1856 | 133,000 | 203,000 | 336,000 |
| 1857 | 155,000 | 160,000 | 315,000 |
| 1858 | 146,000 | 132,000 | 278,000 |
| 1859 | 190,000 | 150,000 | 340,000 |
| 1860 | 200,000 | 155,000 | 355,000 |

With regard to the distribution of Scotch pig iron, it will be sufficient to give the quantities, under the several heads, for the following years ; these, although indicating a marked increase, also exhibit considerable fluctuation, but not more than might be expected from the variable conditions to which the iron trade has been subject during the years given :—

| Year. | Rail to England. | EXPORTED. | | HOME CONSUMPTION. | |
|-------|------------------|-----------|------------|-------------------|-----------------------|
| | | Foreign. | Coastwise. | Foundries. | Malleable Iron Works. |
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1868 | 22,200 | 324,018 | 238,922 | 208,000 | 179,800 |
| 1869 | 21,911 | 388,639 | 240,450 | 240,000 | 207,000 |
| 1870 | 35,174 | 388,842 | 230,984 | 298,000 | 208,000 |
| 1871 | 54,027 | 512,479 | 303,494 | 275,000 | 190,000 |
| 1872 | 74,372 | 616,933 | 224,695 | 270,000 | 200,000 |
| 1873 | 81,089 | 398,850 | 214,061 | 230,000 | 143,000 |
| 1874 | 60,093 | 296,803 | 166,104 | 193,000 | 124,000 |
| 1875 | 73,491 | 368,453 | 174,056 | 205,000 | 155,000 |
| 1876 | 70,058 | 303,752 | 166,190 | 195,000 | 175,000 |
| 1877 | 59,937 | 274,409 | 170,654 | 175,000 | 160,000 |
| 1878 | 38,472 | 233,908 | 161,620 | 153,500 | 140,500 |
| 1879 | 23,482 | 340,385 | 200,133 | 155,045 | 146,955 |
| 1880 | 29,952 | 440,200 | 200,848 | 189,000 | 195,000 |

Malleable Ironworks, Mills and Forges.—Many of these works are some of the most extensive in the kingdom, possessing the necessary appliances for manufacturing the heaviest descrip-

tion of ironwork; consisting of crank shafts, propeller shafts, stern posts, rudder posts, &c., and possessing in addition rolling mills and steam hammers for manipulating large masses of malleable iron, besides lathes of various kinds for reducing the forgings to a more or less finished condition. The Lancefield Works, near Glasgow, possess great resources. It was at this forge that all the great forgings for the *Great Eastern* were made, the propeller shaft of which was 47 feet in length and weighed 35 tons; the crank shaft, 31 tons, and the stern frame, 25 tons. These works also have puddling, scrap, and forge furnaces, rolling mills, and steam hammers of various sizes, the hammer-head of the largest exceeding 7 tons in weight. Another extensive establishment at Parkhead contains the necessary appliances for the heaviest forgings, as well as for ship and boiler plates and other varieties of finished iron. It was at Parkhead that the heavy double crank shaft of the *Monarch*, weighing upwards of 30 tons, was forged. These works possess 46 puddling furnaces and 3 rolling mills, are furnished with 14 steam hammers, the heads varying in weight, the heaviest exceeding 7 tons. The puddling furnaces each make on an average 6 charges of 4 cwt. each per day of 10 hours, the charges producing about 20 cwt. of puddled bars. The puddled bars are shingled with $2\frac{1}{2}$ -ton hammers, and are rolled down in a pair of 24-inch grooved and collared rolls, which keep the bars to an uniform width. These rolls are described as worked by a pair of horizontal engines, with cylinders 30 inches in diameter and 60 inches stroke, at the rate of 40 revolutions per minute, and worked by steam with 45 lb. pressure; the crank shaft of the engine makes 30 revolutions per minute. The same engines drive the other rolling mills. The mill bars are used for piling and forging, or they are piled and rolled for the production of plates; the best qualities of plate are piled and rolled a second time, and then reheated and finished, each successive reheating consuming from 10 to 18 cwt. of coal per ton of iron, the loss of material in the operation being about 5 per cent.

The works of the Glasgow Iron Company, at St. Rollox and Motherwell are large establishments, with an aggregate of 87 puddling furnaces and 12 rolling mills, besides reheating furnaces, &c. The Saint Rollox Works is capable of producing from 100 to 200 tons per week, of hoops, bars, nails, rods and small

merchant iron. The works at Motherwell are capable of producing from 500 to 600 tons per week, of hoops, nails, rods, iron sheets, plates, rails, &c. These works were amongst the first in Scotland in which the regenerative furnaces of Dr. Siemens were employed. The Glasgow Ironworks, belonging to the same company, were established about the year 1845, and are capable of producing from 300 to 400 tons of finished iron per week.

The annexed table gives the names of the malleable ironworks in Scotland, the owners, the numbers of puddling furnaces and rolling mills, according to the last published return:—

SCOTLAND.

| No. | Name of Works. | Name of Firm. | Nearest Port or Railway Station. | No. of Puddling Furnaces. | No. of Rolling Mills. |
|-------------------|-----------------------------|----------------------------|----------------------------------|---------------------------|-----------------------|
| 1 | Blockhairn, St. } Rollox | Hannay & Sons. | Glasgow. | .. | .. |
| 2 | Clifton | John Wylie & Co. | Coatbridge. | 20 | 2 |
| 3 | Clydesdale | Clydesdale Iron Co. | " | .. | .. |
| 4 | Coats | Thomas Jackson | " | 7 | 2 |
| 5 | Coatbridge | Hugh Martin & Sons | " | 12 | 2 |
| 6 | Crown | William Tudhope | " | 19 | 2 |
| 7 | Dalzell | David Colville | Motherwell | 18 | 3 |
| 8 | Drumpeller | Henderson and Dimmock | Coatbridge | 6 | 1 |
| 9 | Globe | A. and T. Miller | " | 37 | 4 |
| 10 | Glasgow | Glasgow Iron Co. | Glasgow. | 50 | 6 |
| 11 | Motherwell | " | " | 6 | 2 |
| 12 | Millwood | John Alton & Co. | Holytown | .. | .. |
| 13 | Govan | William Dixon | Glasgow | 46 | 6 |
| 14 | Calder Bank | Monkland Iron and Coal Co. | " | 30 | 4 |
| 15 | Mossend | Mossend Iron Co. | Holytown | 9 | 4 |
| 16 | North British | Thomas Ellis | Coatbridge | 19 | 3 |
| 17 | Parkhead | W. and J. Beardmore | Parkhead | 11 | 2 |
| 18 | Phoenix | John Spencer | Coatbridge | 9 | 2 |
| 19 | Rochsolloch | Rochsolloch Iron Co. | Glasgow | 30 | 4 |
| 20 | Muirkirk | Eglinton Iron Co. | " | .. | .. |
| 21 | Excelsior | John Williams & Co. | Wishaw | .. | .. |
| Total of Scotland | | | | 320 | 51 |

For the manufacture of steel the Atlas Bessemer Steel Works of the Glasgow Company possess two converters, each of a capacity of 3 tons. The Steel Company of Scotland and the Moss End Iron Company, Holytown, being manufacturers of steel by the Open-hearth Steel Melting process.

An important addition to the steel industries of Scotland is recently announced in the opening of the Dalziel Steel Works, Motherwell. These extensive works, belonging to the firm of Mr. David Colville, have been in course of construction during the past twelve months, and commenced the manufacture of steel in February last. The works comprise 32 Siemens' gas producers, with large wrought-iron overhead conducting tubes for the gas.

One main leads to the melting department and another to the re-heating furnaces of the mill department. The melting shop contains four 12-ton Siemens' steel melting furnaces, capable of producing 500 tons of steel ingots weekly, and one accessory combined sand and manganese furnace. The ingots are handed over to the mill department by two steam cranes, capable of lifting 6 and 10 tons respectively. The ingots are then re-heated in two large gas furnaces and reduced from 14 inches thick to slabs of 4 or 5 inches in thickness by a powerful steam hammer, the cylinder of which is 33 inches in diameter, with an 8-foot stroke. The anvil consists of a huge iron casting weighing about 140 tons, mounted by a smaller one, with a steel face, in all weighing over 150 tons. The weight of the tap, piston and rod is 12 tons, and with a working steam pressure of 80 lbs. per square inch, the hammer is capable of giving a blow considerably over 400 foot tons.

The slabs thus consolidated are cut into sizes suited for the plates required, are again re-heated in other three large Siemens' gas furnaces, and then again passed through the plate mill. In a central position of the mill floor are placed a pair of powerful Ramsbottom reversing mill engines, the cylinders of which are 40 inches in diameter, stroke 4 feet 6 inches, and worked with 80 lbs. of steam. The engines are fitted with the Allan link motion, and are placed under the driver's easy control by means of steam and cataract reversing cylinders. On the right hand side of the driver is placed the plate mill, with two pairs of rolls, 8 feet long by 28 inches diameter, the one pair being chilled, the other grain, and capable of rolling plates up to 93 inches in width by almost any length and thickness. On the left hand side is placed a 27-inch bar mill, consisting of three pairs of rolls, and capable of rolling the heaviest sections of angle, bars, &c. Both mills, like the engines, are of the most massive proportions throughout, the forgings and gearing being almost wholly of Siemens' steel. The machine for shearing the plates to the exact dimensions required is also of a massive description, the steel shearing blades are 10 feet in length, with a stroke of 12 inches, and capable of shearing steel plates $1\frac{1}{2}$ inches in thickness by 7 feet broad, through at one stroke. The machine has also combined a scrap shears, and is driven by a combined steam engine of 16 inches cylinder by 20-inch stroke, working with 80 lbs. steam. There are four boilers for supplying steam

to the various machinery of combined flue and multitubular type, constructed entirely of Siemens' steel, and worked at a pressure of 80 lbs. The mechanical and chemical testing houses adjoin the works. The testing machine is capable of testing up to 50 tons on the piece, the whole operation being entirely done by steam power. The roofing covers an area of over 5,490 square yards, is constructed entirely of wrought iron and galvanised corrugated sheet iron covering, and is supported on cast-iron columns; the works occupying an area of about 14 acres of ground.

Production of Malleable Iron in Scotland.—The steady progress of this branch of industry will be seen in the annexed table, giving the returns for 15 years, also the average price of bars during the same period; side by side appears, in each of the same years, the average, highest and lowest prices of Scotch pig iron in the Glasgow market:—

| Year. | MALLEABLE IRON. | | | SCOTCH PIG IRON. | | | | | | |
|-------|-----------------|----------|----|------------------|----------|----|----------|---|---------|----|
| | Quantities. | Per Ton. | | | Average. | | Highest. | | Lowest. | |
| | Tons. | £ | s. | d. | £ | s. | d. | £ | s. | d. |
| 1864 | 163,500 | 8 | 12 | 6 | 2 | 17 | 4 | 3 | 4 | 10 |
| 1865 | 173,890 | 7 | 15 | 0 | 2 | 14 | 9 | 3 | 1 | 9 |
| 1866 | 155,231 | 7 | 15 | 0 | 3 | 0 | 6 | 3 | 18 | 2 |
| 1867 | 143,800 | 7 | 0 | 0 | 2 | 13 | 6 | 2 | 14 | 11 |
| 1868 | 179,626 | 6 | 15 | 0 | 2 | 12 | 9 | 2 | 13 | 8 |
| 1869 | 206,960 | 7 | 0 | 0 | 2 | 13 | 3 | 2 | 17 | 0 |
| 1870 | 199,353 | 7 | 10 | 0 | 2 | 14 | 4 | 3 | 0 | 0 |
| 1871 | 200,131 | 8 | 0 | 0 | 2 | 18 | 11 | 3 | 10 | 0 |
| 1872 | 223,377 | 12 | 5 | 0 | 5 | 1 | 10 | 6 | 9 | 3 |
| 1873 | 189,312 | 13 | 10 | 0 | 5 | 17 | 3 | 6 | 17 | 9 |
| 1874 | 180,000 | 10 | 15 | 0 | 4 | 7 | 6 | 5 | 6 | 3 |
| 1875 | 196,000 | 8 | 15 | 0 | 3 | 5 | 9 | 3 | 17 | 0 |
| 1876 | 236,000 | 7 | 15 | 0 | 2 | 18 | 6 | 3 | 4 | 8 |
| 1877 | 218,000 | 7 | 0 | 0 | 2 | 14 | 4 | 2 | 17 | 2 |
| 1878 | 195,000 | 6 | 10 | 0 | 2 | 8 | 5 | 2 | 11 | 0 |
| 1879 | 222,000 | 6 | 0 | 0 | 2 | 10 | 4 | 3 | 0 | 5 |
| 1880 | 292,000 | 6 | 0 | 10 | 2 | 14 | 6 | 3 | 13 | 3 |

The manufacture of malleable iron in Scotland is of comparatively recent date, the industry having been commenced in the neighbourhood of Glasgow about the year 1839; in 1845 the total production of the works amounted to but 35,000 tons, increased to 80,000 tons in the year 1850, and in the year 1861 to 122,500 tons; the average price of bar iron at this period

ranging as high as £7 per ton. In the year 1872, remarkable alike for the high prices which then ruled as well as for increased production, the make amounted to 223,377 tons, but even this was eclipsed in the year 1876, when the production increased to 236,000 tons, since which a slight falling off appears, until the year 1880, when the returns show a production of 292,000 tons, the largest on record.

Coal consumed in Malleable Ironworks in Scotland.—The quantities of coal used in these works in Scotland since the year 1872 has been as follows :—

| Year. | Coal Used. | Year. | Coal Used. |
|-------|------------|-------|------------|
| | Tons. | | Tons. |
| 1872 | 415,000 | 1876 | 439,720 |
| 1873 | 360,517 | 1877 | 411,854 |
| 1874 | 345,226 | 1878 | 370,985 |
| 1875 | 373,512 | 1879 | 409,527 |

And in the year 1880 the coal consumed in manufacture amounted to 537,508 tons.

Coal and Iron Ore used in Manufacture.—It is recorded in the survey of Ayrshire that towards the close of the last century on the estate of the Muirkirk Iron Company, 9 tons of coal was considered sufficient to make 1 ton of the best pig iron. Advancing to the year 1840, it appears on the authority of Mr. Porter, F.R.S.,* that the 241,000 tons of pig iron made in that year consumed 723,000 tons of coal in its manufacture, or 3 tons of coal to each ton of pig iron made. Again, in the years 1854 and 1860, economy appears in the consumption of materials employed, as shown in the annexed items :—

| Materials. | 1854. | 1860. |
|-------------------------|-------------|-------------|
| | Tons. Cwts. | Tons. Cwts. |
| Calcined ores | 1 12 | 1 14 |
| Large coal | 2 5 | 2 2 |
| Small coal | 0 16 | 0 10 |
| Limestone | 0 7 | 0 9 |

Mr. St. John V. Day, C.E.,† writing in the year 1876, referring to the Almond Ironworks, near Falkirk, gives some interesting facts showing the economy attained at these works. “The fur-

* “Progress of the Nation.”

† “Iron,” Dec. 2, 1876, p. 714.

nace has a height of 72 feet, and owing to the character of the coal at Almond a portion of it requires to be coked in order to get the furnaces to drive, and it is so used in the high as well as the low furnaces. The quantity of coal and coke used per ton of pig iron varies with the quantity of hard splint coal supplied from the pits. At the time referred to, the fuel used was half coal and half coke, and it appears that over a series of years, using the same burdens, the 72-foot furnaces had secured an economy to the extent of 10 cwt. of fuel to each ton of pig iron made, as compared with a furnace at the same works 50 feet in height. The average quantity of fuel, computed into coke, put in the 72-foot furnace, (blast heaters and boilers excepted), being $22\frac{1}{4}$ cwt. The ironstone (calcined) and ore being 37 cwt. per ton of pig."

"In the 50-foot furnace the consumption of coke was 29 cwt., and ironstone, $38\frac{1}{4}$ cwt. per ton of pig. The temperature of the blast at the Almond works is about 800° Fahr.; the average weekly make 200 tons. In the blast heaters the quantity of dross used is $4\frac{1}{2}$ cwt., and in the boilers for driving the blowing engines, $3\frac{1}{4}$ cwt. per ton of pig iron. The pressure of blast for the 50-foot furnace is 2.5 lbs. per square inch, and for the 72-foot furnace, from 3 to 3.25 lbs. per square inch."

While referring to the Almond Works we must not omit to notice the system of coking coal carried on there. "The novelty consists in forcing either heated or cold air into the space above the upper surface of the coal being coked, thus burning the gases inside the oven as they are evolved, and thereby promoting the coking process. In working these ovens they are charged and ignited in the ordinary manner, and so soon as the heat has evolved sufficient gas and ignited it, the air is turned on and continued in regulated quantity so long as gas is given off by the coal, care being taken that the mixture of air and gas shall always contain an excess of carbon, so as to prevent the ignition of that portion of the solid carbon which goes to form coke. In practice it is found that the quantity of air is always largest at the beginning of the charge and gradually diminishes to the close. So soon as the gas is all evolved the coke is either allowed to cool down, or is watered out and drawn."

The introduction of Ferrie's Patent has also greatly contributed to economy in the use of fuel; the process consists in dividing

the upper part of a blast furnace using raw coal into a series (about four) of vertical retorts, arranged with flues all round them, through which a portion of the gases pass and wherein they burn, the heat thereby developed being utilized in coking the coal and calcining the ironstone and limestone. In this manner it has been found practicable, not only to utilise all the waste gases from a blast furnace using raw coal, but owing to the frictional support which the materials receive in their descent from the sides of the retorts, Mr. Ferrie has succeeded in carrying a column of materials or burthen of about 88 feet in height. The results of Mr. Ferrie's observations on iron smelting in his furnace are thus referred to. He says, "The quantity of coal used to the ton of iron varies with the ores employed, but this quantity in practice is from 35 to 40 cwt. to the ton of iron. The quantity of coal increases as the quantity of black band in the charge decreases, and *vice versa*. When the quantity used to the ton is 35 cwt., the mixture of ores will be in the proportion of $\frac{2}{3}$ black band and $\frac{1}{3}$ clay band. An open furnace, 45 to 50 feet high, working on similar materials, will consume from 52 to 56 cwt. of coal to the ton of iron." In addition to the advantages claimed for the above arrangements, it is stated that, "In addition to the saving of coal noted above, that there is a saving of fuel in raising steam and heating the blast."

Before considering the total quantities of coal and ores employed in the furnaces of Scotland during the past ten years, the following reliable data presents some important details of the materials employed in the Gartsherrie Ironworks twenty years ago, when of the 16 furnaces built 14 were in blast, making 97,156 tons of pig iron, and consuming materials in the annexed quantities, to which is added the average quantity per ton:—

| Materials Used. | Quantities. | Average per Ton. | | | |
|------------------------------|-------------|------------------|-------|------|------|
| | Tons. | Tons. | Cwts. | Qrs. | Lbs. |
| Calcined ironstone | 162,784 | 1 | 13 | 1 | 15 |
| Coal | 278,983 | 2 | 17 | 1 | 0 |
| Limestone | 49,794 | 0 | 10 | 1 | 0 |
| Total materials | 491,561 | 5 | 0 | 3 | 15 |

In the Castlehill Ironworks of the Shotts Iron Company in the same year, the production of pig iron amounted to 13,673

tons, in the manufacture of which the following materials were employed :—

| Materials Used. | Quantities. | Average. | | | |
|----------------------------|-------------|----------|-------|------|------|
| | Tons. | Tons. | Cwts. | Qrs. | Lbs. |
| Coal used | 36,347 | 2 | 13 | 0 | 20 |
| Calcined clay band | 19,489 | 2 | 0 | 0 | 0 |
| „ black band | 6,941 | | | | |
| Hæmatite ore | 2,605 | 0 | 4 | 0 | 0 |
| Limestone | 8,918 | 0 | 13 | 0 | 0 |
| Total materials | 74,300 | 5 | 10 | 0 | 20 |

Another return, the aggregate of four ironworks in Lanarkshire, producing also in the year 1858, some 201,174 tons of pig iron, presents the following details; the works referred to at the time possessed 29 furnaces, of which 25 were in blast, consuming the materials given :—

| Materials Used. | Quantities. | Average. | | | |
|----------------------------|-------------|----------|-------|------|------|
| | Tons. | Tons. | Cwts. | Qrs. | Lbs. |
| Calcined ironstone | 351,452 | 1 | 13 | 3 | 20 |
| Coal | 544,873 | 2 | 14 | 0 | 0 |
| Limestone | 83,915 | 0 | 9 | 0 | 0 |
| Total materials | 980,240 | 4 | 16 | 3 | 20 |

It therefore appears from the above figures that in the year 1858 the proportions of materials employed were regular, the difference in the amount of calcined ironstone being due to the variable proportion in each case of black band and clay band ores. The loss by calcination of black band may be generally set down at 50 per cent., and of clay band ironstone at 90 per cent. The average yield of the furnaces per annum being respectively, Gartsherrie, 6,966 tons; Castlehill, 6,836 tons; and the Lanarkshire group of furnaces, 8,047 tons.

Mr. Ralph Moore, in his interesting paper on black band ironstone, read before the Royal Scottish Society of Arts in the year 1861, gives the average quantity of materials used to make a ton of pig iron as follows :—Calcined black band, 34 cwt., coals, 50 cwt., dross, 13 cwt. and limestone, 12 cwt., making in all a total of 109 cwt. of material to each ton of pig iron made.

Advancing to the year 1872, when information was obtained by the Committee of the House of Commons appointed to inquire into the causes leading to the extravagantly high price of coal ruling at that period, the following figures are available, showing the quantity of coal used in the manufacture of pig iron, to which is appended the total quantity of iron ore employed :—

| Year. | Pig Iron Made. | Coal Used. | Iron Ore Used. |
|-------|----------------|------------|----------------|
| | Tons. | Tons. | Tons. |
| 1872 | 1,090,000 | 3,215,000 | 2,325,000 |
| 1873 | 993,000 | 2,730,000 | 2,194,000 |
| 1874 | 806,000 | 2,143,199 | 2,035,000 |
| 1875 | 1,050,000 | 2,950,000 | 2,400,000 |
| 1876 | 1,103,000 | 3,050,000 | 2,575,000 |
| 1877 | 982,000 | 2,672,638 | 2,385,000 |
| 1878 | 902,000 | 2,244,813 | 2,490,000 |
| 1879 | 932,000 | 2,256,189 | 2,560,000 |
| 1880 | 1,049,000 | 2,542,055 | 2,628,610 |

The economy in the consumption of fuel has gone on steadily in the Scotch furnaces since the year 1872, when the average consumption of coal to each ton of iron made was 55 cwt., decreasing to 49½ cwt. in the year 1878, and 48½ cwt. in the years 1879 and 1880. The average consumption in Great Britain being 51 cwt. in 1873, decreasing in 1877 to 46 cwt.; in 1878 to 44½ cwt.; in the year 1879 to 44 cwt., and in 1880 to 43½ cwt.

The annexed table furnishes the approximate quantities of iron ore used in the blast furnaces of Scotland between the years 1872 and 1880, distinguishing the places from which it was received :—

| Year. | Scotland. | Foreign. | Lancashire. | Cumberland. | Ireland. | Total. |
|-------|-----------|----------|-------------|-------------|----------|-----------|
| | Tons.* | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1872 | 2,192,481 | 50,024 | 7,474 | 75,021 | ... | 2,325,000 |
| 1873 | 2,021,868 | 60,358 | 7,075 | 104,699 | ... | 2,194,000 |
| 1874 | 1,892,925 | 54,175 | 6,309 | 81,591 | ... | 2,035,000 |
| 1875 | 2,165,313 | 83,986 | 7,247 | 141,954 | 1,500 | 2,400,000 |
| 1876 | 2,345,432 | 73,367 | 7,699 | 146,723 | 1,779 | 2,575,000 |
| 1877 | 2,126,067 | 125,985 | 9,733 | 121,013 | 2,212 | 2,385,000 |
| 1878 | 2,371,762 | 61,168 | 5,731 | 49,859 | 1,480 | 2,490,000 |
| 1879 | 2,480,863 | 51,370 | 6,060 | 19,746 | 1,961 | 2,560,000 |
| 1880 | 2,430,000 | 134,267 | 16,542 | 44,820 | 2,981 | 2,628,610 |

* These quantities also include a small proportion of calcined stone, purple ore, and forge and mill cinder from the Malleable Iron Works.

Iron Shipbuilding.—There is yet another important branch of the iron industries of Scotland to refer to, that of iron shipbuilding. As soon as iron was found a suitable material for the construction of our mercantile marine, this industry soon attained immense proportions in Scotland, the banks of the Clyde being rapidly studded with iron shipbuilding yards. These yards may be said to commence at the termination of the quays and wharves of Glasgow, and they recur at intervals for miles along both banks of the river. The first application of iron to shipbuilding was in the construction of canal boats. Some half a century since the Horsley Company of Staffordshire constructed a sea-going steamer, and a few years later the same company constructed another vessel to ply on the river Shannon, in Ireland. It was not, however, till the year 1830 that the first iron steamer was constructed on the Clyde. This was the *Anglia*, of 80 tons burden, which plied on Lake Eck, *en route* to Inverary. The *Fairy Queen*, also of 80 tons burden, being the first iron steamer plying on the Clyde, was built in 1831. This last-named vessel was constructed in the Old Basin, some mile and a half distant from the Bromielaw, was launched into the Clyde, and propelled by an oscillating engine.

The *City of Glasgow* appears to have been the earliest example of the new form of iron ship of any size; this vessel was built in the year 1850, of 1,609 tons, and was propelled by a screw.

The earliest paddle steamer constructed of iron was the *Royal Sovereign*, of 447 tons, and plied between Glasgow and Liverpool, while of sailing ships, the *Iron Duke*, of 398 tons, was constructed about the year 1840, and sailed from Glasgow to India; and in the year 1842 the schooner-rigged sailing ship, *Glasgow*, of 100 tons, plied between the last-named place and Rotterdam, *via* the Forth and Clyde Canal.

The foregoing sketch shows the rise and progress of iron shipbuilding on the Clyde; it will be remembered, however, that this important industry is also pursued with vigour and success in Aberdeen, Dundee, Leith, and other places on the Fifeshire coast. For many of the above facts our acknowledgments are due to the interesting and historical paper on this subject by Mr. D. Rowan, of Glasgow, read at the Glasgow Meeting of the Iron and Steel Institute in 1872.

The remarkable development of this industry is due to the

boundless resources of coal and ironstone within easy distance of the Clyde; the iron ore being wrought, reduced to the metallic state, rolled and finished in those extensive works to which attention has been previously directed.

The earliest available statistics at hand showing the tonnage of iron vessels launched, and under contract, and on the stocks in the Clyde shipbuilding district, will be seen in the annexed table :—

| Year. | Tonnage Launched. | On Stocks and Under Contract. | Year. | Tonnage Launched. | On Stocks and Under Contract. |
|-------|----------------------|----------------------------------|-------|----------------------|----------------------------------|
| | Tons. | Tons. | | Tons. | Tons. |
| 1863 | 124,000 | 140,000 | 1872 | 230,347 | 247,345 |
| 1864 | 178,505 | 105,957 | 1873 | 232,926 | 192,608 |
| 1865 | 153,932 | 109,404 | 1874 | 266,800 | ... |
| 1866 | 124,513 | 71,869 | 1875 | 228,200 | ... |
| 1867 | 108,024 | 124,082 | 1876 | 204,770 | ... |
| 1868 | 169,571 | 134,818 | 1877 | 168,000 | ... |
| 1869 | 192,310 | 140,199 | 1878 | 215,640 | ... |
| 1870 | 180,401 | 180,175 | 1879 | 174,570 | ... |
| 1871 | 196,229 | 301,809 | 1880 | 236,579 | ... |

The Clyde owes much of its prosperity to the invention of the dredging machine, and the shipbuilders on its banks do a considerable trade in building dredges and numerous appliances for improving navigation. It may be further added, that though the practicability of constructing vessels of iron had been successfully tested, it was not until the year 1838 that it was used in the hull of any vessel of large size.

CHAPTER XXII.

IRON INDUSTRIES OF IRELAND.

Description of the Ironstone Measures of the Northern Coal-fields, Leitrim, Tyrone, Antrim—Analyses and Production of Coal—Southern Coal-fields, Leinster, Castlecomer, Kilkenny—Analyses and Production of Coal—Iron Ore Deposits (Tertiary Age) county Antrim—Magnetic Ores, county Wicklow—Ores of county Cavan—Analyses and Production of Ore—List of Iron Mines in 1880, and details of Production—Pig Iron Manufacture—Works at Drumshambo—Account of the Arigna Iron Works—Materials employed in Manufacture—Production of Pig Iron in 1856.

Iron Industries, Northern Districts (*Leitrim, Tyrone, and Antrim*):—**Ironstone Measures of the Leitrim Coal-field.**—Sir Robert Kane * refers to the "Iron Mountain (Slieve-a-Nierin), on the eastern shore of Lough Allen, as a hill of considerable elevation, and describes it as consisting of alternate beds of sandstone and slate clay, resting upon the basis of the upper limestone. The great bed of slate clay varies from 300 to 500 feet in thickness. In this clay the nodules of ironstone are disseminated in abundance, and the rains washing away the softened and decomposing clay, the balls of iron ore are carried down to the shore of the lake, whence, and from the beds of the rivulets, they are collected by the peasantry and brought to the works for use. At the base of this mountain on the eastern side of the outlet of the lake lies Drumshambo, where this ore was formerly smelted." In purity this ore is said to be somewhat superior to that which is found on the western side.

The stratification of the country on the western side of Lough Allen in the Arigna district is similar to that already described in the Iron Mountain, "Resting on the limestone of the surrounding country occurs the great bed of slate clay, 600 feet in thickness, which contains numerous beds of ironstone from half an inch to two feet in thickness. Their number is, as Sir R. Griffith mentions, almost incredible, but the most important occur from

* "Industrial Resources of Ireland," 2nd edit., p. 133.

200 to 300 feet above the limestone, while the thin beds are described as being in most cases the best; that of Altagowlan, which is a foot thick, was amongst the richest ironstone Sir R. Griffith ever saw. The usual form is that of nodules, in size from an egg to that of a bull's head, but it forms also strata or sheets of considerable extent."

In a report on the Arigna district in 1880, made to the Directors of the Company by Mr. Twigg, that gentleman observes, "The ironstone mines have been examined and the result found extremely favourable. A greater variety of ironstones I never met with, from which, by a proper admixture and good management, I have no hesitation in saying that pig iron of best marks, and fit for foundry work of every kind, may be obtained. The iron mines begin in Rover and continue for two miles and a half. I measured several of the beds to more than two feet thick, in some places laid bare in the ravines, and in the bed of the Arigna river we can get any quantity at the shortest notice." *

Analyses of the Ironstones.—The annexed analyses of numerous specimens obtained from different portions of the Arigna district, appear in their detailed character and composition as follows:—

CLAY IRONSTONE NODULES FROM ARIGNA.†

| Constituents. | No. 1. | No. 2. | No. 3. |
|---------------------------------|--------|--------|--------|
| Protoxide of iron | 53·65 | 54·42 | 51·52 |
| Lime | ... | 2·23 | 0·69 |
| Magnesia | ... | 2·02 | 1·55 |
| Alumina | 1·00 | 1·43 | ... |
| Insoluble clay | 12·43 | 8·65 | 15·50 |
| Carbonic acid | 32·92 | 31·25 | 30·74 |
| Total | 100·00 | 100·00 | 100·00 |
| Loss by roasting | 31·50 | 30·90 | 30·70 |
| Metallic iron per cent. | 41·70 | 42·30 | 40·00 |

Of the veins of ironstone two specimens were analysed, taken *in situ*; they gave:—

* "Industrial Resources of Ireland," 1845, 2nd edit., p. 135.

† *Ibid.*, p. 135.

| Constituents. | No. 4. | No. 5. |
|----------------------------------|--------|--------|
| Protoxide of iron | 47·28 | 49·94 |
| Lime | 1·26 | 3·75 |
| Magnesia | 2·23 | 3·79 |
| Alumina | 1·59 | 0·87 |
| Insoluble clay | 18·46 | 9·08 |
| Carbonic acid | 29·18 | 32·57 |
| Total | 100·00 | 100·00 |
| Loss by roasting | 32·14 | 29·80 |
| Metallic iron, per cent. | 37·70 | 38·80 |

Sir Robert Kane adds that, as none of these were picked specimens, the average of all of them may be fairly calculated as the material available on the large scale at Lough Allen, and the mean of the above five analyses gives:—

RESULTS TABULATED.

| | |
|----------------------------------|--------|
| Protoxide of iron | 51·36 |
| Lime | 1·59 |
| Magnesia | 1·92 |
| Alumina | 0·98 |
| Insoluble clay | 12·82 |
| Carbonic acid | 31·33 |
| Total | 100·00 |
| Loss by calcining | 31·33 |
| Metallic iron, per cent. | 40·00 |

It therefore appears that these ironstones are equal to the best argillaceous ores of South Staffordshire, or South Wales, and are only surpassed by the Black Bands of the Clyde valley in Lanarkshire.

Ironstones of the Tyrone Coal-field.—In the shales and fine clays of the middle series of coal measures of Dungannon there is a good deal of ironstone occurring both in beds and nodules; the former, in one or two instances, from one to two feet thick, the latter abundant. None of them have been worked to any extent, so far as is known. They have the usual composition of clay ironstones, and contain about the average per-centage of iron. Traces of an old furnace are found in the townland of Derry near the road leading from Derryvale to Stewartstown, and a quantity of slag lies about. It is possible, therefore, that some of the

ironstones above the Derry coal were formerly smelted. Mr. Hardman, who has examined some of them, both for the amount of iron, and the presence or absence of sulphur and phosphorus, gives the annexed results. The specimens were all obtained from the neighbourhood of Coal Island :—*

ANALYSES OF IRONSTONES, DUNGANNON COAL-FIELD.

- No. 1. Thin seam of ironstone from above the Shining Seam.†
 Metallic iron 35·50 per cent.
 Neither sulphur nor phosphorus present.
- No. 2. Ironstone nodules from Gortnaskea Coal.
 Metallic iron 34·40 per cent.
 Neither sulphur nor phosphorus present.
- No. 3. Ironstone nodules above Beltiboy Coal.
 (a) Metallic iron 32·50 per cent.
 Neither sulphur nor phosphorus.
 (b) Metallic iron 21·70 per cent.
 No sulphur; a trace of phosphorus.
 (c) (?) Black Band Ironstones.
 Metallic iron 23·50 per cent.
 No sulphur; a trace of phosphorus.
- No. 4. Iron nodules from Derry Coal.
 Metallic iron 28·80 per cent.
 No sulphur; no phosphorus.

Ironstone of the Antrim Coal-field.—This coal-field contains an important measure of Black Band raised in notable quantities and exported to Scotland in the calcined state. "The ironstone occurs in the lower beds of the carboniferous series. These beds consist of red and yellow sandstones, sometimes coarse, with beds of shale, the base of the series being a quartzose conglomerate reposing upon contorted mica-schist with veins of quartz." † Analyses of the Ballycastle Black Band is not at hand; the composition, however, of one or two varieties raised extensively in Lanarkshire will show the constituents of these ores. The average yield of the Black Bands of the Clyde district may be taken at 31·60 per cent. in the raw, and 45·80 per cent. in the calcined state; Mushet's Black Band giving in the raw state 41·00 per cent. of metallic iron, increased to 63·10 per cent. in the calcined state :—§

* "Proceedings of the Royal Irish Academy," Second series, vol. ii., p. 537.

† The term "Shining Seam," is usually applied to "Micaceous Iron Ore."

‡ "Coal-fields of Great Britain," 4th edition, p. 339.

§ "Industrial Resources of Ireland," 1845, 2nd edition, p. 27.

| Constituents. | Cross Basket Ironstone. | Mushet's Black Band. |
|---------------------------|-------------------------|----------------------|
| Protoxide of iron | 42·15 | 53·03 |
| Lime | 4·93 | 3·33 |
| Magnesia | 4·80 | 1·77 |
| Silica | 9·73 | 1·40 |
| Alumina | 3·77 | 0·63 |
| Bituminous matter | 3·12 | 3·03 |
| Carbonic acid | 31·50 | 35·17 |
| Moisture and loss | ... | 1·41 |
| Peroxide of iron | ... | 0·23 |
| Total | 100·00 | 100·00 |

Ireland, Southern Districts.—Ironstones of the Leinster Coal-field.—The ironstones of this coal-field are fairly illustrated by the following description and analysis of ironstone raised from the Castlecomer Collieries of Mr. Wandesford :—* “The colour is dark grey when fresh, but becoming rust-coloured by long exposure to the air. The specific gravity is about 3·250. When ignited it loses 29 per cent. of its weight, and the residue is strongly attracted by the magnet.” Two different specimens give the annexed results :—

| Constituents. | First. | Second. |
|---------------------------|--------|---------|
| Protoxide of iron | 51·08 | 48·03 |
| Lime | ·16 | 1·51 |
| Magnesia | 1·05 | 4·24 |
| Alumina | 1·86 | 1·45 |
| Insoluble matter | 13·92 | 16·17 |
| Carbonic acid | 31·93 | 28·60 |
| Total | 100·00 | 100·00 |
| Metallic iron | 39·70 | 37·60 |

It is remarked of these ironstones that as they were not selected for analysis on account of any apparent superiority to other specimens, they may probably represent the ordinary run of the ironstone of the Leinster district.

Iron Ore Deposits of the County Antrim.—The most important deposits of iron ore in Ireland now in process of development are situated in the county Antrim. For an account of the area including these deposits we reproduce an interesting paper

* “Industrial Resources of Ireland,” 1845, 2nd edition, p. 132.

by Mr. J. D. Kendall, C.E., F.G.S., on the "Iron Ores of Antrim :—"

"The north-east corner of Ireland, that occupied by the county Antrim, is almost entirely covered by a sheet of basalt, varying in thickness from a few feet to upwards of a thousand feet. This basalt rests upon chalk, and is supposed, from the nature of the fossil plants yielded by it, to be of Miocene age. The following generalised section of the rocks in the county of Antrim will show its relative position in the geological scale :—

| SYSTEM. | CHARACTER OF ROCK. |
|-------------------------|-----------------------------------|
| Tertiary | Basalt. |
| Cretaceous | { Chalk. |
| | { Greensand. |
| Oolitic | Wanting. |
| Jurassic | Lower lias shales. |
| Triassic | { Variegated marls, &c. (Keuper). |
| | { Sandstone (Bunter). |
| Permian (?) | Magnesian limestone, &c. |
| | { Coal measures. |
| Carboniferous | { Carboniferous limestone. |
| | { Carboniferous slates. |
| Devonian | Red sandstone and conglomerate. |
| Silurian | Wanting. |
| Cambrian | Mica slate. |

"Generally, the basalt may be divided into three classes—the amorphous, the columnar, and the concretionary—the second of which is well known to all who have visited the Giant's Causeway, on the north coast. The amorphous and concretionary varieties may also there be seen, between and below the tiers of columns.

"Although the basalt is not a sedimentary rock, yet it shows evident traces of bedding, as will have been noticed by all who have been along the Causeway coast. The basalt there exhibits two fine parallel tiers of columns, which have a gentle inclination inland. The lower tier, as it crops out at one point, forms the celebrated Giant's Causeway. Between and below the columns, the basalt has quite a bedded appearance, the beds being parallel to those exhibiting the columnar structure, that is dipping inland.

"**Mode in which the Ores occur and their Nature.**—Interstratified with the basalt, and parallel to the bed planes thereof, are a number of ferruginous clayey bands, of reddish appearance, which may be distinctly seen along the coast cliffs, presenting a

* "Colliery Guardian," 27th October, 1876, p. 637.

striking contrast to the basalt. The precise number of these bands is not known, but there are as many as five in some parts of the field, and there may be more. They occur one above the other, like seams of coal, at variable distances apart. Usually they consist of a ferruginous clay, called "bole," with an underlying layer of lithomarge. But there is one of the seams, which, in addition to these two materials, contains, above the bole, a thin band of iron ore, of a pisolitic nature. This is the most important band in the series. From it is obtained that ore of iron, which passes by the name of Irish ore. It occurs below the bottom tier of columns, and appears to be the highest of the series of ferruginous bands. It may be seen in the cliffs near the Giant's Causeway, and is found nearly all over the county. The following section of it will explain its nature, and show the relation it has to the basalt above and below it:—

| | | |
|------------------|---|---|
| BOOF OF SEAM. | { | <i>Columnar basalt.</i> —Lower tier. <i>Clay.</i> —Slate coloured, passing imperceptibly into the overlying basalt. Its thickness is very irregular, and it peels off the basalt in laminæ parallel to the sinuosities of the under surface thereof. |
|------------------|---|---|

"**Pisolitic Bed.**—This bed, which varies in thickness from a few inches to between 2 and 3 feet, consists of a soft, brown, or reddish-brown ferruginous ochre, in which are thickly embedded small dark grey irregular pieces of harder ore, which are strongly attracted by the magnet. The junction between this bed and the overlying clay is very distinct, and they separate easily. Pieces of fossil (coniferous) wood have been found in it, the tissue replaced by iron ore.

"**Bole.**—A yellowish-red ferruginous ochre containing a number of concretionary nodules of basalt. Not hard, and breaking up into irregular cuboidal pieces. The junction between this rock and the overlying ore is not very distinct. Thickness, usually 5 to 10 feet.

"**Lithomarge.**—A variegated soft rock of a prevailing blue slate colour. Like the bole, it contains concretionary nodules of basalt, but more of them. The line separating this bed from the bole is not very distinct. Sometimes this bed is nearly 80 feet thick:—

| | | |
|---------------------|---|---|
| SOLE OF SEAM. | { | <i>Concretionary basalt</i> passes gradually into the overlying lithomarge. |
|---------------------|---|---|

"The extent of the pisolitic bed is not known, but it must cover some thousands of acres, although it does not occur everywhere within the basaltic area. In many places it has been removed by denudation, being found in the hills, but absent in the intervening valleys. The breach of continuity thus brought about is further increased by the numerous faults and dislocations that traverse the country.

"It is possible that there may be more than one pisolitic bed, that the seams which have been worked by the different mining companies in the county may not be portions of one original seam as is generally supposed, but may belong to different seams. So far, however, as is at present known, they appear to be parts of the same seam.

"The quality of the pisolitic ore is very good, as shown by the following analyses of ore worked at Red Bay by the Glenariff Iron Ore and Harbour Co., at Cargan and Broughshane by the Antrim Iron Ore Co., and at Slievenanee by Messrs. Fisher and Co.:—

ANALYSES OF PISOLITIC ORE.

| Constituents. | Red Bay. | Red Bay. | Cargan. | Broughshane. | Knockboy. | Slievenanee. | Slievenanee. |
|------------------------------|----------|----------|---------|--------------|-----------|--------------|--------------|
| Peroxide of iron . . . | 59.40 | 77.22 | 66.56 | 65.42 | 63.70 | 71.00 | 81.50 |
| Protoxide of iron . . . | .. | .. | .. | .. | .. | 18.00 | .. |
| Oxide of manganese . . . | .. | .. | 0.11 | trace | .. | trace | 2.57 |
| Titanic acid | .. | .. | 3.68 | 5.28 | 4.60 | .. | trace |
| Vanadic acid | .. | trace | .. | .. | .. | .. | .. |
| Alumina | 2.80 | .. | 7.92 | 12.54 | 12.75 | .. | 4.20 |
| Silica | 10.40 | 20.65 | 5.47 | 7.08 | 6.30 | 9.00 | 5.50 |
| Sulphur | .. | .. | 0.03 | trace | 0.02 | .. | .. |
| Phosphorus | .. | .. | trace | 0.02 | 0.06 | .. | .. |
| Magnesia | .. | .. | 0.16 | 0.08 | 0.05 | .. | .. |
| Lime | .. | .. | 0.68 | 0.20 | 0.10 | .. | 0.03 |
| Water of combination . . . | 8.40 | 2.13 | 14.34 | 8.82 | 12.70 | .. | 1.06 |
| Per-centage of metallic iron | 41.58 | 54.05 | 46.61 | 45.99 | 44.60 | 63.70 | 65.30 |
| Analyst | Apjohn. | Cameron. | Tosh. | Tosh. | Tosh. | Cameron. | Hodges. |

"The average amount of metallic iron contained in the above seven varieties of pisolitic ore is equivalent to 51.70 per cent., compared with 28.85, the average of the four following analyses of bole.

"The bole as a rule yields less than half as much iron as the pisolitic ore. The following are analyses of samples taken chiefly from the bole, but having a slight admixture of the pisolitic ore. The yield of iron is consequently higher than could be obtained from an unmixed sample of bole:—

ANALYSES OF BOLE.

| Constituents. | Kilwaughter. | | Glenarm. | Tully. |
|--------------------------|--------------|----------|----------|----------|
| Peroxide of iron | 41·00 | 45·00 | 33·34 | 45·50 |
| Oxide of manganese . . . | ... | trace | ... | trace |
| Titanic acid | 0·50 | 36·44 | 5·31 | 2·00 |
| Alumina | 51·00 | | 41·13 | 35·50 |
| Silica | 1·00 | | 3·78 | 4·00 |
| Magnesia | trace | 2·44 | 0·97 | ... |
| Lime | 0·50 | 0·56 | 0·21 | 0·35 |
| Sulphur | ... | ... | trace | ... |
| Phosphorus | ... | ... | 0·04 | ... |
| Water of combination . . | 6·00 | 18·00 | 15·55 | 12·65 |
| Total | 100· | 102·44 | 100·33 | 100· |
| Metallic iron | 28·70 | 31·50 | 23·34 | 31·85 |
| Analyst | Cameron. | Cameron. | Toosh. | Cameron. |

"The main difference between the pisolitic ore and the bole is, according to these analyses, in the greater quantity of iron and less quantity of alumina contained by the former. The yield of iron by the lithomarge is too small to render it of any value for iron making.

"Origin of the Deposits: Lithomarge and Bole.—The way in which the bole and lithomarge have been produced seems to be rendered very clear by the presence of the concretionary nodules. The graduation from bole to basalt, and from lithomarge to basalt, in the two sets of nodules, leaves no doubt that both these beds are the result of metamorphic action on basalt.

"The appearance presented by these nodules cannot possibly be explained on any other assumption than that both bole and lithomarge are metamorphosed basalt. But whether the rock from which they were produced, was exactly alike in chemical constitution to the basalt now above and below them, it is impossible at present to say, as, indeed, it is also to say whether they both have been produced from the same sort of rock, or from two chemically different rocks. The probability is that they were formed from beds of rock chemically different. If not, and they were both subjected to the same sort of metamorphism, then the two beds must represent two different stages of the process. But if bole be metamorphosed lithomarge, that is, if it has undergone a higher degree of metamorphism than lithomarge, we should

find in the concretionary nodules of the bole a transition from basalt to lithomarge in the first place, and then from lithomarge to bole; in other words, between the bole and basalt we ought to find a layer of lithomarge, but we do not—at least I have not. Then again if lithomarge is altered bole, we should find in the concretions of the lithomarge bed a layer of bole immediately round the basalt, which we do not. This inclines me to the idea that the bole has been produced from a bed of rock (basalt) having a different composition from that which has been altered to lithomarge. A fact which may throw some light on the mode of metamorphism may be observed in connection with the bed of clay lying between the pisolitic bed and the overlying basalt. This clay, I believe, is also metamorphosed basalt, for there is a most gradual laminated passage from hard basalt to soft clay.

“The fact I refer to is that whenever the clay bed crops out to day it appears to thicken, which seems to indicate that whatever was the metamorphic influence, it acted more powerfully than at any other point.

“**Pisolitic Bed.**—This bed has been variously accounted for; some have supposed it to be of igneous origin, others consider that it is metamorphosed bole, whilst not a few are of opinion that it had an aqueous origin. The fact already pointed out that fossil wood has been found in the bed seems to favour the last idea. It clearly precludes the possibility of the first and second. Besides if this ore is the result of metamorphic action on the bole, why do we not find the same sort of ore accompanying the other bole beds? They were all alike overlaid by a bed of basalt, which, according to the holders of this theory, had a considerable influence in altering the bole into ore.

“The precise mode of deposition usually advocated by those who believe in the aqueous origin of this bed, is the sedimentary. But that, I think, is scarcely reconcilable with the facts. The freedom of the ore from the mechanical admixture of other rocks seems to me alone a sufficient argument against any theory which would account for its deposition in that way.

“The most likely mode of origin appears to be that of precipitation from a chemical solution, possibly by organic agency, but not necessarily so. On that supposition the absence of foreign matter, such as would almost assuredly have been present had the bed been of sedimentary origin, offers no difficulty, whilst the occurrence of

the wood is as easily explained as by the sedimentary theory. And if we suppose that the bed of rock (basalt) from which the bole was produced was in a comparatively soft and decomposed state, at the time the ore was deposited, we have a probable explanation of the fact, already stated, that the junction between the ore and bole is not very distinct. Some of the first precipitated ore would almost certainly find its way into the decomposed bed below, the effect of which would be to produce the appearance of a regular transition from iron ore to bole. The pisolitic condition of the ore is probably due to the influence of the overlying lava whilst in a heated condition.

“Working the Deposits.—The geographical conformation of the area covered by the basalt is such as to render the working of the iron deposits a matter of great simplicity. The seam (assuming that there is only one) is usually found cropping out on the hill sides and lying nearly level. It is in consequence worked by day levels. No shafts are required, nor any pumping machinery, the water being carried off by the levels. The ore is soft and easily worked, whilst the roof is strong and good, so that very little timber is required. All that is used is obtained from the immediate neighbourhood at a very low price. In addition to all these advantages wages are low; so that the working expenses of a mine are very light. The greatest drawback to the working of these mines is their distance from port, some of them being so far away that the ore costs 3*s.* or 4*s.* or more per ton for carriage. In some cases, too, the pisolitic ore is not more than a foot in thickness, so that a portion of the bole has to be worked away with it, and it is only in good times that much of this bole can be sold, so that the necessity to work it whether it can be sold or not, increases, as a consequence, the cost of getting the pisolitic ore. But for these two circumstances Irish ore would occupy a much more important position in our market than it does.”

The area of the county Antrim occupying the ferruginous deposits extends on the north-east coast from Cushendall to Carrickfergus, and inland from two to ten miles. From this area for some years past the mines have furnished the great bulk of the iron ore raised in Ireland.

At Evishacrow, between Ballymena and Cushendall, in the county Antrim, hematitic iron ore is wrought in some quantities. A section of strata at these mines presents the following stratified

beds : at the surface appears basaltic rock reposing upon a seam of iron ore known as pisolitic or "shot ore," and having an average thickness of some 18 inches ; this ore consists of nodules of almost pure oxide of iron, varying in size from the head of a pin to a small nutmeg, and embedded in a soft ochreous matrix or paste. Locally it has received the appropriate name of shot ore. Next in descending order occurs a bed of aluminous ore, varying in thickness from 4 to 6 feet, and containing 22 per cent. of metallic iron ; this is advantageously employed in the blast furnace as a flux. Beneath the aluminous ore occurs a deposit of blue lithomarge found in thickness varying from 25 to 35 feet.

The ferruginous deposits of the Evishacrow mines occur at an elevation of 870 feet above the level of the sea, the strata dipping gently to the south-west.

The mode of working these mines, like others in the district, is by driftways driven in from the mountain side at the outcrop of the deposit. The headings are pushed forward to the north-east, following the rise of the pisolitic deposit, which affords a gentle incline to the mouth of the workings, thus facilitating the running out of the loaded corves. This inclination also allows the mine waters to get away easily by gravitation, a very effective natural drainage being thus formed. The roof of the mine is self-supporting, no timbering being used in the workings beyond the first 13 fathoms or so in each of the drifts. The mode of working is the long wall system, the ore is easily won, and does not require blasting, being brought away easily with the pick ; it is of singular purity, having no trace of either sulphur or phosphorus. This class of ore is extensively used in steel making. The mines are connected by a branch with the Ballymena, Cushendall, and Red Bay Railway, which enables the ore to be sent either to Belfast or Larne for shipment, from which latter port considerable quantities are shipped, the port having been lately greatly improved, and recently connected with the Ballymena and Larne Railway.

The royalty under which the workings at Evishacrow are carried out covers an area of 800 acres, and it is estimated that iron ore exists under the greater part of this area. Dr. Percy, to whom samples of the ore was submitted, gives the following analysis, showing its composition per cent. :—

RESULTS TABULATED.

| | |
|----------------------------------|--------|
| Peroxide of iron | 75·51 |
| Protoxide of iron | 2·92 |
| Protoxide of manganese | 0·24 |
| Lime. | traces |
| Magnesia | traces |
| Alumina | 3·14 |
| Silica | 5·54 |
| Titanic acid | 9·50 |
| Combined water | 2·00 |
| Hygroscopic water | 1·32 |
| Phosphorus | none |
| Sulphur | none |
| Total. | 100·17 |
| Metallic iron, per cent. | 55·13 |

Dr. Percy adds, "The ore is *remarkably* free from phosphorus and sulphur, and will yield pig iron very suitable for conversion into steel by the Bessemer process. The presence of titanic acid will not injuriously affect the quality of the pig iron, for some of the best Swedish bar iron is made from ore rich in titanic acid. The ore may be regarded as rich, and in that respect is equal to the average of the red hematites."

The mines of the Antrim Iron Ore Company, situated at Broughshane, Cargan, Carnlough, Glenarm, and Newton Crommellin, are of considerable extent, and yield large returns. The pisolitic ore here wrought is found, as in the districts previously referred to, in beds varying from 15 to 24 inches in thickness, and beneath basaltic rock which reposes upon it. A bed of aluminous ore occurs below the pisolitic ore, but it is only worked to a limited extent from the circumstance of its being less rich in metallic iron than the pisolitic ore. Lithomarge is also met with of a prevailing blue colour, in a bed of considerable thickness, and, like the aluminous ore, it is not extensively worked, as it is too poor in metallic iron to render it of value for iron making. The deposits in the above-named localities lie some 600 or 700 feet above the level of the sea.

The constituents of these ores, rich in alumina, varying from 30·00 to 34·55 per cent., from the mines of Glenarm and Carnlough, are as follows:—*

* Favoured by Silas Evans, Esq., of Belfast.

| Constituents. | Glenariff. | Carnlough. | Carnlough. |
|--------------------------------|------------|------------|------------|
| Peroxide of iron | 50·23 | 29·88 | 24·75 |
| Protoxide of iron | 1·03 | 1·99 | 0·72 |
| Protoxide of manganese | 0·44 | 0·24 | 0·35 |
| Alumina | 30·00 | 33·69 | 34·55 |
| Lime | 0·29 | 0·92 | 0·77 |
| Magnesia | 0·26 | 0·16 | 0·27 |
| Silica | 9·50 | 11·58 | 5·10 |
| Titanic acid | 0·70 | 0·74 | 1·15 |
| Sulphuric acid | ... | trace | ... |
| Phosphoric acid | ... | ... | ... |
| Water { hygroscopic | 2·51 | } 21·65 | 32·48 |
| { combined | 5·13 | | |
| Total | 100·09 | 100·85 | 100·14 |
| Metallic iron | 35·96 | 22·47 | 17·89 |
| Analyst | Heywood. | Tosh. | Tosh. |

Mr. Charles A. Heywood, public analyst of Whitehaven, who examined the Glenariff ore, remarks of it, "That it contains a high per-centage of metallic iron, some manganese, and no sulphuric or phosphoric acids. It is of great use on account of its containing an excess of alumina, as a flux in the blast furnaces using siliceous red hematites. The per-centage of water is very small, the ore is hard, and will bear a heavy burden in the furnace."

The deposits worked at the Glenariff mines situated near Cloughor, in the county Antrim, by the Glenariff Iron Ore and Harbour Company, Limited, are thus described by Mr. Philip Argall, captain of the mines: "The iron ore measures of the Glenariff valley are found interstratified with igneous rocks (dolerites, basalts, and tuffs) of tertiary age."

At the mines now working the iron ore the measures are about 70 feet thick, and are found to rest on about 400 feet of dolerite, being covered by about 300 feet of a similar rock; these measures or ores may be divided into four classes as follows: "Lithomarge,"* "Pavement," Aluminous Ore (Ball or Second Ore), and Pisolitic Hematite or First Ore.

The lithomarge varies from 40 to 45 feet thick, and contains from 15 to 20 per cent. of metallic iron, and 80 per cent. of

* "Lithomarge." A silicate of Alumina. In many respects resembling Kaolin, or China clay. In this instance it appears to bear a local signification.

alumina; it varies in colour from light lavender to black, and is often liver coloured, or bluish with white spots.

Analysis of the lithomarge above referred to is not available. A continental variety, however, rich in alumina, will show its general composition.*

| CONSTITUENTS. | |
|----------------------------|--------------|
| Silica | 49·20 |
| Alumina | 36·20 |
| Peroxide of iron | 0·50 |
| Water | 14·00 |
| Total | <u>99·90</u> |

Resting on the lithomarge is a yellowish ochreous rock, called "pavement" by the miners, as it forms the floor or pavement of the first and second ores; this rock varies in thickness from 15 to 20 feet, and contains from 20 to 25 per cent. of metallic iron, and about 30 per cent. of alumina.

The aluminous ore (second ore) is generally found resting on the "pavement," but it frequently occurs in beds of from 4 to 5 feet in thickness, interstratified with the lithomarge and pavement. The aluminous ore is of a light red colour, and is brittle though soft, and contains from 25 to 30 per cent. of metallic iron, and from 35 to 40 per cent. of alumina; this ore is sometimes called *bauxite*: where it occurs immediately under the pisolitic ore it usually has a few pisolites of the former disseminated through it.

Overlying the aluminous ore, or where it is absent, is found the pisolitic, or first ore; this is covered by the hard dolerite roof, and separated from it by a few inches of steatitic clay.

The pisolitic ore varies from 12 to 20 inches, and sometimes swells from 24 to 30 inches in thickness, and is usually found best developed at the top of the seam which is the richest part. The ore is also found to vary in colour from red through brown to black, the latter being most abundant at the Glenariff mines. The black ores usually contain from eight to ten per cent. of titan acid, and are regarded as the richest and purest to be found in the county. The first two ores, examined by Mr. E. W. J. Jones, public analyst of Wolverhampton, give the following results:—the first a pisolitic ore, the second an aluminous ore.†

* "Glossary of Mineralogy." H. W. Bristow, F.R.S., p. 221.

† Favoured by John Ham, Esq., Secretary of the Glenariff Iron Ore and Harbour Company, Limited.

The third analysis of best Glenariff ore is by Mr. A. B. Cowan.

RESULTS TABULATED.

| Constituents. | First. | Second. | Best Ore. |
|----------------------------------|--------|---------|-----------|
| Combined water | ... | 10.23 | 1.88 |
| Peroxide of iron | 71.64 | 35.93 | 62.43 |
| Protoxide of iron | 1.88 | trace | 4.75 |
| Protoxide of manganese | 0.27 | 0.11 | 0.28 |
| Alumina | 4.25 | 36.50 | 10.19 |
| Silica | 5.05 | 12.20 | 8.40 |
| Lime | 0.81 | 0.53 | 2.80 |
| Magnesia | 0.61 | 1.41 | 0.59 |
| Phosphoric acid | 0.20 | trace | nil |
| Sulphuric acid | nil | nil | nil |
| Carbonic acid | trace | nil | trace |
| Pyrites | nil | nil | ... |
| Titanic acid | 8.89 | nil | ... |
| Moisture at 100 C. | 6.40 | 2.76 | 8.48 |
| Loss, &c. | ... | 0.33 | ... |
| | 100.00 | 100.00 | 99.80 |
| Metallic iron per cent. | ... | 25.15 | 47.40 |

The iron ore and "bauxite" deposits worked by the Irish Hill Mining Company at their Irish Hill and Straid Mines, situated near Ballyclare, possess some interesting features; they were discovered some 5 or 6 years since by Mr. Alexander Sutherland.* The bauxite is believed to be the largest deposit of that ore hitherto discovered in this country. The rocks of the surrounding district are basalt, trap, and porphyry. The iron ore exists in conformable strata, not unfrequently with very little rise or dip, and the best qualities are found close to the basalt which forms the roof of the level drifts and workings in the above-named mines. The strata containing the iron ore is divided into three distinct layers or seams; the first, nearest the roof or base of the basalt, is from 1 to 2 feet 6 inches thick of pisolitic ore, containing 60 per cent. of peroxide of iron. The second seam beneath the first, is 3 feet thick, and contains 40 per cent. of peroxide; the third or lowest seam in the series is lithomarge, which is often 20 feet deep, containing at its top (or junction with the base of the second) from 20 to 30 per cent. of peroxide of iron, which, however, is found to gradually diminish in percentage towards the bottom of the seam.

* Who has kindly furnished the following description and analyses of the iron ore and bauxite deposits.

The lithological characteristics of these ores are thus referred to :—First ore, rich red coloured, often purple, in which are embedded nodules of peroxide and magnetic oxide of iron, varying in size from a pin's head to that of a hazel nut ; the smaller nodules when rubbed with a file are said to present the same appearance as cast-iron under the same process. In some cases the upper seam is dark brown in colour, especially when disturbed by basaltic or trap dykes, which are frequently met with. The ore is then found to consist of loosely aggregated particles, having a bright metallic lustre, the nodules being invariably small and highly magnetic.

The second seam also possesses a considerable quantity of nodules ; these, however, are poor in iron, and often so soft as to be easily cut with a knife, the surrounding ore or matrix being much lighter and softer than the first or upper seam.

The third or lithomarge seam never contains any nodules, is homogeneous throughout, for the greater part of its depth ; it is of a fine brick-red colour, easily cut with a knife, friable, breaking into small pieces on exposure to the air ; near its base, however, it becomes lighter in colour, ultimately changing to a purple, and often presenting a very beautiful appearance, the purple being often speckled with small red and white coloured spots.

Analysis of the ore of the first and second seams, made by Mr. John Pattinson of Newcastle-on-Tyne, gives the following results :—

ANALYSIS MADE ON SAMPLE DRIED AT 212° FAHR.

| Constituents. | First Ore. | Second Ore. |
|----------------------------------|------------|-------------|
| Peroxide of iron | 53·50 | 41·85 |
| Protoxide of iron | 0·70 | 0·25 |
| Protoxide of manganese | trace | trace |
| Alumina | 18·67 | 31·10 |
| Lime | 0·48 | 2·55 |
| Magnesia | 0·58 | 0·48 |
| Titanic acid | 4·00 | 3·60 |
| Silica | 11·80 | 9·67 |
| Sulphur | nil | 0·03 |
| Phosphoric acid | trace | trace |
| Combined water | 5·50 | 10·37 |
| Moisture | 5·10 | ... |
| | 100·33 | 99·90 |
| Metallic iron | 38·00 | 29·50 |

These ores have been employed in the works of the Ditton Brook Iron Co. Limited, near Warrington, with very satisfactory results, in making, in admixture with other ores, the higher classes of pig iron for Bessemer steel making.

The bauxite deposits worked at Irish Hill are found taking exactly the place of the first or pisolitic iron ore seam previously referred to, and like it, also, having basalt overlying it. What has been said as to the disposition of the iron ore, is true also regarding that of the bauxite, except that the order is entirely reversed, the best bauxite, *i.e.*, containing the least amount of iron, is found on the top of the strata, or at the base of the basalt, and the greatest amount of iron exists at the bottom of the strata, in fact the iron gradually increases in depth.

The total depth of the bauxite strata has not hitherto been ascertained. The best, or that containing under 1 per cent. of iron, may be represented as averaging some 3 feet thick, indeed, it is never under 2 feet, and often varies from 5 to 6 feet thick; beneath this is the second quality containing from 4 to 5 per cent. of iron; the third or lowest containing from 12 to 15 per cent. of iron, with about the same percentage of titanitic acid. It is stated that the bauxite is most compact next the roof, and is occasionally found fractured into innumerable cubes.

The only division existing between the bauxite and the basalt is a thin seam, varying from a film to 2 or 3 inches, and composed chiefly of decomposed basalt, and sometimes organic matter similar to lignite, but much softer. Mr. Sutherland, in conclusion, adds, "that it must be borne in mind that the basalt in juxtaposition shows no symptoms of deterioration. There is a decided parting between the first and second and also the third seams. No substance intervenes to effect this parting, which is somewhat similar to that existing in limestones, but not so clearly delineated as in limestone partings." The bauxite deposits are invariably associated with lignite, and in some cases lignite occurs above and below. The lignite often exists in seams, and exhibits very distinct parallel, polished striæ, or slickensides; which is most interesting, as they denote the movements by disturbance to which the locality has been affected.

The three varieties of bauxite above referred to, have been examined by Mr. John Pattison, of Newcastle-on-Tyne, with the following results:—

ANALYSES OF THE SAMPLES DRIED AT 212° FAHR.

| Constituents. | First quality. | Second quality. | Third quality. |
|----------------------------|----------------|-----------------|----------------|
| Alumina | 53·83 | 52·00 | 46·13 |
| Peroxide of iron | 1·57 | 4·57 | 15·14 |
| Lime | 0·62 | 0·79 | 0·18 |
| Magnesia | 0·13 | 0·20 | 0·26 |
| Potash | 0·01 | 0·02 | 0·04 |
| Soda | none | 0·06 | 0·24 |
| Silica | 8·67 | 12·00 | 10·40 |
| Titanic acid | 5·80 | 6·20 | 4·20 |
| Sulphuric acid | 0·07 | 0·07 | 0·10 |
| Phosphoric acid | trace | trace | trace |
| Combined water | 29·27 | 24·00 | 23·39 |
| | 99·97 | 99·91 | 100·08 |

The amounts of moisture lost by drying at 212° Fahr. were as follows :—

| | |
|--------------------------|----------------|
| First quality | 7·50 per cent. |
| Second quality | 0·90 „ |
| Third quality | 0·85 „ |

The following is the composition of the three samples in the condition in which they were received :—

| Constituents. | First quality. | Second quality. | Third quality. |
|----------------------------|----------------|-----------------|----------------|
| Alumina | 49·80 | 51·53 | 45·74 |
| Peroxide of iron | 1·45 | 4·53 | 15·01 |
| Lime | 0·57 | 0·78 | 0·18 |
| Magnesia | 0·12 | 0·20 | 0·26 |
| Potash | 0·01 | 0·02 | 0·04 |
| Soda | none | 0·06 | 0·24 |
| Silica | 8·02 | 11·89 | 10·31 |
| Titanic acid | 5·37 | 6·14 | 4·16 |
| Sulphuric acid | 0·06 | 0·07 | 0·10 |
| Phosphoric acid | trace | trace | trace |
| Combined water | 27·07 | 23·79 | 23·19 |
| Moisture | 7·50 | 0·90 | 0·85 |
| | 99·97 | 99·91 | 100·08 |

Iron Ore Deposits of the County Wicklow.—Deposits of iron ore have been recently wrought to some extent at Kilbride, in the county Wicklow, of the variety known as magnetic oxide. Mr. Tichborne has examined these deposits, and in a paper read before the Royal Geological Society of Ireland, in November, 1876,

he describes the ore "as forming a vein certainly two miles, and, according to indications, three miles long; with a width varying to 6 feet in some parts, and a supply reported to be very extensive. Specimens of the ore from the surface submitted for examination were a loose friable sand, more or less spongy, but perfectly free from organic remains. As the vein was pursued in a vertical direction, it became more compact, until a dense ore with a specific gravity of 4.37 was arrived at. The silica, which in large quantities made magnetic ore useless for smelting, is extremely low in this ore." Iron ore also occurs, and is wrought in this county at the Cronebane and Ballymurtagh mines.

Iron Ore Deposits of the Counties of Longford and Cavan.—Professor Hull, F.R.S., gives the following interesting particulars respecting the hematitic ores of the counties of Longford and Cavan. "The lower silurian rocks were known for some years past to have possessed such ores, but until railways communicating with shipping ports were constructed there was little prospect of these ores being turned to profitable account. This obstacle has been overcome, and the hematite ores are now sent by the Midland and North-Western lines to Dublin and Dundalk, where they are shipped to the iron furnaces of the north of England and Wales. These ores are known to exist in at least four localities, three of which lie in the district between Granard and Carrick on Shannon, and another in the district between Cavan and Ballybay."

Another district examined by Professor Hull at Red Hills, in the neighbourhood of Belturbet, in the county Cavan, is now in process of development. Here the ore has been traced at intervals in a S.W. and N.E. direction for a distance of about six miles, following the strike of the silurian rocks from Ballyhaise through Red Hills to the grounds of Scott's house, the residence of Mr. Madden. Whether it is perfectly continuous throughout this distance is uncertain, as the strata are frequently concealed by boulder clay, but in any case the quantity of ore must be very large. On the property of the Rev. E. B. Whyte Venables at Red Hills the ore is wrought and conveyed by canal and rail to the port of Dundalk, where it is shipped to Lancashire, Cumberland, and North Wales.

The hill on which the principal excavations are in progress shows the following approximate section of the strata :—

- | | |
|---|-------------------------------|
| 1. <i>At the top</i> .—Siliceous hematite, sometimes passing into green jasper (only locally workable) | } About 50 feet in thickness. |
| 2. <i>Best Ore</i> .—Dark fissile brown hematite about 12 feet in thickness | |
| 3. <i>Inferior quality</i> .—Siliceous brown hematite, irregularly accumulated, passing into jaspery rock | |
| 4. <i>Reddish shales</i> of considerable thickness, sunk through in a pit for 80 feet | } 65 feet. |

In appearance the ore when opened out seems almost devoid of definite arrangement or structure, and it is only when in contact with beds of shale or grit that it can be observed to coincide approximately with the bedding of the rock. It therefore does not occur in a lode or vein traversing the strata in a highly inclined position, but rather in the form of lenticular beds of extreme irregularity; the ore itself is split up by innumerable planes of jointage, or false cleavage, traversing the mass in various directions.

An analysis of the Red Hills ore by Mr. John Cameron, F.C.S., of Askham-in-Furness, for the Red Hills Mining Company, shows that the ore is well suited for the manufacture of Bessemer steel, phosphorus and sulphur being entirely absent:—

ANALYSIS OF RED HILLS IRON ORE.

| | |
|---------------------------------|---------------|
| Peroxide of iron | 57.57 |
| Peroxide of manganese | traces |
| Protoxide | 6.20 |
| Alumina | 8.93 |
| Carbonate of lime | 0.50 |
| Silica | 22.80 |
| Water of combination | 3.00 |
| Soluble matter | 1.00 |
| Total | <u>100.00</u> |

Amount of metallic iron 40.30 per cent.

Ireland: Production of Iron Ore.—Brown hematite has been raised in considerable quantity in the county Wicklow at the Ballymurtagh and Cronebane mines, where also copper ore and pyrites are obtained. In the former mine the iron ore is found occurring in the North Pyrites lode. This lode is composed of iron ore to a depth of some 16 fathoms from the surface, when it passes into the ordinary pyrites of the neighbourhood. Iron ore was first raised about the year 1856, but the earliest return

met with is for the year 1863, since which year iron ore has been sold in the following quantities, giving an average price of 12s. per ton at port of shipment, the ore yielding of metallic iron from 46 to 50 per cent. :—

BALLYMURTAGH IRON ORE.

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1863 | 6,286 | 2,200 | 1872 | 9,978 | 8,890 |
| 1864 | 25,816 | 7,744 | 1873 | ...* | ... |
| 1865 | 5,136 | 1,798 | 1874 | 16,433 | 16,411 |
| 1866 | 4,850 | 1,455 | 1875 | 6,663 | 3,331 |
| 1867 | 5,500 | 1,512 | 1876 | 56 | 29 |
| 1868 | 12,500 | 2,968 | 1877 | 2,778 | 1,529 |
| 1869 | 7,000 | 1,750 | 1878 | 1,100 | 610 |
| 1870 | 8,250 | 2,062 | 1879 | 100 | 65 |
| 1871 | 9,860 | 4,930 | 1880 | 4,002 | 2,502 |

At Cronebane the brown hematite or limonite is found occurring as a gossan on the backs of the mineral veins, and is generally found near the surface, continuing in depth about 8 fathoms. The greatest depth at which it has been reached is 25 fathoms, its breadth varying from a few inches (where the vein is filled with flookan, more or less impregnated with oxide of iron) to 6 fathoms, and would average about two fathoms. The gossan rests upon decomposed clay slate and pyrites, which becomes firmer and harder in depth, and in which black oxide of copper occurs disseminated throughout the mass in every direction.

The quantities and value of iron ore produced in each year since 1872 are as follows :—

| Year. | Quantities. | Value. |
|-------|-------------|--------|
| | Tons. | £ |
| 1872 | 2,155 | 1,239 |
| 1873 | 4,143 | 2,485 |
| 1874 | 27 | 21 |
| 1875 | 1,324 | 662 |

The character of the Cronebane ore will appear in its average value per ton, which at the port of shipment in 1873 was 12s., receding to 10s. in the year 1875, since which date the working of the iron ore has been in abeyance.

* No return.

Before proceeding to summarise the total output of iron ore raised from the mines in Ireland, which is steadily increasing, it will afford some interest to note in detail the quantities and values of the ores of a few of the more important mines, which are as follows :—

ANTRIM IRON ORE COMPANY'S MINES.

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1871 | 37,000 | 16,650 | 1876 | 30,812 | 13,865 |
| 1872 | 40,048 | 20,024 | 1877 | 40,835 | 24,659 |
| 1873 | 38,522 | 19,261 | 1878 | 50,700 | 26,957 |
| 1874 | 37,719 | 33,947 | 1879 | 54,193 | 26,316 |
| 1875 | 29,060 | 21,975 | 1880 | 68,660 | 31,038 |

In the year 1871 the average price of these ores was 9s. per ton; four years later 18s. per ton was realised, since which date prices have diminished, till in 1879 the average was 10s. per ton, F. O. B. at port of shipment, and in 1880 of the above quantity 52,000 sold at 10s. per ton, the remainder at 6s. per ton.

The Glenravel mines, situated at Slieve-an-nee, also in the county Antrim, and worked by Messrs. John Fisher & Co., produced ore in the following quantities and value in each year since 1870 :—

GLENRAVEL MINES.

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1870 | 15,000 | ... | 1876 | 14,403 | 7,921 |
| 1871 | 20,000 | 18,000 | 1877 | 18,367 | 10,102 |
| 1872 | 23,605 | 21,243 | 1878 | 16,770 | 8,385 |
| 1873 | 24,699 | 22,158 | 1879 | 15,961 | 7,980 |
| 1874 | 21,791 | 19,611 | 1880 | 43,043 | 10,761 |
| 1875 | 16,896 | 12,516 | | | |

The Newton Crommelin Mines, producing brown hematite, the Irish Hill and Straid Mines bauxite, and the Island Magee Mines bole and lithomarge, the latter belonging to the Irish Hill Mining Co., produced ore in the following quantities and value in each year since 1870 :—

| Year. | Newton Crommelin. | Irish Hill, Bauxite. | Island Magee. |
|-------|-------------------|----------------------|---------------|
| | Tons. | Tons. | Tons. |
| 1873 | 5,815 | ... | ... |
| 1874 | ... | 2,000 | 6,450 |
| 1875 | ... | ... | 1,200 |
| 1876 | 6,786 | 594 | 9,000 |
| 1877 | 26,842 | 2,763 | ... |
| 1878 | 32,142 | 3,426 | 3,683 |
| 1879 | 30,715 | 3,657 | 2,845 |
| 1880 | 22,500 | 2,470 | 4,403 |

In the last-named year the Newton Crommelin ore averaged 10s. 6d. per ton; bauxite, 20s. per ton; and the Island Magee ores 10s. per ton at port of shipment.

Of the iron ore produced in the county Antrim the great bulk is exported from Belfast, the remainder from neighbouring ports on the coast. The quantities shipped from Belfast were as follows in each of the years named, a great increase appearing in the exports of 1880 over previous years:—

| Year. | Tons. | Year. | Tons. |
|-------|--------|-------|---------|
| 1870 | 24,835 | 1876 | 71,215 |
| 1871 | 14,408 | 1877 | 96,805 |
| 1872 | 22,254 | 1878 | 83,327 |
| 1873 | 9,768 | 1879 | 88,071 |
| 1874 | 33,108 | 1880 | 122,529 |

The black band ironstone raised at Ballycastle in the Antrim coal-field, with its value, in each year since 1858, appears as follows:—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1858 | 3,600 | 1,170 | 1869 | 26,746 | 6,686 |
| 1859 | 3,000 | 1,100 | 1870 | 25,000 | 6,250 |
| 1863 | 15,736 | 3,934 | 1871 | 14,409 | 8,644 |
| 1864 | 18,763 | 4,690 | 1872 | 30,000 | 27,000 |
| 1865 | 15,000 | 3,750 | 1873 | 24,835 | 22,351 |
| 1866 | 9,821 | 2,455 | 1875 | 300 | 150 |
| 1867 | 17,600 | 4,400 | 1876 | 431 | 237 |
| 1868 | 17,000 | 4,500 | 1878 | 4,375 | 1,187 |

The quantity raised in 1880 was 1,051 tons, of the value of £680 12s.

The ironstone is conveyed to Belfast where it is shipped to Scotland, and from the above returns it is clear that in years

when the iron trade is active the ironstone is in good demand, commanding a high price. In 1872 and 1873 the average price per ton reached 18s., since which date the production shows a falling off, also the price, which in 1880 gives an average of 12s. per ton.

In the annexed summary is given the production of iron ore of all varieties in Ireland since the year 1856, also its value, and the number of mines raising and selling ore in each of the same years :—

| Year. | Number of Mines. | Iron Ore. | Value. |
|-------|------------------|-----------|---------|
| | | Tons. | £ |
| 1856 | 1 | 441 | ... |
| 1857 | 2 | 3,000 | ... |
| 1858 | 1 | 3,600 | 1,170 |
| 1859 | 1 | 3,000 | 1,100 |
| 1860 | 3 | 107 | 43 |
| 1861 | 2 | 165 | 66 |
| 1862 | 4 | 10,431 | 6,038 |
| 1863 | 4 | 31,673 | 11,085 |
| 1864 | 4 | 60,602 | 20,326 |
| 1865 | 5 | 29,117 | 8,202 |
| 1866 | 5 | 25,525 | 5,314 |
| 1867 | 7 | 42,016 | 10,641 |
| 1868 | 5 | 41,469 | 10,492 |
| 1869 | 6 | 48,804 | 12,201 |
| 1870 | 8 | 77,600 | 19,405 |
| 1871 | 13 | 107,735 | 66,043 |
| 1872 | 18 | 176,500 | 158,562 |
| 1873 | 15 | 138,705 | 123,567 |
| 1874 | 21 | 140,360 | 112,089 |
| 1875 | 21 | 128,602 | 91,332 |
| 1876 | 20 | 116,010 | 60,748 |
| 1877 | 17 | 155,382 | 85,427 |
| 1878 | 16 | 156,834 | 74,809 |
| 1879 | 18 | 155,833 | 79,286 |
| 1880 | 21 | 239,325 | 112,812 |

The returns of production given above, more especially of late years, indicate clearly that as a flux these ores are becoming more and more appreciated by the ironmasters of Great Britain. The ores are exported largely to Cumberland, Lancashire, South Wales and Scotland, Staffordshire, and the Cleveland district. Since the year 1875, it will be seen that the production has increased nearly twofold. In the following statement is given the quantities used in the districts named (as far as returns have been received) in each year since 1875. The quantities fall far

short of the production of the iron mines of Ireland in each of the same years :—

| Year. | Cumberland. | Lancashire. | South Wales. | Scotland. | Other Districts. |
|-------|-------------|-------------|--------------|-----------|------------------|
| | Tons. | Tons. | Tons. | Tons. | Tons. |
| 1875 | 21,119 | 28,460 | 14,757 | 11,500 | 52,766 |
| 1876 | 16,029 | 25,000 | 13,913 | 11,779 | 49,289 |
| 1877 | 17,487 | 39,804 | 19,436 | 12,212 | 66,443 |
| 1878 | 18,633 | 38,000 | 17,470 | 11,480 | 71,251 |
| 1879 | 20,791 | 38,460 | 19,800 | 10,961 | 65,821 |
| 1880 | 38,206 | 26,093 | 25,146 | 15,981 | 133,899 |

The production of the iron mines in the year 1880 are shown in the following table, with the values of the several varieties :—

IRELAND.

| No. | County and Name of Mine. | Character of Ore. | Quantities. | Value. |
|----------------------------|---|-------------------|-------------|------------|
| | | | Tons. Cwts. | £ s. |
| <i>County Antrim.</i> | | | | |
| 1 | Aughalun (Carnlough) | Aluminous | 413 0 | 144 11 |
| 2 | Ballybalea | " | 3,170 0 | 1,109 10 |
| 3 | Ballypalady | " | 11,446 0 | 4,006 2 |
| 4 | Ballycastle | Black Band | 1,015 0 | 630 12 |
| 5 | { Cargan and Parkmore (Ballymena) | Pisolithie | 24,368 0 | 12,184 0 |
| 6 | Cloughor and Glenariff | " | 15,862 0 | 7,931 0 |
| 7 | Duneany (Glarryford) | Aluminous | 5,668 0 | 2,834 0 |
| 8 | Evishnabally and Gortnagerah | " | 27,760 0 | 13,880 0 |
| 9 | Evishnacrow (Glenravel) | Brown Hematite | 12,500 0 | 4,687 10 |
| 10 | Glenarm | Aluminous | 16,459 0 | 4,937 14 |
| 11 | Glenravel (Slieve-an-nee) | Brown Hematite | 43,043 4 | 21,528 12 |
| 12 | Island Magee | Lithomarge | 4,403 0 | 1,100 15 |
| 13 | Irish Hill and Straid (Ballymena) | Bauxite | 2,470 0 | 2,284 15 |
| 14 | Knockboy | " | 2,000 0 | 700 0 |
| 15 | Main | Aluminous | 5,391 0 | 2,695 11 |
| 16 | Newton Crommelin | Brown Hematite | 22,500 0 | 11,250 0 |
| 17 | Orblereigh (Portrush) | " | 4,795 0 | 2,397 10 |
| 18 | { Rathkenny and Broughahane (Ballymena) | Aluminous | 27,833 0 | 13,916 10 |
| | Total | | 231,132 4 | 108,216 12 |
| <i>County Tyrone.</i> | | | | |
| 1 | Barrow (Cookstown) | Brown Hematite | 572 0 | 286 0 |
| <i>County Londonderry.</i> | | | | |
| 1 | Ballylaggin (Coleraine) | Aluminous | 3,617 0 | 1,808 10 |
| <i>County Wicklow.</i> | | | | |
| 1 | Ballymurtagh | Brown Hematite | 4,002 0 | 2,501 5 |
| | Total of Ireland | | 239,235 4 | 112,812 7 |

The mines producing iron ore or in course of development in Ireland in 1880 appear in the following list, with their situation, proprietor, or company, working the same, and the manager :—

| No. | Name of Mine. | Situation. | Name of Proprietor or Company. | Name of Manager or Agent. |
|-----------------|-------------------------------|--------------------------------|--|---------------------------------|
| ANTRIM. | | | | |
| 1 | Aughalan . . . | Carnlough . . | Francis Ritchie and Sons | Robert M'Calmont. |
| 2 | Ballybale . . . | " " " | " " " | " " |
| 3 | Ballymartin . . . | " " " | " " " | " " |
| 4 | Ballylaggin . . . | Coleraine . . | Benj. Townson . . | Thomas Simmons. |
| 5 | Carran . . . | Ballymena . . | Antrim Iron Ore Co., Lim. | Robert Browne, Sec. |
| 6 | Glenarm . . . | Glenarm . . | " " " | " " |
| 7 | Rathkenny . . . | Ballymena . . | " " " | " " |
| 8 | Glenariff . . . | Clogheor . . | { Glenariff Iron Ore and Harbour Co., Lim. } | John Ham, Sec. Philip Argal. |
| 9 | Cloughor . . . | Ballymena . . | " " " | " " |
| 10 | Ballycastle . . . | Ballymoney . . | Golden and McDonald . | John James. |
| 11 | Drumnavaddy . . . | Dunloys . . | Dunloys Iron Ore Co. | Silas Evans. |
| 12 | Duneany . . . | Garryford . . | Wm. Bouden and Co. | Peter Hanlon. |
| 13 | Elgenay . . . | { Broughshane, Ballymena. } | Knockboy Mining Co. | Isaac Ross. |
| 14 | Eviahnably . . . | Garryford . . | { Mountcassell Iron Ore Co., Lim.; J. F. Row- botham, Sec. } | Silas Evans. |
| 15 | Eviahserow . . . | Glenravel . . | Charles Chambers . . | John Robertson. Wm. Edwards. |
| 16 | Irish Hill and Straid | Ballynure . . | Irish Mill Mining Co. | Alexander Sutherland. |
| 17 | Glenravel . . . | Sleive-an-nee . | John Fisher and Co. . | Hugh Raw. |
| 18 | Island Magee . . . | Larne . . . | Francis Ritchie and Sons | Robert M'Calmont. |
| 19 | Ballypalady . . . | " " " | " " " | " " |
| 20 | Knockboy . . . | Ballymena . . | Knockboy Mining Co. | Isaac Ross. |
| 21 | Parkmore . . . | " " " | Parkmore Iron Ore Co. | Alexander Gillespie. |
| 22 | { Shanes and Agnews Hill } | { Larne . . . } | { The Larne Iron Mining Co. } | Thomas Fisher, En- gineer. |
| 23 | Orblerleigh . . . | Portrush . . | Benjamin Townson . . | Thomas Simmonds. |
| 24 | Newton Crommellin . . | Glenravel . . | S. D. Crommellin . . | James G. Carrick. |
| 25 | Maiden Mount . . . | Carrickfergus . | M. Robert Dalway, M.P. | James Hodgkinson. |
| 26 | Main . . . | Portrush . . | Benjamin Townson . . | Thomas Simmonds. |
| DOWN. | | | | |
| 1 | Deehomed . . . | Ballynahinch . | { County Down Iron Mining Co. } | Jas. C. Greer. |
| WICKLOW. | | | | |
| 1 | Cronebane . . . | Ovoca . . . | { Associated Irish Mines Co. } | Geo. Oates. |
| 2 | Ballymurtagh . . . | " " " | { The Wicklow Copper Mines Co. } | John Hodge. |
| TYRONE. | | | | |
| 1 | Barrow . . . | Cookstown . . | { The Barrow, Hematite Co., Limited . } | William Kellett. |

Manufacture of Pig Iron.—It appears from the "Geological and Mining Survey of the Connaught Coal-field" published in the year 1818,* that at an early period the number and richness of the beds of ironstone in the Connaught coal district attracted the attention of Irish speculators, resulting in the establishment of works on a small scale called bloomerics, carried on in various parts of the adjoining country as long as wood remained to supply them with charcoal. At the time referred to, no coal had been discovered, and if it had been, the process of making pig iron from pit coal was then, though partially known, not practised even in England.

* By Sir Richard Griffith.

The ironworks of Drumshambo were the last that continued to work; they were given up about the year 1765. These works were situated at the southern extremity of Lough Allen, in the county of Leitrim, a quarter of a mile west of the village of Drumshambo. The locality selected possessed much interest; the works were built upon a limestone rock, distant about a quarter of a mile from the coal country. The situation was particularly favourable for making iron at a cheap rate. The ironstone was chiefly collected from the eastern shore of Lough Allen, and in the beds of the precipitous streams which descend from the Slieve-a-Nierin mountains to the lake.

The appearance of trivial workings, made in search of the ironstone, are still visible along the borders of these streams. The ironstone when collected was conveyed by boats to the works, and charcoal from the vast woods which at one time flourished in all the valleys, was carried by the same means. Limestone, the only remaining ingredient for smelting iron, was quarried close to the works. Judging from the accounts given by the oldest inhabitants, and the remains still visible, the Drumshambo ironworks appear to have consisted of one blast furnace 3 feet square in the interior, and about 18 or 20 feet high. Large heaps of ironstone of excellent quality still remain at the works. It is much superior to that used at the more modern Arigna ironworks. The smelted iron from the Drumshambo works was carried to the neighbouring village, where it was forged into bars.

The Arigna ironworks were commenced about the year 1788 by three brothers of the name of O'Reilly. At that time the practicability of smelting iron with pit coal or coke instead of charcoal was well known and long practised in England and Scotland with great advantages to the adventurers. In the same year in which the Arigna works were commenced there were 53 blast furnaces in England and Wales, and 6 in Scotland, the annual produce amounting to 53,800 tons of pig iron.

The Arigna works, situated on the west side of the river Arigna, about one mile from Lough Allen, were the only works hitherto erected in Ireland to smelt iron with coal, and have therefore attracted much attention. The works as first constructed were divided into two distinct parts, the upper and lower works. The iron was smelted and all the castings were made in the upper

works, and the lower were confined to rendering cast-iron malleable, forming it into bars, &c.

The upper works, in the beginning of the century, when reported upon by Mr. John Grieve, "consisted of a blast furnace 44 feet high and 12 feet wide in the boshes; the furnace bank descending to the bridge-house and tunnel head; so that the materials were thrown into the furnace out of wheelbarrows. An overshot wheel of 27 feet diameter furnished the necessary blast for this furnace, and also worked a very good boring mill. There was also a foundry with a cupola furnace."

The lower works, according to the same report, "originally consisted of a forge with a refining hearth, worked by an overshot water-wheel 16 feet in diameter, with 8 cranks on its axis, working 3 cylinder bellows, each 30 inches in diameter, a mumbling hammer, about 3 tons weight, worked by an overshot water-wheel 13 feet in diameter, and 4 feet 8 inches broad, with air furnaces, &c. &c., for puddling. A slitting mill with two overshot water-wheels of 20 feet in diameter and 4½ broad. The rollers and cutters were each 13 inches in diameter. About the time the late Sir Richard Griffith wrote (1818), these lower works were in such a ruinous state, that nothing but the stones, and some iron materials which remain, can ever be converted to any use." *

At the period referred to, the estimated cost of making a ton of pig iron, calculated from the cost of the different materials delivered at the works, is given as follows:—

| | £ | s. | d. |
|--|---|----|----|
| Five tons of raw coal at 4s. per ton | 1 | 0 | 0 |
| Four tons of ironstone at 5s. per ton | 1 | 0 | 0 |
| One ton of limestone | 0 | 2 | 0 |
| Expense of cookeing, roasting the ore, labour, &c. | 0 | 10 | 0 |
| Contingencies at 20 per cent. | 0 | 10 | 5 |
| Total cost of a ton of pig iron | 3 | 2 | 5 |

In the year 1804, Mr. Thomas Guest, of the Dowlais Ironworks in Glamorganshire, reported upon the condition of the Arigna Ironworks, and estimated the cost of production as follows. He considered that the coal of the Aughabehy and Rover collieries could be delivered at 6s. 4d. per ton, and that

* "Geological and Mining Survey," Connaught Coal-field, 1818, pp. 63, 65.

the ironstone, the greater part of which must be raised on the eastern side of Lough Allen, would ultimately cost 6*s.* per ton, and the limestone 4*s.* ; therefore :—

| | £ | s. | d. |
|--|---|----|----|
| Five tons raw coal, at 6 <i>s.</i> 4 <i>d.</i> | 1 | 11 | 8 |
| Four tons ironstone, at 6 <i>s.</i> | 1 | 4 | 0 |
| One ton limestone, 4 <i>s.</i> | 0 | 4 | 0 |
| Labour, 10 <i>s.</i> | 0 | 10 | 0 |
| Rent, wear and tear, and other incidental expenses | 1 | 5 | 4 |
| Total, per ton | 4 | 15 | 0 |

At a more recent date, in 1827, when Mr. Twigg reported to the directors of the Arigna Company, the result of his investigations led to an estimate being made of the cost of manufacture of iron, which was as follows :—*

| | £ | s. | d. |
|---|---|----|----|
| Five and a half tons of raw coal, at 7 <i>s.</i> 10 <i>d.</i> | 2 | 3 | 1 |
| Three tons four cwts. of ironstone, at 4 <i>s.</i> 10 <i>d.</i> | 0 | 15 | 5 |
| One ton of limestone, at 3 <i>s.</i> | 0 | 3 | 0 |
| Workmen's wages, &c. | 0 | 13 | 3 |
| Cost of engine, slack, agency, &c. | 0 | 11 | 0 |
| Total | 4 | 5 | 9 |
| If limestone be supplied by railway deduct 1 <i>s.</i> 11 <i>d.</i> per ton | 0 | 1 | 11 |
| Final cost of a ton of No. 1 Pig | 4 | 3 | 10 |

Sir R. Kane remarks generally upon the above estimate that it is too high, and adduces very good reasons, inasmuch as the best coal of the district, the Aughabehy, was then selling at 6*s.* 4*d.* per ton, and the coal of the Rover colliery at 4*s.* 9*d.* per ton. In the same way the ironstone is undervalued in its contents of metallic iron, 30 per cent. being taken ; whereas the average contained is fully 40 per cent., which, at 4*s.* 10*d.*, would cost but 12*s.* 1*d.*, but two tons and a half being required. One point is quite clear that all the necessary materials for the manufacture of pig iron are found in the Arigna district in abundance.

About the year 1856, towards its close, the works at Arigna appear to have been re-opened, and the manufacture of pig iron again carried on ; in the year 1857 it is recorded that 1,000 tons of pig iron were produced by the single blast furnace then in operation. Soon afterwards the works appear to have been closed, and subsequently abandoned.

* "Industrial Resources of Ireland," 2nd edition, 1845, p. 147.

CHAPTER XXIII.

FOREIGN IRON ORES IMPORTED.

General Description of these Ores—Their mode of occurrence—Analyses of Ores—Quantities imported from Spain, Portugal, France, Algeria, Italy, Greece, Norway, Sweden, Russia, and Turkey in Asia—Bauxite and Analyses.

Spain, especially rich in her deposits of ironstone, furnishes large supplies to Great Britain; indeed, the deposits may be said to be almost inexhaustible. In the early part of the past decade the unsettled condition of affairs in that kingdom greatly retarded the development of this important industry. In recent years, however, a more prosperous condition appears; thus in 1860 the total imports of iron ore into the ports of the United Kingdom did not exceed 20,542 tons, while in the year 1870, when the industry was assuming importance, the quantities received in this country had increased to 179,083 tons, showing an increase four-fold in a period of six years; yet ten years later the imports amounted to 2,278,962 tons.

The more important deposits of iron ore are found in the carboniferous limestone, the most extensive at Bilbao, near the port of the same name, where at the Somorrostro mines upwards of 1,000 tons are daily raised. The other important deposits yielding valuable ores, are situated near Carthagena, Catalonia, Granada, and Santander.

In referring generally to these valuable ores of iron, it will be interesting to give a brief account of the more important deposits, now so extensively worked at Somorrostro.*

"The Somorrostro ironstone district, which is situated north-west of Bilbao, is the principal seat of the industry. The centre of the district is about $7\frac{1}{2}$ miles from Bilbao, and about the same distance from the shipping place on the River Nervion, between Bilbao and the sea. The known deposits of iron ore

* Abstract of a paper by E. Bourson, "On the Somorrostro Mines."

occur here and there over a large area, some deposits being found quite near to Bilbao, and others 19 miles north-west of it. The principal mass is about $2\frac{1}{4}$ miles in length by $1\frac{1}{4}$ mile in width; its thickness has not yet been proved, but the workings have been carried down to the depth of 246 feet in some places, and 105 feet in others. The ore is chiefly brown hematite, interspersed with blocks of unaltered spathic ore. It contains in the undried state from 50 to 64 per cent. of metallic iron, about 1 per cent. of manganese, but only a fractional percentage of sulphur and phosphorus." In all the localities wrought, the ore crops out to the surface, and it is consequently obtained from open workings, blasting being generally employed.

The conveyance of the ore from the mines to the railways is either in carts drawn by oxen or by wire tramways, and afterwards by rail to the shipping places. Two systems of conveyance by wire-rope are used—Hodgson's and Bleichert's. The arrangement by Bleichert has more recently been introduced; the main ropes in it are fixed, serving as rails for the trams, or tubs suspended from them to run on. The trams are drawn by a lighter running rope. The first cost is greater with Bleichert's than with Hodgson's system, but the working cost is less, and it is capable of carrying twice the quantity per day. The cost of transport by Bleichert's wire-rope line, is about 2'66*d.* per ton per mile. There are five lines of railway or wire-rope lines connecting the mines with the shipping places. The waggons are filled by hand, and are so arranged as to tip at the end or bottom.

The shipping stages are constructed of timber, the waggons being run out on them singly, then tipped into the vessels through inclined spouts, in one case by a vertical spout, over which the bottom tipping-waggons discharge. The average cost of the ore per ton on board is nearly as follows:—Quarrying, 1'04*s.* per ton; conveyance to railway by wire-rope line, '37*s.* per ton; filling into railway waggons, carriage by rail, and transshipping, 1'65*s.* per ton; duty, '10*s.* per ton; total, 3'16*s.*, or 8*s.* 2*d.* per ton. The quantity of ore shipped at the harbour of Bilbao in the year 1877 was 964,533 tons, increased in the year 1878 to 1,224,730 tons, of which England received 856,038 tons, and Scotland 47,445 tons.

Analyses of the Iron Ores of Spain.—At the mines of San Prudencia, in the neighbourhood of Bilbao, the ore obtained in a

nodular state from the deposit of drift is known by the name of "Small," while the ore obtained from the deposits in the carboniferous limestone is designated "Rock Ore;" of these varieties and of the rich hematites worked at the Campanil and Ollargan mines, ores in good demand and commanding a good price, the annexed analyses give the respective constituents:—

| Constituents. | SAN PRUDENCIA. | | CAMPANIL. | OLLARGAN. |
|---------------------------|----------------|-------|-----------|-----------|
| | Small. | Rock. | Rock. | Rock. |
| Peroxide of iron | 71·93 | 79·59 | 80·06 | 70·10 |
| Protoxide of iron | ... | ... | 5·42 | ... |
| Silica | 9·77 | 5·34 | 2·00 | 13·66 |
| Manganese | 1·95 | 2·02 | 2·10 | 3·65 |
| Alumina | 4·23 | 1·97 | 0·40 | 6·33 |
| Lime | 0·08 | trace | ... | 0·22 |
| Magnesia | trace | trace | ... | 0·23 |
| Carbonic acid | ... | ... | 3·21 | ... |
| Water and loss | 11·39 | 10·81 | 6·71 | 5·71 |
| Total | 99·35 | 99·73 | 99·90 | 99·90 |
| Metallic iron | 50·35 | 55·70 | 60·25 | 54·00 |

Other analyses of Bilbao ores from three different localities show the following results; the analyses were made by the late Mr. William Baker, of Sheffield, one of the earliest Associates of the Royal School of Mines:—

BILBAO ORES.

| Constituents. | No. 1. | No. 2. | No. 3. |
|--------------------------------|---------|---------|---------|
| Silica | 5·55 | 1·70 | 7·65 |
| Peroxide of iron | 78·80 | 79·20 | 76·00 |
| Alumina | 3·50 | 6·80 | 5·80 |
| Protoxide of manganese | 0·651 | 2·88 | 0·83 |
| Sulphuric acid | 0·068 | 0·62 | 0·34 |
| Lime and magnesia | trace | trace | trace |
| Phosphoric acid | none | none | none |
| Water combined | 11·653 | 9·672 | 10·128 |
| Total | 100·222 | 100·872 | 100·748 |
| Loss in drying | 0·66 | 1·80 | 1·60 |
| Metallic iron | 55·16 | 55·44 | 54·20 |

The ores of Spain are extensively employed in the furnaces of Durham, Cleveland, Lancashire, and Cumberland, also in Shef-

field, South Wales, and Scotland. The Deseada ore, raised by the Santander Mining Company, yielding 58·66 per cent. of metallic iron, employed in some of the Cumberland furnaces, gives the following results on analysis :—

RESULTS TABULATED.

| | | | |
|----------------------------------|-------|------------------------------|-------|
| Sesquioxide of iron | 83·79 | Brought forward | 88·73 |
| Alumina | 0·45 | Sulphuric acid | 0·31 |
| Protoxide of manganese | 0·18 | Sulphur | 0·06 |
| Lime | 1·35 | Phosphoric acid | 0·09 |
| Magnesia | 0·16 | Carbonic acid | 0·60 |
| Silica | 2·80 | Water, hygroscopic | 1·19 |
| Titanic acid | trace | „ combined | 8·71 |
| Carried forward | 88·73 | Total | 99·69 |

The ores raised by the same company at their Onton mines has been examined by Dr. Noad, F.R.S. The five samples examined give the following results :—

RESULTS TABULATED.

| Constituents. | No. 1. | No. 2. | No. 3. | No. 4. | No. 5. |
|----------------------------|--------|--------|--------|--------|--------|
| Water | 13·60 | 10·80 | 12·80 | 11·80 | 11·00 |
| Peroxide of iron | 71·43 | 79·50 | 78·70 | 73·60 | 78·20 |
| Silica | 14·60 | 9·80 | 8·40 | 14·20 | 10·50 |
| Total | 99·63 | 100·10 | 99·90 | 99·60 | 99·70 |
| Metallic iron | 51·00 | 55·65 | 55·00 | 51·06 | 55·00 |

An average of the above giving 58·54 per cent. of metallic iron.

Imports of Iron Ore from Spain.—In the following table is given the quantities and values of these ores imported into Great Britain since the year 1864 :—

| Years. | Quantities. | Value. | Years. | Quantities. | Value. |
|--------|-------------|--------|--------|-------------|-----------|
| | Tons. | £ | | Tons. | £ |
| 1859 | 25,701 | 19,273 | 1870 | 179,083 | 146,747 |
| 1860 | 20,542 | 13,865 | 1871 | 302,382 | 264,255 |
| 1861 | 22,208 | 17,423 | 1872 | 631,134 | 705,441 |
| 1862 | 33,517 | 24,797 | 1873 | 790,891 | 1,000,720 |
| 1863 | 38,388 | 26,097 | 1874 | 541,963 | 665,614 |
| 1864 | 43,927 | 32,887 | 1875 | 250,641 | 273,757 |
| 1865 | 37,121 | 29,476 | 1876 | 522,383 | 556,756 |
| 1866 | 27,619 | 22,160 | 1877 | 990,039 | 983,566 |
| 1867 | 67,356 | 54,298 | 1878 | 1,088,862 | 1,021,455 |
| 1868 | 88,770 | 74,635 | 1879 | 1,007,617 | 981,276 |
| 1869 | 99,816 | 78,134 | 1880 | 2,278,962 | 2,270,462 |

From the foregoing it appears, that in the year 1864, these ores had a value at the port of importation of nearly 15*s.* per ton, increased in the year 1873 to nearly 25*s.* per ton, since which year a gradual falling off in value appears; the returns for the year 1880 giving 20*s.* per ton.

Regarding the development of the hematite deposits of Spain, the Consular Reports, published at the beginning of 1880, are of great interest at the present time. The English consul at Bilbao reported on the iron ore trade of that district in the following terms: *—"Considering the depressed state of the iron market during nearly the whole of last year, it is satisfactory to observe that the decrease in this export was only trifling; and it may be mentioned that the export during the current year will largely exceed the most sanguine expectations entertained of the development of this trade, contracts having been made for the delivery of upwards of 2,500,000 tons of ore before the 31st of December next. The average price of the ore up to October last ruled from 6*s.* to 7*s.* per ton free on board, and at the date of this report it is 15*s.* per ton delivered at the loading wharves. Freights to England were from 7*s.* to 7*s.* 6*d.*, and iron ore from 10*s.* to 10*s.* 6*d.* (March, 1880), significant facts reflecting on the improvement in the iron trade throughout the world. About three-fourths of the ore continues as hitherto to be shipped to the United Kingdom." The total exports of iron ore from the port of Bilbao in the four years ending 1880, were as follows, the average price of the ore in June, 1881, being about 7*s.* per ton F.O.B. at port of shipment:—

| Year. | Quantities. | Value. |
|-------|-------------|---------|
| | Tons. | £ |
| 1877 | 964,000 | 771,200 |
| 1878 | 1,224,000 | 979,700 |
| 1879 | 1,160,248 | 870,000 |
| 1880 | 2,345,598 | ... |

In the following statement, from "The Revista Minera," a Spanish official return, appears the quantities of iron ore received at the several ports in England and Scotland in the years 1878 and 1879:—

* "H. M. Consular Reports" for the year 1879, p. 922.

| Ports. | 1878. | 1879. |
|------------------------------|----------------|----------------|
| <i>England—</i> | <i>Tons.</i> | <i>Tons.</i> |
| Cardiff | 295,300 | 299,085 |
| Newport | 221,041 | 219,783 |
| Middlesborough | 133,461 | 36,783 |
| Newcastle | 113,479 | 51,771 |
| Sunderland | 48,804 | 30,658 |
| Port Talbot | 16,094 | 30,543 |
| Swansea | 11,502 | 11,528 |
| Stockton | ... | 2,574 |
| Maryport | 6,895 | ... |
| Liverpool | 5,030 | 6,413 |
| Porthcawl | ... | 1,307 |
| Briton Ferry | 1,311 | ... |
| Llanelly | 1,271 | ... |
| Workington | ... | 536 |
| West Hartlepool | 650 | 1,033 |
| Saltney | 639 | 244 |
| Barrow and Chester | ... | 714 |
| London | 302 | ... |
| Grimsby | 259 | ... |
| <i>Scotland—</i> | | |
| Glasgow | 40,734 | 41,496 |
| Ardrossan | 4,876 | 351 |
| Troon | 1,061 | ... |
| Granton | ... | 480 |
| Ayr | 636 | ... |
| Borrowstonness | 138 | ... |
| Grangemouth | ... | 144 |
| Total | 903,483 | 735,443 |

The quantities received in England in 1878 amounting to 856,088 tons, and, in Scotland to 47,445 tons, compared with 692,972 tons and 42,471 tons in 1879.

The bar at the mouth of the River Nervion is a great obstruction to navigation; practically it stops the entrance during the half of each month. Vessels of large draught can cross it at spring tides only. Steamers drawing $13\frac{1}{2}$ to 14 feet of water, capable of carrying a cargo of 1,000 tons, with engines of 120 horse-power, are the best adapted for the trade of this port. The freight of such vessels going back in ballast from Bilbao to Calais or Rotterdam is about 7s. 8d. per ton.

Portugal.—In this kingdom iron ore exists in abundance in nearly all the provinces; some of these ores are known to be rich in manganese, and are likely by-and-by to attract attention. The granitic rocks and metamorphic schists contain lodes of magnetite or magnetic oxide of iron; one of the most important of these is

that in the Serra dos Monges, in the province of Alentejo, which, on account of its proximity to the railway from Evora to Lisbon, is well situated for exploration on a large scale; other remarkable lodes of this ore occur at Villa Boim, near Elvas, in the same province, and at Campo Major, near the Spanish frontier. The specular oxide of iron, hematite, and spathic carbonates of iron, are also found in Portugal. At Moncorvo there are some remarkable lodes of oligist iron ore, and at Quadramil, in the province of Traz-os-Montes, a very rich lode, containing brown hematites and hydrated oxides of iron, is seen to have an extension of some 4 or 5 miles, with a breadth at places of 60 feet.

Powerful lodes of carbonate of iron are known to exist in various districts; one especially may be mentioned recently discovered rich in manganese in the province of Alentejo, the proportion of the manganese to the iron being as three to five, the percentage of phosphorus under a thousandth per cent.; the earthy matter in this ore is not more than 10 per cent., and is composed of clay, with a little carbonate of lime, so that it is expected that this ore will prove an admirable material for the production of spiegeleisen or ferro-manganese.*

The annexed analyses of the iron ores raised at Monges, in Portugal, employed in the blast furnaces of Scotland, will show their composition:—†

| Constituents. | No. 1. | No. 2. | No. 3. | No. 4. |
|------------------------------------|--------|--------|--------|--------|
| Peroxide of iron | 70·44 | 67·52 | 62·86 | 59·71 |
| Protoxide of iron | 18·00 | 7·09 | 7·20 | 8·81 |
| Oxide of manganese | 0·04 | trace | trace | 1·48 |
| Lime | ... | 0·66 | ... | trace |
| Magnesia | ... | trace | 0·67 | trace |
| Carbonic acid | ... | 0·46 | 0·63 | ... |
| Phosphoric acid | trace | 0·08 | 0·14 | 0·06 |
| Sulphur | 2·38 | ... | ... | 0·17 |
| Iron combined with sulphur | 2·08 | ... | ... | 0·15 |
| Alumina | 1·22 | 4·70 | 5·49 | 7·17 |
| Silica | 2·76 | 10·83 | 11·72 | 16·20 |
| Water combined | 3·08 | 8·66 | 11·29 | 6·25 |
| Total | 100·00 | 100·00 | 100·00 | 100·00 |
| Metallic iron | 65·48 | 52·78 | 49·60 | 48·80 |

* "Journal of the Iron and Steel Institute," 1875, p. 302.

† "Iron," 7th October, 1876, p. 459. Paper by Mr. J. St. Day, C.E.

The importation of iron ore from Portugal commenced in the year 1873, when 24,812 tons, valued at £32,063 were received in Great Britain. In subsequent years the returns are as follows :—

| Year. | Quantities. | Value. |
|-------|-------------|--------|
| | Tons. | £ |
| 1873 | 24,812 | 32,063 |
| 1874 | 29,398 | 37,969 |
| 1875 | 48,277 | 55,891 |
| 1876 | 12,894 | 13,234 |
| 1877 | 13,998 | 13,168 |
| 1878 | 3,154 | 2,946 |
| 1879 | nil | nil |
| 1880 | 39,775 | 44,433 |

France, though rich in her deposits of iron ore, does not export largely, but on the contrary, to meet the demands of her metallurgical works, imports iron ore from her Algerian colonies, Belgium, and other countries. Magnetic ores do not abound in France; hematitic ores are wrought in considerable quantity in the department of the Ardèche, near the towns of Privas and La Voulte, and furnishes to some extent the furnaces of the Terrenoire, La Voulte, and Bessèges companies. The ore occurs in strata between the Lower Oolite and Liassic Marl, and, as described by Professor S. Jordan, “varies in character from the red hematite, with a conchoidal fracture and agate-like texture (containing 56 per cent. of iron), to the schistous and even oolitic hematite (with only 30 per cent. of iron).” The production of these deposits does not exceed 260,000 tons per annum. Analyses of the ores show the annexed results :—

RESULTS TABULATED.

| Constituents. | Privas. | La Voulte. |
|----------------------------|---------|------------|
| Peroxide of iron | 58·16 | 79·21 |
| Oxide of manganese | trace | trace |
| Silica | 10·90 | 10·50 |
| Alumina | 7·10 | 2·26 |
| Lime | 10·35 | 1·22 |
| Phosphorus | 0·325 | 0·49 |

The other constituents, namely, iron in form of protoxide, magnesia, sulphur, and loss by calcination, are not determined,

and it is remarked that these red hematites of the Ardèche have a geological situation very different from those of the north-west of England, where they are found in older rocks.

The principal repositories of iron ore in France are found in the Liassic and Oolitic rocks, the conditions of occurrence being somewhat similar to ores of the same geological age in this country, though it has been remarked that in their general character they are more argillaceous than the English ores of the same age. Brown iron ore of a sandy character, occurring in superficial deposits in the Wealden rocks, between Boulogne and Calais, where it is extensively worked at a small cost, is smelted in admixture with ore from Africa, and hematite from Spain and Cumberland, at the blast furnaces of Marquise and Outreau, the last-named furnaces being situated on the River Lianne, a short distance from Boulogne. The ores raised in this area yield from 32 to 35 per cent. of metallic iron. The most important deposit in France is the great ironstone field extending from Luxemburg through Lorraine up to and beyond Nancy, in the valley of the Upper Moselle. It occupies the upper part of the Lias formation, or, according to some geologists, it belongs to the Lower Oolites. The ore obtained in this iron field is very variable, ranging from 20 to 35 per cent. of metallic iron.

Spathose ore is obtained in a few localities in France, the principal deposit being in the Department of the Isère, where it is worked at Allevard. The constituents of three varieties of these spathose ores are given as follows by Professor S. Jordan, of Paris :—

RESULTS TABULATED.

| Constituents. | Isère. | Savoy. | Pyrénées Orientales. |
|-----------------------------|--------|--------|-------------------------|
| Protoxide of iron | 48·15 | 50·50 | 61·70 |
| Oxide of manganese | 3·02 | 8·00 | 4·06 |
| Silica | 4·85 | ... | ... |
| Quartz and clay | ... | 1·00 | 1·34 |
| Lime | 2·50 | 1·70 | 0·21 |
| Magnesia | 0·67 | 0·70 | ... |
| Sulphur | 0·16 | ... | ... |
| Loss by calcination | 40·49 | 38·10 | 31·95 |
| Total | 99·74 | 100·00 | 99·26 |

Referring to the Boulonnais Ironworks in the Pas de Calais,

it is a curious coincidence, and worthy of note, that they should have commenced operations about the time that the Wealden Ironworks ceased; these latter were situated at Ashburnham, in Sussex, and were finally extinguished in the year 1828, the ironworks of the Boulonnais commencing operations between the years 1829 and 1834.

In the following table appear the quantities and value of all kinds of ore imported into this country from France, between the years 1864 and 1877, since which there has been no imports:—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1864 | 19,454 | 12,216 | 1870 | 10,300 | 6,471 |
| 1865 | 19,477 | 12,765 | 1873 | 16,761 | 16,522 |
| 1866 | 16,064 | 9,718 | 1874 | 20,077 | 19,463 |
| 1867 | 12,540 | 7,675 | 1875 | ... | ... |
| 1868 | 10,766 | 6,074 | 1876 | ... | ... |
| 1869 | 9,424 | 5,753 | 1877 | 2,110 | 9,910 |

Algeria.—This important colonial possession of France contains extremely rich deposits of iron ore; at Djebel, near Arousse, and Sfer, in the province of Oran, specular iron ore is extensively wrought, while at Mokta-el-Hadid, in the province of Constantine, magnetic iron ore is worked. The annexed analysis shows the constituents of the ore raised in the province of Oran and used in the blast furnaces of Great Britain:—

RESULTS TABULATED.

| | |
|-----------------------------|--------|
| Peroxide of iron | 71·00 |
| Lime | 11·09 |
| Magnesia | 1·73 |
| Carbonic acid | 10·61 |
| Alumina | 0·74 |
| Silica | 1·36 |
| Combined water | 1·87 |
| Water at 212° Fahr. | 1·60 |
| Total | 100·00 |
| Metallic iron | 49·70 |

Algeria, with her extensive iron ore deposits, possesses but one metallurgical establishment of any importance engaged in the manufacture of pig iron. These ironworks are situated at Atelik,

near Bona, in the province of Constantine, where pig-iron is made from the spathose ores of the district; native coal, previously coked, being employed in their reduction.

The quantities and value of the iron ores imported from Algeria appear as under in each year since 1863 :—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1863 | 268 | 201 | 1872 | 53,162 | 66,741 |
| 1864 | 1,090 | 788 | 1873 | 69,856 | 96,964 |
| 1865 | 3,225 | 2,801 | 1874 | 62,233 | 79,863 |
| 1866 | 509 | 492 | 1875 | 55,620 | 61,808 |
| 1867 | nil | nil | 1876 | 42,112 | 47,355 |
| 1868 | 326 | 293 | 1877 | 22,151 | 24,194 |
| 1869 | 285 | 319 | 1878 | 13,124 | 14,783 |
| 1870 | 2,116 | 1,559 | 1879 | 18,911 | 18,317 |
| 1871 | 1,640 | 1,803 | 1880 | 82,248 | 86,884 |

In the year 1872 the average price of these ores exceeded 25*s.* per ton, increased to 28*s.* per ton in 1873, falling in 1874 to 26*s.* per ton, since which date prices have declined, till in 1879 they realized 20*s.*, increasing in 1880 to upwards of 21*s.* per ton.

Italy.—Iron ore exists abundantly in the states of the Italian kingdom.* “The chief iron ores of Lombardy are those known as spathic or carbonate of iron, and brown hematites; these are found in beds enclosed by metamorphic gneiss in the neighbourhood of the lakes of Como and Iseo, and in the Val Sassina, also in the Bergamask Mountains, where they compose layers or seams, sometimes two and even three fathoms thick in triassic red sandstone or green slate. The brown hematite contains much manganese, and is therefore particularly suitable for the production of manganiferous spiegeleisen or a white radiated pig iron.” In the island of Elba, on the eastern side, at Rio Albano, Rio Marina, Terranera, and Capo Calamita, specular iron ore, red hematite, and magnetic ores, are still wrought as they were centuries ago. The mines at Elba furnished the Etruscans with iron ore, from which they made iron long before the foundation of ancient Rome; and the mines are now far from being exhausted. The oldest mines in Elba are those of Rio Marina, but the operations in recent years are confined to picking the rich ores from

* “Reports of the Vienna Exhibition, 1873,” vol. iii. p. 423.

the heaps left by the old miners; these heaps in some places attaining a height of 500 feet. The production of iron ore in Elba exceeds 200,000 tons per annum, the greater part of which is exported to Corsica, France, England, and Germany, about 40,000 tons being smelted in Tuscany, at Follonica, Cecina, Valpiana, and other places.

The deposits of Rio Marina are specular iron ore, and red hematite resting upon talcose schist, and covered by crystalline limestone, having an area of about 30 acres, the depth of the deposit being considerable. At Rio Albano and Terranera the lodes of specular iron ore break through the talcose schist, and cover it with beds of the same material from 30 to 100 feet thick; and at Capo Calamita there is a lode of magnetic iron ore which, rising from the level of the sea, intersects a thick crystalline limestone, sending frequently branches into the latter, and surmounting it by a large bell-shaped mass which attains a thickness of 150 feet, composed chiefly of specular iron ore, red hematite, actinolite, and green garnet. The iron ores above referred to yield respectively of metallic iron 66·27 per cent., 65·35 per cent., and 61·81 per cent. The following analyses show the composition of these ores; those of Calamita and Terranera are by Professor Sestini; that of Rio Albano was made in the laboratory of the Phoenix Ironworks in Germany:—

RESULTS TABULATED.

| Constituent. | Calamita. | Terranera. | Rio Albano. |
|-----------------------------|-----------|------------|-------------|
| Sesquioxide of iron | 94·67 | 93·36 | 87·84 |
| Oxide of manganese | 0·33 | trace. | 0·07 |
| Alumina | ... | 0·58 | 3·47 |
| Lime | ... | 0·16 | 0·22 |
| Magnesia | ... | 0·17 | 0·34 |
| Silica | 3·28 | ... | 5·97 |
| Copper | 0·04 | ... | ... |
| Sulphur | 0·03 | 0·11 | 0·17 |
| Phosphorus | trace. | ... | 0·01 |
| Insoluble rock | ... | 3·64 | ... |
| Water and loss | 1·65 | 1·98 | 1·91 |
| Total | 100·00 | 100·00 | 100·00 |
| Metallic iron | 66·27 | 65·35 | 61·81 |

Imports of Iron Ore from Italy.—These are considerable,

although great fluctuations appear in recent years ; since 1864 the quantities imported into this country, with the value in each of the same years, are given as follows in the "Trade and Navigation Returns :"—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|---------|
| | Tons. | £ | | Tons. | £ |
| 1864 | 6,224 | 6,221 | 1873 | 31,729 | 46,545 |
| 1865 | 4,289 | 4,271 | 1874 | 33,394 | 46,938 |
| 1866 | 1,292 | 1,292 | 1875 | 40,109 | 46,859 |
| 1867 | * | ... | 1876 | 60,620 | 63,302 |
| 1868 | * | ... | 1877 | 86,301 | 86,836 |
| 1870 | 119 | 445 | 1878 | 48,771 | 46,104 |
| 1871 | 3,320 | 3,167 | 1879 | 43,763 | 49,713 |
| 1872 | 47,755 | 61,091 | 1880 | 176,750 | 182,556 |

The average price of these ores previous to 1872 was about 20*s.* per ton ; in 1872 they rose to 25*s.* 6*d.* per ton, and in 1874 to 28*s.* per ton, since which prices have receded, not exceeding 22*s.* 6*d.* per ton in the year 1879, and 20*s.* 8*d.* in 1880.

Greece.—The iron ores obtained from the Grecian Archipelago are found in the Island of Seriphos. The deposits consist both of magnetic iron ore and of brown hematite, similar to the Bilbao ore, but in some of the mines strongly manganiferous. The magnetic ores have not hitherto been worked, as they are not so favourably situated for transport as the brown hematites. These occur as beds interstratified with calcareous shales and marbles, and often forming the surface stratum, so that they can be worked simply by open quarrying ; and, as they are situated close to the coast, ships can lie within a few hundred feet from the mines themselves, by which the expense of extraction is reduced to a minimum. As to quantity, although the works are of small extent and principally open quarries, enough has been opened out to prove more than a million tons of ore, and there is no reason to doubt the continuance of these iron ore beds in depth. The ore raised and imported into this country from the mines in the Island of Seriphos was smelted some years ago with very satisfactory results, at the Royal Greek Ironworks, situated at Wallsend, near Newcastle-upon-Tyne. The quality of the ore was excellent, as may be seen by the following analyses, made by Mr. John Pattinson, of Newcastle, from the different mines :—†

* Not separately distinguished.

† "Journal of the Iron and Steel Institute," 1875, p. 293.

| Constituents. | No. 1. | No. 2. | No. 3. | No. 4. |
|---------------------------------|--------|--------|--------|--------|
| Peroxide of iron . . . | 80·64 | 81·64 | 66·07 | 67·55 |
| Sesquioxide of iron . . . | 0·96 | 1·41 | ... | ... |
| Peroxide of manganese . . . | 0·98 | 1·75 | 6·91 | 8·73 |
| Alumina | 1·20 | 0·40 | 0·40 | 0·20 |
| Lime | 1·90 | 2·55 | 9·83 | 8·65 |
| Magnesia | 0·63 | 0·51 | 0·39 | 0·48 |
| Carbonic acid | ... | 0·76 | 6·90 | 6·80 |
| Silica | 7·23 | 5·43 | 3·67 | 3·47 |
| Sulphur | trace. | trace. | 0·06 | 0·02 |
| Phosphoric acid | 0·07 | 0·05 | 0·06 | 0·07 |
| Combined water | 5·68 | 5·08 | 4·61 | 4·43 |
| Moisture | 0·81 | 0·76 | 1·37 | 1·57 |
| Total | 100·10 | 100·34 | 100·27 | 101·97 |
| Metallic iron per cent. | 57·20 | 58·25 | 46·25 | 45·90 |
| Manganese per cent. | 0·61 | 0·89 | 5·62 | 7·33 |

The reduction of these ores commenced in the works above-named about the year 1873, north country coke being alone employed, the pig iron produced by its superior quality proving the high character of the ores, which, being in part calcareous, are mixed with one another when charged into the blast furnace, so as to require no limestone or other flux to assist in their reduction. The pig iron produced has proved of admirable quality, and well adapted for conversion into steel by the Bessemer process, while puddled steel has also been made from it. Owing to the quantity of manganese contained in the pig iron, it is considered to be particularly well suited for the manufacture of steel.

The quantities imported do not appear regularly in the official returns, being included with ores received from other countries; in 1875, however, the quantities imported amounted to 10,249 tons, valued at £14,736, giving an average of 26s. per ton.

Norway.—The ores of Norway are chiefly magnetic, and have been wrought from a remote period. The principal deposits are found in the neighbourhood of Kragerø and Arendal, and have a range of many miles in a direction parallel to the coast, occurring in hornblendic and micaceous schists. The mines near Arendal are situated at Langsev and Solberg. At Langsev and at the Barbo, an adjoining mine, a large rock of garnet is intimately mixed with augite, calcspar, and magnetic iron ore; where the latter forms concentrations, which are sometimes 3 to 4 fathoms thick, and contain from 30 to 40 per cent. of iron, the

ore is obtained in open quarry workings. The Solberg Mine produces a similar ore, being a mixture of magnetic iron ore, garnet, augite, and calcspar, and both ores are smelted without a flux, yielding a pure and exceptionally strong iron. The deposits are not extensively worked, as the yield of metallic iron does not exceed 40 per cent., and consequently the ores are not exported to any great extent.

Since the year 1865 the quantities of iron ore imported into Great Britain from the mines of Norway appear in the annexed table, with the respective values :—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1865 | 5,850 | 8,372 | 1872 | 21,014 | 25,098 |
| 1866 | 4,857 | 5,441 | 1873 | 16,651 | 17,985 |
| 1867 | 5,560 | 5,367 | 1874 | 28,680 | 32,786 |
| 1868 | 12,073 | 10,503 | 1875 | 24,192 | 26,813 |
| 1869 | 16,556 | 12,822 | 1876 | 8,749 | 8,927 |
| 1870 | 15,928 | 12,532 | 1877 | 5,865 | 6,421 |
| 1871 | 2,264 | 1,975 | 1878 | 1,023 | 978 |

The imported quantities from Norway show a great falling off since 1875 from 24,192 tons to 1,023 tons in 1878, and in the year 1879 the name has disappeared from the customs returns. In 1874, the year of greatest importation, the average price of these ores was 22s. per ton.

Sweden.—Ores of iron exist in abundance in this kingdom, although mineral fuel is almost entirely deficient, and the little it possesses has not yet been utilised in its iron industries. The iron ores of Sweden are either magnetic iron ore or specular iron ore and hematite, principally found in metamorphic gneiss; also bog iron ores. The most celebrated mines are those worked at Taberg, in Jonkoping, where a greenstone, containing over 30 per cent. of iron and 6·2 per cent. of titanium and vanadium, constitutes a whole mountain. Another important district, Upsala county, may be mentioned, where are situated the celebrated mines of Dannemora. Bog iron is extensively raised in the counties of Jonkoping, Kronoberg, Kalmar, and Skaraborg; this ore is chiefly reduced in the blast furnaces of the localities named, where foundry pig iron is made, the iron thus made containing so much phosphorus as to unfit it for conversion into malleable iron, it is therefore exclusively employed for the production of light castings, such as stoves, kitchen ranges, and hollow ware.

The iron ores of Sweden imported into Great Britain are inconsiderable, not exceeding 5,850 tons in any one year since 1865. It will, however, be interesting to note the imports and values in each year since 1861, which are as follows; importation ceasing in 1877:—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1861 | 376 | 313 | 1870 | 15 | 37 |
| 1862 | 554 | 533 | 1871 | 397 | 397 |
| 1863 | 270 | 358 | 1872 | 625 | 1,884 |
| 1864 | 1,984 | 1,804 | 1873 | 436 | 1,847 |
| 1865 | 5,850 | 8,372 | 1874 | 41 | 322 |
| 1866 | 4,685 | 6,746 | 1875 | 143 | 740 |
| 1867 | 305 | 475 | 1876 | 23 | 147 |
| 1868 | 1,506 | 2,258 | 1877 | 91 | 431 |
| 1869 | 835 | 1,251 | | | |

Analyses of Swedish Ores.—The following five important varieties illustrate the ores of Sweden, the Dannemora ore No. 1 being especially employed for producing the highest class of steel iron, is referred to as a fine-grained magnetite. In the first analysis, by Ward, the ore is described as a compact black mineral, containing a very small trace of iron pyrites. The second and third, by Noad, are of magnetic ores from Roslagen, on the east coast of Sweden, north of Stockholm; the fourth is of a lake ore from Flaten, Wermland, by Svanberg;* and the last a titanite ore.

RESULTS TABULATED.

| Constituents. | No. 1. | No. 2. | No. 3. | Lake Ore. | Titanic Ore. |
|--------------------------|--------|--------|--------|-----------|--------------|
| Peroxide of iron . . . | 58·93 | 62·06 | 56·80 | 67·59 | 54·00 |
| Protoxide of iron . . . | 27·55 | 28·42 | 27·50 | ... | 28·29 |
| Protoxide of manganese | 0·10 | ... | 0·24 | ... | ... |
| Oxide of manganese . . . | ... | ... | ... | 1·45 | ... |
| Lime | 0·38 | trace. | 1·80 | 0·47 | ... |
| Magnesia | 0·61 | 1·44 | 0·80 | 0·23 | ... |
| Alumina | 0·29 | ... | ... | 4·18 | 0·96 |
| Silica | 12·54 | 7·60 | 13·20 | 7·81 | 3·05 |
| Titanic acid | ... | ... | ... | ... | 13·50 |
| Carbonic acid | 0·12 | ... | ... | ... | ... |
| Sulphur | 0·04 | 0·07 | ... | 0·18 | ... |
| Phosphoric acid | trace. | ... | ... | ... | ... |
| Water | 0·11 | ... | ... | 17·81 | 0·20 |
| Total | 100·67 | 99·59 | 100·34 | 99·72 | 100·00 |
| Metallic iron | 62·60 | 65·60 | 61·16 | 47·32 | 59·80 |

* Bauerman, "Metallurgy of Iron," pp. 62, 79.

Russia.—Ores of iron have in recent years been imported from this distant empire in notable quantities, commanding a very high price, inducing to the belief that they contain chromate of iron.

“The chromic iron ore of the Ural mountains forms masses, nests or veins, in serpentine. The richest kind contains 60 per cent. of chromium, but it is usually less, going as low as 30 per cent., the average being from 52 to 54 per cent.; often it is so intimately mixed with magnetite, that it ceases to be a chrome ore proper. (The deposits are mostly on the eastern slope of the Ural mountains.) Since 1862 they have been in demand for export, but the cost of transport is so great that ores below 50 per cent. are practically unsaleable.”*

Russia is comparatively rich in iron ores, considerable deposits of brown hematite occur in Western Russia in the district of Bieloi; where the upper bed, described as “a brown hematite,” mixed with clay and sand, is found at a depth varying from one to seven feet from the surface, the overlying soil being a reddish-yellow clay. This bed of iron ore varies in thickness from 20 to 30 inches, and in many parts is succeeded by another bed of similar ore from seven to fifteen inches in thickness. The chemical analyses of the ores of the above-named district made at Moscow and St. Petersburg show it to be an hydrated peroxide of iron, with an admixture of sand and clay containing from 29·70 to 35·00 per cent. of metallic iron. Similar ores are said to occur in more than twenty localities situated from each other about fifteen miles in the same district.

Appended are the quantities and values of the ores imported from Russia in each year since 1870, according to the “Trade and Navigation returns”:—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1870 | 7,892 | 58,415 | 1875 | 3,602 | 28,641 |
| 1871 | 3,888 | 23,334 | 1876 | 4,866 | 31,076 |
| 1872 | 14,236 | 94,481 | 1877 | 6,339 | 45,486 |
| 1873 | 4,668 | 37,600 | 1878 | 8,051 | 49,328 |
| 1874 | 12,244 | 94,527 | 1879 | 4,043 | 22,455 |

The total quantity of ore imported in the year 1880 amounted to 15,728 tons, of the declared value of £98,264, giving an average value of nearly £6 5s. per ton.

* *Aperçu des Richesses Minérales de la Russie*, p. 106.

Turkey in Asia.—The ores imported from Turkey, like those from Russia, are of a valuable description, and in all probability of the same character, containing perhaps some chromate of iron. The quantities annually imported since 1866 appear in the following table, with the values :—

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|--------|-------|-------------|--------|
| | Tons. | £ | | Tons. | £ |
| 1866 | 436 | 2,680 | 1873 | 1,329 | 10,927 |
| 1867 | 507 | 3,140 | 1874 | 835 | 5,630 |
| 1868 | 1,427 | 10,850 | 1875 | 6,538 | 46,921 |
| 1869 | 1,717 | 4,800 | 1876 | 7,778 | 54,577 |
| 1870 | 4,426 | 29,140 | 1877 | 12,016 | 70,942 |
| 1871 | 6,032 | 37,923 | 1878 | 3,215 | 16,456 |
| 1872 | 4,090 | 23,295 | 1879 | 4,881 | 34,271 |

The imports in the year 1880 amounted to 10,683 tons, of the value of £71,897, giving an average value of nearly £6 5s. per ton.

Total Imported Ores.—With the foregoing general reference to those countries furnishing supplies of iron ore to the United Kingdom, and the localities of some of the more important deposits, it only remains to give the total quantities and values in each year, which are here appended :—

IRON ORE IMPORTED INTO GREAT BRITAIN.*

| Year. | Quantities. | Value. | Year. | Quantities. | Value. |
|-------|-------------|---------|-------|-------------|-----------|
| | Tons. | £ | | Tons. | £ |
| 1863 | 62,167 | 46,486 | 1872 | 801,503 | 1,014,842 |
| 1864 | 74,163 | 55,702 | 1873 | 967,536 | 1,278,278 |
| 1865 | 76,977 | 72,491 | 1874 | 754,141 | 1,021,481 |
| 1866 | 56,689 | 49,081 | 1875 | 458,693 | 583,571 |
| 1867 | 86,569 | 69,218 | 1876 | 672,235 | 795,510 |
| 1868 | 114,438 | 94,620 | 1877 | 1,142,308 | 1,256,069 |
| 1869 | 131,321 | 101,644 | 1878 | 1,173,860 | 1,161,638 |
| 1870 | 208,310 | 166,190 | 1879 | 1,083,692 | 1,037,719 |
| 1871 | 324,034 | 343,175 | 1880 | 2,634,401 | 2,792,717 |

The returns for 1880 show a remarkable increase over the previous year; the largest importation coming from Spain. Prices showing an upward tendency, from nearly 20s. per ton, in the year 1879, to 22s. per ton in the year 1880.

The aluminous ore known as "Bauxite," though not imported into this country, possesses much interest from the fact that it is

* Trade and Navigation Returns.

employed in some of the Continental iron works, where, in recent investigations on the dephosphorisation of iron and steel, considerable attention has been given to it and its constituents. Seven varieties, subjected to analysis by M. de Wendels, confirming others made by M. Fovey, show the following results. It being remarked that it is impossible to procure bauxite containing much less than 10 per cent. of silica :—

RESULTS TABULATED.

| No. | Kind of Bauxite. | Silica. | Alumina. | Peroxide of iron. | Lime. | Value. |
|-----|---|---------|----------|-------------------|-------|---------------|
| 1 | White | 10·40 | 66·99 | 5·71 | ... | Francs. 16 |
| 2 | Rose coloured | 10·90 | 67·21 | 5·14 | ... | 14 |
| 3 | Red | 11·80 | 53·46 | 23·99 | ... | 10 |
| 4 | Reddish brown | 11·90 | 53·51 | 23·99 | ... | 8 |
| 5 | { Dark reddish brown of compact quality . . } | 34·50 | 29·44 | 23·26 | ... | 5 |
| 6 | { Red with pisolitic iron ore grain } | 9·80 | 41·62 | 35·08 | 3·15 | 6 |
| 7 | { Gray with pisolitic iron ore grain } | 9·70 | 41·54 | 35·46 | 3·10 | 5 |

The value of the bauxite delivered at Arles or Tarascon, near Marseilles, varying, according to quality, from 4s. to 12s. 6d. per ton.

It is explained, in reference to the above analyses, that the specimens were previously dried and calcined. The amount of water contained in the ores *in situ* varying, according to the season, from 12 to 22 per cent. The ores referred to as Nos. 4 and 6 are employed as fluxes, with Algerian ores, in the blast furnaces at Beaucaire, situated near Tarascon.

An Italian Company, some years since made many experiments to use bauxite, for the production of iron. The final result, however, was a failure with considerable loss. Bauxite was formerly used in this country and in France for the production of aluminium, as it was found that the alumina existed in a state of much purity in this ore.

The only deposit of bauxite wrought in the United Kingdom is that worked by the Irish Hill Mining Co., at their Irish Hill and Straid Mines, situated near Ballyclare, in the County Antrim, on the north-east coast of Ireland.*

* For Analyses, see page 778.

CHAPTER XXIV.

FLUXES (LIMESTONES) USED IN PIG IRON MANUFACTURE.

Fluxes (Limestones) used in the reduction of the Ores of Iron in the Blast Furnaces of Great Britain—Description and Analyses of Fluxes used in Durham and Northumberland and the North Riding of Yorkshire—Cumberland—Lancashire—North and South Staffordshire—Northamptonshire—Wiltshire—South Wales and Scotland.

Fluxes (Limestones) used in Pig Iron Manufacture.—*North of England, Durham, Northumberland, and North Riding of Yorkshire.*—The principal flux employed by the iron smelter in the above-named counties is limestone, this material exists abundantly in the districts under review. Adjoining the town of Stanhope the carboniferous or mountain limestone is extensively wrought, furnishing the chief part of the limestone used in the blast furnaces in which the Cleveland stone is smelted. At Stanhope it constitutes a rock of great thickness and is very readily excavated from a bed of from 60 to 70 feet in thickness, lying immediately under the alluvial covering. While speaking of the limestone, it may be mentioned that it is traversed in some places by metalliferous veins occasionally rich in lead, containing among other minerals carbonate and hydrated peroxide of iron.

The composition of the mountain limestone is exhibited in the following analysis:—

RESULTS TABULATED.

| | |
|--|--------|
| Insoluble in hydrochloric acid | 2·00 |
| Peroxide of iron and alumina | 0·98 |
| Magnesia | 1·08 |
| Lime | 53·35 |
| Carbonic acid | 43·02 |
| | <hr/> |
| | 100·43 |
| | <hr/> |

The lime manufactured from this stone is valuable as an agri-

cultural manure, and is also employed for purifying gas, tanning, and other chemical purposes.

The limestone used at the Stockton Iron Works obtained from the Broadwood quarries described as "dark gray in colour, and crystalline;" and another variety used at the Iron Works of the Weardale Company, "slatey gray in colour and containing fossil shells," show the following constituents: both samples were dried at a temperature of 212° Fahr. :—

RESULTS TABULATED.

| Constituents. | Stockton. | Weardale. |
|------------------------------|-----------|-----------|
| Carbonate of lime | 95·92 | 95·55 |
| Carbonate of magnesia . . . | 1·85 | 3·20 |
| Carbonate of iron | 0·53 | trace |
| Carbonate of manganese . . . | trace | ... |
| Siliceous matter | 1·70 | 0·90 |
| Carbonaceous matter | ... | 0·23 |
| Organic matter | trace | ... |
| Phosphate of lime | ... | 0·12 |
| Total | 100·00 | 100·00 |

Another limestone (locality not stated) employed at the South Bank furnaces, Middlesborough-on-Tees, described as "dark gray crystalline limestone," gives the annexed composition in 100 parts.*

RESULTS TABULATED.

| | |
|----------------------------------|---------------|
| Carbonate of lime | 83·65 |
| Carbonate of magnesia | 13·43 |
| Carbonate of iron | 1·71 |
| Carbonate of manganese | trace |
| Phosphate of lime | trace |
| Carbonaceous matter | 0·39 |
| Sand and clay | 0·64 |
| Water and loss | 0·18 |
| Total | <u>100·00</u> |

The Hobberlaw limestone, in the neighbourhood of Alnwick, and the limestone obtained at North Sunderland, examined by Mr. Hugh Taylor, of Cramlington, show the following results. It is remarked of the limestones of these districts, that although they differ but little in colour from the rock in other localities,

* "Cast Iron Experiments," Return No. 497, 1858, p. 35.

yet they answer all the requirements of the iron smelter, as carbonate of lime enters so largely into their composition :—

| Constituents. | Hobberlaw. | Sunderland. |
|--------------------------------|------------|-------------|
| Carbonate of lime | 96·986 | 96·637 |
| Carbonate of magnesia . . . | 1·006 | 1·938 |
| Peroxide of iron and alumina . | ·590 | ·526 |
| Sand | 1·209 | ·707 |
| Total | 99·791 | 99·808 |

The carboniferous limestone of Holy Island, distinguished by a "Top" and "Bottom Bed," exhibits some remarkable conditions, from the quantity of carbonate of magnesia contained in the top bed exceeding 85 per cent.; the respective constituents appear in the annexed analyses :—

| Constituents. | Top Bed. | Bottom Bed. |
|-----------------------------|----------|-------------|
| Carbonate of lime | 59·280 | 96·234 |
| Carbonate of magnesia . . . | 35·121 | 2·076 |
| Iron and alumina | 3·746 | ·242 |
| Sand | 1·384 | 1·273 |
| Total | 99·531 | 99·825 |

The Permian limestone of Raisby Hill and the carboniferous of Harmby, largely employed by the iron smelter, also chalk, which is used in small quantities in admixture with the limestone, exhibit the following results on analyses; it may be observed that the chalk is obtained from the south of England, from whence it is brought by coasting vessels to the northern parts :—

| Constituents. | Raisby. | Harmby. | Chalk. |
|--------------------------------|---------|---------|--------|
| Carbonate of lime | 97·54 | 95·26 | 96·15 |
| Carbonate of magnesia . . . | 0·90 | 2·21 | 1·32 |
| Alumina and peroxide of iron . | 1·35 | 2·98 | 3·20 |
| Total | 99·79 | 100·45 | 100·67 |

Cumberland.—The aluminous ores of the County Antrim, in the North of Ireland, are extensively used as a flux in the iron works of Cumberland, in admixture with the hematite ores.

These ores are fairly represented in the annexed analyses of two samples by Mr. C. Tookey; an analysis of bauxite, by Mr. Bell, is given side by side:—

| Constituents. | Aluminous Ore. | | Bauxite. |
|----------------------------------|----------------|--------|----------|
| Silica | 9·75 | 9·87 | 2·8 |
| Alumina | 27·95 | 34·57 | 57·4 |
| Peroxide of iron | 35·91 | 27·93 | 25·6 |
| Protoxide of iron | 6·57 | 5·08 | ... |
| Protoxide of manganese | 0·05 | traces | ... |
| Lime | 0·60 | 0·91 | 0·2 |
| Magnesia | 0·20 | 0·62 | ... |
| Potash | 0·49 | ... | ... |
| Titanic acid | ... | 3·51 | 3·1 |
| Volatile | 18·60 | 19·36 | 11·0 |
| Total | 100·12 | 101·85 | 100·0 |

The limestone abounding in the Whitehaven district is very generally used as it is a good material. It is described as “fine grained crystalline; light brownish-gray in colour, and containing fossil shells (terebratula);” * on analysis this limestone gives the following results:—

SAMPLE DRIED AT 212° FAHR.

| | |
|-------------------------------------|---------------|
| Carbonate of lime | 97·63 |
| Carbonate of magnesia | 1·03 |
| Carbonate of iron | 0·24 |
| Carbonate of manganese | 0·11 |
| Sulphate of lime | 0·07 |
| Phosphate of lime | trace |
| Carbonaceous matter | 0·06 |
| Alumina | 0·10 |
| Silica (principally sand) | 0·76 |
| Total | <u>100·00</u> |

The ordinary black shale of the coal measures, consisting of clay and carbonaceous matter, and not containing an appreciable amount of sulphur, has occasionally been employed as a flux.

Lancashire. *Fluxes employed.*—The shale of the coal measures sometimes used as a flux is thus composed. The sample examined by Dr. Frankland was obtained from the neighbourhood of Manchester:—

* “Cast Iron Experiments,” Return No. 497, 1858, p. 19.

COAL MEASURE SHALE.

| | |
|-----------------------------|--------------|
| Silica | 61·91 |
| Alumina | 21·73 |
| Protoxide of iron | 4·73 |
| Lime | 0·09 |
| Magnesia | 0·59 |
| Potash | 3·16 |
| Soda | 0·25 |
| Volatile matter | 7·43 |
| Total | <u>99·89</u> |

The carboniferous limestone of Lancashire in which the hematite occurs affords a plentiful and good supply; that used at Askam is obtained from a neighbouring quarry at Stainton, and has the following composition:—

ANALYSIS OF STAINTON LIMESTONE.

| | |
|-------------------------------------|---------------|
| Carbonate of lime | 95·00 |
| Carbonate of magnesia | 4·20 |
| Silica | 0·50 |
| Oxide of iron and alumina | 0·30 |
| Total | <u>100·00</u> |

The aluminous ores of the North of Ireland from the County Antrim are also to some extent employed in admixture with the ores of Furness and Whitehaven, as a means of producing a better slag and to some extent controlling the percentage of silica in the pig iron. These aluminous ores are of several varieties, containing from 20 to 27 and as much as 35 per cent. of alumina, and will be found fully described with their respective analyses in the section devoted to the iron ore deposits of Ireland.

North Staffordshire.—The limestone raised from the Froghall quarries, and used at the Goldendale Iron Works, near Stoke-upon-Trent, described as “light coloured and crystalline,” gives the following constituents on analysis:—

SAMPLE DRIED AT 212° FAHR.

| | |
|----------------------------------|--------------|
| Carbonate of lime | 97·89 |
| Carbonate of magnesia | 0·87 |
| Carbonate of iron | 0·48 |
| Carbonate of manganese | traces |
| Phosphate of lime | trace |
| Silica (sand) | 0·63 |
| Total | <u>99·87</u> |

South Staffordshire.—The Silurian limestone of Dudley is extensively employed in the furnaces of South Staffordshire and Worcestershire. The varieties used in the Netherton furnaces and the Park Head furnaces, derived from the Dudley quarries, are described as “light-coloured and crystalline,” average samples being selected for analysis from fine and coarse grained specimens, giving the annexed results :—

| Constituents. | Netherton Furnace. | Park Head Furnace. |
|--------------------------------|-----------------------|-----------------------|
| Carbonate of lime . . . | 97·31 | 97·10 |
| Carbonate of magnesia . . . | 1·00 | 0·85 |
| Carbonate of iron . . . | 0·62 | 0·60 |
| Clay and sand . . . | 1·27 | 1·15 |
| Organic matter and water . . . | 0·20 | ... |
| Water and loss . . . | ... | 0·30 |
| Total . . . | 100·40 | 100·00 |

Another limestone obtained from the Springfield quarry, Dudley, used at the Old Hill furnaces, being described as “light-coloured, crystalline; with a small vein of quartz running through the sample,” exhibits the annexed constituents. In each case the limestone was dried at 212° Fahr. :—

| | |
|---------------------------------|---------------|
| Carbonate of lime | 88·85 |
| Carbonate of magnesia | 2·03 |
| Carbonate of iron | 1·21 |
| Phosphoric acid | 0·26 |
| Siliceous matter | 8·15 |
| Total | <u>100·50</u> |

Traces of carbonate of manganese and organic matter were also found, it being further ascertained that the siliceous matter consisted of quartz with a little clay.

Northamptonshire.—The materials principally employed are light-coloured argillaceous limestone and chalk; of the former, two varieties may be referred to, the one “pale yellow in colour, and oolitic in structure;” the other “light-coloured and composed entirely of an agglomeration of fossil shells;” while the chalk is of the ordinary description, consisting of carbonate of lime, with traces only of silica, alumina, peroxide of iron and carbonate of magnesia. The two following analyses of limestone are obtained

from samples dried at a temperature of 212° Fahr., and have the following constituents:—*

RESULTS TABULATED.

| Constituents. | No. 1. | No. 2. |
|-----------------------------------|--------|--------|
| Carbonate of lime | 89·36 | 96·86 |
| Carbonate of iron | 3·38 | 1·36 |
| Carbonate of magnesia | 0·97 | 0·90 |
| Siliceous matter | ... | 0·88 |
| Organic matter | trace | ... |
| Ferruginous clay and sand | 6·00 | ... |
| Water | 0·43 | ... |
| Total | 100·14 | 100·00 |

The first named variety was formerly employed at the East End Ironworks, near Wellingborough, of Messrs. Butlin and Co. These works have been for some years dismantled; and the second variety at the Heyford Iron Works, near Weedon, during the occupation of Messrs. Judkins and Co.

Wiltshire.—The rocks of the immediate neighbourhood yield the required materials, two varieties are at hand, and are advantageously used as reducing agents in the smelting operations of the blast furnace. The one a limestone, oolitic in character, the other a hard chalk, both rich in carbonate of lime, which will appear in the following analysis of each variety:—

| Constituents. | Oolitic Limestone. | Hard Chalk. |
|----------------------------|--------------------|-------------|
| Carbonate of lime | 91·833 | 93·104 |
| Magnesia | 0·796 | 0·188 |
| Oxide of iron | 0·885 | ... |
| Oxide of manganese | 0·721 | ... |
| Alumina | 1·102 | trace |
| Potash | 0·584 | ... |
| Soda | 0·610 | ... |
| Sulphuric acid | 0·897 | ... |
| Phosphoric acid | trace | ... |
| Silica | 1·204 | 1·110 |
| Chloride of sodium | ... | trace |
| Carbonate of iron | ... | 2·677 |
| Phosphate of lime | ... | 0·523 |
| Sulphate of lime | ... | 0·132 |
| Organic matter | ... | 1·865 |
| Water and loss | 1·368 | 0·401 |
| Total | 100·00 | 100·00 |

* "Cast Iron Experiments," Return No. 497, 1858, p. 118.

The Westbury Iron Company (Limited) in the year 1862 contributed a most interesting and instructive series of the materials employed, and the products of their furnaces, to the exhibition of London in that year, and at the close of the exhibition presented the collection to the Museum of Practical Geology, where it was in due course deposited and may be examined. The case containing the collection will be found on the principal floor, at the south east corner, amongst the specimens illustrating the manufacture of iron. It comprises samples of the Wiltshire ore from Westbury, of the brown and green varieties, of which analyses appear in a previous page, as well as the oolitic limestone and hard chalk used as fluxes; examples of the iron made from Nos. 1 to 4 are included, exhibiting the structure and character of each variety, and the cinder obtained therefrom.

Bright iron, white iron, and mottled iron, also refined metal, are illustrated in the series, together with a sample of the cinder produced by each variety. There also appears in this collection some very curious and interesting products derived from the furnaces, amongst which may be named Cyano-Nitride of titanium, and an artificial graphite known as "Kish."

South Wales.—Few of the ores of iron are found to contain earthy ingredients in proportions sufficient to form readily fusible slags alone, it therefore becomes necessary to supply the deficiency. This is done by the admixture of ores of dissimilar character; for instance, siliceous with calcareous ores or both with argillaceous ores in such quantities as shall yield slags of the desired composition, or by the addition of calcareous or aluminous minerals not containing iron. The principal flux employed by the iron smelter is limestone, usually obtained from a neighbouring quarry, the varieties selected being such as contain the greatest amount of carbonate of lime. In the case of the rich red hematite ores of the West Coast of Ulverston and Whitehaven, argillaceous fluxes are necessary in addition to limestone. Aluminous ore obtained from the County Antrim, and known as "Belfast aluminous ore," containing a large quantity of free alumina, has in recent years been extensively used.

Of the fluxes used in the South Wales furnaces, those situated in the eastern area of the coal-field in Monmouthshire employ two varieties of limestone, known as "rough" and "smooth;" these are employed at the Blaenavon Iron Works, and are thus

described in the Report of cast iron experiments made at Woolwich, as follows:—

1. "Rough limestone" has a large crystalline structure, is light brown in colour, and contains numerous fossil shells.

2. "Smooth limestone" has an oolitic structure and is usually pale in colour.

SAMPLES DRIED AT 212° FAHRENHEIT.

| Constituents. | Rough. | Smooth. |
|-----------------------------|--------|---------|
| Carbonate of lime . . . | 98·55 | 99·26 |
| Carbonate of magnesia . . . | 0·54 | 0·63 |
| Carbonate of iron . . . | 0·50 | 0·33 |
| Phosphate of lime . . . | 0·03 | 0·02 |
| Silica (sand) . . . | 0·73 | 0·27 |
| Total . . . | 100·35 | 100·51 |

Scotland.—Analyses of limestones employed in the iron furnaces of Scotland. The following are some of the most important, examined by Mr. St. John V. Day, C.E., of Glasgow, and published in "Iron" in 1876:—

| Constituents. | 1. | 2. | 3. | 4. | 5. | 6. |
|----------------------------------|--------|--------|--------|--------|--------|--------|
| Lime . . . | 50·46 | 51·97 | 51·93 | 52·35 | 49·30 | 47·98 |
| Magnesia . . . | ·62 | ·29 | ·60 | ·21 | ·49 | 1·71 |
| Protoxide of iron . . . | ·48 | ·90 | ·66 | ·16 | ·51 | ·98 |
| Carbonic acid . . . | 40·57 | 41·61 | 41·72 | 41·44 | 39·57 | 40·02 |
| Phosphoric acid . . . | ·05 | ·09 | ·16 | ·02 | ·02 | ·17 |
| Sulphur . . . | ·12 | ... | ·21 | ·16 | ·26 | ·32 |
| Iron combined with sulphur . . . | ·11 | ... | ·18 | ·14 | ·23 | ·28 |
| Alumina . . . | 2·61 | ·92 | 1·25 | 1·48 | 2·42 | 2·54 |
| Silica . . . | 4·88 | 2·48 | 1·92 | 2·64 | 6·60 | 4·80 |
| Organic matter . . . | trace | 1·44 | 1·07 | 1·10 | ·40 | ·84 |
| Water . . . | ·10 | ·30 | ·30 | ·30 | ·20 | ·36 |
| Total . . . | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 | 100·00 |
| Specific gravity . . . | 2·553 | 2·727 | 2·715 | 2·703 | 2·717 | 2·500 |

CHAPTER XXV.

COAL USED IN PIG IRON MANUFACTURE IN GREAT BRITAIN.

Coal used towards the close of the past century—Mr. W. Jessop's Inquiry—Coal Commission and Mining Record Office Inquiries—Coal used in recent years since 1871—Details of Coal used and Iron made in the years 1872 and 1890—Extent of economy in each year since 1871.

Coal used in Pig Iron Manufacture.—It appears desirable, at the conclusion of a work so full of statistical details as this volume is, that a general summary should be given, directing attention to the more important points in this large inquiry. In the year 1788 the average quantity of coal employed was 7 tons to each ton of pig iron produced in the furnaces of England and Wales. Ten years later the quantity employed did not exceed 6 tons, and between 1800 and 1802 the consumption averaged but 5 tons.

Mr. William Jessop's Return, which has been frequently referred to, gives the average consumption in the furnaces of Great Britain, in the year 1840, as not exceeding 70 cwts. of coal to each ton of pig iron made.

The Report of the Royal Coal Commission in the year 1870, shows that the quantity of coal employed was 60 cwts., compared with 70 cwts. thirty years previously. Before considering in detail the advance made in recent years towards economy in the use of fuel in pig iron manufacture, it will be a fitting place to refer to some important observations recently made by the President of the Society of Engineers, on the subject of the manufacture of iron, in which he observes :—

“ Competition in this and other countries, through the opening out by new railways of fresh iron and coal measures, and in consequence of every one endeavouring to do more than his neighbour, and to reduce the cost of smelting iron to the lowest

amount, has, I fear, in many instances, not contributed to the improvement in the quality of iron. The lives of blast furnaces are of very short duration, compared with what they were in the early part of the present century. I can give two instances of the length of time furnaces lasted without being blown out, and which furnaces were at the Alfreton Iron Works, Derbyshire. One blown in during the year 1812, was in blast till 1879, whilst another blown in during 1821 was not blown out until 1866. This latter furnace was visited by the members of the British Association, during their meeting at Nottingham. After the furnace was blown out, an examination showed that there had been formed a partial lining of plumbago, which protected the fire brick lining, which I think you will admit was a very remarkable incident in blast furnace practice. I do not find charcoal had been used in smelting during the earlier period of the life of these furnaces. Coke alone was used up to the year 1829, when equal parts of coal and coke were substituted. The introduction of the hot blast was the cause of all coal being used; at that time the Furnace or Tupton coal, mixed with a lower hard coal, was the fuel used. The ironstone used was the argillaceous of the coal measures, containing from 25 to 37 per cent. of metallic iron. The iron in the raw stone exists as a carbonate, and requires calcining at a cherry red heat to convert the carbonate into a peroxide of iron for smelting. Iron made from this ore is very strong indeed. The bands of ironstone, technically called 'rakes,' are some of them found with the coal seams; the blue rake lies above the lower hard coal; the kernel rake lies above the yard coal. Nine different rakes have been worked at the Alfreton Iron Works, and it was found that the greater the variety used, the better and stronger was the iron produced. I find Durham coke the best for smelting furnaces. The demand for iron being greater, and the deposits of the oolitic formation being used, iron making took a new form. Blast furnaces were constructed to produce very large quantities of pig iron, and works were erected for the purpose of using the oolitic ores alone. In consequence of not having any of the old strong argillaceous ores mixed with them, iron sometimes gets into bad repute, and makers of strong iron are sometimes to their disadvantage classed with others who do not so mix the iron ores. I find also

that the hard coal of Derbyshire gives the iron a better quality than coke as used in the north."

"Furnaces using coal do not require to be built more than 50 feet high, but those using coke are best at 70 feet or upwards. Low furnaces are undoubtedly the best for the iron ores lying in the Midland Counties, and are about 48 feet high, 3 to 3½ inch tuyeres, pressure of blast 4 to 4½ lbs., and blast heated to about 750° Fahr. A furnace of this description makes a good tenacious iron, from a mixture of ores from Lincolnshire, Leicestershire, Northamptonshire, and the argillaceous ores of Derbyshire, and smelted with the best hard coal, clean and free from pyrites. Remelting iron in the cupola should be very carefully performed. The iron should consist of a mixture of three or four kinds of pig, and the coke should be very clean and free from sulphur; or, however good the pig iron may be, the remelting will ruin the iron, make it tender, and it will not sustain nearly the strain it should do, hence some of the best founders do not sell pig iron. The metal from the blast furnace requires testing every day, and if the remelting be carefully carried out, and the castings allowed to remain in the sand long enough to prevent them being chilled, there need then be no fear of the iron not standing the required test, which generally is as follows:—

"That a bar of 1 inch square, and 38 inches long, and weighing not more than 10 pounds, will, when supported at points 36 inches apart, and loaded in the middle, sustain a weight of not less than 7 cwt. I think it would be well for every one entering our profession to go first for a time into a foundry and see for himself the varying contraction which goes on in different kinds of iron; afterwards he should go into the pattern shop. He would afterwards remember to design his works so that the iron should contract as far as possible uniformly, and so that one part should not fracture another during cooling, which is very often the case."

Returning to the question of the economy of fuel in manufacture, the year 1878, known as the year of the coal famine, led to more precise information on the subject; in that year a Committee of the House of Commons appointed to inquire into the cause of the "Dearness and Scarcity of Coal," extended its inquiries to the quantities consumed in the manufacture of pig

iron; circulars were issued to every ironmaster in the country; these were liberally responded to, and the result of the inquiry showed that in the manufacture of 6,741,929 tons of pig iron made in the year 1872, the total quantity of coal employed amounted to 17,211,729 tons, thus distributed in Great Britain:

| | Pig Iron. | Coal Used. |
|--------------|-----------|------------|
| | Tons. | Tons. |
| England . . | 4,594,614 | 11,388,342 |
| Wales . . . | 1,057,315 | 2,607,887 |
| Scotland . . | 1,090,000 | 3,215,500 |
| Total . . . | 6,741,929 | 17,211,729 |

These figures giving an average of 2 tons 11 cwt. of coal to each ton of pig iron made. In some districts this average was greatly exceeded, particularly in the West Riding of Yorkshire and Shropshire, where coal is still employed in the furnaces, in making those brands of iron for which these districts are celebrated; the average in the West Riding district in 1872 was 65 cwts. of coal, and in Shropshire 47 cwts. of coal to each ton of pig iron made.

The Durham, Lancashire, and Cumberland districts, in which the rich coke of the Great Northern Coal Field is extensively employed, giving an average respectively of 40 cwts., 42 cwts., and 47 cwts. to each ton of pig iron made.

Again, in Scotland where raw coal is extensively used in the smelting operations of the blast furnaces, the average in 1872 was 55 cwts. of coal to each ton of iron. Of late years, however, the more general application of gas-saving apparatus in iron works has largely contributed to economy in the use of fuel.

Taking the years 1872 and 1873 when these special series were instituted as marking a new era in the history of iron and of coal used in manufacture, the annexed statement for the named year will afford generally reliable information and serve for comparison in the returns of production in future years.

In this table appears the numbers of furnaces in each iron-producing district, in Great Britain, the iron made, coal used, with the average yield per furnace, and of coal used to each ton of pig iron made in the year 1873 :—

| Districts. | FURNACES. | | Pig Iron Made. | Coal Used. | AVERAGE. | |
|--|-----------|-----------|----------------|------------|--------------|------------|
| | Built. | In Blast. | | | Per Furnace. | Coal Used. |
| | Nos. | Nos. | Tons. | Tons. | Tons. | Cwts. |
| <i>England—</i> | | | | | | |
| Northumberland | 10 | 4 | 44,807 | 101,347 | 11,202 | 45 |
| Durham | 54 | 49½ | 799,573 | 1,848,100 | 16,071 | 40 |
| Yorkshire, North Riding | 78 | 76 | 1,156,431 | 2,643,997 | 15,216 | 46 |
| „ West Riding | 40 | 30 | 151,511 | 493,976 | 5,050 | 65 |
| Derbyshire | 47 | 39 | 296,468 | 865,350 | 7,601 | 68 |
| Lancashire | 44 | 36 | 529,271 | 1,108,192 | 14,702 | 42 |
| Cumberland | 48 | 33½ | 456,877 | 1,079,118 | 13,638 | 47 |
| Shropshire | 29 | 21 | 135,149 | 407,876 | 6,435 | 60 |
| Staffordshire, North | 36 | 29 | 241,166 | 710,856 | 8,316 | 59 |
| „ South | 142 | 99 | 673,397 | 1,968,680 | 6,801 | 58 |
| Northamptonshire | 16 | 10 | 58,480 | 169,592 | 5,848 | 58 |
| Lincolnshire | 13 | 9 | 52,076 | 142,236 | 5,786 | 55 |
| Gloucestershire | 10 | 6 | 44,409 | 134,019 | 3,841 | 60 |
| Wiltshire | 7 | 5 } | 48,944 | 131,293 | 8,157 | 53 |
| Somersetshire | 1 | 1 } | | | | |
| Total England | 575 | 448½ | 4,688,199 | 11,804,632 | 10,406 | 51 |
| <i>North Wales—</i> | | | | | | |
| Denbighshire | 9 | 5 | 42,773 | 135,180 | 8,554 | 63 |
| Flintshire | 4 | 3 | 24,690 | 52,098 | 8,230 | 42 |
| Total North Wales | 13 | 8 | 67,463 | 187,278 | 8,433 | 55 |
| <i>South Wales—</i> | | | | | | |
| Anthracite furnaces | 13 | 8 | 32,322 | 81,837 | 4,102 | 50 |
| Bituminous Coal } Glamorganshire | 73 | 51 | 424,384 | 1,047,245 | 8,321 | 49 |
| Districts } Monmouthshire | 62 | 42 | 360,583 | 867,640 | 8,585 | 48 |
| Total South Wales | 148 | 101 | 817,789 | 1,996,722 | 8,012 | 50 |
| <i>Scotland</i> | 156 | 126 | 993,000 | 2,730,000 | 7,881 | 55 |
| Total Great Britain | 892 | 683½ | 6,566,451 | 16,718,532 | 9,512 | 50½ |

Since the year 1872 a great advance has been made in the economical use of coal in pig iron manufacture. In that year the average consumption of coal in Great Britain did not exceed 51 cwts., the returns for 1873 as given above, being slightly less, about 50½ cwts., showing a saving of one quarter cwt. on each ton of pig iron made. The amount appears trifling, yet when considered with reference to the total production of pig iron, it gives an aggregate of nearly 835,000 tons of coal. This economy appears prominently in the annexed table, giving the quantity of pig iron made, of coal used in its manufacture, and the average quantity of coal employed to each ton of pig iron made in each of the following years :—

| Year. | Pig Iron Made. | Coal Used. | Coal Used per Ton of Iron. | | |
|-------|----------------|------------|----------------------------|-------|------|
| | Tons. | Tons. | Tons. | Cwts. | Qrs. |
| 1871 | 6,627,179 | 19,881,537 | 3 | 0 | 0 |
| 1872 | 6,741,929 | 17,211,729 | 2 | 11 | 0 |
| 1873 | 6,566,451 | 16,718,562 | 2 | 10 | 3 |
| 1874 | 5,991,408 | 15,292,201 | 2 | 11 | 2 |
| 1875 | 6,365,462 | 15,645,774 | 2 | 9 | 0 |
| 1876 | 6,555,997 | 15,598,381 | 2 | 8 | 0 |
| 1877 | 6,608,664 | 15,342,445 | 2 | 6 | 2 |
| 1878 | 6,381,051 | 14,112,005 | 2 | 4 | 2 |
| 1879 | 5,995,337 | 13,117,411 | 2 | 4 | 0 |
| 1880 | 7,749,233 | 16,982,629 | 2 | 3 | 3 |

The average consumption of coal used in the year 1874 exhibits an increase over previous years; this can scarcely be the case, and a careful consideration of the question points to the probability that in the year named too high an average was taken in the conversion of coke into its equivalent of coal. There is, therefore, good reason to assume that the average consumption of coal in that year did not exceed 2 tons 10 cwts. to each ton of pig iron made.

From the above statement it will be seen that during the past decade a saving of upwards of 16 cwt. of fuel has been effected in the manufacture of each ton of pig iron, equivalent to 26·6 per cent. in the fuel used in 1880 compared with the year 1871.

To bring out more clearly the extent of the economy secured since the year 1871, when the average consumption was 60 cwt. of coal to each ton of pig iron produced in the blast furnace, the following table has been prepared, showing the actual quantity of coal used in each year since 1871; the quantity that would have been consumed had the average of the year 1871 been maintained; and the extent of the economy in each year since 1871, between the actual returns, and the assumed, of 3 tons of coal to each ton of pig iron.

It will be seen from the annexed table that in the ten years ending 1880, the total quantity of coal used in pig iron manufacture in Great Britain, amounted to 159,902,674 tons; had the average of 1871 been maintained 196,748,193 tons would have been the quantity consumed; the extent of economy, amounting to 36,845,459 tons, therefore represents an actual saving of coal in ten years of no less than 23·00 per cent. in this branch of our national industries.

| Year. | Coal Used in Pig Iron Manufacture. | Assuming Three Tons of Coal to each Ton of Pig Iron. | Extent of Economy in each Year. |
|-------|------------------------------------|--|---------------------------------|
| | Tons. | Tons. | Tons. |
| 1871 | 19,881,537 | 19,881,537 | ... |
| 1872 | 17,211,729 | 20,225,787 | 3,014,058 |
| 1873 | 16,718,562 | 19,699,353 | 2,980,791 |
| 1874 | 15,292,201 | 17,974,224 | 2,682,023 |
| 1875 | 15,645,774 | 19,096,386 | 3,450,612 |
| 1876 | 15,598,381 | 19,667,991 | 4,069,610 |
| 1877 | 15,342,445 | 19,825,992 | 4,483,547 |
| 1878 | 14,112,005 | 19,143,153 | 5,031,148 |
| 1879 | 13,117,411 | 17,986,011 | 4,868,600 |
| 1880 | 16,982,629 | 23,247,699 | 6,265,070 |
| Total | 159,902,674 | 196,748,133 | 36,845,459 |

Of the many improvements in late years tending to economy in the use of fuel in pig iron manufacture, the enlargement of the furnace may be referred to, its increased height and capacity securing, to the utmost limits, the pressure that the coal or coke would stand without being crushed by the superincumbent weight of materials in the furnace; and enabling a greater pressure of blast to be employed. Another improvement which has of late years exercised an important influence on our iron industries, is the raising of the blast to double the temperature that was usual when the hot blast was introduced by Neilson, and for a considerable period afterwards. This is effected by the use of a firebrick "Regenerator" (such as is known as a "Siemens Regenerator"), placed inside an air-tight wrought-iron case, such firebrick being heated by the combustion of the waste gases from the top of the furnace. The cold blast to be heated is then passed in the reverse direction through this hot brickwork, so that it is raised to a temperature of 1,500 degrees Fahrenheit, or a full red heat. These stoves are known as "Cowper's Stoves," and "Whitwell's Stoves," after the names of the inventors, and are extensively employed, not only in Great Britain, but also in Continental countries, and in the United States of America.

The saving of fuel in the use of these stoves varies in different districts; twenty per cent., however, may be generally regarded as the increased make of the furnace and the economy in each ton of iron made where these arrangements have been introduced.

With these general remarks, it only remains to refer to the

volume of Mineral Statistics of the United Kingdom for the year 1880, giving the details appearing in the annexed table, of the furnaces built and in blast, of pig iron made and coal used in each iron-making district in Great Britain; to which is added the average yield per furnace, and of coal used in manufacture:—

| Districts. | FURNACES. | | Pig Iron Made. | Coal Used. | AVERAGE. | |
|--|-----------|-----------|----------------|------------|--------------|------------|
| | Built. | In Blast. | | | Per Furnace. | Coal Used. |
| | Nos. | Nos. | Tons. | Tons. | Tons. | Cwts. |
| <i>England—</i> | | | | | | |
| Northumberland | 4 | 2 | 750,262 | 1,420,766 | 23,445 | 38 |
| Durham | 72 | 30 | | | | |
| Yorkshire, North Riding | 91 | 80 | 1,666,156 | 3,611,543 | 20,825 | 45 |
| West Riding | 47 | 33 | | | | |
| Derbyshire | 54 | 40 | 366,792 | 964,035 | 9,169 | 52 |
| Lancashire | 49 | 37 | 750,884 | 1,362,164 | 20,291 | 36½ |
| Cumberland | 51 | 40 | 790,343 | 1,604,097 | 19,758 | 40½ |
| Shropshire | 24 | 12 | 88,338 | 249,254 | 7,361 | 56½ |
| Staffordshire, North | 36 | 23½ | 225,023 | 434,171 | 9,575 | 38½ |
| South | 137 | 46 | 384,556 | 878,581 | 8,360 | 45½ |
| Northamptonshire | 23 | 17 | 178,714 | 470,165 | 10,512 | 52½ |
| Lincolnshire | 21 | 15 | 207,704 | 481,807 | 13,847 | 46 |
| Gloucestershire | 9 | 2 | 37,351 | 97,550 | 10,672 | 53 |
| Wiltshire | 4 | 1½ | | | | |
| Hampshire | 1 | .. | | | | |
| Somersetshire | 1 | .. | | | | |
| Total England | 624 | 379 | 5,752,683 | 12,333,642 | 15,180 | 42½ |
| <i>North Wales—</i> | | | | | | |
| Denbighshire | 8 | 5 | 57,812 | 139,328 | 8,259 | 48 |
| Flintshire | 2 | 2 | | | | |
| Total North Wales | 10 | 7 | 57,812 | 139,328 | 8,259 | 48 |
| <i>South Wales—</i> | | | | | | |
| Anthracite furnaces | 11 | 4 | 440,915 | 922,155 | 12,970 | 42 |
| Bituminous Coal Districts. } Glamorganshire. | 74 | 30 | | | | |
| } Monmouthshire | 56 | 35 | 448,823 | 1,045,449 | 12,823 | 46½ |
| Total South Wales | 141 | 69 | 889,738 | 1,967,604 | 25,793 | 44½ |
| <i>Scotland</i> | 149 | 112½ | 1,049,000 | 2,542,055 | 8,134 | 48½ |
| Total Great Britain | 924 | 567½ | 7,749,233 | 16,982,629 | 10,113 | 43½ |

The following section arranged by Mr. Hilary Bauerman, F.G.S., shows clearly the Distribution of British Iron Ores in the various Geological Strata:—

GEOLOGICAL DISTRIBUTION OF BRITISH IRON ORES.

| Formations. | Ores. | Principal Localities. | Production in 1880. |
|------------------------------------|---|--|-------------------------------------|
| MIOCENE (Igneous). | Brown Aluminous. | Basalt of Antrim, Larne, Red Bay, Glenarm, &c. | Tons. 234,751 |
| Eocene. | Nodular Carbonate. | London Clay, Dorsetshire (not worked) | .. |
| UPPER CRETACEOUS. | .. | .. | .. |
| LOWER CRETACEOUS. | Brown, Sandy. { | Lower Greensand, SEKND , Wiltshire . . . | .. |
| | Calcareous, Brown. } | " Linslade, Bucks (not now worked) } | .. |
| | | Neocomian Tealby, Lincolnshire . . | .. |
| WEALDEN. | Nodular Carbonate. | Weald of Kent and Sussex (not now worked) | .. |
| UPPER OOLITE. | .. | .. | .. |
| MIDDLE OOLITE. | Brown Oolitic. | Coral Rag, Westbury, Wilts | 67,500 |
| LOWER OOLITE. | Brown Oolitic. { | NORTHAMPTON SAND in Oxfordshire . . . | } 1,550,013 |
| | Brown and Magnetic. } | Northamptonshire, Lincolnshire, &c. . | |
| | | Dogger Ironstone, ROSEDALE , Yorkshire . | 6,079 |
| UPPER LIAS. | .. | .. | .. |
| MIDDLE LIAS (Marlstone). | Brown Oolitic. { | Adderbury, Fawler, } Oxfordshire . . . | } 8,360 |
| | Argillaceous Carbonate. } | Steeple Ashton } CLEVELAND IRONSTONE, North Riding of Yorkshire } | |
| LOWER LIAS. | Brown Oolitic. | Brigg, Scunthorpe, &c., N. Lincolnshire . | 1,154,584 |
| TRIAS (New Red Sandstone). | Red and Brown. | Red Hill, &c., near Bristol (included in Somersetshire). | .. |
| PERMIAN. | .. | .. | .. |
| COAL MEASURES. | Nodular Carbonates (principally). | COAL-FIELDS OF { Yorkshire 286,698 Derbyshire 150,248 North Staffordshire 1,350,313 South " 362,773 Shropshire 226,721 Warwickshire 36,972 North Wales 41,413 South " 278,361 Gloucester and Somerset 875 | |
| CARBONIFEROUS LIMESTONE. | Clay Band and Black Band Nodular Carbonate. { | COAL-FIELDS OF SCOTLAND, | 2,659,317 |
| | Brown. Red. Spathic, and Brown. } | Riddale, Northumberland Gloucestershire and Dean Forest FURNESS and WHITEHAVEN Alston Moor and Weardale (Lead District of Northumberland and Durham) . . | .. 92,159 2,767,944 41,359 |
| DEVONIAN. | Spathic, Brown-Red, and Magnetic. | Somersetshire Devonshire Cornwall | 29,818 12,653 15,865 |
| SILURIAN. | Red, Brown. { | Skiddaw Slate and Granite of Ennerdale, Eskdale, &c., Cumberland | } 4,574 |
| | Spathic, and Brown. } | Wicklow Isle of Man | |
| CAMERIAN. | Magnetic Oolitic. | Tremador, Cader Idris, &c., North Wales | .. |

APPENDICES.

No. 1.—IRON ORE AND PURPLE ORE. PRODUCTION IN THE UNITED KINGDOM.

No. 2.—PIG IRON MANUFACTURE. RETURNS OF PRODUCTION SINCE 1740, AND EXPORTS SINCE 1829.

No. 3.—MALLEABLE IRON WORKS, MILLS, AND FORGES, AND STEEL WORKS;—LIST OF WORKS, AND PRODUCTION OF BAR IRON IN 1750, AND FROM 1861 TO 1880—BESSEMER STEEL WORKS IN GREAT BRITAIN AND PRODUCTION OF BESSEMER STEEL—OPEN HEARTH STEEL WORKS IN GREAT BRITAIN, AND PRODUCTION OF OPEN HEARTH STEEL—SIEMENS' REGENERATIVE GAS FURNACES FOR MELTING STEEL IN CRUCIBLES, AND PRODUCTION OF CRUCIBLE STEEL.

No. 4.—TIN PLATE MANUFACTURE. LIST OF WORKS—PRODUCTION AND EXPORTS OF TIN PLATES.

APPENDIX—No. 1.

IRON ORES PRODUCED FROM THE MINES OF THE UNITED KINGDOM—AND PURPLE ORE OBTAINED FROM METAL EXTRACTION WORKS.

TABLE I.—Iron Ore raised from the Mines of the United Kingdom.

„ II.—Iron Ores raised in the years 1860, 1870 and 1880.

„ III.—Ironstone raised from the Coal Measures in the years 1860, 1870 and 1880.

„ IV.—Purple Ore—Analyses and Quantities obtained in each year since 1871.

TABLE I.

IRON ORE PRODUCE

Raised from the Mines of the United Kingdom in each of the following Years, distinguishing the quantities of Argillaceous Carbonates and Black Bands, obtained from the Coal Measures, from that raised from Mines and Workings not in the Coal Measures:—

| Year. | Ore not in Coal Measures. | Ore from Coal Measures. | Total Ore Raised. |
|-------|------------------------------|----------------------------|----------------------|
| | Tons. | Tons. | Tons. |
| 1855 | 1,894,241 | 7,659,500 | 9,553,741 |
| 1856 | 2,673,745 | 7,809,564 | 10,483,309 |
| 1857 | 3,365,115 | 6,208,166 | 9,573,281 |
| 1858 | 2,884,065 | 5,156,894 | 8,040,959 |
| 1859 | 3,105,765 | 4,774,551 | 7,880,316 |
| 1860 | 2,858,142 | 5,166,063 | 8,024,205 |
| 1861 | 2,913,478 | 4,302,040 | 7,215,518 |
| 1862 | 3,397,531 | 4,164,709 | 7,562,240 |
| 1863 | 4,501,627 | 4,587,333 | 9,088,960 |
| 1864 | 5,107,145 | 4,957,725 | 10,064,890 |
| 1865 | 5,534,438 | 4,375,607 | 9,910,045 |
| 1866 | 5,365,167 | 4,299,845 | 9,665,012 |
| 1867 | 5,616,816 | 4,404,242 | 10,021,058 |
| 1868 | 5,822,175 | 4,347,056 | 10,169,231 |
| 1869 | 6,870,199 | 4,638,326 | 11,508,525 |
| 1870 | 7,859,477 | 6,511,178 | 14,370,655 |
| 1871 | 10,124,708 | 6,210,180 | 16,334,888 |
| 1872 | 9,632,375 | 5,951,982 | 15,584,357 |
| 1873 | 10,058,004 | 5,519,495 | 15,577,499 |
| 1874 | 9,390,214 | 5,454,722 | 14,844,936 |
| 1875 | 10,592,050 | 5,229,010 | 15,821,060 |
| 1876 | 11,182,160 | 5,659,423 | 16,841,583 |
| 1877 | 10,768,075 | 5,924,727 | 16,692,802 |
| 1878 | 10,320,593 | 5,405,777 | 15,726,370 |
| 1879 | 9,248,868 | 5,130,849 | 14,379,735 |
| 1880 | 12,627,881 | 5,398,528 | 18,026,409 |

TABLE II.

Giving the Quantities of Iron Ore raised in the United Kingdom, from Mines not in the Coal Measures, in each of the years 1860, 1870 and 1880 :—

IRON ORE PRODUCE.

| Counties, etc. | Quantities. 1860. | Quantities. 1870. | Quantities. 1880. |
|---|----------------------|----------------------|----------------------|
| | Tons. Cwts. | Tons. Cwts. | Tons. Cwts. |
| Cornwall | 23,953 4 | 11,214 4 | 15,865 3 |
| Devonshire | 3,836 0 | 10,193 17 | 12,652 15 |
| Somersetshire | 24,102 0 | 18,764 7 | 29,318 0 |
| Gloucestershire | 90,466 0 | 183,503 9 | 92,159 0 |
| Wiltshire | 76,201 0 | 101,423 0 | 67,500 0 |
| Hampshire | 6,119 0 | ... | ... |
| Oxfordshire | 5,833 0 | 38,803 17 | 8,360 0 |
| Northamptonshire | 95,664 0 | 761,248 0 | 1,550,103 10 |
| Lincolnshire | 16,892 0 | 248,329 17 | 1,154,584 1 |
| Staffordshire, North | ... | 62,882 0 | 48,378 2 |
| Lancashire | 520,829 0 | 871,938 0 | 1,266,503 14 |
| Cumberland | 468,782 0 | 1,221,303 4 | 1,491,440 18 |
| Leicestershire | ... | ... | 52,387 0 |
| Yorkshire, N. Riding | 1,471,319 6 | 4,072,888 1 | 6,486,654 18 |
| Northumberland and } Durham } | 12,500 0 | 100,332 0 | 41,357 18 |
| North Wales | 97 0 | 100 0 | 1,603 3 |
| South Wales and } Monmouthshire } | 39,817 0 | 88,721 2 | 65,566 10 |
| Ireland | 61 0 | 167,832 0 | 238,272 4 |
| Scotland | ... | ... | 5,166 0 |
| Isle of Man | 1,671 8 | ... | 9 0 |
| | | | |
| *Iron Ore (Argilla- ceous and Black Band) obtained from Collieries } | 2,858,142 18 | 7,859,476 18 | 12,627,881 16 |
| | 5,166,062 14 | 6,511,178 0 | 5,398,528 0 |
| | | | |
| Total iron ore raised in the United Kingdom } | 8,024,205 12 | 14,370,654 18 | 18,026,409 16 |

* The details of production of Argillaceous Carbonates and Black Bands in each of the same years are given in the following Table III.

TABLE III.

Giving the quantities of Argillaceous Carbonates and Black Band Ores obtained from the Coal Measures of the Coal Fields of the United Kingdom in each of the years 1860, 1870 and 1880 :—

IRON STONE PRODUCE.

| Coal Fields. | Quantities. 1860. | Quantities. 1870. | Quantities. 1880. |
|--------------------------------------|----------------------|----------------------|----------------------|
| | Tons. | Tons. | Tons. |
| <i>England—</i> | | | |
| Somersetshire . . | ... | 975 | 665 |
| Gloucestershire . . | ... | ... | 210 |
| Shropshire . . . | 165,500 | 337,627 | 226,721 |
| Warwickshire . . | 19,500 | 17,500 | 36,972 |
| Derbyshire . . . | 375,500 | 384,865 | 150,248 |
| Nottinghamshire . . | ... | ... | 2,264 |
| Staffordshire, North . | 738,229 | 847,252 | 1,350,315 |
| Staffordshire, South . | 785,700 | 450,000 | 362,773 |
| Yorkshire, W. Riding | 255,700 | 307,717 | 286,698 |
| Lancashire . . . | ... | ... | 1,520 |
| Durham and North- umberland . . } | ... | 125,000 | ... |
| <i>Wales—</i> | | | |
| North Wales . . . | 85,000 | 59,140 | 41,413 |
| South Wales . . . | 590,889 | 471,333 | 278,361 |
| <i>Scotland—</i> | | | |
| East Division . . } | 2,150,000 | 3,500,000 | 2,659,317 |
| West Division . . } | | | |
| <i>Ireland</i> | 45 | 9,768 | 1,051 |
| Total | 5,166,063 | 6,511,177 | 5,398,528 |

TABLE IV.

PURPLE ORE.

In addition to the ores of iron raised from the mines of the United Kingdom, and the valuable foreign ores imported, there is another source of supply in the residue known as "Purple Ore." It is obtained from the cupriferous iron pyrites which has been treated for sulphur in the manufacture of sulphuric acid. This is roasted with an addition of salt, and then lixiviated with water in order to dissolve the chloride of copper formed. The copper is removed as a soluble chloride, and then obtained as cement copper by running the solution into vats containing scrap iron. The residue of these operations is nearly pure peroxide of iron in the form of a heavy, purplish

red powder, having the following composition, according to Mr. John A. Phillips, F.R.S., managing director of the Widnes Metal Company.

RESULTS TABULATED.*

| | |
|--|--------|
| Peroxide of iron | 96·00 |
| Lead (as sulphate) | 0·75 |
| Copper | 0·20 |
| Sulphur | 0·36 |
| Phosphorus | nil |
| Lime | 0·40 |
| Soda | 0·10 |
| Cobalt, arsenic and chlorine | traces |
| Insoluble residue | 2·11 |
| | <hr/> |
| | 99·92 |
| | <hr/> |
| Metallic iron | 67·00 |

The results are computed in the dry state, but as ordinarily sold, the ore contains about 15 per cent. of water.

This oxide of iron is used in blast furnaces in form of blocks as well as in powder; viz.: at Palmer's Shipbuilding and Iron Company, Newcastle-on-Tyne; The Ditton Brook Iron Company, near Warrington; Bolckow, Vaughan and Co., Limited, Middlesborough; Messrs. Merry, and Cunningham and Co., Glasgow; Messrs. Giers, Mills and Co., Middlesborough, and the West Yorkshire Coal and Iron Company, Leeds. It is also used as fettling ore for puddling furnaces; being in a powder it does not require grinding as hematite does. When used in the blast furnace in those works where it is employed, it is added in the proportion of 25 per cent. to the amount of solid ore.

Mason's pyrites, as previously stated, gives on analysis 67 per cent. of metallic iron; other pyrites, the Tharsis, giving 62 per cent., and Buitron, 66 per cent. of metallic iron.

The annexed tabulated statement gives the quantities of "Purple Ore" available in each year since 1871:—

PURPLE ORE

Produced from the Metal Extraction Works in Great Britain.

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1871 | 200,000 | 1876 | 292,000 |
| 1872 | 252,239 | 1877 | 415,000 |
| 1873 | 275,000 | 1878 | 400,000 |
| 1874 | 255,000 | 1879 | 332,300 |
| 1875 | 280,000 | 1880 | 427,730 |

* Mason's Pyrites.

APPENDIX—No. 2.

PRODUCTION OF PIG IRON IN GREAT BRITAIN IN EACH IRON MAKING DISTRICT.

| | | | | | |
|-------|--|-----|-----|-------------------------|----------------|
| TABLE | I.—Furnaces in Blast and Production of Pig iron in 1740. | | | | |
| " | II.—Do. | do. | do. | do. | 1788. |
| " | III.—Summary of | | do. | do. | 1796. |
| " | IV.—Production of each Iron Works in | | | | 1796. |
| " | V.—Furnaces in Blast and Production of Pig Iron in 1806. | | | | |
| " | VI.—Do. | do. | do. | do. | 1823 and 1830. |
| " | VII.—Do. | do. | do. | do. | 1839. |
| " | VIII.—Do. | do. | do. | do. | 1840. |
| " | IX.—Do. | do. | do. | in 1840, 1843 and 1847. | |
| " | X.—Do. | do. | do. | do. | 1852. |
| " | XI.—Do. | do. | do. | do. | since 1854. |
| " | XII.—Pig Iron exported from the United Kingdom since 1829. | | | | |
| " | XIII.—Do. | do. | do. | in 1878, 1879 and 1880. | |

TABLE I.

In the following series of tables will be found the number of furnaces, with the production of pig iron, and occasionally notes of the quantities of coal used in manufacture; the earliest is for the year 1740. The flourishing and extensive works referred to by Dud Dudley no longer existed; the 300 blast furnaces mentioned by him were now reduced to 59, and their total annual produce to 17,350 tons, giving an average yield per furnace of 294 tons.

The details are as follows:—*

PIG IRON PRODUCTION IN THE YEAR 1740.

| Districts. | Number of Furnaces. | Pig Iron Made. |
|--------------------------------|------------------------|----------------|
| | | Tons. |
| Derbyshire | 2 | 550 |
| Gloucestershire | 4 | 800 |
| Hampshire | 3 | 1,350 |
| Kent | 1 | 200 |
| Nottinghamshire | 1 | 200 |
| Shropshire | 6 | 2,100 |
| Staffordshire, North | 3 | 1,700 |
| Staffordshire, South | 2 | 1,000 |
| Sussex | 10 | 1,400 |
| North Wales | 4 | 400 |
| South Wales | 13 | 4,850 |
| Warwickshire | 2 | 700 |
| Worcestershire | 2 | 700 |
| Yorkshire | 6 | 1,400 |
| Total | 59 | 17,350 |

* "History of the Iron Trade." By Harry Scrivener. 1854. P. 57.

TABLE II.

For the year 1788 the following information appears, many of the charcoal furnaces having died out since 1740. In some districts the wood was exhausted; in others, the ironmaster was prohibited from using it; and in others the use of charred coal (coke), by reducing the price of pig iron, compelled the charcoal iron maker to abandon or to alter his mode of manufacture. The production of charcoal iron made was 14,500 tons, and of coke pig iron 53,800 tons, in the furnaces of Great Britain; the average make of the charcoal furnaces being 545 tons; and of the coke furnaces, 909 tons per annum. The details are as follows, and the total production 68,300 tons:—

PIG IRON PRODUCTION IN THE YEAR 1788.

| Districts. | CHARCOAL PIG IRON. | | COKE PIG IRON. | |
|------------------------------|--------------------|--------|----------------|--------|
| | Furnaces. | Tons. | Furnaces. | Tons. |
| Brecknockshire | ... | ... | 2 | 1,600 |
| Caermarthenshire | 1 | 400 | ... | ... |
| Cheshire | ... | ... | 1 | 600 |
| Cumberland | 1 | 300 | 1 | 700 |
| Derbyshire | 1 | 300 | 7 | 4,200 |
| Glamorganshire | 3 | 1,800 | 6 | 6,600 |
| Gloucestershire | 4 | 2,600 | ... | ... |
| Lancashire | 3 | 2,100 | ... | ... |
| Merionethshire | 1 | 400 | ... | ... |
| Monmouthshire | 3 | 2,100 | ... | ... |
| Shropshire | 3 | 1,800 | 21 | 23,100 |
| Staffordshire, South | ... | ... | 3 | 2,400 |
| Staffordshire, North | ... | ... | 6 | 4,500 |
| Sussex | 2 | 300 | ... | ... |
| Westmoreland | 1 | 400 | ... | ... |
| Yorkshire | 1 | 600 | 6 | 4,500 |
| Scotland | 2 | 1,400 | 6 | 5,600 |
| Total | 26 | 14,500 | 59 | 53,800 |

Mr. Mushet, writing some years later, gives the quantity of charcoal necessary to produce a ton of pig iron as 2,422 lbs.; and reliable authorities estimate the quantity of coal used in the year 1788 in smelting the 53,800 tons of coke pig iron, to have been from 376,000 to 400,000 tons, giving an average of between 7 and 8 tons of coal to each ton of iron made.

TABLE III.

When in the year 1796 previously referred to, Mr. Pitt proposed to levy a tax on coal at the pit's mouth, a formidable opposition was offered to the measure, and an independent inquiry was instituted by our ironmasters, who strongly resisted the proposed impost. The House of Commons appointed a committee of inquiry into the project, the result being the abandonment of the measure. The annexed summary gives the number of furnaces and the make of the several iron making districts at that period:—

SUMMARY OF PIG IRON PRODUCTION IN THE YEAR 1796.

| Districts. | Furnaces. | Pig Iron. |
|-----------------------------|-----------|-------------|
| | Nos. | Tons. Cwts. |
| North Staffordshire | 2 | 1,958 10 |
| Cumberland | 2 | 565 0 |
| Derbyshire | 12 | 9,656 0 |
| Gloucestershire | 2 | 380 0 |
| Herefordshire | 4 | 1,749 0 |
| Lancashire | 3 | 2,249 0 |
| Yorkshire | 13 | 10,398 0 |
| Shropshire | 23 | 32,969 10 |
| Sussex | 1 | 173 0 |
| South Wales | 24 | 34,101 0 |
| Mid Wales | 1 | 150 0 |
| North Wales | 5 | 1,144 0 |
| West Wales | 1 | 290 0 |
| South Staffordshire | 14 | 13,210 10 |
| Scotland (coal) | 15 | 15,186 0 |
| „ (charcoal) | 2 | 900 0 |
| Total | 124 | 125,079 10 |

Detailed particulars of this important return, of which the above is a summary, giving the names of the furnaces, the counties in which situated, and the annual make of pig iron, appear in Table IV.

In this table is indicated the division and the names of all the furnaces in Great Britain in 1796, with the Excise return of the quantity of pig iron made, the quantities supposed and calculated upon by Mr. C., Mr. G., and Mr. W., and the returns of the quantities really made:—*

* Dr. H. G. Macnab. "Observations, &c., on the Coal and Iron Trades, 1796." P. 47. Published 1801.

TABLE IV.

PIG IRON PRODUCTION IN THE YEAR 1796.

| Name of Furnace. | What Division. | Excise Return. | Supposed Quantities. | Exact Return. |
|-------------------------------|----------------|-----------------------|----------------------|---------------|
| | | Tons. | Tons. | Tons. Cwts. |
| Apedale | Chester | 2,100 | 1,000 | 728 10 |
| Silverdale | " | 2,600 | 1,200 | 1,230 0 |
| Bearpot | Cumberland | 2,080 | 1,200 | 240 0 |
| Dudden | " | 1,664 | 400 | 325 0 |
| Newland | " | 700 | 700 | 700 0 |
| Backbarrow | " | 700 | 700 | 769 0 |
| Dale Abboy | Derby | 474 | 474 | 443 0 |
| Morley Park | " | 728 | 728 | 728 0 |
| Butterly | " | 936 | 936 | 936 0 |
| Flaxley | Gloucester | 360 | 360 | 360 0 |
| Forest of Dean | " | 20 | 20 | 20 0 |
| Abry Tinton | Hereford | 70 | 70 | 70 0 |
| Bishopwood | " | 500 | 500 | 947 0 |
| Cornbrook | " | 1,000 | 1,000 | 482 0 |
| Brigwood | " | 500 | 500 | 250 0 |
| Leighton | Lancaster | 780 | 780 | 780 0 |
| Bowling (2) | Leeds | 2,000 | 2,000 | 2,000 0 |
| Wibsey Moor (2) | " | 2,000 | 2,000 | 2,500 0 |
| Shelf | " | 1,000 | 1,000 | 1,140 0 |
| Birkenshaw | " | 780 | 780 | 846 0 |
| Renishaw (2) | Lincoln | 500 | 500 | 705 0 |
| Old Park (3) | Salop | 11,332 $\frac{1}{2}$ | 6,240 | 5,952 0 |
| Horsehay | " | 4,927 $\frac{1}{2}$ | 2,080 | 1,458 4 |
| Lightmoor (3) | " | 8,946 | 6,240 | 2,498 15 |
| Coalbrookdale (3) | " | 7,175 | 4,160 | 2,659 11 |
| Madeley Wood | " | 3,777 $\frac{1}{2}$ | 2,080 | 1,856 8 |
| Jackfield (2) | " | 7,086 | 4,160 | 1,820 0 |
| Benthal | " | 2,367 $\frac{1}{2}$ | 1,600 | 1,334 0 |
| Willey | " | 3,702 $\frac{1}{2}$ | 1,600 | 1,554 10 |
| Broseley | " | 1,775 | 1,400 | 1,076 10 |
| Ketley (3) | " | 7,590 | 6,240 | 5,068 19 |
| Snedhill (2) | " | 4,730 | 3,400 | 3,367 10 |
| Donnington Wood (2) | " | 4,720 | 4,160 | 3,323 0 |
| Chesterfield | Sheffield | 940 | 940 | 940 0 |
| Little Brampton (2) | " | 1,800 | 1,800 | 1,560 0 |
| Wingerworth | " | 1,274 | 1,274 | 1,274 0 |
| Staveley | " | 1,000 | 1,000 | 761 0 |
| Park | " | 1,092 | 1,092 | 853 0 |
| Chappel | " | 1,456 | 1,456 | 1,456 0 |
| Horncliffe (2) | " | 1,092 | 1,092 | 712 0 |
| Elsecar | " | 800 | 800 | 950 0 |
| Brelton | " | 250 | 250 | 250 0 |
| Holmes (3) | " | 6,000 | 6,000 | 2,000 0 |
| Carried forward | | 105,325 $\frac{1}{2}$ | 75,912 | 58,924 17 |

PRODUCTION OF FIG IRON.

833

FIG IRON PRODUCTION IN THE YEAR 1796—continued.

| Name of Furnaces. | What Division. | Excise Returns. | Supposed Quantities. | Exact Return. |
|----------------------------|----------------|-----------------|----------------------|---------------|
| | | Tons. | Tons. | Tons. Cwts. |
| Brought forward . | | 105,325½ | 75,912 | 58,924 17 |
| Aahburnham . | Sussex | 172½ | 173 | 173 0 |
| Clydach . | South Wales | 1,820 | 1,820 | 1,625 0 |
| Blaendare (3) . | " | 1,404 | 1,404 | 1,500 0 |
| Blaenavon . | " | 5,460 | 5,460 | 4,318 0 |
| Sirhowy . | " | 1,820 | 1,820 | 1,930 0 |
| Beaufort . | " | 1,560 | 1,560 | 1,660 0 |
| Penyca or } Ebbw Vale } | " | 1,560 | 1,560 | 397 0 |
| Hirwain . | " | 1,400 | 1,400 | 1,050 0 |
| Melincourt . | " | 648 | 648 | 503 0 |
| Ennisgygedyr . | " | 1,352 | 1,352 | 800 0 |
| Neath Abbey (2) . | " | 3,120 | 3,120 | 1,759 0 |
| Caerfilly . | " | 600 | 600 | 695 0 |
| Cfarthfa (3) . | " | 6,000 | 6,000 | 7,204 0 |
| Plymouth . | " | 2,000 | 2,000 | 2,200 0 |
| Penydarren (2) . | " | 4,000 | 4,000 | 4,100 0 |
| Dowlais (3) . | " | 4,100 | 5,400 | 2,800 0 |
| Llanally . | " | 1,664 | 1,664 | 1,660 0 |
| Dovey . | Mid Wales | 200 | 200 | 150 0 |
| Ruabon . | North Wales | 1,560 | 1,560 | 1,144 0 |
| Brymbo . | " | 884 | silent | ... |
| Brymbo Gate . | " | 728 | none | ... |
| Penyvron . | " | 1,498 | lead work | ... |
| Pentroben . | " | 1,560 | " | ... |
| Carmarthen . | West Wales | 1,056 | 1,056 | 290 0 |
| Level . | Staffordshire | 1,560 | 1,560 | 1,391 0 |
| Brierly . | " | 1,300 | 1,300 | 1,046 10 |
| Deepfield (2) . | " | 2,600 | 2,600 | 2,526 0 |
| Bilston (2) . | " | 2,340 | 2,340 | 1,429 0 |
| Bradley (3) . | " | 3,640 | 3,000 | 1,920 0 |
| Graveyard . | " | 1,260 | 1,336 | 213 0 |
| Dudley Port . | " | 1,040 | 1,040 | 869 0 |
| Tipton (2) . | " | 2,080 | 2,080 | 2,203 0 |
| Gospel Oak . | " | ... | ... | 1,613 0 |
| <i>Scotch Furnaces—</i> | | | | |
| Carron (4) . | | ... | 5,200 | 5,616 0 |
| Wilson's Town (2) . | | ... | 2,080 | 2,080 0 |
| Muirkirk (2) . | | ... | 3,120 | 2,878 0 |
| Eglinton (3) . | | ... | 3,640 | 2,216 0 |
| Dalrymple (2) } | | ... | 3,000 | 2,396 0 |
| Addison (2) } | | ... | | |
| Argyle, charcoal . | | ... | 1,600 | { 300 0 |
| Bunawe " . | | ... | | { 600 0 |
| Totals . | | 167,312½ | 152,605 | 125,079 7 |

TABLE V.

PRODUCTION OF PIG IRON IN THE YEAR 1806.

The number of furnaces built and in blast in Great Britain and the production of pig iron in districts are given as follows:—*

| Districts. | FURNACES. | | | Make of Pig Iron. |
|---------------------------|-----------|------|--------|-------------------|
| | In. | Out. | Total. | |
| | Nos. | Nos. | Nos. | Tons. |
| <i>England—</i> | | | | |
| Staffordshire | 32 | 10 | 42 | 50,002 |
| Cumberland | 4 | ... | 4 | 1,955 |
| Derbyshire | 11 | 6 | 17 | 9,074 |
| Shropshire | 30 | 12 | 42 | 54,966 |
| Lancashire | 1 | 2 | 3 | 780 |
| Leicestershire | ... | 1 | 1 | ... |
| Northumberland | 2 | ... | 2 | 2,500 |
| Yorkshire | 22 | 4 | 26 | 27,646 |
| Monmouthshire | 3 | ... | 3 | 2,240 |
| <i>Wales—</i> | | | | |
| North Wales | 3 | 1 | 4 | 2,981 |
| South Wales | 35 | 10 | 45 | 68,867 |
| <i>Scotland</i> | 18 | 9 | 27 | 22,840 |
| Total | 161 | 55 | 216 | 243,851 |

TABLE VI.

PRODUCTION OF PIG IRON IN THE YEARS 1823 AND 1830.

In the following comparative statement, made by Mr. Frederick Finch, M.P., who undertook the inquiry for the Government, we have the annexed returns. Mr. Finch took a considerable amount of care to obtain correct results, and was aided in the Scotch returns by Mr. Scudamore:—

| Districts. | FURNACES. | | PIG IRON MADE. | | Increase since 1823. |
|--|-----------|-------|----------------|---------|----------------------|
| | 1823. | 1830. | 1823. | 1830. | |
| | Nos. | Nos. | Tons. | Tons. | Tons. |
| Northumberland and } Durham | 2 | 4 | 2,379 | 5,327 | 2,948 |
| Yorkshire | 26 | 27 | 27,311 | 28,926 | 1,615 |
| Derbyshire | 15 | 18 | 14,038 | 17,999 | 3,961 |
| Shropshire | 38 | 48 | 57,923 | 73,418 | 15,495 |
| Staffordshire | 84 | 123 | 133,590 | 211,604 | 78,014 |
| South Wales | 72 | 113 | 182,325 | 277,643 | 95,318 |
| North Wales | 7 | 12 | 13,100 | 25,000 | 11,900 |
| Scotland | 22 | 27 | 24,500 | 37,500 | 13,000 |
| Total | 266 | 372 | 455,166 | 677,417 | 222,251 |

The above figures show the average make per furnace in 1823 to have been 1,730 tons, compared with 1,824 tons in the year 1830, and an increase in production between the two years of 222,251 tons, equivalent to 49 per cent.

* Parliamentary Return.

TABLE VII.

PRODUCTION OF PIG IRON IN THE YEAR 1839.

Mr. Mushet, in his papers on Iron and Steel, gives the following as the number of furnaces and the production of pig iron in each district in Great Britain in 1839, to which is added the average make per furnace :—

| Districts. | FURNACES. | | | Pig Iron Made. | Average per Furnace. |
|--|-----------|------|----------------|----------------|----------------------|
| | In. | Out. | Build- ing. | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| South Wales | 122 | 5 | 32 | 453,880 | 3,802 |
| Forest of Dean | 5 | 3 | 2 | 18,200 | 3,640 |
| Shropshire | 29 | 5 | ... | 80,940 | 2,791 |
| Staffordshire, North . . | 7 | 3 | 3 | 18,200 | 2,600 |
| Staffordshire, South . . | 120 | 106 | ... | 346,213 | 2,885 |
| North Wales | 13 | 7 | ... | 33,800 | 2,600 |
| Derbyshire | 14 | 2 | 2 | 34,372 | 2,455 |
| Yorkshire | 24 | 5 | ... | 52,416 | 2,175 |
| Durham and Northum- berland | 5 | ... | ... | 13,000 | 2,600 |
| Scotland | 54 | 6 | 18 | 196,560 | 3,621 |
| „ (charcoal) | 1 | ... | ... | 400 | 400 |
| Lancashire, „ | 2 | ... | ... | 800 | 400 |
| Total | 396 | 142 | 57 | 1,248,781 | 3,153 |

The make of pig iron in 1839 exceeded that of 1830 by 570,364 tons, equivalent to an increase in the ten years of 84 per cent.

TABLE VIII.

PRODUCTION OF PIG IRON IN THE YEAR 1840.

Previous to the discovery by Neilson of the application of the hot blast, about the year 1829, which was successfully carried out at the Clyde Iron-works, 8 tons of coal previously coked were required to make each ton of pig iron, but by heating the air to a temperature of 300° Fahr. before its introduction into the blast furnace, 5 tons 2 cwt 2 qrs. of coal, converted into coke, were sufficient, and the temperature of the blast being increased to 600°, it was found that raw uncoked coal could be used advantageously. A very important inquiry bearing on the consumption of fuel, instituted by Mr. William Jessop, of the Butterley Ironworks, Derbyshire, led to the fact that in the year 1840, of the 490 furnaces then existing in Great Britain, 402 were in blast, and produced 1,396,400 tons of pig iron with a consumption of 4,877,000 tons of coals. The details of Mr. Jessop's return are as follows :—

| Districts. | FURNACES. | | Pig Iron Made. | Coal Used. | Coal Used per Ton of Iron. | | |
|---------------------------|-----------|-----------|----------------|------------|----------------------------|-------|------|
| | Built. | In Blast. | | | | | |
| | Noa. | Noa. | Tons. | Tons. | Tons. | Cwts. | Qrs. |
| Forest of Dean . . . | 4 | 4 | 15,500 | 60,000 | 3 | 17 | 2 |
| South Wales . . . | 163 | 132 | 505,000 | 1,436,000 | 2 | 16 | 3 |
| North Wales . . . | 15 | 12 | 26,500 | 110,000 | 4 | 4 | 2 |
| Northumberland . . . | 6 | 5 | 11,000 | 38,500 | 3 | 9 | 0 |
| Yorkshire . . . | 32 | 25 | 56,000 | 306,500 | 5 | 9 | 0 |
| Derbyshire . . . | 18 | 13 | 31,000 | 129,000 | 4 | 3 | 0 |
| North Staffordshire . . . | 16 | 7 | 20,500 | 83,000 | 4 | 1 | 0 |
| South Staffordshire . . . | 135 | 116 | 407,150 | 1,582,000 | 3 | 17 | 3 |
| Shropshire . . . | 31 | 24 | 82,750 | 409,000 | 4 | 19 | 3 |
| Scotland . . . | 70 | 64 | 241,000 | 723,000 | 3 | 0 | 0 |
| Total . . . | 490 | 402 | 1,396,400 | 4,877,000 | 3 | 10 | 0 |

When Mr. Jessop made his inquiry it was ascertained that of the 402 furnaces in operation 162 were using hot blast, the remaining 240 cold blast. The high rate of consumption of coal in many of the districts, notably those of Yorkshire and Shropshire, being due to the use of the cold blast.

Comparing the above return with that of the previous year, an increase of production is shown of 147,619 tons, equal to nearly 12 per cent.; the average make of the furnaces being 3,473 tons, compared with 3,153 tons.

TABLE IX.

PRODUCTION OF PIG IRON IN THE YEARS 1843 AND 1847.

With the general depression of trade between the years 1840 and 1845 a great falling off appears, amounting in the year 1843 to 181,050 tons, compared with the production of 1840. It was about the year 1843 that the great extension of our railway system set in, causing a good demand for iron of all kinds, and better prices. To compare the extent of production at this most eventful period in the history of the trade of the country, the returns of the year 1840 are given for comparison with those of 1843 and 1847:—

| Districts. | 1840. Pig Iron. | 1843. Pig Iron. | 1847. Pig Iron. |
|-------------------------------|--------------------|--------------------|--------------------|
| | Tons. | Tons. | Tons. |
| Derbyshire | 31,000 | 25,750 | 95,160 |
| Forest of Dean | 15,500 | 8,000 | ... |
| North Staffordshire | 20,500 | 21,750 | 65,520 |
| Northumberland | 11,000 | 25,750 | 99,840 |
| Shropshire | 82,750 | 76,200 | 88,400 |
| South Staffordshire | 407,150 | 300,250 | 320,320 |
| North Wales | 26,500 | 19,750 | 16,120 |
| South Wales | 505,000 | 457,350 | 706,680 |
| Yorkshire | 56,000 | 42,000 | 67,600 |
| Scotland | 241,000 | 238,550 | 539,968 |
| Total | 1,396,400 | 1,215,350 | 1,999,608 |

Thus it will be seen that between 1843 and 1847 the iron industries of Great Britain bounded forward at a rapid pace, the increased production in four years amounting to 784,258 tons, equal to 65 per cent.

TABLE X.

PRODUCTION OF PIG IRON IN THE YEAR 1852.

Braithwaite Poole in his "Statistics of Commerce," gives the annexed statement of the furnaces in Great Britain in the year 1852, with the make of pig iron, which is supplemented by the average make per furnace in each district:—

| Districts. | FURNACES. | | | Pig Iron Made. | Average per Furnace. |
|---|-----------|------|--------|----------------|----------------------|
| | In. | Out. | Total. | | |
| | Nos. | Nos. | Nos. | Tons. | Tons. |
| Scotland | 113 | 31 | 144 | 775,000 | 6,860 |
| South Wales | 135 | 27 | 162 | 635,000 | 4,705 |
| " (anthracite) | 12 | 23 | 35 | 31,000 | 2,583 |
| South Staffordshire . . | 127 | 32 | 159 | 725,000 | 5,708 |
| North Staffordshire . . | 17 | 4 | 21 | 90,000 | 5,294 |
| North Wales | 6 | 7 | 13 | 30,000 | 5,000 |
| Shropshire | 27 | 13 | 40 | 120,000 | 4,444 |
| Durham | 7 | 6 | 13 | 35,000 | 5,000 |
| Northumberland . . . | 18 | 8 | 26 | 110,000 | 6,111 |
| Yorkshire and Derby- shire } | 35 | 7 | 42 | 150,000 | 4,285 |
| Total | 497 | 158 | 655 | 2,701,000 | 5,440 |

Comparing the above return with that of 1847, when of the 623 furnaces in Great Britain, 433 were in blast, producing 1,999,608 tons of pig iron, or an average of 4,618 tons per furnace; there appears an increase in production of 701,392 tons, equivalent to nearly 36 per cent., and an increase per furnace of 822 tons, the furnaces of smallest capacity being those employing anthracite in South Wales.

TABLE XI.

PRODUCTION OF PIG IRON BETWEEN THE YEARS 1854 AND 1880,

*Showing the Number of Furnaces Built and in Blast in Great Britain, the Production of Pig Iron, and the Average Make per Furnace in each Year.**

| Year. | FURNACES. | | Pig Iron Made. | Average per Furnace. |
|-------|-----------|-------------------|----------------|----------------------|
| | Built. | In Blast. | | |
| | Nos. | Nos. | Tons. | Tons. |
| 1854 | 724 | 555 | 3,069,838 | 5,530 |
| 1855 | 763 | 589 | 3,218,154 | 5,463 |
| 1856 | 785 | 622 | 3,586,377 | 5,766 |
| 1857 | 823 | 628 | 3,659,447 | 5,829 |
| 1858 | 833 | 617 | 3,456,064 | 5,600 |
| 1859 | 862 | 607 | 3,712,904 | 6,116 |
| 1860 | 872 | 582 | 3,826,752 | 5,575 |
| 1861 | 852 | 569 | 3,712,390 | 6,524 |
| 1862 | 876 | 561 | 3,943,469 | 7,029 |
| 1863 | 908 | 597 | 4,510,040 | 7,554 |
| 1864 | 883 | 612 | 4,767,951 | 7,790 |
| 1865 | 919 | 656 | 4,825,254 | 7,355 |
| 1866 | 839 | 618 | 4,523,897 | 7,320 |
| 1867 | 818 | 551 | 4,761,023 | 8,640 |
| 1868 | 912 | 560 | 4,970,206 | 8,873 |
| 1869 | 901 | 600 | 5,445,757 | 9,076 |
| 1870 | 916 | 664 | 5,963,515 | 9,000 |
| 1871 | 897 | 673 | 6,627,179 | 9,847 |
| 1872 | 876 | 702 | 6,741,929 | 8,604 |
| 1873 | 892 | 683 | 6,566,451 | 9,613 |
| 1874 | 915 | 649 | 5,991,408 | 9,232 |
| 1875 | 899 | 629 | 6,365,462 | 10,120 |
| 1876 | 927 | 585 | 6,555,997 | 11,106 |
| 1877 | 940 | 541 | 6,608,664 | 12,215 |
| 1878 | 948 | 498 | 6,381,051 | 12,813 |
| 1879 | 929 | 496 | 5,995,337 | 12,090 |
| 1880 | 926 | 567 $\frac{1}{2}$ | 7,749,233 | 13,679 |

* "Mineral Statistics of the United Kingdom."

TABLE XII.

PIG IRON EXPORTED FROM THE UNITED KINGDOM IN EACH YEAR SINCE 1829:—

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1829 | 8,931 | 1855 | 291,776 |
| 1830 | 12,036 | 1856 | 357,326 |
| 1831 | 12,444 | 1857 | 422,086 |
| 1832 | 17,566 | 1858 | 360,425 |
| 1833 | 22,988 | 1859 | 316,376 |
| 1834 | 21,788 | 1860 | 342,567 |
| 1835 | 33,073 | 1861 | 388,004 |
| 1836 | 33,880 | 1862 | 444,708 |
| 1837 | 44,387 | 1863 | 466,423 |
| 1838 | 48,554 | 1864 | 465,985 |
| 1839 | 43,460 | 1865 | 547,641 |
| 1840 | 49,801 | 1866 | 500,500 |
| 1841 | 85,866 | 1867 | 565,612 |
| 1842 | 93,851 | 1868 | 552,999 |
| 1843 | 154,770 | 1869 | 710,856 |
| 1844 | 99,960 | 1870 | 753,339 |
| 1845 | 77,362 | 1871 | 1,061,004 |
| 1846 | 159,163 | 1872 | 1,331,143 |
| 1847 | 176,086 | 1873 | 1,142,065 |
| 1848 | 175,650 | 1874 | 774,280 |
| 1849 | 161,775 | 1875 | 947,227 |
| 1850 | 141,973 | 1876 | 910,005 |
| 1851 | 201,264 | 1877 | 881,442 |
| 1852 | 240,491 | 1878 | 923,080 |
| 1853 | 333,585 | 1879 | 1,223,436 |
| 1854 | 293,432 | 1880 | 1,631,629 |

TABLE XIII.

PIG IRON EXPORTED FROM THE UNITED KINGDOM.

Showing Countries to which exported and Value of Exports for the Three Years ending 1880:—

| Countries to which Exported. | QUANTITIES. | | | VALUE. | | |
|------------------------------|-------------|-----------|-----------|-----------|-----------|-----------|
| | 1878. | 1879. | 1880. | 1878. | 1879. | 1880. |
| | Tons. | Tons. | Tons. | £ | £ | £ |
| Russia . . . | 85,509 | 146,830 | 152,966 | 253,036 | 412,830 | 503,317 |
| Germany . . . | 228,434 | 233,900 | 247,874 | 591,360 | 517,328 | 635,771 |
| Holland . . . | 240,969 | 213,386 | 190,026 | 674,892 | 547,170 | 600,926 |
| Belgium . . . | 90,318 | 83,750 | 116,628 | 221,902 | 194,230 | 342,417 |
| France . . . | 96,363 | 85,520 | 99,036 | 223,175 | 184,690 | 251,961 |
| United States . | 32,663 | 277,939 | 612,013 | 133,008 | 873,320 | 2,278,916 |
| British North America . } | 23,423 | 29,820 | 54,748 | 69,016 | 79,360 | 177,421 |
| Other countries | 125,401 | 152,291 | 158,338 | 303,803 | 341,461 | 416,546 |
| Totals . | 923,080 | 1,223,436 | 1,631,629 | 2,470,182 | 3,150,389 | 5,207,294 |

APPENDIX.—No. 3.

MALLEABLE IRON WORKS (MILLS AND FORGES) AND STEEL WORKS.

| | |
|--------------|--|
| TABLE | I.—Summary of Production of Bar Iron in each county in England and Wales in 1750. |
| " | II.—List of Works and their Production of Bar Iron in the year 1750. |
| " | III.—Number of Works, Puddling Furnaces, and Rolling Mills in Great Britain in each year since 1861. |
| " | IV.—List of Bessemer Steel Works in Great Britain, giving the Number and Capacity of Converters in the year 1880. |
| " | V.—Production of Bessemer Steel in Great Britain since the year 1871. |
| " | VI.—Production of Bessemer Steel in each District of Great Britain in the years 1879 and 1880. |
| " | VII.—Siemens' Steel Works, List of Firms manufacturing Steel by the Open Hearth Steel Melting Process. |
| " | VIII.—Production of Open Hearth Steel in Great Britain since 1873. |
| " | IX.—Production of Open Hearth Steel in each District in 1879 and 1880. |
| " | X.—List of Firms employing the Siemens' Regenerative Gas Furnaces for Melting Steel in Crucibles. |
| " | XI.—Production of Crucible Steel in Great Britain since the year 1873. |

TABLE I.

MILLS AND FORGES.

*Quantities of Bar Iron made in each county in England and Wales in the year 1750.**

| Counties. | Quantities. | Counties. | Quantities. |
|----------------------|-------------|---------------------|-------------|
| | Tons. | | Tons. |
| Breconshire . . . | 350 | Brought forward . . | 7,180 |
| Caermarthenshire . . | 480 | Monmouthshire . . | 2,000 |
| Cardiganshire . . . | 120 | Montgomeryshire . . | 200 |
| Cheshire | 640 | Nottinghamshire . . | 370 |
| Denbighshire . . . | 280 | Northumberland . . | 120 |
| Derbyshire | 640 | Pembrokeshire . . . | 240 |
| Durham | 250 | Shropshire | 2,260 |
| Flintshire | 200 | Surrey and Kent . . | ...† |
| Gloucestershire . . | 1,120 | Sussex | ...† |
| Glamorganshire . . | 1,100 | Staffordshire . . . | 1,990 |
| Herefordshire . . . | 1,000 | Warwickshire . . . | 300 |
| Hampshire | 250 | Worcestershire . . | 1,580 |
| Lancashire | 750 | Yorkshire | 2,560 |
| Carried forward . . | 7,180 | Total | 18,800 |

* For number of Forges in each county and production of bar iron see Table II.

† Quantities not ascertained.

TABLE II.

"A LIST of the FORGES in ENGLAND and WALES in 1750; with an account of the quantity of BAR-IRON they make annually according to the best information that could be got on a strict inquiry, blanks being left for the quantity made yearly at different places, whereof we could not have a certain account. The FORGES in SCOTLAND are not included."

The original document of which this is a copy, is in the possession of Samuel Timmins, Esq., of Elvethan Lodge, Birmingham, who courteously placed it at the service of the author for publication.

| BRECONSHIRE. | | Brought Forward . . . 4,080 | |
|-----------------------------------|-----------|------------------------------|-----|
| Tanner's Forge | Tons. 150 | GLAMORGANSHIRE. | |
| Llanelly | 200 | Forrest | 200 |
| CAERMARTHENSHIRE. | | Aberavan | 350 |
| Kidwelly | 100 | Velin Griffy's | 300 |
| Whitland | 100 | New Forge | 250 |
| Cymdwyfran | 120 | HEREFORDSHIRE. | |
| Cambrayne | 60 | New Weare | 350 |
| Lannovaine | 100 | Bringwoode | 450 |
| CARDIGANSHIRE. | | Landiloe | 200 |
| Lanfrede | 120 | HAMPSHIRE. | |
| CHESHIRE. | | Sowley | 50 |
| Cranage | 200 | Tichfield | 200 |
| Warmingham | 300 | LANCASHIRE. | |
| Lea | 140 | Cunsey | 120 |
| DENBIGHSHIRE. | | Backbarrow | 260 |
| Pontablue | 200 | Sparke Bridge | 120 |
| Wrexham | 80 | Coniston | 80 |
| DERBYSHIRE. | | Caton | 50 |
| Barton Fields | 120 | Burgh | 120 |
| New Mills | 250 | MONMOUTHSHIRE. | |
| Plesley | 150 | Malion and Tredegar, } | 600 |
| Staveley | 120 | Three Forges } | |
| DURHAM. | | Pont Pool | 700 |
| Winlaton } | 250 | Tuiton, Two Forges | 300 |
| Swallowwell } | | Monmouth | 400 |
| Teams | | MONTGOMERYSHIRE. | |
| FLINTSHIRE. | | Mattravil | 200 |
| Badvary | 200 | Dolobran | ... |
| GLOUCESTERSHIRE. | | NOTTINGHAMSHIRE. | |
| Lidney | 350 | Bulwell | 150 |
| Lidbrooke, Three Forges | 350 | Carburton | 220 |
| Upleadon | 120 | Clipton | ... |
| Tortworth | 150 | Cuckney | ... |
| Flaxley | 150 | Carried Forward . . . 9,750 | |
| Carried Forward . . . 4,080 | | | |

A LIST of the FORGES in ENGLAND and WALES in 1750—continued.

| | Tons. | | Tons. |
|-----------------------------------|--------|---------------------------|--------|
| Brought Forward | 9,750 | Brought Forward | 12,370 |
| NORTHUMBERLAND. | | STAFFORDSHIRE. | |
| Darwincoat | 120 | Consall | 300 |
| PEMBROKESHIRE. | | Hints | 250 |
| Blackpoole | 240 | Cannock | 180 |
| Coiducore is rebuilding | ... | Bromwiche | 300 |
| SHROPSHIRE. | | Little Aston | 100 |
| Cloebury | 250 | Corngreve | 120 |
| Longnor | 140 | Coven | 100 |
| Upton | 260 | Heath | 200 |
| Colebrookdale | 150 | Whittington | 300 |
| Wittheford | 250 | Swiner | 140 |
| Sutton | 260 | WARWICKSHIRE. | |
| Tern | 150 | Bromford | 300 |
| Kaynton | 250 | Clifford | ... |
| Norton | 150 | WORCESTERSHIRE. | |
| Winnington | 100 | Shellery | 350 |
| Prescot | 100 | Wildon | 450 |
| Lizard | 200 | Jennypole | 450 |
| SURREY AND KENT. | | Lower Milton | 400 |
| Touchley | ... | Woolverley | 300 |
| Barden | ... | Cookley | 300 |
| Mr. Johnston's | ... | Cradley and Lye | 160 |
| Mr. Gale's | ... | Powick | 150 |
| Mr. Dibble's | ... | YORKSHIRE. | |
| Shingley | ... | Attercliffe | 260 |
| Pophole | ... | Colnbridge | 150 |
| SUSSEX. | | Kirkstall | 160 |
| Bivelham | ... | Waddealey | 200 |
| Hawkesden | ... | Kilnhurst | 220 |
| Brightlin | ... | Wortley | 350 |
| Burwash | ... | Roach Abbey | 60 |
| Westfield | ... | Mousehole | 60 |
| Marshfield | ... | Seamore | 120 |
| Woodcock | ... | Total | |
| Carried Forward | 12,370 | 18,800 | |

TABLE III.

MALLEABLE IRON WORKS.

Showing the Number of these Works, the Number of Puddling Furnaces and Rolling Mills in Great Britain in each year since 1861.

| Year. | Number of Works. | Number of Puddling Furnaces. | Number of Rolling Mills. |
|-------|------------------|------------------------------|--------------------------|
| 1861 | 213 | 4,147 | 439 |
| 1862 | 217 | 4,832 | 647 |
| 1863 | 223 | 5,013 | 654 |
| 1864 | 248 | 6,338 | 705 |
| 1865 | 252 | 6,407 | 730 |
| 1866 | 256 | 6,239 | 826 |
| 1867 | 254 | 6,009 | 831 |
| 1868 | 247 | 5,903 | 831 |
| 1869 | 245 | 6,243 | 859 |
| 1870 | 255 | 6,699 | 851 |
| 1871 | 267 | 6,841 | 866 |
| 1872 | 276 | 7,311 | 1,015 |
| 1873 | 287 | 7,264 | 939 |
| 1874 | 298 | 6,803 | 866 |
| 1875 | 314 | 7,575 | 909 |
| 1876 | 312 | 7,159 | 942 |
| 1877 | 300 | 6,796 | 935 |
| 1878 | 232 | 5,125 | 830 |
| 1879 | 314 | 5,149 | 846 |
| 1880 | 314 | 5,134 | 855 |

TABLE IV.

BESSEMER STEEL WORKS.

LIST OF WORKS in Great Britain in the Year 1880, giving the Number of Convertors and their Capacity.

| No. | Name and Situation of Works. | Number of Convertors. | Capacity of Convertors. |
|-----|--|-----------------------|-------------------------|
| | | | Tons. Cwts. |
| 1 | Bessemer, Henry and Co., Sheffield | 2 | 3 0 |
| 2 | Bolckow, Vaughan and Co., Limited | 4 | 8 0 |
| | | 2 | 15 0 |
| 3 | Brown, John and Co., Limited, Sheffield | 4 | 7 10 |
| | | 2 | 10 0 |
| 4 | { Brown, Bayley, and Dixon, Limited, Sheffield Steel and Iron Works | 2 | 4 0 |
| | | 4 | 8 0 |
| 5 | { Cammel, Charles and Co., Limited, Cyclops Works, Sheffield | 4 | 4 0 |
| 6 | { Cammel, Charles & Co., Limited, Yorkshire Works, Sheffield | 2 | 5 0 |
| | | 2 | 7 0 |
| 7 | Weardale Iron Co., Tudhoe, Ferryhill | 2 | 2 10 |

TABLE IV.—*continued.*

| No. | Name and Situation of Works. | Number of Convertors. | Capacity of Convertors. |
|-----|---|-----------------------|-------------------------|
| | | | Tons. Cwts. |
| 8 | Glasgow, The, Bessemer Steel Co., Limited, Atlas Works, Glasgow | 2 | 3 0 |
| 9 | Fox, Samuel and Co., Stockbridge Works, Sheffield | 2 | 5 0 |
| 10 | Patent Shaft and Axletree Co., Limited, Monway Works, Wednesbury | 4 | 3 0 |
| 11 | Bolton Iron and Steel Co., Limited, Bolton, Lancashire | 4 | 5 0 |
| 12 | London and North Western Railway Co., Crewe Works, Cheshire | 2 | 3 0 |
| 13 | Manchester, Sheffield, and Lincolnshire Railway Co., Gorton Works, Manchester | 4 | 3 0 |
| 14 | Mersey Iron and Steel Works, Toxteth Park, Liverpool | 8 | 5 0 |
| 15 | Manchester Steel and Railway Plant Co., Gibraltar Works, Newton Heath, Manchester | 4 | 3 0 |
| 16 | Barrow Hematite Steel Co., Barrow Works, North Lancashire | 8 | 7 0 |
| 17 | Dowlais Iron Co., Dowlais Works, Glamorganshire | 2 | 7 10 |
| | | 2 | 6 0 |
| | | 2 | 5 0 |
| 18 | West Cumberland Iron and Steel Co., Workington | 2 | 8 0 |
| | | 2 | 6 0 |
| | | 2 | 8 0 |
| 19 | Steel, Tozer, & Hampton, Limited, Phoenix Works, The Ickles, near Sheffield | 2 | 4 0 |
| | | 2 | 2 0 |
| 20 | Carnforth Hematite Iron Co., Limited, Carnforth, Lancashire | 2 | 6 0 |
| 21 | Muller, Charles Emile, Erimus Steel Works, Middlesborough | 2 | 6 0 |
| 22 | Darlington Iron Co., Darlington | 2 | ... |
| 23 | Moss Bay Hematite Iron and Steel Co., Workington, Cumberland | 3 | 8 0 |
| 24 | Rhymney Iron Co., Monmouthshire | 3 | 7 0 |
| 25 | Blaenavon Iron and Steel Co., Blaenavon, Monmouthshire | 2 | 8 0 |
| 26 | The Standard Iron and Steel Co. | 2 | ... |
| 27 | Ebbw Vale Co., Ebbw Vale, Monmouthshire | 4 | 8 0 |
| | | 2 | 10 0 |

TABLE V.

PRODUCTION OF BESSEMER STEEL in Great Britain in each year since 1871.

| Year. | Bessemer Steel. | Year. | Bessemer Steel. |
|-------|-----------------|-------|-----------------|
| | Tons. | | Tons. |
| 1871 | 329,000 | 1876 | 700,000 |
| 1872 | 410,000 | 1877 | 750,000 |
| 1873 | 496,000 | 1878 | 807,527 |
| 1874 | 540,000 | 1879 | 834,511 |
| 1875 | 620,000 | 1880 | 1,044,382 |

TABLE VI.

PRODUCTION OF BESSEMER STEEL in each district in Great Britain in the years 1879 and 1880.*

| District. | 1879. Bessemer Steel. | 1880. Bessemer Steel. |
|-----------------------|--------------------------|--------------------------|
| | Tons. | Tons. |
| South Wales | 252,573 | 308,233 |
| Sheffield | 210,346 | 273,365 |
| Lancashire | 152,130 | 167,870 |
| Cumberland | 127,163 | 140,869 |
| North East Coast . . | 85,299 | 144,000 |
| Staffordshire | 7,200 | 10,045 |
| Total | 834,711 | 1,044,382 |

TABLE VII.

SIEMENS' STEEL WORKS.

LIST OF FIRMS who are manufacturers of Steel by the Open-Hearth Steel Melting Process, with the number of Furnaces erected by each.

| NAME AND SITUATION OF WORKS. | NO. OF FURNACES. |
|--|---------------------|
| The Landore Siemens Steel Co., Limited, Landore | 24 |
| Messrs. Vickers, Sons, and Co., Limited, Sheffield . . . | 10 |
| The Steel Co. of Scotland, Limited, Glasgow | 20 |
| Sir Joseph Whitworth and Co., Limited, Manchester . . . | 5 |
| The Panteg Steel Works and Engineering Co. | 13 |
| The London and North Western Railway Co., Crewe . . . | 5 |
| The Bolton Iron and Steel Co., Limited, Bolton | 3 |
| Messrs. Charles Cammell and Co., Sheffield | 6 |
| Messrs. John Spencer and Sons, Newcastle | 2 |
| The Dowlais Iron Co., Dowlais, Glamorganshire | 6 |
| The Bowling Iron Co., Limited, Bradford | 2 |
| The Railway Steel and Plant Co., Limited, Manchester . . | 2 |
| The Butterley Co., Alfreton, Derbyshire | 3 |
| Sir John Brown and Co., Limited, Sheffield | 1 |
| The Albion Steel and Wire Co., Limited, Sheffield . . . | 2 |
| Messrs. Wright Buller and Co., Elba Steel Works, near } Swansea | 4 |
| Messrs. White and Challingsworth, Pontymister, } Newport, Monmouthshire | 1 |
| Messrs. E. Morewood and Co., Llanelly, Glamorganshire . | 2 |
| Messrs. W. and T. Beardmore, Glasgow | 5 |
| Messrs. John Williams and Co., Wiahaw | 3 |
| Mr. James Butler, Middlesborough-on-Tees | 1 |

* "British Iron Trade Association," Report, 1880. p. 29.

TABLE VII.—*continued.*

| NAME AND SITUATION OF WORKS. | NO. OF FURNACES. |
|--|---------------------|
| The Barrow Hematite Steel Co., Limited, Barrow, } Lancashire } | 3 |
| The H. P. Horse Nail Co., Limited, London | 1 |
| The Mossend Iron Co., Holytown, N.B. | 4 |
| Mr. David Colville, Motherwell, N.B. | 4 |
| The West Cumberland Iron and Steel Co., Limited, } Workington } | 2 |
| The Consett Iron Co., Limited, Blackhill | 2 |
| The Shotts Iron Co., Carlisle, N.B. | 1 |

TABLE VIII.

PRODUCTION OF OPEN-HEARTH STEEL in *Great Britain in the year 1880 and seven previous years.**

| Year. | Quantities. | Year. | Quantities. |
|-------|-------------|-------|-------------|
| | Tons. | | Tons. |
| 1873 | 77,500 | 1877 | 137,000 |
| 1874 | 90,500 | 1878 | 175,000 |
| 1875 | 88,000 | 1879 | 175,000 |
| 1876 | 123,000 | 1880 | 251,000 |

The details of production, with the number of Open-Hearth Furnaces in each district in the years 1879 and 1880 appear in the following return :—

TABLE IX.

PRODUCTION OF OPEN-HEARTH STEEL in *each district in Great Britain in the years 1879 and 1880 :—**

| Districts. | Open Hearth Furnaces. | | Open Hearth Steel. | |
|-------------------------|-----------------------|-------|--------------------|---------|
| | 1879. | 1880. | 1879. | 1880. |
| | Nos. | Nos. | Tons. | Tons. |
| South Wales | 48 | 49 | 85,000 | 116,000 |
| Scotland | 16 | 36 | 50,000 | 84,500 |
| Sheffield | 15 | 19 | 21,000 | 23,500 |
| Lancashire and Cheshire | 12 | 14 | 15,000 | 19,500 |
| North East Coast . . . | 5 | 5 | 1,000 | 3,200 |
| Other Districts . . . | 6 | 3 | 3,000 | 4,300 |
| Total | 102 | 126 | 175,000 | 251,000 |

* "British Iron Trade Association," Report, 1880, pp. 34, 35.

TABLE X.

LIST OF FIRMS *who employ the "SIEMENS REGENERATIVE GAS FURNACES"*
for melting Steel in Crucibles.

YORKSHIRE.

Messrs. Vickers, Sons, and Co., Limited, Sheffield.
Messrs. Sanderson Brothers and Co., Limited, Sheffield.
Mr. Robert Marsden, Sheffield.
The Monkbridge Iron Co., Leeds.
The Bowling Iron Co., Limited, Bradford.

LANCASHIRE.

The Bolton Iron and Steel Co., Limited, Bolton.
The Mersey Steel and Iron Co., Limited, Liverpool.
The Steel Casting Co., Limited, Barrow-in-Furness.

CUMBERLAND.

The West Cumberland Iron and Steel Co., Limited, Workington.

STAFFORDSHIRE.

The Patent Shaft and Axle Co., Old Park, Wednesbury.

SHROPSHIRE.

Messrs. Nettlefolds, Limited, Castle Iron Works, Wellington.

DURHAM.

Messrs. John Spencer and Sons, Newcastle-on-Tyne.

MONMOUTHSHIRE.

Ebbw Vale Co., Ebbw Vale, Monmouthshire.

REGENERATIVE GAS HEATING FURNACES.

The Low Moor Works, Bradford.
Carnforth Hematite Iron Co., Carnforth.
Messrs. Samuel Fox and Co., Limited, Sheffield.
Messrs. R. Johnson and Nephew, Bradford, Manchester.

TABLE XI.

PRODUCTION OF CRUCIBLE STEEL *since the year 1873, in the Works in*
Great Britain by the Siemens Regenerative Gas Furnaces.

| Year. | Crucible Steel. | Year. | Crucible Steel. |
|-------|-----------------|-------|-----------------|
| | Tons. | | Tons. |
| 1873 | 5,900 | 1877 | 3,900 |
| 1874 | 3,300 | 1878 | 2,980 |
| 1875 | 4,000 | 1879 | 2,900 |
| 1876 | 4,150 | 1880 | 3,050 |

Sheffield still continues to be the chief centre of this industry; and it further appears that during the year 1880 nearly 1,500 tons of Steel were made in this locality by a process patented by Mr. W. R. Hadfield and described as a combination of the Bessemer and Siemens processes.*

* "British Iron Trade Association," Report, 1880, p. 37.

APPENDIX.—No. 4.

TIN PLATE MANUFACTURE.

| | |
|--------------|--|
| TABLE | I.—Production of Tin Terne and Black Plates in Great Britain, and Number of Works since 1871. |
| „ | II.—Summary of Tin Plate Works in Great Britain in the year 1880. |
| „ | III.—List of Tin Plate Works in Glamorganshire |
| „ | IV.—Do. do. in Caermarthenshire |
| „ | V.—Do. do. in Monmouthshire |
| „ | VI.—Do. do. in Gloucestershire |
| „ | VII.—Do. do. in Staffordshire and Worcestershire, Scotland, Cumberland, and Flintshire in 1880. |
| „ | VIII.—Exports of Tin Plates (Number of Boxes), since the year 1873. |
| „ | IX.—Do. do. and Principal Countries to which exported in each year since 1873. |
| „ | X.—Tin Plates exported and declared value in the years, 1870, 1875 and 1880. |

The earliest establishment engaged in this industry appears to have been founded in this country about the year 1720 at Pontypool in Monmouthshire. The art of tinning was early practised in the kingdom of Bohemia in the beginning of the 17th century, it is said about the year 1620, and some years later the art was introduced into the kingdom of Saxony. The art, as previously stated, was introduced into this country about the year 1720; it was not, however, until the year 1728 that any considerable advance was made, when Mr. John Payne invented a process for rolling iron; this appears to have been further supplemented by the grooved mills, invented about the year 1783, by Mr. Henry Cort. Many years, however, passed away before Cort's invention was fully appreciated. Mr. Reynolds, of the Ketley Iron Works, in Shropshire, erected the first of Cort's Rolls, and about the year 1790 Mr. Richard Crawshay erected rolling mills at Cyfarthfa, in Glamorganshire.*

The selection of iron for the making of the various descriptions of tin plate is of the utmost importance, the great tests of quality being ductility, strength, and a peculiar crystalline structure and grain, well known to the tin-plate manufacturer.

The greatest care is taken to reject any plate at all faulty, after it has passed through the various processes necessary in its preparation for tinning. This faulty condition is observed in the passage of the plate through the chilled rolls after being freed from rust, or scale of oxide iron, formed in the previous operations through which the tin plates pass in heating and reheating in the furnace, and cleansing in the acid bath.

In the process of tinning, Dr. Percy† says: "About 8 or 8½ lbs. of tin are used on an average per box of tin plates," and that "the quantity of

* The process of manufacture, tin plates, charcoal plates, &c., will be found fully described in Dr. Percy's Metallurgy, "Iron and Steel," p. 725.

† *Ibid.* p. 729.

mixed metal for terne plates will vary from 10 lbs. to 14 lbs., according to the proportions of lead employed; this last-named variety of tin plates, called "terne plates," are coated with an alloy of tin and lead, the surface being dull compared with that of tin plates. Terne plates are exported in considerable quantities to Canada where they are in great request for roofing. The standard of quotation is always taken at 1C (Common No. 1); this is a box containing 225 plates, $13\frac{1}{2}$ inches by 10 inches, which should weigh 1 cwt. or 112 lbs.

TABLE I.

PRODUCTION OF TIN, TERNE AND BLACK PLATES IN GREAT BRITAIN.

The year 1870 furnishes the earliest information on the subject: 57 works were then in operation in Great Britain, more or less actively employed; of these 33 furnished returns amounting to 199,782 boxes weighing 81,477 tons, the total production the same year amounting to 3,459,782 boxes. In subsequent years the number of works were as follows, the actual returns being distinguished from those estimated, these latter quantities being arrived at by gentlemen connected and intimately acquainted with the tin plate manufacture:—

| Year. | No. of Works. | BOXES RETURNED. | | Boxes Estimated. | Total Number of Boxes. |
|-------|---------------|-----------------|---------|------------------|------------------------|
| | | Number. | Weight. | | |
| | | Nos. | Tons. | Nos. | Nos. |
| 1871 | 57 | 1,444,087 | 83,917 | 949,204 | 2,393,291 |
| 1872 | 61 | 1,534,181 | 78,088 | 1,443,670 | 2,977,851 |
| 1873 | 69 | 1,974,989 | 116,943 | 710,056 | 2,685,045 |
| 1874 | 69 | 1,204,576 | 62,268 | 1,325,000 | 2,529,576 |
| 1875 | 68 | 1,601,516 | 82,490 | 1,350,600 | 2,952,116 |
| 1876 | 68 | 1,646,276 | 85,472 | 1,170,117 | 2,815,393 |
| 1877 | 75 | 1,788,549 | 86,738 | 2,261,201 | 4,049,750 |
| 1878 | 75 | 2,257,791 | 109,183 | 1,800,209 | 4,058,000 |
| 1879 | 78 | 2,631,166 | 117,970 | 1,619,179 | 4,250,345 |
| 1880 | 97 | 3,390,647 | 158,925 | 2,609,353 | 6,000,000 |

In the year 1879, the 78 works engaged in the various forms of tin plate possessed 264 mills; of these 222 were in operation, producing 4,250,345 boxes, the total weight being 190,576 tons, the average weight of each box being nearly 1 cwt.; while it was in the same year estimated by the highest authority in the trade, that, had the works been in full activity during the year, they were capable of producing 6,854,740 boxes.

TABLE II.

SUMMARY OF TIN PLATE WORKS IN GREAT BRITAIN IN THE YEAR 1880:—*

| Counties. | No. of Works. | Mills Built. |
|--|---------------|--------------|
| Glamorganshire | 45 | 188 |
| Caermarthenshire | 14 | 65 |
| Monmouthshire | 17 | 63 |
| Gloucestershire | 6 | 18 |
| Staffordshire and Worcestershire | 11 | 31 |
| Scotland | 2 | 5 |
| Cumberland | 1 | 5 |
| Flintshire | 1 | 2 |
| Total | 97 | 377 |

The details of returns received from tin plate works for the year 1880 have been as follows:—

| | Boxes. |
|---|------------------|
| Number of boxes of tin and terne plates | 2,478,742 |
| „ of boxes of black plates | 911,905 |
| Total number of boxes | <u>3,390,647</u> |

Actual weight of the whole returned, 158,925 tons.

The tin plate works which have not made returns are estimated as follows:—

| | Boxes. |
|---|------------------|
| The <i>estimated</i> number of boxes of tin, terne, and black plates | 2,609,353 |
| Actual number of boxes of tin, terne, and black plates returned as above | 3,390,647 |
| Total number of tin, terne, and black plates, made in the United Kingdom in the year 1880 | <u>6,000,000</u> |

The total estimated weight of the whole, 237,084 tons.

* Mineral statistics of the United Kingdom.

TABLE III.

GLAMORGANSHIRE.

The annexed Table presents a COMPLETE LIST of the TIN PLATE WORKS of GREAT BRITAIN at the present time, 1880:—

| Name of Works. | Name of Firm. | Total Mills. |
|-----------------------------------|-------------------------------------|--------------|
| Aberdulais (Neath) . . . | Joshua Williams & Co., Limited | 5 |
| Amman (Bryn Amman) . . . | Amman Iron Co. | 4 |
| Avon Vale (Aberavon) . . . | Port Talbot Tin Plate Co. | 4 |
| Beaufort (Morriston) . . . | Beaufort Tin Plate Co. | 7 |
| Burrows (Taibach) . . . | Glamorgan Tin Plate Co. | 3 |
| Cambria (Pontardulais) . . . | Cambria Co-operative Co. | 1 |
| Cilfrero (Neath) . . . | Prosser Son & Co., Limited | 2 |
| Clydach (Swansea) . . . | John Player | 2 |
| Clyne (Neath) . . . | H. Thomas & Co., Limited | 2 |
| Cwm Avon (Taibach) . . . | Copper Miners' Tin Plate Co. | 8 |
| Cwm Bwrla (Swansea) . . . | Swansea Tin Plate Co. | 5 |
| Cwm Felin (Swansea) . . . | Cwm Felin Tin Plate Co. Lmtd. | 5 |
| Dowlais (Merthyr) . . . | Dowlais Iron Co. | 2 |
| Dyffryn (Morriston) . . . | Daniel Edwards and Co. | 6 |
| Foxhall (Llansamlet) . . . | Foxhall Tin Plate Co. | 2 |
| Gadlys Uchaff (Cardiff) . . . | Hosgood & Smith | 3 |
| Glamorgan (Pontardulais) . . . | Webb, Shakespear, & Williams | 2 |
| Glantawe (Swansea) . . . | Glantawe Tin Plate Co. | 2 |
| Glanyrafon (Swansea) . . . | Glanyrafon Iron & Tin Plate Co. | 2 |
| Gorceinon (Swansea) . . . | Gorceinon Tin Plate Co. | 2 |
| Gower (Penclawd) . . . | Morris, Smith, Thomas & Co. | 4 |
| Gurnos (Ystalyfera) . . . | Gurnos Tin Plate Co. | 2 |
| Landore (Swansea) . . . | Landore Tin Plate Co. | 7 |
| Llantrissant (Cardiff) . . . | Llantrissant Tin Plate Co. | 4 |
| Llwydarth (Maesteg) . . . | Llwydarth Tin Plate Co. | 5 |
| Mansel (Taibach) . . . | Mansel Tin Plate Co. | 6 |
| Margam (Neath) . . . | Robert B. Byass & Co. | 6 |
| Melyn Griffith (Cardiff) . . . | T. W. Booker & Co., Limited | 6 |
| Melyn (Neath) . . . | Leach, Flower, & Co. | 7 |
| Merthyr (Aberdare) . . . | Stuart Steel, Iron, & Tin Plate Co. | 2 |
| Midland (Morriston) . . . | D. Glasbrook & Co. | 3 |
| Morriston (Swansea) . . . | Morriston Tin Plate Co. | 5 |
| Pontardawe (Swansea) . . . | W. Gilbertson & Co. | 6 |
| Pontardulais (Pontardulais) . . . | Pontardulais Tin Plate Co. | 3 |
| Taibach (Port Talbot) . . . | D. R. David & Co. | 2 |
| Teilo (Pontardulais) . . . | Teilo Tin Plate Co. | 2 |
| Treforest (Pontypridd) . . . | Treforest Tin Plate Co. | 5 |
| Upper Forest (Swansea) . . . | Llansamlet Tin Plate Co. | 7 |
| Vernon (Breton Ferry) . . . | David Morris & Co. | 8 |
| Waterloo (Cardiff) . . . | George Geen & Co. | 2 |
| Worcester (Swansea) . . . | Llansamlet Tin Plate Co. | 5 |
| Ynismendwy (Swansea) . . . | Ynismendwy Tin Plate Co. | 2 |
| Ynispennllwch (Clydach) . . . | Tawe Tin Plate Co., Limited | 5 |
| Yspitty (Loughor R. S. O.) . . . | J. Rushton Turnock | 3 |
| Ystalyfera (Swansea) . . . | Ystalyfera Iron Co. | 12 |
| Total of Glamorganshire . . . | | 188 |

TABLE IV.
CAERMARTHENSHIRE.

| Name of Works. | Name of Firm. | Total Mills. |
|-------------------------------------|---|--------------|
| Avondale | Avondale Iron and Tin Plate Co. | 1 |
| Burry (Llanelly) | Burry Tin Plate Co., Limited . | 4 |
| Caermarthen (Caermarthen) | Thomas Lester & Co. | 5 |
| Dafen (Llanelly). | Phillips, Nunes, & Co. | 4 |
| Glanamman (Cwmamman) | Glanamman Tin Plate Co., Lim. | 2 |
| Gwendraeth (Kidwelly) | J. Chivers & Son | 10 |
| Hendy (Pontardulais) | Edm. Boughton & Co., Limited | 4 |
| Lion | H. Thomas | 2 |
| Llanelly (Llanelly) | John S. Tregonning & Son | 4 |
| Llangennech (do.) | Llangennech Tin Plate Co. | 8 |
| Morlais (Llangennech) | Llansamlet Tin Plate Co. | 2 |
| Old Castle (Llanelly) | Old Castle Iron and Tin Plate Co., Limited. | 6 |
| South Wales (Llanelly) | E. Morewood & Co. | 9 |
| Western (Llanelly) | Western Tin Plate Co., Limited | 4 |
| Total of Caermarthenshire | | 65 |

TABLE V.
MONMOUTHSHIRE.

| Name of Works. | Name of Firm. | Total Mills. |
|--|--|--------------|
| Abergavenny (Abergavenny) | Llanelly Iron and Tin Plate Co. | 2 |
| Abercarne (Newport) | Daniel Whitehouse | 8 |
| Abertillery (Newport) | Philip S. Phillips | 7 |
| Blaina (Blaina) | Blaina Iron and Tin Plate Co. | 6 |
| Caerleon (Newport) | F. Moggridge & Co. | 2 |
| Garth (Newport) | Garth Iron and Tin Plate Co. | 4 |
| Machen (Newport) | Machen Iron and Tin Plate Co. | 3 |
| Monmouth Forges | H. T. Griffiths & Co. | 1 |
| Pontnewydd (Newport) | B. Conway & Co. | 2 |
| Pontrhydyrun (Newport) | Conway Brothers | 2 |
| Pontheer (Caerleon) | Conway, Conway & Co. | 2 |
| Pontymister (Newport) | Pontymister Tin Plate Co. | 5 |
| Pontypool (Pontypool) | Pontypool Iron and Tin Plate Co. | 8 |
| Redbrook (Monmouth) | Redbrook Tin Plate Co. | 3 |
| Rhiwderin (Newport) | Garth Iron and Tin Plate Co. | 4 |
| Tydu and Rogerston (Newport) | Tydu and Rogerston Tin Plate Co. | 2 |
| Tynewydd (Pontnewydd) | Tynewydd Iron and Tin Plate Co., Limited | 2 |
| Total of Monmouthshire | | 63 |

TABLE VI.
GLOUCESTERSHIRE.

| Name of Works. | Name of Firm. | Total Mills. |
|------------------------------------|--|--------------|
| Abbey Tintern (Chepstow) . { | Abbey Tintern Wire and Tin Plate Co. | 2 |
| Caldicot (Chepstow) | Caldicot Tin Plate Co. | 2 |
| Hawkwell (Cinderford) | J. Chivers & Co. | 3 |
| Lydney (Lydney) | Richard Thomas & Co. | 4 |
| Lydbrook (Ross) | Richard Thomas & Co. | 5 |
| Parkend (Lydney) | Henry Crawshaw & Sons | 2 |
| Total of Gloucestershire | | 18 |

TABLE VII.
STAFFORDSHIRE AND WORCESTERSHIRE; SCOTLAND, CUMBERLAND, AND FLINTSHIRE.

| Name of Works. | Name of Firm. | Total Mills. |
|---|----------------------------------|--------------|
| <i>Staffordshire and Worcestershire.</i> | | |
| Bradley (Bilston) | Hatton, Sons, & Co. | 4 |
| Broadwaters (Kidderminster) . . | | 2 |
| Brockmoor (Brierley Hill) . . . | Budd and Co. " | 4 |
| Cookley (Kidderminster) | John Knight & Co. | 3 |
| Hope (Tipton) | Hope Iron and Tin Plate Co. . . | 2 |
| Horseley Fields (Wolverhampton) . } | E. P. and W. Baldwin | 1 |
| Manor (Wolverhampton) | Stephen Thompson | 2 |
| Osier Bed " | Osier Bed Iron Co. | 3 |
| Rugeley | David Griffiths & Co. | 1 |
| Tividale (Tipton) | Budd & Co. | 4 |
| Wilden (Stourport) | E. P. and W. Baldwin | 5 |
| Total of Staffordshire and Worcestershire | | 31 |
| <i>Scotland.</i> | | |
| Coatbridge (Glasgow) | Coatbridge Tin Plate Co., Lim. . | 3 |
| Milton (Motherwell) | Isaac Summerhill & Co. . . . | 2 |
| Total of Scotland | | 5 |
| <i>Cumberland.</i> | | |
| Derwent (Workington) | W. Griffiths & Co. | 5 |
| <i>Flintshire.</i> | | |
| Mold (Flint) | Alyn Tin Plate Co. | 2 |

TABLE VIII.

EXPORTS OF TIN PLATES in each of the following years, and Ports from which Exported.

| Ports from which Exported. | 1873. | 1874. | 1875. | 1876. | 1877. | 1878. | 1879. | 1880. |
|----------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| | Boxes. | Boxes. | Boxes. | Boxes. | Boxes. | Boxes. | Boxes. | Boxes. |
| Liverpool . . | 1,585,012 | 1,497,440 | 1,808,737 | 1,769,313 | 2,102,620 | 2,052,932 | 2,115,632 | 2,345,247 |
| London . . | 251,806 | 231,262 | 327,800 | 310,372 | 357,159 | 345,508 | 397,399 | 364,268 |
| Swansea . . | 73,077 | 41,456 | 65,487 | 108,616 | 102,721 | 109,829 | 134,309 | 60,162 |
| Bristol . . | 68,392 | 110,471 | 107,883 | 125,082 | 190,460 | 213,092 | 603,644 | 1,032,934 |
| Cardiff . . | 41,948 | 130,224 | 18,734 | 982 | 11,020 | 88,258 | 262,064 | 162,755 |
| Glasgow . . | 8,059 | 4,128 | 3,472 | 2,875 | 2,468 | 3,828 | 8,351 | 14,436 |
| Southampton . | 104,804 | 105,869 | 96,505 | 67,244 | 34,193 | 5,772 | 3,970 | 97,987 |
| Hull . . | 12,560 | 19,562 | 19,018 | 10,263 | 14,157 | 15,490 | 7,860 | 8,476 |
| Newcastle . . | 613 | 1,838 | 2,470 | 5,102 | 4,153 | 2,698 | 939 | 2,836 |
| Newhaven . . | 12,206 | 1,218 | 280 | 189 | 120 | 274 | 1 | 59 |
| Total . . | 2,153,477 | 2,143,468 | 2,448,986 | 2,400,038 | 2,819,098 | 2,837,776 | 3,534,169 | 4,089,160 |

TABLE IX.

Exports of TIN PLATES (number of Boxes) from the UNITED KINGDOM to all Ports, in each of the following years, and Countries receiving the same.

| Countries to which Exported. | 1873. | 1874. | 1875. | 1876. | 1877. | 1878. | 1879. | 1880. |
|-----------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| United States Ports. | 1,511,632 | 1,585,994 | 1,673,435 | 1,609,515 | 1,943,444 | 1,931,128 | 2,755,421 | 2,959,390 |
| Holland, Germany, and Belgium . . | 63,647 | 96,313 | 129,114 | 140,165 | 121,884 | 149,640 | 159,362 | 126,805 |
| Australia and New Zealand . . | 76,890 | 42,394 | 52,655 | 69,782 | 76,855 | 63,578 | 42,081 | 80,355 |
| Italy and Mediterranean . . | 114,699 | 72,990 | 121,348 | 97,879 | 91,675 | 141,691 | 108,977 | 196,377 |
| Canada and B. N. America . . | 69,318 | 66,188 | 78,022 | 95,684 | 167,592 | 103,284 | 120,798 | 200,138 |
| France and Switzerland . . | 71,589 | 40,318 | 63,455 | 108,752 | 97,517 | 97,928 | 75,311 | 148,914 |
| South America and Brazil . . | 50,852 | 51,079 | 54,151 | 52,586 | 54,402 | 62,676 | 48,537 | 68,661 |
| Spain and Portugal . . | 64,041 | 54,013 | 72,174 | 60,994 | 68,612 | 70,101 | 61,225 | 86,179 |
| Norway, Sweden, and Baltic . . | 67,639 | 71,555 | 114,993 | 83,233 | 88,298 | 103,008 | 81,029 | 93,147 |
| India and China . . | 42,515 | 44,636 | 71,897 | 61,763 | 86,369 | 92,260 | 63,431 | 124,554 |
| West Indies . . | 8,434 | 8,953 | 8,847 | 10,143 | 12,891 | 12,033 | 9,346 | 13,626 |
| Cape, Ceylon, and Mauritius . . | 7,984 | 3,111 | 2,018 | 4,261 | 3,174 | 3,080 | 3,414 | 3,718 |
| Africa and Outside Islands . . | 3,038 | 4,169 | 4,281 | 3,919 | 4,478 | 5,676 | 4,242 | 4,504 |
| Unclassed . . | 1,199 | 1,755 | 1,690 | 1,862 | 1,907 | 1,693 | 995 | 2,302 |
| Total Boxes . . | 2,153,477 | 2,143,468 | 2,448,986 | 2,400,038 | 2,819,098 | 2,837,776 | 3,534,169 | 4,089,160 |

TABLE X.

. TIN PLATES EXPORTED.

Countries to which exported, Quantities and Value in each of the years 1870, 1875, and 1880 (according to Trade and Navigation Returns).

| Countries to which Exported. | Quantities. | | | Value. | | |
|---------------------------------|-------------|---------|---------|-----------|-----------|-----------|
| | 1870. | 1875. | 1880. | 1870. | 1875. | 1880. |
| | Tons. | Tons. | Tons. | £ | £ | £ |
| France | 1,258 | 3,186 | 4,418 | 27,135 | 84,602 | 82,362 |
| United States | 75,372 | 95,995 | 164,284 | 1,762,914 | 2,541,004 | 3,374,010 |
| British North America | 2,982 | 4,134 | 10,399 | 73,740 | 118,004 | 221,245 |
| Australia | 3,136 | 3,192 | 4,474 | 82,925 | 91,234 | 95,723 |
| Other Countries . . . | 17,329 | 31,856 | 34,124 | 421,843 | 856,638 | 674,752 |
| Total | 100,077 | 138,363 | 217,690 | 2,368,557 | 3,691,382 | 4,448,092 |

INDEX.

ABERDARE Coal, parish returns, 206.
 — Iron Works, pig iron made at, 619.

Adalbert Shaft, Bohemia, depth of, 77.
 Adderbury iron ore, Oxfordshire, production of, 679.

Ages of persons employed in coal mining, 312.

Alfreton Iron Works, Derbyshire, 814.

Algeria, iron ore from, 795.

Altynowian coal basin, Ireland, 284.

Analyses of Coal :—

Anthracite, South Wales :—Big Vein, 193.—Bonville's, 192.—Gwendraeth, 192.—Pontyeats, 193.—Saundersfoot, 193.—Timber Vein, 193.—Watney's, 193.

Bituminous, United Kingdom :—

Arley, Lancashire, 71.
 Aughabehy, Ireland, 285.
 Bagillt Main, Flintshire, 178.
 Balcarres, Lancashire, 71.
 Ballycastle, Ireland, 288.
 Barnaley, Yorkshire, 39.
 Birchgrove Graigola, Caermarthen, 197.
 Blackley Hurst, Lancashire, 71.
 Black Vein, Monmouth, 196.
 Bovey Tracey, Devon, 250.
 Bowden Close, Durham, 9.
 Bristol, Somerset, 240.
 Brockwell, Durham, 12.
 Brora, Scotland, 268.
 Brymbo, Denbigh, 175.
 Buddles, Hartley, 10.
 Busty, Durham, 12.
 Caermarthenshire, 197.
 Charcoal Vein, Monmouth, 196.
 Coleford High Delf, Forest of Dean, 227.
 Dalkeith, Scotland, 264.
 Darfield Main, Yorkshire, 40.
 Dukinfield, Cheshire, 93.
 Dungannon, Ireland, 286.
 Edmund's Main, Yorkshire, 40.
 Eglinton, Scotland, 267.
 Elsecar, Yorkshire, 40.
 Ewloe, Flintshire, 178.
 Fordell Splint, Scotland, 265.

Analyses of Coal—(continued.)

Forest of Dean, Gloucester, 225.
 Garesfield, Durham, 9.
 Glamorganshire, South Wales, 197.
 Hartley, Durham, 8.
 Haswell, Durham, 8.
 Haydock, Lancashire, 74.
 Hurlford, Scotland, 267.
 Ibstock, Leicester, 119.
 Ince Hall, Lancashire, 72.
 Langley, Derbyshire, 102.
 Little Row, Stafford, North, 143.
 Loscoe, Derbyshire, 102.
 Maasbro' Park, Yorkshire, 40.
 Newcastle Hartley, Durham, 10.
 Nixon's Merthyr, Caermarthen, 197.
 Oaks, Yorkshire, 40.
 Original Hartley, Durham, 8.
 Park End, Forest of Dean, 226.
 Pemberton, Lancashire, 73.
 Portland, Nottingham, 114.
 Radstock, Somerset, 240.
 Renishaw, Derbyshire, 102.
 Rover, Ireland, 285.
 Ruabon, Denbigh, 174.
 Seaton Burn, Durham, 10.
 Shireoaks, Nottingham, 113.
 Shropshire, 134.
 Silkstone, Yorkshire, 41.
 Silkstone Brights, Yorkshire, 42.
 Slievardagh, Ireland, 289.
 South Peareth, Durham, 9.
 Splint Coal, Scotland, 261.
 Staveley, Derbyshire, 102.
 Sunderland, Durham, 10.
 Ten Yard, or Thick Coal, Staffordshire, South, 156.
 Thomas, Merthyr, Caermarthen, 197.
 Top, Yard, and Double, Shropshire, 134.
 Trenchard, Forest of Dean, 227.
 Wellwood, Scotland, 265.
 Whitwick, Leicester, 120.
 Willington, Durham, 9.
 Wombwell Main, Yorkshire, 41.
 Wrexham, Denbigh, 175.
Cannel :—Boghead, Scotland, 179.—
 Capeldrea, Scotland, 259.—Dovenby,

Analyses of Coal—(continued.)

Cumberland, 60.—Dukinfield, Cheshire, 93.—Leeswood Curly, Flintshire, 179.—Leeswood Smooth, Flintshire, 179.—Lesmahago, Scotland, 179.—Lochgelly, Scotland, 259.—Pirnie, Scotland, 260.—Wigan, Lancashire, 179.

Analysis of Coke :—

Durham, 12.

Analyses of Foreign Iron Ores :—

Allevard, France, 793.
 Bilbao, Spain, 787.
 Calamita, Italy, 796.
 Dannemora, Sweden, 800.
 Deseada, Spain, 788.
 Djebel, Algeria, 794.
 Island of Seriphos, Greece, 798.
 Lake Ore, Flaten, Sweden, 800.
 Monges, Portugal, 791.
 Privas, France, 792.
 Rio Albano, Italy, 796.
 Roslagen, Sweden, 800.
 Terranera, Italy, 796.

Analyses of Iron Ore and Ironstone :—

Abbotsbury, Dorset, 674.
 Abercarne, Monmouth, 592.
 Adderbury, Oxfordshire, 681.
 Arigna, Ireland, 773.
 Auchencarne, Scotland, 723.
 Bassy Mine, Stafford, North, 500.
 Bauxite, Ireland, 773.
 Bedworth, Warwick, 479.
 Belmont, Cleveland, 370.
 Black Band, Scotland, 721.
 Black Bed Mine, Yorkshire, W.R., 349.
 Black Pin, Wales, South, 593.
 Blaenavon, Wales, South, 590.
 Blisworth, Northampton, 544.
 Billingsley, Shropshire, 485.
 Bole, Ireland, 763.
 Brandy Brush, Forest of Dean, 648.
 Brendon Hills (Calcined ore), Somerset, 688.
 — (Spathose), Somerset, 667.
 Brigg, Lincolnshire, 566.
 Brixworth, Northampton, 544.
 Brixham, Devonshire, 695.
 Brown and Black Rakes, Derbyshire, 464.
 Brush Ore, Forest of Dean, 647.
 Butterley District, Derbyshire, 465.
 Cannel Mine, Stafford, North, 501.
 Carnlough, Ireland, 768.
 Castlecomer, Ireland, 759.
 Cheese Mine, Wales, South, 597.
 Clay Bands, Scotland, 722.
 Cleator Moor, Cumberland, 419.
 Cogenhoe, Northampton, 546.
 Culworth, Northampton, 545.
 Donnington Wood, Shropshire, 482.

Analyses of Iron Ore and Ironstone—(continued.)

Dowlais Rosser Vein, Wales, South, 594.
 Dowlais Spotted Vein, Wales, South, 595.
 Duchy and Peru, Cornwall, 711.
 Dungannon, Ireland, 757.
 Easton Neston, Northampton, 545.
 Eskdale, Cumberland, 420.
 Eston, Cleveland, 368.
 Evishacrow, Ireland, 767.
 Fawler, Oxfordshire, 680.
 Forest of Dean, Eastern Side, 649.
 Frank Mills, Devonshire, 693.
 Frodingham, Lincolnshire, 564.
 Furness, Lancashire, 438.
 Gilbrow, Lancashire, 437.
 Glenarm, Ireland, 768.
 Glenariff, Ireland, 770.
 Grains, Stafford, South, 516.
 Gravel Hill, Cornwall, 712.
 Grey Vein, Forest of Dean, 647.
 Gubbin, Stafford, South, 516.
 Gutter Mine, Stafford, South, 500.
 Hareshaw, Durham, 326.
 Haytor, Devon, 689.
 Heyford, Northampton, 541.
 Hutton Low Cross, Cleveland, 371.
 Ingleby, Cleveland, 373.
 Irish Hill, Ireland, 771.
 Knightor, Cornwall, 707.
 Lindal Moor, Lancashire, 437.
 Mid-Lincoln, Lincolnshire, 566.
 Mount, Cornwall, 711.
 Mushet's Black Band, Scotland, 720.
 Mwyndy, Wales, South, 602.
 Paint Ore (Brixham), Devon, 695.
 Park Gate, Yorkshire, W.R., 350.
 Pawton, Cornwall, 706.
 Perran, Cornwall, 712.
 Pisolithic Ore, Ireland, 762.
 Pontypool Black Band, Wales, South, 592.
 Red Hills, Ireland, 775.
 Red Mine, Stafford, North, 500.
 Red Shag, Stafford, North, 500.
 Red Vein, Wales, South, 593.
 Restormel, Cornwall, 704.
 Ridsdale, Durham, 326.
 Rosedale Abbey, Cleveland, 373.
 Saint Austell, Cornwall, 714.
 Seend, Wiltshire, 676.
 Shotley Bridge, Durham, 326.
 Smallacombe, Devon, 691.
 Smith Ore, Forest of Dean, 647.
 Soap Vein, Wales, South, 593.
 South Terras, Cornwall, 715.
 Staveley District, Derbyshire, 467.
 Sulphury Mine, Wales, South, 596.
 Treamble, Cornwall, 712.

Analyses of Iron Ore and Ironstone—
(continued.)

- Trecastle, Wales, South, 604.
Trefechan, Wales, North, 575.
Upleatham, Cleveland, 369.
Weardale (Spathose), Durham, 327.
Wellington, Northampton, 441.
Westbury, Wiltshire, 676.
Whitchurch, Wales, South, 603.
White Bed Mine, Yorkshire, W.R., 349.
White Pines Mine, Wales, South, 596.
"Anglesea Coal Field."—Ramsay, Prof., 173.
Anthracite in Blast Furnaces.—Budd, Mr. J. P., application of, 622.
— analyses of, *see* Analyses of Anthracite.
— Coal, Pembrokeshire, 192.
— Furnaces, Wales, South, Average produce of, 625.—Capacity of, 622.
— pig iron, 625.
Antrim Black Band ironstone, 758.
— Coal-field, Ireland, 287.
— Iron Ore Co.'s Mines, Ireland, 767.
— iron ore deposits of, Ireland, 759.
— iron ore, working of deposits, 765.
— succession of strata, 760.
Apedale Iron Works, Stafford, North, 506.
Areas of coal-fields :—
Anglesea, 186.
Bovey Tracey, Devonshire, 249.
Brecknockshire, 188.
Caernarthenshire, 188.
Cheshire (*see* Lancashire), 68.
Cumberland, 59.
Denbighshire, 186.
Derbyshire (*see* Yorkshire), 32.
Durham and Northumberland, 3.
Flintshire, 186.
Forest of Dean, 223.
Gloucestershire, 223.
Great Northern Coal-field, 3.
Lancashire and Cheshire, 68.
Leicestershire, 294.
Nottinghamshire (*see* Yorkshire), 32.
Scotland, 254.
Somersetshire, 294.
Staffordshire, North, 140.
Staffordshire, South, 153.
Wales, North, 294.
— South, 188.
Warwickshire, 125.
Yorkshire (including Derby and Notts), 32.
Arigna Coal Basin, Ireland, 284.
— Ironstone, Ireland, 218.
— Iron Works, Ireland, 782.
— Reports on, Ireland, 783, 784.
Artesian Well, Potsdam, Missouri, 77.
Ashton Moss Colliery, Manchester, 75.
Auchencarne iron ore, Scotland, 723.

Aughabehy Coal-field, Ireland, 284.

Average produce of coal per man :—

- Anglesea Coal-field, 183.
Cheshire " 96.
Cumberland " 65.
Denbighshire " 184.
Derbyshire " 110.
Durham " 29, 30.
Flintshire " 185.
Gloucestershire " 233.
Ireland " 291.
Lancashire " 86.
Leicestershire " 123.
Northumberland " 29, 30.
Nottinghamshire " 117.
Scotland " 280.
Shropshire " 138.
Somersetshire " 245.
Staffordshire, N. " 150.
— S. " 168.
Wales, North " 185.
— South " 221.
Warwickshire " 130.
Yorkshire " 52—54.
Ayrshire Coal-field, Scotland, 266.
"Ayr County, General View of," Scotland, Aiton, William, 723.

BAGILLT Main Coal, Flintshire, 177.

- Ballycastle Bay. "Coal-fields of Great Britain," Hull, Prof., 284.
Ballycastle, black band ironstone, 758.—
Production of, 778.
Ballymurtagh Iron Mine, Ireland, 776.
Bar iron manufacture at Middlesboro, 375.
— prices of, in Cleveland, 414.
Barnsley, section of strata, 37.
— thick coal, 348.
Barrow Hæmatite Iron & Steel Co., Analyses of ores, 438.—Mechanical arrangements of, 450.
Barrow Iron Works established, 449.
— Silkstone Colliery, Yorkshire, 40.
Bauxite deposits, Ireland, 772.—Production of, 778.
Beaufort Iron Works, Brecknockshire, .. pig iron made, 1829 to 1838, 612.
Bessèges process, coke manufacture, 202.
Bessemer Steel Works, Crewe, Cheshire, 460.—Dowlais, Glamorganshire, 629.—
Ebbw Vale, 623.—List of, in Great Britain in 1880, 843.—Lancashire, 456.
— Monmouthshire, 626.—Sheffield and Rotherham, 363.—Old Park Works, Staffordshire, South, 533.
Bessemer steel, production of in Great Britain :—Since 1871, 844.—In each district in 1879—80, 845.
Biddulph Valley Iron Works, Staffordshire, North, 508.

- Bideford anthracite, 252.
 Bilbao iron ore deposits, Spain, 785.
 — Consular Report, 789.
 Billingsley coal, Shropshire, 133.
 Birker Moor Iron Mines, Eskdale, Cumberland, 417.
 Birmingham Canal Navigation, coal carried, 164.
 Black band ironstone, order of occurrence :—Scotland, 257.
 Black vein coal, Merthyr : Mr. T. Crowder, "Analysis by," 196.
 Blackwell, Mr. S., of Dudley : "Iron Ores of the United Kingdom Report," 584.
 Blaenavon Iron Works, Monmouthshire, pig iron made, 1829 to 1838, 612.
 Blaina Iron Works, Monmouthshire, pig iron made, 1829 to 1838, 612.
 Blast furnaces, average produce of :—
 Cumberland, 432.
 Denbighshire, 581.
 Derbyshire, 473.
 Durham, 337.
 Glamorganshire, 620.
 Great Britain in 1880, 820.
 Great Britain in 1872, 817.
 Great Britain since 1854, 838.
 Lancashire, 453.
 Lincolnshire, 572.
 Northamptonshire, 555.
 Scotland, 740.
 Shropshire, 493.
 Staffordshire, North, 507.
 Staffordshire, South, 527.
 Wales, North, 581.
 Wales, South (anthracite), 625.
 Wiltshire, 685.
 Yorkshire, North Riding, 395.
 Yorkshire, West Riding, 359.
 — dimensions of, at Askham, Lancashire, 454.
 — dimensions of, Staffordshire, North, 507.
 Blisworth Iron Mines, Northamptonshire, produce of, 549.
 Blocking Bed coal, Yorkshire, 38.
 Bloomfield Iron Works, Tipton, Stafford, South :—"Pig Boiling, 1811," 533.
 "Boat load," Staffordshire, South, 160.
 Blowing machinery, introduction of, by Smeaton, Scotland, 727.
 Bodfari, Flintshire, Wales, North, iron ore deposits, 575.
 Boghead coal, analyses of, 179.
 Bole deposits, Antrim, Ireland, 761.
 "Borlase" iron ore deposits of, Cornwall, 702.
 Boulonnaise iron ore deposits, France, 793.
 Bovey Tracey Coal (Lignite), Devonshire, 249.
 "Bovey Tracey," Devonshire, Phil. Trans. — Milles, Rev. J., on, 250.
 Bovey Tracey Lignite, Devonshire :
 Analysis of "Board Coal," Percy, Dr., Fuel, 251.
 Analysis of, by Vaux, Mr. F., 250.
 Bowling Iron Works, Yorkshire, W. R., founded 1780, 352.
 "Bowling Iron Works," Yorkshire, W. R., Wilcock, Mr. J., on, 353.
 Brecknockshire, Wales, South :—Furnaces built and in blast, 614.—Pig iron production, 1806, 610 ; 1823—1830, 611.—Pig iron made, 1829—1838, 613 ; 1857—1872, 614.—Production of ironstone, 599.
 Brendon Hills, Somersetshire :—Ancient iron ore workings, 666.—Iron ore deposits, 665.
 "Brendon Hills Spathose Iron Ore and Mines," Morgans, Mr. on, 667.
 Bridgewater Canal, construction of, 75.
 — Navigation, coal carried by, 83.
 Brinkburn clay ironstone, Northumberland, 7.
 "British Iron Ores, General Distribution of," by Bauerman, Mr. H., 821.
 Bristol Coal-field, 235.
 "Bristol Coal-field," British Association Report, 1875, 241.
 Bristol coal exports, 231.
 — and Radstock Coal Basin, 236.
 Brixham Iron Mines, Devonshire, 693.—Production of, 696.
 Brora Coal-field, 268.
 Buckinghamshire iron ore deposits, 682.
 Buckshraff Iron Mine, Forest of Dean, 642.
 Bunawe Charcoal-iron furnace, Scotland, 726.
 Burnley District, Lancashire, coals worked in, 68.
 Bute Docks, Cardiff, 210.
 Butterley Iron Works, Derbyshire, 470.—Celebrated for examples of castings, 471.
 CALCINATION of iron ores, Staffordshire, North, 503.
 Calder Iron Works, Scotland, 731.
 Caledonian Railway, Scotland, coal carried by, 277.
 Canal distribution of South Staffordshire coal, 164.
 Cannel coals, analyses of. (*See* Analyses of Cannel coals).
 — Coal, Great Britain, production of in 1865, 182.
 Carboniferous Limestone, iron ore deposits of. (*See* Iron Ore deposits of Carboniferous Limestone).

- Carboniferous Limestone Series, Scotland, coal seams in, 263
 — Limestone-coal Series, Northumberland, 6.
 — system, Yorkshire, 32.
 Carron Iron Works, Scotland, 727.
 Castlecomer Coal Basin, Ireland, 288.
 Cefn Cwse ironstone measures, Wales, South, 589.
 Charcoal iron furnaces :—
 Cumberland, 428.
 Goatfield, Scotland, 727.
 Hampshire, 686.
 Lancashire, 44.
 Monmouthshire (1788), 607.
 Pontypool, 604.
 Scotland, 726.
 — pig iron, make of :—
 Derbyshire, 470.
 Hampshire, 686.
 Lancashire, 448.
 Cheadle Coal-field, 143.
 Cheshire coal, analysis of, "Toothill, Mr. R. S.," 93.
 — coal, analysis of, by "Percy, Dr., Metallurgy—Fuel," 93.
 — Coal-field, 92.—"Coal Com. Report," Dickinson, Mr. J., 97.
 — distribution of coal, 95.
 — Iron Industries, 460.
 — production of coal, 94.
 Chromic iron ore, Russia, 801.
 Churnet Valley iron ore, Staffordshire, North, 502.
 Cinder iron, Staffordshire, South, 530.
 Cinderford Iron Works, Forest of Dean, 659.—Iron ore used in, 664.
 Clackmannan Coal-field, 266.
 Clapton in Gordano and Severn Basin, Somersetshire, section of boring at, 237.
 Clay, analysis of, Santon, Lincolnshire, 573.
 Cleator Moor Mines, Whitehaven, 415.
 Cleveland and Whitby districts, mines working in 1880, 381.
 — Coal and iron ore used in pig iron manufacture, 399.
 — Bessemer pig iron made, 396.
 "Cleveland Blast Furnaces," average yield of, Richards, Mr. W., 396.
 — calcined ironstone, analysis of, 372.
 — furnaces, ironstone smelted, 385.
 "Cleveland Ironstone District, Resources of," Barrow, Mr. G., Paper on, 387.
 — ironstone field, area of, 368.
 "Cleveland Ironstone, Memoir on," Marley, Mr. J., 376.
 — ironstone mining, population employed, "Reports H. M.'s Inspectors of Mines," 385.
 — ironstone, yield of metallic iron, 374.
 Cleveland Iron Works, when established, 394.
 — Iron Works in 1880, 397.
 — "main ironstone seam," 365.
 — Malleable Ironworks in 1880, 413.
 — mines producing ore in 1880, 378.
 — pig iron, average prices of, 398.
 — pig iron, distribution of, 397.
 — raw ironstone, analysis of, 372.
 Clydach Ironworks, Brecknockshire, pig iron made, 1829 to 1838, 612.
 Clyde Coal Basin, Scotland, 257.
 — Ironworks, Glasgow, 729.
 — Valley coal and ironstone series, 258.
 Coal, analyses of (*see* Analyses of coal).
 — average used in pig iron manufacture, 1871 to 1880, 818.
 — average produce per man (*see* Average produce of coal per man).
 "Coal and Coal Mining," Smyth, Mr. W. W., 289.
 Coal-fields of the United Kingdom :
 — fields, areas of (*see* Areas of coal-fields).
 — first tax on, 1379, 2.
 — and ironstone carried by North-Eastern Railway, Durham, 24.
 "Coal and Ironstone Series, Clyde Valley," Moore, Mr. W., on, 258.
 "Coal and Ironstone Strata of Scotland," Geikie, Mr. J., on, 258.
 Coal and ironstone used in pig iron manufacture :—
 Cleveland district, 399.
 Cumberland, 432.
 Derbyshire, 475.
 Durham and Northumberland, 343.
 Forest of Dean, 663.
 Great Britain, 813.
 Great Britain in 1840, 836.
 Lancashire, 458.
 Lincolnshire, 572.
 Muirkirk, Scotland, 748.
 Northamptonshire, 556.
 Scotland, since 1872, 752.
 Shropshire, 497.
 Staffordshire, North, 509.
 Staffordshire, South, 527.
 Wales, North, 582.
 Wales, South, 640.
 Wiltshire, 685.
 Yorkshire, North Riding, 402.
 Yorkshire, West Riding, 363.
 Coal, cinders, and culm sent coastwise since 1834 :—England, 307.—Ireland, 307.—Scotland, 307.
 —, coke, cinders, and patent fuel exported, 310.
 — coking (*see* Coking coal).
 "Coal Committee Report, 1873," coal used in pig iron manufacture, 816.

- Coal crushing and washing in Coke manufacture, Lancashire, 453.
- deep-winning, at Harris' Navigation Pits, Brown and Adams, Messrs., on, 206.
- distribution of (*see* Distribution of coal).
- economy of, by Cowper's and Whitwell's stoves, 819.
- economy in pig iron manufacture since 1871, 819.
- exported to foreign countries, 1816 to 1832, 308.
- exported to foreign countries, and value, since 1856, 310.
- Coal-fields of :—
- Cheshire, 92.
 - Cumberland, 59.
 - Derbyshire, 99.
 - Devonshire, 249.
 - Durham, 1.
 - Gloucestershire, 223.
 - Ireland, 283.
 - Lancashire, 68.
 - Leicestershire, 118.
 - Monmouthshire, 188.
 - Northumberland, 1.
 - Nottinghamshire, 111.
 - Scotland, 254.
 - Shropshire, 132.
 - Somersetshire, 235.
 - Staffordshire, North, 140.
 - Staffordshire, South, 153.
 - United Kingdom, 294.
 - Wales, North, 172.
 - Wales, South, 188.
 - Warwickshire, 125.
 - Yorkshire, 32.
- Coal first sent to London, 1.
- Household, Durham, 7.
- Pit Heath, Gloucestershire, 237.
- previously coked, used at Coalbrookdale by Darby, 487.
- production of (*see* Production of Coal).
- Slievardagh, 289.
- strata (*see* Strata, Section of).
- used in Edward III.'s time, 2.
- used in Malleable Iron Works (*see* Malleable Iron Works, coal used in).
- washing apparatus, Pemberton Colliery, 79.
- wrought under the sea :—
- Monkwearmouth, 18.
 - Workington, Cumberland, 60.
- Coalbrookdale Coal-field, 132.
- Ironworks, 487.
- Ironworks, when established, 495.
- Coke, experiments on, Clarence Ironworks, 11.
- Coke, manufacture of, Almond Works, Scotland, 749.
- Bainbridge, Mr. E., on, 201.
- Bességes process, Belgium, 202.
- Durham, 14.
- Ebbw Vale, Coppée process, 199.
- production of, Durham, 13, 15.
- Somercotes Works by Mushet, Mr. D., 470.
- Wigan Coal and Iron Co., 452.
- yield per cent. from Durham Coals, 13.
- Ynysawdre Coal Co., 201.
- Coking Coal :—
- Bességes process, 202.
 - Coppée process, 199.
 - Lancashire, 453.
 - Ordinary process, 13.
 - Tyne and South Durham, 10.
 - Yield of Glamorganshire coal, 198.
 - Yield of Monmouthshire coal, 196.
- Collieries, number of :—
- Anglesea, 181.
 - Bristol and Somerset, 245.
 - Cheshire, 94.
 - Cumberland, 63.
 - Denbighshire, 181.
 - Derbyshire, 104.
 - Flintshire, 181.
 - Forest of Dean, 228.
 - Ireland, 291.
 - Lancashire, 78.
 - Leicestershire, 120.
 - Monmouthshire, 205.
 - Nottinghamshire, 115.
 - Scotland, 270.
 - Shropshire, 134.
 - Somersetshire, 244.
 - Staffordshire, North, 146.
 - Staffordshire, South, 159.
 - United Kingdom, 296.
 - Wales, North, 181.
 - Wales, South, 205.
 - Warwickshire, 127.
 - Yorkshire, 44.
- Colliery Guardian, prices of finished iron, 537.
- Concealed Coal-fields, coal remaining unwrought, 315.
- "Connaught Coal-field," Griffith, Sir R., 781.
- Consumption of Coal, South Staffordshire collieries, 163.
- Coppée process, coke manufacture, 199.
- Cornwall iron industries, 702.
- price of iron ore, 715.
 - St. Austell iron ore deposits, 714.
 - situation of the principal iron mines, 716.
 - Tregorne iron lode, 713.
- "Cowper Stoves," description of, 399.

- Cowper's and Whitwell's Stoves, economy in use of fuel by, 819.
- Crane, Mr. G., application of anthracite in blast furnace, 622.
- Crews, engineering and metallurgical works at, 460.
- Cronebane Iron Mine, Ireland, 776.
- Cumberland coal-field, 59.
- "Cumberland Coal-field," Coal Commission Report, 66.
- "Cumberland Coal-field," Reports H. M. Inspectors of Coal Mines, 65.
- History and Antiquities of—Hutchinson, 428.
- Iron industries, 415.
- Iron mines, list of, in 1880, 426.
- Iron ore conveyed to Iron Works and shipped, 426.
- Iron ore deposits, Roanhead Mines, 436.
- "Cumberland iron ore deposits," Wurzburger, Mr. P., on, 416.
- Iron ore used in furnaces, 434.
- Iron Works, when established, 430.
- Iron Works and furnaces in 1880, 433.
- Pig iron manufacture, 428.
- Produce of coal per man, 65.
- West, Steel Works, 431.
- Cyfarthfa Iron Works, Account of, 621.
- Cyfarthfa Iron Works, Glamorganshire, Pig Iron made 1829 to 1839, 619.
- D****ALZIEL** Steel Works, near Glasgow, Account of, 745.
- Dannemora iron mines, Sweden, 799.
- Darby, A., "Use of pit coal for smelting iron," 487.
- De la Beche, on "Devon and Cornwall," 253.
- Deep Shafts (*see* Shafts, Deep).
- De la Beche and Playfair.—"Coals suited to the Steam Navy," 195.
- Denbighshire Coal Field, 172.
- production of ironstone, 576.
- production of pig iron, 578.
- succession of strata, 577.
- Derbyshire, analyses of ironstones, 464.
- Coal-field, 99.
- Coals, Analyses of Report.—"Coals suited to the Steam Navy," 102.
- Coal, Canal and Railway distribution, 107—108.
- "Derbyshire, General View of, &c.," John Farey, 1811, 475.
- Derbyshire ironstone measures or "rakes," 462.
- Iron industries, 462.
- Iron works, when established, 470.
- Derbyshire, list of Iron Works in, 1796, 470.
- list of Iron Works in, 1851, 472.
- mills and forges, list of, in 1806, 474.
- mills and forges, list of, in 1880,— coal used, 475.
- pig iron manufacture, 469.
- production of coal, "Mineral Statistics," 104.
- production of pig iron since 1855, 473.
- "Derbyshire, view of," by Farey, J., 103.
- "Derbyshire, view of," Pilkington, quoted, 103.
- Devon Iron Works, Scotland, 730.
- North, iron ore deposits, 698.
- Devonshire coal and lignite deposits, 249.
- iron industries, 688.
- iron mines, producing ore in 1880, 699.
- iron ore deposits, 692.
- iron ore, distribution of, 700.
- iron ores, value of, 699.
- iron ore, yield of metallic iron, 701.
- production of iron ore, 699.
- Distribution of coal:—
- Cheshire, 96.
- Cumberland, 64.
- Derbyshire, 103.
- Durham, 17, 19.
- Durham, early account of, 20.
- Durham, coastwise and exported, 22, 23.
- Durham, by Great Northern and Furness railways, 25.
- Forest of Dean, 230.
- Lancashire, 80.
- Leicestershire, 120.
- Nottinghamshire, 116.
- Scotland, 268.
- Scotland, coastwise and exported, 273.
- Shropshire, 135.
- Staffordshire, North, 146.
- Staffordshire, South, 161.
- Wales, North, 183.
- Wales, South, coastwise and exported, 216.
- Wales, South, by railway, 217.
- Wales, South, by rail and sea, 210.
- of ironstone, Cleveland, 385.
- of iron ore, Cornwall, 716.
- of iron ore, Cumberland, 423.
- of iron ore, Lancashire, 444.
- of ironstone by railway, Lincolnshire, 569.
- Dorsetshire iron ore deposits, 673.
- Dovenby Colliery, Maryport, 60.
- Dowlais Iron Works, Glamorganshire, 615.
- Iron Works, Glamorganshire, pig iron made, 1829 to 1839, 619.
- Wales, South, section of strata, 586.
- Dronfield, section of strata, Derbyshire, 463.

- Drumshambo Iron Works, Ireland, 782.
 Duchy and Peru Mine, Cornwall, 710.
 Dud Dudley, "Metallum Martis," account of his labours, 562.
 Dungannon Coal-field, Ireland, 286.
 "Dungannon Coal-field," Ireland, Hardman, Mr. E. F., 286.
 Durham coal:—Carried by Great Northern and Furness Railways, 25.—Carried by North Eastern Railway, 24.
 — Coal-field, 1.
 — Furnaces, ironstone smelted, 385.
 — Iron Works in 1851, 335.
 "Durham and Northumberland Coal-field":—Elliot, Sir G., 30.—Forster, Mr. T. E., 30.—Howell, Mr. H. H., 3.
 —Inspectors of H. M. Coal Mines, 29.
 —"Mineral Statistics," 19.
 Duties on coal, 18th century, 2.
 Duty on coal exported to foreign countries, 308.
- EAST END** Iron Works, Northamptonshire, 552.
 East Lothian Coal-field, 264.
 Ebbw Vale Iron Works, Monmouthshire, pig iron made, 1829 to 1838, 612.
 Edinburgh Coal-field, 262.
 Elba, Island of, iron ore, 795.
 Erewash Valley, sales of coals, 105.
 Eskdale, Cumberland, iron ore deposits, 417.
 Eston (Cleveland), production of mines since 1856, 379.
 — Hill (Cleveland), ironstone first worked, 1850, 376.
 — Steel Works opened, 1877, 406.
 Evisnacrow iron ore deposits, Antrim, Ireland, 765.
 Exmoor iron ore deposits, Devon, 697.
 Export duty on coals repealed, 2.
- FAWLER** iron ore, Oxfordshire, production of, 679.
 "Ferrie's Patent," economy in the use of fuel, 749.
 Fifeshire coals, analyses of, 265.
 — Coal-field, 265.
 Finished iron, prices of, Staffordshire, South, 536.
 — production in North of England, 406.
 Fire-clays, analysis of Bowling, 35.
 "Flintshire Coal-field," Hull, Professor, 173.
 — population employed in iron mining, 597.
 — production of ironstone, 576.
- Fluxes used in iron smelting :
 — Cumberland, 806.
 — Durham, 805.
 — Lancashire, 807.
 — Northamptonshire, 809.
 — Scotland, 812.
 — Staffordshire, North, 808.
 — " " South, 809.
 — Wales, South, 811.
 — Wiltshire, 810.
 Foreign iron ores imported, 785.
 — imported into northern ports, 345.
 — total imports and value, 802.
 — bauxite, analysis of, 803.
 — " price of at Arles, 803.
 Foreign iron ores, analysis of (see Analysis of foreign iron ores).
 Forest of Dean :—
 — Bar iron made; referred to in Domesday Book, 662.
 — Cinderford Iron Works, 659.
 — "Coal Com. Report," Dickenson, Mr. J., 234.
 — duty on coal exported from, 230.
 — furnaces built and in blast, 660.
 — iron mines, produce and value of iron ore, 651.
 — iron mines in 1880, 645.
 — iron mines, production of, 652.
 — iron ore, distribution of, 650, 655.
 — " distribution of by railway, 656.
 — iron ore raised, eastern side, 655.
 — " " western side, 655.
 — mineral basin, depth of, 643.
 — model of, Sopwith, Thomas, 643.
 — Park End Iron Works, 659.
 — pig iron made, 1740, 658.
 — " manufacture, early history, 657.
 — pig iron production, 660.
 France, imports and value of iron ore from, 794.
 — iron ore deposits of, 792.
 Frampton Cotterell mines, produce of iron ore, 650.
 Frodingham ironstone deposits, Lincolnshire, 559.
 "Frodingham Iron Fields," Dove, Mr., 564.
 Furnaces built and in blast :—
 — Great Britain since 1854, 838.
 — " " in 1872, 817.
 — " " in 1880, 820.
 — Scotland, since 1850, 739.
 — South Wales, since 1854, 626.
 — Yorkshire, W. R., since 1851, 359.
 Furnaces in Great Britain, average yield in 1880, 820.
 Furness Iron and Steel Co., Lancashire, mines of, and ore raised, 1872, 444.

GANISTER and fireclay, analyses of, Halifax, 34.

Ganisters and underclay, Yorkshire, 34.

Gartsherrie Iron Works, Scotland, 732.

— materials employed, 750.

Gas for illuminating purposes introduced, 8.

Gelligaer coal, parish returns, 206.

"**Geology of Rocks of North Lincolnshire**," Cross, Rev. J. E., 560.

Geological distribution of British iron ores, 821.

German colony of iron workers, Shotley Bridge, 330.

Glamorganshire, area of Coal-field, 188.

— (Anthracite Districts), coal used in pig iron manufacture, 633.

— average yield per furnace, 620

— (Bituminous Coal District), coal used in pig iron manufacture, 633.

— Bituminous Districts, pig iron manufacture, 615.

— iron ore used in pig iron manufacture, 639.

— Iron Works in 1880, 621.

— parish returns, 207.

— pig iron made, 1796, 616.

— pig iron made, 1806, 617.

— pig iron made, 1823—1830, 618.

— pig iron made, 1857 to 1880, 620.

— pig iron made and coal used, 1872 to 1880, 633.

— production of ironstone, 599.

Glasgow and North Western Railway, coal carried by, 277.

Glendon Iron Works, Northamptonshire, 553.

Glenariff Mines, Ireland, Argall, Capt., on 768.

Glenravel Mines, Ireland, 777.

Gloucestershire. Bar iron made and list of works in 1750, 662.

— and Berkeley Canal, coal carried, 232.

— Coal-field, 223.

— coal exports, 231.

— coal produce per man, 233.

— iron industries, 642.

— iron works in 1830, 661.

— military forge established at Bath by the Romans, 661.

— production and value of iron ore, 651.

"**Gloucestershire, Survey of**," Rudge, Thomas, 232, 642.

Goatfield Charcoal Iron Furnace, Scotland, 727.

Great Britain. Coal used in pig iron manufacture, 813, 820.

— production of coal, 294.

— production of iron ore in 1849, 420.

Great Northern Railway, distribution of coal by, 301.

— **Retallack and Duchy Peru Mines**, Cornwall, 709.

— **Western Railway**, distribution of coal by, 302.

Greece, iron ore deposits, 797.

Greek Iron Works, Royal, Newcastle-on-Tyne, 797.

Grooved rolls, application of, by Payne, J., 495.

Grosmount ironstone first worked, 1836, 375.

— ironstone first sent to Birtley, Durham, 333.

Guibal fan, Pemberton Colliery, 79.

Guisborough (Cleveland) mines producing iron ore since 1872, 380.

Gupworthy Mine, Brendon Hills, Somersetshire, 667.

HADDINGTON Coal-field, 262.

Hampshire iron industry, 682.

Hampshire, production of iron ore, 682.

Harris' Navigation Pits, 206.

Haytor iron ore deposits, Devonshire, 683.

— Iron Mine, Devonshire, production of ore and value, 690.

Heathfield, Bovey Tracey, 250.

Heathen coal, Stafford, South, used in iron manufacture, 528.

Hennock iron ore, production and value, 692.

— iron ore deposits, Devon, 691.

"**Henwood, Mr.**, on the Perran Great Iron Lode," 708.

Hodbarrow Iron Mines, Millom, production of, 424.

Hot blast, invention of, by Neilson, 733.

"**INDUSTRIAL Resources of Ireland**,"

Kane, Sir Robert, Aughabeghy Coal, 285.—Castlecomer ironstone, 759.

—**Leitrim ironstone**, 755.—**Ballycastle Coal-field**, 288.

"**Industrial Resources of the Tyne, Wear, and Tees**," quoted, 16.

"**Inland Coal Trade**," Report of Committee, 158.

Ireland coal, analyses of (*see* Analyses of Coal).

Ireland, iron industries of, 755.

Iron mines, list of, 1883, 781.

Iron ore, its distribution, 783.

Iron ore produced in 1880, 780.

Iron ore produce and value, 779.

Pig iron manufactured in 1857, 784.

Irish Hill and Straid Iron Mines, 770.

- Iron, first application to shipbuilding, 753.
 "Iron, Manufacture of," Bell, Mr. I. L., 386.
 Iron mines in Cumberland in 1880, 426.
 — mining in Cumberland, population employed in, 427.
 — mining, persons employed, Durham, 329.
 — mining—population employed in Lancashire, 447.
 — mines, raising ore in Lancashire in 1880, 443.
 — mines, Northamptonshire, ironstone raised in 1880, 551.
 —, on the Manufacture of Iron, by the President of Society of Engineers, 813.
 — ore and ironstone, analyses of (*see* Analyses of Iron Ore and Ironstone).
 — ores and their mineralogical characters, Rutley, Mr. F., 319.
 — ores of the carboniferous limestone : Alston Moor, 326.
 — ores of the carboniferous limestone : Lancashire, 436.
 — ores of the carboniferous limestone series : Stiddle Moor, and Ridsdale, 325.
 — ore deposits, Eskdale, Cumberland, 417.
 — ore, mode of occurrence, Antrim, Ireland, 760.
 — ores, geological distribution of, British, Bauerman, Mr. H., 821.
 — ore deposits, Carboniferous limestone, Whitehaven, 415.
 — ore, Carboniferous limestone, Wales, South, 600.
 — ore, Carboniferous limestone, Wales, North, 574.
 — ore, Carboniferous limestone, Lancashire, 436.
 — ore, Carboniferous limestone, Gloucestershire, 642.
 — ore, Dalton-in-Furness, Mouzell Mine, 446.
 — ore deposits, Longford and Cavan, Ireland, 774.
 — ore, production, Ireland, 775.
 — ore deposits, Wicklow, Ireland, 773.
 — ore, distribution of, Lancashire, by ship and rail, 445.
 — ore, production of :—
 — Brendon Hills, 669.
 — Cornwall, 715.
 — Cumberland mines since 1858, 421.
 — Cumberland mines in 1880, 422.
 — Devonshire, 699.
 — Forest of Dean, 649.
 — Great Britain in 1849, 420.
 — Lancashire, 1849, 420.
 — Lancashire since 1855, 442.
 Iron ore, Somersetshire, production and value, since 1857, 671.
 — ore shipped from Whitehaven, 423.
 "Iron Ore" Report, Braithwaite, Poole, 421.
 — ore and ironstone used in :—
 — Cumberland furnaces, 434.
 — Derbyshire furnaces, 477.
 — Durham furnaces, 344.
 — Lancashire furnaces, 459.
 — North Staffordshire, 511.
 — Sources of supply, 511.
 — Yorkshire, North Riding, 403.
 — ores, United Kingdom :—
 — ores from coal measures, production in 1860, 1870, and 1880, 827.
 — ores not in coal measures, production in 1860, 1870, 1880, 826.
 — ores, production of, since the year 1855, 825.
 — rails first used in collieries, 21.
 — rails, prices of in Cleveland, 414.
 — shipbuilding, rise and progress of, 753.
 Ironstone, analysis of (*see* Analysis of Ironstone).
 — average produce per man, Cleveland, 386.
 — average produce per man, Flintshire, 577.
 — average produce per man, Lancashire, 448.
 — calcination of, Staffordshire, South, 529.
 "Ironstone Mining in Cleveland," Steavenson, Mr. A. L. 381.
 Ironstone, Derbyshire, 462.
 — Durham, Wear district, 324.
 — Northamptonshire, first worked in, 547.
 — Northamptonshire, yield of metallic iron, 547.
 — Nottinghamshire, production of, 478.
 — Ruabon Coal-field, 574.
 — Scotland—population employed in mining, 726.
 — Shropshire, 480.
 — Shropshire, North, Coal-field, 142.
 — Staffordshire, North, Coal-field, description of, 499.
 — Wales, South, production of, 599.
 — Warwickshire, production of, 479.
 — Yorkshire, West Riding of, 347—production of and value, 351.
 Ironworks, Denbighshire, 580.
 — Derbyshire in 1796, 471.
 — Derbyshire in 1880, 474.
 — Durham in 1880, 339.
 — Lancashire, list of, 1880, 454.
 — Lincolnshire, 570.
 — Northamptonshire, 1880, 555.

Ironworks, Northumberland, in 1880, 838.
 — Production of pig iron in 1796, 832.
 — Scotland, when established, 735.
 — Staffordshire, North, in 1880, 508.
 Isle of Wight, production of iron ore, 682.
 Italy, imports and value of iron ore from, 797.
 — iron ore deposits, 795.

JESSOP'S, Mr. W., return of pig iron production, 1840, 836.

KENDALL, Mr. J. D., "On the Iron Ores of Antrim," 760.

Ketley Ironworks, when established, 495.
 Kilburne Colliery, Derbyshire, section of strata, 100.
 Kilns employed in ironstone calcining, 530.
 Kirkless Hall Ironworks, Wigan, mechanical arrangements, 450.
 Kirkstall Ironworks, near Leeds, 360.
 Knightor and Ruby Iron Mine, Cornwall, production of iron ore, 708.

LADOCK Iron Mine, Cornwall, production of iron ore, 708.

Lanarkshire Ironworks, Scotland, materials employed, 751.

Lancashire, average produce of iron ore per man, 448.

— average yield per furnace, 453.

— Coal-field, 68.

"Lancashire Coal-field," population employed, Reports H. M. Inspectors of Coal Mines, 86.

"Lancashire Coal Seams," Coal-fields of Great Britain, Hull, Professor, 69.

Lancashire coal, railway distribution, 18.

— Harrison Ainslie's Iron Works, 449.

— hematite ore raised, 1842, 440.

— iron industries, 436.

— iron mines working in 1880, 447.

— malleable ironworks, list of, 1880, 457.

— pig iron production, 1872 to 1880, 453.

— produce of coal per man, 86—87.

— puddling furnaces, rolling mills, and coal used, 457.

— steel works, list of, 456.

"Lancashire Ten Years' Coal Mining," *Colliery Guardian*, 83.

Lancefield Works, near Glasgow, 744.

Landore "Siemens's" Steel Works, near Swansea, 629.

Lee Hall Ironworks, near Bellingham, Northumberland, 331.

Leeds, section of strata, 35.

Leeds, south of Emley Moor, section of strata, 36.

Leeswood cannell, analyses of, 179.

Leicestershire coal, "Coal suited to the Steam Navy," De la Beche and Playfair, 119.

— Coal-field, 118.

— Coal-field, "Coal Commission Report," Woodhouse, J. T., 123.

— coal, analysis of, Percy, Dr., "Metallurgy: Fuel," 120.

— and North Derbyshire Association sales of coal, 106.

— "Population Employed in Coal Mining," Report H. M. Inspectors of Coal Mines, 122.

Leinster Coal-fields, 288.

— Coal-field, ironstones of, 759.

Leitrim Coal-field, 284.

— Coal-field, ironstone measures of, 755.

Lemington furnaces, Durham, materials employed in 1830, 333.

Leamahago cannell, analyses of, 179.

— Coal Basin, 267.

— gas coal, 256.

"Lignites and Clays of Bovey Tracy," Pengelly, Mr., F.G.S., 249.

Lignite, production of, Bovey Tracey, 252.

Limestone, &c., analyses of:—

Broadwood, Durham, 805.

Chalk, hard, Wiltshire, 810.

Dudley, 809.

Froghall, Stafford, North, 808.

Harmby, Durham, 806.

Hobberlaw, Alwick, 805.

Monmouthshire limestone, rough and smooth, 812.

Northamptonshire, 809.

Oolitic limestone, Wiltshire, 810.

Raisby Hill, Durham, 806.

Scotland, 812.

Stanhope, Durham, 804.

Sunderland, 806.

Stainton, Lancashire, 808.

Lincolnshire, coal and ironstone used, 572.

— iron first made in, 571.

— iron furnaces, dimensions of 571.

— iron industries, 559.

— iron mines producing stone in 1880, 568.

—, North, ironstone deposits, 559.

"Lincolnshire Ironstone Deposits," by Dove, Mr. G., junr., 562.

Lincolnshire, succession of strata, 560.

Lithomarge deposits, Antrim, Ireland, 761.

Llanwonno coal, parish returns, 206.

Local Government Board, 8th Report, Calcination of Ironstone, 530.

Locomotives first used on Wylam Railway, 21.

- London Coal Exchange, prices of coal since 1861, 26.
 — and North-Western Railway, distribution of coal by, 300.
 "Lower Lias" ironstone, North Lincolnshire, 561.
 Lowmoor Ironworks, Dawson, Mr. J., founder of: Sketch of his life, 354.
 Lugar, Ayrshire, coal seams, 267.
- M**ACHINERY employed in Ironstone mining in Cleveland, 383.
 Malleable iron, prices of, in Cleveland, 413.
 — Iron and Steel Works in Cleveland, 404.
 — Iron Works in Cleveland in 1880, 412, coal used, 413.
 — Iron and Steel Works, Cumberland, 434.
 — Iron Works, Derbyshire, and coal used, 475.
 — Iron Works, Derbyshire, 1811, 474.
 — Iron Works in 1880, Durham and Northumberland, 342.
 — Iron Works, and coal used, Durham and Northumberland, 339.
 — Iron Works, Glamorganshire, 630.
 — Iron Works, Gloucestershire, 661.
 — Iron Works Great Britain since 1861, 843.
 — Iron Works, Lancashire, 456.
 — Iron Works, Leeds and Bradford, 361.
 — Iron Works, Monmouthshire, 1880, 628.
 — Iron Works, Scotland, list of, 1880, 745, and coal used, 748.
 — Iron Works, Sheffield and Rotherham, 362.
 — Iron Works, Shropshire, 494.
 — Iron Works, Shropshire, coal used, 496.
 — Iron Works, Somersetshire, 672.
 — Iron Works, Staffordshire, North, 509.
 — Iron and Steel Works, Staffordshire, South, 532.—Coal used, 536.
 — Iron Works, Wales, North, coal used, 582.
 — iron rails first rolled at Bedlington by Birkenshaw, in 1820, 339.
 "Manchester Country Around," Aikins, description of, 82.
 Manufacture of Steel, Thomas-Gilchrist process, 407.
 Marsden Colliery, deep sinking, South Shields, 18.
 Mersey Steel Works, mechanical arrangement of, 455.
 Merthyr coal, analysis of, 196.
 Merthyr mineral property, 604.
 Metropolis, coal brought into, by sea, railway, and canal, 305.
 — coal consumed in, 304.
 Middlesborough Bar Ironworks, projected in 1840, 403.
 Middle Lias, Northamptonshire, ironstone deposits, 538.
 "Middle Neocomian," Lincolnshire, ironstone deposits, 563.
 Mid-Lincolnshire ironstone, analysis of, 566.
 "Midland Coal-field," Coal Commission Reports, 56.
 Midland Railway, distribution of coal by, 300.
 Midlothian Coal-field, 262.
 Miller, Mr. W., analysis of Merthyr coal, 196.
 Millom, Cumberland, iron industries of, by Massicks, Mr. Thomas, 428.
 — iron ore deposits, 423.
 Mills and forges, England and Wales, summary, in 1750, 840.
 Mills and forges, England and Wales, in 1750, and make of bar iron, 841.
 Mills, forges and Steel Works, Lancashire, 455.
 Mills and forges, Staffordshire, North, 509.
 Mills and forges, Staffordshire, South, since 1863, 533.
 Miners, privileges of, Forest of Dean, 225.
 "Mines Drainage Act, South Staffordshire," Marten, Mr. E. B., 156.
 "Model of Staffordshire South," drainage area, by Jordan, Mr. J. B., 156.
 Moel Hirradug, Wales, North, cobaltiferous ore, 575.
 Moira District, section of strata, 118.
 Monmouthshire, area of coal-field, 188.
 — (Bituminous Coal District), coal used in pig iron manufacture, 631.
 — furnaces built and in blast, 614.
 — "General view of," Hassall C., 627.
 — furnaces, iron ore, districts supplying, 639.
 — iron ore used in pig iron manufacture, 637.
 — iron works and owners, 1880, 615.
 — mills and forges in 1812, 626.
 — pig iron production, 1806, 610.
 — pig iron production, 1823 to 1830, 611.
 — pig iron made, 1829 to 1838, 613.
 — pig iron made, 1857 to 1880, 614.
 — pig iron made and coal used, 1872 to 1880, 632.
 — production of ironstone, 599.
 Morley Park Iron Works, Derbyshire, 469.
 Moss Bay Steel Works, Workington, 431.
 Mostyn and Bychton Collieries, Flintshire, 179.

Mouzell Mine, deposit of ore at, Dalton-in-Furness, 446.

Muirkirk, Ayrshire coal seams, 267.

— Iron Works, Scotland, 729.

Munster Coal-field, Ireland, 290.

Murdoch, introduction of gas by, 9.

Mushet, David, and Clyde Iron Works, 729.

Mushet's Black Band, discovery of, 719.

Mwyddy iron ore deposits, Wales, South, 601.

Mynyddysallwyn coal, 191.

NAILSEA coal basin, 238.

Nantyglo Iron Works, Monmouthshire, pig iron made, 1829 to 1838, 612.

Neilson's Hot Blast, account of by Dr. Percy, 733.

Neilson, James B., and Clyde Iron Works, 729.

Nettlebridge coal series, 239.

Newburn Iron Works, near Newcastle-upon-Tyne, 332.

Newcastle-upon-Tyne, charter to dig coals, 1.

North British Railway, coal carried by, 277.

North-Eastern Railway, distribution of coal, 297.

North Staffordshire, *see* Staffordshire (North).

North Wales, *see* Wales (North).

"Northampton Sand," succession of strata, 538.

Northamptonshire iron, remarks on, by Butlin, Mr. W., 558.

Northamptonshire, iron industries of, 538.

— iron mines, 552.

— iron mines, produce of, 550.

— ironstone carried by railway, 548.

— ironstone raised, 548.

— yield of ironstone deposits, 440.

— iron, "*Iron and Coal Trades Review*" on, 558.

Northumberland Coal-field, 1.

"Northumberland and Durham Coal series," Hull, Professor, 4.

Northumberland Iron Works in 1851, 335.

Nottinghamshire coal, "Report, Coal suited to the Steam Navy," 113.

— Coal-field, 111.

— pig iron manufacture, 469.

— population employed in coal mining, Reports H.M. Inspector of Coal Mines, 117.

— production of coal, 115.

— production of ironstone, 478.

Norway, imports, and value of iron ore from, 799.

— iron ore deposits, 798.

OPEN Hearth Steel, production of, in Great Britain in 1879, 1880, 846.

Oxfordshire iron ore deposits, 677.

— iron ore, production of, 679.

PAGE, Dr., "Economic Geology," 191.

Paint ore, Brixham, Devon, analysis of, 695.

Park End Iron Works, Forest of Dean, 659.

— iron ore used at, 664.

Parkgate ironstone measures, analyses of, 350.

Parkhead Works, near Glasgow, 744.

Patent fuel, exported from Great Britain, 311.

Paulton Engine Pit, coal seams, 237.

Pawton Iron Mine, Cornwall, 705.

— Mine, Cornwall, production of iron ore, 708.

Pecten and Avicula beds, succession of, 373.

"Pecten Ironstone," Lincolnshire, 561.

Penydarren Iron Works, Glamorganshire, 616.

— Iron Works, pig iron made, 1829 to 1839, 619.

Pemberton Colliery, Lancashire, 79.

Perran Iron Lode, Cornwall, 708.

Peterborough, Abbey of, early supply of coal to, 1.

Pig iron:—

Cost of making at Arigna, Ireland, 783.

Exported since 1829, 839.

Exported and value in 1878, 1879, 1880, 839.

Pig iron manufacture, and coal used:—

Great Britain, 813.

Great Britain, 1872, 817.

Great Britain, 1871 to 1880, 818.

Great Britain, 1880, 820.

Great Britain, average used in 1880, 820.

Pig iron manufacture:—

Cleveland (N. R. of Yorkshire), 392.

Cumberland, 428.

Derbyshire, 469.

Derbyshire, in the years 1823 and 1830, 472.

Durham and Northumberland, 380.

Forest of Dean, 656.

Ireland, 781.

Lancashire, 448.

Lincolnshire, 570.

Northamptonshire, 552.

Nottinghamshire, 469.

Scotland, 726.

Shropshire, 487.

Somersetshire, 671.

Staffordshire, North, 505.

Staffordshire, South, 521.

Pig iron manufacture (*continued*) :—

- Staffordshire, South, 1796, 523.
- Staffordshire, South, 1806, 524.
- Staffordshire, South, 1823—1830, 525.
- Wales, North, 578.
- Wales, South, 604.
- Wiltshire, 683.
- Yorkshire, North Riding, 392.
- Yorkshire, West Riding, 352.
- Pig iron, production of :—**
 - Brecknockshire, 1796, 608.
 - Cleveland, 395.
 - Cumberland, 432.
 - Denbighshire, 578.
 - Derbyshire, 1806, 471.
 - Derbyshire since 1855, 473.
 - Durham in 1847, 337.
 - Durham since 1856, 338.
 - Flintshire, 581.
 - Forest of Dean, 660.
 - Glamorganshire, 621.
 - Great Britain :—**
 - 1740, 829.
 - 1788, 830.
 - 1796, 831.
 - 1806, 834.
 - 1823—1830, 834.
 - 1839, 623.
 - 1840, 836.
 - 1843 and 1847, 836.
 - 1852, 837.
 - Since 1854, 838.
 - Ireland, 1857, 784.
 - Lancashire, 1860 to 1871, 450.
 - Lincolnshire, 572.
 - Monmouthshire, 1796, 608.
 - Northumberland in 1847, 336.
 - Northumberland since 1856, 338.
 - Scotland, 1788, 729.
 - 1796, 730.
 - 1806, 732.
 - 1823—1830, 734.
 - 1843, 736.
 - 1848, 737.
 - since 1850, 739.
 - Shropshire, 1740, 1788, 488.
 - 1796, 1806, 489.
 - 1823—1830, 491.
 - since 1855, 493.
 - Staffordshire, North, 1848, 506.
 - North, since 1854, 507.
 - South, 1740, 1788, 522.
 - 1796, 523.
 - 1806, 524.
 - 1823—1830, 525.
 - since 1840, 527.
 - Wales, North, 1796, 578.
 - since 1855, 581.
 - Yorkshire, West Riding, 1740, 350.
 - West Riding, 1788—1796, 356.
 - West Riding, 1806, 356.

Pig iron, production of (*continued*) :—

- Yorkshire, West Riding, 1823—1830, 357.
- West Riding, 1840, 363.
- West Riding, 1851 to 1880, 359.
- Pisolitic iron ore, Ireland, 761.
- Plate-iron, prices of, in Cleveland, 414.
- Plott's "History of Staffordshire," reference to, 157.
- Plymouth Ironworks, Glamorganshire, pig iron made, 1829 to 1839, 619.
- Population employed in coal mining :—**
 - Bristol, 246.
 - Cheshire, 96.
 - Cumberland, 65.
 - Derbyshire, 110.
 - Durham and Northumberland, 29.
 - Gloucestershire, 233.
 - Ireland, 291.
 - Lancashire, 85.
 - Leicestershire, 122.
 - Nottinghamshire, 117.
 - Scotland, 280.
 - Shropshire, 138.
 - Somersetshire, 245.
 - Wales, North, 183.
 - Wales, South, 221.
 - Warwickshire, 129.
 - Westmoreland, 67.
 - United Kingdom, 312.
- Population employed in coal and iron mining :—**
 - Staffordshire, North, 150.
 - Staffordshire, South, 167.
 - Wales, South, 220.
 - Yorkshire, 52.
- Population employed in iron mining :—**
 - Cleveland, 335.
 - Durham, 329.
 - Lancashire, 447.
- Portugal, imports of iron ore from, 792.**
 - , iron ore deposits of, 790.
- Prices of angle iron, Cleveland, 414.**
- Prices of coal and cost of production :—**
 - Bristol, 244.
 - Cumberland, 61.
 - Derbyshire, 109.
 - Dudley, 167.
 - Durham and Northumberland, 25.
 - Gloucestershire, 232.
 - Ireland, 293.
 - Lancashire, 88.
 - Scotland, 278.
 - Shropshire, 135.
 - Staffordshire, North, 148.
 - Staffordshire, South, 164.
 - Wales, South, 218.
 - Warwickshire, 129.
 - Yorkshire, 50.
- Prices of bar iron, Cleveland, 414.**
 - of finished iron, Staffordshire, South, 537.

Prices of iron ore :—

Barrow in 1849, 441.

Cleveland, 377.

Cornwall, 715.

Lancashire, 442.

Shropshire, 486.

Yorkshire, 352.

Prices of iron rails, Cleveland, 414.

— of malleable iron, Scotland, 747.

— of pig iron, Scotland, 741.

— of plate iron, Cleveland, 414.

— of steel rails, Cleveland, 414.

— of Seaborne coal in London Market since 1861, 26.

Privileges of miners, Forest of Dean, 225.

Production of anthracite, Bideford, Devon, 253.

— of anthracite pig iron, Wales, South, 625.

Production of coal :—

Bristol, 244.

Cheshire, 94.

Cumberland, 63.

Derbyshire, 103.

Durham and Northumberland, 15—19.

England, 296.

Forest of Dean, 227.

Gloucestershire, 227.

Great Britain, 294.

Ireland, 290.

Lancashire, 75.

Leicestershire, 120.

Monmouthshire Coal-field, 205.

Nottinghamshire, 115.

Scotland, 270.

— since 1854, 296.

Shropshire, 134.

Somersetshire, 241.

"Somerset and Bristol," Inspectors of Coal Mines Reports, 245.

Staffordshire, North, 145.

—, South, 157.

United Kingdom, 297.

Wales, North and South, 296.

—, North, 180.

Wales, South, Coal-field, 203—205.

Warwickshire, 127.

Yorkshire districts, 45.

— Coal-field, 43.

Production of iron ore :—

Antrim Iron Company's Mines, 777.

Buckinghamshire, 682.

Cornwall, 1880, 715.

Cumberland since 1858, 421.

Devonshire, 699.

Duchy and Peru, Cornwall, 713.

Durham, 327.

Flintshire, 576.

Forest of Dean, 649.

Gloucestershire, 651.

Hampshire, 682.

Production of iron ore (*continued*) :—

Ireland, 775.

Lancashire, 442.

Scotland, 725.

Somersetshire, 671.

Treamble, Cornwall, 713.

Trebisken and Mount, Cornwall, 713.

Production of ironstone :—

Cleveland district, 375.

Derbyshire, 468.

Flintshire, 576.

Ireland, 773.

Lincolnshire, 567.

Northamptonshire, 547.

Nottinghamshire, 478.

Oxfordshire, 679.

Scotland, 724.

Shropshire, 485.

Somersetshire, 670.

Staffordshire, North, 504.

Staffordshire, South, 520.

Wales, North, 576.

Wales, South, 599.

Warwickshire, 479.

Wiltshire, 675.

Puddlers' wages in Cleveland, 413.

Puddling furnaces and rolling mills in Great Britain since 1861, 843.

— process of, Staffordshire, South, 533.

Purple ore, analysis of, 828.

— produced from Extraction Works since 1871, 828.

RADSTOCK Coal series, 238.

Railway distribution of Cumberland coal, 64.

Railway distribution of coal, Scotland, 276.

— distribution of Yorkshire coal by Lancashire and Yorkshire Railway, 48.

— by Manchester, Sheffield, and Lincolnshire Railway, 47.

Ravenson, his experiments with coke, 522.

Regenerating gas furnaces, Siemens', list of in Great Britain, 847.

Renishaw Colliery, section of strata, 38.

"Resources of Cleveland Ironstone District," Barrow, Mr. G., Paper on, 387.

Resources and probable duration of Coal-fields :—

Bristol, 246.

Cheshire, 97.

Cumberland, 66.

Durham and Northumberland, 30.

Forest of Dean, 234.

Gloucestershire, 234.

Ireland, 290.

Lancashire, 90.

Leicestershire, 123.

Scotland, 281.

Resources and probable duration of Coal-fields (*continued*):—

- Shropshire, 139.
- Somersetshire, 246.
- Staffordshire, North, 151.
- South, 170.
- United Kingdom, 313.
- Wales, North, 186.
- South, 221.
- Warwickshire, 131.
- York, Derby, and Notts, 56.
- Restormel Iron Mine, Cornwall, 702.—
- Production of, 705.
- Rhynchonella Bed, North Lincolnshire, 561.
- Roanhead Mines, Cumberland, iron ore deposits, 436.
- Rock drills, Richards, Mr. W., sketch of, used in Cleveland, 383.
- Rolling iron, Cort's claims, account of, "Metallurgy of Iron and Steel," 495.
- Cort's system of, 494.
- Rolls, grooved, application of, by Payne, J., 495.
- Rosebridge Colliery, deep workings, Wigan, 75.
- Rosedale Abbey Estate, Yorkshire, 380.
- Abbey mines, "Dogger Bed," 367.
- Abbey mines, iron ore produced since 1861, 380.
- iron stone, "Percy, Dr., Metallurgy: Iron and Steel," 373.
- Russia, iron ore deposits, 801.
- imports and value of iron ores from, 801.

SAINT HELEN'S, Lancashire, Prices of coal, 89.

- Saltburn by the Sea (Cleveland), mines producing iron ore since 1872, 379.
- Sampson Shaft, Hanover, 77.
- Santon clay, Lincolnshire, used as a flux, 573.
- Saundersfoot coals, Anthracite, 193.
- Scotch pig iron consumed in foundries and iron works, 743.
- distribution of, coastwise and exported, 742.
- home consumption, 743.
- Scotland, Black Band ores, production of, 719.
- brown iron ores, 720.
- carboniferous series of, 255.
- Clay Band ores, production of, 726.
- "Scotland, Coal-fields of," 252.—"Geddes, Mr. J., Coal Com. Report," 282.
- coal produce per man, 280, 281.
- coal raised by collieries, 273.
- districts furnishing iron ore for smelting, 752.

Scotland, eastern coal districts, 271.

- eastern ports, coal carried from, 275.
- furnaces built and in blast, 739.
- iron industries of, 719.
- iron shipbuilding, 753.
- ironstone measures, 719.
- ironstone produced in each county, 725.
- ironstone, production of eastern districts, 725.
- ironstone, production of western districts, 725.
- ironstone used in blast furnaces—quantities, 752.
- iron works, list of, in 1880, 740.
- malleable iron works, 743.—Prices, 747.
- miners' wages, 280.
- western coal districts, 271.
- western ports, coal carried from 274.
- Section of strata, (*see* Strata, section of).
- Seend Iron Works, Wiltshire, 683.—Production of, 675.
- Shafts, Deep, Sampson Mine, Hanover, 77.
- Rosebridge Colliery, Wigan, 75.
- Adalbert, Bohemia, 77.
- Ashton Moss Colliery, Manchester, 75.
- Shelton Bar Iron Works, Staffordshire, North, 508.
- Shipley Colliery, Derbyshire, section of strata, 100.
- Shrewsbury Coal-field, 133.
- Shropshire, average consumption of coal: iron ore, 498.
- coal produced per man, 138.
- cost of getting coal, "Miner's Guide," Smith, Thomas, 135; Parton, Mr. T., 137.
- coal, distribution of, 134.
- Coal-field, population employed, 138.
- furnaces built and in blast, 493.
- iron industries, 480.
- ironstone measures, description of, "Iron Ores of Great Britain," 480.
- "Shropshire Ironstone Measures," thickness and yield; "Miner's Guide," 486.
- ironstone measures, yield per acre, 487.
- list of iron works in 1880, 494.
- mills and forges in 1880, 496.
- Siemens, Dr. C. W., iron making, direct process, 553.
- steel, Great Britain, production of in, 846.
- Steel Works in Great Britain, 845.
- "Silkstone Hards Coal" analysis: of Carr, Mr. W., Halifax, 48.
- Silkstone Coal, Yorkshire, 348.

- Silverdale Iron Works, Staffordshire, North, 506.
 "Sinclair, Sir John," account of Devon Ironworks, Scotland, 730.
 Slag bottle manufacture, Northamptonshire, 555.
 Slag-heaps of ancient furnaces, Northumberland, 325.
 Slievardagh Coal-field, Ireland, 289.
 Slitting-mills first used at Gateshead Ironworks in 1772, 340.
 Smallacombe iron ore deposits, Devon, 690.
 — Iron Mines, production of, 691.
 Smeaton's blowing machinery, 727.
 Smith, Dr. Angus, "Manufacture of Coke," 202.
 Somercotes Ironworks, Derbyshire, 470.
 "Somerset East, and Bristol Coal-field," Woodward, Mr. H. R., 239.
 Somersetshire Coal-field, 235.
 — furnaces built and in blast, 660.
 — iron industries, 665.
 — iron mines producing ore in 1880, 671.
 — pig-iron manufacture, 671.
 — pig-iron production, 660.
 — production of iron ore, 669.
 Sommorrostro iron mines, Spain, 786.
 Soudley Ironworks, Gloucestershire, iron ore used in, 664.
 South Staffordshire (*see* Staffordshire, South).
 South Wales (*see* Wales, South).
 — Coal-field, 188.
 Spain, analyses of the iron ores of, 787.
 — imports of iron ore from, 345.
 — value of imports of, 788.
 — ports receiving iron ore from, 790.
 Spathose iron ore, Brendon Hills, 668.
 — Frank Mills, &c., 693.
 — iron ore, production of, Weardale district, Durham, 327.
 Springs for railway purposes, first made at Newburn, 332.
 Staffordshire, North, Coal-field, 140.
 "Staffordshire, North, Coal-field," Coal Commission Report, 161.
 Staffordshire, North, coal produce per man, 150.
 — North, coal seams, yield per acre—"Miner's Guide," 149.
 "Staffordshire, N., Coal-field and Ironstone Measures," Homer, Mr., 145.
 — North, coal and iron ore used in manufacture, 509.
 — North, coal used in ironworks and potteries, 147.
 — North, coal used in metallurgical operations in 1796, 510.
 — North, coal used in pig iron manufacture in 1854, 510.
 Staffordshire, North, furnaces, charges of materials, 512.
 — North, iron industries, 499.
 — North, iron ores of, "Iron Ores of Great Britain," 501.
 — ironstone carried by canal and railway, 505.
 — North, ironstone working, 144.
 — North, iron-works, list of in 1880, 508.
 — North, list of mills and forges in 1880, 509.
 — North, system of coal working, 141.
 — Railway, North, iron ore carried by, 505.
 "Staffordshire, South, Coals," analyses of Percy, Dr., 156.
 — South, blast furnaces, 1880, 531.
 — South, calcination of iron-stone, 530.
 — South, Coal-field, 153.
 — South, coal produce per man, 168.
 — South, cost of getting coals, &c., "Miner's Guide," 165.
 — South, distribution of coal, 161.
 "Staffordshire, South: Coal-field: Memoir of," Jukes, Professor J. B., 153.
 — South, ironstone measures, 513.
 — South, ironstone and yield of metallic iron, 520.
 — South, malleable iron works, 1880, 534.
 — South, "Mine Drainage Act," area of coal-field included under, 160.
 "Staffordshire, South, Miners' Wages," Smith, Mr. Fisher, 166.
 Staffordshire, South, pig-iron manufacture, 1796, 523; 1806, 524; 1823, 525; 1840, 527.
 "Staffordshire, South," population employed, 168.
 — South, production of ironstone, 520.
 — South, "Ten Years' Coal Mining," *Colliery Guardian*, 166.
 — South, Works erected between 1823 and 1830, 526.
 Stanhope Furnace, Durham, erected 1844, 334.
 Stanton District, Derbyshire, analyses of ironstones, 466.
 "Statistics and Calculations," Salt, Samuel, coal production, 1816, 295.
 Staveley district, Derbyshire, analyses of ironstones, 467.
 Steel, crucible, production in Great Britain, since 1873, 847.
 — rails, prices of, in Cleveland, 414.
 — Works of the Barrow Hematite Steel Co., 451.
 — Works, Moss Bay Company, Cumberland, 431.
 — Works, West Cumberland, 431.

Stiddle Moor, &c., Ironstone measures, 325.
 "Stockport, Geology of," Hull, Professor, 93.

Stockton and Darlington Railway opened, 21.

Stoves, Cowper, Mr. E. A., description of, 399.

— Whitwell, account of, 400.

Strata, section of :—

Anglesea Coal-field, 172

Arigna Colliery, 284.

Barnsley district, 37.

Bedworth Colliery, Warwickshire, 125.

Bredbury Collieries, Cheshire, 92.

Bristol Coal-field, 235.

Castlecoimer coal basin, 288.

Cavan, Ireland, 775.

Cefn Cwse, Wales, South, 589.

Cinderhill, Notts, 111.

Clyde Valley, 258.

Coalbrookdale, Shropshire, 132.

Denbighshire Coal-field, 173.

Derbyshire, 99.

Donnington Wood, Shropshire, 460.

Dowlais, South Wales, 586.

Dronfield, Derbyshire, 463.

Dungannon Coal-field, Ireland, 286.

East Lothian, Scotland, 264.

Emley Moor, Yorkshire, 36.

Fawler, Oxfordshire, 678.

Flintshire Coal-field, 173.

Forest of Dean, 223.

Leeds, Yorkshire, 35.

Lincolnshire, 560.

Moir district, 118.

Newcastle-upon-Tyne, 4.

Northamptonshire, 538.

Old Sauchie, Clackmannanshire, 266.

Renishaw Colliery, 38.

Shipley, Derbyshire, 100.

Staffordshire, North, Coal-field, 141.

— South, 154.

Upleatham, 366.

Wales, South, 586.

Whitehaven, 59.

Workington, 59.

Yniscedwyn, 587.

Ystalyfera, 587.

Sturtevant, Simon, his experiments with coke, 522.

Sutherland, Mr. Alexander, on "Irish Hill and Straid Mines," Antrim, 770.

Swansea, coal exported from, 214.

— Docks, 212.

Sweden iron ore deposits, 799.

— ore imported and value, 800.

TAFF VALE Railway, distribution of coal by, 303.

"Tap Cinder," Staffordshire, South, 530.

Tax on coal, 2.

Tealby, Lincolnshire, ironstone deposits, 563.

Ten Yard, or Thick coal, 154.

— used in iron manufacture, 528.

— yield per acre, 161.

Thick coal used in iron manufacture, 528.

Thomas-Gilchrist process of steel manufacture, 407.

Tichborne, Mr., "Iron Ore Deposits, Wicklow," 773.

Tin plates exported since 1873, 854.

— plates exported, 1878 to 1880, 855.

— plate manufacture, 848.

—terne and black plate, production of, 849.

— plate works :—

— Caermarthenshire, 852.

— Cumberland, 853.

— Flintshire, 853.

— Glamorganshire, 851.

— Great Britain, 850.

— Gloucestershire, 853.

— Monmouthshire, 852.

— Scotland, 853.

— Staffordshire, 853.

Tonnage of iron vessels launched on the Clyde, 754.

Torbane Hill mineral, 258.

— analysis of, 179.

"Tour in Wales," Pennant, Thomas, 179.

Tourget, M. F., manufacture of coke, Besseges process, 202.

Towcester Ironworks : iron made by direct process, 553.

Tredegar Ironworks : pig iron made, 612.

Tregorne Iron Lode, Cornwall, 713.

Trent and Mersey Navigation : distribution of iron ore, 506.

Turkey in Asia, imports of iron ore from, 802.

Tuyere, water, invention of, by Condie, 733.

"Tyne, Wear & Tees Manufacture of Iron," Bell, Mr. I. Lowthian, 375.

Tyrone Coal-field, 285.

— ironstone measures of, 757.

UNITED KINGDOM, areas of coal-fields, 294.

— coal, cinders, and culm exported, 307.

— Coal-fields, resources, and probable duration of, 313.

— coal produce per man, 312.

Upleatham, ironstone series of, "Tate and Blake," 366.

- VENTILATION**, Guibal Fan, Pemberton Colliery, 79.
 — Schiele Fan, 209.
 Vivian, Mr. Hussey—"Wales, South, Coal-field," Coal Commission Report, 221.
- "WALES, North, Agricultural Survey,"** Davies, Rev. W., 180.
 Wales, North, Coal-field, 172.
 "Wales, North, Coal-field," Dickinson, Mr. J., on, 187.
 "Wales, North," coal raised, Hall, Mr. Henry, 186.
 Wales, North, coal produce per man, 185.
 — iron industries, 574.
 — production of iron ore, 576.
 "Wales, South, Coal-field," Brown, Mr. T. F., 182.
 "Wales, South, Coal-field," Clarke, Mr. G. T., Coal Commission Report, 221.
 Wales, South, area of coal-field, 188.
 "Wales, South, Coal-field," Coal Commission Report, 203, 204.
 Wales, South, coal produce per man, 221.
 — coal used in pig iron manufacture, 636.
 — (coal and iron districts), Central Anticlinal District, 587.
 — eastern outcrop, ironstone measures, 584.
 — north-eastern outcrop, ironstone measures, 585.
 — southern outcrop, ironstone measures, 588.
 — western or Anthracite District, 587.
 — coal exported and duty received, 215.
 — furnaces and pig iron made, 1839 to 1852, 619.
 "Wales, South, Industrial Capacities of," Symons, Mr. J., 211.
 Wales, South, iron industries, 584.
 Wales, South, iron ore deposits :—
 Bute hematite, 601.
 Garth hematite, 601.
 Llantrissant hematite, 601.
 Mwyndy hematite, 601.
 Pentyrch hematite, 601.
 Wales, South, ironstone measures :—
 Blaenavon, 585.
 Coalbrook Vale, 585.
 Llynvi and Cwm Avon, 587.
 Wales, South, ironstones and their yield of metallic iron, 598.
 iron ore mines, 602.
 — used in pig iron manufacture, 640.
 iron works, when erected, 607.
 — in the year 1839, 618.
 — in 1848, 624.
 pig iron made, 1823—1830, 617.
 pig iron, total production, 626.
 production of ironstone, 600.
- Walker Iron Works, Northumberland, commenced manufacture of bar iron, 334.
 Wallsend coal, account of, 7.
 Warsash Charcoal Furnaces, Hampshire, 686.
 "Warwick, Agricultural View of," by Widee, John, 127.
 Warwickshire, analysis of ironstone, 479.
 "Warwickshire Coal-field," 125.
 "Warwickshire Coal-field," Howell, Mr. H. H., on, 126.
 Warwickshire coal, distribution of, 128.
 — produce per man, 127.
 Warwickshire, cost of getting coal, "Miner's Guide," Smith, Thos., 129.
 Warwickshire, "Population employed in Coal Mining," 130.
 Warwickshire, production of ironstone, 479.
 Waste gases in blast furnaces, their utilization, in Ystalyfera Iron Works, 635.
 Watney's anthracite, analysis of, Playfair, Dr., 193.
 Westbury iron ore, Wiltshire, production of, 675.
 Westminster Bridge lighted with gas, 9.
 Westmoreland Coal-field, 67.
 — produce of coal per man, 67.
 Whitehaven, iron ore shipped from, 423.
 — section of strata, 59.
 Whitehill Iron Works, near Chester-le-Street, 331.
 Whitwell Stoves, account of, 400.
 Wigan canal, analyses of, 179.
 — Coal and Iron Co.'s Works, 449.
 "Wigan Coal and Iron Co.," Hewlett, Mr. Alfred, on coal trade, 89.
 Wigan district, coals worked in, 69.
 Wilsonstown Iron Works, Scotland, 728.
 Wiltshire furnaces built and in blast, 660.
 — iron industries, 673.
 — iron ore, production of, 675.
 — production of pig iron, 685.
 Wingerworth Iron Works, Derbyshire, 472.
 Witton Park Iron Works, Auckland, Durham, 335.
 Workington Colliery, Cumberland, 60.
 — section of strata, 59.
 Wylam Wagon Way, first plain plate railway laid, 332.
- YNISCEDWYN** ironstone measures, section of strata, 587.
 Ynysawdre Co. coke manufacture by, 201.
 Yorkshire coal carried by—
 Manchester, Sheffield & Lincolnshire Railway, 47.
 Midland Railway, 46.
 North-Eastern Railway, 47.

- Yorkshire, coal sent coastwise and exported, 49.
 — Coal-field, 32.
 "Yorkshire Coal-field," Green, Prof., on, 34.
 Yorkshire Coal-field, persons employed and minerals raised, 54.
 — produce of coal per man, 52.
 — Coal-field, production of, 44.
 Yorkshire, "Coals suited to the Steam Navy," De la Beche and Playfair, 39.
 "Yorkshire Lias, The," Tate and Blake, 366.
 "Yorkshire, Wages of Coal Miners," *Collicry Guardian* on, 52.
- Yorkshire, North Riding, iron industries, 365.
 — North Riding, works in operation in 1855, 393.
 — make of pig iron, 395.
 — production of iron ore, 377.
 — West Riding, ironstone measures, 347.
 — West Riding, iron works, 1851, 353.
 — make of pig iron, 359.
 — production of iron ore, 351.
 — Works in operation in 1880, 360.
 Ystalyfera ironstone measures, section of strata, 587.
 Ystradylfodwg coal, parish returns of, 206.

THE END.

7, STATIONERS' HALL COURT, LONDON, E.C.
January, 1888.

A
CATALOGUE OF BOOKS
INCLUDING MANY NEW AND STANDARD WORKS IN
ENGINEERING, MECHANICS, ARCHITECTURE,
NATURAL AND APPLIED SCIENCE,
INDUSTRIAL ARTS, TRADE & COMMERCE, AGRICULTURE,
GARDENING, LAND MANAGEMENT, LAW, &c.
PUBLISHED BY
CROSBY LOCKWOOD & SON.

MECHANICS, MECHANICAL ENGINEERING, etc.

New Manual for Practical Engineers.

THE PRACTICAL ENGINEER'S HAND-BOOK, Comprising a Treatise on Modern Engines and Boilers, Marine, Locomotive, and Stationary. And containing a large collection of Rules and Practical Data relating to recent Practice in Designing and Constructing all kinds of Engines, Boilers, and other Engineering work. The whole constituting a comprehensive Key to the Board of Trade and other Examinations for Certificates of Competency in Modern Mechanical Engineering. By **WALTER S. HUTTON**, Civil and Mechanical Engineer, Author of "The Works' Manager's Hand-book for Engineers," &c. With upwards of 370 Illustrations. Second Edition, Revised with Additions. Medium 8vo., nearly 500 pp., price 18s. Strongly bound. [Just published.]

This work is designed as a companion to the Author's "WORKS' MANAGER'S HAND-BOOK." It possesses many new and original features, and contains, like its predecessor, a quantity of matter not originally intended for publication, but collected by the Author for his own use in the construction of a great variety of modern engineering work.

The information is given in a condensed and concise form, and is illustrated by upwards of 370 Woodcuts; and comprises a quantity of tabulated matter of great value to all engaged in designing, constructing, or estimating for ENGINES, BOILERS, and OTHER ENGINEERING WORK.

*** * * OPINIONS OF THE PRESS.**

"We have kept it at hand for several weeks, referring to it as occasion arose, and we have not on a single occasion consulted its pages without finding the information of which we were in quest." *Athenaeum*.

"A thoroughly good practical handbook, which no engineer can go through without learning something that will be of service to him."—*Marine Engineer*.

"An excellent book of reference for engineers, and a valuable text-book for students of engineering."—*Scottsman*.

"This valuable manual embodies the results and experience of the leading authorities on mechanical engineering."—*Building News*.

"The author has collected together a surprising quantity of rules and practical data, and has shown much judgment in the selections he has made. . . . There is no doubt that this book is one of the most useful of its kind published, and will be a very popular compendium."—*Engineer*.

"A mass of information, set down in simple language, and in such a form that it can be easily referred to at any time. The matter is uniformly good and well chosen, and is greatly elucidated by the illustrations. The book will find its way on to most engineers' shelves, where it will rank as one of the most useful books of reference."—*Practical Engineer*.

"Full of useful information, and should be found on the office shelf of all practical engineers."—*English Mechanic*.

Handbook for Works' Managers.

THE WORKS' MANAGER'S HANDBOOK OF MODERN RULES, TABLES, AND DATA. For Engineers, Millwrights, and Boiler Makers; Tool Makers, Machinists, and Metal Workers; Iron and Brass Founders, &c. By W. S. HUTTON, Civil and Mechanical Engineer, Author of "The Practical Engineer's Handbook." Third Edition, carefully Revised, with Additions. In One handsome Volume, medium 8vo, price 15s. strongly bound.

"The Author having compiled Rules and Data for his own use in a great variety of modern engineering work, and having found his notes extremely useful, decided to publish them—revised to date—believing that a practical work, suited to the DAILY REQUIREMENTS of MODERN ENGINEERS, would be favourably received."

In the Third Edition, the following among other additions have been made, viz. :—Rules for the Proportions of Riveted Joints in Soft Steel Plates, the Results of Experiments by PROFESSOR KENNEDY for the Institution of Mechanical Engineers—Rules for the Proportions of Turbines—Rules for the Strength of Hollow Shafts of Whitworth's Compressed Steel, &c.

* * OPINIONS OF THE PRESS.

"The author treats every subject from the point of view of one who has collected workshop notes for application in workshop practice, rather than from the theoretical or literary aspect. The volume contains a great deal of that kind of information which is gained only by practical experience, and is seldom written in books."—*Engineer*.

"The volume is an exceedingly useful one, brimful with engineers' notes, memoranda, and rules, and well worthy of being on every mechanical engineer's bookshelf."—*Mechanical World*.

"The information is precisely that likely to be required in practice. . . . The work forms a desirable addition to the library not only of the works manager, but of anyone connected with general engineering."—*Mining Journal*.

"A formidable mass of facts and figures, readily accessible through an elaborate index. . . . Such a volume will be found absolutely necessary as a book of reference in all sorts of 'works' connected with the metal trades."—*Ryland's Iron Trades Circular*.

"Brimful of useful information, stated in a concise form, Mr. Hutton's books have met a pressing want among engineers. The book must prove extremely useful to every practical man possessing a copy."—*Practical Engineer*.

"The Modernised Templeton."

THE PRACTICAL MECHANIC'S WORKSHOP COMPANION.

Comprising a great variety of the most useful Rules and Formulæ in Mechanical Science, with numerous Tables of Practical Data and Calculated Results for Facilitating Mechanical Operations. By WILLIAM TEMPLETON, Author of "The Engineer's Practical Assistant," &c. &c. Fifteenth Edition, Revised, Modernised, and considerably Enlarged by WALTER S. HUTTON, C.E., Author of "The Works' Manager's Handbook," "The Practical Engineer's Handbook," &c. Fcap. 8vo, nearly 500 pp., with 8 Plates and upwards of 250 Illustrative Diagrams, 6s., strongly bound for workshop or pocket wear and tear.

TEMPLETON'S "MECHANIC'S WORKSHOP COMPANION" has been for more than a quarter of a century deservedly popular; and, as the well-worn and thumb-marked vade mecum of several generations of intelligent and aspiring workmen, it has had the reputation of having been the means of raising many of them in their position in life.

In consequence of the lapse of time since the Author's death, and the great advances in Mechanical Science, the Publishers have thought it advisable to have it entirely Reconstructed and Modernised; and in its present greatly Enlarged and Improved form, they are sure that it will commend itself to the English workmen of the present day all the world over, and become, like its predecessors, their indispensable friend and referee.

A smaller type having been adopted, and the page increased in size, while the number of pages has advanced from about 330 to nearly 500, the book practically contains double the amount of matter that was comprised in the original work.

* * OPINIONS OF THE PRESS.

"In its modernised form Hutton's 'Templeton' should have a wide sale, for it contains much valuable information which the mechanic will often find of use, and not a few tables and notes which he might look for in vain in other works. This modernised edition will be appreciated by all who have learned to value the original editions of 'Templeton.'"—*English Mechanic*.

"It has met with great success in the engineering workshop, as we can testify; and there are a great many men who, in a great measure, owe their rise in life to this little book."—*Building News*.

"This familiar text-book—well known to all mechanics and engineers—is of essential service to the every-day requirements of engineers, millwrights, and the various trades connected with engineering and building. The new modernised edition is worth its weight in gold."—*Building News*. (Second Notice.)

"This well-known and largely-used book contains information, brought up to date, of the sort so useful to the foreman and draughtsman. So much fresh information has been introduced as to constitute it practically a new book. It will be largely used in the office and workshop."—*Mechanical World*.

"The publishers wisely entrusted the task of revision of this popular, valuable, and useful book to Mr. Hutton, than whom a more competent man they could not have found."—*Iron*.

Stone-working Machinery.

STONE-WORKING MACHINERY, and the Rapid and Economical Conversion of Stone. With Hints on the Arrangement and Management of Stone Works. By M. POWIS BALE, M.I.M.E., A.M.I.C.E. With numerous Illustrations. Large crown 8vo, 9s. cloth.

"The book should be in the hands of every mason or student of stonework."—*Colliery Guardian*.

"It is in every sense of the word a standard work upon a subject which the author is fully competent to deal exhaustively with."—*Builder's Weekly Reporter*.

"A capital handbook for all who manipulate stone for building or ornamental purposes."—*Machinery Market*.

Turning.

LATHE-WORK: A Practical Treatise on the Tools, Appliances, and Processes employed in the Art of Turning. By PAUL N. HASLUCK. Third Edition, Revised and Enlarged. Crown 8vo, 5s. cloth.

"Written by a man who knows not only how work ought to be done, but who also knows how to do it, and how to convey his knowledge to others. To all turners this book would be valuable."—*Engineering*.

"We can safely recommend the work to young engineers. To the amateur it will simply be invaluable. To the student it will convey a great deal of useful information."—*Engineer*.

"A compact, succinct, and handy guide to lathe-work did not exist in our language until Mr. Hasluck, by the publication of this treatise, gave the turner a true *vade mecum*."—*House Decorator*.

Screw-Cutting.

SCREW THREADS: And Methods of Producing Them. With Numerous Tables and complete directions for using Screw-Cutting Lathes. By PAUL N. HASLUCK, Author of "Lathe-Work," "The Metal Turner's Handbook," &c. Waistcoat-pocket size, price 1s. [Just published.]

"Full of useful information, hints, and practical criticism. Taps, dies, and screwing-tools generally are illustrated and their action described."—*Mechanical World*.

"It is a complete compendium of all the details of the screw-cutting lathe; in fact, a *multum in parvo* on all the subjects it treats upon."—*Carpenter & Builder*.

Engineer's and Machinist's Assistant.

THE ENGINEER'S, MILLWRIGHT'S, AND MACHINIST'S PRACTICAL ASSISTANT. A collection of Useful Tables, Rules, and Data. By WILLIAM TEMPLETON. Seventh Edition, with Additions. 18mo, 2s. 6d. cloth.

"Templeton's handbook occupies a foremost place among books of this kind. A more suitable present to an apprentice to any of the mechanical trades could not possibly be made."—*Building News*.

"A deservedly appreciated work, which should be in the 'drawer' of every mechanic."—*English Mechanic*.

Iron and Steel.

"IRON AND STEEL": A Work for the Forge, Foundry, Factory, and Office. Containing ready, useful, and trustworthy Information for Ironmasters and their Stock-takers; Managers of Bar, Rail, Plate, and Sheet Rolling Mills; Iron and Metal Founders; Iron Ship and Bridge Builders; Mechanical, Mining, and Consulting Engineers; Architects, Contractors, Builders, and Professional Draughtsmen. By CHARLES HOARE, Author of "The Slide Rule," &c. Eighth Edition, Revised throughout and considerably Enlarged. With folding Scales of "Foreign Measures compared with the English Foot," and "Fixed Scales of Squares, Cubes, and Roots, Areas, Decimal Equivalents, &c." Oblong 32mo, leather, elastic-band, 6s.

"For comprehensiveness the book has not its equal."—*Iron*.

"One of the best of the pocket books, and a useful companion in other branches of work than iron and steel."—*English Mechanic*.

"We cordially recommend this book to those engaged in considering the details of all kinds of iron and steel works."—*Naval Science*.

High-Pressure Steam Engines.

THE HIGH-PRESSURE STEAM-ENGINE; an Exposition of its Comparative Merits, and an Essay towards an Improved System of Construction. By DR. ERNST ALBAN. Translated from the German, with Notes, by DR. POLE, M. Inst. C.E. &c. With 28 Plates. 8vo, 16s. 6d. cloth.

"Goes thoroughly into the examination of the high-pressure engine, the boiler, and its appendages, and deserves a place in every scientific library."—*Siam Shipping Chronicle*.

Engineering Construction.

PATTERN-MAKING: A Practical Treatise, embracing the Main Types of Engineering Construction and including Gearing, both Hand and Machine-made, Engine Work, Sheaves and Pulleys, Pipes and Columns, Screws, Machine Parts, Pumps and Cocks, the Moulding of Patterns in Loam and Greensand, &c.; together with the methods of Estimating the weight of Castings; to which is added an Appendix of Tables for Workshop Reference. By A FOREMAN PATTERN-MAKER. With upwards of 370 Illustrations. Crown 8vo, 7s. 6d. cloth.

"A well-written technical guide, evidently written by a man who understands and has practised what he has written about. . . . We cordially recommend it to engineering students, young journeymen, and others desirous of being initiated into the mysteries of pattern-making."—*Builder*.

"The trade of the pattern maker is now an important specialty in all branches of engineering and construction. . . . We can confidently recommend this comprehensive treatise."—*Building News*.

"Likely to prove a welcome guide to many workmen, especially to draughtsmen who have lacked a training in the shops, pupils pursuing their practical studies in our factories, and to employers and managers in engineering works."—*Hardware Trade Journal*.

"More than 370 illustrations help to explain the text, which is, however, always clear and explicit, thus rendering the work an excellent *vide mecum* for the apprentice who desires to become master of his trade."—*English Mechanic*.

Dictionary of Mechanical Engineering Terms.

LOCKWOOD'S DICTIONARY OF TERMS USED IN THE PRACTICE OF MECHANICAL ENGINEERING, embracing those current in the Drawing Office, Pattern Shop, Foundry, Fitting, Turning, Smiths' and Boiler Shops, &c. &c. Comprising upwards of 6,000 Definitions. Edited by A FOREMAN PATTERN-MAKER, Author of "Pattern Making." Crown 8vo, 7s. 6d. cloth. [Just published.]

"Just the sort of handy dictionary required by the various trades engaged in mechanical engineering. The practical engineering pupil will find the book of great value in his studies, and every foreman engineer and mechanic should have a copy."—*Building News*.

"After a careful examination of the book, and trying all manner of words, we think that the engineer will here find all he is likely to require. It will be largely used."—*Practical Engineer*.

"This admirable dictionary, although primarily intended for the use of draughtsmen and other technical craftsmen, is of much larger value as a book of reference, and will find a ready welcome in many libraries."—*Glasgow Herald*.

Smith's Tables for Mechanics, &c.

TABLES, MEMORANDA, AND CALCULATED RESULTS, FOR MECHANICS, ENGINEERS, ARCHITECTS, BUILDERS, &c. Selected and Arranged by FRANCIS SMITH. Fourth Edition, Revised and Enlarged, 250 pp. Waistcoat-pocket size, 1s. 6d. limp leather. [Just published.]

"It would, perhaps, be as difficult to make a small pocket-book selection of notes and formulae to suit ALL engineers as it would be to make a universal medicine; but Mr. Smith's waistcoat-pocket collection may be looked upon as a successful attempt."—*Engineer*.

"The best example we have ever seen of 240 pages of useful matter packed into the dimensions of a card-case."—*Building News*. "A veritable pocket treasury of knowledge."—*Iron*.

Steam Boilers.

A TREATISE ON STEAM BOILERS: Their Strength, Construction, and Economical Working. By R. WILSON, C.E. Fifth Edition. 12mo, 6s. cloth.

"The best treatise that has ever been published on steam boilers."—*Engineer*.

"The author shows himself perfect master of his subject, and we heartily recommend all employing steam power to possess themselves of the work."—*Ryland's Iron Trade Circular*.

Boiler Chimneys.

BOILER AND FACTORY CHIMNEYS: Their Draught-Power and Stability. With a Chapter on *Lightning Conductors*. By ROBERT WILSON, A.I.C.E., Author of "A Treatise on Steam Boilers," &c. Second Edition. Crown 8vo, 3s. 6d. cloth.

Boiler Making.

THE BOILER-MAKER'S READY RECKONER. With Examples of Practical Geometry and Templating, for the Use of Platers, Smiths, and Riveters. By JOHN COURTNEY, Edited by D. K. CLARK, M.I.C.E. Second Edition, revised with additions, 12mo, 5s. half-bound.

"A most useful work. . . . No workman or apprentice should be without this book."—*Iron Trade Circular*.

"A reliable guide to the working boiler maker."—*Iron*.

"Boiler makers will readily recognise the value of this volume. . . . The tables are clearly printed, and so arranged that they can be referred to with the greatest facility, so that it cannot be doubted that they will be generally appreciated and much used."—*Mining Journal*.

Steam Engine.

TEXT-BOOK ON THE STEAM ENGINE. With a Supplement on Gas Engines. By T. M. GOODEVE, M.A., Barrister-at-Law, Author of "The Elements of Mechanism," &c. Ninth Edition, Enlarged. With numerous Illustrations. Crown 8vo, 6s. cloth. [Just published.]

"Professor Goodeve has given us a treatise on the steam engine, which will bear comparison with anything written by Huxley or Maxwell, and we can award it no higher praise."—*Engineer*.

"Professor Goodeve's book is ably and clearly written. It is a sound work."—*Athenaeum*.

"Mr. Goodeve's text-book is a work of which every young engineer should possess himself."—*Mining Journal*.

"Essentially practical in its aim. The manner of exposition leaves nothing to be desired."—*Scottsman*.

"A valuable *vade mecum* for the student of engineering, and should be in the possession of every scientific reader."—*Colliery Guardian*.

Gas Engines.

ON GAS ENGINES. Being a reprint, with some additions, of the Supplement to the *Text-book on the Steam Engine*, by T. M. GOODEVE, M.A. Crown 8vo, 2s. 6d. cloth. [Just published.]

"Like all Mr. Goodeve's writings, the present is no exception in point of general excellence. It is a valuable little volume."—*Mechanical World*.

"This little book will be useful to those who desire to understand how the gas-engine works."—*English Mechanic*.

Steam.

THE SAFE USE OF STEAM. Containing Rules for Unprofessional Steam-users. By an ENGINEER. Fifth Edition. Sewed, 6d.

"If steam-users would but learn this little book by heart, boiler explosions would become sensations by their rarity."—*English Mechanic*.

Coal and Speed Tables.

A POCKET BOOK OF COAL AND SPEED TABLES, for Engineers and Steam-users. By NELSON FOLEY, Author of "Boiler Construction." Pocket-size, 3s. 6d. cloth; 4s. leather.

"This is a very useful book, containing very useful tables. The results given are well chosen, and the volume contains evidence that the author really understands his subject. We can recommend the work with pleasure."—*Mechanical World*.

"These tables are designed to meet the requirements of every-day use; they are of sufficient scope for most practical purposes, and may be commended to engineers and users of steam."—*Iron*.

"This pocket-book well merits the attention of the practical engineer. Mr. Foley has compiled a very useful set of tables, the information contained in which is frequently required by engineers, coal consumers, and users of steam."—*Iron and Coal Trades Review*.

Fire Engineering.

FIRES, FIRE-ENGINES, AND FIRE-BRIGADES. With a History of Fire-Engines, their Construction, Use, and Management; Remarks on Fire-Proof Buildings, and the Preservation of Life from Fire; Statistics of the Fire Appliances in English Towns; Foreign Fire Systems; Hints on Fire-Brigades, &c. &c. By CHARLES F. T. YOUNG, C.E. With numerous Illustrations, 544 pp., demy 8vo, £1 4s. cloth.

"To such of our readers as are interested in the subject of fires and fire apparatus, we can most heartily commend this book. It is really the only English work we now have upon the subject."—*Engineering*.

"It displays much evidence of careful research, and Mr. Young has put his facts neatly together. It is evident enough that his acquaintance with the practical details of the construction of steam fire engines, old and new, and the conditions with which it is necessary they should comply, is accurate and full."—*Engineer*.

Gas Lighting.

COMMON SENSE FOR GAS-USERS: A Catechism of Gas-Lighting for Household, Gasfitters, Millowners, Architects, Engineers, &c. &c. By ROBERT WILSON, C.E., Author of "A Treatise on Steam Boilers." Second Edition. With Folding Plates and Wood Engravings. Crown 8vo, price 1s. in wrapper.

"All gas-users will decidedly benefit both in pocket and comfort, if they will avail themselves of Mr. Wilson's counsels."—*Engineering*.

THE POPULAR WORKS OF MICHAEL REYNOLDS

("THE ENGINE DRIVER'S FRIEND").

Locomotive-Engine Driving.

LOCOMOTIVE-ENGINE DRIVING: A Practical Manual for Engineers in charge of Locomotive Engines. By MICHAEL REYNOLDS, Member of the Society of Engineers, formerly Locomotive Inspector, L. B. and S. C. R. Seventh Edition. Including a KEY TO THE LOCOMOTIVE ENGINE. With Illustrations and Portrait of Author. Crown 8vo, 4s. 6d. cloth.

"Mr. Reynolds has supplied a want, and has supplied it well. We can confidently recommend the book not only to the practical driver, but to everyone who takes an interest in the performance of locomotive engines."—*The Engineer*.

"Mr. Reynolds has opened a new chapter in the literature of the day. This admirable practical treatise, of the practical utility of which we have to speak in terms of warm commendation."—*Athenæum*.

"Evidently the work of one who knows his subject thoroughly."—*Railway Service Gazette*.

"Were the cautions and rules given in the book to become part of the every-day working of our engine-drivers, we might have fewer distressing accidents to deplore."—*Scotsman*.

Stationary Engine Driving.

STATIONARY ENGINE DRIVING: A Practical Manual for Engineers in Charge of Stationary Engines. By MICHAEL REYNOLDS. Third Edition, Enlarged. With Plates and Woodcuts. Crown 8vo, 4s. 6d. cloth.

"The author is thoroughly acquainted with his subjects, and his advice on the various points treated is clear and practical. . . . He has produced a manual which is an exceedingly useful one for the class for whom it is specially intended."—*Engineering*.

"Our author leaves no stone unturned. He is determined that his readers shall not only know something about the stationary engine, but all about it."—*Engineer*.

"An engineman who has mastered the contents of Mr. Reynolds's book will require but little actual experience with boilers and engines before he can be trusted to look after them."—*English Mechanic*.

The Engineer, Fireman, and Engine-Boy.

THE MODEL LOCOMOTIVE ENGINEER, FIREMAN, AND ENGINE-BOY. Comprising a Historical Notice of the Pioneer Locomotive Engines and their Inventors. By MICHAEL REYNOLDS. With numerous Illustrations, and a fine Portrait of George Stephenson. Crown 8vo, 4s. 6d. cloth.

"From the technical knowledge of the author, it will appeal to the railway man of to-day more forcibly than anything written by Dr. Smiles. . . . The volume contains information of a technical kind, and facts that every driver should be familiar with."—*English Mechanic*.

"We should be glad to see this book in the possession of everyone in the kingdom who has ever laid, or is to lay, hands on a locomotive engine."—*Iron*.

Continuous Railway Brakes.

CONTINUOUS RAILWAY BRAKES: A Practical Treatise on the several Systems in Use in the United Kingdom; their Construction and Performance. With copious Illustrations and numerous Tables. By MICHAEL REYNOLDS. Large crown 8vo, 9s. cloth.

"A popular explanation of the different brakes. It will be of great assistance in forming public opinion, and will be studied with benefit by those who take an interest in the brake."—*English Mechanic*.

"Written with sufficient technical detail to enable the principal and relative connection of the various parts of each particular brake to be readily grasped."—*Mechanical World*.

Engine-Driving Life.

ENGINE-DRIVING LIFE; or, Stirring Adventures and Incidents in the Lives of Locomotive Engine-Drivers. By MICHAEL REYNOLDS. Ninth Thousand. Crown 8vo, 2s. cloth.

"From first to last perfectly fascinating. Wilkie Collins's most thrilling conceptions are thrown into the shade by true incidents, endless in their variety, related in every page."—*North British Mail*.

"Anyone who wishes to get a real insight into railway life cannot do better than read 'Engine-Driving Life' for himself, and if he once takes it up he will find that the author's enthusiasm and real love of the engine-driving profession will carry him on till he has read every page."—*Saturday Review*.

Pocket Companion for Enginemen.

THE ENGINEMAN'S POCKET COMPANION and Practical Educator for Enginemen, Boiler Attendants, and Mechanics. By MICHAEL REYNOLDS. With Forty-five Illustrations and numerous Diagrams. Second Edition, Revised. Royal 18mo, 3s. 6d. strongly bound for pocket wear. [Just published.]

"This admirable work is well suited to accomplish its object, being the honest workmanship of a competent engineer."—*Glasgow Herald*.

"A most meritorious work, giving in a succinct and practical form all the information an engineman desirous of mastering the scientific principles of his daily calling would require."—*The Miller*.

"A boon to those who are striving to become efficient mechanics."—*Daily Chronicle*.

French-English Glossary for Engineers, &c.

A POCKET GLOSSARY OF TECHNICAL TERMS: ENGLISH-FRENCH, FRENCH-ENGLISH; with Tables suitable for the Architectural, Engineering, Manufacturing and Nautical Professions. By JOHN JAMES FLETCHER, Engineer and Surveyor; 200 pp. Waistcoat-pocket size, 1s. 6d. limp leather.

"It ought certainly to be in the waistcoat-pocket of every professional man."—*Iron*.

"It is a very great advantage for readers and correspondents in France and England to have so large a number of the words relating to engineering and manufacturers collected in a slipshod volume. The little book will be useful both to students and travellers."—*Architect*.

"The glossary of terms is very complete, and many of the Tables are new and well arranged. We cordially commend the book."—*Mechanical World*.

Portable Engines.

THE PORTABLE ENGINE; ITS CONSTRUCTION AND MANAGEMENT, A Practical Manual for Owners and Users of Steam Engines generally. By WILLIAM DYSON WANSBROUGH. With 90 Illustrations. Crown 8vo, 3s. 6d. cloth. [Just published.]

"This is a work of value to those who use steam machinery. . . . Should be read by every one who has a steam engine, on a farm or elsewhere."—*Mark Lane Express*.

"We cordially commend this work to buyers and owners of steam engines, and to those who have to do with their construction or use."—*Timber Trades Journal*.

"Such a general knowledge of the steam-engine as Mr. Wansbrough furnishes to the reader should be acquired by all intelligent owners and others who use the steam engine."—*Building News*.

"An excellent textbook of this useful form of engine, which describes with all necessary minuteness the details of the various devices. . . . The 'Hints to Purchasers' contain a good deal of common-sense and practical wisdom."—*English Mechanic*.

CIVIL ENGINEERING, SURVEYING, etc.**MR. HUMBER'S IMPORTANT ENGINEERING BOOKS.****The Water-Supply of Cities and Towns.**

A COMPREHENSIVE TREATISE ON THE WATER-SUPPLY OF CITIES AND TOWNS. By WILLIAM HUMBER, A-M. Inst. C.E., and M. Inst. M.E., Author of "Cast and Wrought Iron Bridge Construction," &c. &c. Illustrated with 50 Double Plates, 1 Single Plate, Coloured Frontispiece, and upwards of 250 Woodcuts, and containing 400 pages of Text. Imp. 4to, £6 6s. elegantly and substantially half-bound in morocco.

LIST OF CONTENTS.

I. Historical Sketch of some of the means that have been adopted for the Supply of Water to Cities and Towns.—II. Water and the Foreign Matter usually associated with it.—III. Rainfall and Evaporation.—IV. Springs and the water-bearing formations of various districts.—V. Measurement and Estimation of the Flow of Water.—VI. On the Selection of the Source of Supply.—VII. Wells.—VIII. Reservoirs.—IX. The Purification of Water.—X. Pumps.—XI. Pumping

Machinery.—XII. Conduits.—XIII. Distribution of Water.—XIV. Meters, Service Pipes, and House Fittings.—XV. The Law and Economy of Water Works.—XVI. Constant and Intermittent Supply.—XVII. Description of Plates.—Appendices, giving Tables of Rates of Supply, Velocities, &c. &c., together with Specifications of several Works illustrated, among which will be found: Aberdeen, Bideford, Canterbury, Dundee, Halifax, Lambeth, Rotherham, Dublin, and others.

"The most systematic and valuable work upon water supply hitherto produced in English, or in any other language. . . . Mr. Humber's work is characterised almost throughout by an exhaustiveness much more distinctive of French and German than of English technical treatises."—*Engineer*.

"We can congratulate Mr. Humber on having been able to give so large an amount of information on a subject so important as the water supply of cities and towns. The plates, fifty in number, are mostly drawings of executed works, and alone would have commanded the attention of every engineer whose practice may lie in this branch of the profession."—*Builder*.

Cast and Wrought Iron Bridge Construction.

A COMPLETE AND PRACTICAL TREATISE ON CAST AND WROUGHT IRON BRIDGE CONSTRUCTION, including Iron Foundations. In Three Parts—Theoretical, Practical, and Descriptive. By WILLIAM HUMBER, A-M. Inst. C.E., and M. Inst. M.E. Third Edition, revised and much improved, with 115 Double Plates (20 of which now first appear in this edition), and numerous Additions to the Text. In 2 vols., imp. 4to, £6 16s. 6d. half-bound in morocco.

"A very valuable contribution to the standard literature of civil engineering. In addition to elevations, plans, and sections, large scale details are given, which very much enhance the instructive worth of these illustrations."—*Civil Engineer and Architect's Journal*.

"Mr. Humber's stately volumes, lately issued—in which the most important bridges erected during the last five years, under the direction of the late Mr. Brunel, Sir W. Cubitt, Mr. Hawkshaw, Mr. Page, Mr. Fowler, Mr. Hemans, and others among our most eminent engineers, are drawn and specified in great detail."—*Engineer*.

MR. HUMBER'S GREAT WORK ON MODERN ENGINEERING.

Complete in Four Volumes, imperial 4to, price £12 12s., half-morocco. Each volume sold separately as follows :—

A RECORD OF THE PROGRESS OF MODERN ENGINEERING.

FIRST SERIES. Comprising Civil, Mechanical, Marine, Hydraulic, Railway, Bridge, and other Engineering Works, &c. By WILLIAM HUMBER, A.M. Inst. C.E., &c. Imp. 4to, with 36 Double Plates, drawn to a large scale, Photographic Portrait of John Hawkshaw, C.E., F.R.S., &c., and copious descriptive Letterpress, Specifications, &c., £3 3s. half-morocco.

LIST OF THE PLATES AND DIAGRAMS.

Victoria Station and Roof, L. B. & S. C. R. (8 plates); Southport Pier (2 plates); Victoria Station and Roof, L. C. & D. and G. W. R. (6 plates); Roof of Cremorne Music Hall; Bridge over G. N. Railway; Roof of Station, Dutch

Rhenish Rail (2 plates); Bridge over the Thames, West London Extension Railway (5 plates); Armour Plates: Suspension Bridge, Thames (4 plates); The Allen Engine; Suspension Bridge, Avon (3 plates); Underground Railway (3 plates).

"Handsomely lithographed and printed. It will find favour with many who desire to preserve in a permanent form copies of the plans and specifications prepared for the guidance of the contractors for many important engineering works."—*Engineer*.

HUMBER'S RECORD OF MODERN ENGINEERING. SECOND

SERIES. Imp. 4to, with 36 Double Plates, Photographic Portrait of Robert Stephenson, C.E., M.P., F.R.S., &c., and copious descriptive Letterpress, Specifications, &c., £3 3s. half-morocco.

LIST OF THE PLATES AND DIAGRAMS.

Birkenhead Docks, Low Water Basin (15 plates); Charing Cross Station Roof, C. C. Railway (3 plates); Digswell Viaduct, Great Northern Railway; Robbery Wood Viaduct, Great Northern Railway; Iron Permanent Way; Clydach Viaduct, Merthyr, Tredegar, and Abergavenny Railway;

Ebbw Viaduct, Merthyr, Tredegar, and Abergavenny Railway; College Wood Viaduct, Cornwall Railway; Dublin Winter Palace Roof (3 plates); Bridge over the Thames, L. C. and D. Railway (6 plates); Albert Harbour, Greenock (4 plates).

"Mr. Humber has done the profession good and true service, by the fine collection of examples he has here brought before the profession and the public."—*Practical Mechanic's Journal*.

HUMBER'S RECORD OF MODERN ENGINEERING. THIRD

SERIES. Imp. 4to, with 40 Double Plates, Photographic Portrait of J. R. M'Clean, late Pres. Inst. C.E., and copious descriptive Letterpress, Specifications, &c., £3 3s. half-morocco.

LIST OF THE PLATES AND DIAGRAMS.

MAIN DRAINAGE, METROPOLIS—*North Side*.—Map showing Interception of Sewers; Middle Level Sewer (2 plates); Outfall Sewer, Bridge over River Lea (3 plates); Outfall Sewer, Bridge over Marsh Lane, North Woolwich Railway, and Bow and Barking Railway Junction; Outfall Sewer, Bridge over Bow and Barking Railway (3 plates); Outfall Sewer, Bridge over East London Waterworks' Feeder (2 plates); Outfall Sewer, Reservoir (2 plates); Outfall Sewer, Tumbling Bay and Outlet; Outfall Sewer, Penstocks. *South Side*.—Outfall Sewer, Bermondsey Branch

(2 plates); Outfall Sewer, Reservoir and Outlet (4 plates); Outfall Sewer, Filth Hoist; Sections of Sewers (North and South Sides).

THAMES EMBANKMENT.—Section of River Wall; Steamboat Pier, Westminster (2 plates); Landing Stairs between Charing Cross and Waterloo Bridges; York Gate (2 plates); Overflow and Outlet at Savoy Street Sewer (3 plates); Steamboat Pier, Waterloo Bridge (3 plates); Junction of Sewers, Plans and Sections; Gullies, Plans, and Sections; Rolling Stock; Granite and Iron Forts.

"The drawings have a constantly increasing value, and whoever desires to possess clear representations of the two great works carried out by our Metropolitan Board will obtain Mr. Humber's volume."—*Engineer*.

HUMBER'S RECORD OF MODERN ENGINEERING. FOURTH

SERIES. Imp. 4to, with 36 Double Plates, Photographic Portrait of John Fowler, late Pres. Inst. C.E., and copious descriptive Letterpress, Specifications, &c., £3 3s. half-morocco.

LIST OF THE PLATES AND DIAGRAMS.

Abbey Mills Pumping Station, Main Drainage, Metropolis (4 plates); Barrow Docks (3 plates); Manquis Viaduct, Santiago and Valparaiso Railway (2 plates); Adam's Locomotive, St. Helen's Canal Railway (2 plates); Cannon Street Station Roof, Charing Cross Railway (3 plates); Road Bridge over the River Moka (2 plates); Telegra-

phic Apparatus for Mesopotamia; Viaduct over the River Wye, Midland Railway (3 plates); St. Germans Viaduct, Cornwall Railway (2 plates); Wrought-Iron Cylinder for Diving Bell; Millwall Docks (6 plates); Milroy's Patent Excavator Metropolitan District Railway (6 plates); Harbours, Ports, and Breakwaters (3 plates).

"We gladly welcome another year's issue of this valuable publication from the able pen of Mr. Humber. The accuracy and general excellence of this work are well known, while its usefulness in giving the measurements and details of some of the latest examples of engineering, as carried out by the most eminent men in the profession, cannot be too highly prized."—*Artisan*.

MR. HUMBER'S ENGINEERING BOOKS—continued.**Strains, Calculation of.**

A HANDY BOOK FOR THE CALCULATION OF STRAINS IN GIRDERS AND SIMILAR STRUCTURES, AND THEIR STRENGTH. Consisting of Formulæ and Corresponding Diagrams, with numerous details for Practical Application, &c. By WILLIAM HUMBER, A-M. Inst. C.E., &c. Fourth Edition. Crown 8vo, with nearly 100 Woodcuts and 3 Plates, 7s. 6d. cloth.

"The formulæ are neatly expressed, and the diagrams good."—*Athenæum*.

We heartily commend this really *handy* book to our engineer and architect readers."—*English Mechanic*.

Barlow's Strength of Materials, enlarged by Humber.

A TREATISE ON THE STRENGTH OF MATERIALS; with Rules for Application in Architecture, the Construction of Suspension Bridges, Railways, &c. By PETER BARLOW, F.R.S. A New Edition, revised by his Sons, P. W. BARLOW, F.R.S., and W. H. BARLOW, F.R.S.; to which are added, Experiments by HODGKINSON, FAIRBAIRN, and KIRKALDY; and Formulæ for Calculating Girders, &c. Arranged and Edited by WM. HUMBER, A-M. Inst. C.E. Demy 8vo, 400 pp., with 19 large Plates and numerous Woodcuts, 18s. cloth.

"Valuable alike to the student, tyro, and the experienced practitioner, it will always rank in future, has hitherto done, as the standard treatise on that particular subject."—*Engineer*.

"There is no greater authority than Barlow."—*Building News*.

"As a scientific work of the first class, it deserves a foremost place on the bookshelves of every civil engineer and practical mechanic."—*English Mechanic*.

Trigonometrical Surveying.

AN OUTLINE OF THE METHOD OF CONDUCTING A TRIGONOMETRICAL SURVEY, for the Formation of Geographical and Topographical Maps and Plans, Military Reconnaissance, Levelling, &c., with Useful Problems, Formulæ, and Tables. By Lieut.-General FROME, R.E. Fourth Edition, Revised and partly Re-written by Major-General Sir CHARLES WARREN, G.C.M.G., R.E. With 19 Plates and 115 Woodcuts, royal 8vo, 16s. cloth.

"The simple fact that a fourth edition has been called for is the best testimony to its merits. No words of praise from us can strengthen the position so well and so steadily maintained by this work. Sir Charles Warren has revised the entire work, and made such additions as were necessary to bring every portion of the contents up to the present date."—*Broad Arrow*.

Oblique Bridges.

A PRACTICAL AND THEORETICAL ESSAY ON OBLIQUE BRIDGES. With 13 large Plates. By the late GEORGE WATSON BUCK, M.I.C.E. Third Edition, revised by his Son, J. H. WATSON BUCK, M.I.C.E.; and with the addition of Description to Diagrams for Facilitating the Construction of Oblique Bridges, by W. H. BARLOW, M.I.C.E. Royal 8vo, 12s. cloth.

"The standard text-book for all engineers regarding skew arches is Mr. Buck's treatise, and it would be impossible to consult a better."—*Engineer*.

"Mr. Buck's treatise is recognised as a standard text-book, and his treatment has divested the subject of many of the intricacies supposed to belong to it. As a guide to the engineer and architect, on a confessedly difficult subject, Mr. Buck's work is unsurpassed."—*Building News*.

Bridge Construction.

EXAMPLES OF BRIDGE AND VIADUCT CONSTRUCTION OF MASONRY, TIMBER, AND IRON. Consisting of 46 Plates from the Contract Drawings or Admeasurement of select Works. By W. D. HASKOLL, C.E. Second Edition, with the addition of 554 Estimates, and the Practice of Setting out Works. Illustrated with 6 pages of Diagrams. Imp. 4to, £2 12s. 6d. half-morocco.

"A work of the present nature, by a man of Mr. Haskoll's experience, must prove invaluable. The tables of estimates will considerably enhance its value."—*Engineering*.

Earthwork.

EARTHWORK TABLES. Showing the Contents in Cubic Yards of Embankments, Cuttings, &c., of Heights or Depths up to an average of 80 feet. By JOSEPH BROADBENT, C.E., and FRANCIS CAMPIN, C.E. Crown 8vo, 5s. cloth.

"The way in which accuracy is attained, by a simple division of each cross section into three elements, two in which are constant and one variable, is ingenious."—*Athenæum*.

Statics, Graphic and Analytic.

GRAPHIC AND ANALYTIC STATICS, in their Practical Application to the Treatment of Stresses in Roofs, Solis & Lattice, Bowstring, and Suspension Bridges, Braced Iron Arches and Towers, and other Frameworks. By R. HUDSON GRAHAM, C.E. Containing Diagrams and Plates to Scale. With numerous Examples, many taken from existing Structures. Specially arranged for Class-work in Colleges and Universities. Second Edition, Revised and Enlarged. 8vo, 16s. cloth.

"Mr. Graham's book will find a place wherever graphic and analytic statics are used or studied."—*Engineer*.

"This exhaustive treatise is admirably adapted for the architect and engineer, and will tend to wean the profession from a tedious and laboured mode of calculation. To prove the accuracy of the graphical demonstrations, the author compares them with the analytic formulæ given by Rankine."—*Building News*.

"The work is excellent from a practical point of view, and has evidently been prepared with much care. The directions for working are ample, and are illustrated by an abundance of well-selected examples. It is an excellent text-book for the practical draughtsman."—*Athenæum*.

Survey Practice.

AID TO SURVEY PRACTICE: for Reference in Surveying, Levelling, Setting-out and in Route Surveys of Travellers by Land and Sea. With Tables, Illustrations, and Records. By LOWIS D'A. JACKSON, A.M.I.C.E., Author of "Hydraulic Manual," "Modern Metrology," &c. Large crown 8vo, 12s. 6d. cloth.

"Mr. Jackson has produced a valuable *vade-mecum* for the surveyor. We can recommend this book as containing an admirable supplement to the teaching of the accomplished surveyor."—*Athenæum*.

"We cannot recommend to the student who knows something of the mathematical principles of the subject a better course than to fortify his practice in the field under a competent surveyor with a study of Mr. Jackson's useful manual."—*Building News*.

"As a text-book we should advise all surveyors to place it in their libraries, and study well the matured instructions afforded in its pages."—*Colliery Guardian*.

"The author brings to his work a fortunate union of theory and practical experience which, aided by a clear and lucid style of writing, renders the book a very useful one."—*Builder*.

Surveying, Land and Marine.

LAND AND MARINE SURVEYING, in Reference to the Preparation of Plans for Roads and Railways; Canals, Rivers, Towns' Water Supplies; Docks and Harbours. With Description and Use of Surveying Instruments. By W. DAVIS HASKOLL, C.E., Author of "Bridge and Viaduct Construction," &c. Second Edition, Revised, with Additions. Large crown 8vo, 9s. cloth.

"This book must prove of great value to the student. We have no hesitation in recommending it, feeling assured that it will more than repay a careful study."—*Mechanical World*.

"A most useful and well arranged book for the aid of a student. We can strongly recommend it as a carefully-written and valuable text-book. It enjoys a well-deserved repute among surveyors."—*Builder*.

"This volume cannot fail to prove of the utmost practical utility. It may be safely recommended to all students who aspire to become clean and expert surveyors."—*Mining Journal*.

Levelling.

A TREATISE ON THE PRINCIPLES AND PRACTICE OF LEVELLING, Showing its Application to purposes of Railway and Civil Engineering in the Construction of Roads; with Mr. TELFORD's Rules for the same. By FREDERICK W. SIMMS, F.G.S., M. Inst. C.E. Seventh Edition, with the addition of LAW's Practical Examples for Setting-out Railway Curves, and TRAUTWINE's Field Practice of Laying-out Circular Curves. With 7 Plates and numerous Woodcuts, 8vo, 8s. 6d. cloth. * * * TRAUTWINE ON CURVES may be had separate, 5s.

"The text-book on levelling in most of our engineering schools and colleges."—*Engineer*.

"The publishers have rendered a substantial service to the profession, especially to the younger members, by bringing out the present edition of Mr. Simms's useful work."—*Engineering*.

Tunnelling.

PRACTICAL TUNNELLING. Explaining in detail the Setting-out of the works, Shaft-sinking and Heading-driving, Ranging the Lines and Levelling under Ground, Sub-Excavating, Timbering, and the Construction of the Brickwork of Tunnels, with the amount of Labour required for, and the Cost of, the various portions of the work. By FREDERICK W. SIMMS, F.G.S., M. Inst. C.E. Third Edition, Revised and Extended by D. KINNEAR CLARK, M.Inst.C.E. Imp. 8vo, with 21 Folding Plates and numerous Wood Engravings, 30s. cloth.

"The estimation in which Mr. Simms's book on tunnelling has been held for over thirty years cannot be more truly expressed than in the words of the late Professor Rankine:—'The best source of information on the subject of tunnels is Mr. F. W. Simms's work on Practical Tunnelling.'"—*Architect*.

"It has been regarded from the first as a text book of the subject . . . Mr. Clark has added immensely to the value of the book."—*Engineer*.

"The additional chapters by Mr. Clark, containing as they do numerous examples of modern practice, bring the book well up to date."—*Engineering*.

Heat, Expansion by.

EXPANSION OF STRUCTURES BY HEAT. By JOHN KELLY, C.E., late of the Indian Public Works and Victorian Railway Departments. Crown 8vo, 3s. 6d., cloth. [Just published.]

SUMMARY OF CONTENTS.

Section I.—FORMULAS AND DATA.

Section II.—METAL BARS.

Section III.—SIMPLE FRAMES.

Section IV.—COMPLEX FRAMES AND PLATES.

Section V.—THERMAL CONDUCTIVITY.

Section VI.—MECHANICAL FORCE OF HEAT.

Section VII.—WORK OF EXPANSION AND CONTRACTION.

Section VIII.—SUSPENSION BRIDGES.

Section IX.—MASONRY STRUCTURES.

"The aim the author has set before him, viz., to show the effects of heat upon metallic and other structures, is a laudable one, for this is a branch of physics upon which the engineer or architect can find but little reliable and comprehensive data in books."—*Builder*.

"Whoever is concerned to know the effect of changes of temperature on such structures as suspension bridges and the like could not do better than consult Mr. Kelly's valuable and handy exposition of the geometrical principles involved in these changes. The book is lucidly written throughout."—*Scotsman*.

Practical Mathematics.

MATHEMATICS FOR PRACTICAL MEN: Being a Common-place Book of Pure and Mixed Mathematics. Designed chiefly for the Use of Civil Engineers, Architects and Surveyors. By OLINTHUS GREGORY, LL.D., F.R.A.S., Enlarged by HENRY LAW, C.E. Fourth Ed., carefully revised by J. R. YOUNG, formerly Professor of Mathematics, Belfast College. With 13 Plates, 8vo, £1 1s. cloth.

"The engineer or architect will here find ready to his hand rules for solving nearly every mathematical difficulty that may arise in his practice. The rules are in all cases explained by means of examples, in which every step of the process is clearly worked out."—*Builder*.

"One of the most serviceable books for practical mechanics. . . . It is an instructive book for the student, and a Text-book for him who, having once mastered the subjects it treats of, needs occasionally to refresh his memory upon them."—*Building News*.

Hydraulic Tables.

HYDRAULIC TABLES, CO-EFFICIENTS, and FORMULÆ for Finding the Discharge of Water from Orifices, Notches, Weirs, Pipes, and Rivers. With New Formulæ, Tables, and General Information on Rain-fall, Catchment-Basins, Drainage, Sewerage, Water Supply for Towns and Mill Power. By JOHN NEVILLE, Civil Engineer, M.R.I.A. Third Edition, carefully revised, with considerable Additions. Numerous Illustrations. Crown 8vo, 14s. cloth.

"Alike valuable to students and engineers in practice; its study will prevent the annoyance of avoidable failures, and assist them to select the readiest means of successfully carrying out any given work connected with hydraulic engineering."—*Mining Journal*.

"It is, of all English books on the subject, the one nearest to completeness. . . . From the good arrangement of the matter, the clear explanations and abundance of formulæ, the carefully calculated tables, and, above all, the thorough acquaintance with both theory and construction, which is displayed from first to last, the book will be found to be an acquisition."—*Architect*.

River Engineering.

RIVER BARS: The Causes of their Formation, and their Treatment by "Induced Tidal Scour;" with a Description of the Successful Reduction by this Method of the Bar at Dublin. By I. J. MANN, Assist. Eng. to the Dublin Port and Docks Board. Royal 8vo, 7s. 6d. cloth.

"We recommend all interested in harbour works—and, indeed, those concerned in the improvements of rivers generally—to read Mr. Mann's interesting work on the treatment of river bars."—*Engineer*.

"The author's discussion on wave-action, currents and scour is intelligent and interesting. . . . A most valuable contribution to the history of this branch of engineering."—*Engineering and Mining Journal*.

Hydraulics.

HYDRAULIC MANUAL. Consisting of Working Tables and Explanatory Text. Intended as a Guide in Hydraulic Calculations and Field Operations. By LOWIS D'A. JACKSON, Author of "Aid to Survey Practice," "Modern Metrology," &c. Fourth Edition. Rewritten and Enlarged. Large crown 8vo, 16s. cloth.

"The author has had a wide experience in hydraulic engineering, both in South America and in India, and has been a careful observer of the facts which have come under his notice, as well as a painstaking collector and critic of the results of the experiments of others, and from the great mass of material at his command he has constructed a manual which may be accepted as a trustworthy guide to this branch of the engineer's profession. We can heartily recommend this volume to all who desire to be acquainted with the latest development of this important subject."—*Engineering*.

"The standard work in this department of mechanics. The present edition has been brought abreast of the most recent practice."—*Scotsman*.

"The most useful feature of this work is its freedom from what is superannuated, and its thorough adoption of recent experiments; the text is in fact in great part a short account of the great modern experiments."—*Nature*.

Drainage.

ON THE DRAINAGE OF LANDS, TOWNS AND BUILDINGS.

By G. D. DEMPSEY, C. E., Author of "The Practical Railway Engineer," &c. Revised, with large Additions on RECENT PRACTICE IN DRAINAGE ENGINEERING, by D. KINNAR CLARK, M.Inst. C.E., Author of "Tramways: their Construction and Working," "A Manual of Rules, Tables, and Data for Mechanical Engineers," &c. &c. Crown 8vo, 7s. 6d. cloth. [Just published.]

"The new matter added to Mr. Dempsey's excellent work is characterised by the comprehensive grasp and accuracy of detail for which the name of Mr. D. K. Clark is a sufficient voucher."—*Athenæum*.

"As a work on recent practice in drainage engineering, the book is to be commended to all who are making that branch of engineering science their special study."—*Iron*.

"A comprehensive manual on drainage engineering, and a useful introduction to the student."—*Building News*.

Tramways and their Working.

TRAMWAYS: Their CONSTRUCTION and WORKING. Embracing a Comprehensive History of the System; with an exhaustive Analysis of the Various Modes of Traction, including Horse Power, Steam, Heated Water, and Compressed Air; a Description of the Varieties of Rolling Stock; and ample Details of Cost and Working Expenses; the Progress recently made in Tramway Construction, &c., &c. By D. KINNAR CLARK, M.Inst. C.E. With over 200 Wood Engravings, and 13 Folding Plates. Two Vols. Large crown 8vo, 30s. cloth.

"All interested in tramways must refer to it, as all railway engineers have turned to the author's work 'Railway Machinery.'"—*Engineer*.

"An exhaustive and practical work on tramways, in which the history of this kind of locomotion, and a description and cost of the various modes of laying tramways, are to be found."—*Building News*.

"The best form of rails, the best mode of construction, and the best mechanical appliances, are so fairly indicated in the work under review that any engineer about to construct a tramway will be enabled at once to obtain the practical information which will be of most service to him."—*Athenæum*.

Oblique Arches.

A PRACTICAL TREATISE ON THE CONSTRUCTION OF OBLIQUE ARCHES. By JOHN HART. Third Edition, with Plates. Imperial 8vo, 8s. cloth.

Curves, Tables for Setting-out.

TABLES OF TANGENTIAL ANGLES AND MULTIPLES FOR SETTING-OUT CURVES from 5 to 200 Radius. By ALEXANDER BEAZELEY, M.Inst.C.E. Third Edition. Printed on 48 Cards, and sold in a cloth box, waistcoat-pocket size, 3s. 6d.

"Each table is printed on a small card, which, being placed on the theodolite, leaves the hands free to manipulate the instrument—no small advantage as regards the rapidity of work."—*Engineer*.

"Very handy: a man may know that all his day's work must fall on two of these cards, which he puts into his own card-case, and leaves the rest behind."—*Athenæum*.

Engineering Fieldwork.

THE PRACTICE OF ENGINEERING FIELDWORK, Applied to Land and Hydraulic, Hydrographic, and Submarine Surveying and Levelling. Second Edition, Revised, with considerable Additions, and a Supplement on Water-works, Sewers, Sewage, and Irrigation. By W. DAVIS HASKOLL, C.E. Numerous Folding Plates. In One Volume, demy 8vo, £1 5s. cloth.

Tunnel Shafts.

THE CONSTRUCTION OF LARGE TUNNEL SHAFTS. A Practical and Theoretical Essay. By J. H. WATSON BUCK, M. Inst. C.E., Resident Engineer, London and North-Western Railway. Illustrated with Folding Plates, royal 8vo, 12s. cloth.

Many of the methods given are of extreme practical value to the mason, and the observations on the form of arch, the rules for ordering the stone, and the construction of the templates, will be found of considerable use. We commend the book to the engineering profession."—*Building News*.

"Will be regarded by civil engineers as of the utmost value, and calculated to save much time and obviate many mistakes."—*Colliery Guardian*.

Girders, Strength of.

GRAPHIC TABLE FOR FACILITATING THE COMPUTATION OF THE WEIGHTS OF WROUGHT IRON AND STEEL GIRDERS, &c., for Parliamentary and other Estimates. By J. H. WATSON BUCK, M. Inst. C.E. On a Sheet, 2s. 6d.

Trusses.

TRUSSES OF WOOD AND IRON. *Practical Applications of Science in Determining the Stresses, Breaking Weights, Safe Loads, Scantlings, and Details of Construction.* With Complete Working Drawings. By WILLIAM GRIFFITHS, Surveyor, Assistant Master, Tranmere School of Science and Art. Oblong 8vo, 4s. 6d. cloth.

"This handy little book enters so minutely into every detail connected with the construction of roof trusses, that no student need be ignorant of these matters for want of an easy source to come at the knowledge."—*Practical Engineer.*

"From the manner of treating the subject, Mr. Griffiths' book is clear enough to enable a student to be his own teacher. It will be useful in the science school and in workshops."—*Architect.*

Railway Working.

SAFE RAILWAY WORKING. *A Treatise on Railway Accidents: Their Cause and Prevention; with a Description of Modern Appliances and Systems.* By CLEMENT E. STRETTON, C. E., Vice-President and Consulting Engineer, Amalgamated Society of Railway Servants. With Illustrations and Coloured Plates, crown 8vo, 4s. 6d. strongly bound.

OUTLINE OF CONTENTS.

Chapter I.—SUMMARY OF ACCIDENTS, 1885.
Chapter II.—PERMANENT WAY.
Chapter III.—SIGNALLING; BLOCK SYSTEM.
Chapter IV.—CONTINUOUS BRAKES.
Chapter V.—BREAKING OF RAILWAY AXLES.
Chapter VI.—RAILWAY COUPLINGS.

Chapter VII.—RAILWAY SERVANTS AND THE LAW OF MANSLAUGHTER.
Appendix I.—RAILWAY TRAFFIC RETURNS.
Appendix II.—RAILWAY SIGNAL RETURNS.
Appendix III.—CONTINUOUS BRAKES RETURNS.
Appendix IV.—MIXED TRAINS.

*** * * OPINIONS OF THE PRESS.**

"A book for the engineer, the directors, the managers; and, in short, all who wish for information on railway matters will find a perfect encyclopedia in 'Safe Railway Working.'"—*Railway Review.*

"Mr. Clement E. Stretton, the energetic Vice-President of the Amalgamated Society of Railway Servants, may be congratulated on having collected, in a very convenient form, much valuable information on the principal questions affecting the safe working of railways."—*Railway Engineer.*

"We commend the remarks on railway signalling to all railway managers, especially where a uniform code and practice is advocated."—*Herepath's Railway Journal.*

Field-Book for Engineers.

THE ENGINEER'S, MINING SURVEYOR'S, and CONTRACTOR'S FIELD-BOOK. Consisting of a Series of Tables, with Rules, Explanations of Systems, and use of Theodolite for Traverse Surveying and Plotting the Work with minute accuracy by means of Straight Edge and Set Square only; Levelling with the Theodolite, Casting-out and Reducing Levels to Datum, and Plotting Sections in the ordinary manner; Setting-out Curves with the Theodolite by Tangential Angles and Multiples with Right and Left-hand Readings of the Instrument; Setting-out Curves without Theodolite on the System of Tangential Angles by Sets of Tangents and Offsets; and Earthwork Tables to 80 feet deep, calculated for every 6 inches in depth. By W. DAVIS HASKOLL, C.E. With numerous Woodcuts. Fourth Edition, Enlarged. Crown 8vo, 12s. cloth.

"The book is very handy; the separate tables of sines and tangents to every minute will make it useful for many other purposes, the genuine traverse tables existing all the same."—*Athenaeum.*

"Every person engaged in engineering field operations will estimate the importance of such a work and the amount of valuable time which will be saved by reference to a set of reliable tables prepared with the accuracy and fulness of those given in this volume."—*Railway News.*

Earthwork, Measurement of.

A MANUAL ON EARTHWORK. By ALEX. J. S. GRAHAM, C.E. With numerous Diagrams. 18mo, 2s. 6d. cloth.

"A great amount of practical information very admirably arranged, and available for rough estimates, as well as for the more exact calculations required in the engineer's and contractor's offices."—*Artisan.*

Strains in Ironwork.

THE STRAINS ON STRUCTURES OF IRONWORK; with Practical Remarks on Iron Construction. By F. W. SHEILDS, M. Inst. C.E. Second Edition, with 5 Plates. Royal 8vo, 5s. cloth.

"The student cannot find a better little book on this subject."—*Engineer.*

Cast Iron and other Metals, Strength of.

A PRACTICAL ESSAY ON THE STRENGTH OF CAST IRON AND OTHER METALS. By THOMAS TREDDGOLD, C.E. Fifth Edition, including HODGKINSON'S Experimental Researches. 8vo, 12s. cloth.

ARCHITECTURE, BUILDING, etc.

Construction.

THE SCIENCE OF BUILDING: An Elementary Treatise on the Principles of Construction. By E. WYNDHAM TARN, M.A., Architect. Second Edition, Revised, with 58 Engravings. Crown 8vo, 7s. 6d. cloth.

"A very valuable book, which we strongly recommend to all students."—*Builder*.

"No architectural student should be without this hand-book of constructional knowledge."—*Architect*.

Villa Architecture.

A HANDY BOOK OF VILLA ARCHITECTURE: Being a Series of Designs for Villa Residences in various Styles. With Outline Specifications and Estimates. By C. WICKES, Architect, Author of "The Spires and Towers of England," &c. 61 Plates, 4to, £1 11s. 6d. half-morocco, gilt edges.

"The whole of the designs bear evidence of their being the work of an artistic architect, and they will prove very valuable and suggestive."—*Building News*.

Text-Book for Architects.

THE ARCHITECT'S GUIDE: Being a Text-book of Useful Information for Architects, Engineers, Surveyors, Contractors, Clerks of Works, &c., &c. By FREDERICK ROGERS, Architect, Author of "Specifications for Practical Architecture," &c. Second Edition, Revised and Enlarged. With numerous Illustrations. Crown 8vo, 6s. cloth.

"As a text-book of useful information for architects, engineers, surveyors, &c., it would be hard to find a handier or more complete little volume."—*Standard*.

"A young architect could hardly have a better guide-book."—*Timber Trades Journal*.

Taylor and Cresy's Rome.

THE ARCHITECTURAL ANTIQUITIES OF ROME. By the late G. L. TAYLOR, Esq., F.R.I.B.A., and EDWARD CRESY, Esq. New Edition, thoroughly revised by the Rev. ALEXANDER TAYLOR, M.A. (son of the late G. L. Taylor, Esq.), Fellow of Queen's College, Oxford, and Chaplain of Gray's Inn. Large folio, with 130 Plates, half-bound, £3 3s.

N.B.—This is the only book which gives on a large scale, and with the precision of architectural measurement, the principal Monuments of Ancient Rome in plan, elevation, and detail.

"Taylor and Cresy's work has from its first publication been ranked among those professional books which cannot be bettered. . . . It would be difficult to find examples of drawings, even among those of the most painstaking students of Gothic, more thoroughly worked out than are the one hundred and thirty plates in this volume."—*Architect*.

Architectural Drawing.

PRACTICAL RULES ON DRAWING, for the Operative Builder and Young Student in Architecture. By GEORGE PYNE. With 14 Plates, 4to, 7s. 6d. boards.

Civil Architecture.

THE DECORATIVE PART OF CIVIL ARCHITECTURE. By Sir WILLIAM CHAMBERS, F.R.S. With Illustrations, Notes, and an Examination of Grecian Architecture, by JOSEPH GWILT, F.S.A. Edited by W. H. LEEDS. 66 Plates, 4to, 21s. cloth.

House Building and Repairing.

THE HOUSE-OWNER'S ESTIMATOR; or, What will it Cost to Build, Alter, or Repair? A Price Book adapted to the Use of Unprofessional People, as well as for the Architectural Surveyor and Builder. By the late JAMES D. SIMON, A.R.I.B.A. Edited and Revised by FRANCIS T. W. MILLER, A.R.I.B.A. With numerous Illustrations. Third Edition, Revised. Crown 8vo, 3s. 6d. cloth.

"In two years it will repay its cost a hundred times over."—*Field*.

"A very handy book"—*English Mechanic*.

Designing, Measuring, and Valuing.

THE STUDENT'S GUIDE to the PRACTICE of MEASURING and VALUING ARTIFICERS' WORKS. Containing Directions for taking Dimensions, Abstracting the same, and bringing the Quantities into Bill, with Tables of Constants, and copious Memoranda for the Valuation of Labour and Materials in the respective Trades of Bricklayer and Slater, Carpenter and Joiner, Painter and Glazier, Paperhanger, &c. With 8 Plates and 63 Woodcuts. Originally edited by EDWARD DOBSON, Architect. Fifth Edition, Revised, with considerable Additions on Mensuration and Construction, and a New Chapter on Dilapidations, Repairs, and Contracts, by E. WYNDHAM TARN, M.A. Crown 8vo, 9s. cloth.

"Well fulfils the promise of its title-page, and we can thoroughly recommend it to the class for whose use it has been compiled. Mr. Tarn's additions and revisions have much increased the usefulness of the work, and have especially augmented its value to students."—*Engineering*.

"The work has been carefully revised and edited by Mr. E. Wyndham Tarn, M.A., and comprises several valuable additions on construction, mensuration, dilapidations and repairs, and other matters. . . . This edition will be found the most complete treatise on the principles of measuring and valuing artificers' work that has yet been published."—*Building News*.

Pocket Estimator and Technical Guide.

THE POCKET TECHNICAL GUIDE, MEASURER, AND ESTIMATOR FOR BUILDERS AND SURVEYORS. Containing Technical Directions for Measuring Work in all the Building Trades, with a Treatise on the Measurement of Timber and Complete Specifications for Houses, Roads, and Drains, and an Easy Method of Estimating the various parts of a Building collectively. By A. C. BEATON, Author of "Quantities and Measurements," &c. Fourth Edition. Carefully Revised and Priced according to the Present Value of Materials and Labour, with 53 Woodcuts, leather, waistcoat-pocket size, 1s. 6d. gilt edges.

"No builder, architect, surveyor, or valuer should be without his 'Beaton's Guide.'—*Building News*.

"Contains an extraordinary amount of information in daily requisition in measuring and estimating. Its presence in the pocket will save valuable time and trouble."—*Building World*.

"An exceedingly handy pocket companion, thoroughly reliable."—*Builder's Weekly Reporter*.

"This neat little compendium contains all that is requisite in carrying out contracts for excavating, tiling, bricklaying, paving, &c."—*British Trade Journal*.

Donaldson on Specifications.

THE HANDBOOK OF SPECIFICATIONS; or, Practical Guide to the Architect, Engineer, Surveyor, and Builder, in drawing up Specifications and Contracts for Works and Constructions. Illustrated by Precedents of Buildings actually executed by eminent Architects and Engineers. By Professor T. L. DONALDSON, P.R.I.B.A., &c. New Edition, in one large vol., 8vo, with upwards of 1,000 pages of Text, and 33 Plates, £1 11s. 6d. cloth.

"In this work forty-four specifications of executed works are given, including the specifications for parts of the new Houses of Parliament, by Sir Charles Barry, and for the new Royal Exchange, by Mr. Tite, M.P. The latter, in particular, is a very complete and remarkable document. It embodies, to a great extent, as Mr. Donaldson mentions, 'the bill of quantities, with the description of the works.' . . . It is valuable as a record, and more valuable still as a book of precedents. . . . Suffice it to say that Donaldson's 'Handbook of Specifications' must be bought by all architects."—*Builder*.

Bartholomew and Rogers' Specifications.

SPECIFICATIONS FOR PRACTICAL ARCHITECTURE. A Guide to the Architect, Engineer, Surveyor, and Builder. With an Essay on the Structure and Science of Modern Buildings. Upon the Basis of the Work by ALFRED BARTHOLOMEW, thoroughly Revised, Corrected, and greatly added to by FREDERICK ROGERS, Architect. Second Edition, Revised, with Additions. With numerous Illustrations, medium 8vo, 15s. cloth.

"The collection of specifications prepared by Mr. Rogers on the basis of Bartholomew's work is too well known to need any recommendation from us. It is one of the books with which every young architect must be equipped; for time has shown that the specifications cannot be set aside through any defect in them."—*Architect*.

"Good forms for specifications are of considerable value, and it was an excellent idea to compile a work on the subject upon the basis of the late Alfred Bartholomew's valuable work. The second edition of Mr. Rogers's book is evidence of the want of a book dealing with modern requirements and materials."—*Building News*.

Geometry for the Architect, Engineer, &c.

PRACTICAL GEOMETRY, for the Architect, Engineer, and Mechanic. Giving Rules for the Delineation and Application of various Geometrical Lines, Figures, and Curves. By E. W. TARN, M.A., Architect, Author of "The Science of Building," &c. Second Edition. With Appendices on Diagrams of Strains and Isometrical Projection. With 172 Illustrations, demy 8vo, 9s. cloth.

"No book with the same objects in view has ever been published in which the clearness of the rules laid down and the illustrative diagrams have been so satisfactory."—*Schoolman*.

"This is a manual for the practical man, whether architect, engineer, or mechanic. . . . The object of the author being to avoid all abstruse formulæ or complicated methods, and to enable persons with but a moderate knowledge of geometry to work out the problems required."—*English Mechanic*.

The Science of Geometry.

THE GEOMETRY OF COMPASSES; or, Problems Resolved by the mere Description of Circles, and the use of Coloured Diagrams and Symbols. By OLIVER BYRNE. Coloured Plates. Crown 8vo, 3s. 6d. cloth.

"The treatise is a good one, and remarkable—like all Mr. Byrne's contributions to the science of geometry—for the lucid character of its teaching."—*Building News*.

DECORATIVE ARTS, etc.

Woods and Marbles, Imitation of.

SCHOOL OF PAINTING FOR THE IMITATION OF WOODS AND MARBLES, as taught and practised by A. R. VAN DER BURG and P. VAN DER BURG, Directors of the Rotterdam Painting Institution. Royal folio, 18½ by 12½ in., illustrated with 24 full-size Coloured Plates; also 12 plain Plates, comprising 154 Figures. Second and cheaper Edition. Price £1 11s. 6d.

LIST OF PLATES.

1. Various Tools required for Wood Painting—2, 3. Walnut; Preliminary Stages of Graining and Finished Specimen—4. Tools used for Marble Painting and Method of Manipulation—5, 6. St. Remi Marble; Earlier Operations and Finished Specimen—7. Methods of Sketching different Grains, Knots, &c.—8, 9. Ash: Preliminary Stages and Finished Specimen—10. Methods of Sketching Marble Grains—11, 12. Breche Marble; Preliminary Stages of Working and Finished Specimen—13. Maple; Methods of Producing the different Grains—14, 15. Bird's-eye Maple; Preliminary Stages and Finished Specimen—16. Methods of Sketching the different species of White Marble—17, 18. White Marble; Preliminary Stages of Pro-

cess and Finished Specimen—19. Mahogany; Specimens of various Grains and Methods of Manipulation—20, 21. Mahogany; Earlier Stages and Finished Specimen—22, 23, 24. Sienna Marble; Varieties of Grain, Preliminary Stages and Finished Specimen—25, 26, 27. Juniper Wood; Methods of producing Grain, &c.—Preliminary Stages and Finished Specimen—28, 29, 30. Vert de Mer Marble; Varieties of Grain and Methods of Working, Unfinished and Finished Specimens—31, 32, 33. Oak; Varieties of Grain, Tools employed and Methods of Manipulation, Preliminary Stages and Finished Specimen—34, 35, 36. Waulsort Marble; Varieties of Grain, Unfinished and Finished Specimens.

* * * OPINIONS OF THE PRESS.

"Those who desire to attain skill in the art of painting woods and marbles will find advantage in consulting this book. . . . Some of the Working Men's Clubs should give their young men the opportunity to study it."—*Builder*.

"A comprehensive guide to the art. The explanations of the processes, the manipulation and management of the colours, and the beautifully executed plates will not be the least valuable to the student who aims at making his work a faithful transcript of nature."—*Building News*.

"Students and novices are fortunate who are able to become the possessors of so noble a work."—*Architect*.

House Decoration.

ELEMENTARY DECORATION: A Guide to the Simpler Forms of Everyday Art, as applied to the Interior and Exterior Decoration of Dwelling Houses, &c. By JAMES W. FACEY, Jun. With 68 Cuts. 12mo, 2s. cloth limp.

"As a technical guide-book to the decorative painter it will be found reliable."—*Building News*.

PRACTICAL HOUSE DECORATION: A Guide to the Art of Ornamental Painting, the Arrangement of Colours in Apartments, and the principles of Decorative Design. With some Remarks upon the Nature and Properties of Pigments. By JAMES WILLIAM FACEY, Author of "Elementary Decoration," &c. With numerous Illustrations. 12mo, 2s. 6d. cloth limp.

N.B.—The above Two Works together in One Vol., strongly half-bound, 5s.

Colour.

A GRAMMAR OF COLOURING. Applied to Decorative Painting and the Arts. By GEORGE FIELD. New Edition, Revised, Enlarged, and adapted to the use of the Ornamental Painter and Designer, by ELLIS A. DAVIDSON. With New Coloured Diagrams and Engravings. 12mo, 3s. 6d. cloth boards.

"The book is a most useful *resumé* of the properties of pigments."—*Builder*.

House-Painting, Graining, etc.

HOUSE-PAINTING, GRAINING, MARBLING, & SIGN WRITING, A Practical Manual of. By ELLIS A. DAVIDSON. Fourth Edition. With Coloured Plates and Wood Engravings. 12mo, 6s. cloth boards.

"A mass of information, of use to the amateur and of value to the practical man."—*English Mechanic*.

"Simply invaluable to the youngster entering upon this particular calling, and highly serviceable to the man who is practising it."—*Furniture Gazette*.

Decorators, Receipts for.

THE DECORATOR'S ASSISTANT; A Modern Guide to Decorative Artists and Amateurs, Painters, Writers, Gilders, &c. Containing upwards of 600 Receipts, Rules and Instructions; with a variety of Information for General Work connected with every Class of Interior and Exterior Decorations, &c., 152 pp., crown 8vo, 1s. in wrapper.

"Full of receipts of value to decorators, painters, gilders, &c. The book contains the gist of larger treatises on colour and technical processes."—*Building News*.

"It would be difficult to meet with a work so full of varied information on the painter's art."—*Building News*.

"We recommend the work to all who, whether for pleasure or profit, require a guide to decoration."—*Plumber and Decorator*.

Moyr Smith on Interior Decoration.

ORNAMENTAL INTERIORS, ANCIENT AND MODERN. By J. MOYR SMITH. Super-roy. 8vo, with Thirty-Two Full-Page Plates and numerous smaller Illustrations, handsomely bound in cloth, gilt top, price 18s.

[Just published.]

In "ORNAMENTAL INTERIORS" the designs of more than thirty artist-decorators and architects of high standing have been illustrated. The book may therefore fairly claim to give a good general view of the works of the modern school of decoration, besides giving characteristic examples of earlier decorative arrangements.

"ORNAMENTAL INTERIORS" gives a short account of the styles of Interior Decoration as practised by the Ancients in Egypt, Greece, Assyria, Rome, and Byzantium. This part is illustrated by characteristic designs. The main body of the work, however, is devoted to the illustration of the modern styles of Decorative Art, and many examples are given of decorative designs suitable for modern Dining-Rooms, Drawing-Rooms, Libraries, Staircases and Halls, Parlours, Studies, and Smoking-Rooms. The Decoration of Public Buildings is illustrated by views of the chief State Apartments in Buckingham Palace and Windsor Castle, the Salle de Leys at Antwerp, the Salle des Mariages at Brussels, and of other works which have distinctive features suitable for the purpose.

*** * * OPINIONS OF THE PRESS.**

"The book is well illustrated and handsomely got up, and contains some true criticism and a good many good examples of decorative treatment."—*The Builder*.

"We can greatly commend Mr. Moyr Smith's book, for it is the production of one professedly capable in decorative work, and abounds with useful hints and descriptions of executed modern work, together with a well-put *resumé* of ancient styles. . . . As much a book for the drawing-room as for the manufacturer."—*The British Architect*.

"Well fitted for the dilettante, amateur, and professional designer."—*Decoration*.

"This is the most elaborate and beautiful work on the artistic decoration of interiors that we have seen. . . . The scrolls, panels, and other designs from the author's own pen are very beautiful and chaste; but he takes care that the designs of other men shall figure even more than his own."—*Liverpool Albion*.

"To all who take an interest in elaborate domestic ornament this handsome volume will be welcome."—*Graphic*.

"Mr. Moyr Smith deserves the thanks of art workers for having placed within their reach a book that seems eminently adapted to afford, by example and precept, that guidance of which most craftsmen stand in need."—*Furniture Gazette*.

British and Foreign Marbles.

MARBLE DECORATION and the Terminology of British and Foreign Marbles. A Handbook for Students. By GEORGE H. BLAGROVE, Author of "Shoring and its Application," &c. With 28 Illustrations. Cr. 8vo, 3s. 6d. cloth.

[Just published.]

DELAMOTTE'S WORKS ON ILLUMINATION AND ALPHABETS.

A PRIMER OF THE ART OF ILLUMINATION, for the Use of *Beginners*: with a Rudimentary Treatise on the Art, Practical Directions for its exercise, and Examples taken from Illuminated MSS., printed in Gold and Colours. By F. DELAMOTTE. New and Cheaper Edition. Small 4to, 6s. ornamental boards.

"The examples of ancient MSS. recommended to the student, which, with much good sense, the author chooses from collections accessible to all, are selected with judgment and knowledge, as well as taste."—*Athenæum*.

ORNAMENTAL ALPHABETS, *Ancient and Mediæval, from the Eighth Century, with Numerals*; including Gothic, Church-Text, large and small, German, Italian, Arabesque, Initials for Illumination, Monograms, Crosses, &c. &c., for the use of Architectural and Engineering Draughtsmen, Missal Painters, Masons, Decorative Painters, Lithographers, Engravers, Carvers, &c. &c. Collected and Engraved by F. DELAMOTTE, and printed in Colours. New and Cheaper Edition. Royal 8vo, oblong, 2s. 6d. ornamental boards.

"For those who insert enamelled sentences round gilded chalices, who blazon shop legends over shop-doors, who letter church walls with pithy sentences from the Decalogue, this book will be useful."—*Athenæum*.

EXAMPLES OF MODERN ALPHABETS, *Plain and Ornamental*, including German, Old English, Saxon, Italic, Perspective, Greek, Hebrew, Court Hand, Engrossing, Tuscan, Riband, Gothic, Rustic, and Arabesque; with several Original Designs, and an Analysis of the Roman and Old English Alphabets, large and small, and Numerals, for the use of Draughtsmen, Surveyors, Masons, Decorative Painters, Lithographers, Engravers, Carvers, &c. Collected and Engraved by F. DELAMOTTE, and printed in Colours. New and Cheaper Edition. Royal 8vo, oblong, 2s. 6d. ornamental boards.

"There is comprised in it every possible shape into which the letters of the alphabet and numerals can be formed, and the talent which has been expended in the conception of the various plain and ornamental letters is wonderful."—*Standard*.

MEDIÆVAL ALPHABETS AND INITIALS FOR ILLUMINATORS. By F. G. DELAMOTTE. Containing 21 Plates and Illuminated Title, printed in Gold and Colours. With an Introduction by J. WILLIS BROOKS. Fourth and Cheaper Edition. Small 4to, 4s. ornamental boards.

"A volume in which the letters of the alphabet come forth glorified in gilding and all the colours of the prism interwoven and intertwined and intermingled."—*Sun*.

THE EMBROIDERER'S BOOK OF DESIGN. Containing Initials, Emblems, Cyphers, Monograms, Ornamental Borders, Ecclesiastical Devices, Mediæval and Modern Alphabets, and National Emblems. Collected by F. DELAMOTTE, and printed in Colours. Oblong royal 8vo, 1s. 6d. ornamental wrapper.

"The book will be of great assistance to ladies and young children who are endowed with the art of plying the needle in this most ornamental and useful pretty work."—*East Anglian Times*.

Wood Carving.

INSTRUCTIONS IN WOOD-CARVING, for *Amateurs*; with Hints on Design. By A LADY. With Ten large Plates, 2s. 6d. in emblematic wrapper.

"The handicraft of the wood-carver, so well as a book can impart it, may be learnt from 'A Lady's' publication."—*Athenæum*.

"The directions given are plain and easily understood."—*English Mechanic*.

Glass Painting.

GLASS STAINING AND THE ART OF PAINTING ON GLASS. From the German of Dr. GESSERT and EMANUEL OTTO FROMBERG. With an Appendix on THE ART OF ENAMELLING. 12mo, 2s. 6d. cloth limp.

Letter Painting.

THE ART OF LETTER PAINTING MADE EASY. By JAMES GREIG BADENOCH. With 12 full-page Engravings of Examples, 1s. cloth limp.

"The system is a simple one, but quite original, and well worth the careful attention of letter painters. It can be easily mastered and remembered."—*Building News*.

CARPENTRY, TIMBER, etc.

Tredgold's Carpentry, Revised and Enlarged by Tarn.

THE ELEMENTARY PRINCIPLES OF CARPENTRY: A Treatise on the Pressure and Equilibrium of Timber Framing, the Resistance of Timber, and the Construction of Floors, Arches, Bridges, Roofs, Uniting Iron and Stone with Timber, &c. To which is added an Essay on the Nature and Properties of Timber, &c., with Descriptions of the kinds of Wood used in Building; also numerous Tables of the Scantlings of Timber for different purposes, the Specific Gravities of Materials, &c. By THOMAS TREDGOLD, C.E. With an Appendix of Specimens of Various Roofs of Iron and Stone, Illustrated. Seventh Edition, thoroughly revised and considerably enlarged by E. WYNDHAM TARN, M.A., Author of "The Science of Building," &c. With 61 Plates, Portrait of the Author, and several Woodcuts. In one large vol., 4to, price 25s. cloth.

"Ought to be in every architect's and every builder's library."—*Builder*.

"A work whose monumental excellence must commend it wherever skilful carpentry is concerned. The author's principles are rather confirmed than impaired by time. The additional plates are of great intrinsic value."—*Building News*.

Woodworking Machinery.

WOODWORKING MACHINERY: Its Rise, Progress and Construction. With Hints on the Management of Saw Mills and the Economical Conversion of Timber. Illustrated with Examples of Recent Designs by leading English, French, and American Engineers. By M. POWIS BALE, A.M.Inst.C.E., M.I.M.E. Large crown 8vo, 12s. 6d. cloth.

"Mr. Bale is evidently an expert on the subject, and he has collected so much information that his book is all-sufficient for builders and others engaged in the conversion of timber."—*Architect*.

"The most comprehensive compendium of wood-working machinery we have seen. The author is a thorough master of his subject."—*Building News*.

"The appearance of this book at the present time will, we should think, give a considerable impetus to the onward march of the machinist engaged in the designing and manufacture of wood-working machines. It should be in the office of every wood-working factory."—*English Mechanic*.

Saw Mills.

SAW MILLS: Their Arrangement and Management, and the Economical Conversion of Timber. (A Companion Volume to "Woodworking Machinery.") By M. POWIS BALE. With numerous Illustrations. Crown 8vo, 10s. 6d. cloth.

"The administration of a large sawing establishment is discussed, and the subject examined from a financial standpoint. Hence the size, shape, order, and disposition of saw-mills and the like are gone into in detail, and the course of the timber is traced from its reception to its delivery in its converted state. We could not desire a more complete or practical treatise."—*Builder*.

"We highly recommend Mr. Bale's work to the attention and perusal of all those who are engaged in the art of wood conversion, or who are about building or remodelling saw-mills on improved principles."—*Building News*.

Carpentering.

THE CARPENTER'S NEW GUIDE; or, Book of Lines for Carpenters; comprising all the Elementary Principles essential for acquiring a knowledge of Carpentry. Founded on the late PETER NICHOLSON'S standard work. A New Edition, revised by ARTHUR ASHPITEL, F.S.A. Together with Practical Rules on Drawing, by GEORGE PYNE. With 74 Plates, 4to, £1 1s. cloth.

Handrailing.

A PRACTICAL TREATISE ON HANDRAILING: Showing New and Simple Methods for Finding the Pitch of the Plank, Drawing the Moulds, Beveling, Jointing-up, and Squaring the Wreath. By GEORGE COLLINGS. Illustrated with Plates and Diagrams. 12mo, 1s. 6d. cloth limp.

"Will be found of practical utility in the execution of this difficult branch of joinery."—*Builder*.

"Almost every difficult phase of this somewhat intricate branch of joinery is elucidated by the aid of plates and explanatory letterpress."—*Furniture Gazette*.

Circular Work.

CIRCULAR WORK IN CARPENTRY AND JOINERY: A Practical Treatise on Circular Work of Single and Double Curvature. By GEORGE COLLINGS, Author of "A Practical Treatise on Handrailing." Illustrated with numerous Diagrams. 12mo, 2s. 6d. cloth limp. [Just published.]

"An excellent example of what a book of this kind should be. Cheap in price, clear in definition and practical in the examples selected."—*Builder*.

Timber Merchant's Companion.

THE TIMBER MERCHANT'S AND BUILDER'S COMPANION.

Containing New and Copious Tables of the Reduced Weight and Measurement of Deals and Battens, of all sizes, from One to a Thousand Pieces, and the relative Price that each size bears per Lineal Foot to any given Price per Petersburg Standard Hundred; the Price per Cube Foot of Square Timber to any given Price per Load of 50 Feet; the proportionate Value of Deals and Battens by the Standard, to Square Timber by the Load of 50 Feet; the readiest mode of ascertaining the Price of Scantling per Lineal Foot of any size, to any given Figure per Cube Foot, &c. &c. By WILLIAM DOWSING. Fourth Edition, Revised and Corrected. Cr. 8vo, 3s. cloth.

"Everything is as concise and clear as it can possibly be made. There can be no doubt that every timber merchant and builder ought to possess it."—*Hull Advertiser*.

"We are glad to see a fourth edition of these admirable tables, which for correctness and simplicity of arrangement leave nothing to be desired."—*Timber Trades Journal*.

"An exceedingly well-arranged, clear, and concise manual of tables for the use of all who buy or sell timber."—*Journal of Forestry*.

Practical Timber Merchant.

THE PRACTICAL TIMBER MERCHANT; Being a Guide for the use of Building Contractors, Surveyors, Builders, &c., comprising useful Tables for all purposes connected with the Timber Trade, Marks of Wood, Essay on the Strength of Timber, Remarks on the Growth of Timber, &c. By W. RICHARDSON. Fcap. 8vo, 3s. 6d. cloth.

"This handy manual contains much valuable information for the use of timber merchants, builders, erectors, and all others connected with the growth, sale, and manufacture of timber."—*Journal of Forestry*.

Timber Freight Book.

THE TIMBER MERCHANT'S, SAW MILLER'S, AND IMPORTER'S FREIGHT BOOK AND ASSISTANT. Comprising Rules, Tables, and Memoranda relating to the Timber Trade. By WILLIAM RICHARDSON, Timber Broker; together with a Chapter on SPEEDS OF SAW MILL MACHINERY, by M. POWIS BALE, M.I.M.E., &c. 12mo, 3s. 6d. cloth boards.

"A very useful manual of rules, tables, and memoranda, relating to the timber trade. We recommend it as a compendium of calculation to all timber measurers and merchants, and as supplying a real want in the trade."—*Building News*.

Packing-Case Makers, Tables for.

PACKING-CASE TABLES; showing the number of Superficial Feet in Boxes or Packing-Cases, from six inches square and upwards. By W. RICHARDSON, Timber Broker. Second Edition. Oblong 4to, 3s. 6d. cloth.

"Invaluable labour-saving tables."—*Ironmonger*. "Will save much labour and calculation."—*Grocer*.

Superficial Measurement.

THE TRADESMAN'S GUIDE TO SUPERFICIAL MEASUREMENT. Tables calculated from 1 to 200 inches in length, by 1 to 108 inches in breadth. For the use of Architects, Surveyors, Engineers, Timber Merchants, Builders, &c. By JAMES HAWKINGS. Third Edition. Foolsap, 3s. 6d. cloth.

"A useful collection of tables to facilitate rapid calculation of surfaces. The exact area of any surface of which the limits have been ascertained can be instantly determined. The book will be found of the greatest utility to all engaged in building operations."—*Scottsman*.

"These tables will be found of great assistance to all who require to make calculations in superficial measurement."—*English Mechanic*.

Forestry.

THE ELEMENTS OF FORESTRY. Designed to afford Information concerning the Planting and Care of Forest Trees for Ornament or Profit, with suggestions upon the Creation and Care of Woodlands. By F. B. HOUGH. Large crown 8vo, 10s. cloth.

Timber Importer's Guide.

THE TIMBER IMPORTER'S, TIMBER MERCHANT'S, AND BUILDER'S STANDARD GUIDE. By RICHARD E. GRANDY. Comprising:—An Analysis of Deal Standards, Home and Foreign, with Comparative Values and Tabular Arrangements for fixing Nett Landed Cost on Baltic and North American Deals, including all intermediate Expenses, Freight, Insurance, &c. &c.; together with copious Information for the Retailer and Builder. Second Edition, carefully revised and corrected. 12mo, 3s. 6d. cloth boards.

"Everything it pretends to be: built up gradually, it leads one from a forest to a treenail, and throws in, as a makeweight, a host of material concerning bricks, columns, cisterns, &c."—*English Mechanic*.

NAVAL ARCHITECTURE, NAVIGATION, etc.

Chain Cables.

CHAIN CABLES AND CHAINS. Comprising Sizes and Curves of Links, Studs, &c., Iron for Cables and Chains, Chain Cable and Chain Making, Forming and Welding Links, Strength of Cables and Chains, Certificates for Cables, Marking Cables, Prices of Chain Cables and Chains, Historical Notes, Acts of Parliament, Statutory Tests, Charges for Testing, List of Manufacturers of Cables, &c., &c. By THOMAS W. TRAILL, F.E.R.N., M.Inst.C.E., Engineer-Surveyor-in-Chief, Board of Trade, Inspector of Chain Cable and Anchor Proving Establishments, and General Superintendent, Lloyd's Committee on Proving Establishments. With numerous Tables, Illustrations, and Lithographic Drawings. Folio, £2 2s. cloth, bevelled boards.

"The author writes not only with a full acquaintance with scientific formulae and details, but also with a profound and fully-instructed sense of the importance to the safety of our ships and sailors of fidelity in the manufacture of cables. We heartily recommend the book to the specialists to whom it is addressed."—*Athenaeum*.

"The business of chain cable making is well explained and illustrated. We can safely recommend this work to all in any way connected with the manufacture of chain cables and chains, as a good book."—*Nature*.

"It contains a vast amount of valuable information. Nothing seems to be wanting to make it a complete and standard work of reference on the subject."—*Nautical Magazine*.

Pocket-Book for Naval Architects and Shipbuilders.

THE NAVAL ARCHITECT'S AND SHIPBUILDER'S POCKET-BOOK of Formulae, Rules, and Tables, and MARINE ENGINEER'S AND SURVEYOR'S Handy Book of Reference. By CLEMENT MACKROW, Member of the Institution of Naval Architects, Naval Draughtsman. Third Edition, Revised. With numerous Diagrams, &c. Fcap., 12s. 6d., strongly bound in leather.

"Should be used by all who are engaged in the construction or design of vessels. . . . Will be found to contain the most useful tables and formulae required by shipbuilders, carefully collected from the best authorities, and put together in a popular and simple form."—*Engineer*.

"The professional shipbuilder has now, in a convenient and accessible form, reliable data for solving many of the numerous problems that present themselves in the course of his work."—*Iron*.

"There is scarcely a subject on which a naval architect or shipbuilder can require to refresh his memory which will not be found within the covers of Mr. Mackrow's book."—*English Mechanic*.

Pocket-Book for Marine Engineers.

A POCKET-BOOK OF USEFUL TABLES AND FORMULÆ FOR MARINE ENGINEERS. By FRANK PROCTOR, A.I.N.A. Third Edition. Royal 32mo, leather, gilt edges, with strap, 4s.

"We recommend it to our readers as going far to supply a long-felt want."—*Naval Science*.

"A most useful companion to all marine engineers."—*United Service Gazette*.

Lighthouses.

EUROPEAN LIGHTHOUSE SYSTEMS; Being a Report of a Tour of Inspection made in 1873. By Major GEORGE H. ELLIOT, Corps of Engineers, U.S.A. Illustrated by 51 Engravings and 31 Woodcuts. 8vo, 21s. cloth.

* * The following are published in WEALE'S **RUDIMENTARY SERIES.**

MASTING, MAST-MAKING, AND RIGGING OF SHIPS. By ROBERT KIPPING, N.A. Fifteenth Edition. 12mo, 2s. 6d. cloth boards.

SAILS AND SAIL-MAKING. Eleventh Edition, Enlarged, with an Appendix. By ROBERT KIPPING, N.A. Illustrated. 12mo, 3s. cloth boards.

NAVAL ARCHITECTURE. By JAMES PEAKE. Fifth Edition, with Plates and Diagrams. 12mo, 4s. cloth boards.

MARINE ENGINES AND STEAM VESSELS (A Treatise on). By ROBERT MURRAY, C.E., Principal Officer to the Board of Trade for the East Coast of Scotland District. Eighth Edition, thoroughly Revised, with considerable Additions by the Author and by GEORGE CARLISLE, C.E., Senior Surveyor to the Board of Trade at Liverpool. 12mo, 5s. cloth boards.

PRACTICAL NAVIGATION. Consisting of the Sailor's Sea-Book, by JAMES GREENWOOD and W. H. ROSSER; together with the requisite Mathematical and Nautical Tables for the Working of the Problems, by HENRY LAW, C.E., and Professor J. R. YOUNG. Illustrated. 12mo, 7s., strongly half-bound.

MINING AND MINING INDUSTRIES.

Metalliferous Mining.

BRITISH MINING: A Treatise on the History, Discovery, Practical Development, and Future Prospects of Metalliferous Mines in the United Kingdom. By ROBERT HUNT, F.R.S., Keeper of Mining Records; Editor of "Ure's Dictionary of Arts, Manufactures, and Mines," &c. Upwards of 950 pp., with 230 Illustrations. Second Edition, Revised. Super-royal 8vo, £2 2s. cloth.

[Just published.

* * OPINIONS OF THE PRESS.

"One of the most valuable works of reference of modern times. Mr. Hunt, as Keeper of Mining Records of the United Kingdom, has had opportunities for such a task not enjoyed by anyone else, and has evidently made the most of them. . . . The language and style adopted are good, and the treatment of the various subjects laborious, conscientious, and scientific."—*Engineering*.

"Probably no one in this country was better qualified than Mr. Hunt for undertaking such a work. Brought into frequent and close association during a long life-time with the principal guardians of our mineral and metallurgical industries, he enjoyed a position exceptionally favourable for collecting the necessary information. The use which he has made of his opportunities is sufficiently attested by the dense mass of information crowded into the handsome volume which has just been published. . . . In placing before the reader a sketch of the present position of British Mining, Mr. Hunt treats his subject so fully and illustrates it so amply that this section really forms a little treatise on practical mining. . . . The book is, in fact, a treasure-house of statistical information on mining subjects, and we know of no other work embodying so great a mass of matter of this kind. Were this the only merit of Mr. Hunt's volume it would be sufficient to render it indispensable in the library of everyone interested in the development of the mining and metallurgical industries of this country."—*Athenæum*.

"A mass of information not elsewhere available, and of the greatest value to those who may be interested in our great mineral industries."—*Engineer*.

"A sound, business-like collection of interesting facts. . . . The amount of information Mr. Hunt has brought together is enormous. . . . The volume appears likely to convey more instruction upon the subject than any work hitherto published."—*Mining Journal*.

"The work will be for the mining industry what Dr. Percy's celebrated treatise has been for the metallurgical—a book that cannot with advantage be omitted from the library."—*Iron and Coal Trades Review*.

"The volume is massive and exhaustive, and the high intellectual powers and patient persistent application which characterise the author have evidently been brought into play in its production. Its contents are invaluable."—*Colliery Guardian*.

"The literature of mining has hitherto possessed no work approaching in importance to that which has just been published. There is much in Mr. Hunt's valuable work that every shareholder in a mine should read with close attention. The entire subject of practical mining—from the first search for the lode to the latest stages of dressing the ore—is dealt with in a masterly manner."—*Academy*.

Coal and Iron.

THE COAL AND IRON INDUSTRIES OF THE UNITED KINGDOM. Comprising a Description of the Coal Fields, and of the Principal Seams of Coal, with Returns of their Produce and its Distribution, and Analyses of Special Varieties. Also, an Account of the occurrence of Iron Ores in Veins or Seams; Analyses of each Variety; and a History of the Rise and Progress of Pig Iron Manufacture since the year 1740, exhibiting the Economies introduced in the Blast Furnaces for its Production and Improvement. By RICHARD MEADE, Assistant Keeper of Mining Records. With Maps of the Coal Fields and Ironstone Deposits of the United Kingdom. 8vo, £1 8s. cloth.

"The book is one which must find a place on the shelves of all interested in coal and iron production and in the iron, steel, and other metallurgical industries."—*Engineer*.

"Of this book we may unreservedly say that it is the best of its class which we have ever met. . . . A book of reference which no one engaged in the iron or coal trades should omit from his library."—*Iron and Coal Trades Review*.

"An exhaustive treatise and a valuable work of reference."—*Mining Journal*.

Prospecting for Gold and other Metals.

THE PROSPECTOR'S HANDBOOK: A Guide for the Prospector and Traveller in Search of Metal-Bearing or other Valuable Minerals. By J. W. ANDERSON, M.A. (Camb.), F.R.G.S., Author of "Fiji and New Caledonia." Third Edition, Revised, with Additions. Small crown 8vo, 3s. 6d. cloth.

[Just published.

"Will supply a much felt want, especially among Colonists, in whose way are so often thrown many mineralogical specimens the value of which it is difficult for anyone, not a specialist, to determine. The author has placed his instructions before his readers in the plainest possible terms, and his book is the best of its kind."—*Engineer*.

"How to find commercial minerals, and how to identify them when they are found, are the leading points to which attention is directed. The author has managed to pack as much practical detail into his pages as would supply material for a book three times its size."—*Mining Journal*.

"Those toilers who explore the trodden or untrodden tracks on the face of the globe will find much that is useful to them in this book."—*Athenæum*.

Mining Notes and Formulæ.

NOTES AND FORMULÆ FOR MINING STUDENTS. By JOHN HERMAN MERIVALE, M.A., Certificated Colliery Manager, Professor of Mining in the Durham College of Science, Newcastle-upon-Tyne. Second Edition, carefully Revised. Small crown 8vo, cloth, price 2s. 6d. [Just published.]

"This book consists of a collection of notes and formula drawn from various sources, the authority being quoted in most instances. It is hoped that the work will be useful, not only to students but to the profession."

The principal sources of information upon mining matters are the Transactions of the various Engineering Societies to which the student, in most of our large towns, has access. A great many references to the most familiar of them are given, so that the student who wishes to follow up a subject may be in a position to acquaint himself with details which could not be included in a work like this.

The examples of the use of the formula, at the end of the book, are merely given to assist students working without a teacher.

"Invaluable to anyone who is working up for an examination on mining subjects."—*Coal and Iron Trades Review*.

"The author has done his work in an exceedingly creditable manner, and has produced a book that will be of service to students, and those who are practically engaged in mining operations."—*Engineer*.

"A vast amount of technical matter of the utmost value to mining engineers, and of considerable interest to students."—*Schoolmaster*.

Mineral Surveying and Valuing.

THE MINERAL SURVEYOR AND VALUER'S COMPLETE GUIDE, comprising a Treatise on Improved Mining Surveying and the Valuation of Mining Properties, with New Traverse Tables. By WM. LINTERN, Mining and Civil Engineer. Second Edition, with an Appendix on "Magnetic and Angular Surveying," with Records of the Peculiarities of Needle Disturbances. With Four Plates of Diagrams, Plans, &c. 12mo, 4s. cloth. [Just published.]

"An enormous fund of information of great value."—*Mining Journal*.

"Mr. Lintern's book forms a valuable and thoroughly trustworthy guide."—*Iron and Coal Trades Review*.

"This new edition must be of the highest value to colliery surveyors, proprietors and managers."—*Colliery Guardian*.

Metalliferous Minerals and Mining.

TREATISE ON METALLIFEROUS MINERALS AND MINING. By D. C. DAVIES, F.G.S., Mining Engineer, &c., Author of "A Treatise on Slate and Slate Quarrying." Illustrated with numerous Wood Engravings. Fourth Edition, carefully revised. Crown 8vo, 12s. 6d. cloth.

"Neither the practical miner nor the general reader, interested in mines, can have a better book for his companion and his guide."—*Mining Journal*.

"The volume is one which no student of mineralogy should be without."—*Colliery Guardian*.

"We are doing our readers a service in calling their attention to this valuable work."—*Mining World*.

"A book that will not only be useful to the geologist, the practical miner, and the metallurgist; but also very interesting to the general public."—*Iron*.

"As a history of the present state of mining throughout the world this book has a real value, and it supplies an actual want, for no such information has hitherto been brought together within such limited space."—*Athenæum*.

Earthy Minerals and Mining.

A TREATISE ON EARTHY AND OTHER MINERALS, AND MINING. By D. C. DAVIES, F.G.S. Uniform with, and forming a Companion Volume to, the same Author's "Metalliferous Minerals and Mining." With 76 Wood Engravings. Second Edition. Crown 8vo, 12s. 6d. cloth.

"It is essentially a practical work, intended primarily for the use of practical men. . . : We do not remember to have met with any English work on mining matters that contains the same amount of information packed in equally convenient form."—*Academy*.

"The book is clearly the result of many years' careful work and thought, and we should be inclined to rank it as among the very best of the handy technical and trades manuals, which have recently appeared."—*British Quarterly Review*.

"The volume contains a great mass of practical information, carefully methodised and presented in a very intelligible shape."—*Scotsman*.

"The subject matter of the volume will be found of high value by all—and they are a numerous class—who trade in earthy minerals."—*Athenæum*.

Underground Pumping Machinery.

MINE DRAINAGE: Being a Complete and Practical Treatise on Direct-Acting Underground Steam Pumping Machinery, with a Description of a large number of the best known Engines, their General Utility and the Special Sphere of their Action, the Mode of their Application, and their merits compared with other forms of Pumping Machinery. By STEPHEN MICHELL. 8vo, 15s. cloth.

"Will be highly esteemed by colliery owners and lessees, mining engineers, and students generally who require to be acquainted with the best means of securing the drainage of mines. It is a most valuable work, and stands almost alone in the literature of steam pumping machinery."—*Colliery Guardian*.

"Much valuable information is given, so that the book is thoroughly worthy of an extensive circulation amongst practical men and purchasers of machinery."—*Mining Journal*.

Mining Tools.

A MANUAL OF MINING TOOLS. For the Use of Mine Managers, Agents, Students, &c. By WILLIAM MORGANS, Lecturer on Practical Mining at the Bristol School of Mines. 12mo, 3s. cloth boards.

ATLAS OF ENGRAVINGS to illustrate the above, containing 235 Illustrations of Mining Tools, drawn to scale. 4to, 4s. 6d. cloth.

"Students in the science of mining, and overmen, captains, managers, and viewers may gain practical knowledge and useful hints by the study of Mr. Morgans' manual."—*Colliery Guardian*.

"A valuable work, which will tend materially to improve our mining literature."—*Mining Journal*.

Coal Mining.

COAL AND COAL MINING: A Rudimentary Treatise on. By Sir WARINGTON W. SMYTH, M.A., F.R.S., &c., Chief Inspector of the Mines of the Crown. New Edition, Revised and Corrected. With numerous Illustrations, 12mo, 4s. cloth boards.

"As an outline is given of every known coal-field in this and other countries, as well as of the principal methods of working, the book will doubtless interest a very large number of readers."—*Mining Journal*.

Subterraneous Surveying.

SUBTERRANEAN SURVEYING, Elementary and Practical Treatise on; with and without the Magnetic Needle. By THOMAS FENWICK, Surveyor of Mines, and THOMAS BAKER, C.E. Illustrated. 12mo, 3s. cloth boards.

NATURAL AND APPLIED SCIENCE.

Text-Book of Electricity.

THE STUDENT'S TEXT-BOOK OF ELECTRICITY. By HENRY M. NOAD, Ph.D., F.R.S., F.C.S. New Edition, carefully Revised. With an Introduction and Additional Chapters, by W. H. PREECE, M.I.C.E., Vice-President of the Society of Telegraph Engineers, &c. With 470 Illustrations. Crown 8vo, 12s. 6d. cloth.

"The original plan of this book has been carefully adhered to so as to make it a reflex of the existing state of electrical science, adapted for students. . . . Discovery seems to have progressed with marvellous strides; nevertheless it has now apparently ceased, and practical applications have commenced their career; and it is to give a faithful account of these that this fresh edition of Dr. Noad's valuable text-book is launched forth."—*Extract from Introduction by W. H. Preece, Esq.*

"We can recommend Dr. Noad's book for clear style, great range of subject, a good index, and a plethora of woodcuts. Such collections as the present are indispensable."—*Athenæum*.

"An admirable text-book for every student—beginner or advanced—of electricity."—*Engineering*.

"Dr. Noad's text-book has earned for itself the reputation of a truly scientific manual for the student of electricity, and we gladly hail this new amended edition, which brings it once more to the front. Mr. Preece as reviser, with the assistance of Mr. H. R. Kempe and Mr. J. P. Edwards, has added all the practical results of recent invention and research to the admirable theoretical expositions of the author, so that the book is about as complete and advanced as it is possible for any book to be, within the limits of a text-book."—*Telegraphic Journal*.

Electricity.

A MANUAL OF ELECTRICITY; including Galvanism, Magnetism, Dia-Magnetism, Electro-Dynamics, Magneto-Electricity, and the Electric Telegraph. By HENRY M. NOAD, Ph.D., F.R.S., F.C.S. Fourth Edition. With 500 Woodcuts. 8vo, £1 4s. cloth.

"The accounts given of electricity and galvanism are not only complete in a scientific sense, but which is a rarer thing, are popular and interesting."—*Lancet*.

"It is worthy of a place in the library of every public institution."—*Mining Journal*.

Electric Light.

ELECTRIC LIGHT: Its Production and Use. Embodying Plain Directions for the Treatment of Voltaic Batteries, Electric Lamps, and Dynamo-Electric Machines. By J. W. URQUHART, C.E., Author of "Electroplating: A Practical Handbook." Edited by F. C. WEBB, M.I.C.E., M.S.T.E. Second Edition, revised, with large Additions and 128 Illustrations. 7s. 6d. cloth.

"The book is by far the best that we have yet met with on the subject."—*Athenaeum*.

"It is the only work at present available, which gives in language intelligible for the most part to the ordinary reader, a general but concise history of the means which have been adopted up to the present time in producing the electric light."—*Metropolitan*.

"The book contains a general account of the means adopted in producing the electric light, not only as obtained from voltaic or galvanic batteries, but treats at length of the dynamo-electric machine in several of its forms."—*Colliery Guardian*.

Electric Lighting.

THE ELEMENTARY PRINCIPLES OF ELECTRIC-LIGHTING.

By ALAN A. CAMPBELL SWINTON, Associate S.T.E. Crown 8vo, 1s. 6d. cloth.

"Anyone who desires a short and thoroughly clear exposition of the elementary principles of electric-lighting cannot do better than read this little work."—*Bradford Observer*.

Dr. Lardner's School Handbooks.

NATURAL PHILOSOPHY FOR SCHOOLS. By Dr. LARDNER. 328 Illustrations. Sixth Edition. One Vol., 3s. 6d. cloth.

"A very convenient class-book for junior students in private schools. It is intended to convey, in clear and precise terms, general notions of all the principal divisions of Physical Science."—*British Quarterly Review*.

ANIMAL PHYSIOLOGY FOR SCHOOLS. By Dr. LARDNER. With 190 Illustrations. Second Edition. One Vol., 3s. 6d. cloth.

"Clearly written, well arranged, and excellently illustrated."—*Gardener's Chronicle*.

Dr. Lardner's Electric Telegraph.

THE ELECTRIC TELEGRAPH. By Dr. LARDNER. Revised and Re-written by E. B. BRIGHT, F.R.A.S. 140 Illustrations. Small 8vo, 2s. 6d. cloth.

"One of the most readable books extant on the Electric Telegraph."—*English Mechanic*.

Storms.

STORMS: Their Nature, Classification, and Laws; with the Means of Predicting them by their Embodiments, the Clouds. By WILLIAM BLASIUS. With Coloured Plates and numerous Wood Engravings. Crown 8vo, 10s. 6d. cloth.

"A very readable book. . . . The fresh facts contained in its pages, collected with evident care, form a useful repository to meteorologists in the study of atmospherical disturbances. . . . The book will repay perusal as being the production of one who gives evidence of acute observation."—*Nature*.

The Blowpipe.

THE BLOWPIPE IN CHEMISTRY, MINERALOGY, AND GEOLOGY. Containing all known Methods of Anhydrous Analysis, many Working Examples, and Instructions for Making Apparatus. By Lieut.-Colonel W. A. ROSS, R.A., F.G.S. With 120 Illustrations. Cr. 8vo, 3s. 6d. cloth.

"The student who goes conscientiously through the course of experimentation here laid down will gain a better insight into inorganic chemistry and mineralogy than if he had 'got up' any of the best text-books of the day, and passed any number of examinations in their contents."—*Chemical News*.

The Military Sciences.

AIDE-MÉMOIRE TO THE MILITARY SCIENCES. Framed from Contributions of Officers and others connected with the different Services. Originally edited by a Committee of the Corps of Royal Engineers. Second Edition, most carefully revised by an Officer of the Corps, with many Additions; containing nearly 350 Engravings and many hundred Woodcuts. Three Vols., royal 8vo, extra cloth boards, and lettered, £4 10s.

"A compendious encyclopedia of military knowledge, to which we are greatly indebted."—*Edinburgh Review*.

"The most comprehensive work of reference to the military and collateral sciences."—*Volunteer Service Gazette*.

Field Fortification.

A TREATISE ON FIELD FORTIFICATION, THE ATTACK OF FORTRESSES, MILITARY MINING, AND RECONNOITRING. By Colonel I. S. MACAULAY, late Professor of Fortification in the R.M.A., Woolwich. Sixth Edition, crown 8vo, cloth, with separate Atlas of 12 Plates, 12s.

Temperaments.

OUR TEMPERAMENTS, THEIR STUDY AND THEIR TEACHING. *A Popular Outline.* By ALEXANDER STEWART, F.R.C.S. Edin. In one large 8vo volume, with 30 Illustrations, including a Selection from Lodge's "Historical Portraits," showing the Chief Forms of Faces. Price 15s. cloth, gilt top.

CONTENTS.

Chap. I. Preliminary.—II. General View of the Temperaments.—III. The Temperaments and Mind.—IV. Scheme of the Four Pure Temperaments.—A Methodical Arrangement of their Physical and Mental Characteristics.—V. Observations on the Scheme.—VI. The Nervous Temperament.—VII. The Compound Temperaments.

—VIII. Modification of the Temperament.—IX. The Organs of the Temperaments.—X. The Temperaments available in Education.—XI. The Choice of a Profession.—XII. The Promotion of Health.—XIII. The Use of the Word Temperament.—XIV. Word, Biographic, or Temperament Portraiture.

"The book is exceedingly interesting, even for those who are not systematic students of anthropology. . . . To those who think the proper study of mankind is man, it will be full of attraction."—*Daily Telegraph*.

"The author's object is to enable a student to read a man's temperament in his aspect. The work is well adapted to its end. It is worthy of the attention of students of human nature."—*Scotsman*.

"The volume is heavy to hold, but light to read. Though the author has treated his subject exhaustively, he writes in a popular and pleasant manner that renders it attractive to the general reader."—*Punch*.

Pneumatics and Acoustics.

PNEUMATICS: including Acoustics and The Phenomena of Wind Currents, for the Use of Beginners. By CHARLES TOMLINSON, F.R.S., F.C.S., &c. Fourth Edition Enlarged. With Numerous Illustrations. 12mo, 1s. 6d. cloth. [Just published.]

"Beginners in the study of this important application of science could not have a better manual."—*Scotsman*.

"A valuable and suitable text-book for students of Acoustics and the Phenomena of Wind Currents."—*Schoolmaster*.

Conchology.

A MANUAL OF THE MOLLUSCA: Being a Treatise on Recent and Fossil Shells. By S. P. WOODWARD, A.L.S., F.G.S., late Assistant Palæontologist in the British Museum. Fifth Edition. With an Appendix on *Recent and Fossil Conchological Discoveries* by RALPH TATE, A.L.S., F.G.S. Illustrated by A. N. WATERHOUSE and JOSEPH WILSON LOWRY. With 23 Plates and upwards of 300 Woodcuts. Crown 8vo, 7s. 6d. cloth boards.

"A most valuable storehouse of conchological and geological information."—*Science Gossip*.

Astronomy.

ASTRONOMY. By the late Rev. ROBERT MAIN, M.A., F.R.S., formerly Radcliffe Observer at Oxford. Third Edition, Revised and Corrected to the present Time, by WILLIAM THYNNE LYNN, B.A., F.R.A.S., formerly of the Royal Observatory, Greenwich. 12mo, 2s. cloth limp.

"A sound and simple treatise, very carefully edited, and a capital book for beginners."—*Knowledge*.

"Accurately brought down to the requirements of the present time by Mr. Lynn."—*Educational Times*.

Geology.

RUDIMENTARY TREATISE ON GEOLOGY, PHYSICAL AND HISTORICAL. Consisting of "Physical Geology," which sets forth the Leading Principles of the Science; and "Historical Geology," which treats of the Mineral and Organic Conditions of the Earth at each successive epoch, especial reference being made to the British Series of Rocks. By RALPH TATE, A.L.S., F.G.S., &c. &c. With 250 Illustrations. 12mo, 5s. cloth boards.

"The fulness of the matter has elevated the book into a manual. Its information is exhaustive and well arranged."—*School Board Chronicle*.

Geology and Genesis.

THE TWIN RECORDS OF CREATION; or, Geology and Genesis, their Perfect Harmony and Wonderful Concord. By GEORGE W. VICTOR LE VAUX. Numerous Illustrations. Fcap. 8vo, 5s. cloth.

"A valuable contribution to the evidences of Revelation, and disposes very conclusively of the arguments of those who would set God's Works against God's Word. No real difficulty is shirked, and no sophistry is left unexposed."—*The Rock*.

"The remarkable peculiarity of this author is that he combines an unbounded admiration of science with an unbounded admiration of the Written record. The two impulses are balanced to a nicety; and the consequence is that difficulties which to minds less evenly poised would be serious find immediate solutions of the happiest kinds."—*London Review*.

DR. LARDNER'S HANDBOOKS OF NATURAL PHILOSOPHY.

THE HANDBOOK OF MECHANICS. Enlarged and almost re-written by BENJAMIN LOEWY, F.R.A.S. With 378 Illustrations. Post 8vo, 6s. cloth.

"The perspicuity of the original has been retained, and chapters which had become obsolete have been replaced by others of more modern character. The explanations throughout are studiously popular, and care has been taken to show the application of the various branches of physics to the industrial arts, and to the practical business of life."—*Mining Journal*.

"Mr. Loewy has carefully revised the book, and brought it up to modern requirements."—*Nature*.

"Natural philosophy has had few exponents more able or better skilled in the art of popularising the subject than Dr. Lardner; and Mr. Loewy is doing good service in fitting this treatise, and the others of the series, for use at the present time."—*Scotsman*.

THE HANDBOOK OF HYDROSTATICS AND PNEUMATICS.

New Edition, Revised and Enlarged by BENJAMIN LOEWY, F.R.A.S. With 236 Illustrations. Post 8vo, 5s. cloth.

"For those 'who desire to attain an accurate knowledge of physical science without the profound methods of mathematical investigation,' this work is not merely intended, but well adapted."—*Chemical News*.

"The volume before us has been carefully edited, augmented to nearly twice the bulk of the former edition, and all the most recent matter has been added. . . . It is a valuable text-book."—*Nature*.

"Candidates for pass examinations will find it, we think, specially suited to their requirements."—*English Mechanic*.

THE HANDBOOK OF HEAT. Edited and almost entirely re-written by BENJAMIN LOEWY, F.R.A.S., &c. 117 Illustrations. Post 8vo, 6s. cloth.

"The style is always clear and precise, and conveys instruction without leaving any cloudiness or lurking doubts behind."—*Engineering*.

"A most exhaustive book on the subject on which it treats, and is so arranged that it can be understood by all who desire to attain an accurate knowledge of physical science. . . . Mr. Loewy has included all the latest discoveries in the varied laws and effects of heat."—*Standard*.

"A complete and handy text-book for the use of students and general readers."—*English Mechanic*.

THE HANDBOOK OF OPTICS. By DIONYSIUS LARDNER, D.C.L., formerly Professor of Natural Philosophy and Astronomy in University College, London. New Edition. Edited by T. OLVER HARDING, B.A. Lond., of University College, London. With 298 Illustrations. Small 8vo, 44s. pages, 5s. cloth.

"Written by one of the ablest English scientific writers, beautifully and elaborately illustrated."—*Mechanic's Magazine*.

THE HANDBOOK OF ELECTRICITY, MAGNETISM, AND ACOUSTICS. By Dr. LARDNER. Ninth Thousand. Edited by GEO. CAREY FOSTER, B.A., F.C.S. With 400 Illustrations. Small 8vo, 5s. cloth.

"The book could not have been entrusted to anyone better calculated to preserve the terse and lucid style of Lardner, while correcting his errors and bringing up his work to the present state of scientific knowledge."—*Popular Science Review*.

* * * The above five volumes, though each is complete in itself, form A COMPLETE COURSE OF NATURAL PHILOSOPHY.

Dr. Lardner's Handbook of Astronomy.

THE HANDBOOK OF ASTRONOMY. Forming a Companion to the "Handbook of Natural Philosophy." By DIONYSIUS LARDNER, D.C.L., formerly Professor of Natural Philosophy and Astronomy in University College, London. Fourth Edition. Revised and Edited by EDWIN DUNKIN, F.R.A.S., Royal Observatory, Greenwich. With 38 Plates and upwards of 100 Woodcuts. In One Vol., small 8vo, 550 pages, 9s. 6d. cloth.

"Probably no other book contains the same amount of information in so compendious and well-arranged a form—certainly none at the price at which this is offered to the public."—*Athenaeum*.

"We can do no other than pronounce this work a most valuable manual of astronomy, and we strongly recommend it to all who wish to acquire a general—but at the same time correct—acquaintance with this sublime science."—*Quarterly Journal of Science*.

"One of the most deservedly popular books on the subject . . . We would recommend not only the student of the elementary principles of the science, but him who aims at mastering the higher and mathematical branches of astronomy, not to be without this work beside him."—*Practical Magazine*.

DR. LARDNER'S MUSEUM OF SCIENCE AND ART.

THE MUSEUM OF SCIENCE AND ART. Edited by DIONYSIUS LARDNER, D.C.L., formerly Professor of Natural Philosophy and Astronomy in University College, London. With upwards of 1,200 Engravings on Wood. In 6 double volumes, £1 1s., in a new and elegant cloth binding; or handsomely bound in half morocco, 31s. 6d.

CONTENTS.

The Planets: Are they Inhabited Worlds?—Weather Prognostics—Popular Fallacies in Questions of Physical Science—Latitudes and Longitudes—Lunar Influences—Meteoric Stones and Shooting Stars—Railway Accidents—Light—Common Things: Air—Locomotion in the United States—Cometary Influences—Common Things: Water—The Potter's Art—Common Things: Fire—Locomotion and Transport, their Influence and Progress—The Moon—Common Things: The Earth—The Electric Telegraph—Terrestrial Heat—The Sun—Earthquakes and Volcanoes—Barometer, Safety Lamp, and Whitworth's Micrometric Apparatus—Steam—The Steam Engine—The Eye—The Atmosphere—Time—Common Things: Pumps—Common Things: Spectacles, the Kaleidoscope—Clocks and Watches—Microscopic Drawing and Engraving—Locomotive—Thermo-

meter—New Planets: Leverrier and Adams's Planet—Magnitude and Minuteness—Common Things: The Almanack—Optical Images—How to observe the Heavens—Common Things: The Looking-glass—Stellar Universe—The Tides—Colour—Common Things: Man—Magnifying Glasses—Instinct and Intelligence—The Solar Microscope—The Camera Lucida—The Magic Lantern—The Camera Obscura—The Microscope—The White Ants: Their Manners and Habits—The Surface of the Earth, or First Notions of Geography—Science and Poetry—The Bee—Steam Navigation—Electro-Motive Power—Thunder, Lightning, and the Aurora Borealis—The Printing Press—The Crust of the Earth—Comets—The Stereoscope—The Pre-Adamite Earth—Eclipses—Sound.

* * OPINIONS OF THE PRESS.

"This series, besides affording popular but sound instruction on scientific subjects, with which the humblest man in the country ought to be acquainted, also undertakes that teaching of 'Common Things' which every well wisher of his kind is anxious to promote. Many thousand copies of this serviceable publication have been printed, in the belief and hope that the desire for instruction and improvement widely prevails; and we have no fear that such enlightened faith will meet with disappointment."—*Times*.

"A cheap and interesting publication, alike informing and attractive. The papers combine subjects of importance and great scientific knowledge, considerable inductive powers, and a popular style of treatment."—*Spectator*.

"The 'Museum of Science and Art' is the most valuable contribution that has ever been made to the scientific instruction of every class of society."—Sir DAVID BRAWSTER, in the *North British Review*.

"Whether we consider the liberality and beauty of the illustrations, the charm of the writing, or the durable interest of the matter, we must express our belief that there is hardly to be found among the new books one that would be welcomed by people of so many ages and classes as a valuable present."—*Examiner*.

* * *Separate books formed from the above, suitable for Workmen's Libraries, Science Classes, &c.*

Common Things Explained. Containing Air, Earth, Fire, Water, Time, Man, the Eye, Locomotion, Colour, Clocks and Watches, &c. 233 Illustrations, cloth gilt, 5s.

The Microscope. Containing Optical Images, Magnifying Glasses, Origin and Description of the Microscope, Microscopic Objects, the Solar Microscope, Microscopic Drawing and Engraving, &c. 147 Illustrations, cloth gilt, 2s.

Popular Geology. Containing Earthquakes and Volcanoes, the Crust of the Earth, &c. 201 Illustrations, cloth gilt, 2s. 6d.

Popular Physics. Containing Magnitude and Minuteness, the Atmosphere, Meteoric Stones, Popular Fallacies, Weather Prognostics, the Thermometer, the Barometer, Sound, &c. 85 Illustrations, cloth gilt, 2s. 6d.

Steam and its Uses. Including the Steam Engine, the Locomotive, and Steam Navigation. 89 Illustrations, cloth gilt, 2s.

Popular Astronomy. Containing How to observe the Heavens. The Earth, Sun, Moon, Planets. Light, Comets, Eclipses, Astronomical Influences, &c. 182 Illustrations, 4s. 6d.

The Bee and White Ants: Their Manners and Habits. With Illustrations of Animal Instinct and Intelligence. 135 Illustrations, cloth gilt, 2s.

The Electric Telegraph Popularized. To render intelligible to all who can Read, irrespective of any previous Scientific Acquirements, the various forms of Telegraphy in Actual Operation. 100 Illustrations, cloth gilt, 1s. 6d.

COUNTING-HOUSE WORK, TABLES, CALCULATORS, etc.**Accounts for Manufacturers.**

FACTORY ACCOUNTS: Their Principles and Practice. A Hand-book for Accountants and Manufacturers, with Appendices on the Nomenclature of Machine Details; the Income Tax Acts; the Rating of Factories; Fire and Boiler Insurance; the Factory and Workshop Acts, &c., including also a Glossary of Terms and a large number of Specimen Rulings. By EMILE GARCKE and J. M. FELLIS. Demy 8vo, 250 Pages. Price 10s. 6d. strongly bound. [Just published.]

"One of the most important works ever published dealing with these matters. The authors have treated the subject from the standpoint of the factory, as practical men speaking to practical men, and not, as has been too often the case, as schoolmasters to schoolboys."—*Electrician*.

"A very interesting description of the requirements of Factory Accounts. . . . The principle of assimilating the Factory Accounts to the general commercial books is one which we thoroughly agree with."—*Accountants' Journal*.

"Characterised by extreme thoroughness. There are few owners of factories who would not derive great benefit from the perusal of this most admirable work."—*Local Government Chronicle*.

Foreign Commercial Correspondence.

THE FOREIGN COMMERCIAL CORRESPONDENT: Being Aids to Commercial Correspondence in Five Languages, English, French, German, Italian, and Spanish. By CHARLES E. BAKER. Crown 8vo. Price about 5s.

[In preparation.]

Intuitive Calculations.

THE COMPENDIOUS CALCULATOR; or, Easy and Concise Methods of Performing the various Arithmetical Operations required in Commercial and Business Transactions, together with Useful Tables. By DANIEL O'GORMAN. Corrected and extended by J. R. YOUNG, formerly Professor of Mathematics at Belfast College. Twenty-sixth Edition, carefully Revised by C. NORRIS. Fcap. 8vo, 3s. 6d. strongly half bound in leather.

"It would be difficult to exaggerate the usefulness of a book like this to everyone engaged in commerce or manufacturing industry. It is crammed full of rules and formulae for shortening and employing calculations."—*Knowledge*.

"Supplies special and rapid methods for all kinds of calculations. Of great utility to persons engaged in any kind of commercial transactions."—*Scotsman*.

Modern Metrical Units and Systems.

MODERN METROLOGY: A Manual of the Metrical Units and Systems of the present Century. With an Appendix containing a proposed English System. By LOWIS D'A. JACKSON, A.M. Inst. C.E., Author of "Aid to Survey Practice," &c. Large crown 8vo, 12s. 6d. cloth.

"The author has brought together much valuable and interesting information. . . . We cannot but recommend the work to the consideration of all interested in the practical reform of our weights and measures."—*Nature*.

"For exhaustive tables of equivalent weights and measures of all sorts, and for clear demonstrations of the effects of the various systems that have been proposed or adopted, Mr. Jackson's treatise is without a rival."—*Academy*.

The Metric System and the British Standards.

A SERIES OF METRIC TABLES, in which the British Standard Measures and Weights are compared with those of the Metric System at present in Use on the Continent. By C. H. DOWLING, C.E. 8vo, 10s. 6d. strongly bound.

"Their accuracy has been certified by Professor Airy, the Astronomer-Royal."—*Builder*.

"Mr. Dowling's Tables are well put together as a ready reckoner for the conversion of one system into the other."—*Athenaeum*.

Iron and Metal Trades' Calculator.

THE IRON AND METAL TRADES' COMPANION: For expeditiously ascertaining the Value of any Goods bought or sold by Weight, from 1s. per cwt. to 112s. per cwt., and from one farthing per pound to one shilling per pound. Each Table extends from one pound to 100 tons; to which are appended Rules on Decimals, Square and Cube Root, Mensuration of Superficies and Solids, &c.; also Tables of Weights of Materials, and other Useful Memoranda. By THOMAS DOWNIE. Strongly bound in leather, 396 pp., 9s.

"A most useful set of tables, and will supply a want, for nothing like them before existed."—*Building News*.

"Although specially adapted to the iron and metal trades, the tables will be found useful in every other business in which merchandise is bought and sold by weight."—*Railway News*.

Calculator for Numbers and Weights Combined.

THE COMBINED NUMBER AND WEIGHT CALCULATOR.

Containing upwards of 250,000 Separate Calculations, showing at a glance the value at 421 different rates, ranging from 1/16th of a Penny to 20s. each, or per cwt., and £20 per ton, of any number of articles consecutively, from 1 to 470.—Any number of cwt., qrs., and lbs., from 1 cwt. to 470 cwt.—Any number of tons, cwt., qrs. and lbs., from 1 to 23½ tons. By WILLIAM CHADWICK, Public Accountant. Imp. 8vo, 30s. strongly bound for Office wear and tear.

☞ *This comprehensive and entirely unique and original Calculator is adapted for the use of Accountants and Auditors, Railway Companies, Canal Companies, Shippers, Shipping Agents, General Carriers, &c.*

Ironfounders, Brassfounders, Metal Merchants, Iron Manufacturers, Ironmongers, Engineers, Machinists, Boiler Makers, Millwrights, Roofing, Bridge and Girder Makers, Colliery Proprietors, &c.

Timber Merchants, Builders, Contractors, Architects, Surveyors, Auctioneers, Valuers, Brokers, Mill Owners and Manufacturers, Mill Furnishers, Merchants, and General Wholesale Tradesmen.

* * OPINIONS OF THE PRESS.

"The book contains the answers to questions, and not simply a set of ingenious puzzle methods of arriving at results. It is as easy of reference for any answer or any number of answers as a dictionary, and the references are even more quickly made. For making up accounts or estimates the book must prove invaluable to all who have any considerable quantity of calculations involving price and measure in any combination to do."—*Engineer*.

"The most complete and practical ready reckoner which it has been our fortune yet to see. It is difficult to imagine a trade or occupation in which it could not be of the greatest use, either in saving human labour or in checking work. The publishers have placed within the reach of every commercial man an invaluable and unfailing assistant."—*The Miller*.

"The most perfect work of the kind yet prepared."—*Glasgow Herald*.

Comprehensive Weight Calculator.

THE WEIGHT CALCULATOR; Being a Series of Tables upon a New and Comprehensive Plan, exhibiting at one Reference the exact Value of any Weight from 1 lb. to 15 tons, at 300 Progressive Rates, from 1d. to 168s. per cwt., and containing 186,000 Direct Answers, which, with their Combinations, consisting of a single addition (mostly to be performed at sight), will afford an aggregate of 10,266,000 Answers; the whole being calculated and designed to ensure correctness and promote despatch. By HENRY HARBEN, Accountant. Fourth Edition, carefully corrected. Royal 8vo, strongly half-bound, £1 5s. [*Just published.*]

"A practical and useful work of reference for men of business generally; it is the best of the kind we have seen."—*Ironmonger*.

"Of priceless value to business men. It is a necessary book in all mercantile offices."—*Sheffield Independent*.

Comprehensive Discount Guide.

THE DISCOUNT GUIDE. Comprising several Series of Tables for the use of Merchants, Manufacturers, Ironmongers, and others, by which may be ascertained the exact Profit arising from any mode of using Discounts, either in the Purchase or Sale of Goods, and the method of either Altering a Rate of Discount, or Advancing a Price, so as to produce, by one operation, a sum that will realise any required profit after allowing one or more Discounts: to which are added Tables of Profit or Advance from 1¼ to 90 per cent., Tables of Discount from 1¼ to 98½ per cent., and Tables of Commission, &c., from ½ to 10 per cent. By HENRY HARBEN, Accountant, Author of "The Weight Calculator." New Edition, carefully Revised and Corrected. Demy 8vo, 544 pp., half-bound, £1 5s.

"A book such as this can only be appreciated by business men, to whom the saving of time means saving of money. We have the high authority of Professor J. R. Young that the tables throughout the work are constructed upon strictly accurate principles. The work is a model of typographical clearness, and must prove of great value to merchants, manufacturers, and general traders."—*British Trade Journal*.

Iron Shipbuilders' and Merchants' Weight Tables.

IRON-PLATE WEIGHT TABLES: For Iron Shipbuilders, Engineers, and Iron Merchants. Containing the Calculated Weights of upwards of 150,000 different sizes of Iron Plates from 1 foot by 6 in. by ¼ in. to 10 feet by 5 feet by 1 in. Worked out on the basis of 40 lbs. to the square foot of Iron of 1 inch in thickness. Carefully compiled, and thoroughly Revised by H. BURLINSON and W. H. SIMPSON. Oblong 4to, 25s. half-bound.

"This work will be found of great utility. The authors have had much practical experience of what is wanting in making estimates, and the use of the book will save much time in making elaborate calculations."—*English Mechanic*.

INDUSTRIAL AND USEFUL ARTS.

Soap-making.

THE ART OF SOAP-MAKING: A Practical Handbook of the Manufacture of Hard and Soft Soaps, Toilet Soaps, &c. Including many New Processes, and a Chapter on the Recovery of Glycerine from Waste Leys. By ALEXANDER WATT, Author of "Electro-Metallurgy Practically Treated," &c. With numerous Illustrations. Third Edition, Revised. Crown 8vo, 7s. 6d. cloth.

"The work will prove very useful, not merely to the technological student, but to the practical soap-boiler who wishes to understand the theory of his art."—*Chemical News*.

"Really an excellent example of a technical manual, entering as it does, thoroughly and exhaustively, both into the theory and practice of soap manufacture. The book is well and honestly done, and deserves the considerable circulation with which it will doubtless meet."—*Knowledge*.

"Mr. Watt's book is a thoroughly practical treatise on an art which has almost no literature in our language. We congratulate the author on the success of his endeavour to fill a void in English technical literature."—*Nature*.

Leather Manufacture.

THE ART OF LEATHER MANUFACTURE: Being a Practical Handbook, in which the Operations of Tanning, Currying, and Leather Dressing are fully Described, and the Principles of Tanning Explained, and many Recent Processes Introduced; as also Methods for the Estimation of Tannin, and a Description of the Arts of Glue Boiling, Gut Dressing, &c. By ALEXANDER WATT, Author of "Soap-Making," "Electro-Metallurgy," &c. With numerous Illustrations. Second Edition. Crown 8vo, 9s. cloth. [Just published.]

"Mr. Watt has rendered an important service to the trade, and no less to the student of technology."—*Chemical News*.

"A sound, comprehensive treatise on tanning and its accessories. The book is an eminently valuable production, which redounds to the credit of both author and publishers."—*Chemical Review*.

"This volume is technical without being tedious, comprehensive and complete without being prosy, and it bears on every page the impress of a master hand. We have never come across a better trade treatise, nor one that so thoroughly supplied an absolute want."—*Shoe and Leather Trades' Chronicle*.

Boot and Shoe Making.

THE ART OF BOOT AND SHOE-MAKING: A Practical Handbook, including Measurement, Last-Fitting, Cutting-Out, Closing and Making, with a Description of the most approved Machinery Employed. By JOHN B. LENO, late Editor of *St. Crispin*, and *The Boot and Shoe-Maker*. With numerous Illustrations. Second Edition. Crown 8vo, 2s. 6d. cloth. [Just published.]

"This excellent treatise is by far the best work ever written on the subject. A new work embracing all modern improvements was much wanted. This want is now satisfied. The chapter on clicking, which shows how waste may be prevented, will save fifty times the price of the book."—*Scottish Leather Trader*.

"This volume is replete with matter well worthy the perusal of boot and shoe manufacturers and experienced craftsmen, and instructive and valuable in the highest degree to all young beginners and craftsmen in the trade of which it treats."—*Leather Trades' Circular*.

Dentistry.

MECHANICAL DENTISTRY: A Practical Treatise on the Construction of the various kinds of Artificial Dentures. Comprising also Useful Formulæ, Tables, and Receipts for Gold Plate, Clasps, Solders, &c. &c. By CHARLES HUNTER. Third Edition, Revised. With upwards of 100 Wood Engravings. Crown 8vo, 3s. 6d. cloth. [Just published.]

"The work is very practical."—*Monthly Review of Dental Surgery*.

"We can strongly recommend Mr. Hunter's treatise to all students preparing for the profession of dentistry, as well as to every mechanical dentist."—*Dublin Journal of Medical Science*.

"A work in a concise form that few could read without gaining information from."—*British Journal of Dental Science*.

Wood Engraving.

A PRACTICAL MANUAL OF WOOD ENGRAVING. With a Brief Account of the History of the Art. By WILLIAM NORMAN BROWN. With numerous Illustrations. Crown 8vo, 2s. cloth.

"The author deals with the subject in a thoroughly practical and easy series of representative lessons."—*Paper and Printing Trades Journal*.


"The book is clear and complete, and will be useful to anyone wanting to understand the first elements of the beautiful art of wood engraving."—*Graphic*.

Paper Making.

A TREATISE ON PAPER; with an Outline of its Manufacture, Complete Tables of Sizes, &c. For Printers and Stationers. By RICHARDSON PARKINSON. 8vo, 3s. cloth; 2s. 6d. paper wrapper.

"An admirable handbook, honestly written by a man who understands his subject."—*Printers Register*.

LOCKWOOD'S HANDYBOOKS FOR HANDICRAFTS.

 These Handybooks are written to supply Handicraftsmen with information on workshop practice, and are intended to convey, in plain language, technical knowledge of the several crafts. Workshop terms are used, and workshop practice described, the text being freely illustrated with drawings of modern tools, appliances and processes, useful alike to the young beginner and to the old hand, whose range of experience has been narrowed under a system of divided labour, as well as to amateurs.

N.B.—The following Volumes are already published, and others are in preparation.

Metal Turning.

THE METAL TURNER'S HANDYBOOK. *A Practical Manual for Workers at the Foot-Lathe:* Embracing information on the Tools, Appliances and Processes employed in Metal Turning. By PAUL N. HASLUCK, A.I.M.E., Author of "Lathe-Work." With upwards of One Hundred Illustrations. Second Edition, Revised. Crown 8vo, 2s. cloth. [Just published.]

"Altogether admirably adapted to initiate students into the art of turning."—*Leicester Post*.

"Clearly and concisely written, excellent in every way, we heartily commend it to all interested in metal turning."—*Mechanical World*.

"With the assistance of a clever master, a clear and vivid expounder, and an abundance of illustrations, the work lets handicraftsmen know what are the resources of the turning-lathe and how these may be developed."—*Dundee Advertiser*.

Wood Turning.

THE WOOD TURNER'S HANDYBOOK. *A Practical Manual for Workers at the Lathe:* Embracing Information on the Tools, Appliances and Processes Employed in Wood Turning. By PAUL N. HASLUCK, A.I.M.E. Author of "Lathe-Work," "The Metal Turner's Handybook," &c. With upwards of One Hundred Illustrations. Crown 8vo, 2s. cloth. [Just published.]

"The volume is well and clearly written in a lucid style, and all the instructions are fully given. It will be found of great value to workmen and amateurs, and forms a safe and reliable guide to every branch of lathe manipulation."—*Carpenter and Builder*.

"An excellent manual for workers at the lathe."—*Glasgow Herald*.

"We recommend the book to young turners and amateurs. A multitude of workmen have hitherto sought in vain for a manual of this special industry."—*Mechanical World*.

Watch Repairing.

THE WATCH JOBBER'S HANDY BOOK. *A Practical Manual on Cleaning, Repairing and Adjusting.* Embracing Information on the Tools, Materials, Appliances and Processes Employed in Watchwork. By PAUL N. HASLUCK, A.I.M.E. Author of "Lathe-Work," "The Metal Turner's Handy-Book," "The Wood Turner's Handybook," &c. With upwards of One Hundred Illustrations. Crown 8vo, 2s. cloth. [Just published.]

"Written in a clear style exactly suited to beginners and amateurs. We heartily recommend it."—*Practical Engineer*.

"We recommend it to craftsmen in watchmaking as a useful and well written grammar of their art."—*Scotsman*.

"All young persons connected with the trade should acquire and study this excellent, and at the same time, inexpensive work."—*Clerkenwell Chronicle*.

Pattern Making.

THE PATTERN MAKER'S HANDYBOOK. *A Practical Manual, embracing Information on the Tools, Materials and Appliances employed in Constructing Patterns for Founders.* By PAUL N. HASLUCK, A.I.M.E. With One Hundred Illustrations. Crown 8vo, 2s. cloth. [Just published.]

"Mr. Hasluck's 'Lathe Work' and kindred productions have acquired a high reputation. His new volume, 'Pattern Making,' contains invaluable advice, and furnishes the studious workman with a very large amount of practical information."—*Lloyd's News*.

"Especially useful to the beginner. We commend it to all who are interested in the counsels it so ably gives."—*Colliery Guardian*.

"This handy volume contains sound information of considerable value to students and artificers."—*Hardware Trade Journal*.

Mechanical Manipulation.

THE MECHANIC'S WORKSHOP HANDYBOOK. *A Practical Manual on Mechanical Manipulation.* Embracing Information on various Handicraft Processes, with Useful Notes and Miscellaneous Memoranda. By PAUL N. HASLUCK, A.I.M.E., Author of "Lathe Work," "The Metal Turner's Handybook," "The Wood Turner's Handybook," &c. Cr. 8vo, 2s. cloth. [Just ready.]

Electrolysis of Gold, Silver, Copper, &c.

ELECTRO-DEPOSITION: A Practical Treatise on the Electrolysis of Gold, Silver, Copper, Nickel, and other Metals and Alloys. With descriptions of Voltaic Batteries, Magneto and Dynamo-Electric Machines, Thermopiles, and of the Materials and Processes used in every Department of the Art, and several Chapters on **ELECTRO-METALLURGY**. By ALEXANDER WATT, Author of "Electro-Metallurgy," &c. With numerous Illustrations. Second Edition, Revised and Corrected. Crown 8vo, 9s., cloth. [Just published.]

"Evidently written by a practical man who has spent a long period of time in electro-plate workshops. The information given respecting the details of workshop manipulation is remarkably complete. . . . Mr. Watt's book will prove of great value to electro-depositors, jewellers, and various other workers in metal."—*Nature*.

"Eminently a book for the practical worker in electro-deposition. It contains minute and practical descriptions of methods, processes and materials, as actually pursued and used in the workshop. Mr. Watt's book recommends itself to all interested in its subjects."—*Engineer*.

Electro-Metallurgy.

ELECTRO-METALLURGY; Practically Treated. By ALEXANDER WATT, F.R.S.S.A. Eighth Edition, Revised, with Additional Matter and Illustrations, including the most recent Processes. 12mo, 3s. 6d. cloth boards.

"From this book both amateur and artisan may learn everything necessary for the successful prosecution of electroplating."—*Iron*.

Electroplating.

ELECTROPLATING: A Practical Handbook. By J. W. URQUHART, C.E. With numerous Illustrations. Crown 8vo, 5s. cloth.

"The information given appears to be based on direct personal knowledge. . . . Its science is sound and the style is always clear."—*Athenæum*.

Electrotyping.

ELECTROTYPING: The Reproduction and Multiplication of Printing Surfaces and Works of Art by the Electro-deposition of Metals. By J. W. URQUHART, C.E. Crown 8vo, 5s. cloth.

"The book is thoroughly practical; the reader is, therefore, conducted through the leading laws of electricity, then through the metals used by electrotypers, the apparatus, and the depositing processes, up to the final preparation of the work."—*Art Journal*.

"We can recommend this treatise, not merely to amateurs, but to those actually engaged in the trade."—*Chemical News*.

Goldsmiths' Work.

THE GOLDSMITH'S HANDBOOK. By GEORGE E. GEE, Jeweller, &c. Third Edition, considerably enlarged. 12mo, 3s. 6d. cloth boards.

"A good, sound, technical educator, and will be generally accepted as an authority. It is essentially a book for the workshop, and exactly fulfils the purpose intended."—*Horological Journal*.

"Will speedily become a standard book which few will care to be without."—*Jeweller and Metal-worker*.

Silversmiths' Work.

THE SILVERSMITH'S HANDBOOK. By GEORGE E. GEE, Jeweller, &c. Second Edition, Revised, with numerous Illusts. 12mo, 3s. 6d. cloth boards.

"The chief merit of the work is its practical character. . . . The workers in the trade will speedily discover its merits when they sit down to study it."—*English Mechanic*.

"This work forms a valuable sequel to the author's 'Goldsmith's Handbook.'"—*Silversmiths' Trade Journal*.

. The above two works together, strongly half-bound, price 7s.

Textile Manufacturers' Tables.

UNIVERSAL TABLES OF TEXTILE STRUCTURE. For the use of Manufacturers in every branch of Textile Trade. By JOSEPH EDMONDSON. Oblong folio, strongly bound in cloth, price 7s. 6d. [Just published.]

These Tables provide what has long been wanted, a simple and easy means of adjusting yarns to "reeds" or "setts," or to "picks" or "shots," and vice versa, so that fabrics may be made of varying weights or fineness, but having the same character and proportions. The principle on which the tables are founded is well-known and much used in the muslin manufacture, but the intricacy of the calculations hitherto required (especially where warp and weft differ in counts and in the closeness of the threads) has prevented its general application. By these tables all the adjustments may be made without calculation. Mere references to the proper places bring out the required information. The tables are universally applicable throughout the whole range of woven fabrics, whatever the material composing them or whatever the mode of numbering their yarns or "setts."

"Immense labour has been bestowed on the work by the author. The tables are adapted to every mode of numbering yarns and setts, and apply to all the branches of textile manufacture."—*Textile Recorder*.

Horology.**A TREATISE ON MODERN HOROLOGY, in Theory and Practice.**

Translated from the French of CLAUDIUS SAUNIER, ex-Director of the School of Horology at Macon, by JULIEN TRIPPLIN, F.R.A.S., Besancon Watch Manufacturer, and EDWARD RIGG, M.A., Assayer in the Royal Mint. With Seventy-Eight Woodcuts and Twenty-Two Coloured Copper Plates. Second Edition. Super-royal 8vo, £2 2s. cloth, £2 10s. half-calf.

"There is no horological work in the English language at all to be compared to this production of M. Saunier's for clearness and completeness. It is alike good as a guide for the student and as a reference for the experienced horologist and skilled workman."—*Horological Journal*.

"The latest, the most complete, and the most reliable of those literary productions to which continental watchmakers are indebted for the mechanical superiority over their English brethren—in fact, the Book of Books, is M. Saunier's 'Treatise.'"—*Watchmaker, Jeweller, and Silversmith*.

"This magnificent treatise is one of the most valuable and comprehensive contributions to the literature of horological art and science ever produced, and cannot be too highly commended. It is a perfect cyclopædia of watch and clockmaking."—*The Coventry Watch and Clockmaker*.

Watchmaking.**THE WATCHMAKERS' HANDBOOK.** Intended as a Workshop

Companion for those engaged in Watchmaking and the Allied Mechanical Arts. Translated from the French of CLAUDIUS SAUNIER, and considerably enlarged by JULIEN TRIPPLIN, F.R.A.S., Vice-President of the Horological Institute, and EDWARD RIGG, M.A., Assayer in the Royal Mint. With Numerous Woodcuts and Fourteen Copper Plates. Second Edition, Revised. With Appendix. Crown 8vo, 9s. cloth. *Just published.*

"Each part is truly a treatise in itself. The arrangement is good and the language is clear and concise. It is an admirable guide for the young watchmaker."—*Engineering*.

"It is impossible to speak too highly of its excellence. It fulfils every requirement in a handbook intended for the use of a workman. Should be found in every workshop."—*Watch and Clockmaker*.

"This book contains an immense number of practical details bearing on the daily occupation of a watchmaker, and it will be found of great use to an army of workers."—*Watchmaker and Metalworker* (Chicago).

CHEMICAL MANUFACTURES AND COMMERCE.**The Alkali Trade, Manufacture of Sulphuric Acid, &c.****A MANUAL OF THE ALKALI TRADE,** including the Manufacture

of Sulphuric Acid, Sulphate of Soda, and Bleaching Powder. By JOHN LOMAS, Alkali Manufacturer, Newcastle-upon-Tyne and London. With 232 Illustrations and Working Drawings, and containing 390 pages of Text. Second Edition, with Additions. Super-royal 8vo, £1 10s. cloth.

"This book is written by a manufacturer for manufacturers. The working details of the most approved forms of apparatus are given, and these are accompanied by no less than 232 wood engravings, all of which may be used for the purposes of construction. Every step in the manufacture is very fully described in this manual, and each improvement explained. Everything which tends to introduce economy into the technical details of this trade receives the fullest attention."—*Athenæum*.

"The author is not one of those clever compilers who, on short notice, will 'read up' any conceivable subject, but a practical man in the best sense of the word. We find here not merely a sound and luminous explanation of the chemical principles of the trade, but a notice of numerous matters which have a most important bearing on the successful conduct of alkali works but which are generally overlooked by even the most experienced technological authors."—*Chemical Review*.

Brewing.**A HANDBOOK FOR YOUNG BREWERS.** By HERBERT EDWARDS

WRIGHT, B.A. Crown 8vo, 3s. 6d. cloth.

"This little volume, containing such a large amount of good sense in so small a compass, ought to recommend itself to every brewery pupil, and many who have passed that stage."—*Brewers' Guardian*.

"The book is very clearly written, and the author has successfully brought his scientific knowledge to bear upon the various processes and details of brewing."—*Brewer*.

Commercial Chemical Analysis.**THE COMMERCIAL HANDBOOK OF CHEMICAL ANALYSIS;**

or, Practical Instructions for the determination of the Intrinsic or Commercial Value of Substances used in Manufactures, in Trades, and in the Arts. By A. NORMANDY, Editor of Rose's "Treatise on Chemical Analysis." New Edition, to a great extent re-written by HENRY M. NOAD, Ph.D., F.R.S. With numerous illustrations. Crown 8vo, 12s. 6d. cloth.

"We strongly recommend this book to our readers as a guide, alike indispensable to the housewife as to the pharmaceutical practitioner."—*Medical Times*.

"Essential to the analysts appointed under the new Act. The most recent results are given, and the work is well edited and carefully written."—*Nature*.

Dye-Wares and Colours.

THE MANUAL OF COLOURS AND DYE-WARES: *Their Properties, Applications, Valuation, Impurities, and Sophistications.* For the use of Dyers, Printers, Drysalers, Brokers, &c. By J. W. SLATER. Second Edition, Revised and greatly Enlarged, crown 8vo, 7s. 6d. cloth.

"A complete encyclopædia of the *materia tinctoria*. The information given respecting each article is full and precise, and the methods of determining the value of articles such as these, so liable to sophistication, are given with clearness, and are practical as well as valuable."—*Chemist and Druggist*.

"There is no other work which covers precisely the same ground. To students preparing for examinations in dyeing and printing it will prove exceedingly useful."—*Chemical News*.

Pigments.

THE ARTISTS' MANUAL OF PIGMENTS. Showing their Composition, Conditions of Permanency, Non-Permanency, and Adulterations; Effects in Combination with Each Other and with Vehicles; and the most Reliable Tests of Purity. Together with the Science and Arts Department's Examination Questions on Painting. By H. C. STANDAGE. Second Edition, Revised. Small crown 8vo, 2s. 6d. cloth. [Just published.]

"This work is indeed *multum in parvo*, and we can, with good conscience, recommend it to all who come in contact with pigments, whether as makers, dealers, or users."—*Chemical Review*.

"This manual cannot fail to be a very valuable aid to all painters who wish their work to endure and be of a sound character; it is complete and comprehensive."—*Spectator*.

"The author supplies a great deal of very valuable information and memoranda as to the chemical qualities and artistic effect of the principal pigments used by painters."—*Builder*.

Gauging. Tables and Rules for Revenue Officers, Brewers, &c.

A POCKET BOOK OF MENSURATION AND GAUGING: Containing Tables, Rules and Memoranda for Revenue Officers, Brewers, Spirit Merchants, &c. By J. B. MANT (Inland Revenue). Oblong 18mo, 4s. leather, with elastic band. [Just published.]

"This handy and useful book is adapted to the requirements of the Inland Revenue Department, and will be a favourite book of reference. The range of subjects is comprehensive, and the arrangement simple and clear."—*Civilian*.

"A most useful book. It should be in the hands of every practical brewer."—*Brewers' Journal*.

AGRICULTURE, FARMING, GARDENING, etc.

Agricultural Facts and Figures.

NOTE-BOOK OF AGRICULTURAL FACTS AND FIGURES FOR FARMERS AND FARM STUDENTS. By PRIMROSE MCCONNELL, Fellow of the Highland and Agricultural Society; late Professor of Agriculture, Glasgow Veterinary College. Third Edition. Royal 32mo, full roan, gilt edges, with elastic band, 4s.

"The most complete and comprehensive Note-book for Farmers and Farm Students that we have seen. It literally teems with information and we can cordially recommend it to all connected with agriculture."—*North British Agriculturist*.

Youatt and Burn's Complete Grazier.

THE COMPLETE GRAZIER, AND FARMER'S AND CATTLE-BREEDER'S ASSISTANT. A Compendium of Husbandry; especially in the departments connected with the Breeding, Rearing, Feeding, and General Management of Stock; the Management of the Dairy, &c. With Directions for the Culture and Management of Grass Land, of Grain and Root Crops, the Arrangement of Farm Offices, the use of Implements and Machines, and on Draining, Irrigation, Warping, &c.; and the Application and Relative Value of Manures. By WILLIAM YOUATT, Esq., V.S. Twelfth Edition, Enlarged by ROBERT SCOTT BURN, Author of "Outlines of Modern Farming," "Systematic Small Farming," &c. One large 8vo Volume, 860 pp., with 244 Illustrations, £1 1s. half-bound.

"The standard and text-book with the farmer and grazier."—*Farmers' Magazine*.

"A treatise which will remain a standard work on the subject as long as British agriculture endures."—*Mark Lane Express* (First Notice).

"The book deals with all departments of agriculture, and contains an immense amount of valuable information. It is, in fact, an encyclopædia of agriculture put into readable form, and it is the only work equally comprehensive brought down to present date. It is excellently printed on thick paper, and strongly bound, and deserves a place in the library of every agriculturist."—*Mark Lane Express* (Second Notice).

"This esteemed work is well worthy of a place in the libraries of agriculturists."—*North British Agriculturist*.

Flour Manufacture, Milling, etc.

FLOUR MANUFACTURE: A Treatise on Milling Science and Practice. By FRIEDRICH KICK, Imperial Regierungsrath, Professor of Mechanical Technology in the Imperial German Polytechnic Institute, Prague. Translated from the Second Enlarged and Revised Edition with Supplement. By H. H. P. POWLES, Assoc. Memb. Institution of Civil Engineers. Nearly 400 pp. Illustrated with 28 Folding Plates, and 167 Woodcuts. Roy. 8vo, 25s., cloth. [*Just published.*]

* * * OPINIONS OF THE PRESS.

"This valuable work is, and will remain, the standard authority on the science of milling. . . . The miller who has read and digested this work will have laid the foundation, so to speak, of a successful career; he will have acquired a number of general principles which he can proceed to apply. In this handsome volume we at last have the accepted text-book of modern milling in good, sound English, which has little, if any, trace of the German idiom."—*The Miller*.

"Professor Kick treats the subject so thoroughly both on its theoretical and practical sides that his work is well suited to be a text-book of technical education anywhere. Mr. H. H. P. Powles's admirable English translation will therefore be welcome to milling engineers here."—*Scotsman*.

"The appearance of this celebrated work in English is very opportune, and British millers will, we are sure, not be slow in availing themselves of its pages."—*Millers' Gazette*.

Small Farming.

SYSTEMATIC SMALL FARMING; or, The Lessons of my Farm. Being an Introduction to Modern Farm Practice for Small Farmers in the Culture of Crops; The Feeding of Cattle; The Management of the Dairy, Poultry and Pigs; The Keeping of Farm Work Records; The Ensilage System, Construction of Silos, and other Farm Buildings; The Improvement of Neglected Farms, &c. By ROBERT SCOTT BURN, Author of "Outlines of Landed Estates' Management," and "Outlines of Farm Management," and Editor of "The Complete Grazier." With numerous Illustrations, crown 8vo, 6s. cloth.

"This is the completest book of its class we have seen, and one which every amateur farmer will read with pleasure, and accept as a guide."—*Field*.

"Mr. Scott Burn's pages are severely practical, and the tone of the practical man is felt throughout. The book can only prove a treasure of aid and suggestion to the small farmer of intelligence and energy."—*British Quarterly Review*.

"The volume contains a vast amount of useful information. No branch of farming is left untouched, from the labour to be done to the results achieved. It may be safely recommended to all who think they will be in paradise when they buy or rent a three-acre farm."—*Glasgow Herald*.

Modern Farming.

OUTLINES OF MODERN FARMING. By R. SCOTT BURN. Soils, Manures, and Crops—Farming and Farming Economy—Cattle, Sheep, and Horses—Management of Dairy, Pigs, and Poultry—Utilization of Town-Sewage, Irrigation, etc. Sixth Edition. In one vol., 1,250 pp., half-bound, profusely Illustrated, 12s.

"The aim of the author has been to make his work at once comprehensive and trustworthy, and in this aim he has succeeded to a degree which entitles him to much credit."—*Morning Advertiser*.

"Eminently calculated to enlighten the agricultural community on the varied subjects of which it treats, and hence it should find a place in every farmer's library."—*City Press*.

"No farmer should be without this book."—*Banbury Guardian*.

Agricultural Engineering.

FARM ENGINEERING, The Complete Text-Book of. Comprising Draining and Embanking; Irrigation and Water Supply; Farm Roads, Fences and Gates; Farm Buildings, their Arrangement and Construction, with Plans and Estimates; Barn Implements and Machines; Field Implements and Machines; Agricultural Surveying, Levelling, &c. By Professor JOHN SCOTT, Editor of the "Farmers' Gazette," late Professor of Agriculture and Rural Economy at the Royal Agricultural College, Cirencester, &c. &c. In one vol., 1,150 pages, half-bound, with over 600 Illustrations, 12s.

"Written with great care, as well as with knowledge and ability. The author has done his work well; we have found him a very trustworthy guide wherever we have tested his statements. The volume will be of great value to agricultural students."—*Mark Lane Express*.

"For a young agriculturist we know of no handy volume likely to be more usefully studied."—*Bell's Weekly Messenger*.

English Agriculture.

THE FIELDS OF GREAT BRITAIN: A Text-Book of Agriculture. Adapted to the Syllabus of the Science and Art Department. For Elementary and Advanced Students. By HUGH CLEMENTS (Board of Trade). 18mo, 2s. 6d. cloth.

"A most comprehensive volume, giving a mass of information."—*Agricultural Economist*.

"It is a long time since we have seen a book which has pleased us more, or which contains such a vast and useful fund of knowledge."—*Educational Times*.

Farm and Estate Book-keeping.

BOOK-KEEPING FOR FARMERS AND ESTATE OWNERS.

A Practical Treatise, presenting, in Three Plans, a System adapted to all Classes of Farms. By JOHNSON M. WOODMAN, Chartered Accountant. Cr. 8vo, 3s. 6d. cloth.

"The volume is a capital study of a most important subject."—*Agricultural Gazette*.

"Will be found of great assistance by those who intend to commence a system of book-keeping, the author's examples being clear and explicit, and his explanations, while full and accurate, being to a large extent free from technicalities."—*Live Stock Journal*.

"The young farmer, land agent, and surveyor will find Mr. Woodman's treatise more than repay its cost and study."—*Building News*.

Farm Account Book.

WOODMAN'S YEARLY FARM ACCOUNT BOOK. Giving a Weekly Labour Account and Diary, and showing the Income and Expenditure under each Department of Crops, Live Stock, Dairy, &c. &c. With Valuation, Profit and Loss Account, and Balance Sheet at the end of the Year, and an Appendix of Forms. Ruled and Headed for Entering a Complete Record of the Farming Operations. By JOHNSON M. WOODMAN, Chartered Accountant, Author of "Book-keeping for Farmers." Folio, 7s. 6d. half-bound.

"Contains every requisite form for keeping farm accounts readily and accurately."—*Agriculture*.

Early Fruits, Flowers and Vegetables.

THE FORCING-GARDEN; or, How to Grow Early Fruits, Flowers, and Vegetables. With Plans and Estimates for Building Glasshouses, Pits and Frames. Containing also Original Plans for Double Glazing, a New Method of Growing the Gooseberry under Glass, &c. &c., and on Ventilation, Protecting Vine Borders, &c. With Illustrations. By SAMUEL WOOD. Crown 8vo, 3s. 6d. cloth.

"A good book, and fairly fills a place that was in some degree vacant. The book is written with great care, and contains a great deal of valuable teaching."—*Gardeners' Magazine*.

"Mr. Wood's book is an original and exhaustive answer to the question, 'How to Grow Early Fruits, Flowers and Vegetables?'"—*Land and Water*.

Good Gardening.

A PLAIN GUIDE TO GOOD GARDENING; or, How to Grow Vegetables, Fruits, and Flowers. With Practical Notes on Soils, Manures, Seeds, Planting, Laying-out of Gardens and Grounds, &c. By S. WOOD. Third Edition, with considerable Additions, &c., and numerous Illustrations. Crown 8vo, 5s. cloth.

"A very good book, and one to be highly recommended as a practical guide. The practical directions are excellent."—*Athenæum*.

"May be recommended to young gardeners, cottagers, and specially to amateurs, for the plain, simple, and trustworthy information it gives on common matters too often neglected."—*Gardeners' Chronicle*.

Gainful Gardening.

MULTUM-IN-PARVO GARDENING; or, How to make One Acre of Land produce £620 a-year, by the Cultivation of Fruits and Vegetables; also, How to Grow Flowers in Three Glass Houses, so as to realise £176 per annum clear Profit. By SAMUEL WOOD, Author of "Good Gardening," &c. Fourth and Cheaper Edition, revised, with Additions. Crown 8vo, 1s. sewed.

"We are bound to recommend it as not only suited to the case of the amateur and gentleman's gardener, but to the market grower."—*Gardeners' Magazine*.

Gardening for Ladies.

THE LADIES' MULTUM-IN-PARVO FLOWER GARDEN, and Amateurs' Complete Guide. With Illusts. By S. WOOD. Cr. 8vo, 3s. 6d. cloth.

"This volume contains a good deal of sound, common-sense instruction."—*Florist*.

"Full of shrewd hints and useful instructions, based on a lifetime of experience."—*Scotsman*.

Receipts for Gardeners.

GARDEN RECEIPTS. Edited by CHARLES W. QUIN. 12mo, 1s. 6d. cloth limp.

"A useful and handy book, containing a good deal of valuable information."—*Athenæum*.

Kitchen Gardening.

THE KITCHEN AND MARKET GARDEN. By Contributors to "The Garden." Compiled by C. W. SHAW, Editor of "Gardening Illustrated."

12mo, 3s. 6d. cloth boards.

"The most valuable compendium of kitchen and market-garden work published."—*Farmer*.

Cottage Gardening.

COTTAGE GARDENING; or, Flowers, Fruits, and Vegetables for Small Gardens. By E. HOBDAY. 12mo, 1s. 6d. cloth limp.

"Contains much useful information at a small charge."—*Glasgow Herald*.

ESTATE MANAGEMENT, AUCTIONEERING, LAW, etc.**Hudson's Land Valuer's Pocket-Book.**

THE LAND VALUER'S BEST ASSISTANT: Being Tables on a very much improved Plan, for Calculating the Value of Estates. With Tables for reducing Scotch, Irish, and Provincial Customary Acres to Statute Measure, &c. By R. HUDSON, C.E. New Edition. Royal 32mo, leather, elastic band, 4s.

"This new edition includes tables for ascertaining the value of leases for any term of years; and for showing how to lay out plots of ground of certain acres in forms, square, round, &c., with valuable rules for ascertaining the probable worth of standing timber to any amount; and is of incalculable value to the country gentleman and professional man."—*Farmers' Journal*.

Ewart's Land Improver's Pocket-Book.

THE LAND IMPROVER'S POCKET-BOOK OF FORMULÆ, TABLES, and MEMORANDA required in any Computation relating to the Permanent Improvement of Landed Property. By JOHN EWART, Land Surveyor and Agricultural Engineer. Second Edition, Revised. Royal 32mo, oblong, leather, gilt edges, with elastic band, 4s.

"A compendious and handy little volume."—*Spectator*.

Complete Agricultural Surveyor's Pocket-Book.

THE LAND VALUER'S AND LAND IMPROVER'S COMPLETE POCKET-BOOK. Consisting of the above Two Works bound together. Leather, gilt edges, with strap, 7s. 6d.

"Hudson's book is the best ready-reckoner on matters relating to the valuation of land and crops, and its combination with Mr. Ewart's work greatly enhances the value and usefulness of the latter-mentioned. . . . It is most useful as a manual for reference."—*North of England Farmer*.

Auctioneer's Assistant.

THE APPRAISER, AUCTIONEER, BROKER, HOUSE AND ESTATE AGENT AND VALUER'S POCKET ASSISTANT, for the Valuation for Purchase, Sale, or Renewal of Leases, Annuities and Reversions, and of property generally; with Prices for Inventories, &c. By JOHN WHEELER, Valuer, &c. Fifth Edition, Re-written and greatly Extended by C. NORRIS, Surveyor, Valuer, &c. Royal 32mo, 5s. cloth.

"A neat and concise book of reference, containing an admirable and clearly-arranged list of prices for inventories, and a very practical guide to determine the value of furniture, &c."—*Standard*.

"Contains a large quantity of varied and useful information as to the valuation for purchase, sale, or renewal of leases, annuities and reversions, and of property generally, with prices for inventories, and a guide to determine the value of interior fittings and other effects."—*Builder*.

Auctioneering.

AUCTIONEERS: Their Duties and Liabilities. By ROBERT SQUIBBS, Auctioneer. Demy 8vo, 10s. 6d. cloth.

"The position and duties of auctioneers treated compendiously and clearly."—*Builder*.

"Every auctioneer ought to possess a copy of this excellent work."—*Ironmonger*.

"Of great value to the profession. . . . We readily welcome this book from the fact that it treats the subject in a manner somewhat new to the profession."—*Estates Gazette*.

Legal Guide for Pawnbrokers.

THE PAWNBROKERS', FACTORS' AND MERCHANTS' GUIDE TO THE LAW OF LOANS AND PLEDGES. With the Statutes and a Digest of Cases on Rights and Liabilities, Civil and Criminal, as to Loans and Pledges of Goods, Debentures, Mercantile and other Securities. By H. C. FOLKARD, Esq., Barrister-at-Law, Author of "The Law of Slander and Libel," &c. With Additions and Corrections to 1876. Fcap. 8vo, 3s. 6d. cloth.

"This work contains simply everything that requires to be known concerning the department of the law of which it treats. We can safely commend the book as unique and very nearly perfect."—*Iron*.

"The task undertaken by Mr. Folkard has been very satisfactorily performed. . . . Such explanations as are needful have been supplied with great clearness and with due regard to brevity."—*City Press*.

How to Invest.

HINTS FOR INVESTORS: Being an Explanation of the Mode of Transacting Business on the Stock Exchange. To which are added Comments on the Fluctuations and Table of Quarterly Average prices of Consols since 1759. Also a Copy of the London Daily Stock and Share List. By WALTER M. PLAYFORD, Sworn Broker. Crown 8vo, 2s. cloth.

"An invaluable guide to investors and speculators."—*Bullionist*.

Metropolitan Rating Appeals.

REPORTS OF APPEALS HEARD BEFORE THE COURT OF GENERAL ASSESSMENT SESSIONS, from the Year 1871 to 1885. By EDWARD RYDE and ARTHUR LYON RYDE. Fourth Edition, brought down to the Present Date, with an Introduction to the Valuation (Metropolis) Act, 1869, and an Appendix by WALTER C. RYDE, of the Inner Temple, Barrister-at-Law. 8vo, 16s. cloth.

"A useful work, occupying a place mid-way between a handbook for a lawyer and a guide to the surveyor. It is compiled by a gentleman eminent in his profession as a land agent, whose specialty, it is acknowledged, lies in the direction of assessing property for rating purposes."—*Land Agents' Record*.

House Property.

HANDBOOK OF HOUSE PROPERTY: A Popular and Practical Guide to the Purchase, Mortgage, Tenancy, and Compulsory Sale of Houses and Land, including the Law of Dilapidations and Fixtures: with Examples of all kinds of Valuations, Useful Information on Building and Suggestive Elucidations of Fine Art. By E. L. TARBUCK, Architect and Surveyor. Fourth Edition, Enlarged. 12mo, 5s. cloth.

"The advice is thoroughly practical."—*Law Journal*.

"This is a well-written and thoughtful work. We commend the work to the careful study of all interested in questions affecting houses and land."—*Land Agents' Record*.

"Carefully brought up to date, and much improved by the addition of a division on fine art."—*Land Agents' Record*.

Inwood's Estate Tables.

TABLES FOR THE PURCHASING OF ESTATES, Freehold, Copyhold, or Leasehold; Annuities, Advowsons, &c., and for the Renewing of Leases held under Cathedral Churches, Colleges, or other Corporate bodies, for Terms of Years certain, and for Lives; also for Valuing Reversionary Estates, Deferred Annuities, Next Presentations, &c.; together with SMART'S Five Tables of Compound Interest, and an Extension of the same to Lower and Intermediate Rates. By W. INWOOD. 22nd Edition, with considerable Additions, and new and valuable Tables of Logarithms for the more Difficult Computations of the Interest of Money, Discount, Annuities, &c., by M. FEDOR THOMAN, of the Société Cr dit Mobilier of Paris. 12mo, 8s. cloth.

"Those interested in the purchase and sale of estates, and in the adjustment of compensation cases, as well as in transactions in annuities, life insurances, &c., will find the present edition of eminent service."—*Engineering*.

"Inwood's Tables' still maintain a most enviable reputation. The new issue has been enriched by large additional contributions by M. F dor Thoman, whose carefully arranged Tables cannot fail to be of the utmost utility."—*Mining Journal*.

Agricultural and Tenant-Right Valuation.

THE AGRICULTURAL AND TENANT-RIGHT-VALUER'S ASSISTANT. A Practical Handbook on Measuring and Estimating the Contents, Weights and Values of Agricultural Produce and Timber, the Values of Estates and Agricultural Labour, Forms of Tenant-Right-Valuations, Scales of Compensation under the Agricultural Holdings Act, 1883, &c. &c. By TOM BRIGHT, Agricultural Surveyor, Author of "The Live Stock of North Devon," &c. Crown 8vo, 3s. 6d. cloth. [Just published.]

"Full of tables and examples in connection with the valuation of tenant-right, estates, labour, contents and weights of timber, and farm produce of all kinds. The book is well calculated to assist the valuer in the discharge of his duty."—*Agricultural Gazette*.

"An eminently practical handbook, full of practical tables and data of undoubted interest and value to surveyors and auctioneers in preparing valuations of all kinds."—*Farmer*.


"Shows at a glance the value of land, crops, and the cost of seeding, harvesting, &c. &c. It is a really practical and useful handbook, for which we anticipate a very large sale."—*Reading Mercury*.

A Complete Epitome of the Laws of this Country.

EVERY MAN'S OWN LAWYER: A Handy-Book of the Principles of Law and Equity. By A BARRISTER. Twenty-fifth Edition. Reconstructed, Thoroughly Revised, and Much Enlarged. Brought down to the end of last Session, and including careful digests of *Coroners Act, 1887*; *Probation of First Offenders Act, 1887*; *Margarine Act, 1887*; *Agricultural Holdings (England) Act, 1883*; *Cottage Gardens (Compensation for Crops) Act, 1887*; *Bankruptcy Act, 1883*; *Allotments Act, 1887*; *Merchandise Trade Marks Act, 1887*; *Truck Amendment Act, 1887*; *Water Companies (Regulation of Powers) Act, 1887*; *Registration of Deeds of Arrangements Act, 1887*. Crown 8vo, 684 pp., price 6s. 8d. (saved at every consultation!), strongly bound in cloth. [Just published.]

*. * THE BOOK WILL BE FOUND TO COMPRISE (AMONGST OTHER MATTER)—

RIGHTS AND WRONGS OF INDIVIDUALS—MERCANTILE AND COMMERCIAL LAW—PARTNERSHIPS—CONTRACTS AND AGREEMENTS—GUARANTIES—PRINCIPALS AND AGENTS—CRIMINAL LAW—PARISH LAW—COUNTY COURT LAW—GAME AND FISHERY LAWS—POOR MEN'S LAWSUITS—LAWS OF BANKRUPTCY—WAGERS—CHEQUES, BILLS, AND NOTES—COPYRIGHT—ELECTIONS AND REGISTRATION—INSURANCE—LIBEL AND SLANDER—MARRIAGE AND DIVORCE—MERCHANT SHIPPING—MORTGAGES—SETTLEMENTS—STOCK EXCHANGE PRACTICE—TRADE MARKS AND PATENTS—TRESPASS—NUISANCES—TRANSFER OF LAND—WILLS, &c. &c. Also LAW for LANDLORD AND TENANT—MASTER AND SERVANT—HEIRS—DEVISEES AND LEGATEES—HUSBAND AND WIFE—EXECUTORS AND TRUSTEES—GUARDIAN AND WARD—MARRIED WOMEN AND INFANTS—LENDER, BORROWER, AND SURETIES—DEBTOR AND CREDITOR—PURCHASER AND VENDOR—COMPANIES—FRIENDLY SOCIETIES—CLERGYMEN—CHURCHWARDENS—MEDICAL PRACTITIONERS—BANKERS—FARMERS—CONTRACTORS—STOCK BROKERS—SPORTSMEN—GAMEKEEPERS—FARRIERS—HORSE DEALERS—AUCTIONEERS—HOUSE AGENTS—INNKEEPERS—BAKERS—MILLERS—PAWNBROKERS—SURVEYORS—RAILWAYS AND CARRIERS—CONSTABLES—SEAMEN—SOLDIERS, ETC. ETC.

 The following subjects may be mentioned as some of those which have received special attention during the present revision:—Marriage of British Subjects Abroad; Police Constables; Pawnbrokers; Intoxicating Liquors Licensing; Domestic Servants; Landlord and Tenant; Vendors and Purchasers; Parliamentary Elections; Municipal Elections; Local Elections; Corrupt Practices at all Elections; Public Health and Local Government and Nuisances; Highways; Churchwardens; Vestry Meetings; Rates.

It is believed that the extensions and amplifications of the present edition, while intended to meet the requirements of the ordinary Englishman, will also have the effect of rendering the book useful to the legal practitioner in the country.

One result of the reconstruction and revision, with the extensive additions thereby necessitated, has been the *enlargement of the book by nearly a hundred and fifty pages*, while the price remains as before.

The PUBLISHERS feel every confidence, therefore, that this standard work will continue to be regarded, as hitherto, as an absolute necessity FOR EVERY MAN OF BUSINESS AS WELL AS EVERY HEAD OF A FAMILY.

*. * OPINIONS OF THE PRESS.

"It is a complete code of English Law written in plain language, which all can understand. Should be in the hands of every business man, and all who wish to abolish lawyers' bills."—*Weekly Times*.

"A useful and concise epitome of the law, compiled with considerable care."—*Law Magazine*.

"A concise, cheap, and complete epitome of the English law. So plainly written that he who runs may read, and he who reads may understand."—*Figaro*.

"A dictionary of legal facts well put together. The book is a very useful one."—*Spectator*.

"A work which has long been wanted, which is thoroughly well done, and which we most cordially recommend."—*Sunday Times*.

"The latest edition of this popular book ought to be in every business establishment, and on every library table."—*Sheffield Post*.

Private Bill Legislation and Provisional Orders.

HANDBOOK FOR THE USE OF SOLICITORS AND ENGINEERS

Engaged in Promoting Private Acts of Parliament and Provisional Orders, for the authorization of Railways, Tramways, Works for the Supply of Gas and Water, and other undertakings of a like character. By L. LIVINGSTON MACASKEY, of the Middle Temple, Barrister-at-Law, and Member of the Institution of Civil Engineers; Author of "Hints on Water Supply." Demy 8vo, 950 pp., price 25s., cloth.

[Just published.]

"The volume is a desideratum on a subject which can be only acquired by practical experience, and the order of procedure in Private Bill Legislation and Provisional Orders is followed. The author's suggestions and notes will be found of great value to engineers and others professionally engaged in this class of practice."—*Building News*.

"The author's double experience as an engineer and barrister has eminently qualified him for the task, and enabled him to approach the subject alike from an engineering and legal point of view. The volume will be found a great help both to engineers and lawyers engaged in promoting Private Acts of Parliament and Provisional Orders."—*Local Government Chronicle*.

January, 1888.

Weale's Rudimentary Series.



London, 1862,
THE PRIZE MEDAL
Was awarded to the Publishers of
"WEALE'S SERIES."



A NEW LIST OF WEALE'S SERIES OF RUDIMENTARY SCIENTIFIC WORKS.

"WEALE'S SERIES includes Text-Books on almost every branch of Science and Industry, comprising such subjects as Agriculture, Architecture and Building, Civil Engineering, Fine Arts, Mechanics and Mechanical Engineering, Physical and Chemical Science, and many miscellaneous Treatises. The whole are constantly undergoing revision, and new editions, brought up to the latest discoveries in scientific research, are constantly issued. The prices at which they are sold are as low as their excellence is assured."—*American Literary Gazette*.

"Amongst the literature of technical education, WEALE'S SERIES has ever enjoyed a high reputation, and the additions being made by Messrs. CROSBY LOCKWOOD & Co. render the series even more complete, and bring the information upon the several subjects down to the present time."—*Mining Journal*.

"Any persons wishing to acquire knowledge cannot do better than look through WEALE'S SERIES and get all the books they require. The Series is indeed an inexhaustible mine of literary wealth."—*The Metropolitan*.

"WEALE'S SERIES has become a standard as well as an unrivalled collection of treatises in all branches of art and science."—*Public Opinion*.

"The excellence of WEALE'S SERIES is now so well appreciated that it would be wasting our space to enlarge upon their general usefulness and value."—*Builder*.

"It is not too much to say that no books have ever proved more popular with or more useful to young engineers and others than the excellent treatises comprised in WEALE'S SERIES."—*Engineer*.

"A standard and popular collection of treatises in all branches of science and art, written by practical men."—*Iron and Coal Trades Review*.

"A collection of technical manuals which is unrivalled."—*Weekly Dispatch*.



Philadelphia, 1876,
THE PRIZE MEDAL
Was awarded to the Publishers for
Books: Rudimentary Scientific,
"WEALE'S SERIES," &c.



CROSBY LOCKWOOD & SON,
7, STATIONERS' HALL COURT, LUDGATE HILL, LONDON, E.C.



WEALE'S RUDIMENTARY SCIENTIFIC SERIES.

* * The volumes of this Series are freely Illustrated with Woodcuts, or otherwise, where requisite. Throughout the following List it must be understood that the books are bound in limp cloth, unless otherwise stated; but the volumes marked with a † may also be had strongly bound in cloth boards for 6d. extra.

N.B.—In ordering from this List it is recommended, as a means of facilitating business and obviating error, to quote the numbers affixed to the volumes, as well as the titles and prices.

CIVIL ENGINEERING, etc.

31. **WELLS AND WELL-SINKING.** By JOHN GEO. SWINDELL, A.R.I.B.A., and G. R. BURNELL, C.E. Revised Edition. With a New Appendix on the Qualities of Water. Illustrated. 2/0
 "Solid practical information, written in a concise and lucid style. The work can be recommended as a text-book for all surveyors, architects, &c."—*Iron and Coal Trades Review*.
35. **THE BLASTING AND QUARRYING OF STONE,** for Building and other Purposes. With Remarks on the Blowing up of Bridges. By Gen. Sir J. BURGOYNE, K.C.B. 1/6
43. **TUBULAR AND OTHER IRON GIRDER BRIDGES,** describing the Britannia and Conway Tubular Bridges. With a Sketch of Iron Bridges, &c. By G. DRYSDALE DEMPSEY, C.E. Fourth Edition . . . 2/0
44. **FOUNDATIONS AND CONCRETE WORKS.** With Practical Remarks on Footings, Planking, Sand, Concrete, Béton, Pile-driving, Caissons, and Cofferdams. By E. DOBSON, M.R.I.B.A. Sixth Edition . . . 1/6
60. **LAND AND ENGINEERING SURVEYING.** For Students and Practical Use. By T. BAKER, C.E. Fourteenth Edition, revised and corrected by J. R. YOUNG, formerly Professor of Mathematics, Belfast College. Illustrated with Plates and Diagrams . . . [Just published 2/0]
- 80*. **EMBANKING LANDS FROM THE SEA.** With Examples and Particulars of actual Embankments, &c. By JOHN WIGGINS, F.G.S. . . 2/0
81. **WATER WORKS,** for the Supply of Cities and Towns. With a Description of the Principal Geological Formations of England as influencing Supplies of Water; and Details of Engines and Pumping Machinery for raising Water. By SAMUEL HUGHES, F.G.S., C.E. Enlarged Edition . . . 4/0†
 "Every one who is debating how his village, town, or city shall be plentifully supplied with pure water should read this book."—*Newcastle Courant*.
117. **SUBTERRANEAN SURVEYING.** By THOMAS FENWICK. Also the Method of Conducting Subterranean Surveys without the use of the Magnetic Needle, and other modern Improvements. By T. BAKER, C.E. 2/6†
118. **CIVIL ENGINEERING IN NORTH AMERICA,** A Sketch of. By DAVID STEVENSON, F.R.S.E., &c. Plates and Diagrams. . . 3/0
167. **A TREATISE ON THE APPLICATION OF IRON TO THE CONSTRUCTION OF BRIDGES, ROOFS, AND OTHER WORKS.** By FRANCIS CAMPIN, C.E. Second Edition 2/6†
 "For numbers of young engineers the book is just the cheap, handy, first guide they want."—*Middlesborough Weekly News*. "Remarkably accurate and well written."—*Artisan*.
197. **ROADS AND STREETS (THE CONSTRUCTION OF),** in Two Parts: I. THE ART OF CONSTRUCTING COMMON ROADS, by H. LAW, C.E., Revised by D. KINNEAR CLARK, C.E.; II. RECENT PRACTICE: Including Pavements of Stone, Wood, and Asphalte. By D. K. CLARK, C.E. 4/6†
 "A book which every borough surveyor and engineer must possess, and which will be of considerable service to architects, builders, and property owners generally."—*Building News*.
203. **SANITARY WORK IN THE SMALLER TOWNS AND IN VILLAGES.** By CHARLES SLAGG, Assoc. M. Inst. C.E. Second Edition, enlarged 3/0†
 "This is a very useful book. There is a great deal of work required to be done in the smaller towns and villages, and this little volume will help those who are willing to do it."—*Builder*.

† The † indicates that these vols. may be had strongly bound at 6d. extra.

Civil Engineering, etc., continued.

212. **THE CONSTRUCTION OF GAS WORKS**, and the Manufacture and Distribution of Coal Gas. By S. HUGHES, C.E. Re-written by WILLIAM RICHARDS, C.E. Seventh Edition, with important Additions . 5/6†
 "The work is exhaustive in its character, and therefore will be found of infinite service alike to manufacturers, distributors, and consumers of the article."—*Foreman Engineer*.
213. **PIONEER ENGINEERING: A Treatise on the Engineering Operations** connected with the Settlement of Waste Lands in New Countries. By EDWARD DOBSON, A.I. C.E. With numerous Plates. Second Edition . 4/6†
 "Mr. Dobson is familiar with the difficulties which have to be overcome in this class of work, and much of his advice will be valuable to young engineers proceeding to our colonies."—*Engineering*.
216. **MATERIALS AND CONSTRUCTION: A Theoretical and Practical Treatise** on the Strains, Designing, and Erection of Works of Construction. By FRANCIS CAMPIN, C.E. Second Edition, carefully revised. 2/0†
 "No better exposition of the practical application of the principles of construction has yet been published to our knowledge in such a cheap comprehensive form."—*Building News*.
219. **CIVIL ENGINEERING**. By HENRY LAW, M. Inst. C.E. Including a Treatise on HYDRAULIC ENGINEERING by G. R. BURNELL, M.I.C.E. Seventh Edition, revised, WITH LARGE ADDITIONS ON RECENT PRACTICE by D. KINNEAR CLARK, M. Inst. C.E. 6s. 6d., cloth boards . 7/6
 "An admirable volume, which we warmly recommend to young engineers."—*Builder*.
 "One of the best rudimentary manuals of engineering in existence."—*Scotsman*.
260. **IRON BRIDGES OF MODERATE SPAN: Their Construction and Erection**. By HAMILTON WELDON PENDRED, late Inspector of Ironwork to the Salford Corporation. With 40 Illustrations . . . 2/0
 "We recommend students and engineers to obtain this book for constant and practical use."—*Colliery Guardian*.

MECHANICAL ENGINEERING, etc.

33. **CRANES**, the Construction of, and other Machinery for Raising Heavy Bodies for the Erection of Buildings, &c. By JOSEPH GLYNN, F.R.S. 1/6
34. **THE STEAM ENGINE**. By Dr. LARDNER. Illustrated . 1/6
59. **STEAM BOILERS: Their Construction and Management**. By R. ARMSTRONG, C.E. Illustrated . . . 1/6
 "A mass of information suitable for beginners."—*Design and Work*.
82. **THE POWER OF WATER**, as applied to drive Flour Mills, and to give motion to Turbines and other Hydrostatic Engines. By JOSEPH GLYNN, F.R.S., &c. New Edition, Illustrated . . . 2/0
98. **PRACTICAL MECHANISM**, and Machine Tools. By T. BAKER, C.E. With Remarks on Tools and Machinery, by J. NASMYTH, C.E. 2/6†
139. **THE STEAM ENGINE**, a Treatise on the Mathematical Theory of, with Rules and Examples for Practical Men. By T. BAKER, C.E. 1/6
 "This volume, by Mr. Baker, a well-known authority, teems with scientific information in reference to the expansion of steam and the duty of the steam-engine, &c., &c."—*Design and Work*.
164. **MODERN WORKSHOP PRACTICE**, as applied to Marine, Land, and Locomotive Engines, Floating Docks, Dredging Machines, Bridges, Cranes, Ship-building, &c. &c. By J. G. WINTON. Illustrated . . . 3/0†
 "Whether for the apprentice determined to master his profession, or for the artisan bent upon raising himself to a higher position, this clearly written and practical treatise will be a great help."—*Scotsman*.
165. **IRON AND HEAT**, exhibiting the Principles concerned in the Construction of Iron Beams, Pillars, and Bridge Girders, and the Action of Heat in the Smelting Furnace. By J. ARMOUR, C.E. Numerous Woodcuts. 2/6;
 "A very useful and thoroughly practical little volume."—*Mining Journal*.
166. **POWER IN MOTION: Horse-power Motion, Toothed-Wheel Gearing, Long and Short Driving Bands, Angular Forces, &c.** By JAMES ARMOUR, C.E. With 73 Diagrams. Third Edition . . . 2/0†
 "The value of the theoretic and practical knowledge imparted cannot well be over-estimated."—*Newcastle Weekly Chronicle*.
171. **THE WORKMAN'S MANUAL OF ENGINEERING DRAWING**. By JOHN MAXTON, Instructor in Engineering Drawing, Royal Naval College, Greenwich. Sixth Edition. 300 Plates and Diagrams. 3/6;
 "A copy of it should be kept for reference in every drawing office."—*Engineering*.

† The † indicates that these vols. may be had strongly bound at 6d. extra.

Mechanical Engineering, etc., continued.

190. **STEAM AND THE STEAM ENGINE**, Stationary and Portable, An Elementary Treatise on. Being an Extension of Mr. Sewell's Treatise on Steam. By D. K. CLARK, C.E. Third Edition . . . 3/6†
 "Every essential part of the subject is treated of competently, and in a popular style."—*Iron*.
200. **FUEL, ITS COMBUSTION AND ECONOMY**. Consisting of an Abridgment of "A Treatise on the Combustion of Coal and the Prevention of Smoke." By C. W. WILLIAMS, A.I.C.E. With extensive Additions by D. KINNEAR CLARK, M. Inst. C.E. Third Edition, corrected 3/6†
 "Students should buy the book and read it, as one of the most complete and satisfactory treatises on the combustion and economy of fuel to be had."—*Engineer*.
202. **LOCOMOTIVE ENGINES**, A Rudimentary Treatise on. By G. D. DEMPSEY, C.E. With large Additions treating of the Modern Locomotive, by D. K. CLARK, M. Inst. C.E. With numerous Illustrations . . . 3/0†
 "A model of what an elementary technical book should be."—*Academy*.
211. **THE BOILERMAKER'S ASSISTANT** in Drawing, Tempering, and Calculating Boiler Work, &c. By J. COURTNEY, Practical Boilermaker. Edited by D. K. CLARK, C.E. Second Edition, revised . . . 2/0
 "With very great care we have gone through the 'Boilermaker's Assistant,' and have to say that has our unqualified approval. Scarcely a point has been omitted."—*Foreman Engineer*.
217. **SEWING MACHINERY**: Its Construction, History, &c. With full Technical Directions for Adjusting, &c. By J. W. URQUHART, C.E. 2/0†
 "A full description of the principles and construction of the leading machines, and minute instructions as to their management."—*Scotsman*.
223. **MECHANICAL ENGINEERING**. Comprising Metallurgy, Moulding, Casting, Forging, Tools, Workshop Machinery, Mechanical Manipulation, Manufacture of the Steam Engine, &c. By FRANCIS CAMPIN, C.E. . . . 2/6†
 "A sound and serviceable text-book, quite up to date."—*Building News*.
236. **DETAILS OF MACHINERY**. Comprising Instructions for the Execution of various Works in Iron in the Fitting-Shop, Foundry, and Boiler-Yard. By FRANCIS CAMPIN, C.E. . . . 3/0†
 "A sound and practical handbook for all engaged in the engineering trades."—*Building World*.
237. **THE SMITHY AND FORGE**, including the Farrier's Art and Coach Smithing. By W. J. E. CRANE. Second Edition, revised . . . 2/6†
 "The first modern English book on the subject. Great pains have been bestowed by the author upon the book; shoeing smiths will find it both useful and interesting."—*Builder*.
238. **THE SHEET-METAL WORKER'S GUIDE**: A Practical Handbook for Tinsmiths, Coppersmiths, Zincworkers, &c., with 46 Diagrams and Working Patterns. By W. J. E. CRANE. Second Edition, revised. [Just published. 1/6
 "The author has acquitted himself with considerable tact in choosing his examples, and with no less ability in treating them."—*Plumber*.
251. **STEAM AND MACHINERY MANAGEMENT**: A Guide to the Arrangement and Economical Management of Machinery, with Hints on Construction and Selection. By M. POWIS BALE, M. Inst. M.E. 2/6†
 "Of high practical value."—*Colliery Guardian*.
 "Gives the results of wide experience."—*Lloyd's Newspaper*.
254. **THE BOILER-MAKER'S READY RECKONER**, with Examples of Practical Geometry and Templating for the Use of Platers, Smiths, and Riveters. By JOHN COURTNEY. Edited by D. K. CLARK, M.I.C.E. Second Edition, revised, with Additions . . . 4/0
 "The above, strongly half-bound, price 5s.
 "A most useful work. No workman or apprentice should be without it."—*Iron Trade Circular*.
255. **LOCOMOTIVE ENGINE-DRIVING**. A Practical Manual for Engineers in charge of Locomotive Engines. By MICHAEL REYNOLDS, M.S.E. Eighth Edition. 3s. 6d. limp; cloth boards . . . 4/6
 "We can confidently recommend the book, not only to the practical driver, but to everyone who takes an interest in the performance of locomotive engines."—*The Engineer*.
256. **STATIONARY ENGINE-DRIVING**. A Practical Manual for Engineers in charge of Stationary Engines. By MICHAEL REYNOLDS, M.S.E. Third Edition. 3s. 6d. limp; cloth boards . . . 4/6
 "The author is thoroughly acquainted with his subjects, and has produced a manual which is an exceedingly useful one for the class for whom it is specially intended."—*Engineering*.

† The † indicates that these vols. may be had strongly bound at 6d. extra.

MINING, METALLURGY, etc.

4. **MINERALOGY**, Rudiments of: A concise View of the General Properties of Minerals. By A. RAMSAY, F.G.S. Third Edition, revised and enlarged. Woodcuts and Plates . . . 3/6½
- "The author throughout has displayed an intimate knowledge of his subject, and great facility in imparting that knowledge to others. The book is of great utility."—*Mining Journal*.
117. **SUBTERRANEAN SURVEYING**, with and without the Magnetic Needle. By T. FENWICK and T. BAKER, C.E. Illustrated . . . 2/6½
133. **METALLURGY OF COPPER**: An Introduction to the Methods of Seeking, Mining, and Assaying Copper, and Manufacturing its Alloys. By ROBERT H. LAMBORN, Ph.D. Woodcuts. . . 2/6½
135. **ELECTRO-METALLURGY**, Practically Treated. By ALEXANDER WATT. Eighth Edition, including the most Recent Processes . . . 3/0½
- "From this book both amateur and artisan may learn everything necessary."—*Iron*.
172. **MINING TOOLS**, Manual of. By WILLIAM MORGANS, Lecturer on Practical Mining at the Bristol School of Mines . . . 2/6½
- 172*. **MINING TOOLS, ATLAS** of Engravings to Illustrate the above, containing 235 Illustrations of Mining Tools, drawn to Scale. 4to. . . 4/6
- "Students in the Science of Mining, and Overmen, Captains, Managers, and Viewers may practical knowledge and useful hints by the study of Mr. Morgans' Manual."—*Colliery Guardian*.
176. **METALLURGY OF IRON**. Containing History of Iron Manufacture, Methods of Assay, and Analyses of Iron Ores, Processes of Manufacture of Iron and Steel, &c. By H. BAUERMAN, F.G.S., A.R.S.M. With numerous Illustrations. Fifth Edition, revised and much enlarged. . . 5/0½
- "Carefully written, it has the merit of brevity and conciseness, as to less important points; while all material matters are very fully and thoroughly entered into."—*Standard*.
180. **COAL AND COAL MINING**, A Rudimentary Treatise on. By WARINGTON W. SMYTH, M.A., F.R.S., &c., Chief Inspector of the Mines of the Crown. Sixth Edition, revised and enlarged. With numerous Illusts. 3/6½
- "Every portion of the volume appears to have been prepared with much care, and as an outline is given of every known coal-field in this and other countries, as well as of the two principal methods of working, the book will doubtless interest a very large number of readers."—*Mining Journal*.
195. **THE MINERAL SURVEYOR AND VALUER'S COMPLETE GUIDE**. Comprising a Treatise on Improved Mining Surveying and the Valuation of Mining Properties, with New Traverse Tables. By W. LINTNER, Mining and Civil Engineer. Second Edition, with an Appendix on Magnetic and Angular Surveying, with Records of the Peculiarities of Needle Disturbances. With Four Plates of Diagrams, Plans, &c. [Just published. 3/6½]
- "Contains much valuable information, and is thoroughly trustworthy."—*Iron & Coal Trades Review*.
214. **SLATE AND SLATE QUARRYING**, Scientific, Practical, and Commercial. By D. C. DAVIES, F.G.S., Mining Engineer, &c. With numerous Illustrations and Folding Plates. Third Edition . . . 3/0½
- "One of the best and best-balanced treatises on a special subject, having at once scientific, practical, and commercial relations, that we have met with."—*Engineer*.

ARCHITECTURE, BUILDING, etc.

16. **ARCHITECTURE—ORDERS**—The Orders and their Æsthetic Principles. By W. H. LEEDS. Illustrated . . . 1/6
17. **ARCHITECTURE—STYLES**—The History and Description of the Styles of Architecture of Various Countries, from the Earliest to the Present Period. By T. TALBOT BURY, F.R.I.B.A., &c. Illustrated . . . 2/0
- *. * ORDERS AND STYLES OF ARCHITECTURE, in One Vol., 3s. 6d.
18. **ARCHITECTURE—DESIGN**—The Principles of Design in Architecture, as deducible from Nature and exemplified in the Works of the Greek and Gothic Architects. By EDW. LACY GARBETT, Architect. Illustrated 2/6
- "We know no work that we would sooner recommend to an attentive reader desirous to obtain clear views of the nature of architectural art. The book is a valuable one."—*Builder*.
- *. * The three preceding Works in One handsome Vol., half bound, entitled "MODERN ARCHITECTURE," price 6s.

☞ The † indicates that these vols. may be had strongly bound at 6d. extra.

Architecture, Building, etc., continued.

22. **THE ART OF BUILDING**, Rudiments of. General Principles of Construction, Strength and Use of Materials, Working Drawings, Specifications, &c. By EDWARD DOBSON, M.R.I.B.A., &c. 2/0†
 "A good book for practical knowledge, and about the best to be obtained."—*Building News*.
25. **MASONRY AND STONECUTTING**: The Principles of Masonic Projection and their application to Construction. By E. DOBSON, M.R.I.B.A. 2/6†
42. **COTTAGE BUILDING**. By C. BRUCE ALLEN. Tenth Edition, with a Chapter on Economic Cottages for Allotments, by EDWARD E. ALLEN, C.E. 2/0
45. **LIMES, CEMENTS, MORTARS, CONCRETES, MAS-TICS, PLASTERING, &c.** By G. R. BURNELL, C.E. Thirteenth Edition 1/6
57. **WARMING AND VENTILATION** of Domestic and Public Buildings, Mines, Lighthouses, Ships, &c. By CHARLES TOMLINSON, F.R.S. 3/0
111. **ARCHES, PIERS, BUTTRESSES, &c.**: Experimental Essays on the Principles of Construction in. By WILLIAM BLAND . . . 1/6
116. **THE ACOUSTICS OF PUBLIC BUILDINGS**; or, The Principles of the Science of Sound applied to the purposes of the Architect and Builder. By T. ROGER SMITH, M.R.I.B.A., Architect. Illustrated . . . 1/6
127. **ARCHITECTURAL MODELLING IN PAPER**, The Art of. By T. A. RICHARDSON. With Illustrations, engraved by O. JEWITT . . . 1/6
 "A valuable aid to the practice of architectural modelling."—*Builder's Weekly Reporter*.
128. **VITRUVIUS—THE ARCHITECTURE OF MARCUS VITRUVIUS POLLO**. In Ten Books. Translated from the Latin by JOSEPH GWILT, F.S.A., F.R.A.S. With 23 Plates 5/0
N.B.—This is the only Edition of VITRUVIUS procurable at a moderate price.
130. **GRECIAN ARCHITECTURE**, An Inquiry into the Principles of Beauty in; with an Historical View of the Rise and Progress of the Art in Greece. By the EARL OF ABERDEEN. 1/0
- * * The two preceding Works in One handsome Vol., half bound, entitled "ANCIENT ARCHITECTURE," price 6s.
132. **DWELLING-HOUSES**, The Erection of, Illustrated by a Perspective View, Plans, Elevations, and Sections of a Pair of Villas, with the Specification, Quantities, and Estimates. By S. H. BROOKS, Architect . . 2/6†
156. **QUANTITIES AND MEASUREMENTS**, in Bricklayers', Masons', Plasterers', Plumbers', Painters', Paperhangers', Gilders', Smiths', Carpenters' and Joiners' Work. By A. C. BEATON, Surveyor 1/6
 "This book is indispensable to builders and their quantity clerks."—*English Mechanic*.
175. **LOCKWOOD'S BUILDER'S AND CONTRACTOR'S PRICE BOOK** for 1888; containing the latest Prices of Materials and Labour, and in all Trades connected with Building. With many useful Memoranda and Tables; Revised and Edited by F. T. W. MILLER, A.R.I.B.A. 3/6†
 "Recognised as an authority on matters connected with materials and labour."—*Leeds Mercury*.
 "Admits of easy reference, and contains ample information on all points connected with the building and contracting businesses."—*Builders' Weekly Reporter*.
- CARPENTRY AND JOINERY—THE ELEMENTARY PRINCIPLES OF CARPENTRY**. Chiefly composed from the Standard Work of THOMAS TREDGOLD, C.E. With Additions, and a TREATISE ON JOINERY by E. W. TARN, M.A. Fourth Edition, Revised and Extended . . 3/6†
- 182*. **CARPENTRY AND JOINERY. ATLAS** of 35 Plates to accompany and illustrate the foregoing book. With Descriptive Letterpress. 4to 6/0
 "These two volumes form a complete treasury of carpentry and joinery, and should be in the hands of every carpenter and joiner in the empire."—*Iron*.
185. **THE COMPLETE MEASURER**; setting forth the Measurement of Boards, Glass, Timber and Stone. By R. HORTON. Fifth Edition . 4/0
 * * The above, strongly bound in leather, price 5s.
- "We recommend the work to all foresters, and all who buy or sell timber, who will find it a handy, correct, and valuable companion."—*Journal of Forestry*.

† The † indicate that these vols. may be had strongly bound at 6d. extra.

Architecture, Building, etc., continued.

187. **HINTS TO YOUNG ARCHITECTS.** By GEORGE WIGHTWICK, Architect, Author of "The Palace of Architecture," &c., &c. Fifth Edition, revised and enlarged by G. HUSKISSON GUILLAUME, Architect. 3/6½
 "A copy ought to be considered as necessary a purchase as a box of instruments."—*Architect*.
188. **HOUSE PAINTING, GRAINING, MARBLING, AND SIGN WRITING:** With a Course of Elementary Drawing, and a Collection of Useful Receipts. By ELLIS A. DAVIDSON. Fourth Edition. Coloured Plates 10
 "The above in cloth boards, strongly bound, 6s.
 "A mass of information of use to the amateur and of value to the practical man."—*English Mechanic*.
189. **THE RUDIMENTS OF PRACTICAL BRICKLAYING.**
 General Principles of Bricklaying; Arch Drawing, Cutting, and Setting; Pointing; Paving, Tiling, &c. By ADAM HAMMOND. With 68 Woodcuts. 1/6
 "The young bricklayer will find it infinitely valuable to him."—*Glasgow Herald*.
191. **PLUMBING:** A Text-Book to the Practice of the Art or Craft of the Plumber, with above 330 Illustrations. By WM. PATON BUCHAN, Sanitary Engineer. Fourth Edition, revised and enlarged. 3/6½
 "A text-book which may be safely put into the hands of every young plumber, and which will also be found useful by architects and medical professors."—*Builder*.
192. **THE TIMBER IMPORTER'S, TIMBER MERCHANT'S, AND BUILDER'S STANDARD GUIDE.** By RICHARD E. GRANDY. Third Edition, revised. 2/0
 "Everything it pretends to be: built up gradually, it leads one from a forest to a treenail, and throws in, as a makeweight, a host of material concerning bricks, columns, cisterns, &c."—*English Mechanic*.
206. **A BOOK ON BUILDING, Civil and Ecclesiastical.** By Sir EDMUND BECKETT, Bart., LL.D., Q.C., F.R.A.S., Author of "Clocks and Watches and Bells," &c. Second Edition, enlarged. 4/6½
 "A book which is always amusing and nearly always instructive. The style throughout is in the highest degree condensed and epigrammatic."—*Times*.
226. **THE JOINTS MADE AND USED BY BUILDERS.**
 By WYVILL J. CHRISTY, Architect. With 160 Woodcuts. 3/0½
 "The work is deserving of high commendation."—*Builder*.
228. **THE CONSTRUCTION OF ROOFS, OF WOOD AND IRON:** Deduced chiefly from the Works of Robison, Tredgold, and Humber. By E. WYNDHAM TARN, M.A., Architect. Second Edition, revised. 1/6
 "Mr. Tarn is so thoroughly master of his subject, that although the treatise is founded on the works of others, he has given it a distinct value of his own. It will be found valuable by all students."—*Builder*.
229. **ELEMENTARY DECORATION:** As applied to Dwelling Houses, &c. By JAMES W. FACEY. Illustrated. 2/0
 "The principles which ought to guide the decoration of dwelling-houses are clearly set forth, and elucidated by examples; while full instructions are given to the learner."—*Scotsman*.
257. **PRACTICAL HOUSE DECORATION.** A Guide to the Art of Ornamental Painting, the Arrangement of Colours in Apartments, and the Principles of Decorative Design. By JAMES W. FACEY. 2/6
 "Nos. 229 and 257 in One handsome Vol., half-bound, entitled "HOUSE DECORATION, ELEMENTARY AND PRACTICAL," price 5s.
230. **A PRACTICAL TREATISE ON HANDRAILING;**
 Showing New and Simple Methods. By GEO. COLLINGS. With Plates. 1/6
 "Will be found of practical utility in the execution of this difficult branch of joinery."—*Builder*.
247. **BUILDING ESTATES:** A Treatise on the Development, Sale, Purchase, and Management of Building Land. By F. MAITLAND. Second Edition, revised. 2/0
 "This book should undoubtedly be added to the library of every professional man dealing with building land."—*Land Agent's Record*.
248. **PORTLAND CEMENT FOR USERS.** By HENRY FAIJA, A.M. Inst. C.E. Second Edition, Corrected. 2/0
 "Supplies in a small compass all that is necessary to be known by users of cement."—*Building News*.
252. **BRICKWORK:** A Practical Treatise, embodying the General and Higher Principles of Bricklaying, Cutting and Setting; with the Application of Geometry to Roof Tiling, &c. By F. WALKER. 1/6
 "Contains all that a young tradesman or student needs to learn from books."—*Building News*.
259. **GAS FITTING:** A Practical Handbook. By JOHN BLACK. With 122 Illustrations. 2/6½
 "Contains all the requisite information for the successful fitting of houses for a gas service, &c. It is written in a simple practical style, and we heartily recommend it."—*Plumber and Decorator*.

☞ The † indicates that these vols. may be had strongly bound at 6d. extra.

Architecture, Building, etc., continued.

253. **THE TIMBER MERCHANT'S, SAW MILLER'S, AND IMPORTER'S FREIGHT BOOK AND ASSISTANT.** By WILLIAM RICHARDSON, Timber Broker; together with a Chapter on "Speeds of Saw-Mill Machinery, by M. POWIS BALE, M.I.M.E., &c. . . 3/0†
 "A compendium of calculations which supplies a real want in the trade."—*Building News*.
23. **THE PRACTICAL BRICK AND TILE BOOK.** Com-
 189. {prising: BRICK AND TILE MAKING, by E. DOBSON, A.I.C.E.; Practical
 252. {BRICKLAYING, by A. HAMMOND; BRICKWORK, by F. WALKER. 550 pp.
 with 270 Illustrations, strongly half-bound . . . 6/0
258. **CIRCULAR WORK IN CARPENTRY AND JOINERY.**
 A Practical Treatise on Circular Work of Single and Double Curvature. By
 GEORGE COLLINGS, Author of "A Treatise on Handrailing," &c. . . 2/6
 "This is an excellent example of what a book of this kind should be—cheap in price, clear in de-
 finition, and practical in the examples selected."—*Builder*.
261. **SHORING, and Its Application: A Handbook for the Use of**
 Students. By GEORGE H. BLAGROVE. With 31 Illustrations . . . 1/6
 "The author treats his subject in a sound and practical way."—*English Mechanic*.
 "We recommend this valuable treatise to all students."—*Building News*.

SHIPBUILDING, NAVIGATION, etc.

51. **NAVAL ARCHITECTURE**, an Exposition of the Elemen-
 tary Principles of the Science, and their Practical Application. By JAMES
 PEAKE, School of N. A., H.M. Dockyard, Portsmouth. . . 3/6†
53. **SHIPS FOR OCEAN AND RIVER SERVICE**, Elementary
 and Practical Principles of the Construction of. By HAKON A. SOMMERFELDT. 1/6
- 53**. **AN ATLAS OF ENGRAVINGS** to Illustrate the above.
 Twelve large folding Plates. Royal 4to, cloth. . . 7/6
54. **MASTING, MAST-MAKING, AND RIGGING OF**
SHIPS. Also Tables of Spars, Rigging, Blocks; Chain, Wire, and Hemp
 Ropes, &c., relative to every class of vessels. By ROBERT KIPPING, N.A. 2/0
- 54*. **IRON SHIP-BUILDING.** With Practical Examples and
 Details. By JOHN GRANTHAM. Fifth Edition . . . 4/0
55. **THE SAILOR'S SEA BOOK: A Rudimentary Treatise on**
 Navigation. By JAMES GREENWOOD, B.A. With numerous Woodcuts
 and Coloured Plates. New and enlarged Edition. By W. H. ROSSER . . 2/6†
 "Is perhaps the best and simplest epitome of navigation ever compiled."—*Field*.
- 55 & **PRACTICAL NAVIGATION.** Consisting of THE SAILOR'S
 204. & SEA-BOOK, by JAMES GREENWOOD and W. H. ROSSER; together with
 Mathematical and Nautical Tables for the Working of the Problems, by
 HENRY LAW, C.E., and Professor J. R. YOUNG. 12mo, strongly half-bound
 in leather . . . 7/0
 "A vast amount of information is contained in this volume, and we fancy in a very short time that it
 will be seen in the library of almost every ship or yacht afloat."—*Hunt's Yachting Magazine*.
80. **MARINE ENGINES AND STEAM VESSELS.** By
 ROBERT MURRAY, C.E., Principal Officer to the Board of Trade for the East
 Coast of Scotland District. Eighth Edition, thoroughly Revised, with Addi-
 tions by the Author and by GEORGE CARLISLE, C.E., Senior Surveyor to the
 Board of Trade, Liverpool . . 4/6†
 "Of great value to engineers in both the Royal and Mercantile navies."—*Broad Arrow*.
 "It is an indispensable manual for the student of marine engineering."—*Liverpool Mercury*.
- 83bis. **THE FORMS OF SHIPS AND BOATS.** By W. BLAND.
 Seventh Edition, revised, with numerous Illustrations and Models. . . 1/6
99. **NAVIGATION AND NAUTICAL ASTRONOMY**, in
 Theory and Practice. By Prof. J. R. YOUNG. New Edition. Illustrated. 2/6
 "A very complete, thorough, and useful manual for the young navigator."—*Observatory*.
106. **SHIPS' ANCHORS**, a Treatise on. By GEORGE COTSELL. 1/6
149. **SAILS AND SAIL-MAKING.** With Draughting, and the
 Centre of Effort of the Sails. Also, Weights and Sizes of Ropes; Mast-
 ing, Rigging, and Sails of Steam Vessels, &c. By ROBERT KIPPING, N.A. . . 2/6†
155. **THE ENGINEER'S GUIDE TO THE ROYAL AND**
MERCANTILE NAVIES. By a PRACTICAL ENGINEER. Revised by
 D. F. M'CARTHY, late of the Ordnance Survey Office, Southampton . . 3/0

✂ The † indicates that these vols. may be had strongly bound at 6d. extra.

AGRICULTURE, GARDENING, etc.

- 61*. **A COMPLETE READY RECKONER FOR THE ADMEASUREMENT OF LAND, &c.** By A. ARMAN. Third Edition, revised and extended by C. NORRIS, Surveyor, Valuer, &c. 2/0
 "A very useful book to all who have land to measure."—*Mark Lane Express*.
 "Should be in the hands of all persons having any connection with land."—*Irish Farm*.
131. **MILLER'S, CORN MERCHANT'S, AND FARMER'S READY RECKONER.** Second Edition, revised, with a Price List of Modern Flour Mill Machinery, by W. S. HUTTON, C.E. 2/0
 "Will prove an indispensable *vade mecum*. Nothing has been spared to make the book complete and perfectly adapted to its special purpose."—*Miller*.
140. **SOILS, MANURES, AND CROPS.** (Vol. I. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 2/0
141. **FARMING AND FARMING ECONOMY,** Historical and Practical. (Vol. II. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. 3/0
 "Eminently calculated to enlighten the agricultural community on the varied subjects of which it treats; hence it should find a place in every farmer's library."—*City Press*.
142. **STOCK; CATTLE, SHEEP, AND HORSES.** (Vol. III. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 2/6
 "The author's grasp of his subject is thorough, and his grouping of facts effective. . . . We commend this excellent treatise."—*Weekly Dispatch*.
145. **DAIRY, PIGS, AND POULTRY.** (Vol. IV. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 2/0
 "We can testify to the clearness and intelligibility of the matter, which has been compiled from the best authorities."—*London Review*.
146. **UTILIZATION OF SEWAGE, IRRIGATION, AND RECLAMATION OF WASTE LAND.** (Vol. V. OUTLINES OF MODERN FARMING.) By R. SCOTT BURN. Woodcuts. 2/6
 "A work containing valuable information, which will recommend itself to all interested in modern farming."—*Field*.
140. } **OUTLINES OF MODERN FARMING.** By R. SCOTT
 141. } BURN, Author of "Landed Estates Management," "Farm Management,"
 142. } and Editor of "The Complete Grazier." Consisting of the above Five
 145. } Volumes in One, 1,250 pp., profusely Illustrated, half-bound 12/0
 146. }
 "The aim of the author has been to make his work at once comprehensive and trustworthy, and in this aim he has succeeded to a degree which entitles him to much credit."—*Morning Advertiser*.
 "Should find a place in every farmer's library."—*City Press*.
 "No farmer should be without it."—*Banbury Guardian*.
177. **FRUIT TREES,** The Scientific and Profitable Culture of. From the French of M. DU BREUIL. Third Edition, carefully Revised by GEORGE GLENNY. With 187 Woodcuts. 3/6†
 "The book teaches how to prune and train fruit trees to perfection."—*Field*.
198. **SHEEP:** The History, Structure, Economy, and Diseases of. By W. C. SPOONER, M.R.V.C., &c. Fourth Edition, with fine Engravings, including Specimens of New and Improved Breeds. 366 pp. 3/6
 "The book is decidedly the best of the kind in our language."—*Scotsman*.
201. **KITCHEN GARDENING MADE EASY.** Showing the best means of Cultivating every known Vegetable and Herb, &c., with directions for management all the year round. By GEO. M. F. GLENNY. Illustrated 1/6†
 "This book will be found trustworthy and useful."—*North British Agriculturist*.
207. **OUTLINES OF FARM MANAGEMENT.** Treating of the General Work of the Farm; Stock; Contract Work; Labour, &c. By R. SCOTT BURN, Author of "Outlines of Modern Farming," &c. 2/6†
 "The book is eminently practical, and may be studied with advantage by beginners in agriculture, while it contains hints which will be useful to old and successful farmers."—*Scotsman*.
208. **OUTLINES OF LANDED ESTATES MANAGEMENT:** Treating of the Varieties of Lands, Methods of Farming, the Setting-out of Farms, &c.; Roads, Fences, Gates, Irrigation, Drainage, &c. By R. S. BURN. 2/6†
 "A complete and comprehensive outline of the duties appertaining to the management of landed estates."—*Journal of Forestry*.
 * Nos. 207 & 208 in One Vol., handsomely half-bound, entitled "OUTLINES OF LANDED ESTATES AND FARM MANAGEMENT." By ROBERT SCOTT BURN. Price 6s.

† The † indicates that these vols. may be had strongly bound at 6d. extra.

Agriculture, Gardening, etc., continued.**209. THE TREE PLANTER AND PLANT PROPAGATOR:**

With numerous Illustrations of Grafting, Layering, Budding, Cuttings, Useful Implements, Houses, Pits, &c. By SAMUEL WOOD, Author of "Good Gardening," &c. 2/0⁺

"Sound in its teaching and very comprehensive in its aim. It is a good book."—*Gardeners' Magazine*.
 "The instructions are thoroughly practical and correct."—*North British Agriculturist*.

210. THE TREE PRUNER: Being a Practical Manual on the

Pruning of Fruit Trees, including also their Training and Renovation, also treating of the Pruning of Shrubs, Climbers and Flowering Plants. With numerous Illustrations. By SAMUEL WOOD, Author of "Good Gardening," &c. 2/0⁺

"A useful book, written by one who has had great experience."—*Mark Lane Express*.
 "We recommend this treatise very highly."—*North British Agriculturist*.

* * Nos. 209 & 210 in One Vol., handsomely half-bound, entitled "THE TREE PLANTER, PROPAGATOR AND PRUNER." By SAMUEL WOOD. Price 5s.

218. THE HAY AND STRAW MEASURER: New Tables

for the Use of Auctioneers, Valuers, Farmers, Hay and Straw Dealers, &c., forming a complete Calculator and Ready Reckoner. By JOHN STEELE . . . 2/0

"A most useful handbook. It should be in every professional office where agricultural valuations are conducted."—*Land Agent's Record*.

SUBURBAN FARMING: A Treatise on the Laying-out and

Cultivation of Farms, adapted to the Produce of Milk, Butter and Cheese, Eggs, Poultry, and Pigs. By the late Prof. JOHN DONALDSON. With Additions, illustrating Modern Practice, by R. SCOTT BURN. With numerous Illustrations 3/6⁺

"An admirable treatise on all matters connected with dairy farms."—*Live Stock Journal*.

231. THE ART OF GRAFTING AND BUDDING. By

CHARLES BALTET. With Illustrations 2/6⁺

"The one standard work on this subject."—*Scotsman*.

232. COTTAGE GARDENING; or, Flowers, Fruits, and Vege-

tables for Small Gardens. By E. HOBDAV 1/6

"Definite instructions as to the cultivation of small gardens."—*Scotsman*.

"Contains much useful information at a small charge."—*Glasgow Herald*.

233. GARDEN RECEIPTS. Edited by CHARLES W. QUIN. 1/6

"A singularly complete collection of the principal receipts needed by gardeners."—*Farmer*.

"A useful and handy book, containing a good deal of valuable information."—*Athenaeum*.

234. THE KITCHEN AND MARKET GARDEN. By Con-

tributors to "The Garden." Compiled by C. W. SHAW 3/0⁺

"The most valuable compendium of kitchen and market-garden work published."—*Farmer*.

"A most comprehensive volume on market and kitchen-gardening."—*Mark Lane Express*.

239. DRAINING AND EMBANKING. A Practical Treatise.

By JOHN SCOTT, late Professor of Agriculture and Rural Economy at the Royal Agricultural College, Cirencester. With 68 Illustrations. 1/6

"A valuable handbook to the engineer, as well as to the surveyor."—*Land*.

"This volume should be perused by all interested in this important branch of estate improvement."—*Land Agent's Record*.

240. IRRIGATION AND WATER SUPPLY: A Practical

Treatise on Water Meadows, Sewage Irrigation, Warping, &c.; on the Construction of Wells, Ponds and Reservoirs, &c. By Professor JOHN SCOTT. With 34 Illustrations 1/6

"A valuable and indispensable book for the estate manager and owner."—*Forestry*.

"Well worth the study of all farmers and landed proprietors."—*Building News*.

241. FARM ROADS, FENCES, AND GATES: A Practical

Treatise on the Roads, Tramways, and Waterways of the Farm; the Principles of Enclosures; and the different kinds of Fences, Gates, and Stiles. By Professor JOHN SCOTT. With 75 Illustrations 1/6

"Mr. Scott's treatise will be welcomed as a concisely compiled handbook."—*Building News*.

"A useful practical work, which should be in the hands of every farmer."—*Farmer*.

242. FARM BUILDINGS: A Practical Treatise on the Buildings

necessary for various kinds of Farms, their Arrangement and Construction, with Plans and Estimates. By Prof. JOHN SCOTT. With 105 Illustrations . . . 2/0

"The work of a practical man. No one who is called upon to design farm-buildings can afford to be without this handy little work."—*Builder*.

"This book ought to be in the hands of every landowner and agent."—*Kelso Chronicle*.

⁺ The † indicates that these vols. may be had strongly bound at 6d. extra.

Agriculture, Gardening, etc., continued.

243. **BARN IMPLEMENTS AND MACHINES.** Treating of the Application of Power to the Operations of Agriculture; and of the various Machines used in the Threshing-barn, in the Stock-yard, Dairy, &c. By Professor JOHN SCOTT. With 123 Illustrations . . . 2/0
244. **FIELD IMPLEMENTS AND MACHINES:** With Principles and Details of Construction and Points of Excellence, their Management, &c. By Prof. JOHN SCOTT. With 138 Illustrations . . . 2/0
245. **AGRICULTURAL SURVEYING:** A Treatise on Land Surveying, Levelling, and Setting-out; with Directions for Valuing and Reporting on Farms and Estates. By Prof. J. SCOTT. With 62 Illustrations 1/6
239. } **FARM ENGINEERING:** By Professor JOHN SCOTT. Com-
10 } prising the above Seven Volumes in One, 1,150 pages, and over 600 Illustrations.
245. } Half-bound . . . 12/0.
- "A copy of this work should be treasured up in every library where the owner thereof is in any way connected with land."—*Farm and Home.*
250. **MEAT PRODUCTION:** A Manual for Producers, Distributors, and Consumers of Butchers' Meat. By JOHN EWART, Author of "The Land Improver's Pocket-Book," &c. With numerous Illustrations . . . 2/6
- "A compact and handy volume on the meat question."—*Meat and Provision Trades' Review.*

MATHEMATICS, ARITHMETIC, etc.

32. **MATHEMATICAL INSTRUMENTS,** a Treatise on; Their Construction, Adjustment, Testing, and Use concisely Explained. By J. F. HEATHER, M.A., of the Royal Military Academy, Woolwich. Fourteenth Edition, Revised, with Additions, by A. T. WALMSLEY, M.I.C.E., Fellow of the Surveyors' Institution. Original Edition, in 1 vol., Illustrated . . . 2/0†
- [*Just published.*]
- * * In ordering the above, be careful to say "Original Edition," or give the number in the Series (32), to distinguish it from the Enlarged Edition in 3 vols. (Nos. 168-9-70).
76. **DESCRIPTIVE GEOMETRY,** an Elementary Treatise on; with a Theory of Shadows and of Perspective, extracted from the French of G. MONGE. To which is added a Description of the Principles and Practice of Isometrical Projection. By J. F. HEATHER, M.A. With 14 Plates . . . 2/0
178. **PRACTICAL PLANE GEOMETRY:** giving the Simplest Modes of Constructing Figures contained in one Plane and Geometrical Construction of the Ground. By J. F. HEATHER, M.A. With 215 Woodcuts . . . 2/0
- "The author is well-known as an experienced professor, and the volume contains as complete a collection of problems as is likely to be required in ordinary practice."—*Architect.*
83. **COMMERCIAL BOOK-KEEPING.** With Commercial Phrases and Forms in English, French, Italian, and German. By JAMES HADDON, M.A., formerly Mathematical Master, King's College School . . . 1/6
84. **ARITHMETIC,** a Rudimentary Treatise on: with full Explanations of its Theoretical Principles, and numerous Examples for Practice. For the Use of Schools and for Self-Instruction. By J. R. YOUNG, late Professor of Mathematics in Belfast College. Eleventh Edition . . . 1/6
- 84*. **A KEY TO THE ABOVE.** By J. R. YOUNG . . . 1/6
85. **EQUATIONAL ARITHMETIC,** applied to Questions of Interest, Annuities, Life Assurance, and General Commerce; with various Tables by which all Calculations may be greatly facilitated. By W. HIPSLEY. 2/0
86. **ALGEBRA,** the Elements of. By JAMES HADDON, M.A., formerly Mathematical Master of King's College School. With Appendix, containing Miscellaneous Investigations, and a collection of Problems . . . 2/0
- 86*. **A KEY AND COMPANION TO THE ABOVE.** An extensive repository of Solved Examples and Problems in Illustration of the various Expedients necessary in Algebraical Operations. By J. R. YOUNG . . . 1/6
88. **EUCLID, THE ELEMENTS OF:** with many Additional Propositions and Explanatory Notes; to which is prefixed an Introductory Essay on Logic. By HENRY LAW, C.E. . . . 2/6†
- * * Sold also separately, viz. :—
88. **EUCLID, The First Three Books.** By HENRY LAW, C.E. . . . 1/6
89. **EUCLID, Books 4, 5, 6, 11, 12.** By HENRY LAW, C.E. . . . 1/6

† The † indicates that these vols. may be had strongly bound at 6d. extra.

Mathematics, Arithmetic, etc., continued.

90. **ANALYTICAL GEOMETRY AND CONIC SECTIONS**, a Rudimentary Treatise on. By JAMES HANN. A New Edition, re-written and enlarged by Professor J. R. YOUNG. 2/0½
 "The author's style is exceedingly clear and simple, and the book is well adapted for the beginner, and those who may be obliged to have recourse to self-tuition."—*Engineer*.
91. **PLANE TRIGONOMETRY**, the Elements of. By JAMES HANN, formerly Mathematical Master of King's College, London 1/6
92. **SPHERICAL TRIGONOMETRY**, the Elements of. By JAMES HANN. Revised by CHARLES H. DOWLING, C.E. 1/0
 "Or with 'The Elements of Plane Trigonometry,' in One Volume, 2s. 6d.
93. **MENSURATION AND MEASURING**, for Students and Practical Use. With the Mensuration and Levelling of Land for the purposes of Modern Engineering. By T. BAKER, C.E. New Ed. by E. NUGENT, C.E. 1/6
101. **DIFFERENTIAL CALCULUS**, Elements of the. By W. S. B. WOOLHOUSE, F.R.A.S., &c. 1/6
102. **INTEGRAL CALCULUS**. By HOMERSHAM COX, B.A. 1/0
105. **MNEMONICAL LESSONS**.—GEOMETRY, ALGEBRA, AND TRIGONOMETRY, in Easy Mnemonical Lessons. By the Rev. THOMAS PENYNGTON KIRKMAN, M.A. 1/6
136. **ARITHMETIC**, Rudimentary, for the Use of Schools and Self-Instruction. By JAMES HADDON, M.A. Revised by ABRAHAM ARMAN 1/6
137. **A KEY TO THE ABOVE**. By A. ARMAN 1/6
168. **DRAWING AND MEASURING INSTRUMENTS**. Including—I. Instruments employed in Geometrical and Mechanical Drawing, and in the Construction, Copying, and Measurement of Maps and Plans. II. Instruments used for the purposes of Accurate Measurement, and for Arithmetical Computations. By J. F. HEATHER, M.A. 1/6
 "Valuable and instructive to all whose occupations require exceptional accuracy in measurements."—*Jeweller and Metal Worker*.
169. **OPTICAL INSTRUMENTS**. Including (more especially) Telescopes, Microscopes, and Apparatus for producing copies of Maps and Plans by Photography. By J. F. HEATHER, M.A. Illustrated 1/6
 "An excellent treatise."—*British Journal of Photography*.
170. **SURVEYING & ASTRONOMICAL INSTRUMENTS**. Including—I. Instruments used for Determining the Geometrical Features of a portion of Ground. II. Instruments employed in Astronomical Observations. By J. F. HEATHER, M.A. Illustrated 1/6
 "A good, sensible, useful book."—*School Board Chronicle*.
- * * The above three volumes form an enlargement of the Author's original work, "Mathematical Instruments": price 1s. 6d. (See No. 32 in the Series.)
168. } **MATHEMATICAL INSTRUMENTS: Their Construction,**
 169. } Adjustment, Testing and Use. Comprising Drawing, Measuring, Optical,
 170. } Surveying, and Astronomical Instruments. By J. F. HEATHER, M.A.
 Enlarged Edition, for the most part entirely re-written. The Three Parts as above, in One thick Volume 4/6½
 "An exhaustive treatise, belonging to the well-known Weale's Series. Mr. Heather's experience well qualifies him for the task he has so ably fulfilled."—*Engineering and Building Times*.
158. **THE SLIDE RULE, AND HOW TO USE IT**. Containing full, easy, and simple Instructions to perform all Business Calculations with unexampled rapidity and accuracy. By CHARLES HOARE, C.E. With a Slide Rule, in tuck of cover. Fifth Edition 2/6½
196. **THEORY OF COMPOUND INTEREST AND ANNUITIES**; with Tables of Logarithms for the more Difficult Computations of Interest, Discount, Annuities, &c., in all their Applications and Uses for Mercantile and State Purposes. By FEDOR THOMAN, of the Société Crédit Mobilier, Paris. Third Edition, carefully revised and corrected 4/0½
 "A very powerful work, and the author has a very remarkable command of his subject."—Professor A. de MORGAN. "We recommend it to the notice of actuaries and accountants."—*Athenæum*.

⚡ The † indicates that these vols. may be had strongly bound at 6d. extra.

Mathematics, Arithmetic, etc., continued.

199. *THE COMPENDIOUS CALCULATOR* (*Intuitive Calculations*); or, Easy and Concise Methods of Performing the various Arithmetical Operations required in Commercial and Business Transactions; together with Useful Tables, &c. By DANIEL O'GORMAN. Twenty-sixth Edition, carefully revised by C. NORRIS 3/0†
- "It would be difficult to exaggerate the usefulness of this book to everyone engaged in commerce or manufacturing industry. It is crammed full with rules and formulae for shortening and employing calculations in money, weights and measures, &c. of every sort and description."—*Knowledge*.
204. *MATHEMATICAL TABLES*, for Trigonometrical, Astronomical, and Nautical Calculations; to which is prefixed a Treatise on Logarithms. By H. LAW, C.E. Together with a Series of Tables for Navigation and Nautical Astronomy. By Professor I. R. YOUNG. New Edition 4/0
- 204.* *LOGARITHMS*. With Mathematical Tables for Trigonometrical, Astronomical, and Nautical Calculations. By HENRY LAW, C.E. Revised Edition. (Forming part of the above work.) 3/0
221. *MEASURES, WEIGHTS, AND MONEYS OF ALL NATIONS*, and an Analysis of the Christian, Hebrew, and Mahometan Calendars. By W. S. B. WOOLHOUSE, F.R.A.S., F.S.S. Sixth Edition, 2/0†
- "A work necessary for every mercantile office."—*Building Trades Journal*.
227. *A TREATISE ON MATHEMATICS*, as applied to the Constructive Arts. By FRANCIS CAMPIN, C.E., &c. Second Edition 3/0†
- "This volume should be in the hands of everyone connected with building construction."—*Builder's Weekly Reporter*.

PHYSICAL SCIENCE, NATURAL PHILOSOPHY, etc.

1. *CHEMISTRY*, for the Use of Beginners. By Prof. GEO. FOWNES, F.R.S. With an Appendix on the Application of Chemistry to Agriculture. 1/0
2. *NATURAL PHILOSOPHY*, for the Use of Beginners. By CHARLES TOMLINSON, F.R.S. 1/6
6. *MECHANICS*: Being a concise Exposition of the General Principles of Mechanical Science, and their Applications. By CHARLES TOMLINSON, F.R.S. 1/6
7. *ELECTRICITY*; showing the General Principles of Electrical Science, and the Purposes to which it has been applied. By Sir W. SNOW HARRIS, F.R.S., &c. With considerable Additions by R. SABINE, C.E., F.S.A. 1/6
- 7*. *GALVANISM*. By Sir W. SNOW HARRIS. New Edition, revised, with considerable Additions, by ROBERT SABINE, C.E. 1/6
8. *MAGNETISM*. By Sir W. SNOW HARRIS. New Edition, revised and enlarged by H. M. NOAD, Ph.D. With 165 Woodcuts 3/6†
- "The best popular exposition of magnetism, its intricate relations and complicating effects, with which we are acquainted."—*School Board Chronicle*.
11. *THE ELECTRIC TELEGRAPH*: its History and Progress; with Descriptions of some of the Apparatus. By R. SABINE, C.E., F.S.A., &c. 3/0
- "Essentially a practical and instructive work."—*Daily Telegraph*.
12. *PNEUMATICS*, including Acoustics and the Phenomena of Wind Currents, for the Use of Beginners. By CHARLES TOMLINSON, F.R.S. Fourth Edition, enlarged. Illustrated. [Just published] 1/6
72. *MANUAL OF THE MOLLUSCA*: A Treatise on Recent and Fossil Shells. By Dr. S. P. WOODWARD, A.L.S. With Appendix by RALPH TATE, A.L.S., F.G.S. With numerous Plates and 300 Woodcuts. 6/6
- *.* The above handsomely bound in cloth boards, 7s. 6d.
- "A storehouse of conchological and geological information."—*Hardwicke's Science Gossip*.
- "An important work, with such additions as complete it to the present time."—*Land and Water*.
96. *ASTRONOMY*. By the late Rev. ROBERT MAIN, M.A., F.R.S., formerly Radcliffe Observer at Oxford. Third Edition, revised and corrected to the Present Time, by WILLIAM THYNNE LYNN, B.A., F.R.A.S. 2/0
- "A sound and simple treatise, very carefully edited, and a capital book for beginners."—*Knowledge*.
97. *STATICS AND DYNAMICS*, the Principles and Practice of; embracing also a clear development of Hydrostatics, Hydrodynamics, and Central Forces. By T. BAKER, C.E. Fourth Edition 1/6

† The † indicates that these vols. may be had strongly bound at 6d. extra.

Physical Science, Natural Philosophy, etc., continued.

138. **TELEGRAPH, HANDBOOK OF THE:** A Guide to Candidates for Employment in the Telegraph Service. By R. BOND. Fourth Edition, revised and enlarged; to which is appended, **QUESTIONS on MAGNETISM, ELECTRICITY, and PRACTICAL TELEGRAPHY**, for the Use of Students, by W. MCGREGOR, Indian Government Telegraphs. Woodcuts . 3/0†

"This book is one of the very best works of the sort we have ever come across. All who desirous of being employed in the service of the telegraph should at once procure it."—*Civilian*.

173. **PHYSICAL GEOLOGY**, partly based on Major-General PORTLOCK'S "Rudiments of Geology." By RALPH TATE, A.L.S., &c. Woodcuts. 2/0

174. **HISTORICAL GEOLOGY**, partly based on Major-General PORTLOCK'S "Rudiments." By RALPH TATE, A.L.S., &c. Woodcuts. . 2/6

173. **GEOLOGY, PHYSICAL and HISTORICAL.** Consisting of & "Physical Geology," which sets forth the Leading Principles of the Science;

174. and "Historical Geology," which treats of the Mineral and Organic Conditions of the Earth at each successive epoch. By RALPH TATE, F.G.S., &c., &c. With 250 Illustrations 4/6†

"The fulness of the matter has elevated the book into a manual. Its information is exhaustive and well arranged, so that any subject may be opened upon at once."—*School Board Chronicle*.

183. **ANIMAL PHYSICS, Handbook of.** By DIONYSIUS LARD-

184. **NER, D.C.L.** With 500 Illustrations. In One Vol. (732 pages), cloth boards. 7/6

* * Sold also in Two Parts, as follows:—

183. **ANIMAL PHYSICS.** By Dr. LARDNER. Part I., Chapters I.—VII. 4/0

184. **ANIMAL PHYSICS.** By Dr. LARDNER. Part II., Chapters VIII.—XVIII. 3/0

"This book contains a great deal more than an introduction to human anatomy. In it will be found the elements of comparative anatomy, a complete treatise on the functions of the body, and a description of the phenomena of birth, growth, and decay."—*Educational Times*.

FINE ARTS, etc.

20. **PERSPECTIVE FOR BEGINNERS.** Adapted to Young Students and Amateurs in Architecture, Painting, &c. By GEORGE PYNE. 2/0

40. **GLASS STAINING, AND THE ART OF PAINTING ON GLASS.** From the German of Dr. GESSERT and EMANUEL OTTO FROMBERG. With an Appendix on THE ART OF ENAMELLING. 2/6

69. **MUSIC, A Rudimentary and Practical Treatise on.** With numerous Examples. By CHARLES CHILD SPENCER 2/6

"Mr. Spencer has marshalled his information with much skill, and yet with a simplicity that must recommend his works to all who wish to thoroughly understand music."—*Weekly Times*.

71. **PIANOFORTE, The Art of Playing the.** With numerous Exercises and Lessons. By CHARLES CHILD SPENCER 1/6

"A sound and excellent work, written with spirit, and calculated to inspire the pupil with a desire to aim at high accomplishment in the art."—*School Board Chronicle*.

- 69, 71. **MUSIC, AND THE PIANOFORTE.** One Vol. Half-bound. 5/0

181. **PAINTING POPULARLY EXPLAINED.** By THOMAS JOHN GULLICK, Painter, and JOHN TIMBS, F.S.A. Including Fresco, Oil, Mosaic, Water Colour, Water-Glass, Tempera, Encaustic, Miniature, Painting on Ivory, Vellum, Pottery, Enamel, Glass, &c. Fifth Edition 5/0†

* * Adopted as a Prize book at South Kensington.

"Much may be learned, even by those who fancy they do not require to be taught, from the careful perusal of this unpretending but comprehensive treatise."—*Art Journal*.

186. **A GRAMMAR OF COLOURING.** Applied to Decorative Painting and the Arts. By GEORGE FIELD. New Edition, revised and enlarged by ELLIS A. DAVIDSON. With Coloured Plates 3/0†

"The book is a most useful *resumé* of the properties of pigments."—*Builder*.

"One of the most useful of students' books."—*Architect*.

246. **A DICTIONARY OF PAINTERS, AND HANDBOOK FOR PICTURE AMATEURS;** being a Guide for Visitors to Public and Private Picture Galleries, and for Art-Students, including Glossary of Terms, Sketch of Principal Schools of Painting, &c. By PHILIPPE DARYL, B.A. 2/6†
Considering its small compass, really admirable. We cordially recommend the book."—*Builder*.

✂ The † indicates that these vols. may be had strongly bound at 6d. extra.

INDUSTRIAL AND USEFUL ARTS.

23. **BRICKS AND TILES**, Rudimentary Treatise on the Manufacture of; containing an Outline of the Principles of Brickmaking. By E. DOBSON, M.R.I.B.A. Additions by C. TOMLINSON, F.R.S. Illust. 3/0½
 "The best handbook on the subject. We can safely recommend it as a good investment."—*Builder*.
67. **CLOCKS AND WATCHES, AND BELLS**, a Rudimentary Treatise on. By Sir EDMUND BECKETT, Bart. Q.C. Seventh Edition. . 4/6
 "The above handsomely bound, cloth boards, 5s. 6d."
 "The best work on the subject probably extant. The treatise on bells is undoubtedly the best in the language."—*Engineering*.
 "The only modern treatise on clock-making."—*Horological Journal*.
83. **CONSTRUCTION OF DOOR LOCKS**. From the Papers of A. C. HOBBS. Edited by CHARLES TOMLINSON, F.R.S. With a Note upon IRON SAFES by ROBERT MALLET. Illustrated . . . 2/6
162. **THE BRASS FOUNDER'S MANUAL**: Instructions for Modelling, Pattern Making, Moulding, Turning, &c. By W. GRAHAM. . 2/0½
205. **THE ART OF LETTER PAINTING MADE EASY**. By JAMES GREIG BADENOCH. With 12 full-page Engravings of Examples . 1/0
 "Any intelligent lad who fails to turn out decent work after studying this system, has mistaken his vocation."—*English Mechanic*.
215. **THE GOLDSMITH'S HANDBOOK**, containing full Instructions in the Art of Alloying, Melting, Reducing, Colouring, Collecting and Refining. The processes of Manipulation, Recovery of Waste, Chemical and Physical Properties of Gold; Solders, Enamels and other useful Rules and Recipes, &c. By GEORGE E. GEE. Third Edition, considerably enlarged . 3/0½
 "A good, sound, technical educator."—*Horological Journal*.
 "A standard book, which few will care to be without."—*Jeweller and Metalworker*.
225. **THE SILVERSMITH'S HANDBOOK**, on the same plan as the above. By GEORGE E. GEE. Second Edition, Revised . 3/0½
 "A valuable sequel to the author's 'Practical Goldworker.'"—*Silversmith's Trade Journal*.
 "As a guide to workmen it will prove a good technical educator."—*Glasgow Herald*.
 "The two preceding Works, in One handsome Vol., half-bound, entitled 'THE GOLDSMITH'S AND SILVERSMITH'S COMPLETE HANDBOOK,' 7s."
249. **THE HALL-MARKING OF JEWELLERY**. Comprising an account of all the different Assay Towns of the United Kingdom; with the Stamps at present employed; also the Laws relating to the Standards and Hall-Marks at the various Assay Offices. By GEORGE E. GEE . 3/0½
 "Deals thoroughly with its subject from a manufacturer's and dealer's point of view."—*Jeweller*.
 "A valuable and trustworthy guide."—*English Mechanic*.
224. **COACH-BUILDING**: A Practical Treatise, Historical and Descriptive. By JAMES W. BURGESS. With 57 Illustrations . 2/6½
 "This handbook will supply a long-felt want, not only to manufacturers themselves, but more particularly apprentices and others whose occupations may be in any way connected with the trade of coach-building."—*European Mail*.
235. **PRACTICAL ORGAN BUILDING**. By W. E. DICKSON, M.A., Precentor of Ely Cathedral. Second Edition, Revised, with Additions. Illustrated . 2/6½
 "The amateur builder will find in this book all that is necessary to enable him personally to construct a perfect organ with his own hands."—*Academy*.
 "The best work on the subject that has yet appeared in book form."—*English Mechanic*.
262. **THE ART OF BOOT AND SHOEMAKING**, including Measurement, Last-fitting, Cutting-out, Closing and Making; with a Description of the most Approved Machinery employed. By JOHN BEDFORD LENO, late Editor of "St. Crispin" and "The Boot and Shoemaker." With numerous Illustrations. Second Edition . 2/0½
 "This excellent treatise is by far the best work ever written on the subject. The chapter on clicking, which shows how waste may be prevented, will save fifty times the price of the book."—*Scottish Leather Trader*.
263. **MECHANICAL DENTISTRY**: A Practical Treatise on the Construction of the Various Kinds of Artificial Dentures, comprising also Useful Formulæ, Tables and Receipts for Gold Plate, Clasps, Solders, &c. By CHARLES HUNTER. Third Edition, revised, with additions . 3/0½
 "We can strongly recommend Mr. Hunter's treatise to all students preparing for the profession of dentistry, as well as to every mechanical dentist."—*Dublin Journal of Medical Science*.

1888 The † indicates that these vols. may be had strongly bound at 6d. extra.

MISCELLANEOUS VOLUMES.

36. *A DICTIONARY OF TERMS used in ARCHITECTURE, BUILDING, ENGINEERING, MINING, METALLURGY, ARCHÆOLOGY, the FINE ARTS, &c.* By JOHN WEALE. Fifth Edition, with numerous Additions. Edited by ROBT. HUNT, F.R.S., Keeper of Mining Records, Editor of "Ure's Dictionary." Numerous Illustrations . . . 5/0
- * * * *The above, strongly bound in cloth boards, price 6s.*
- "The best small technological dictionary in the language."—*Architect.*
- "The absolute accuracy of a work of this character can only be judged of after extensive consultation and from our examination it appears very correct and very complete."—*Mining Journal.*
- "There is no need now to speak of the excellence of this work; it received the approval of the community long ago. Edited now by Mr. Robert Hunt, and published in a cheap, handy form, it will be the utmost service as a book of reference scarcely to be exceeded in value."—*Scotsman.*
50. *THE LAW OF CONTRACTS FOR WORKS AND SERVICES.* By DAVID GIBBONS. Third Edition, enlarged . . . 3/0†
- "A very compendious, full and intelligible digest of the working and results of the law, in regard to all kinds of contracts between parties standing in the relation of employer and employed."—*Builder.*
- "This exhaustive manual is written in a clear, terse, and pleasant style, and is just the work for masters and servants alike to depend upon for constant reference."—*Metropolitan.*
112. *MANUAL OF DOMESTIC MEDICINE.* By R. GOODING, B.A., M.D. Intended as a Family Guide in all cases of Accident and Emergency. Third Edition, carefully revised . . . 2/0
- "The author has, we think, performed a useful service by placing at the disposal of those situated, by unavoidable circumstances, at a distance from medical aid, a reliable and sensible work in which professional knowledge and accuracy have been well seconded by the ability to express himself in ordinary untechnical language."—*Public Health.*
- 112.* *MANAGEMENT OF HEALTH. A Manual of Home and Personal Hygiene.* By the Rev. JAMES BAIRD, B.A. . . . 1/0
- "The author gives sound instructions for the preservation of health."—*Athenæum.*
- "It is wonderfully reliable, it is written with excellent taste, and there is instruction crowded into every page."—*English Mechanic.*
150. *LOGIC, Pure and Applied.* By S. H. EMMENS. Third Edition 1/6
- "This admirable work should be a text-book not only for schools, students and philosophers, for all literateurs and men of science, but for those concerned in the practical affairs of life, &c."—*The News.*
153. *SELECTIONS FROM LOCKE'S ESSAYS ON THE HUMAN UNDERSTANDING.* With Notes by S. H. EMMENS . . . 2/0
154. *GENERAL HINTS TO EMIGRANTS.* Containing Notices of the various Fields for Emigration. With Hints on Preparation for Emigrating, Outfits, &c., Useful Recipes, Map of the World, &c. . . . 2/0
157. *THE EMIGRANT'S GUIDE TO NATAL.* By ROBERT JAMES MANN, F.R.A.S., F.M.S. Second Edition, revised. Map . . . 2/0
193. *HANDBOOK OF FIELD FORTIFICATION.* By Major W. W. KNOLLYS, F.R.G.S. With 163 Woodcuts . . . 3/0†
- "A well-timed and able contribution to our military literature. . . . The author supplies, in a clear business style, all the information likely to be practically useful."—*Chambers of Commerce Chronicle.*
194. *THE HOUSE MANAGER: Being a Guide to Housekeeping, Practical Cookery, Pickling and Preserving, Household Work, Dairy Management, the Table and Dessert, Cellarage of Wines, Home-brewing and Wine-making, the Boudoir and Dressing-room, Travelling, Stable Economy, Gardening Operations, &c.* By AN OLD HOUSEKEEPER . . . 3/6†
- "We find here directions to be discovered in no other book, tending to save expense to the pocket as well as labour to the head."—*John Bull.*
- "Quite an Encyclopædia of domestic matters. We have been greatly pleased with the neatness and lucidity of the explanatory details."—*Court Circular.*
194. } *HOUSE BOOK (The).* Comprising: I. THE HOUSE MANAGER.
112. } By an OLD HOUSEKEEPER. II. DOMESTIC MEDICINE. By RALPH GOODING,
& M.D. III. MANAGEMENT OF HEALTH. By JAMES BAIRD. In One Vol.,
112*. } strongly half-bound . . . 6/0

† The † indicates that these vols. may be had strongly bound at 6d. extra.



